

## FIRE DEPARTMENT

## Prevention Division (816)969-1300

## **PLANS REVIEW CONDITIONS**

Permit No: PRCOMCOM20240778 Date: February 07, 2025

Project Title: MCC AUTOMOTIVE INSTITUTE - Applicant:

**BUILDING ADDITION** 

Location: 500 SW LONGVIEW RD, LEES SUMMIT, MO 64081

Type of Work:

Occupancy Group: S-1

Description: MCC AUTOMOTIVE INSTITUTE - BUILDING ADDITION AND RENOVATION OF EXISTING

Construction Type: Type IIB (Unprotected)

Map Page:

CAUTOMOTIVE INSTITUTE - Primary: (913) 722-6900 Ext: 111

American Fire Sprinkler Corporation

6750 W 47th Terrace

Kansas, MO 66203

Listed below are requirements from our department for the project noted above. If you have any additional questions, please contact our department for further clarification.

Sprinkler Plan Review Reviewed By: Craig Hill Released for Construction

1. Information only: Call (816) 969-1300 24 hours prior to requesting a hydrostatic test and a flow test.

Sprinkler Plan Review Reviewed By: Craig Hill Rejected

1. Action required: FDC Fire department connection shows 5" connection. FDC needs to be a 4" storz with a 30 degree elbow.

Sprinkler Plan Review Reviewed By: Craig Hill Released for Construction

1. Action required: FDC Fire department connection shows 5" connection. FDC needs to be a 4" storz with a 30 degree elbow.

The applicant understands that the requirements listed above must be corrected to conform to applicable City Codes and Ordinances.