

KC
ELECTRIC
GROUP

14825 W 167th Terrace
Olathe, KS 66062
816-352-2088

Project Name:	Costa Vida Panel Replacement
Project Address:	115 Route 291 Lees Summit, MO 64063
Project Contact:	Alden Bradley
Phone Number:	913-441-1140
Architect:	NA
Date of Plans:	NA
Date of Proposal:	February 26, 2025
Tax Exempt:	No
Prevailing Wage:	No
Addendum:	NA

Includes:

- > Provide all labor and materials to replace the existing 200 amp panel.
- > The new panel to consist of the following:
 - 1 200 amp 120/208 volt main breaker 42 circuit panelboard
 - 14 1P 20 amp circuit breakers
 - 4 1P 20 amp ST circuit breakers
 - 2 2P 20 amp circuit breakers
 - 1 2P 30 amp circuit breaker
 - 1 2P 30 amp ST circuit breaker
 - 1 3P 40 amp circuit breaker
 - 1 3P 80 amp circuit breaker
- > Relocate existing time clock to allow room for new panel.
- > Removal of sheetrock as required for the installation of the new panel.
- > Removal and re-installation of all conduits that are currently landed in the panel.
- > Permit Fees.
- > All work to be performed after business hours.

Excludes:

- > Engineering Fees.
- > Fees from Evergy if Evergy is required to perform an after hours power outage.
- > Sheetrock repairs, patching or painting of sheetrock if applicable.

Proposal Amount: \$4,214.00

Notes:

The installation of a new panelboard and breakers will not eliminate the breakers from tripping if the existing circuit is overloaded.

Derrick Patton
816-352-2088
derrick@kceglc.com

**** This proposal is valid for 30 days from date of the proposal, after which time it is subject to review for price adjustment ****