

Greystone - Masterplan


Address: 2623 SW Firefly Lane, Lees Summit, MO

Lot: 168 Hook Farms 2nd Plat

RELEASE FOR CONSTRUCTION
AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI
04/29/2025







<u>Garage</u>

599 SF

Patio 152 SF

Living Area

1401 SF

Front Porch

24 SF

Address: 2623 SW Firefly Lane, Lees Summit, MO Lot: 168 Hook Farms 2nd Plat

Area - W/ Extended pantry

Basement Finished

Basement Unfinished

Living Area

Front Porch

1238 SF

1401 SF

2639 SF

164 SF

152 SF

24 SF

599 SF

152 SF

1091 SF

939 SF

General Information

2018 Interior Energy Cons. Code (Table N1102.1.2)		
Doors & Windows:	U-0.32 MAX	
Glazing SHGF:	0.40	
Skylights:	U-0.55 MAX	
Roof		
Attic Ceilings:	R-49 MIN	
Vaults:	R-38 MIN	
Vaults < 500sf:	R-30 MIN	
vadito 100001.	1 00 Mil V	
Wood Frame Walls:	R-20 or R-13 + 5 MIN	
Basement Walls:	R-13 or R-10 Continuous	
Floor (over unconditioned):	R-19 MIN	
Slab on Grade:	R-10 for 24" MIN	
Ductwork:	R-8 MIN	
Fuel Fired Furnace:	90% AFUE MIN	
Electic Furnace:	No Minimum	
Cooling System:	13 SEER MIN	
g cycle		
Water Heater		
Gas Fired Storage:	0.67 EF MIN	
Gas Fired Instant:		
Electic Storage:		
Electic Instant:	0.93 EF MIN	
Licotio motant.	O.OO EI WIIIV	

An energy efficient certificate is required to be posted in or on the electrical panel before the final inspection. The certificate will be provided with all new residential permits. It is the permit holder/contractor's responsibility to ensure the certificate has accurate information and is posted before final inspection -- Owner/Contractor is responsibile for meeting the prescriptive requirments of IRC chapter 11 unless a HER Index Analysis for Performance Compliance based on the plans is submitted to the AHJ for approval.

IRC 2018Ground Snow Load:20PSFWind Speed:115mphTopography Effects:NoSeismic Design Category:ADamage From Weather:SevereFrost Line Depth:36 inchesTermite:Moderate to HeavyWinter Design Temperature:6 FIce Barrier Underlayment:YesFlood Hazard:4ir Freezing Index:927 or lessMean Annual Temperature:55.5 F

is required for any dwelling with air infiltration at a rate of less than 5 air changes per hour (at ACH50 standard R303.4). 2. Carbon monoxide detectors required (R315)

Whole House Mechanical Ventilation System

- Carbon monoxide detectors required (R315)
 Steel columns shall be minimum schedule 40 (R507.2)
- 4. Deck Ledger attachment to house shall be per Tables 507.9.1.3.
- New provisions for attachment of rafters, trusses and roof beams. (R802.3 and
- 6. Programmable thermostat required
- 7. Air handlers shall be rated for Maximum 2% air leakage rate (N1103.2.2.1)
- Building cavities used as return air plenums shall be sealed to prevent leakage across the thermal envelope. (N1103.2.3)
- Certain hot water pipes shall be insulated (N1103 4)
- 10. All exhaust fans shall terminate to the building exterior (M1507.2)
- 11. Makeup air system required for kitchen exhaust hoods that exceed 400 CFM M1503.412. Building cavities in a thermal envelope wall (including the wall between the house and
- garage) shall not be used as return air plenums (unless the required insulation and air barrier are maintained) (M1601.1.1,#7.5) 13. An air handling system shall not serve both
- the living space and the garage (M1601.6)

 14. A concrete-Encased grounding electrode
 ('UFER' Ground) connection complies with the
- requirments of the 2018 IRC Section
 E3608.1.2 in providing a connection with no
 less than the required minimum of steel.
 15. Compliance with the requirments and show
- connection as needed for roof beam, trus, rafter, and girder connections for uplift per IRC 802.11

 16. Garage Door Rating: DASMA 115 MPH Rated



Greystone - Masterplan

		Permit Set
Original Issue	e Date:	10/1/2021
	REVISIONS	
lumber	Description	Date





JANUARY 1, 2025

Permit Set


PLAN DESCRIPTION: Cover Sheet

OO miset No.






LEE'S SUMMIT, MISSOURI
04/29/2025




AS NOTED FOR PLAN REVIEW
DEVELOPMENT SERVICES
LEE'S SUMMIT, MISSOURI


04/29/2025




DEVELOPMENT SERVICES LEE'S SUMMIT, MISSOURI 04/29/2025




MAREIDEANSE WOR GONSTRUCTION
AS NOTED FOR PLANTED FOR





LEE'S SUMMIT, MISSOURI 04/29/2025






ne Mæelpease for ponsativation
As noted for planteries
Development services
Lee's summit, missouri
04/29/2025








AS NOTED FOR PLAN REVIEW DEVELOPMENT SERVICES LEE'S SUMMIT, MISSOURI 04/29/2025




File\Grevstone Master Plan.rvt

AS NOTED FOR PLAN REVIEW DEVELOPMENT SERVICES LEE'S SUMMIT, MISSOURI 04/29/2025




AS NOTED FOR PLAN REVIEW DEVELOPMENT SERVICES LEE'S SUMMIT, MISSOURI

04/29/2025



LEE'S SUMMIT, MISSOURI 04/29/2025



File\Greystone Master Plan.rvt
AS NOTED FOR PLAN REVIEW DEVELOPMENT SERVICES LEE'S SUMMIT, MISSOURI 04/29/2025