


Copyright 2025 Herman A. Scharhag Co., Architects
All Rights Reserved. No part of these drawings may be reproduced in any form or by any electronic or mechanical means, without written permission.

NEW BUILDING FOR

SUMMIT ORCHARDS

410 NW CHIPMAN ROAD

J. Jeffrey Schroeder Mo. License A-4226
Herman Scharhag Co., Arch. Cert. of Authority A-22




No.	Description	Date
Revision Schedule		

Area Plan

Project number	2491
Date	05.30.2025

A100

Scale1/8" = 1'-0"



1 Floor Plan
1/8" = 1'-0"

BUILDING CODE SUMMARY

APPLICABLE CODES

2018 INTERNATIONAL BUILDING CODE
2018 INTERNATIONAL MECHANICAL CODE
2018 INTERNATIONAL PLUMBING CODE
2018 INTERNATIONAL FIRE CODE
2018 INTERNATIONAL ENERGY CONSERVATION CODE
2017 NATIONAL ELECTRICAL CODE
2017 ICC/ANSI A117.1

SUMMARY OF WORK

NEW SHELL SPEC BUILDING. NO C.O. IS REQUESTED WITH THIS SUBMITTAL. SEPARATE TENANT FINISH PLANS WILL BE SUBMITTED FOR EACH SPACE AT A LATER DATE.

FIRE SUPPRESSION SUMMARY

NONE

OCCUPANCY CLASSIFICATION

M (RETAIL) & B (OFFICE)
PER 2018 IBC SECT. 303.1.1, SMALL TENANTS WILL QUALIFY AS GROUP 'B' OCCUPANCY.

TYPE OF CONSTRUCTION

V-B, NON - SPRINKLED

FLOOR AREA

BUILDING AREA: 4,956 SQ.FT.

OCCUPANT LOAD

TO BE DETERMINED

EXITS REQUIRED

TO BE DETERMINED

EXITS PROVIDED

TWO PER SPACE

TOILET FACILITIES REQUIRED

TO BE DETERMINED

TOILET FACILITIES PROVIDED

ONE UNISEX TOILET PER SPACE (ADA)

DEFERRED SUBMITTALS TO BE COMPLETED BY OTHERS

ROOF TRUSS PLANS (PLANS BY SUBCONTRACTOR)

INTERIOR FINISH REQUIREMENTS


FLOOR FINISHES: CLASS I or CLASS II
WALL FINISHES: CLASS A (non-sprinkled)
CEILING FINISHES: CLASS A (non-sprinkled)

EGRESS DOORS SHALL BE READILY OPENABLE FROM THE EGRESS SIDE WITHOUT THE USE OF A KEY OR SPECIAL KNOWLEDGE OR EFFORT.

PREMISES SHALL BE IDENTIFIED ON ALL EXTERIOR DOORS, WITH NUMBERS AND/OR LETTERS. EACH CHARACTER SHALL BE NOT LESS THAN 6" HIGH WITH A MINIMUM STROKE WIDTH OF 1.0" INCHES. THEY SHOULD BE INSTALLED ON A CONTRASTING BACKGROUND. STREET FACING DOORS SHALL HAVE ADDRESSES THAT ARE PLAINLY LEGIBLE AND VISIBLE FROM THE STREET FRONTING THE PROPERTY. ADDRESS NUMBERS AND/OR LETTERS SHALL BE ARABIC NUMBERS OR ALPHABETIC LETTERS.

NEW BUILDING FOR SUMMIT ORCHARDS 410 NW CHIPMAN ROAD

J. Jeffrey Schroeder Mo. License A-4226
Herman Scharhag Co., Arch. Cert. of Authority A-22



No.	Description	Date
Revision Schedule		

Floor Plan

Project number 2491
Date 05.30.2025

A101

Scale 1/8" = 1'-0"

scharhag

HERMAN A. SCHARHAG COMPANY ARCHITECTS

6247 Brookside Blvd. #204 Kansas City, Mo 64113
Phone: 816-656-5055 Scharhagarch@gmail.com

Copyright 2025 Herman A. Scharhag Co., Architects
All Rights Reserved. No part of these drawings may be reproduced in any form or by any electronic or mechanical means, without written permission.

Door Schedule					
Number	Family	Type	hardware type	Door type	Frame Type
01	Storefront Entry Single	3'-0" x 7'-0"		AL	AL
02	Storefront Entry Single	3'-0" x 7'-0"		AL	AL
03	Storefront Entry Single	3'-0" x 7'-0"		AL	AL
04	Single-Flush	3 x 7 Toilet	Latchset w/ lever handles, strike plate, 1 1/2 pair hinges, closer	WD	HM
05	Single-Flush	3 x7 Exterior	Lockset w/ lever handles, strike plate, 1 1/2 pair hinges, closer, drip cap, gasketing, bottom sweep	HM	HM
06	Single-Flush	3 x7 Exterior	Lockset w/ lever handles, strike plate, 1 1/2 pair hinges, closer, drip cap, gasketing, bottom sweep	HM	HM
07	Single-Flush	3 x 7 Toilet	Latchset w/ lever handles, strike plate, 1 1/2 pair hinges, closer	WD	HM
08	Single-Flush	3 x7 Exterior	Lockset w/ lever handles, strike plate, 1 1/2 pair hinges, closer, drip cap, gasketing, bottom sweep	HM	HM
09	Single-Flush	3 x7 Exterior	Lockset w/ lever handles, strike plate, 1 1/2 pair hinges, closer, drip cap, gasketing, bottom sweep	HM	HM

HM = 16 GA. HOLLOW METAL, PAINTED
WD = SOLID CORE RED OAK, STAINED
AL = ANODIZED ALUMINIUM
IRP = IMPACT RESISTANT PLASTIC


HARDWARE SHALL BE MEDIUM DUTY COMMERCIAL GRADE. DOOR HARDWARE SHALL CONSIST OF BUTTS, LATCHSET OR LOCKSET, SILENCERS, SMOKE GASKETING FOR RATED DOORS, CLOSERS WHERE NOTED, PANIC DEVICES WHERE NOTED. EXTERIOR DOORS SHALL ALSO HAVE THRESHOLD, WEATHERSTRIPPINGS, SWEEP AND KEYED LOCK. CONTRACTOR SHALL COORDINATE ALL LATCH/LOCK FUNCTIONS AND KEYING OF LOCKS WITH OWNER. MAX. THRESHOLD = 1/2". ALL HARDWARE TO BE LEVER TYPE OR PUSH/PULL. ALL DOORS IN EGRESS PATHWAYS SHALL BE FREE TURNING FOR EXITING. ALL EGRESS DOORS SHALL BE READILY OPENABLE FROM THE EGRESS SIDE WITHOUT THE USE OF A KEY OR SPECIAL KNOWLEDGE OR EFFORT. FURTHER, ALL EGRESS DOORS FROM ROOMS AND EXTERIOR EGRESS DOORS, FOR GROUP A AND GROUP E OCCUPANCIES SHALL NOT HAVE A LOCK OR LATCH OTHER THAN PANIC HARDWARE. ALL DOOR THRESHOLDS SHALL BE A MAX. OF 1/4" ABOVE FLOOR LEVEL AND BOTH SIDES SHALL BE BEVELED AT A SLOPE OF 1:2. SCHLAGE OR EQUAL STANDARD DUTY HARDWARE (SATIN CHROME) WITH LEVERS.

GLASS IN DOORS AND SIDELIGHTS SHALL BE SAFETY GLASS PER IBC SEC. 2406.1


Wall Schedule			
Type Mark	Type	Type Comments	Function
1a	Interior Partition - Wood Stud	2x4 Wood studs @ 16" o.c. w/ 3 1/2" batt insulation and (1) layer 5/8" gyp. board each side. To 10'-0" aff	Interior
1b	Interior Partition -wet wall	2x6 Wood studs at 16" o.c. w/ 6" fiberglass batt insulation and (1) layer 5/8" gyp. board each side. To 10'-0" aff	Interior
1c	Interior Partition -Demising	6" 20 ga. metal studs at 16" o.c. w/ 6" fiberglass batt insulation and (1) layer 5/8" gyp. board each side. To roof deck with slip track.	Interior

Room Schedule					
Number	Name	Base Finish	Wall Finish	Floor Finish	Ceiling Finish
01	White Box	None	Painted gyp. b'd	Concrete	None
02	Owner's Room	None	Painted gyp. b'd	Concrete	2x4 Suspended Acoustical
03	Toilet	6" rubber cove	Epoxy Paint	LVT	2x4 Suspended Acoustical
04	Toilet	6" rubber cove	Epoxy Paint	LVT	2x4 Suspended Acoustical
05	Toilet	6" rubber cove	Epoxy Paint	LVT	2x4 Suspended Acoustical
06	Toilet	6" rubber cove	Epoxy Paint	Concrete	2x4 Suspended Acoustical


CEILING HEIGHT TO BE 9'-0" AFF



1 Window Elevation
1/2" = 1'-0"



2 Entry Detail
1/2" = 1'-0"



3 Awning detail
1/2" = 1'-0"

scharhag
HERMAN A. SCHARHAG COMPANY, ARCHITECTS

6247 Brookside Blvd, #204 Kansas City, Mo 64113
Phone: 816-666-5055 Scharhagarch@gmail.com


Copyright 2025 Herman A. Scharhag Co., Architects
All Rights Reserved. No part of these drawings may be reproduced in any form or by any electronic or mechanical means, without written permission.

NEW BUILDING FOR

SUMMIT ORCHARDS

410 NW CHIPMAN ROAD

J. Jeffrey Schroeder Mo. License A-4226
Herman Scharhag Co., Arch. Cert. of Authority A-22



1	No.	Description	Date
Revision Schedule			


Architectural
Details

Project number 2491
Date 05.30.2025


A102

Scale As indicated


5/31/2025 2:44:26 PM




3 Fire Extinguisher Detail
3/4" = 1'-0"




4 Unisex Handicapped toilet door detail
1/32" = 1'-0"





5 ADA Toilet Detail 1
1/4" = 1'-0"



1 ADA Toilet Detail 3
1/4" = 1'-0"



2 ADA Toilet Details 2017
1/4" = 1'-0"



SANITARY FACILITIES		ICC/ANSI A117.1-2017
1.	GENERAL -PROVIDE SUFFICIENT SPACE IN THE BATHROOM FOR A WHEELCHAIR MEASURING 30" WIDE X 48" LONG TO ENTER THE ROOM AND PERMIT THE DOOR TO CLOSE. THERE SHALL BE ROOM FOR A 67" DIA. TURNING CIRCLE AS SHOWN ON PLAN. THE WATER CLOSET SHALL BE LOCATED IN A SPACE WHICH PROVIDES A 60" WIDE CLEAR SPACE FROM A FIXTURE OR A WALL AT ONE SIDE AND 60" OF CLEAR SPACE IN FRONT OF THE WATER CLOSET.	
2.	DOORS -SANITARY FACILITY DOORS SHALL HAVE AN AUTOMATIC CLOSING DEVICE & BE 3'-0" WIDE	
3.	GRAB BARS - GRAB BARS SHALL BE AS PER DETAIL 3 & 4 AND SHALL BE CAPABLE OF CARRYING 250 LBS PER FT.	
4.	LAVATORY - LAVATORY HEIGHTS AND CLEARANCES SHALL COMPLY WITH DETAIL 2. INSULATE HOT WATER AND DRAIN PIPES UNDER LAVATORIES. NO SHARP OR ABRASIVE SURFACES ARE ALLOWED UNDER LAVATORIES. FAUCET CONTROLS AND OPERATING MECHANISMS ARE REQUIRED TO BE OPERABLE WITH ONE HAND AND CAN NOT REQUIRE GRASPING, PINCHING OR TWISTING OF THE WRIST. THE FORCE REQUIRED TO ACTIVATE CONTROLS IS NOT TO EXCEED 5 LB. LEVER-OPERATED, PUSH-TYPE, AND ELECTRONICALLY CONTROLLED MECHANISMS ARE EXAMPLES OF ACCEPTABLE DESIGNS. SELF-CLOSING VALVES ARE ALLOWED IF THE FAUCET REMAINS OPEN FOR AT LEAST 10 SECONDS.	
5.	ACCESSORIES - IF MIRRORS, PAPER TOWEL, SANITARY NAPKIN, WASTE RECEPTACLES AND SIMILAR DISPENSING AND DISPOSAL FIXTURES ARE PROVIDED, AT LEAST ONE OF EACH TYPE IS TO BE LOCATED WITH BOTTOM MAX. 40 INCHES ABOVE THE FLOOR.	
6.	FINISHES - FLOOR FINISH SHALL BE VCT WITH 6" RUBBER COVE BASE. WALL FINISHES WILL BE EPOXY PAINT	
7.	URINAL - IF PROVIDED, URINAL LIP SHALL BE MAX. 17" ABOVE FLOOR WITH A CLEAR SPACE OF 30" WIDE X 52" IN FRONT OF URINAL.	

scharhag
HERMAN A. SCHARHAG COMPANY, ARCHITECTS


6247 Brookside Blvd, #204 Kansas City, Mo 64113
Phone: 816-656-5055 Scharhagarch@gmail.com

Copyright 2025 Herman A. Scharhag Co., Architects
All Rights Reserved. No part of these drawings may be reproduced in any form or by any electronic or mechanical means, without written permission.

NEW BUILDING FOR

SUMMIT ORCHARDS
410 NW CHIPMAN ROAD

J. Jeffrey Schroeder Mo. License A-4226
Herman Scharhag Co., Arch. Cert. of Authority A-22



No.	Description	Date
Revision Schedule		


Architectural
Details

Project number	2491
Date	05.30.2025


A103

Scale As indicated


5/31/2025 2:44:27 PM




4 Pipe penetration
1" = 1'-0"



1 Roof Plan
1/8" = 1'-0"



2 Roof hatch w/ guard rail
1" = 1'-0"



SCUPPER DETAIL AT PARAPET WALL
NOT TO SCALE

3 Scupper detail
1/2" = 1'-0"


scharhag
HERMAN A. SCHARHAG COMPANY, ARCHITECTS

6247 Brookside Blvd, #204 Kansas City, Mo 64113
Phone: 816-656-5055 Scharhagarch@gmail.com

Copyright 2025 Herman A. Scharhag Co., Architects
All Rights Reserved. No part of these drawings may be reproduced in any form or by any electronic or mechanical means, without written permission.

NEW BUILDING FOR
SUMMIT ORCHARDS
410 NW CHIPMAN ROAD

J. Jeffrey Schroeder Mo. License A-4226
Herman Scharhag Co., Arch. Cert. of Authority A-22



No.	Description	Date
Revision Schedule		


Roof Plan

Project number 2491
Date 05.30.2025

A104

Scale As indicated

5/31/2025 2:44:27 PM




Phone: 816-656-5055 Scharhagarch@gmail.com

Copyright 2025 Herman A. Scharhag Co., Architects
All Rights Reserved. No part of these drawings may
reproduced in any form or by any electronic or
mechanical means, without written permission.



J. Jeffry Schroeder Mo. Licence A-4226
Herman Scharbag Co., Arch. Cert. of Authority A-



No.	Description	Date
Revision Schedule		


Trash Dumpster Details- 11x12

Project number	249
Date	05.30.20


A10

Scale As indicated


1111




4 Trash Dumpster Detail Wall Section
3/4" = 1'-0"



PLAN VIEW




② Hinge Detail Plan 12x12
1" = 1'-0"




ALL STEEL TO BE PAINTED
ALL CMU TO BE RECEIVE CLEAR SILICONE SEALANT @ EXTERIOR


1 Trash Dumpster Detail 11x12
1/2" = 1'-0"




SIDE ELEVATION




③ Trash Dumpster Detail - Hinge Detail
3/4" = 1'-0"




⑤ East - Callout 1
1/4" = 1'-0"




⑥ West - Callout 1
1/4" = 1'-0"




① East
1/8" = 1'-0"



④ West
1/8" = 1'-0"



② North
1/8" = 1'-0"



③ South
1/8" = 1'-0"

PROVIDE CLEAR SILICONE SEALER FOR BRICK

scharhag
HERMAN A. SCHARHAG COMPANY, ARCHITECTS

6247 Brookside Blvd, #204 Kansas City, Mo 64113
Phone: 816-656-5055 Scharhagarch@gmail.com

Copyright 2025 Herman A. Scharhag Co., Architects
All Rights Reserved. No part of these drawings may be reproduced in any form or by any electronic or mechanical means, without written permission.

NEW BUILDING FOR

SUMMIT ORCHARDS

410 NW CHIPMAN ROAD

J. Jeffrey Schroeder Mo. License A-4226
Herman Scharhag Co., Arch. Cert. of Authority A-22



1	No.	Description	Date
Revision Schedule			


Elevations

Project number	2491
Date	05.30.2025


A201

Scale As indicated


5/31/2025 2:44:31 PM




① East Color
1/8" = 1'-0"



④ West Color
1/8" = 1'-0"



② North Color
1/8" = 1'-0"



③ South Color
1/8" = 1'-0"

scharhag
HERMAN A. SCHARHAG COMPANY, ARCHITECTS

6247 Brookside Blvd, #204 Kansas City, Mo 64113
Phone: 816-656-5055 Scharhagarch@gmail.com


Copyright 2025 Herman A. Scharhag Co., Architects
All Rights Reserved. No part of these drawings may be reproduced in any form or by any electronic or mechanical means, without written permission.

NEW BUILDING FOR

SUMMIT ORCHARDS

410 NW CHIPMAN ROAD

J. Jeffrey Schroeder Mo. License A-4226
Herman Scharhag Co., Arch. Cert. of Authority A-22



Revision Schedule		
No.	Description	Date

Colored
Elevations


Project number 2491
Date 05.30.2025

A202


Scale 1/8" = 1'-0"

5/31/2025 2:44:35 PM


PROVIDE CLEAR SILICONE
SEALANT ON ALL SPLIT FACE
BLOCK




1 Section 1
1/2" = 1'-0"




2 Section 2
1/2" = 1'-0"




5 Section 1 - Callout 1
1" = 1'-0"



3 Section 3
1/2" = 1'-0"



6 Section 2 - Callout 1
1" = 1'-0"



4 Section 4
1/2" = 1'-0"

scharhag
HERMAN A. SCHARHAG COMPANY, ARCHITECTS

6247 Brookside Blvd, #204 Kansas City, Mo 64113
Phone: 816-656-5055 Scharhagarch@gmail.com

Copyright 2025 Herman A. Scharhag Co., Architects
All Rights Reserved. No part of these drawings may be reproduced in any form or by any electronic or mechanical means, without written permission.

NEW BUILDING FOR

SUMMIT ORCHARDS
410 NW CHIPMAN ROAD

J. Jeffrey Schroeder Mo. License A-4226
Herman Scharhag Co., Arch. Cert. of Authority A-22



No.	Description	Date
Revision Schedule		

Wall Sections

Project number 2491
Date 05.30.2025

A301

Scale As indicated

5/31/2025 2:44:35 PM

JOSEPH A. TOWNS, M.O. LIC. E-22017
LORAC DESIGN GROUP
CERT. OF AUTHORITY E-2005032846-D

STATE OF MISSOURI
REGISTERED PROFESSIONAL ENGINEER
JOSEPH ALAN TOWNS
NUMBER E-22017

No.	Description	Date
Revision Schedule		

Structural Notes

Project number	2491
Date	05.30.2025
S100	
Scale	As indicated

GENERAL NOTES

A. GENERAL

- These notes shall be read in conjunction with the Specifications and the Drawings. In the event of a conflict, notify the Architect for clarification.
- Before executing anything herein shown, examine actual job conditions. Report any discrepancy, dimensional or otherwise, between architectural and structural Drawings and any other error, omission, or difficulty affecting the work to the Architect and to the Structural Engineer for review.
- The Owner or his Representative reserves the right to inspect any material, fabrication, or workmanship at any time in field or shop for conformance to the Specifications and Drawings.
- All details and sections are intended to be typical and shall be construed to apply to any similar situation elsewhere, except where a different detail is shown.

B. DESIGN

- Codes, specifications and standards (latest editions, U.N.O.)
 - All design and construction shall conform to the International Building Code (currently adopted edition) as amended and adopted by the City of jurisdiction.
 - All construction shall comply with the provisions of the following codes, specifications and standards, except where noted to the contrary on drawings and specifications or where more stringent requirements are specified or shown:

ACI 117 "Standard Specifications for Tolerance for Concrete Construction and Materials"

ACI 301 "Specifications for Structural Concrete for Buildings"

ACI 318 "Building Code Requirements for Reinforced Concrete"

ACI 530 "Building Code Requirements for Masonry Structures"

AISC "Load and Resistance Factor Design (LRFD) Specification for Structural Steel Buildings"

SDI "Steel Deck Manual for Floor Decks and Roof Decks"

AWS D1.1 "Structural Welding Code - Steel"

C. CONCRETE

- Concrete used in the Work shall have the following minimum 28-day ultimate compressive strengths:
 - Columns 4000 psi
 - Retaining walls, slabs on grade, and footings 4000 psi
 - Framed slabs 4000 psi
- Air entrain all exterior concrete (admixture: ASTM C 260).
- Do not use calcium chloride admixtures under any circumstances.
- Reinforcing bars: ASTM A 615 Specifications, Grade 60, deformed. Bend bars cold.
- Welded wire fabric (WWF): ASTM A 185.
- Maintain minimum concrete coverage for reinforcing as indicated, unless noted otherwise. Reference details 17/S1.0 and 18/S1.0 for placement of reinforcement in typical framed slabs.
 - 3 in. clear where concrete is deposited directly against earth.
 - 2 in. clear where concrete is exposed to earth or weather but poured against forms for bars larger than #5.
 - 1-1/2 in. clear where concrete is exposed to earth or weather, but poured against forms for bars #5 or smaller.
 - 3/4 in. clear for slabs and walls formed above grade not exposed to weather.
 - 1-1/2 in. clear for beam and columns formed above grade and not exposed to weather.
- Lap all bars at splices in accordance with ACI 318, unless specifically noted otherwise.
- Top and bottom bars in continuous grade beams shall run continuously through multiple spans, where possible. Otherwise, top bars shall splice within the middle 1/3 span and bottom bars shall splice over supports.
- Pour columns, walls, and pilasters to be monolithic.
- All concrete walls shall be properly braced and held in line until supporting slabs or floors are in place.
- All bar steel and WWF shall be properly supported and held accurately in place as recommended by the Concrete Reinforcing Steel Institute, except that maximum spacing of any bar or mesh support shall be 3 feet.
 - Support top slab bars with continuous high chairs.
 - Support beam bars on heavy beam bolsters.
 - Support footing and grade beam bottom reinforcing on concrete bricks, concrete blocks, or mounds of poured concrete.
 - Support WWF in slab-on-grade properly at the mid-depth of the slab. Hooking and pulling up mesh after concrete has started to take its initial set is prohibited.
 - Supports for reinforcement for exposed-to-view concrete surfaces shall have legs that are in contact with forms plastic protected (CRSI, Class 1) or stainless steel (CRSI, Class 2).
- Where slabs-on-grade make an abrupt change in direction, such as at doors and corners or ends of walls, provide 2-#4 by 4 feet across the reentrant corner.
- Provide the following minimum concrete cover for fire rating:

Interior load bearing walls and columns 2 hrs 1 1/2" cover

Concrete beams 2 hrs 1 1/2" cover

Concrete joists 2 hrs 1 1/2" cover

Floor slab 2 hrs 3/4" cover

D. MASONRY

- Concrete masonry units (CMU): ASTM C 90, lightweight units (105 pcf or less), with the minimum net area compressive strength of 2200 psi.
- Mortar: Portland cement and lime, and proportioned in accordance with ASTM C 270 for the following types:

Type N - for all walls above grade

Type S - for all walls below grade, in contact with earth
- f'm = 1500 psi.
- Provide mortar bed on webs between grouted cells and hollow cells.
- Grout: ASTM C 476, 3000 psi minimum 28-day compressive strength.
- Grout all vertical cells and spaces containing reinforcing bars (as detailed) bond beams, and lintels.
- Vertically reinforce walls as shown on drawings. However, if not indicated on the drawing, reinforce wall as indicated below, at each corner, at ends of 48 inches horizontally throughout the wall, of walls, each side of control joints and openings, and at a maximum spacing unless noted otherwise.

8" or 6" wall #6

12" or 10" wall (2) #6

- Horizontally provide continuous bond beam with 2 #5 minimum for 12" or 10" CMU; 1 #5 minimum for 8" or 6" CMU at floor/roof, near midheight (10'-0 maximum spacing) and top of wall, unless noted otherwise. Provide #5 corner bar for each horizontal bond beam corners.
- Place reinforcement prior to grouting. Hold vertical reinforcement in position with rebar positioner.
- Provide horizontal joint reinforcement as indicated on the drawings and specifications, at a minimum provide at 16" o.c.
- Lap joint reinforcement a minimum of 12 in.
- In no case shall shores and forms at lintels be removed until it is certain that the masonry has hardened sufficiently to carry its own weight and all other reasonable temporary loads that may be placed on it during construction.
- Do not wet concrete masonry units.
- Do not use calcium chloride.
- Do not use masonry cement.
- Keep masonry walls shored during construction until the roof deck and floor slabs are in place to provide lateral stability.

E. STEEL

- Qualifications for Welding Work:
 - Perform all welding by a certified welder.
 - Qualify welding processes and welding operators in accordance with AWS "Standard Qualification Procedure".
 - Provide certifications that welders to be employed in work have satisfactorily passed AWS qualification tests within previous 12 months.

If recertification of welders is required, retesting will be Contractor's responsibility.
- Erector must examine areas and conditions under which structural steel work is to be installed, and notify Contractor in writing of conditions detrimental to proper and timely completion of Work. Do not proceed with work until unsatisfactory conditions have been corrected in a manner acceptable to the Erector.
- Submit shop drawings prepared under supervision of a registered professional engineer, including complete details and schedules for fabrication and assembly of structural steel members, procedures and diagrams. Include details of cuts, connections, camber, holes, and other pertinent data. Indicate welds by standard AWS symbols, and show size, length, and type of each weld. Show size and type of bolt for all bolted connections.
- Provide setting drawings, templates, and directions for installation of anchor bolts and other anchorages to be installed by others.
- Paragraph 4.2.1 of the (AISC) "Code of Standard Practice for Steel Buildings and Bridges" is hereby modified by deletion of the following sentence: "This approval constitutes the owner's acceptance of all responsibility for the design adequacy of any detail configuration of connections developed by the fabricator as a part of his preparation of these shop drawings."

If required cut edges of backing strips, extension bars, or run-off plates flush with edge of abutting parts.
- Where framing members and/or connections for steel stairs are not indicated on either structural or architectural drawings, Design the members and/or connections and submit calculations or supporting data to verify their adequacy. A live load of 125 psf shall be used in the design. Fully detail stair connections, including attachments to supporting members.
- Structural steel: ASTM A 572 - wide flange sections, ASTM A 36 - angles, channels, and plates, ASTM A 501 - pipes, and ASTM A 500, Grade B - tubes.
- High Strength Bolts (steel-to-steel connections): ASTM A 325N, with twist-off load indicator type heads.
- Anchor bolts: ASTM A 307, sizes indicated are based on preliminary reactions and spacing.
- Welded connections: AWS Standards and Specifications using E70xx electrodes, unless noted otherwise.
- Expansion Bolts: Stud type expansion anchors... (Hilti Kwik Bolt II).
- Injection Adhesive: Hilti Dowelling Anchor (HY-150); Rawl/Sika Foil-Fast; Ramset/Redhead Epcon Ceramic 6.
- Drill holes for anchors using a bit incapable of cutting steel. Do not cut existing concrete reinforcing steel. If, while drilling, reinforcing steel is encountered, notify the Structural Engineer for approval of new location. Cleaned and patch the abandoned hole grout.
- Ends of beams which have copes to the extent that allowable shear or bending stress of steel is exceeded shall have web plates of sufficient size welded to the beam to reduce such stresses.
- Provide holes required for securing other work to structural steel framing, and for passage of other work through steel framing members, as shown on final shop drawings.
- Do not flame cut holes or enlarge holes by burning.
- Set structural frames accurately to lines and elevations indicated. Align and adjust various members forming apart of a complete frame or structure before permanently fastening. Perform necessary adjustments to compensate for discrepancies in elevations and alignment.
- Provide temporary shoring and bracing members with connections of sufficient strength to bear imposed loads. Remove temporary members and connections when permanent members are in place and final connections are made. Provide temporary guy line to achieve proper alignment of structure as erection proceeds.
- Clean bearing surfaces of bond-reducing materials and roughen to improve bond to surfaces. Clean bottom surface of base plates.
- Grout plates are prohibited. Tighten anchor bolts after supported members have been positioned and plumbed. Do not remove wedges or shims, but if protruding, cut off flush with edge of base plate prior to packing with grout.
- Nonshrink grout: CRD-621 Type A, premixed, nonmetallic, noncorrosive, nonstaining.
- Provide open-web joists (K-series), longspan joists (LH-series), and joist girders as indicated on the Drawings and in accordance with specifications of SJI.
 - Weld K-series joists to supporting steel with 1/8 in. fillet welds in, long, each side, u.n.o.
 - Weld LH-series joists to supporting steel with 1/4 in. fillet welds 2 in. long, each side, u.n.o.
 - Bolt joists at or nearest a column to supporting steel in conformance with O.S.H.A. with erection bolts.
 - Provide continuous horizontal bridging for joists (u.n.o.) and bottom chord braces for joist girders as required by SJI, except where the net uplift loading requires additional bridging.
 - Provide horizontal bridging to resist 10psf uplift for main roof at service building and main building penthouse.
 - Extend bottom cord to brace beam bottom flange at mid-span of beams in service building.
- Form deck: 9/16 in. galvanized deck with the following minimum properties:

Minimum thickness 0.0295

Moment of Inertia 0.024 in ^4

Section Modulus 0.070 in ^3
- Composite floor deck: 1-1/2 in. galvanized deck with the following minimum properties:

Minimum thickness 0.0358

Moment of Inertia 0.195 in ^4

Section Modulus 0.240 in ^3
- Roof deck: 1-1/2" painted wide rib deck with the following minimum properties:

Minimum thickness 0.358

Moment of Inertia 0.212 in ^4

Section Modulus 0.234 in ^3
- Roof deck shall be welded to supports to resist a net uplift of 20 PSF.
- Provide 2-1/2" x 2-1/2" x 1/4" angles as required to support deck at columns, ends of beams, around openings, etc. Except as noted otherwise.
- Provide 1,500 # misc. steel for use by Engineer, as needed.

E. EPOXY AND MECHANICAL ANCHORS


- For concrete, grouted CMU, and solid masonry use Hilti HIT HY 150 two-part hybrid adhesive. For hollow CMU and masonry use Hilti HIT HY20 two-part hybrid adhesive with screen tubes. Equivalent adhesives may be used with prior written approval by the Structural Engineer.
- Thoroughly clean holes with nylon brush and pressurized air per manufacturers instructions.
- Drill holes to the embedment depths indicated on the drawings. If no depths are indicated, use 9 bolt or bar diameters with HY150 and 12 bolt diameters for HY 20.
- "Wedge" or "Expansion" anchors shall be Hilti Kwik bolt II expansion anchors. Embed anchor 7 bolt diameters unless noted otherwise. Equivalent anchors may be substituted with prior written approval of the Structural Engineer.

F. METAL STUDS

- Install cold-formed metal studs per drawings and manufacturer's recommendations. See Structural Plan for sizes and gauges.


G. CONSTRUCTION

- See architectural and mechanical requirements for embedded items not shown herein and to verify size and location of all openings.
- Coordinate the sizes and locations of all miscellaneous metal items required for mechanical and electrical.
- Requirements for embedded items, sleeves, block outs, duct openings, etc., in the concrete frame shall be submitted (plans and details) to the structural engineer for approval at least two weeks prior to the proposed date of casting concrete. No such items, other than those shown, shall be provided in the structure without the approval of the structural engineer.
- Provide adequate shoring or bracing during construction to resist forces such as wind and unbalanced loading due to construction.
- Field verify the location and depth (or height) of all utilities prior to beginning construction in order to provide adequate clearances and to insure noninterruption of service.




NOTE: TRUSS PROVIDER TO ALLOW 1500# RTU AT MID SPAN.


3 Snow Load Plan
1/16" = 1'-0"




2 Snow load
1/2" = 1'-0"



CORNER




INTERSECTION




FOOTING STEP

5 Typical Footing Detail
1/2" = 1'-0"

Structural Foundation Schedule		
Type Mark	Type	Type Comments
A	8'x 8' x 2'.0" deep	(7) #6's each way
B	4' x 4' x 3'.0" deep	(5) #5's each way at T & B w/ (1) #6 vert. @ each corner
C	Bearing Footing	2'.0" w x 3'.0" deep w/2/ (4) #5's cont. & #3 ties # 36" O.C. w/ #5 dowel 3' x 3' into slab @ 36" O.C.




BASE PLATE 'A'




BASE PLATE 'B'


2 Base Plate Details
1" = 1'-0"




CONTROL JOINT DETAIL




3 Sawcut Floor Slab
3/4" = 1'-0"




1 Foundation Plan
1/8" = 1'-0"



PLAN



4 Column Detail
1" = 1'-0"



6 Footing type 'C'
1/2" = 1'-0"

Scharhag

HERMAN A. SCHARHAG COMPANY, ARCHITECTS


6247 Brookside Blvd, #204 Kansas City, Mo 64113
Phone: 816-656-5055 Scharhagarch@gmail.com

NEW BUILDING FOR

SUMMIT ORCHARDS

410 NW CHIPMAN ROAD

JOSEPH A. TOWNS, MO. LIC. E-22017
LORAC DESIGN GROUP
CERT. OF AUTHORITY E-2005032846-D



No.	Description	Date
Revision Schedule		

Foundation

Project number 2491
Date 05.30.2025

S101

Scale As indicated

5/31/2025 2:44:36 PM

TRUSSES TO BEAR AT 12'-0" AFF
TRUSSES TO BE 4'-0" DEEP AT NORTH WALL
TRUSSES TO BE 2'-0" DEEP AT SOUTH WALL



LINTEL SCHEDULE

LINTEL TYPE 'A' THREE 2X12'S
LINTEL TYPE 'B' W14X26

PROVIDE (4) 2X6'S BEARING AT EACH END OF LINTELS


STRUCTURAL NOTES

1. TRUSS MANUFACTURER TO FURNISH ALL HOLD DOWNS AND CLIPS FOR WOOD TRUSSES
2. PROVIDE HEAVY DUTY CLIPS AT ALL PANEL EDGES PERPENDICULAR TO TRUSSES AT 2'-0" O.C. STAGGER END OF PANELS AND GAP ALL PANELS 1/16" AT ALL EDGES
3. PROVIDE SIMPSON H1 HOLD DOWN CLIPS FOR EACH TRUSS
4. ROOF SHEATHING TO BE 5/8" EXTERIOR APA PLYWOOD, NAILED WITH 10d NAILS AT 6" O.C. ALL AROUND PLYWOOD EDGES (BLOCKING AS REQUIRED) AND ALL AROUND ROOF PERIMETER WITH 10d NAILS AT 6" O.C. AT ALL INTERMEDIATE SUPPORTS
5. BRACING DESIGN BY TRUSS MANUFACTURER
6. TRUSS MANUFACTURER TO PROVIDE DESIGN DRAWINGS AND CALCULATIONS AND LAYOUT PLAN, SEALED BY REGISTERED ENGINEER, FOR REVIEW, AND FOR APPROVAL BY THE CITY
7. WALL SHEATHING TO BE 5/8" OSB, NAILED WITH 8d NAILS AT 6" O.C. AT ALL STUDS AND FULL PERIMETER OF EACH PLYWOOD SHEET (BLOCKING AS REQUIRED) AND ALL AROUND PERIMETER OF WALL AND AROUND ALL OPENINGS
8. SEE ARCHITECTURAL SHEETS FOR ALL OPENING HEIGHTS AND WIDTHS
9. ALL DOOR AND WINDOW OPENINGS TO BE SUPPORTED BY MIN. (3) 2X12 LINTEL ABOVE OPENING, BEARING ON (2) STUDS AT EACH SIDE
10. ALL STEEL LINTEL BEAMS TO BE SUPPORTED BY (4) 2X STUDS AT EACH END




NOTE: ALL EXTERIOR SHEATHING TO HAVE NAILS @ 4" O.C. AROUND EDGE AND 6" O.C. INFIELD.

5 Typical Exterior sheathing wood
1/2" = 1'-0"



NOTE: FOR TYPICAL SHEATHING DETAIL RE: 1/S001

3 typical section at truss bearing wood
1" = 1'-0"



NOTE: TRUSS ATTACHMENT TO BE SIMPSON H1 CLIPS

4 typical section at truss bearing 2 wood
1" = 1'-0"

Scharhag

HERMAN A. SCHARHAG COMPANY, ARCHITECTS


6247 Brookside Blvd, #204 Kansas City, Mo 64113
Phone: 816-656-5055 Scharhagarch@gmail.com

NEW BUILDING FOR

SUMMIT ORCHARDS

410 NW CHIPMAN ROAD

JOSEPH A. TOWNS, MO. LIC. E-22017
LORAC DESIGN GROUP
CERT. OF AUTHORITY E-2005032846-D



No.	Description	Date
Revision Schedule		

Framing


Project number 2491
Date 05.30.2025

S102

Scale As indicated

5/31/2025 2:44:36 PM

SPECIFICATIONS	LEGEND
GENERAL	SYMBOLDESCRIPTION
1. FOR ITEMS NOT COVERED BY THIS SPECIFICATION, REFER TO LATEST VERSION OF MASTERSPEC FOR REQUIREMENTS.	DEMOLITION
2. COORDINATION OF WORK: THE ELECTRICAL CONTRACTOR SHALL PLAN ALL WORK SUCH THAT IT PROCEEDS WITH A MINIMUM OF INTERFERENCE WITH OTHER TRADES. THE CONTRACTOR SHALL BE RESPONSIBLE TO COORDINATE THE INSTALLATION OF WORK WITH LIGHTING PLANS, REFLECTED CEILING PLANS, STRUCTURAL, AND ALL OTHER TRADES. THE INSTALLATION OF ALL EQUIPMENT, DEVICES AND MATERIALS REQUIRING MESS SHALL BE MADE IN SUCH A MANNER AS TO MAKE THE EQUIPMENT, DEVICES AND MATERIALS READILY ACCESSIBLE FOR OPERATION, MAINTENANCE AND REPAIRS.	20 AMP, 120V, NEMA 5-20R, DUPLEX RECEPTACLE
3. SUBSTITUTIONS FOR MATERIAL SPECIFIED: MATERIAL AND ITEMS OF EQUIPMENT FURNISHED MUST MEET THE REQUIREMENTS OF THE DRAWINGS AND SPECIFICATIONS AS TO QUALITY, PERFORMANCE, SUITABILITY, AND APPEARANCE. THIS IS AN "OR EQUAL" SPECIFICATION. ALTERNATE MATERIALS AND EQUIPMENT MAY BE SUPPLIED SIMILAR OR EQUAL TO THE PRODUCT OF THE MANUFACTURER SPECIFIED, GIVEN PRIOR APPROVAL OF THE DESIGN ENGINEER, AND SHALL BE SUPPLIED AT NO ADDITIONAL COST.	20 AMP, 120V, NEMA 5-20R, QUAD RECEPTACLE
4. ALL MATERIALS SHALL BE NEW, UNUSED, AND THE BEST OF THEIR RESPECTIVE KINDS AND FREE OF DEFECTS.	20 AMP, 120V, GFCI RECEPTACLE
5. DRAWINGS ARE DIAGRAMMATIC ONLY, INTENDING TO SHOW GENERAL ROUTING AND LOCATIONS OF THE WORK AND ARE NOT INTENDED TO BE RIGID IN SPECIFIC DETAIL.	50 AMP, 240V, SIMPLEX RECEPTACLE
6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR EXAMINING THE SITE IN RELATION TO THEIR WORK PRIOR TO INSTALLATION. NO ADDITIONAL COMPENSATION WILL BE ALLOWED FOR LACK OF COORDINATION DURING THE COURSE OF THIS CONTRACT.	20 AMP, 120V, DEDICATED DUPLEX RECEPTACLE
7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING ALL MEASUREMENTS AT THE SITE.	UTILITY METER
8. ALL WORK WITHIN THE CONTRACT AREA FURNISHED AND INSTALLED UNDER THE CONTRACT SHALL BE CLEANED TO THE SATISFACTION OF THE OWNER PRIOR TO TURNING OVER TO THE OWNER.	DISCONNECT SWITCH, NON-FUSED, 250V, U.N.O.
9. CONNECT NEW WORK TO EXISTING IN A NEAT AND WORKMAN LIKE MANNER.	FUSED DISCONNECT, SEE NOTATION
10. PROVIDE ALL NECESSARY FLASHING AND COUNTER FLASHING TO MAINTAIN THE INTEGRITY OF THE BUILDING AS REQUIRED BY THE INSTALLATION OR REMOVAL OF PIPES, DUCTS, CONDUIT, AND EQUIPMENT.	JUNCTION BOX, WALL MOUNTED
ELECTRICAL	JUNCTION BOX, CEILING MOUNTED
1. GENERAL:	TRANSFORMER
A. CODES AND PERMITS: ALL WORK SHALL BE INSTALLED IN ACCORDANCE WITH LOCAL AND STATE CODES AND UTILITY COMPANY REGULATIONS. ALL FEES AND PERMITS SHALL BE PAID FOR BY THE CONTRACTOR.	SURFACE MOUNTED ELECTRICAL PANEL
B. WORKMANSHIP: ALL MATERIALS SHALL BE INSTALLED PER MANUFACTURERS RECOMMENDATIONS AND IN ACCORDANCE WITH ACCEPTED GOOD PRACTICE OF THE INDUSTRY.	RECESSED ELECTRICAL PANEL
C. PROVIDE ACCESS PANELS IN HARD CEILINGS BELOW EQUIPMENT THAT REQUIRES ACCESS.	SURFACE-MOUNTED DOWNLIGHT
D. FIELD VERIFY AVAILABLE SPACE ABOVE CEILING BEFORE FABRICATION AND INSTALLATION OF DUCTWORK.	WALL-MOUNTED LUMINAIRE
E. REFER TO ARCHITECTURAL PLANS AND INTERIOR ELEVATIONS FOR FINAL RECEPTACLE AND DEVICE PLACEMENT. COORDINATE ALL RECEPTACLE MOUNTING LOCATIONS WITH FIXTURES, APPLIANCES, FURNITURE, CABINETRY, AND OTHER EQUIPMENT PRIOR TO ROUGH-IN.	EXIT SIGL. DIRECTIONAL ARROWS SHOW DIRECTION
F. REFER TO MECHANICAL EQUIPMENT SCHEDULE FOR CIRCUIT, DISCONNECT, AND CONDUCTORS FOR MECHANICAL EQUIPMENT.	EMERGENCY LIGHT FIXTURE
G. ELECTRICAL CONTRACTOR IS RESPONSIBLE FOR FIELD COORDINATING THE LOCATION OF ELECTRICAL EQUIPMENT JUNCTION BOXES, DISCONNECTS, ETC. EC SHALL BE RESPONSIBLE FOR COORDINATION AND THE ROUTING OF FEEDERS, AND BRANCH CIRCUITS. COORDINATE POWER CONNECTIONS FOR OWNER-PROVIDED EQUIPMENT AND APPLIANCES, AND ALL OTHER EQUIPMENT PROVIDED BY OTHER DIVISIONS WITH SUBMITTAL DATA CUT SHEETS, WIRING DIAGRAMS, AND MANUFACTURER'S WRITTEN INSTALLATION INSTRUCTIONS.	CEILING-MOUNTED OCCUPANCY SENSOR
H. FIELD COORDINATE FINAL LOCATIONS OF EQUIPMENT AND POWER CONNECTIONS WITH GENERAL CONTRACTOR AND OTHER DIVISIONS/CONTRACTORS PRIOR TO ROUGH-IN.	SINGLE POLE SWITCH
I. PROVIDE READILY ACCESSIBLE GROUND-FAULT CIRCUIT-INTERRUPTER (GFCI) PROTECTION FOR RECEPTACLES FOR APPLIANCES LISTED AND IN LOCATIONS REQUIRED IN NEC 210.8.	THREE WAY SWITCH
J. ELECTRICAL CONTRACTOR SHALL SIZE BRANCH CIRCUIT WIRING TO ACCOMMODATE FOR VOLTAGE DROP.	SWITCH: OCCUPANCY SENSOR
2. LIGHTING:	SWITCH: COMPATIBLE DIMMER
A. CIRCUIT ALL EMERGENCY LIGHTING AND EXIT SIGNS TO THE NEAREST LIGHTING BRANCH CIRCUIT AHEAD OF LOCAL SWITCH LEG.	2' X 4' LUMINAIRE, DIAGONAL INDICATES EM FUNCTION
B. LIGHT FIXTURES THAT APPEAR TO BE CENTERED IN A SPACE OR CEILING PANEL SHALL BE CENTERED UNLESS OTHERWISE NOTED.	LUMINAIRE TYPE (REFERENCE LUMINAIRE SCHEDULE) WATTAGE, IF SHOWN, REFERENCES ADJUSTABLE OUTPUT LOWER CASE ID, IF SHOWN, REF. WALL SWITCH/CONTROL SLD: ELECTRICAL PANEL
C. CONTRACTOR IS RESPONSIBLE FOR PROVIDING MOUNTING HARDWARE AND TRIMS REQUIRED FOR INSTALLING ALL LIGHT FIXTURES.	SLD: TRANSFORMER, RATING AS SHOWN
D. VERIFY ALL CEILING FINISHES, CEILING TYPES, AND CEILING THICKNESS PRIOR TO FINAL FIXTURE PURCHASE AND PROCUREMENT.	SLD: METER
E. ALL CONDUIT SHALL BE CONCEALED IN WALLS, FLOOR SLAB, OR ABOVE CEILING, WHERE POSSIBLE. ROUTE CONDUIT AS CLOSE TO STRUCTURAL SLAB OR DECK AS POSSIBLE, AND SUPPORT CONDUIT AND JUNCTION BOXES DIRECTLY FROM THE STRUCTURAL SLAB, DECK OR FRAMING PROVIDED FOR THAT PURPOSE.	SLD: CURRENT TRANSFORMER
F. CONTRACTOR SHALL COORDINATE THE EXACT LOCATION OF ALL EXPOSED CONDUIT WITH ARCHITECT PRIOR TO ROUGH-IN.	SLD: SWITCH, RATING AS SHOWN
G. REFER TO ARCHITECTURAL AND INTERIORS PACKAGE FOR FIXTURE INSTALLATION REQUIREMENTS, INCLUDING MOUNTING HEIGHTS AND MILLWORK DETAILS.	SLD: CIRCUIT BREAKER, RATING AS SHOWN
H. INTERRUPT POWER SUPPLY TO DEMONSTRATE PROPER OPERATION OF ALL EMERGENCY LIGHTING PRIOR TO JOB COMPLETION.	SLD: SAFETY SWITCH, NON-FUSED, 250V, U.N.O.
I. ALL DIMMED LIGHTING CIRCUITS ARE TO RECEIVE DEDICATED NEUTRALS. DO NOT SHARE NEUTRALS ON DIMMED LIGHTING CIRCUITS.	SLD: FUSED DISCONNECT
J. CONTRACTOR TO PROVIDE OWNER WITH A COMPLETE LISTING OF ALL LAMPS UTILIZED ON THE PROJECT INCLUDING MANUFACTURER AND CATALOG INFORMATION. PROVIDE A SUGGESTED SOURCE, INCLUDING CONTACT NAME AND PHONE NUMBER, FOR RE-ORDERING.	EQUIPMENT TAG
K. ALL LIGHT SWITCHES SHALL BE SPECIFICATION GRADE, QUIET OPERATION RATED 120/277VOLT, 20 AMPS, UNLESS OTHERWISE NOTED.	CIRCUIT HOMERUN - PANEL NAME/CIRCUIT NUMBER
L. ALL CONCEALED FIXTURES AND ASSOCIATED WIRING MUST BE CONCEALED FROM VIEW.	CONDUIT AND WIRE CONCEALED U.N.O.
M. FOR TRACK LIGHTING FIXTURES AND LINEAR LED SYSTEMS, ELECTRICAL CONTRACTOR MUST PROVIDE ALL NECESSARY COMPONENTS FOR A FULLY FUNCTIONING SYSTEM.	CONDUIT AND WIRE BELOW GRADE
N. EXIT SIGNS SHALL HAVE INTEGRAL EMERGENCY BATTERY BACK-UP.	STRAIGHT HASH MARKS: CURRENT-CARRYING CONDUCTORS EMPTY DOT: GROUNDED CONDUCTOR (NEUTRAL) ANGLED HASH: EQUIPMENT GROUNDING CONDUCTOR
O. PROVIDE LUMINAIRES SHOWN WITH EM INDICATOR WITH EMERGENCY BATTERY BALLASTS/DRIVERS.	KEY NOTE DESIGNATOR
P. EMERGENCY LUMINAIRES SHALL SENSE UNSWITCHED POWER TO THE SPACE AND OPERATE AUTOMATICALLY UPON LOSS OF NORMAL POWER.	CONTINUED, BUT NOT SHOWN
Q. ALL EMERGENCY LUMINAIRES SHALL HAVE ONE (1) 90 MINUTE EMERGENCY BALLAST.	
R. ALL EMERGENCY LUMINAIRES SHALL HAVE INTEGRAL TEST SWITCHES AND VISIBLE INDICATING LIGHTS. CONNECT THE EMERGENCY BATTERY BALLAST TO THE UN-SWITCHED LEG OF THE LIGHTING CIRCUIT INDICATED.	



ELECTRICAL FLOOR PLAN

SCALE: 3/16" = 1'-0" (36"x24" SHEET)

ELECTRICAL POWER KEYNOTES

- CONSULT LOCAL UTILITY FOR METER CAN REQUIREMENTS.
- DWH AND DISCONNECT MOUNTED OVERHEAD.

GENERAL POWER NOTES

- CONTRACTOR SHALL INSPECT SITE THOROUGHLY TO FAMILIARIZE THEMSELVES WITH THE AREA OF WORK. ANY DISCREPANCIES BETWEEN THESE DOCUMENTS AND ACTUAL CONDITIONS SHALL BE REPORTED TO THE GC/ENGINEER FOR RESOLUTION PRIOR TO BID PRICING.
- COORDINATE EQUIPMENT INSTALLATION WITH PLUMBING, MECHANICAL, FIRE PROTECTION, AND STRUCTURAL CONDITIONS. DUCTWORK AND REFRIGERATION LINE LOCATIONS SHALL TAKE PRECEDENCE OVER ELECTRICAL CONDUIT/CABLE TRAYS.
- CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING A COMPLETE AND WORKING SYSTEM.

NEW BUILDING FOR

SUMMIT ORCHARDS

LEES SUMMIT, MO



No.	Description	Date
Revision Schedule		

Project number	2491
Date	05.08.2025

E101





VUEngineering LLC

4437 Pennsylvannia Ave.

Kansas City MO 64111

www.VUEngineering.co
info@VUEngineering.co
816.888.2823
MO Cert. of Authority - LC 138664



 **LIGHTING PLAN**
SCALE: 3/16" = 1'-0" (36"x24" SHEET)

INTERIOR LIGHTING SCHEDULE						
ID	DESCRIPTION	MANUFACTURER	MODEL	LUMENS	WATTS	CCT
A	2X4' RECESSED LED - HIGH OUTPUT	RAB	EZPANFA2X4/D10	6,104	50W	4000K
B	SURFACE-MOUNT CEILING LIGHT	RAB	CRVFAS-11R-16-9CCT-120-W	1,150	16W	4000K
C	EXTERIOR DOOR LIGHT	INVUE	*ENT-SA1A-740-U-T4FT-BZ-EBP/BPC	1,924	20.1W	4000K
E	EMERGENCY LIGHT	ISOLITE	ELP-6V100-WH-MB-2-L66	N/A	100W	N/A
X	RED LED EXIT SIGN	DUAL-LITE	EVEURWE	N/A	2.01W	N/A

*INCLUDES BUTTON-TYPE PHOTOCELL. SUBSTITUTIONS REQUIRE INTEGRAL PHOTOCELL

LIGHTING KEYNOTES

1. INSTALL AS UNSWITCHED CIRCUIT FOR EXIT AND EMERGENCY LIGHTING. EXTERIOR DOOR EGRESS LIGHTING TO BE CONTROLLED BY PHOTOCELL.

GENERAL LIGHTING NOTES

- A. CONTRACTOR SHALL INSPECT SITE THOROUGHLY TO FAMILIARIZE THEMSELVES WITH THE AREA OF WORK. ANY DISCREPANCIES BETWEEN THESE DOCUMENTS AND ACTUAL CONDITIONS SHALL BE REPORTED TO THE GC/ENGINEER FOR RESOLUTION PRIOR TO BID PRICING.
- B. COORDINATE EQUIPMENT INSTALLATION WITH PLUMBING, MECHANICAL, FIRE PROTECTION, AND STRUCTURAL CONDITIONS. DUCTWORK AND REFRIGERATION LINE LOCATIONS SHALL TAKE PRECEDENCE OVER ELECTRICAL CONDUIT/CABLE TRAYS.
- C. CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING A COMPLETE AND WORKING SYSTEM.


NEW BUILDING FOR
SUMMIT ORCHARDS
LEES SUMMIT, MO



No.	Description	Date
Revision Schedule		

Project number 2491
Date 05.08.2025

E201



ELECTRICAL KEYNOTES

- BOND TO METAL WATER PIPING PER NEC 250.104
- GROUNDED CONDUCTORS SHALL BE #3AWG OR LARGER
- BOND NEUTRAL TO GROUND AT THIS LOCATION

GENERAL ELECTRICAL NOTES

- CONTRACTOR SHALL INSPECT SITE THOROUGHLY TO FAMILIARIZE THEMSELVES WITH THE AREA OF WORK. ANY DISCREPANCIES BETWEEN THESE DOCUMENTS AND ACTUAL CONDITIONS SHALL BE REPORTED TO THE ARCHITECT/ENGINEER FOR RESOLUTION PRIOR TO BID PRICING.
- COORDINATE ELECTRICAL INSTALLATION WITH PLUMBING, MECHANICAL, FIRE PROTECTION, AND STRUCTURAL CONDITIONS.
- CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING A COMPLETE AND WORKING SYSTEM.

PANEL: A1											
SUPPLIED FROM: UTILITY			VOLTS/PHASE: 208Y/120V, 3PH, 4W + G			LOCATION: UNIT A					
BUS RATING: 400A MCB			FAULT CURRENT (Isc):			SERVES: GENERAL POWER					
MAIN SIZE/PHASE: 400A-3P			MIN AIC RATING:			ENCL.: NEMA 1					

CKT	DESCRIPTION	CB AMP	P	VOLTSAMPS/PHASE						P	CB AMP	DESCRIPTION	CKT
				A	B	C	A	B	C				
1	RTU-A1	50	3	4,744			4,744			3	50	RTU-A2	2
3	---				4,744			4,744				---	4
5	---					4,744			4,744			---	6
7	RECEPTACLE	20	1	180			142			1	20	EMERGENCY LIGHTING	8
9	SPACE	0	1		0			150		1	20	AMBIENT LIGHTING	10
11	SPACE	0	1			0			0	1	0	SPACE	12
13	SPACE	0	1	0			0			1	0	SPACE	14
15	SPACE	0	1		0			0		1	0	SPACE	16
17	SPACE	0	1			0			0	1	0	SPACE	18
19	SPACE	0	1	0			0			1	0	SPACE	20
21	SPACE	0	1		0			0		1	0	SPACE	22
23	SPACE	0	1			0			0	1	0	SPACE	24
25	SPACE	0	1	0			0			1	0	SPACE	26
27	SPACE	0	1		0			0		1	0	SPACE	28
29	SPACE	0	1			0			0	1	0	SPACE	30
31	SPACE	0	1	0			0			1	0	SPACE	32
33	SPACE	0	1		0			0		1	0	SPACE	34
35	SPACE	0	1			0			0	1	0	SPACE	36
37	SPACE	0	1	0			0			1	0	SPACE	38
39	SPACE	0	1		0			0		1	0	SPACE	40
41	SPACE	0	1			0			0	1	0	SPACE	42
SUBTOTAL				4,924	4,744	4,744	4,886	4,894	4,744	SUBTOTAL			

TOTAL PHASE A - VA: 9,809	LOAD TYPE	CONN. VA	DF	LOAD TYPE	CONN. VA	DF
AMPS: 27	COOLING	28,461	1.00	REFRIGERATION	0	1.00
TOTAL PHASE B - VA: 9,637	HEATING	0	1.00	SIGN/DISPLAY	0	1.25
AMPS: 27	LIGHTING	292	1.25	KITCHEN	0	1.00
TOTAL PHASE C - VA: 9,487	RECEPTACLES	180	1.00/0.50	EXISTING	0	1.00
AMPS: 26	MOTORS	0	1.00	LARGE MOTOR	0	1.25
TOTAL PNLBRD - VA: 28,933	SUPP HEAT	0	1.00	SHOW WINDOW	0	1.25
CALCULATED AMPS: 80	MISC EQUIP	0	1.00	LTG TRACK	0	1.25
TOTAL DEMAND 29,006 VA 81 A						

PANEL: B1											
SUPPLIED FROM: UTILITY			VOLTS/PHASE: 208Y/120V, 3PH, 4W + G			LOCATION: UNIT B					
BUS RATING: 400A MCB			FAULT CURRENT (Isc):			SERVES: GENERAL POWER					
MAIN SIZE/PHASE: 400A-3P			MIN AIC RATING:			ENCL.: NEMA 1					

CKT	DESCRIPTION	CB AMP	P	VOLTSAMPS/PHASE						P	CB AMP	DESCRIPTION	CKT
				A	B	C	A	B	C				
1	RTU-B	40	3	2,906			180			1	20	RECEPTACLE	2
3	---				2,906			18		1	15	EXHAUST FAN EF-B	4
5	---					2,906			1,500	2	20	WATER HEATER DHW-B	6
7	EMERGENCY LIGHTING	20	1	142			1,500			1	0	SPACE	8
9	AMBIENT LIGHTING	20	1		166			0		1	0	SPACE	10
11	SPACE	0	1			0			0	1	0	SPACE	12
13	SPACE	0	1	0			0			1	0	SPACE	14
15	SPACE	0	1		0			0		1	0	SPACE	16
17	SPACE	0	1			0			0	1	0	SPACE	18
19	SPACE	0	1	0			0			1	0	SPACE	20
21	SPACE	0	1		0			0		1	0	SPACE	22
23	SPACE	0	1			0			0	1	0	SPACE	24
25	SPACE	0	1	0			0			1	0	SPACE	26
27	SPACE	0	1		0			0		1	0	SPACE	28
29	SPACE	0	1			0			0	1	0	SPACE	30
31	SPACE	0	1	0			0			1	0	SPACE	32
33	SPACE	0	1		0			0		1	0	SPACE	34
35	SPACE	0	1			0			0	1	0	SPACE	36
37	SPACE	0	1	0			0			1	0	SPACE	38
39	SPACE	0	1		0			0		1	0	SPACE	40
41	SPACE	0	1			0			0	1	0	SPACE	42
SUBTOTAL				3,048	3,072	2,906	1,680	18	1,500	SUBTOTAL			

TOTAL PHASE A - VA: 4,728	LOAD TYPE	CONN. VA	DF	LOAD TYPE	CONN. VA	DF
AMPS: 13	COOLING	8,718	1.00	REFRIGERATION	0	1.00
TOTAL PHASE B - VA: 3,090	HEATING	0	1.00	SIGN/DISPLAY	0	1.25
AMPS: 9	LIGHTING	308	1.25	KITCHEN	0	1.00
TOTAL PHASE C - VA: 4,406	RECEPTACLES	180	1.00/0.50	EXISTING	0	1.00
AMPS: 12	MOTORS	0	1.00	LARGE MOTOR	0	1.25
TOTAL PNLBRD - VA: 12,224	SUPP HEAT	0	1.00	SHOW WINDOW	0	1.25
CALCULATED AMPS: 34	MISC EQUIP	3,018	1.00	LTG TRACK	0	1.25
TOTAL DEMAND 12,301 VA 34 A						

PANEL: C1											
SUPPLIED FROM: UTILITY			VOLTS/PHASE: 208Y/120V, 3PH, 4W + G			LOCATION: UNIT A					
BUS RATING: 400A MCB			FAULT CURRENT (Isc):			SERVES: GENERAL POWER					
MAIN SIZE/PHASE: 400A-3P			MIN AIC RATING:			ENCL.: NEMA 1					

CKT	DESCRIPTION	CB AMP	P	VOLTSAMPS/PHASE						P	CB AMP	DESCRIPTION	CKT
				A	B	C	A	B	C				
1	RTU-C	80	3	6,521			180			1	20	RECEPTACLE	2
3	---				6,521			18		1	15	EXHAUST FAN EF-C	4
5	---					6,521			1,500	2	20	WATER HEATER DHW-C	6
7	EMERGENCY LIGHTING	20	1	142			1,500			1	0	SPACE	8
9	AMBIENT LIGHTING	20	1		166			0		1	0	SPACE	10
11	SPACE	0	1			0			0	1	0	SPACE	12
13	SPACE	0	1	0			0			1	0	SPACE	14
15	SPACE	0	1		0			0		1	0	SPACE	16
17	SPACE	0	1			0			0	1	0	SPACE	18
19	SPACE	0	1	0			0			1	0	SPACE	20
21	SPACE	0	1		0			0		1	0	SPACE	22
23	SPACE	0	1			0			0	1	0	SPACE	24
25	SPACE	0	1	0			0			1	0	SPACE	26
27	SPACE	0	1		0			0		1	0	SPACE	28
29	SPACE	0	1			0			0	1	0	SPACE	30
31	SPACE	0	1	0			0			1	0	SPACE	32
33	SPACE	0	1		0			0		1	0	SPACE	34
35	SPACE	0	1			0			0	1	0	SPACE	36
37	SPACE	0	1	0			0			1	0	SPACE	38
39	SPACE	0	1		0			0		1	0	SPACE	40
41	SPACE	0	1			0			0	1	0	SPACE	42
SUBTOTAL				6,663	6,687	6,521	1,680	18	1,500	SUBTOTAL			

TOTAL PHASE A - VA: 8,343	LOAD TYPE	CONN. VA	DF	LOAD TYPE	CONN. VA	DF
AMPS: 23	COOLING	19,562	1.00	REFRIGERATION	0	1.00
TOTAL PHASE B - VA: 6,704	HEATING	0	1.00	SIGN/DISPLAY	0	1.25
AMPS: 19	LIGHTING	308	1.25	KITCHEN	0	1.00
TOTAL PHASE C - VA: 8,021	RECEPTACLES	180	1.00/0.50	EXISTING	0	1.00
AMPS: 22	MOTORS	0	1.00	LARGE MOTOR	0	1.25
TOTAL PNLBRD - VA: 23,068	SUPP HEAT	0	1.00	SHOW WINDOW	0	1.25
CALCULATED AMPS: 64	MISC EQUIP	3,018	1.00	LTG TRACK	0	1.25
TOTAL DEMAND 23,145 VA 64 A						

SHORT-CIRCUIT FAULT CALCULATIONS

Distances are for calculation purposes only and shall not be used for contractor takeoffs nor bidding - Contractor shall notify Engineer of any field condition that results in a change of 10% or greater circuit distance.

The following calculations are based on the "Point-by-Point" method where:

$ISC(2) = ISC(1) \times M(1)$ $M = 1/(1+f)$ $Feeder: f(3\Phi) = \frac{1.732 \times L \times I_{sc}}{C \times E}$ $XFMR: f(3\Phi) = \frac{I_p(sca) \times V_p \times 1.732 \times \%Z}{100,000 \times kVA}$ $I_p(sca) = \frac{V_p \times M \times I_p(sca)}{V_s}$

Where:

$ISC(1)$ - short circuit current at fault point 1 $Feeder: f(1\Phi) = \frac{2 \times L \times I_{sc}}{C \times E}$ $XFMR: f(1\Phi) = \frac{I_p(sca) \times V_p \times \%Z}{100,000 \times kVA}$


$ISC(2)$ - short circuit current at fault point 2

L - Length of Conductor E - Line to line volts
C - "C" Factor from Bussman table where "C" = 1 / impedance per lineal foot
I_p - Primary short circuit current
V_p - Primary voltage
I_s - Secondary short circuit current
V_s - Secondary voltage



Feeder Types:
NM - Non Magnetic Conduit, M - Magnetic Conduit, FB - Feeder Busway, PB - Plug-in Busway, HI - High Impedance Busway, TX - Transformer

Fault Point (F#)	Bus/Feeder Description	Source (Fault Pnt)	Phase	Source Isc (Amps)	FEEDER Circuit Type	Material CU or AL	Wires # / Ø	Bus/Wire Size	Conductor C Value	Busway C Value	L-L Volts E	Circuit Lenth L (ft)	Load Power Factor (PF)	Circuit Load A	CONDUCTOR		Conductor Impedence Z / Ø	TRANSFORMER			Sec. Voltage V sec	f	M	FAULT CURRENT		Fault Point (F#)	
															Resistance R	Reactance X		Type	kVA	Degree Rise				Z	Isc		Isc sym RMS
0	Utility Service Point	∞	3		TX						208	-	-	416	-	-	-	150		1.07	208Y/120V, 3PH	-	-	93.46	38,912	38,912	0
1	To METER		3	38,912	M	CU	4	Set(s) of	#500	26706	480		0.9	179	0.000027	0.000039	0.45103	-				0.00	1.00	38,912	38,912	1	
2	To Panel A1		1	38,912	M	CU	2	Set(s) of	#3/0	12844	480	87	0.9	81	0.000079	0.000052	0.45103	-				0.476	0.68	26,371	26,371	2	
3	To Panel B1		1	38,912	M	CU	2	Set(s) of	#3/0	12844	480	64	0.9	34	0.000079	0.000052	0.45103	-				0.350	0.74	28,827	28,827	3	
4	To Panel C1		1	38,912	M	CU	2	Set(s) of	#3/0	12844	480	25	0.9	64	0.000079	0.000052	0.45103	-				0.137	0.88	34,234	34,234	4	
5	To Panel HOUSE		1	38,912	M	CU	1	Set(s) of	#1	7293	480	10	0.9	0.20	0.00016	0.000057	0.45103	-				0.193	0.84	32,630	32,630	5	

PLUMBING FIXTURE SCHEDULE											
MARK	FIXTURE TYPE	MINIMUM CONNECTION SIZE				MARK	FIXTURE TYPE	MINIMUM CONNECTION SIZE			
		WASTE	VENT	DCW	DHW			WASTE	VENT	DCW	DHW
WC1	WATER CLOSET (ADA)	4"	2"	1/2"	-	WCO	WALL CLEANOUT	-	-	-	-
		1. KOHLER CIMARRON MODEL K-3609 A. FLUSH TANK B. FLOOR MOUNTED C. ELONGATED BOWL D. VITREOUS CHINA E. 1.28 GALLON FLUSH F. COLOR WHITE 2. KOHLER LUSTRA TOILET SEAT A. ELONGATED B. OPEN FRONT C. SOLID PLASTIC D. HEAVY DUTY E. COLOR WHITE F. TOILET SEAT COVER 3. CONTRACTOR SHALL FURNISH AND INSTALL FIXTURE PER CURRENT ADA REQUIREMENTS						1. J.R. SMITH 4472T-U A. CAST BRONZE PLUG B. STAINLESS STEEL COVER C. VANDAL PROOF SCREW D. CLEANOUT TEE E. COUNTERSUNK PLUG			
L1	LAVATORY	1-1/2"	1-1/2"	1/2"	1/2"	FCO	FLOOR CLEANOUT	-	-	-	-
		1. AMERICAN STANDARD LUCERNE 0355.12 A. 20"x18" B. WALL HUNG C. VITREOUS CHINA D. COLOR WHITE E. OVERFLOW DRAIN F. WALL CARRIER 2. SLOAN OPTIMA EBF-650 A. BATTERY OPERATED SENSOR B. CHROME PLATED C. 0.5 GPM AERATOR D. THERMOSTATIC MIXING VALVE 3. TRUEBRO "LAV SHIELD" FURNISH & INSTALL PER ADA REQUIREMENTS COMPLETE WITH SOLID BRASS STOPS/STEMS AND CHLORAMINE-CHLORINE RESISTANT WASHERS AND BRAIDED STAINLESS STEEL CONNECTORS. CAST BRASS SOLID TOP OPEN GRID P.O. PLUG WITH 6" 17 GAUGE TAILPIECE WITH CAST BRASS LOCKNUT. HEAVY CAST BRASS ADJUSTABLE P-TRAP W/ 17 GA TUBULAR WALL BEND & BRASS SLIP NUTS. (ALL BRASS MATERIALS SHALL BE CHROME PLATED)						1. J.R. SMITH 4000 SERIES A. CAST IRON CONSTRUCTION B. INTERNAL TAPER BRONZE PLUG C. CAST IRON OR NICKEL BRONZE TOP PROVIDE SPECIFIC MODEL TO MATCH ASSOCIATED FLOOR TYPE.			
WH	WALL HYDRANT	-	-	3/4"	-	GCO	GRADE CLEANOUT	-	-	-	-
		1. WOODFORD B65 A. 3/4" LOOSE KEY FREEZELESS HYDRANT B. INTEGRAL ANTI-SIPHON VACUUM BREAKER-BACKFLOW PREVENTER C. 3/4" HOSE THREAD OUTLET D. ALUMINUM BOX AND DOOR E. LOOSE KEY FOR HYDRANT OPERATION F. CONTRACTOR TO VERIFY WALL THICKNESS PRIOR TO ORDERING WALL HYDRANT.						1. J.R. SMITH 4880-U A. CAST IRON CONSTRUCTION B. SCORIATED CAST IRON COVER C. VANDAL PROOF SCREWS			
BFP1/3/4/5/6	BACKFLOW PREV.	-	-	1"	-	FD	FLOOR DRAIN	2"	-	-	-
		1. WATTS LF909 A. 1" FOR DOMESTIC WATER ENTRY B. CAST COPPER SILICON BODY C. CAST COPPER SILICON TEST COCKS D. BRONZE STRAINER E. SILICON RUBBER DISCS F. MODEL 919AG AIR GAP FITTING G. PROVIDE DRAIN PIPE FROM AIR GAP FITTING TO FLOOR DRAIN WITH 1" AIR GAP AT FLOOR DRAIN.						1. J.R. SMITH 2005-A-NB A. CAST IRON CONSTRUCTION B. TWO PIECE BODY WITH FLANGE C. NICKEL BRONZE ROUND STRAINER D. INVERTABLE NON-PUNCTURING FLASHING COLLAR PROVIDE WITH RECTORSEAL SURESEAL SS2009V WATERLESS INLINE DRAIN TRAP SEAL.			
BFP2	BACKFLOW PREVENTER	-	-	1-1/2"	-						
		1. WATTS LF909 A. 1-1/2" FOR DOMESTIC WATER ENTRY B. CAST COPPER SILICON BODY C. CAST COPPER SILICON TEST COCKS D. BRONZE STRAINER E. SILICON RUBBER DISCS F. MODEL 919AG AIR GAP FITTING G. PROVIDE DRAIN PIPE FROM AIR GAP FITTING TO FLOOR DRAIN WITH 1" AIR GAP AT FLOOR DRAIN.									



PLUMBING FLOOR PLAN







PLUMBING KEYNOTES

- REFER TO CIVIL PLANS FOR CONTINUATION.
- NEW LOW PRESSURE GAS METER. REFER TO NATURAL GAS DETAIL FOR ADDITIONAL INFORMATION.
- REFER TO IRRIGATION PLANS FOR CONTINUATION.
- PROVIDE SHUT-OFF VALVE AND CAP FOR FUTURE CONNECTION.

GENERAL PLUMBING NOTES

- LOCATIONS, SIZES, AND QUANTITIES OF EXISTING EQUIPMENT AND PIPING ARE ESTIMATED, FIELD VERIFY EXACT LOCATIONS, SIZES, AND QUANTITIES BEFORE COMMENCING WORK. DEVIATIONS FROM CONDITIONS SHOWN ON THESE PLANS SHALL BE REPORTED TO THE ARCHITECT AND ENGINEER.
- PLUMBING INSTALLATIONS SHALL CONFORM TO LOCAL CODES. CONSULT WITH OWNER FOR CONNECTIONS TO ANY OWNER FURNISHED EQUIPMENT.
- PROVIDE WATER HAMMER ARRESTORS ON ALL RUNS WITH QUICK CLOSING VALVES. PROVIDE ACCESS PANELS FOR ALL VALVES AND WATER HAMMER ARRESTORS.
- PROVIDE BALL VALVE FOR ISOLATION OF ALL DOMESTIC WATER BRANCH LINES UNLESS OTHERWISE NOTED.
- SEE RISER DIAGRAMS FOR PIPE SIZING.



WASTE/VENT KEYNOTES

1. REFER TO CIVIL PLANS FOR CONTINUATION.


GENERAL WASTE/VENT NOTES

- A. CONTRACTOR SHALL INSPECT SITE THOROUGHLY TO FAMILIARIZE THEMSELVES WITH THE AREA OF WORK. ANY DISCREPANCIES BETWEEN THESE DOCUMENTS AND ACTUAL CONDITIONS SHALL BE REPORTED TO THE ARCHITECT/ENGINEER FOR RESOLUTION PRIOR TO PRICING.
- B. ABOVE-GRADE WASTE PIPE SHALL BE RUN AT 2% GRADE. BELOW-GRADE WASTE PIPE SHALL BE RUN AT 1% GRADE UNLESS NOTED OTHERWISE OR DICTATED BY CODE.
- C. ALL CONDENSATE DRAIN PIPE SHALL BE RUN AT 1% GRADE.
- D. ROUTE ALL PIPING INTENDED FOR ABOVE CEILING LEVEL INSTALLATION AS HIGH AS POSSIBLE. COORDINATE ROUTING WITH OTHER TRADES. SLOPED PIPING ELEVATIONS TAKE PRIORITY OVER ALL OTHER SYSTEMS AND TRADES.
- E. FIELD VERIFY LOCATION AND INVERTS OF SITE UTILITIES PRIOR TO INSTALLATION.
- F. PLUMBING VENTS SHALL TERMINATE A MIN. 10' FROM ALL OUTSIDE AIR INTAKES (OR EXTENDED A MIN. 3' ABOVE INTAKE).
- G. PROVIDE DRAIN TEMPERING VALVE FOR ANY WASTE WATER ABOVE 150°F.
- H. SEE RISER DIAGRAMS FOR PIPE SIZING.


No.	Description	Date
Revision Schedule		

Project number	2491
Date	05.08.2025

P102




WATER HEATER DETAIL




WATER SERVICE ENTRANCE
DETAIL (1" ENTRANCE)

WATER SERVICE ENTRANCE
DETAIL (1-1/2" ENTRANCE)



PROVIDE AND INSTALL B-LINE OR APPROVED EQUAL, HYDROUS CALCIUM SILICATE INSULATION WITH PRE-GALVANIZED STEEL JACKET AT HANGER, STRUT MOUNTED CLAMP, AND PIPE SUPPORT LOCATIONS.

PIPE SUPPORT INSULATION DETAILS



ROOF PIPE SUPPORT DETAIL

ROOFTOP UNIT SCHEDULE																
MARK	TOTAL CFM	OA CFM	ESP (IN)	COOLING CAP. (MBH)			HEATING CAP. (MBH)		MIN EER/SEER	ELECTRICAL DATA				WEIGHT (LBS)	MANUFACTURER & MODEL NO.	REMARKS
				EAT (F) DB/WB	TOTAL	SENSIBLE	INPUT	OUTPUT		VOLTAGE	HP	MCA	MOCP			
RTU-A1	3000	600	0.75	80/67	93.0	74.4	180	146	12.3/15.7	208/3	3.75	43	50	1440	LENNOX LGT092	1,2,3,4,5,6,7,8,10,12,14
RTU-A2	3000	600	0.75	80/67	93.0	74.4	180	146	12.3/15.7	208/3	3.75	43	50	1440	LENNOX LGT092	1,2,3,4,5,6,7,8,10,12,14
RTU-B	2000	400	0.75	80/67	60.9	48.7	150	121	12.7/17.1	208/3	1.5	28	40	1070	LENNOX LGT060	1,2,3,4,5,6,7,8,12
RTU-C	5000	1000	0.75	80/67	141.0	112.8	240	194	10.8/14.6	208/3	3.75	64	80	1440	LENNOX LGT150	1,2,3,4,5,6,7,8,10,12,14


1. LISTED CAPACITIES AT 1000 FT ELEVATION, AND 95°F AMBIENT TEMPERATURE.
2. FURNISH WITH FACTORY INSTALLED DISCONNECT SWITCH.
3. REFRIGERANT TYPE R410A.
4. LISTED WEIGHT INCLUDES ROOF CURB.
5. PROVIDE NEW PROGRAMMABLE THERMOSTAT.
6. PROVIDE WITH HAIL GUARDS.
7. PROVIDE WITH HOT GAS REHEAT HUMIDITY CONTROL.
8. PROVIDE ECONOMIZER WITH DRY BULB CONTROL AND POWERED RELIEF.
9. PROVIDE ECONOMIZER WITH DRY BULB CONTROL AND BAROMETRIC RELIEF.
10. PROVIDE DEMAND CONTROL VENTILATION CONTROLS. LISTED MAX OA CFM IS SHALL BE UPPER SETPOINT, WHILE NOT IN ECONOMIZER, WHEN CO2 LEVELS ARE AT 800PPM OR HIGHER.
11. PROVIDE WITH UV-C LAMP OR GPS PLASMA AIR PURIFIER.
12. PROVIDE SMOKE DETECTORS IN SUPPLY AND RETURN DUCTWORK. DETECTOR IS TO BE PRE-WIRED TO SHUTDOWN THE FAN MOTOR UPON ACTIVATION. COORDINATE ANY REQUIRED INTERLOCKS AND INTERFACE WITH THE BUILDING FIRE ALARM SYSTEM. PROVIDE ALL REQUIRED SERVICE ACCESS TO NEW SMOKE DETECTOR PER CODE.
13. CONNECT TO EXISTING ELECTRICAL CONNECTION. FIELD VERIFY THAT CIRCUIT BREAKER AND BRANCH CIRCUIT CONDUCTOR SIZE ARE SUFFICIENT FOR NEW UNIT OR UPGRADE AS REQUIRED.
14. PROVIDE VARIABLE FAN SPEED THAT IS AUTOMATICALLY CONTROLLED BY HEATING/COOING DEMAND.

EXHAUST FAN SCHEDULE									
MARK	TYPE	MAKE & MODEL	CFM	E.S.P. (IN. WC.)	MAX SONES	DRIVE	ELEC. CHAR.		REMARKS
EF-B/C	CEILING	GREENHECK SP-A110	75	0.3	8	DIRECT	VOLTAGE	HP	1,2,3,4,5


1. LISTED CAPACITIES AT SEA LEVEL.
2. PROVIDE WITH FACTORY MOUNTED DISCONNECT SWITCH.
3. FAN SHALL BE INTERLOCKED WITH LIGHT SWITCH.
4. PROVIDE WITH GRAVITY BACKDRAFT DAMPER.
5. PROVIDE WITH 7"Ø ROOF CAP, GREENHECK RCC-7 OR EQUIVALENT, WITH CURB AND INSECT SCREEN.

WATER HEATER (ELECTRIC)							
MARK	MAKE & MODEL	HTG. INPUT (KW)	RECOVERY @90F (GPH)	TEMP. RISE (F)	STORAGE (GAL)	ELECTRICAL	REMARKS
DWH-B	AO SMITH - EJC6	3	8	90	6	240V	1,2,3,4,5
DWH-C	AO SMITH - EJC6	3	8	90	6	240V	1,2,3,4,5

1. PROVIDE DISCONNECT SWITCH.
2. PROVIDE WITH HEAT TRAP FITTINGS ON COLD AND HOT WATER PIPING CONNECTIONS.
3. FURNISH WITH AMTROL MODEL ST-12 THERMAL EXPANSION TANK, ET-1.
4. PROVIDE T&P VALVE.
5. SET WATER HEATER OUTLET TEMPERATURE AT 110°F.



ROOFTOP UNIT CURB DETAIL



ROOFTOP UNIT DETAIL

Ventilation Spreadsheet (2018 IMC Table 403.3)									
Zone	Room	Use/Classification	Area	People	CFM/Person	CFM/SF	Ventilation Effectiveness	OA	
Tenant A	Tenant Space	Dining Rooms	1072	36	7.5	0.18	80%	463	
	Tenant Space	Kitchen	700	6	7.5	0.12	80%	129	
								Outdoor Air Required	592
								Outdoor Air Provided	2200
Tenant B	Tenant Space	Retail Sales	1249	19	7.5	0.12	80%	290	
								Outdoor Air Required	290
								Outdoor Air Provided	440
Tenant C	Tenant Space	Retail Sales	1793	27	7.5	0.12	80%	417	
								Outdoor Air Required	417
								Outdoor Air Provided	440