SCOPE OF WORK DETAIL: Refer to all attachments in ORCA for specific requirements. Specific Requirements: Reach info: Bill Coday 816-803-4924 /wc7681@att.com. Please update via email with what is placed and upon finishing project. All work to be done as shown on work prints unless otherwise noted here in scope of work detail. Final walk through or pics required for final billing. All changes must be pre-approved prior to work being done (Codes and Cost w/ email approval from LCE).

Project Number: A057LQZ

| Project Number: A05/LQZ | |
|--------------------------------|--|
| Project Name: | -EE4160-PFP* A057LQZ |
| Estimated In- Service Date: | 30-Jul-2025 |
| Project Description: | PFP*-KSCYMO41-@NW MAIN ST AND NW SLOAN-KSCYMO411208PA |
| Mod Code: | FPPFP 100% |
| GEO LOC: | EE4160 |
| FRC: | 845C |
| Project Notes: | WHAT: THIS PROJECT PROVIDES FOR GREENFIELD - MDU AT @NW MAIN ST AND NW SLOAN MAJOR ITEMS OF WORK CONSIST OF PLACING (1) PFP SIZE 864, (2) SPLITTER(S) OF 1X64 USING SPLITTERS # (1-2). THE FIELD ENGINEER WILL SPECIFY SITE REQUIREMENTS AND HAS THE OPTION TO CHANGE EQUIPMENT TYPE AS NECESSARY. FIBERS ASSIGNED ARE: L2012, 193-194. FIBERS ALLOCATED ARE: L2012, 195-204. SPLITTERS COUNT: SPT1208PA, 1-128. |
| | 1. AT HHFID: 99659828 PLACE 144 NEW CABLE UPTO NEW PFP 1100 NW MAIN ST AND NW SLOAN. CABLE PLACEMENT 1. 426' 5BQ2MT-144 (PPA) 845C 2. 2-100' FBRTLTS-144 (PPA) 845C CONDUIT PLACEMENT 1. 2' 4"-PVC (PPA) 845C 2. 326' INNERDUCT (PPA) 845C STRUCTURE PLACEMENT PLACE (1) PFP BABMS864-100ST (PPA) 845C PLACE (2) 1X64 SPL |
| | WHERE: PFP ADDRESS: @NW MAIN ST AND NW SLOAN PSA ID: 1208PA WIRE CENTER: KSCYMO41. |
| | WHY: THIS WORK IS TRIGGERED BY KSCYMO411208PA. DEVLOG 278929 |
| | WHY THIS WAY: LEES SUMMIT IS AN FITP APPROVED WIRE CENTER AND THIS IS TRANSMITED ONLY ON A FIBER MEDIUM. LEGACY T FIBERS WERE CONSIDERED BUT NOT USED FOR THIS PROJECT. IT HAS BEEN DETERMINED THAT THE CLOSEST ACCESS POINT TO ANY LEGACY T FIBERS WOULD MAKE THIS PROJECT MORE COSTLY THAN UTILIZING EXISTING LOOP FIBERS. THIS PFP IS SIZED TO PROVIDE SERVICE FOR 154 ULTIMATE UNITS AND 0 BUSINESS UNITS. THIS PROJECT HAS BEEN PREPARED IN ACCORDANCE WITH THE CURRENT CLRS. |
| | WHY NOW: THE ESTIMATED IN SERVICE DATE IS 2025-06-30. PM TO DETERMINE FINAL OSP DUE DATE. PUBLIC NOTIFICATION OF NETWORK CHANGE IS NOT REQUIRED. THIS IS A COMPLETE UNDERTAKING. |