

										DRAWING INDEX											
										6/18/2025											
										SHEET #		SHEET NAME									
										● G-0.0		COVER SHEET, CODE INFO, PROJECT DATA, & DIRECTORY									
										● G-0.1		SPECIFICATIONS & GENERAL NOTES									
										● G-0.2		DIVISION OF WORK & SYMBOL LEGEND									
										● D-1.1		DEMOLITION PLANS									
										● A-0.1		SCHEDULES									
										● A-1.1		CONSTRUCTION PLAN, SCHEDULES, & NOTES									
										● A-1.2		FITTING ROOM PLAN, ELEVATIONS & DETAILS									
										● A-1.3		TOILET ROOM PLAN, ELEVATIONS & DETAILS									
										● A-1.4		CONSTRUCTION DETAILS									
										● A-2.1		REFLECTED CEILING PLAN & DETAILS									
										● A-3.1		EXTERIOR ELEVATION									
										● A-4.1		INTERIOR ELEVATIONS									
										● A-5.1		FINISH PLAN									
										● A-6.1		LOW VOLTAGE PLAN									
										● F-1.1		FIXTURE PLAN, SCHEDULE & NOTES									
										● F-1.2		FIXTURE DETAILS									
										● F-2.1		INTERIOR SIGNAGE & GRAPHICS PLAN, & DETAILS									
										● E-001		ELECTRICAL COVER SHEET									
										● E-100		ELECTRIC LIGHTING PLAN									
										● E-101		ELECTRIC LIGHTING - DETAILS									
										● E-200		ELECTRIC POWER PLAN									
										● E-300		ELECTRIC POWER - SINGLE LINE DIAGRAM									
										● E-301		ELECTRIC PANEL SCHEDULES									
										● E-400		ENERGY COMPLIANCE									
										● E-500		ELECTRICAL SPECIFICATIONS									
										● E-501		ELECTRICAL SPECIFICATIONS									
										● M-001		MECHANICAL COVER SHEET									
										● M-101		MECHANICAL DUCTWORK PLAN									
										● M-401		ENERGY COMPLIANCE									
										● M-402		ENERGY COMPLIANCE									
										● M-501		MECHANICAL SPECIFICATIONS									
										● M-502		MECHANICAL SPECIFICATIONS									
										● M-601		MECHANICAL DETAILS									
										● M-602		MECHANICAL SPECIFICATIONS									
										● P-001		PLUMBING COVER SHEET									
										● P-101		PLUMBING PLAN									
										● P-501		PLUMBING SPECIFICATIONS									
										● P-601		PLUMBING DETAILS & SCHEDULES									
-		SHEET INDEX																			
FIXTURES - GRAND + BENEDICTS C: MOLLY CROUSER T: 503.233.6222 E: MOLLYC@GRAND-BENEDICTS.COM											STOCK ROOM FIXTURES - PIPP MOBILE STORAGE SYSTEMS, INC. C: KATY LOWRY T: 616.988.4063 E: KLOWRY@PIPPMOBILE.COM										
LIGHTING - CITY LIGHTING C: TOM MISPAGE T: 314.534.1090 E: TMISPAGEL@CITYLIGHTING.COM											SENSORMATIC - JOHNSON CONTROLS C: MH TOTH T: 699.271.8401 E: MH.TOTH@JCI.COM										
LOCKS / SAFE - REDFORD LOCK SECURITY SOLUTIONS C: DAVID BOILORE T: 313.401.7004 E: DBOILORE@REDLORDLOCK.COM																					
SIGNAGE - VICTORY SIGN INDUSTRIES C: DANA REYNOLDS T: 706.820.6820 E: DREYNOLDS@VICTORYSIGN.COM																					
-		VENDOR CONTACTS																			
LANDLORD - TENANT COORDINATOR SUMMIT WOODS CROSSING 1700 NW CHIPMAN RD LEE'S SUMMIT, MO 64081 C: JOSH GALICA E: JGALICA@RAINIERCOMPANIES.COM											PROGRAM MANAGER RGLA SOLUTIONS, INC. 5100 RIVER ROAD, SUITE 125 SCHILLER PARK, IL 60176 C: SANDI LEAMON / ADRIAN TAFOLLA P: 847.707.7452 / 847.916.2728 E: SLEAMON@RGLA.COM / ATAFOLLA@RGLA.COM										
TENANT / OWNER CARHARTT INC. 5750 MERCURY DRIVE DEARBORN, MI 48126 C: MARK KASTNER T: 313.212.7021 E: MKASTNER@CARHARTT.COM											MEP ENGINEER KLH ENGINEERS, PSC 333 EAST MAIN, SUITE 175 LEXINGTON, KY 40507 C: JORDAN LAYCOCK T: 859.547.0242 E: JLAYCOCK@KLHENGERS.COM										
ARCHITECT JOSEPH A. GEOGHEGAN JR. ROBERT G. LYON & ASSOCIATES, INC. 5100 RIVER ROAD, SUITE 125 SCHILLER PARK, IL 60176 PLEASE CONTACT PROGRAM MANAGER FOR ALL INQUIRIES.																					
-		PROJECT DIRECTORY																			

UPON AWARDING THE GENERAL CONTRACTOR'S CONTRACT, THE GENERAL CONTRACTOR MUST INFORM THE OWNER (CARHARTT) IN WRITING OF ALL MATERIALS AND EQUIPMENT WITH LEAD TIMES OF 4 WEEKS OR GREATER

WORK UNDER SEPARATE PERMIT:

- SPRINKLER WORK
- FIRE ALARM
- STOREFRONT SIGNAGE

ALL MATERIAL SUBSTITUTIONS MUST OBTAIN OWNER AND ARCHITECT'S APPROVAL PRIOR TO COMMENCEMENT

GC SHALL PROVIDE CARPENTER ON-SITE FOR ONE EIGHT-HOUR DAY AFTER TURNOVER FOR MISCELLANEOUS TASKS.

REQUIRED SUBCONTRACTORS:

VERIFY WITH MALL OPERATIONS MANAGER FOR ALL REQUIRED SUBCONTRACTORS.

ALL CHANGE ORDERS TO BE APPROVED BY CARHARTT - MARK KASTNER - IN WRITING PRIOR TO PROCEEDING WITH WORK. ANY WORK COMPLETED WITHOUT AN APPROVED CHANGE ORDER WILL NOT BE PAID.


WORK UNDER SEPARATE PERMIT:

- SPRINKLER WORK
- FIRE ALARM
- STOREFRONT SIGNAGE

ALL MATERIAL SUBSTITUTIONS MUST OBTAIN OWNER AND ARCHITECT'S APPROVAL PRIOR TO COMMENCEMENT

GC SHALL PROVIDE CARPENTER ON-SITE FOR ONE EIGHT-HOUR DAY AFTER TURNOVER FOR MISCELLANEOUS TASKS.

REQUIRED SUBCONTRACTORS:  
VERIFY WITH MALL OPERATIONS MANAGER FOR ALL  
REQUIRED SUBCONTRACTORS.




<p><u>SCOPE OF WORK STATEMENT</u></p> <p>THE INTENT OF THE SCOPE CONTAINED WITHIN THESE DOCUMENTS RELATES TO THE INTERIOR BUILD-OUT OF A MERCANTILE SPACE CONTAINED WITHIN AN EXISTING SHOPPING CENTER. PROPOSED WORK INCLUDES CONSTRUCTION AND INSTALLATION OF NEW NON-LOAD BEARING PARTITIONS, FIXTURES, FINISHES, LIGHTING, MECHANICAL, ELECTRICAL, AND PLUMBING.</p>	<p><u>PERMIT SCOPE INCLUDES</u></p> <p>ONLY CHECKED BOXES</p> <p><input checked="" type="checkbox"/> BUILDING</p> <p><input checked="" type="checkbox"/> MECHANICAL</p> <p><input checked="" type="checkbox"/> ELECTRICAL</p> <p><input checked="" type="checkbox"/> PLUMBING</p> <p><input type="checkbox"/> SPRINKLER</p> <p><input type="checkbox"/> STOREFRONT SIGN</p>
<p><u>MALL TYPE</u></p> <p><input type="checkbox"/> COVERED MALL BUILDING</p> <p><input type="checkbox"/> EXTERIOR MALL</p> <p><input type="checkbox"/> STREET LOCATION</p>	

- SCOPE OF WORK

APPLICABLE CODES	
BUILDING:	2018 INTERNATIONAL BUILDING CODE
ELECTRICAL:	2017 NATIONAL ELECTRICAL CODE
MECHANICAL:	2018 INTERNATIONAL MECHANICAL CODE
PLUMBING:	2018 INTERNATIONAL PLUMBING CODE
ACCESSIBILITY:	ICC/ANSI A117.1-2009
FIRE CODE:	2018 INTERNATIONAL FIRE CODE
ENERGY CODE:	2018 INTERNATIONAL ENERGY CONSERVATION CODE
EXISTING BUILDING CODE:	2018 INTERNATIONAL EXISTING BUILDING CODE

OCCUPANCY LOAD CALCULATIONS		
GROSS AREA:	5,510 SQ.FT. (LEASED AREA)	
SALES AREA:	3,871 SQ.FT. / 60 SQ.FT. PER PERSON =	65
FITTING ROOM AREA:	181 SQ.FT. / 60 SQ.FT. PER PERSON =	3
TOILET ROOM:	1 PRIVATE TOILET ROOM =	1
OFFICE	1 PRIVATE OFFICE =	1
HALLWAY	257 SQ.FT. / 300 SQ.FT. PER PERSON =	1
BREAK ROOM	181 SQ.FT. / 300 SQ.FT. PER PERSON =	1
STOCKROOM:	908 SQ.FT. / 300 SQ.FT. PER PERSON =	3
TOTAL OCCUPANCY:		75 PERSONS

BUILDING REQUIREMENTS		
DESCRIPTION	CODE SECTION	REQUIREMENTS
USE GROUP:	IBC CHAPTER 3, SECTION 309	M (MERCANTILE)
NUMBER OF LEVELS:		LOCATED ON GROUND LEVEL OF 1 LEVEL
CONSTRUCTION TYPE:	IBC TABLE 601	TYPE II B
FIRE SPRINKLERS:	IBC SECTIONS 506.3, 903.1	FULLY SPRINKLERED
TENANT AREA:	IBC SECTION 507.3	5,510 SQ.FT. AREA OF WORK
OCCUPANT LOAD:	IBC SECTION 1004.1 & NFPA 101	75 PERSONS
NUMBER OF EXITS:	IBC TABLE 1006.3	2 REQUIRED
		2 PROVIDED
EXIT WIDTH:	IBC TABLE 1005.1	30" REQUIRED
		108" PROVIDED

-	CODE AND BUILDING SUMMARY
<p><u>STATEMENT OF COMPLIANCE</u></p> <p>I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND TO THE BEST OF MY PROFESSIONAL KNOWLEDGE THEY CONFORM TO THE CODES AND ORDINANCES OF LEE'S SUMMIT, MO.</p> <p>JOSEPH A. GEOGHEGAN JR.          LICENSE #: A-2008008193          EXPIRATION DATE: 12/31/2026</p> <p>SEAL:</p> 	
-	CERTIFICATION STATEMENT

WINTER ROAD

NW CHIPMAN ROAD

EXISTING ACCESSIBLE PARKING

PROPOSED CARHARTT SPACE

North Arrow

[illegible]

NUMBER OF LEVELS:		LOCATED ON ROUND LEVEL OF 1 LEVEL
CONSTRUCTION TYPE:	IBC TABLE 601	TYPE II B
FIRE SPRINKLERS:	IBC SECTIONS 506.3, 903.1	FULLY SPRINKLERED
TENANT AREA:	IBC SECTION 507.3	5,510 SQ.FT. AREA OF WORK
OCCUPANT LOAD:	IBC SECTION 1004.1 & NFPA 101	75 PERSONS
NUMBER OF EXITS:	IBC TABLE 1006.3	2 REQUIRED
		2 PROVIDED
EXIT WIDTH:	IBC TABLE 1005.1	30" REQUIRED
		108" PROVIDED
-	CODE AND BUILDING SUMMARY	
<p><u>STATEMENT OF COMPLIANCE</u></p> <p>I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND TO THE BEST OF MY PROFESSIONAL KNOWLEDGE THEY CONFORM TO THE CODES AND ORDINANCES OF LEE'S SUMMIT, MO.</p> <p>JOSEPH A. GEOGHEGAN JR.          LICENSE # : A-2008008193          EXPIRATION DATE: 12/31/2026</p> <p>SEAL:</p>		
-	CERTIFICATION STATEMENT	



## SUMMIT WOODS CROSSING


1744 NW CHIPMAN ROAD  
LEE'S SUMMIT, MO 64081



**rgla solutions, inc.**  
5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
[www.rgla.com](http://www.rgla.com)

REVISIONS:	DATE:
ISSUE FOR PERMIT, LANDLORD, PRICING	06/18/25

**robert g. lyon + associates, inc.**  
retail architecture  
5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
[www.rfgla.com](http://www.rfgla.com)



THE ABOVE DRAWINGS AND SPECIFICATIONS AND IDEAS, DESIGNS AND ARRANGEMENTS REPRESENTED THEREBY ARE AND SHALL REMAIN THE PROPERTY OF THIS OFFICE. AND NO PART THEREOF SHALL BE COPIED, DISCLOSED TO OTHERS OR USED IN THE CONNECTION WITH ANY WORK OR PROJECT OF ANY OTHER PERSON OR FIRM WITHOUT THE CONSENT OF THIS OFFICE. WRITTEN DIMENSIONS ON THESE DRAWINGS OR SPECIFICATIONS SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF THE INTENT AND MEANING OF THESE RESTRICTIONS. WRITTEN DIMENSIONS ON THESE DRAWINGS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS. NO DIMENSIONS SHALL BE CHANGED OR VARYED FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE SHALL BE NOTIFIED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS. NO DIMENSIONS SHALL BE CHANGED OR VARYED FOR APPROVAL BEFORE PROCEEDING WITH FABRICATION.

© 2024 ROBERT S. LYON & ASSOCIATES, INC.  
© 2024 ROBERT G. LYON & ASSOCIATES, INC.



SUMMIT WOODS  
CROSSING

1744 NW CHIPMAN ROAD  
LEE'S SUMMIT, MO 64081

COVER SHEET, CODE  
INFORMATION, PROJECT  
DATA, & DIRECTORY

DRAWN BY
SLS
CHECKED BY
SL
JOB NUMBER
25303
SHEET NAME
G-0.0



<div> <div>1. GENERAL: THESE DRAWINGS AND SPECIFICATIONS INCLUDING DESIGNS AND IDEAS REPRESENTED THEREON ARE AND SHALL REMAIN THE PROPERTY OF THE ARCHITECT, AND NO PART THEREOF SHALL BE COPIED, DISCLOSED TO OTHERS OR USED IN CONJUNCTION WITH ANY WORK OR PROJECT EXCEPT THOSE FOR WHICH THEY HAVE BEEN DEVELOPED AND PREPARED, WITHOUT THE WRITTEN CONSENT OF THE ARCHITECT. VISUAL CONTACT WITH THE DRAWINGS AND SPECIFICATIONS SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS. THE TERM "GENERAL CONTRACTOR" USED IN THESE DOCUMENTS REFER TO TENANTS AS WELL AS LANDLORDS GENERAL CONTRACTOR</div> <div> <div>A. THE WORK UNDER THIS CONTRACT COMPRISES THE BUILD-OUT OF A NEW RETAIL STORE FOR CARHARTT (SEE PLANS FOR SQUARE FOOTAGE AND EXACT SCOPE OF WORK).</div> <div>B. THE LANDLORD/TENANT GENERAL CONTRACTOR SHALL VISIT THE SITE TO VERIFY ANY EXISTING CONDITIONS AND DIMENSIONS BEFORE SUBMITTING BIDSPRINGS AND REPORT TO THE ARCHITECT ANY DISCREPANCIES OR CONDITIONS WHICH MAY INTERFERE WITH THE EXECUTION OF THE DEPICTED WORK. EXTRAS WILL NOT BE ALLOWED FOR UNREPORTED DISCREPANCIES OR CONDITIONS.</div> <div>C. THE GENERAL CONTRACTOR SHALL CONTACT LOCAL UTILITY COMPANIES TO VERIFY ALL ELEVATIONS, SIZES, LOCATIONS AND CONNECTION POINTS FOR ALL UTILITIES AFFECTED BY THIS PROJECT. THE GENERAL CONTRACTOR SHALL COORDINATE AND OBTAIN ALL APPLICATIONS FOR, AND ENSURE ALL UTILITIES ARE TURNED ON PRIOR TO COMPLETION OF WORK.</div> <div>D. CONTRACTOR TO PROVIDE ALL SUB-CONTRACTORS WITH A COMPLETE SET OF THE MOST CURRENT CONSTRUCTION DOCUMENTS.</div> </div> </div> <div> <div>2. CONTRACTS: THE LATEST EDITION OF THE AMERICAN INSTITUTE OF ARCHITECTS' "GENERAL CONDITIONS OF THE CONTRACT FOR CONSTRUCTION (A201)" ARE HEREBY MADE A PART OF THESE DRAWINGS AND SPECIFICATIONS, AS WELL AS THE CONTRACT FOR CONSTRUCTION BY REFERENCE AND THEY SHALL BE LEGALLY ENFORCEABLE TO THE SAME DEGREE AND EXTENT AS IF THEY WERE REPRODUCED HEREON.</div> <div> <div>3. PERMITS &amp; CERTIFICATES: ALL WORK SHALL COMPLY WITH STATE AND LOCAL REGULATIONS AND ORDINANCES, ANY OTHER APPLICABLE CODES AND SHOPPING CENTER CRITERIA</div> <div>A. THE GENERAL CONTRACTOR SHALL OBTAIN AND PAY FOR ALL PERMITS AND LICENSES AND ARRANGE FOR ALL INSPECTIONS BY LOCAL JURISDICTIONS.</div> <div>B. A COMPLETE UP TO DATE SET OF THE DRAWINGS, INCLUDING APPROVED SHOP DRAWINGS SHALL BE KEPT AT THE SITE FOR THE DURATION OF THE WORK. COPIES OR ORIGINALS, IF REQUIRED, OF ALL PERMITS AND APPROVALS, SHALL ALSO BE KEPT AT THE SITE.</div> <div>C. UPON COMPLETION OF THE WORK AND BEFORE FINAL PAYMENT IS MADE, THE CONTRACTOR SHALL SECURE AND DELIVER TO THE LANDLORD AND TENANT (COPY TO ARCHITECT) A PROPERLY ISSUED OCCUPANCY CERTIFICATE AND COPIES OF ANY OTHER REQUIRED APPROVALS BY ANY AND ALL AGENCIES HAVING JURISDICTION OVER THE WORK (INCLUDING THE LANDLORD).</div> </div> <div> <div>4. INSURANCE: ALL CONTRACTORS (GENERAL AND SUB-CONTRACTORS) SHALL COMPLY WITH THE LANDLORDS AND TENANTS REQUIREMENT FOR INSURANCE, BONDS AND WAIVERS OF LIEN</div> <div>A. PRIOR TO COMMENCEMENT OF THE WORK, ALL CONTRACTORS AND SUBCONTRACTORS SHALL OBTAIN INSURANCE POLICIES AS OUTLINED BELOW. INSURANCE POLICIES ARE TO NAME THE TENANT, TENANT'S PROGRAM MANAGER (RGLA SOLUTIONS, INC.) TENANT'S ARCHITECT (ROBERT G. LYON &amp; ASSOCIATES, INC.), LANDLORD AND THE LANDLORD'S GENERAL CONTRACTOR (IF APPLICABLE) AS ADDITIONALLY INSURED. CERTIFICATES OF INSURANCE SHALL BE SUBMITTED TO THOSE NAMED.</div> <div>B. WORKMAN'S COMPENSATION AND OCCUPATIONAL DISEASE INSURANCE</div> <div>B.A. STATE- STATUTORY.</div> <div>B.B. APPLICABLE FEDERAL (E.G.: LONGSHOREMEN, HARBOR WORK, WORK OUTSIDE THE UNITED STATES)- STATUTORY.</div> <div>B.C. EMPLOYER'S LIABILITY:</div> <div>\$500,000.00 PER ACCIDENT</div> <div>\$500,000.00 DISEASE</div> <div>D. BENEFITS REQUIRED BY UNION LABOR CONTRACTS AS APPLICABLE</div> <div>C. COMPREHENSIVE GENERAL LIABILITY (INCLUDING PREMISES - OPERATIONS; INDEPENDENT CONTRACTORS' PROTECTIVE, PRODUCTS AND COMPLETED OPERATIONS; BROAD FORM PROPERTY DAMAGE, AUTOMOBILE COVERAGE, AND CONTRACTUAL LIABILITY.)</div> <div>C.A. BODILY INJURY:</div> <div>\$4,000,000.00 EACH OCCURRENCE</div> <div>\$4,000,000.00 AGGREGATE</div> <div>C.B. PROPERTY DAMAGE (INCLUDING WATER DAMAGE AND SPRINKLER LEAKAGE, LEGAL LIABILITY):</div> <div>\$4,000,000.00 EACH OCCURRENCE</div> <div>\$4,000,000.00 AGGREGATE</div> <div>C.C. PRODUCTS AND COMPLETED OPERATIONS SHALL BE MAINTAINED FOR A MINIMUM OF ONE (1) YEAR AFTER FINAL PAYMENT AND CONTRACTOR SHALL CONTINUE TO PROVIDE EVIDENCE OF SUCH COVERAGE TO OWNER ON AN ANNUAL BASIS DURING THE AFOREMENTIONED PERIOD.</div> <div>C.D. PROPERTY DAMAGE LIABILITY INSURANCE SHALL INCLUDE COVERAGE FOR EXPLOSION AND COLLAPSE.</div> <div>C.E. CONTRACTUAL LIABILITY (HOLD HARMLESS COVERAGE):</div> <div>BODILY INJURY:</div> <div>\$2,000,000.00 EACH OCCURRENCE</div> <div>PROPERTY DAMAGE:</div> <div>\$2,000,000.00 EACH OCCURRENCE</div> <div>\$2,000,000.00 AGGREGATE</div> <div>C.F. PERSONAL INJURY (WITH EMPLOYMENT EXCLUSION DELETED):</div> <div>C.G. \$2,000,000.00 EACH PERSON</div> <div>D. COMPREHENSIVE AUTOMOBILE LIABILITY (OWNED, NON-OWNED, HIRED)</div> <div>D.A. BODILY INJURY:</div> <div>\$2,000,000.00 EACH PERSON</div> <div>\$2,000,000.00 EACH ACCIDENT</div> <div>D.B. PROPERTY DAMAGE:</div> <div>\$2,000,000.00 EACH OCCURRENCE</div> <div>E. OTHER INSURANCE AND BONDS AS MAY BE REQUIRED BY THE LANDLORD (VERIFY REQUIREMENTS WITH THE LANDLORD).</div> </div> </div>	<div> <div>2. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING THE WORK OF ALL OTHER CONTRACTORS AND VENDORS WORKING IN THE SPACE</div> <div> <div>3. SUBMITTALS: SUBMITTALS SHALL BE PROVIDED FOR MATERIALS AND ASSEMBLIES LISTED IN EACH SECTION OF THIS SPECIFICATION:</div> <div>A. SHOP DRAWINGS AND SAMPLES: WHERE CALLED FOR IN DOCUMENTS, SUBMIT TO ARCHITECT FOR APPROVAL AS FOLLOWS:</div> <div>A.A. REPRODUCIBLE DRAWINGS: ONE SEPA TRANSPARENCY.</div> <div>A.B. NON-REPRODUCIBLE DATA: TWO COPIES.</div> <div>A.C. SAMPLES: (2) EACH.</div> <div>A.D. CLEARLY MARK ALL SUBMISSIONS WITH DATA, PROJECT, CONTACT AND SUB-CONTRACTOR AND ALLOW SPACE FOR APPROVAL STAMP.</div> <div>B. PRODUCT DATA: SUBMIT MANUFACTURER'S TECHNICAL INFORMATION AND INSTALLATION INSTRUCTIONS FOR SPECIFIED MATERIALS, EXCEPT BULK MATERIALS, TO THE TENANT (COPY TO THE ARCHITECT).</div> <div>C. PRODUCT WARRANTY: SUBMIT MANUFACTURER'S PRODUCT AND MATERIAL INFORMATION TO TENANT (COPY TO THE ARCHITECT).</div> </div> <div> <div>4. INSPECTION AND TESTING: THE GENERAL CONTRACTOR SHALL EMPLOY AND PAY FOR AN INDEPENDENT FIRM (APPROVED BY THE ARCHITECT) TO PERFORM INSPECTION AND TESTING REQUIRED BY THESE DRAWINGS AND SPECIFICATIONS.</div> <div>A. SUBMIT TESTING AND INSPECTION RESULTS TO THE ARCHITECT, AND TENANT FOR THEIR FILES.</div> </div> <div> <div>5. TEMPORARY SERVICES: PROVIDE TEMPORARY SERVICES NECESSARY TO COMPLETE THE CONSTRUCTION INCLUDING (BUT NOT LIMITED TO): ELECTRICITY, LIGHTING, HVAC, TELEPHONE, FACSIMILE MACHINE, WATER SERVICE, SANITARY FACILITIES, FIRE PROTECTION EQUIPMENT, FENCES/BARRICADES AND SECURITY.</div> <div>A. GENERAL CONTRACTOR SHALL FURNISH AND INSTALL ALL NECESSARY BARRICADES, TEMPORARY CONSTRUCTION, DUSTSHIELDS, AND SCAFFOLDING REQUIRED TO COMPLETE THE PROJECT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR BARRICADE MAINTENANCE, REMOVAL AND REPAIR, CLEANUP OR ANY RECONSTRUCTION REQUIRED AS A RESULT OF THE BARRICADE.</div> <div>B. GENERAL CONTRACTOR IS TO BE FAMILIAR WITH ALL LANDLORD CRITERIA, SPECIAL WORKING CONDITIONS PERTAINING TO BARRICADES, NOISE, DUST, TRASH/REMOVAL, ETC. AND TO COORDINATE WITH LANDLORDS.</div> <div>C. GENERAL CONTRACTOR MUST HAVE A JOB PHONE ON PREMISES DURING ENTIRE CONSTRUCTION PERIOD AND PROVIDE NUMBER AND NAME OF CONTACT TO ARCHITECT AND TENANT IMMEDIATELY.</div> </div> <div> <div>6. SITE ACCESS: COORDINATE SITE ACCESS, WORK HOURS, WORKER PARKING, LOADING AND UNLOADING AND STORAGE OF MATERIALS WITH THE LANDLORD.</div> <div>7. JOB SAFETY REQUIREMENTS: THE GENERAL CONTRACTOR IS RESPONSIBLE FOR PROVIDING SAFETY DURING CONSTRUCTION. PROVIDE AND POST SAFETY RULES AT THE JOBSITE.</div> </div> <div> <div>8. CLEANING/FINAL CLEANING: MAINTAIN SITE IN A CLEAN AND ORDERLY FASHION AT ALL TIMES. FINAL CLEAN THE ENTIRE SITE, DISPOSING OF ANY REMAINING DEBRIS AND TRASH, VACUUMING OR SWEEPING AND MOPPING FLOORS AND CLEANING ALL GLAZED, TILED, PAINTED, ETC. SURFACES FOR SUBSTANTIAL COMPLETION.</div> <div>A. GENERAL CONTRACTOR SHALL PAY FOR ALL SCAVENGER SERVICES, BE RESPONSIBLE FOR REMOVAL OF DEBRIS FOR ALL TRADES (INCLUDING OTHER CONTRACTORS AND VENDORS) AND FOR KEEPING THE JOB SITE CLEAN AT ALL TIMES.</div> <div>B. TENANT GENERAL CONTRACTOR TO PROVIDE FINAL DEEP CLEANING OF ALL WOOD, GLASS, AND METAL FIXTURES, STOREFRONT GLAZING INSIDE AND OUT, VACUUMING OF CARPET, MOPPING AND WAXING OF VCT FLOORING, MOPPING AND BUFFING OF SOLID WYNN FLOORING PRIOR TO TURN OVER TO OPERATING COMPANY.</div> </div> <div> <div>9. RECORD DRAWINGS/OMB MANUALS: MAINTAIN, ON SITE, ONE SET OF CONTRACT DOCUMENTS TO BE UTILIZED FOR RECORD DRAWINGS. RECORD ALL REVISIONS OF WORK.</div> <div>A. UPON COMPLETION OF THE WORK AND BEFORE FINAL PAYMENT IS MADE, THE CONTRACTOR SHALL SECURE AND DELIVER TO THE TENANT (COPY TO THE ARCHITECT) ALL GUARANTEES AND/OR WARRANTIES ON ALL EQUIPMENT SUPPLIED AND/OR INSTALLED BY THE CONTRACTOR, AND HIS SUBCONTRACTORS.</div> <div>B. UPON COMPLETION OF THE WORK AND BEFORE FINAL PAYMENT IS MADE, THE CONTRACTOR SHALL SUBMIT (ON REPRODUCIBLE MYLAR) ONE SET OF AS-BUILT DRAWINGS INDICATING ALL CHANGES AND MODIFICATIONS MADE TO THE PROJECT DURING CONSTRUCTION.</div> <div>B.A. PROVIDE THE LANDLORD WITH COPIES OF RECORD DRAWINGS AND O &amp; M MANUALS AS REQUIRED.</div> </div> <div> <div>10. PUNCH LIST/CLOSE-OUT: UPON NOTIFICATION, THE ARCHITECT &amp; TENANT SHALL PREPARE A PUNCH LIST OF THE PROJECT AND THE GENERAL CONTRACTOR SHALL MAKE GOOD ALL PUNCH LIST ITEMS TO THE SATISFACTION OF THE ARCHITECT / TENANT PRIOR TO FINAL PAYMENT.</div> <div>THE GENERAL CONTRACTOR SHALL:</div> <div>- FINAL CLEAN SITE.</div> <div>- RESOLVE ALL PUNCH LIST ITEMS.</div> <div>- TEST AND BALANCE HVAC SYSTEM.</div> <div>- SUBMIT TWO COPIES OF ALL O&amp;M MANUALS.</div> <div>- SUBMIT COPIES OF MANUFACTURER'S WARRANTIES.</div> <div>- SUBMIT RECORD DRAWINGS.</div> <div>- LEAVE ON SITE ATTIC STOCK FOR CEILING TILE AND FLOOR TILE.</div> <div>NOTE: THE GENERAL CONTRACTOR SHALL BE DIRECTLY RESPONSIBLE FOR ANY EXPENSES INCURRED BY THE ARCHITECT FOR ADDITIONAL VISITS AS A RESULT OF PUNCH LIST ITEMS NOT CORRECTED BEFORE THE FOLLOW-UP VISIT.</div> </div> <div> <div>11. GUARANTEE: THE GENERAL CONTRACTOR SHALL GUARANTEE THE WORK FOR ONE (1) YEAR AFTER THE SUBSTANTIAL COMPLETION OF ALL WORK.</div> <div>A. GUARANTEE/WARRANTY CERTIFICATES BY THE MANUFACTURER SHALL BE SUBMITTED AS APPROPRIATE.</div> <div>B. REFER TO OTHER SECTION OF THE SPECIFICATION FOR ADDITIONAL GUARANTEE/WARRANTY REQUIREMENTS.</div> </div> <div> <div>12. DIVISION 02: SITE WORK:</div> <div>1. REFER TO THE ARCHITECTURAL DRAWINGS FOR ANY NOTES RELATED TO DEMOLITION WORK.</div> <div>2. THE GENERAL CONTRACTOR IS TO DEMOLISH AND REMOVE FROM THE PREMISES IN A MANNER ACCEPTABLE TO ANY JURISDICTIONAL AGENCIES, THE LANDLORD, AND THE APPROVAL OF THE ARCHITECT, ALL WORK SO INDICATED OR REQUIRED BY THE WORK OF THE CONTRACT DOCUMENTS OR AS MAY BE DIRECTED IN THE FIELD BY THE ARCHITECT. THE WORK WHICH IS TO BE REMOVED SHALL INCLUDE ANY EXISTING CONSTRUCTION, FURNISHINGS, EQUIPMENT OR FINISHES NOT TO REMAIN IN THE COMPLETED CONSTRUCTION PERIOD.</div> <div>3. LAYOUT WORK:</div> <div>A. GENERAL CONTRACTOR SHALL LOCATE ALL EXISTING UTILITY SERVICE LINES AND PROTECT THEM THROUGHOUT THE CONSTRUCTION PERIOD.</div> <div>B. GENERAL CONTRACTOR SHALL LAY OUT WORK AND BE RESPONSIBLE FOR ALL LINES, ELEVATIONS, MEASUREMENTS OF THE BUILDING UTILITIES, AND OTHER WORK EXECUTED UNDER THE CONTRACT.</div> <div>C. LANDLORD/ TENANT GENERAL CONTRACTOR SHALL VERIFY ALL DIMENSIONS AS THEY MAY APPLY TO EXISTING CONDITIONS WITH PARTICULAR EMPHASIS ON DIMENSIONS MARKED "VERIFY" OR VERIFY IN FIELD (VIF.) NOTIFY ARCHITECT AND TENANT IMMEDIATELY OF ANY DISCREPANCIES BETWEEN THE DRAWINGS AND EXISTING CONDITIONS IN WRITTEN FORM. WORK.</div> <div>D. ANY DISCREPANCIES, ERRORS, OR OMISSIONS DISCOVERED IN THE CONTRACT DOCUMENTS BY THE CONTRACTOR SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT AND TENANT BEFORE PROCEEDING WITH RELATED WORK. OTHERWISE, THE CORRECTION OF SUCH ITEMS WILL BE THE RESPONSIBILITY OF THE CONTRACTOR.</div> </div> <div> <div>13. DIVISION 03: CONCRETE WORK:</div> <div>1. GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR A SMOOTH TRANSITION BETWEEN STORE FLOORS AND ADJACENT FLOORS. STORE FLOOR MAY REQUIRE LATEX FEATHERING OR, WHERE POSSIBLE, GRINDING DOWN OF STORE SUBFLOOR TO ALLOW FOR A SMOOTH TRANSITION, IF FLOOR GRINDING IS NOT PERMITTED BY LANDLORD CONTACT ARCHITECT.</div> <div>2. (WHEN APPLICABLE) NEW OR ADDITIONAL CONCRETE WORK STAIRS, STOOPS, RAMPS, ECT. REFER TO ALL DRAWINGS FOR ADDITIONAL CONCRETE SPECIFICATIONS.</div> <div>3. DIVISION 04: MASONRY: (WHEN APPLICABLE)</div> <div>1. REFER TO THE ARCHITECTURAL DRAWINGS FOR ADDITIONAL MASONRY SPECIFICATIONS.</div> <div>2. PRODUCTS:</div> <div>A. LINTELS AND BOND BEAMS: (IF APPLICABLE)</div> <div>A.A. INSTALL LINTELS WHERE NOTED ON THE DRAWINGS.</div> <div>A.B. INSTALL BOND BEAMS WHERE NOTED ON THE DRAWINGS; REINFORCE AS DETAILED AND GROUT SOLID.</div> <div>B. REMOVE EXCESS MORTAR AND CLEAN SURFACES UPON COMPLETION OF MASONRY INSTALLATION.</div> </div> <div> <div>4. DIVISION 05: METALS:</div> <div>1. REFER TO THE ARCHITECTURAL DRAWINGS FOR SPECIFICATIONS RELATED TO STRUCTURAL METAL WORK.</div> <div>2. (WHEN APPLICABLE) REFER TO ALL DRAWINGS FOR ADDITIONAL ARCHITECTURAL METAL WORK, RAILINGS, REFER HANDRAILS, ETC.</div> <div>3. DIVISION 06: WOOD AND PLASTIC:</div> <div>1. SCOPE OF WORK INCLUDES, BUT IS NOT LIMITED TO, ROUGH CARPENTRY (WOOD BLOCKING) AND FINISH CARPENTRY (CABINETRY, WOOD TRIM, HARDWARE AND ACCESSORIES).</div> <div>2. ROUGH CARPENTRY: WOOD BLOCKING</div> <div>A. PROVIDE SOLID BLOCKING IN STUD WALLS WHERE ALL FIXTURES OR DEVICES ARE TO BE MOUNTED. ALL WOOD BLOCKING SHALL BE</div> </div> </div>	<div> <div>4. FIRE RESISTANT TREATED:</div> <div>A. ALL DIMENSIONAL LUMBER TO BE FIRE RETARDANT WITH U.L. RATING "NON-COMBUSTIBLE."</div> </div> <div> <div>5. FINISH CARPENTRY: CABINETRY, AND WOOD TRIM:</div> <div>A. ALL MILLWORK SHALL COMPLY WITH THE APPROPRIATE SPECIFICATIONS OF "THE ARCHITECTURAL QUALITY STANDARDS ILLUSTRATED" OF THE AMERICAN WOODWORK INSTITUTE (AWI) FOR "CUSTOM" GRADE MILLWORK.</div> <div>B. PAINT GRADE FINISH LUMBER SHALL BE "POPULAR OR "BIRCH" SANDED SMOOTH AND FREE OF BLEMISHES OR ABRASIONS. ALL WOOD SHALL HAVE TIGHT AND UNIFORM JOINTS.</div> <div>C. MILLWORK CONTRACTOR SHALL VERIFY ALL DIMENSIONS AFFECTING HIS WORK IN THE FIELD PRIOR TO FABRICATION.</div> <div>D. FIXTURE MILLWORK AS NOTED ON DRAWINGS IS SUPPLIED BY TENANT AND INSTALLED BY TENANT GENERAL CONTRACTOR.</div> <div>E. SOME FIELD ASSEMBLY OF MILLWORK IS REQUIRED. FOLLOW SHOP DRAWING ACCOMPANYING MILLWORK. ALL FIELD ASSEMBLED MILLWORK TO BE SCRIBED AND JOINED ACCURATELY.</div> <div>F. INSTALLATION TO BE IN ACCORDANCE WITH MANUFACTURER'S SHOP DRAWINGS.</div> <div>G. MAKE ALL JOINTS INCONSPICUOUS MAINTAINING A UNIFORM FLUSH CONNECTION USING COMBINATION OF SCREWS, DOWELS AND GLUE. BLIND FASTENERS WHERE POSSIBLE. WHERE BLIND FASTENINGS IS IMPOSSIBLE, DRILL HOLES UNIFORMLY, SET AND PUTTY HEADS AND FINISH AS APPLICABLE TO</div> </div> <div> <div>6. PLASTIC LAMINATES:</div> <div>A. ALL LAMINATE SURFACES, EDGES AND ADJACENT MATERIALS TO BE FREE OF ALL ADHESIVES, MARKINGS, CHIPS AND SURFACE BLEMISHES. REMOVE WRAPPINGS.</div> <div>B. PLASTIC LAMINATES TO BE INSTALLED PER MANUFACTURER'S SPECIFICATIONS. ALL EDGES TO BE FLUSH, TRUE AND STRAIGHT, WITHOUT GAPS. ADJACENT LAMINATED PANELS TO BE CONCEALED SPINE JOINTS.</div> <div>C. LAMINATE TO BE INSTALLED OVER MEDIUM DENSITY PARTICLE BOARD. SPACKLE AND SAND SMOOTH TO AVOID TELEGRAPHING OF FASTENER LOCATIONS, BACKER, EDGES, ETC.</div> <div>D. ALL LAMINATE WORK TO BE FASTENED WITH CONCEALED MECHANICAL FASTENERS ATTACHED TO SUBSTRATE FRAMING AND WITH ADHESIVES. SET WITH BLOCKS AND CLAMPS UNTIL ADHESIVES HAVE DEVELOPED ADEQUATE BONDING STRENGTH.</div> </div> <div> <div>7. DIVISION 07: THERMAL &amp; MOISTURE PROTECTION:</div> <div>1. SCOPE OF WORK INCLUDES, BUT IS NOT LIMITED TO, VAPOR BARRIER, BUILDING INSULATION, MEMBRANE ROOFING SYSTEM, "EIFS" SYSTEM, FLASHING, COPING/FASCIA, AND SEALANTS.</div> <div>2. BUILDING INSULATION (SOUND BATT):</div> <div>A. CEILING INSULATION - (WHEN APPLICABLE): 3 1/2" THICK SOUND ATTENUATION BATT INSULATION CONFORMING TO ASTM C665 AS MANUFACTURED BY OWENS CORNING FIBERGLASS "FIRECODE" 60", R19.</div> <div>B. WALL INSULATION - (THERMAL BATT - 1 1/2" THICK FOIL FACED BATT INSULATION - TYPE 705, R 6.5</div> <div>C. WALL INSULATION - (THERMAL BATT - 3 1/2" THICK FOIL FACED BATT INSULATION - TYPE 705, R 15.2 (WHEN APPLICABLE)</div> </div> <div> <div>8. DIVISION 08: DOORS, WINDOWS &amp; GLASS:</div> <div>1. SCOPE OF WORK INCLUDES, BUT IS NOT LIMITED TO, WOOD AND METAL DOORS AND FRAMES, METAL WINDOWS, GLASS AND GLAZING AND HARDWARE.</div> <div>2. WOOD AND STEEL DOORS (WHEN APPLICABLE):</div> <div>A. STEEL DOORS (EXTERIOR): GRADE II, EXTRA HEAVY DUTY, SEAMLESS COMPOSITE CONSTRUCTION, SHOP PRIMED, WITH INSULATED CORES AND FIRE RATED AS NOTED ON THE DRAWINGS. ACCEPTABLE MANUFACTURERS INCLUDE GECO, KEWNAKE OR STEELCRAFT.</div> <div>B. WOOD DOORS (INTERIOR): 1 3/4" THICK SOLID CORE AND HOLLOW CORE CONSTRUCTION WITH WOOD VENEER FACES. FABRICATE DOORS IN ACCORDANCE WITH AMI STANDARDS.</div> <div>B.A. VENEER TO BE BIRCH, ROTARY SLICED WITH RANDOM MATCH GRAIN FOR PAINT FINISH.</div> <div>B.B. PROVIDE CUTOUTS FOR GLAZING AS NOTED ON THE DRAWINGS.</div> </div> <div> <div>3. METAL FRAMES (WHEN APPLICABLE):</div> <div>A. METAL FRAMES (EXTERIOR): 16 GAUGE WITH INSULATED CORE, SHOP PRIMED, WELDED FRAMES AND 4" MASONRY HEAD.</div> <div>B. METAL FRAMES (INTERIOR): 16 GAUGE, SHOP PRIMED, KNOCK-DOWN TYPE FOR DRYWALL SLIP-ON ASSEMBLY, UNLESS OTHERWISE NOTED.</div> </div> <div> <div>4. ALUMINUM DOORS AND WINDOWS (WHEN APPLICABLE):</div> <div>A. ALUMINUM SYSTEM SHALL MATCH EXISTING STOREFRONT SYSTEM. FOLLOW MANUFACTURER'S SPECIFICATIONS FOR FABRICATION AND INSTALLATION.</div> <div>B. ALUMINUM ENTRANCE DOORS SHALL MATCH EXISTING STOREFRONT SWINGING DOORS WITH INTERMEDIATE MULLIONS AS SHOWN ON THE DRAWINGS.</div> <div>C. COLOR TO MATCH EXISTING PROPERTY STOREFRONT.</div> </div> <div> <div>5. HARDWARE: FURNISH AND INSTALL HARDWARE AS NOTED ON THE HARDWARE/DOOR SCHEDULE.</div> <div>6. GLASS (WHEN APPLICABLE):</div> <div>A. GLASS (EXTERIOR) STOREFRONT TO MATCH EXISTING ADJACENT GLAZING. GLAZING TO BE TEMPERED WHERE REQUIRED BY CODE.</div> <div>B. ALL INTERIOR STOREFRONT GLASS TO BE PURCHASED BY G.C. GLASS SHALL BE 1/2" TEMPERED GLASS AS MANUFACTURED BY PPG INDUSTRIES</div> <div>C. FLOAT GLASS (INTERIOR, WHEN APPLICABLE): CLEAR, 1/4" THICKNESS.</div> <div>D. WIRE GLASS VISION PANEL (WHEN APPLICABLE): CLEAR FULLY TEMPERED, 1/4" THICKNESS</div> <div>E. PROVIDE NEOPRENE GASKETS AND GLAZING TAPE AT ALL STOPS (INTERIOR GLAZING).</div> <div>F. MIRRORS TO HAVE ELECTROPLATED COPPER BACKS. EXPOSED MIRROR EDGES TO BE POLISHED AND CONCEALED EDGES TO BE PAINTED FLAT BLACK. USE NON-STAINING MIRROR MASTIC FOR CEMENTING MIRRORS TO WALL. MIRRORS CEMENTED TO WALL SHALL HAVE A CONTINUOUS BEAD OF SILICONE CEMENT AROUND ENTIRE EDGE OF MIRROR AND WALL.</div> </div> <div> <div>7. DIVISION 09: FINISHES:</div> <div>1. SCOPE OF WORK INCLUDES, BUT IS NOT LIMITED TO: GYPSUM BOARD SYSTEMS, SUSPENDED ACOUSTICAL CEILINGS, RESILIENT FLOORING, CARPET, PAINTING AND WALL COVERING AND FLOOR COVERING.</div> <div>A. ALL EXIT WAY WALL AND CEILING FINISHES SHALL HAVE A FLAME SPREAD CLASSIFICATION OF NOT MORE THAN CLASS II AND FLAME SPREAD INDEX OF 75 OR LESS. ALL OTHER WALL AND CEILING FINISHES SHALL HAVE A FLAME SPREAD CLASSIFICATION OF NOT MORE THAN CLASS III AND FLAME SPREAD OF 200 OR LESS.</div> </div> <div> <div>2. GYPSUM BOARD SYSTEMS: INCLUDES METAL STUDS AND GYPSUM BOARD WALLS AND ALL REQUIRED METAL BEADS, CORNER TRIM, FASTENING DEVICES, ETC.</div> <div>A. ALL GYPSUM BOARD WALLS AND CEILINGS SHALL BE BUILT IN ACCORDANCE WITH THE GUIDELINES OF THE MOST RECENT VERSION OF "THE GYPSUM CONSTRUCTION HANDBOOK" OF THE UNITED STATES GYPSUM COMPANY.</div> <div>B. GYPSUM BOARD SHALL BE 5/8" THICK TYPE AS INDICATED ON THE DRAWINGS. ALL DRYWALL TO BE TAPED, RECEIVE THREE COATS SPACKLE, SANDED. ALL CORNERS AND EDGES TO HAVE METAL CORNER BEAD BEDDED AND SANDED FOR FINISH.</div> <div>C. METAL STUDS SHALL BE 20 GAUGE GALVANIZED STEEL, "C" SHAPED. FASTENERS SHALL BE TYPE "W" DRYWALL SCREWS. STRUCTURAL STUDS - CEE (WHEN REQUIRED) SHALL BE BY DALE/INCOR.</div> <div>D. PROVIDE SOUND INSULATION IN PARTITIONS WERE NOTED ON DRAWINGS.</div> <div>E. ACCESS DOORS, WHERE INDICATED OR AS REQUIRED, SHALL BE PROVIDED TO ALL CONTROL DEVICES, CLEAN OUTS, DAMPERS, AND THE MIXED AIR DISCHARGE AND INTAKE PLENUMS AT THE HVAC UNIT (VERIFY WITH LANDLORD) BY G.C.</div> </div> <div> <div>3. SUSPENDED CEILING SYSTEM: (WHEN APPLICABLE)</div> <div>3.1. 2X2X ACOUSTICAL CEILING AND GRID SYSTEM</div> <div>A. CEILING TO BE INSTALLED IN STRICT COMPLIANCE WITH MANUFACTURER'S PUBLISHED SPECIFICATIONS AND CURRENT BULLETIN OF ACOUSTICAL MATERIALS ASSOCIATION - JOB CONDITIONS.</div> <div>B. SUSPENSION SYSTEM TO BE RIGID CEILING GRID SYSTEM WITH CROSS FURRING CHANNELS - DIRECT SUSPENSION SYSTEM.</div> <div>C. ALL FIXTURES INSTALLED IN LAY-IN CEILING SHALL BE PLACED IN CENTER OF CEILING TILE UNLESS DIMENSIONED OTHERWISE.</div> </div> <div> <div>4. RESILIENT FLOORING AND BASE: INCLUDES VINYL TILE, COMPOSITION TILE, VINYL BASE, AND (WHEN APPLICABLE) SHEET VINYL.</div> <div>A. PRODUCTS - AS INDICATED IN THE FINISH SCHEDULE.</div> <div>B. INSTALLATION:</div> <div>B.A. VINYL COMPOSITION, &amp; VINYL TILE FLOORS TO BE PROPERLY PREPARED WITHOUT HOLES, CRACKS AND BUMPS TO INSURE A FIRST CLASS FLOOR INSTALLATION.</div> <div>B.B. VINYL COMPOSITION FLOOR TILE AND VINYL TILE TO BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.</div> <div>B.C. VINYL BASE ROLLED SMOOTH, CORNERS AND EDGES TO BE TRUE AND TIGHT, SEAM SEALER TO BE APPLIED. SIZE OF SMALLEST PIECE TO BE 8 INCH LENGTH.</div> <div>B.D. ALL VINYL BASE SHALL BE FURNISHED WITH PREFORMED INSIDE AND OUTSIDE CORNERS.</div> <div>B.E. CONCRETE SUBSTRATE - SHALL BE CLEAN, SMOOTH AND FREE OF DEFECTS.</div> <div>B.F. AFTER INSTALLATION, CLEAN, SEAL AND WAX FLOOR PER THE MANUFACTURER'S INSTRUCTION.</div> <div>C. DELIVER TO OWNER REPLACEMENT TILES IN THE AMOUNT OF 10% OF MATERIALS (ATTIC STOCK).</div> </div> <div> <div>5. CERAMIC TILE (WHEN APPLICABLE):</div> <div>A. PREPARATION OF SURFACES:</div> <div>A.A. SUBSTRATE SHALL BE FURNISHED CLEAN, SMOOTH AND LEVELLED TO A TOLERANCE OF NO MORE THAN 1/4" IN TEN FEET. JOINTS, CONSTRUCTION SEAMS, AND OTHER IRREGULARITIES ARE TO BE FILLED, LEVEL AND SMOOTH WITH QUALITY PRODUCTS MEETING INDUSTRY STANDARDS SPECIFIED BY THE NATIONAL TILE CONTRACTORS ASSOCIATES, INC. OR THE TILE COUNCIL OF AMERICA. ALL CONTAMINANTS SUCH AS GREASE, WAX, OIL, SEALERS, CURING MEMBRANES, AND OLD ADHESIVE MUST BE COMPLETELY REMOVED. EXPANSION JOINTS MUST BE PROVIDED AS PER SPECIFICATIONS AND MATERIALS DETAILED BY TILE COUNCIL OF</div> </div>	<div> <div>AMERICA INSTALLATION HANDBOOK, SEE E-1171-89.</div> <div>A.B. ALL CONCRETE MUST BE SCAURED (ALSO AFTER PATCHING OR LEVELING) WITH 3/12" OPEN GRIT PAPER TO LOOSEN DIRT AND REMOVE WEAK CONCRETE.</div> </div> <div> <div>8. INSTALLATION OF FLOORING:</div> <div>B.A. INSTALLATION PROCEDURES WILL BE THIN SET METHODS IN STRICT ACCORD WITH MANUFACTURER'S RECOMMENDATIONS CONTAINED IN EACH BOX OF MATERIAL. ACCEPTED METHODS BY THE TILE COUNCIL OF AMERICA INCLUDING USING THE PROPER TROWEL (1/4" X 3/8" X 1/4"), BEATING-IN AND BACK-BUTTERING. THESE TECHNIQUES, ESPECIALLY FOR LARGER TILE, MUST BE FOLLOWED TO OBTAIN PROPER TRANSFER AND LEVELNESS.</div> <div>B.B. CLOSE AREA TO NORMAL TRAFFIC FOR 24 HOURS (OR LONGER) DEPENDING ON TYPE OF MATERIAL AND MANUFACTURER'S RECOMMENDATION. FLOORING WILL BE PROTECTED FROM CONSTRUCTION TRAFFIC AFTER LAYING AND GROUTING.</div> <div>B.C. PROVIDE SETTING AND MATERIALS OBTAINED FROM ONE SOURCE FOR EACH TYPE AND COLOR OF GROUT AND SETTING MATERIALS.</div> </div> <div> <div>9. CARPETING: (WHEN APPLICABLE)</div> <div>A. INSTALLATION:</div> <div>A.A. PREPARE SUBSTRATE FOR CARPET: CLEAN, SCRAPE, FILL AND LEVEL FLOOR AS REQUIRED FOR NEW CARPET.</div> <div>A.B. INSTALLATION TO BE DIRECT GLUE-DOWN METHOD, USING LATEX MASTIC - ROBERT SEAM SEALER #4015, CAPITAL ADHESIVES OR EQUAL.</div> <div>A.C. GENERAL CONTRACTOR TO INSTALL METAL ANGLE PER DETAIL ON DRAWINGS. MITER CUT CORNERS AND NAIL TO SUBFLOOR.</div> <div>A.D. ALL DEBRIS TO BE LEGALLY REMOVED FROM PREMISES. SEE NOTE #6.</div> <div>A.E. SEE SHT. A-1 FOR TRANSITION STRIP LOCATIONS AND FINISH SCHEDULE THIS SHT. FOR SPECS.</div> <div>A.F. CLEAN AND VACUUM AFTER INSTALLATION. ANY SCRAPS LARGER THAN 48" SHALL BE ROLLED AND TURNED OVER TO THE TENANT (ATTIC STOCK).</div> </div> <div> <div>10. PAINTING:</div> <div>A. PAINT SHALL BE MANUFACTURER AND COLOR AS NOTED IN THE SCHEDULES.</div> <div>B. ALL SURFACES TO RECEIVE PAINT SHALL BE PROPERLY PREPARED AND SHALL BE CLEAN AND FREE OF DUST, BLEMISHES AND ABRASIONS PRIOR TO APPLICATION OF FINISH. G.C. TO FOLLOW FLOOR COVERING MANUFACTURER SPECIFICATIONS FOR APPLYING PAINT &amp; FURNISH &amp; INSTALL MOISTURE BARRIER AS ACCEPTABLE TO PAINT MANUFACTURER IF TEST RESULTS DETERMINE THAT ADDITIONAL MOISTURE PROTECTION IS REQUIRED. ALL WORK SHALL BE PERFORMED AS PART OF INITIAL CONTRACT &amp; SHALL BE INCLUDED IN INITIAL BID. EXTRAS WILL NOT BE ALLOWED.</div> <div>C. ALL SURFACES TO BE PAINTED SHALL RECEIVE ONE (1) COAT OF PRIMER AND TWO (2) FINISH COATS.</div> <div>D. PAINT COLORS-SEE FINISH SCHEDULE.</div> <div>E. GENERAL CONTRACTOR TO FILL AND TOUCH UP ALL NAIL HOLES IN WOOD TRIM.</div> <div>F. ALL ELECTRICAL PLATES AND DEVICES TO RECEIVE FINISH AS NOTED ON EMP SPECIFICATIONS.</div> </div> <div> <div>11. ENGINEERED WOOD FLOORING:</div> <div>A. MATERIALS:</div> <div>A.A. PROVIDE MATERIALS AS NECESSARY FOR A COMPLETE INSTALLATION.</div> <div>A.B. UNDER FLOOR MATERIAL, TO BE AS SPECIFIED IN FINISH SCHEDULE.</div> <div>A.C. FINISHES TO BE AS SPECIFIED IN THE FINISH SCHEDULE.</div> <div>B. INSTALLATION</div> <div>B.A. INSTALL PER MANUFACTURER'S DIRECTIONS.</div> <div>B.B. PROVIDE MOISTURE TEST</div> <div>B.C. PROVIDE MANUFACTURER RECOMMENDED MOISTURE BARRIER AS NEEDED</div> </div> <div> <div>12. DIVISION 10: MISCELLANEOUS SPECIALTIES:</div> <div>1. SCOPE OF WORK INCLUDES TOILET ROOM ACCESSORIES AND ANY OWNER SUPPLIED MISCELLANEOUS SPECIALTIES.</div> <div>2. TENANT'S GENERAL CONTRACTOR (TGC) SHALL INSTALL OWNER SUPPLIED MISCELLANEOUS SPECIALTIES (AS NOTED).</div> <div>3. ALL EXTERIOR ILLUMINATED STORE SIGNS SHALL BE FURNISHED AND INSTALLED BY TENANT SIGN CONTRACTOR. TENANT SIGN CONTRACTOR TO PROCURE ALL NECESSARY APPROVALS AND PERMITS, PRIOR TO FABRICATION AND/OR INSTALLATION OF SIGNS. GENERAL CONTRACTOR TO PROVIDE FINISHED SIGN FASCIA AND ACCESS TO BULKHEAD INTERIOR AS REQUIRED FOR ELECTRICAL WIRING AND CONNECTION. FINAL CONNECTION BY</div> </div> <div> <div>13. THE CONTRACTOR SHALL REVIEW DOCUMENTS AND VERIFY ALL DIMENSIONS AND FIELD CONDITIONS AND SHALL CONFIRM THAT WORK IS BUILDABLE AS SHOWN.</div> <div>14. THE CONTRACTOR SHALL MAINTAIN FOR THE ENTIRE DURATION OF THE WORK, ALL EXITS, EXIT LIGHTING, FIRE PROTECTION DEVICES AND ALARMS, SPRINKLERS IN CONFORMANCE WITH ALL APPLICABLE CODES AND ORDINANCES.</div> <div>15. CONTRACTOR SHALL NOT DISTURB THE DELIVERIES AND FUNCTION OF ADJACENT TENANTS OR BUILDINGS OPERATION DURING THE ENTIRE DURATION OF THE PROJECT.</div> <div>16. DO NOT SCALE DRAWINGS. WRITTEN DIMENSIONS GOVERN. FLOOR PLAN PREPARED BY ARCHITECT SUPERSEDE ALL OTHERS. ALL DIMENSIONS MARKED OR NOTED "CLEAR" SHALL BE MAINTAINED AND SHALL ALLOW FOR THICKNESS OF ALL FINISHES.</div> <div>17. THESE GENERAL CONDITIONS APPLY TO ALL DRAWINGS IN THIS SET AND SHALL EXTEND TO ANY CHANGES, EXTRAS OR ADDITIONS AGREED TO DURING THE COURSE OF THE WORK.</div> <div>18. ALL WORK SHALL BE IN CONFORM WITH ARCHITECTS DRAWINGS AND SPECIFICATIONS. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL WORK AS REQUIRED TO FULFILL THE INTENTIONS OF THE DOCUMENTS.</div> <div>19. ALL CONSTRUCTION SHALL CONFORM TO AND BE IN ACCORDANCE WITH, THE REQUIREMENTS OF ALL APPLICABLE MUNICIPAL, STATE AND FEDERAL REGULATIONS HAVING JURISDICTION.</div> <div>20. ALL WORK SHALL BE COMPLETED FOR THE AGREED CONTRACT PRICE WITHOUT RECOURSE TO LABOR STOPPAGES OR REVISIONS OF GOVERNING REGULATIONS, LAWS AND CODES. UNLESS NOTED BY THE CONTRACTOR(S) IN THE BID FOR THE PROJECT, ALL WORK SHALL BE COMPLETED AS SHOWN WITHOUT LIMITATIONS, EXCLUSIONS OR MODIFICATIONS.</div> <div>21. AFTER THE JOB IS IN PROGRESS, THE CONTRACTOR(S) SHALL NOT PROCEED WITH ANY ADDITIONAL WORK OR CHANGES FOR WHICH ADDITIONAL COMPENSATION IS EXPECTED WITHOUT WRITTEN "CHANGE ORDER" AUTHORIZED BY THE TENANT/OWNER OR ARCHITECT (IF APPOINTED AS THE OWNER'S/TENANT'S REPRESENTATIVE. FAILURE TO OBTAIN PRIOR AUTHORIZATION CAN INVALIDATE A CLAIM FOR ADDITIONAL COMPENSATION.</div> <div>22. ALL CONTRACTORS SHALL BE RESPONSIBLE FOR COMPLYING WITH THE LANDLORDS RULES AND REGULATIONS ON MATERIAL HANDLING, EQUIPMENT, DEBRIS, ELEVATOR AND/OR LOADING DOCK AVAILABILITY, AND ALL THERE TENANT CONSTRUCTION REGULATIONS.</div> <div>23. MAINTAIN ALL EXISTING BUILDING SERVICES IN USE AT ALL TIMES UNLESS PERMISSION IS RECEIVED IN WRITING FROM THE LANDLORD TO TEMPORARILY INTERRUPT SERVICE. PERMANENTLY RECONNECT ALL SERVICES DISRUPTED BY THE PROJECT WORK WHETHER WITHIN OR OUTSIDE OF THE CONTRACT LIMIT LINES.</div> <div>24. ALL WORK SHALL BE PERFORMED DURING REGULAR BUSINESS HOURS UNLESS AUTHORIZED IN WRITING BY THE LANDLORD AND/OR OWNER/TENANT.</div> <div>25. IF APPLICABLE TO THE PROJECT, PASSENGER ELEVATORS SHALL NOT BE USED BY THE TRADES AT ANY TIME DURING THE PERFORMANCE OF THE WORK.</div> <div>26. TIME IS OF THE ESSENCE AND THE CONTRACTOR(S) SHALL KEEP SUFFICIENT PERSONNEL ON THE JOB AT ALL TIMES TO PERFORM THE WORK IN THE MOST EXPEDITIOUS MANNER CONSISTENT WITH GOOD WORKMANSHIP, AND SOUND BUSINESS PRACTICE. THE CONTRACTOR(S) SHALL CONFIRM THAT ALL ITEMS WILL BE ORDERED, FABRICATED AND INSTALLED PRIOR TO THE AGREED UPON COMPLETION DATE. EXCEPTIONS WILL NOT BE ALLOWED WITHOUT WRITTEN AUTHORIZATION OF THE OWNER'S/TENANTS REPRESENTATIVE PRIOR TO THE PLACEMENT OF THE ORDER.</div> <div>27. THE CONTRACTOR(S) SHALL PROVIDE TEMPORARY WALLS, ENCLOSURES, AND DUST PROOF BARRICADES AS REQUIRED FOR SAFETY, TO CONTROL, AND MINIMIZE DUST FROM DEMOLITION AND CONSTRUCTION OPERATIONS, AND TO EFFECTIVELY SEPARATE WORK AREAS FROM OTHER OCCUPIED AREAS. THE CONTRACTOR(S) SHALL EXERCISE ALL DUE CARE AND BE RESPONSIBLE FOR ANY DAMAGE TO EXISTING CONDITIONS AND PROVIDE PROTECTION DEVICES TO MAINTAIN SAME. VERIFY WITH OWNER/TENANT AND LANDLORD ANY SPECIAL REQUIREMENTS TO PROTECT BUILDING SYSTEMS, EQUIPMENT OR COMPUTERS.</div> <div>28. DO NOT CLOSE, OBSTRUCT, OR STORE MATERIAL IN WALKWAYS, PASSAGEWAYS, STAIRS OR OTHER MEANS OF EGRESS.</div> <div>29. NO USE OF ARC WELDING BLOWTORCH EQUIPMENT SHALL BE ALLOWED WITHOUT PRIOR WRITTEN APPROVAL OF THE OWNER/TENANT OR LANDLORD.</div> <div>30. CONTRACTOR(S) MUST PROVIDE TEMPORARY LIGHTING FOR THE PERFORMANCE OF HIS WORK AS WELL THAT REQUIRED TO INSURE PUBLIC SAFETY IN OR AROUND THE PREMISES.</div> <div>31. REMOVE DEBRIS AS WORK PROGRESSES. MAINTAIN THE PREMISES IN A NEAT AND CLEAN CONDITION. THE FURNISHINGS OF REFUSE CONTAINERS, CARTS, EQUIPMENT, LABOR AND THE SCHEDULING OF ELEVATOR AND/OR LOADING DOCK (IF APPLICABLE TO PROJECT) SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR(S). UPON COMPLETION OF ALL WORK, REMOVE ALL MATERIALS AND RUBBISH OF ANY SORT AND PROVIDE FINAL CLEAN UP OF PREMISES.</div> <div>32. GENERAL CONTRACTOR IS TO COORDINATE ALL DELIVERIES WITH THE LANDLORDS DESIGNATED REPRESENTATIVES</div> <div>33. GENERAL CONTRACTOR IS TO ACQUIRE AND CONFORM TO THE LANDLORDS CRITERIA AND CONDITIONS FOR GENERAL CONTRACTORS.</div> <div>34. TENANT GENERAL CONTRACTOR IS NOT PERMITTED TO ATTACH OR SUSPEND ANY COMPONENTS / EQUIPMENT TO THE BOTTOM CHORD OF JOISTS OR TO THE ROOF DECK. ALL WALL CONSTRUCTION SHALL BE SUPPORTED BY THE TOP CHORD OF THE STRUCTURAL JOISTS.</div> <div></div></div>
--	--	--	--



ACCESSIBILITY NOTES:							
TENANT MUST COMPLY WITH TITLE III OF THE AMERICANS WITH DISABILITIES ACT (ADA) AND ALL LOCAL AND STATE CODES.							
DOOR HARDWARE: HAND-ACTIVATED DOOR OPENING HARDWARE SHALL BE MOUNTED 2'-10" A.F.F. AND BE OPERABLE WITH A SINGLE EFFORT BY LEVER TYPE HARDWARE.							
DOOR EFFORT: MAXIMUM EFFORT TO OPERATE DOORS SHALL NOT EXCEED 8.5 POUNDS FOR EXTERIOR DOORS AND 5 POUNDS FOR INTERIOR DOORS.							
SMOOTH DOOR BOTTOM: THE BOTTOM OF ALL DOORS SHALL (EXCEPT SLIDING AUTOMATIC) HAVE A SMOOTH UNINTERRUPTED SURFACE.							
REQUIRED DOOR OPENING WIDTH & SIZE: ALL REQUIRED EXIT DOORWAYS SHALL HAVE A MIN. 32" CLEAR OPENING WITH THE DOOR AT 90° TO THE CLOSED POSITION. EVERY REQUIRED ENTRANCE OR PASSAGE DOORWAY SHALL BE OF A SIZE AS TO PERMIT THE INSTALLATION OF A DOOR NOT LESS THAN 3'-0" IN WIDTH & NOT LESS THAN 6'-8" IN HEIGHT.							
THRESHOLD HEIGHT: MAXIMUM HEIGHT OF THRESHOLD SHALL BE 1/2" WITH VERTICAL CHANGE AT EDGE OF 1/2 WITH A MAXIMUM LEVEL OF 45 DEGREES CHANGE IN LEVEL BETWEEN 1/4" AND 1/2" SHALL BE BEVELED WITH A SLOPE NO GREATER THEN 1:2.							
FAUCET LEVERS: ALL FAUCET CONTROLS FOR SINKS (EXISTING AND/OR NEW) ARE TO BE OPERABLE WITH LEVER TYPE CONTROLS.							
PLUMBING PROTECTION: ALL EXPOSED PLUMBING IS TO BE WRAPPED WITH INSULATION.							
DOOR OPERABILITY: LATCHING AND LOCKING DOORS THAT ARE HAND ACTIVATED AND WHICH ARE IN A PATH OF TRAVEL SHALL BE OPERABLE WITH A SINGLE EFFORT BY LEVER TYPE HARDWARE, PANIC BARS OR OTHER HARDWARE DESIGNED TO PROVIDE PASSAGE WITH OUT REQUIRING THE ABILITY TO GRASP THE OPENING HARDWARE.							
CHANGES IN LEVEL: ABRUPT CHANGES IN LEVEL ALONG ACCESSIBLE ROUTES SHALL NOT EXCEED 1/2" IN HEIGHT. WHEN CHANGES IN LEVEL DO OCCUR, THEY SHALL BE BEVELED WITH A SLOPE OF NO GREATER THAN 1:12, EXCEPT THAT LEVEL CHANGES NOT EXCEEDING 1/4 " MAY BE VERTICAL.							
DOOR LANDING AREAS: THE FLOOR OR LANDING ON EACH SIDE OF AN ENTRANCE OR PASSAGE DOOR SHALL BE LEVEL AND CLEAR. THE LEVEL AND CLEAR AREA SHOULD BE LEVEL AND CLEAR IN THE LENGTH AND THE DIRECTION OF THE DOOR SWING AT LEAST 60", AND THE LENGTH ON THE OPPOSITE SIDE OF THE DOOR SWING AT 44" AS MEASURED PERPENDICULAR TO THE PLAN OF THE DOOR IN ITS CLOSED POSITION.							
AVAILABLE SIDE ACCESS TO DOORS: THE WIDTH OF THE LEVEL AND CLEAR AREA ON THE SIDE TO WHICH THE DOOR SWINGS SHALL EXTEND 24" PAST THE STRIKE EDGE OF THE DOOR FOR EXTERIOR DOORS AND 24" PAST THE STRIKE EDGE FOR INTERIOR DOORS.							
TOILET CONTROLS: TOILET FLUSH CONTROLS PROVIDED & INSTALLED AS PART OF THE WORK SHALL BE OPERABLE WITH ONE HAND, & SHALL NOT REQUIRE TIGHT GRASPING, PINCHING, OR TWISTING OF THE WRIST. CONTROL FOR THE FLUSH VALVES SHALL BE MOUNTED ON THE WIDE SIDE OF THE TOILET AREAS. NO MORE THAN 44" ABOVE THE FLOOR. THE FORCE REQUIRED TO ACTIVATE THE CONTROLS SHALL BE NOT GREATER THAN 5 LBS.							
OTHER FLUSH CONTROLS: OTHER FLUSH CONTROLS PROVIDED & INSTALLED AS PART OF THE WORK SHALL BE OPERABLE WITH ONE HAND, & SHALL NOT REQUIRE TIGHT GRASPING, PINCHING, OR TWISTING OF THE WRIST. CONTROL FOR THE FLUSH VALVES SHALL BE MOUNTED ON THE WIDE SIDE OF THE TOILET AREAS. NO MORE THAN 44" ABOVE THE FLOOR. THE FORCE REQUIRED TO ACTIVATE THE CONTROLS SHALL BE NOT GREATER THAN 5 LBS.							
ACCEPTABLE DEVICE/FIXTURE CONTROLS: FAUCET CONTROLS OR OTHER OPERATING MECHANISMS SHALL BE OPERABLE WITH ONE HAND & SHALL NOT REQUIRE TIGHT GRASPING, PINCHING, OR TWISTING OF THE WRIST. THE FORCE REQUIRED TO ACTIVATE THE CONTROLS SHALL BE NOT GREATER THAN 5 POUNDS. LEVER OPERATED, PUSH TYPE & ELECTRONICALLY CONTROLLED MECHANISMS ARE EXAMPLES OF ACCEPTABLE DESIGNS. SELF CLOSING VALVES ARE ALLOWED IF THE FAUCET REMAINS OPEN FOR AT LEAST 10 SECONDS.							
ELECTRICAL & MECHANICAL CONTROLS: THE CENTER OF RECEPTACLE OUTLETS SHALL BE NOT LESS THAN 15" ABOVE THE FINISHED FLOOR OR WORKING PLATFORM. THE CENTER OF THE GRIP OF THE OPERATING HANDLE OF SWITCHES INTENDED TO BE USED BY THE OCCUPANT OF THE ROOM OR AREA TO CONTROL LIGHTING AND RECEPTACLE OUTLETS, APPLIANCES, HVAC EQUIPMENT SHALL BE NOT LESS THAN 36" OR MORE THAN 48" ABOVE THE FLOOR OR WORKING PLATFORM. THE CENTER OF FIRE ALARM INITIATING DEVICES (BOXES) SHALL BE LOCATED 48" ABOVE THE LEVEL OF THE FLOOR, WORKING PLATFORM, GROUND SURFACE, OR SIDEWALK.							
FLOOR FINISHES: FLOOR SHALL BE SLIP RESISTANT.							
ENTRY SIGNAGE: ALL DISABLED ACCESSIBLE ENTRANCES SHALL BE IDENTIFIED WITH AT LEAST ONE STANDARD SIGN AND WITH ADDITIONAL DIRECTIONAL SIGNS, AS REQUIRED, VISIBLE FROM APPROACHING PEDESTRIAN WAYS.							
TELEPHONES & DRINKING FOUNTAINS: WHEN PROVIDED, AT LEAST ONE TELEPHONE & ONE DRINKING FOUNTAIN IN THE BUILDING SHALL BE ACCESSIBLE & USABLE BY THE PHYSICALLY DISABLED.							
ACCESSIBILITY GENERAL NOTES							
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION
	ELEVATION TAG- SEE DWG. AS NOTED		DETAIL TAG- SEE DWG. AS NOTED		RCP KEY TAG- SEE DWG. AS NOTED		ROOM NUMBER TAG
	INTERIOR ELEVATION TAG- SEE DWG. AS NOTED		PARTITION TYPE TAG- SEE WALL TYPE LEGEND		ELEVATION KEY TAG- SEE DWG. AS NOTED		ELEVATION BENCHMARK
	SECTION TAG- SEE DWG. AS NOTED		PLAN KEY TAG- SEE DWG. AS NOTED		FINISH KEY TAG- SEE DWG. AS NOTED		REVISION TAG
SYMBOL LEGEND							
DIVISION OF WORK							

DIVISION OF WORK									
DESCRIPTION	EXIST TO REMAIN	DOES NOT APPLY	GENERAL CONTRACTOR AND SUB-CONTRACTOR		OWNER		LANDLORD		REMARKS
			FURNISH	INSTALL	FURNISH	INSTALL	FURNISH	INSTALL	
DIVISION 01: GENERAL REQUIREMENTS									
AS APPLICABLE PERMITS			●	●	●	●			
DIVISION 02: SITE WORK									
BARRICADE / FENCE GRAPHICS (BARRICADE)		●							
DEMOLITION			●	●					
DIVISION 03: CONCRETE									
CHANNEL / CORE SLAB FOR IN FLOOR PLUMBING FIXTURE			●	●					
CHANNEL / CORE SLAB FOR NEW IN FLOOR ELECTRICAL/DATA CONDUIT			●	●					
CHANNEL, LEVEL AND SLOPE CONCRETE SLAB FOR FINISHES AND TRANSITIONS			●	●					
GRINDING AND POLISHING CONCRETE			●	●					
DIVISION 04: MASONRY									
STOREFRONT STONE REPAIR	●		●	●					
MASONRY FINISHES (SEE FINISH LEGEND ON A0.1)	●	●							
DIVISION 05: METALS									
STRUCTURAL FRAMING			●	●					
STRUCTURAL PANEL SYSTEM	●								
STRUCTURAL COLUMNS AND ANGLES	●								
DIVISION 06: WOOD & PLASTICS									
ROUGH CARPENTRY			●	●					
BLOCKING			●	●					
FINISH CARPENTRY			●	●					
DIVISION 07: THERMAL & MOISTURE CONTROL									
CAULK AND SEALANTS			●	●					
INSULATION ( SOUND)			●	●					
DIVISION 08: DOORS, WINDOWS & GLASS									
STOREFRONT GLAZING / GLAZING SYSTEM	●								
STOREFRONT SYSTEM	●								
STOREFRONT DOOR AND HARDWARE	●		●	●					
INTERIOR DOORS, FRAMES & HARDWARE	●		●	●					
									SEE DOOR SCHEDULE
DIVISION 09: FINISHES									
PATCH AND REPAIR DEMISING WALL			●	●					VERIFY CONDITION
INTERIOR METAL STUD FRAMING AND DRYWALL			●	●					SEE A1.1
PATCH AND REPAIR EXISTING DRYWALL AS REQUIRED			●	●					PATCH AS REQUIRED
INTERIOR DRYWALL CEILING			●	●					SEE A2.1
FINISHES			●	●					SEE FINISH SCHEDULE A0.1
FLOORING TRANSITIONS			●	●					
DIVISION 10: MISCELLANEOUS SPECIALTIES									
COMING SOON GRAPHICS				●	●				SEE F2.1
PERMANENT VINYL GRAPHICS				●	●	●			SEE F2.1
INTERIOR GRAPHICS / SIGNAGE (NON-VINYL)				●	●				SEE F2.1
EXTERIOR AWNINGS		●							
DIVISION 11 AND 12: FURNITURE, FIXTURE AND EQUIPMENT									
UNLOADING FIXTURES				●					
STORE FIXTURES				●	●				SEE FIXTURE PLAN
GRAPHIC RAILS, BRACKETS & HARDWARE			●	●					
PROPS AND DISPLAY				●	●	●			
MANAGEMENT OF OWNER SUPPLIED ITEMS				●	●				
DIVISION 13 AND 14: SPECIAL CONSTRUCTION AND CONVEYING SYSTEMS									
NOT APPLICABLE		●							
DIVISION 16: ELECTRICAL									
LOW VOLTAGE CONDUITS	●		●	●					SEE A6.1 FOR NEW WORK
LOW VOLTAGE WIRING	●		●	●					SEE A6.1 FOR NEW WORK
LOW VOLTAGE WIRING - TERMINATIONS AT THE PATCH PANEL / SWITCH	●		●	●		●			SEE A6.1 FOR NEW WORK
LIGHTING			●	●					USE OWNER REQ'D VENDOR

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		


REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS:		DATE:
ISSUE FOR PERMIT:		06/18/25
LANDLORD PRICING		

REVISIONS	
-----------	--




**rgla solutions, inc.**  
5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com

REVISIONS:	DATE:
ISSUE FOR PERMIT, LANDLORD, PRICING	06/18/25

robert g. lyon + associates, inc.


retail architecture

5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com



THE ABOVE DRAWINGS AND SPECIFICATIONS AND DESIGNATIONS AND ARRANGEMENTS REPRESENTED THEREIN ARE AND SHALL REMAIN THE PROPERTY OF THIS OFFICE, AND NO PART THEREOF SHALL BE COPIED, DISCLOSED TO OTHERS OR USED IN THE CONNECTION WITH ANY WORK OR PROJECT OTHER THAN THE SPECIFIC PROJECT FOR WHICH THEY HAVE BEEN PREPARED AND DEVELOPED WITHOUT THE WRITTEN CONSENT OF THIS OFFICE. VISUAL CONTACT WITH THESE DRAWINGS OR SPECIFICATIONS SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE DRAWINGS. WRITTEN DIMENSIONS ON THESE DRAWINGS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTICED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS. SHOP DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE PROCEEDING WITH FABRICATION.

© 2025 RGLA SOLUTIONS, INC.  
© 2025 ROBERT G. LYON & ASSOCIATES, INC.




**SUMMIT WOODS CROSSING**

1744 NW CHIPMAN ROAD  
LEE'S SUMMIT, MO 64081

DIVISION OF WORK &  
SYMBOLS LEGEND


DRAWN BY	SLS
CHECKED BY	SL
JOB NUMBER	25303
SHEET NAME	G-0.2





2 DEMOLITION CEILING PLAN

SCALE  
1/8"=1'-0"



NOTE:  
GC TO VERIFY CONDITION OF EXISTING  
CONCRETE SLAB AFTER FLOOR FINISH  
REMOVAL TO DETERMINE EXTENT OF PATCH  
& REPAIR PRIOR TO CONCRETE SEALING.

1 DEMOLITION FLOOR PLAN

SCALE  
1/8"=1'-0"

- DEMOLITION PLANS ARE FOR GENERAL SCOPE. GENERAL CONTRACTOR IS TO VERIFY ALL EXISTING CONDITION AND COORDINATE REQUIRED DEMOLITION WITH TENANT & TENANT'S ARCHITECT.
- WHEN EXISTING MECHANICAL, ELECTRICAL AND PLUMBING FIXTURES AND/OR EQUIPMENT ARE TO BE REMOVED, THEY ARE TO BE DISCONNECTED AT THE SOURCE, UNLESS NOTED OR DIRECTED OTHERWISE. COORDINATE ALL WORK WITH MECHANICAL, ELECTRICAL AND PLUMBING PLANS.
- ALL EXISTING DUCTWORK TO REMAIN UNLESS INDICATED ON MECHANICAL PLANS. ALL ABANDONED HVAC EQUIPMENT AND DUCTWORK SHALL BE REMOVED UPON DISCOVERY.
- ELECTRICAL CONTRACTOR SHALL DISCONNECT AND REMOVE ALL EXISTING ELECTRICAL, TELEPHONE OUTLETS, AND ALL ASSOCIATED WIRES IN WALLS TO BE REMOVED AND TERMINATE AT THE LAST OUTLET THAT REMAINS IN SERVICE.
- ALL EMPTY OR ABANDONED CONDUIT AND JUNCTION BOXES TO BE REMOVED.
- DEMOLITION CONTRACTOR SHALL REMOVE ALL EXISTING FLOOR COVERINGS AND/OR FINISHES, UNDERLAYMENT, GLUE AND ANY OTHER ADHESIVE; AND SHALL PATCH REPAIR CONCRETE SLAB AS REQUIRED TO ACCOMMODATE FINAL FLOOR PREP. REFER TO FINISH PLAN FOR ADDITIONAL INFORMATION.
- ALL ABANDONED UTILITIES ARE TO BE REMOVED AS DIRECTED BY LANDLORD OR AS SPECIFIED BY MALL MANAGEMENT. COORDINATE WITH MALL MANAGEMENT OR LANDLORD AS NECESSARY.
- ALL FIREPROOFING AT STRUCTURAL ELEMENTS SHALL REMAIN, UNLESS NOTED OTHERWISE. ANY FIREPROOFING REMOVED AND/OR DAMAGED DURING THE COURSE OF DEMOLITION SHALL BE REPLACED WITH THE SAME MATERIALS AND RATING AS THAT WHICH WAS REMOVED AT THE CONTRACTOR'S EXPENSE.
- LANDLORD ROOFING CONTRACTOR - IF REQUIRED - IS TO REMOVE EXISTING ROOFING INSULATION AND ROOF DECK AS REQUIRED WHERE NEW ROOF TOP EQUIPMENT IS SPECIFIED. G.C. IS TO VERIFY EXACT LOCATION AND EXTENT IN THE FIELD. REFER TO MECHANICAL DRAWINGS.
- PRIOR TO SAWCUTTING OF EXISTING SLAB, G.C. IS TO VERIFY WITH THE LANDLORD THE LOCATION OF ANY AND ALL EXISTING UTILITIES RUNNING THROUGH THE SPACE. IF IT IS DETERMINED THAT UTILITIES ARE PRESENT, BUT EXACT LOCATIONS ARE NOT KNOWN, THEN THE G.C. SHOULD XRAY THE SLAB.
- USE CARE DURING DEMOLITION SO AS NOT TO DISTURB THE REMAINING WALLS, CEILINGS, PIPING AND DUCTWORK. EXISTING DUCTWORK TO BE REVISED BY SHEET METAL CONTRACTOR. GENERAL CONTRACTOR TO PROVIDE TEMPORARY SUPPORT FOR ALL EXISTING DUCTWORK AND SPRINKLER LINES AFFECTED BY THE REMOVAL.
- TENANT RESERVES THE RIGHT TO RETAIN ITEMS AS DESIRED. THE CONTRACTOR SHALL REMOVE RETAINED ITEMS TO A STORAGE AREA AS DIRECTED BY THE TENANT OR HIS REPRESENTATIVE. ALL OTHER MATERIALS AND DEBRIS SHALL BE REMOVED FROM THE BUILDING SITE IMMEDIATELY.
- CONTRACTORS ENGAGED SHALL BE PROTECTED BY THE PROPER INSURANCE AND SHALL FILE EVIDENCE THEREOF WITH THE OWNER'S AGENT, INCLUDING HOLD HARMLESS PROTECTION FOR THE TENANT AND ARCHITECT.
- DEBRIS FROM THE DEMOLITION SHALL BE REMOVED PROMPTLY FROM THE BUILDING BY MEANS APPROVED BY THE LANDLORD.
- DO NOT REMOVE ANY UTILITIES RUNNING THROUGH THE SPACE TO ADJACENT TENANTS.

B GENERAL DEMOLITION NOTES

- FRAMING
  - REMOVE INTERIOR PARTITIONS AND INTEGRATED DOORS, FIXTURES, FINISHES AND POWER (SHOWN DASHED.) NOTIFY ARCHITECT IMMEDIATELY IF DEMOLITION EXPOSES ANY UNFORESEEN CONDITIONS.
  - EXISTING WALLS TO REMAIN (SHOWN SOLID GREYSCALE). SEE SHEET A1.1
  - AT DEMISING WALLS IN SALES AREA, G.C. SHALL REMOVE EXISTING BUILD-OUTS WHILE MAINTAINING INTEGRITY OF RATED DEMISING WALLS. G.C. SHALL CONTACT ARCHITECT IF GYP. BD. IS MISSING ON DEMISING WALLS.
  - REMOVE BUILD-OUTS AT STRUCTURAL COLUMNS.
- CEILINGS
  - REMOVE ALL CEILINGS, SOFFITS, FINISHES & LIGHT FIXTURES THROUGHOUT, UNLESS OTHERWISE NOTED.
  - EXISTING GYP. BD. CLNG TO REMAIN, TOILET ROOM. REMOVE ALL LIGHT FIXTURES & ABANDONED EQUIPMENT. PREPARE SURFACE FOR NEW FINISH.
  - REMOVE ALL EXISTING EXIT & EMERGENCY LIGHTS.
- DOORS / GLAZING
  - EXISTING STOREFRONT SYSTEM TO REMAIN
  - EXISTING DOOR TO REMAIN. SEE A-0.1 FOR NEW HARDWARE.
  - REMOVE ALL EXISTING WEATHERSTRIPPING AND PREPARE DOOR SURFACE FOR NEW.
  - REMOVE EXISTING DOOR & FRAME. PREPARE OPENING FOR NEW. SEE SHEET A-0.1
- FIXTURES / FINISHES
  - REMOVE ALL FINISHES, WALL BASE & TRIM THROUGHOUT INTERIOR (TYP. U.N.O). G.C. SHALL ENSURE INTEGRITY OF EXISTING GYP. BD. BENEATH. NOTIFY ARCHITECT IMMEDIATELY IF DEMOLITION EXPOSES ANY UNFORESEEN CONDITIONS.
  - REMOVE ALL FLOORING, THROUGHOUT
  - WITHIN THIS TOILET ROOM TO REMAIN, G.C. SHALL REMOVE ALL FINISHES.
  - REMOVE FIXTURES THROUGHOUT SALES.
- EQUIPMENT
  - ALL TOILET ROOM ACCESSORIES TO BE REMOVED UNLESS OTHERWISE NOTED.
  - REMOVE EXISTING SECURITY SYSTEM
- MECHANICAL
  - REMOVE / RELOCATE THERMOSTAT / TEMPERATURE SENSOR - SEE MECHANICAL SHEETS
  - EXISTING MECHANICAL SYSTEM SHALL BE MODIFIED AS REQUIRED TO ACCOMMODATE NEW CEILING CONDITIONS. REMOVE ALL HVAC COMPONENTS NOT BEING RE-USED. (SEE MECHANICAL PLANS).
- PLUMBING
  - THIS TOILET ROOM ONLY - EXISTING TOILET, SINK & MOP SINK TO BE REMOVED. ASSOCIATED PLUMBING TO REMAIN AND RE-USED WITH NEW FIXTURES.
  - THIS TOILET ROOM ONLY - EXISTING TOILET, SINK, FLOOR DRAIN, MOP SINK AND ALL ASSOCIATED PLUMBING TO BE REMOVED COMPLETELY.
  - EXISTING DRINKING FOUNTAIN TO BE REMOVED. EXISTING WATER LINES / ELECTRICAL TO BE RE-USED IF FEASIBLE FOR NEW WATER HEATER. SEE PLUMBING DRAWINGS.
  - EXISTING WATER HEATER TO BE REMOVED. EXISTING WATER LINES / ELECTRICAL TO BE RE-USED IF FEASIBLE FOR NEW WATER HEATER. SEE PLUMBING DRAWINGS.
  - EXISTING FLOOR DRAIN TO REMAIN.
- ELECTRICAL
  - REMOVE ALL LIGHTING THROUGHOUT. SEE SHEET A2.1
  - EXISTING ELECTRICAL PANELS TO BE REMOVED. SEE ELECTRICAL SHEETS
  - REMOVE EXISTING OUTLETS THROUGHOUT, INCLUDING ALL FLOOR OUTLETS UNLESS OTHERWISE NOTED. REMOVE WIRE TO SOURCE.
  - EXISTING OUTLETS / OCCUPANCY SENSOR TO REMAIN THIS ROOM
- LOW VOLTAGE COMMUNICATION SYSTEM
  - ALL EXISTING ELECTRIC, VOICE AND DATA COMPONENTS ARE TO BE REMOVED, UNLESS NOTED OTHERWISE. SEE ELECTRICAL SHEETS. DO NOT REMOVE UTILITY PROVIDER DEVICES OR CABLING ON THE PRIMARY SIDE OF UTILITY PROVIDER DEVICES.
  - REMOVE EXISTING SPEAKERS, CAMERAS AND SECURITY DEVICES THROUGHOUT
- FIRE SUPPRESSION / SPRINKLER SYSTEM
  - EXISTING SPRINKLER / HEAD LOCATION TO REMAIN IN PROPOSED 'OPEN TO DECK' & EXISTING GYP. CEILING AREAS. INSPECT AND ENSURE PROPER WORKING ORDER (TYP.) C. SHALL PROTECT DURING CONSTRUCTION.

A KEY NOTES


RGLA

rgla solutions, inc.

5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com

REVISIONS:	DATE:
ISSUE FOR PERMIT LANDLORD PRICING	06/18/25

robert g. lyon + associates, inc.  
retail architecture  
5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com



THE ABOVE DRAWINGS AND SPECIFICATIONS AND IDEAS, DECISIONS AND ARRANGEMENTS REPRESENTED THEREBY ARE AND SHALL REMAIN THE PROPERTY OF THIS OFFICE. AND NO PART THEREOF SHALL BE COPIED, DISCLOSED TO OTHERS OR USED IN THE CONNECTION WITH ANY WORK OR PROJECT OTHER THAN THE SPECIFIC PROJECT FOR WHICH THEY HAVE BEEN PREPARED AND DELIVERED WITHOUT THE WRITTEN CONSENT OF THIS OFFICE. VISUAL CONTACT WITH THESE DRAWINGS OR SPECIFICATIONS SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS. WRITTEN DIMENSIONS ON THESE DRAWINGS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTICED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS. SHOP DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE PROCEEDING WITH FABRICATION.  
© 2025 RGLA SOLUTIONS, INC.  
© 2025 ROBERT G. LYON & ASSOCIATES, INC.

carhartt

SUMMIT WOODS  
CROSSING

1744 NW CHIPMAN ROAD  
LEE'S SUMMIT, MO 64081

DEMOLITION PLANS


DRAWN BY	SLS
CHECKED BY	SL
JOB NUMBER	25303
SHEET NAME	D1.1





- |    |  |
|----|--|
| 5  | DOOR GENERAL NOTES   |
| 1. | ALL FINISH MATERIALS TO BE CLASS 1: = FLAME SPREAD INDEX 0-25: SMOKE-DEVELOPED INDEX 200 |
| 2. | G.C. SHALL VERIFY THAT THE MAXIMUM THRESHOLD HEIGHT DOES NOT EXCEED 1/2"                 |
| 3. | NEW WEATHER-STRIPPING TO BE INSTALLED ON ALL EXISTING EXTERIOR DOORS AS REQUIRED.        |

- ### 3 FINISH GENERAL NOTES



#### 4 FINISH SCHEDULE



- NOTE:**  
OWNER'S VENDOR WILL PROVIDE THE FOLLOWING KEYS:  
AA : 7  
AF : 12  
AA (KNOX BOX) : 1

6	HARDWARE SCHEDULE
---	-------------------



1. ALL WOOD FURRING AND BLOCKING SHALL BE FIRE-RETARDANT TREATED - TYPICAL.
2. ALL DIMENSIONS TO BE TO FINISHED SURFACES UNLESS NOTED OTHERWISE. GENERAL CONTRACTOR SHALL VERIFY ALL DIMENSIONS IN FIELD AND COORDINATE DIMENSIONS WITH VARIOUS TRADES BEFORE FABRICATION OR PURCHASE OF FIXTURES, MILLWORK, COUNTERS, ETC.
3. REQUIREMENTS AND DESIGN DATA SHALL BE FOLLOWED ENTIRELY, REGARDLESS OF WHETHER THEY ARE GIVEN BY BOTH THE SPECIFICATIONS AND DRAWINGS OR BY EITHER ONE ONLY.
4. SHOP DRAWINGS PREPARED BY SUPPLIERS AND SUBCONTRACTORS SHALL BE REVIEWED BY THE GENERAL CONTRACTOR PRIOR TO SUBMITTAL TO ARCHITECT.
5. CONTRACTORS TO ASSUME FULL RESPONSIBILITY, UNRELIEVED BY REVIEW OF SHOP DRAWINGS AND BY SUPERVISION OR PERIODIC OBSERVATION OF CONSTRUCTION, FOR THE FOLLOWING:
- 5.1. COMPLIANCE WITH CONTRACT DOCUMENTS.
- 5.2. DIMENSIONS TO BE CONFIRMED AND CORRELATED ON THE JOB SITE AND BETWEEN INDIVIDUAL DRAWINGS OR SETS OF DRAWINGS.
- 5.3. COORDINATION OF THE VARIOUS TRADES.
- 5.4. SAFE CONDITIONS AT THE JOB SITE.
6. UNLESS OTHERWISE NOTED, ALL DETAILS, SECTIONS AND NOTES ON DRAWINGS ARE INTENDED TO BE TYPICAL FOR SIMILAR SITUATIONS ELSEWHERE.
7. GC TO PROVIDE FIRE EXTINGUISHERS TO MEET LOCAL CODE REQUIREMENTS.

**A GENERAL NOTES**

- LIGHT METAL STRUCTURAL PARTITION BOTTOM TRACKS MAY BE FASTENED TO CONCRETE SLAB USING LOW-VELOCITY POWER DRIVEN PINS FOLLOWING THE MANUFACTURER'S INSTALLATION RECOMMENDATIONS UNLESS OTHERWISE NOTED. THE FASTENING SYSTEM USED SHALL BE AS MANUFACTURED BY HILTI (ICBO REPORT NO. ESR-2269) OR APPROVED EQUAL. PINS SHALL HAVE A MINIMUM SHANK DIAMETER OF 0.157", A MINIMUM LENGTH OF 1-1/8", AND SHALL BE SPACED AT 16" O.C. MAXIMUM.
- THE TOP TRACK OF EACH FULL HEIGHT WALL SHALL BE ATTACHED DIRECTLY TO THE FRAMING WHEN THE WALL IS PERPENDICULAR TO FRAMING AND TO BLOCKING BETWEEN FRAMING @ 4'-0" O.C. WHEN THE WALL IS PARALLEL TO THE FRAMING.
- PROVIDE MIN. 2'-0" HIGH CEMENT BOARD @ FLOOR BEHIND ALL FIBERGLASS REINFORCED PANELS.
- PROVIDE CEMENT BOARD UNDER ALL WALL TILE WHERE APPLICABLE.
- ALL BRACING AND SUSPENDED COMPONENTS ARE FROM STRUCTURE (NOT FROM DECK). DO NOT PENETRATE THROUGH DECK ABOVE.
- GYPSUM BOARD SHALL BE ATTACHED WITH #6 SCREWS MINIMUM UNLESS NOTED OTHERWISE.

**B PARTITION NOTES**


NOTE:	NON-BEARING METAL STUD SCHEDULE		
	STUD SIZE*	SPACING	MAX. HEIGHT (W/ FLEXIBLE FINISH)
	362S162-18	16" O.C.	13'-6"
	362S162-33	16" O.C.	21'-1"
	362S162-43	12" O.C.	25'-0"
	600S162-33	16" O.C.	30'-0"
*STUDS BY ANGELES METAL SYSTEMS, ICBO NO.1715 OR APPROVED EQUAL			

**C STUD SCHEDULE**


NOTE:  
G.C. TO CALL CARHARTT PM DURING FRAMING STAGE TO DISCUSS ANY FIELD DIMENSIONS DISCREPANCIES PRIOR TO FRAMING. ESPECIALLY OVERALL SALES FLOOR AND STOCKROOM DIMENSIONS. FAILURE TO DO SO CAN RESULT IN G.C. RE-FRAMING AT THEIR EXPENSE

NOTE:  
PRIOR TO FRAMING G.C. SHALL VERIFY NEW WALLS DO NOT CONFLICT WITH EXISTING HVAC DROPS & PIPES. FAILURE TO DO SO CAN RESULT IN G.C. RE-FRAMING AT THEIR EXPENSE

NOTE:  
ALL EXISTING WALLS IN SALES AREA TO BE BROUGHT UP TO LEVEL 5 FINISH.




EXTERIOR PARTITION




FULL HEIGHT PARTITION

WALL TYPE




EXISTING DEMISING PARTITION




FULL HEIGHT PARTITION

WALL TYPE




EXISTING INTERIOR PARTITION




FULL HEIGHT PARTITION - PANT WALL

WALL TYPE



EXISTING INTERIOR PARTITION



PARTIAL HEIGHT PARTITION


WALL TYPE

- TENANT LEASE LINE
- FIRE EXTINGUISHER - COORDINATE LOCATIONS WITH FIRE MARSHAL
- SAWOUT GROOVE IN CONCRETE SLAB PER DETAIL 8/A1.4
- EXISTING 3/4" CDX" F.T. PLYWOOD TO REMAIN
- ELECTRICAL PANELS - SEE ELECTRICAL SHEETS. INSTALL 3/4" CDX" F.T. PLYWOOD IF NOT EXISTING
- LOCATION OF NEW DATA RACK.
- NEW WATER FOUNTAIN / BOTTLE FILLER
- NOTIFY ARCHITECT IMMEDIATELY IF EXISTING STUDS OR GYP. BD. DOES NOT EXTEND TO DECK.
- G.C. TO PROVIDE CONCRETE FOR BASE OF WINDOW FIXTURE. FORMWORK IS PROVIDED WITH FIXTURE. EACH BASE IS 30" W. X 6" H.
- G.C. SHALL PROVIDE ACCESS TO WATER HEATER ON PLATFORM ABOVE MOP SINK.
- G.C. TO ENSURE THAT CONCRETE IS LEVEL TO WITHIN 1/8" VARIATIONS AT AREAS UNDER ROLLING SHELVES. VERIFY EXACT LOCATIONS W/ FIXTURE PLAN. ROLLING SHELVES EQUIPMENT IS 2,000-3,000 PSI. VERIFY EXACT CONCRETE LEVELING REQUIREMENTS W/ ARCHITECT & SHELVING VENDOR PRIOR TO CONSTRUCTION.
- G.C. SHALL INSTALL NEW SEALANT AT BOTTOM OF GLAZING AFTER TILE IS REMOVED.

**3 WALL TYPES**

SCALE  
1"=1'-0"

**KEY NOTES**



**1 CONSTRUCTION PLAN / FINISH PLAN**




SCALE  
3/16" = 1'-0"



rgla solutions, inc.  
5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com

REVISIONS:	DATE:
ISSUE FOR PERMIT, LANDLORD, PRICING	06/18/25

robert g. lyon + associates, inc.  
retail architecture  
5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com



THE ABOVE DRAWINGS AND SPECIFICATIONS AND IDEAL DESIGNS AND ARRANGEMENTS REPRESENTED THEREBY ARE AND SHALL REMAIN THE PROPERTY OF THIS OFFICE, AND NO PART THEREOF SHALL BE COPIED, DISCLOSED TO OTHERS OR USED IN THE CONNECTION WITH ANY WORK OR PROJECT OTHER THAN THE SPECIFIC PROJECT FOR WHICH THEY HAVE BEEN PREPARED AND DEVELOPED WITHOUT THE WRITTEN CONSENT OF THIS OFFICE. VISUAL CONTACT WITH THESE DRAWINGS OR SPECIFICATIONS SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE DRAWINGS. WRITTEN DIMENSIONS ON THESE DRAWINGS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTICED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS. SHOP DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE PROCEEDING WITH FABRICATION.

© 2025 RGLA SOLUTIONS, INC.  
© 2025 ROBERT G. LYON & ASSOCIATES, INC.


carhartt  
SUMMIT WOODS CROSSING

1744 NW CHIPMAN ROAD  
LEE'S SUMMIT, MO 64081

CONSTRUCTION PLAN,  
SCHEDULE & NOTES


DRAWN BY	SLS
CHECKED BY	SL
JOB NUMBER	25303
SHEET NAME	A-1.1





3 ELEVATIONS - ADA FITTING ROOM SCALE 1/4"=1'-0"


4 ELEVATIONS - FITTING ROOM SCALE 1/4"=1'-0"




2 ELEVATIONS - FITTING ROOM HALLWAY SCALE 1/4"=1'-0"

- KEY NOTES


- GC TO SECURE BENCH TO THE FLOOR & ADD CLEAR SEALANT TO WALL. CUT BASEBOARD TO ACCOMMODATE BENCH. BENCH IS 24" DEEP X 42" LONG X 18" HIGH
- PENDANT LIGHT - SEE A2.1 & LIGHTING PLANS
- (1) GC SUPPLIED HOOKS INSTALLED ON 'B-4'. HOOKS: SUNMALL INDUSTRIAL PIPE COAT HOOKS - BLACK. AVAILABLE AT AMAZON.COM
- (4) GC SUPPLIED HOOKS INSTALLED ON 'B-4'. HOOKS: SUNMALL INDUSTRIAL PIPE COAT HOOKS - BLACK. AVAILABLE AT AMAZON.COM
- G.C. TO INSTALL OWNER SUPPLIED GRAPHICS. SEE F2.1 FOR DETAILS.
- OWNER SUPPLIED. G.C. INSTALLED FITTING ROOM POST/PARTITION SYSTEM. SEE APPROVED VENDOR SHOP DRAWINGS FOR INSTALLATION INSTRUCTIONS.
- ILLUMINATED WALL MOUNTED FITTING ROOM MIRROR - STYLMARK MODEL 620096-03 BEVEL - LED-LIT SINGLE PANE MIRROR. 36" X 72" FINISH: 123-BUFFED SATIN BLACK - 3700K CORD & PLUG - NO SWITCH
- WALL MOUNTED DOOR STOP
- VINYL GRAPHIC. SEE F-2.1 FOR DETAILS.
- G.C. TO INSTALL FITTING ROOM PANEL ON ADA FITTING ROOM SIDE SO THE BENCH IS MOUNTED TO A FLUSH SURFACE.
- G.C. TO INSTALL BLOCKING WHERE FITTING ROOM PARTITIONS ATTACH TO WALL
- NO DEVICES ARE TO BE INSTALLED ON THIS WALL.
- THIS BENCH TO REMAIN LOOSE.
- 'F-5' TRANSITION TO ALIGN WITH INSIDE CASED OPENING. SEE DETAIL SHEET A-5.1
- FURR WALL TIGHT TO COLUMN.



1 ENLARGED PLAN - FITTING ROOMS SCALE 1/2"=1'-0"



B FITTING ROOM HOOK - FRH4 ④




A FITTING ROOM HOOK - FRH1 ③



rgla solutions, inc.  
5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com

REVISIONS:	DATE:
ISSUE FOR PERMIT	06/18/25
LANDLORD, PRICING	

robert g. lyon + associates, inc.  
retail architecture  
5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com



THE ABOVE DRAWINGS AND SPECIFICATIONS AND IDEAS, DESIGNS AND ARRANGEMENTS REPRESENTED THEREIN ARE AND SHALL REMAIN THE PROPERTY OF THIS OFFICE, AND NO PART THEREOF SHALL BE COPIED, DISCLOSED TO OTHERS OR USED IN THE CONNECTION WITH ANY WORK OR PROJECT OTHER THAN THE SPECIFIC PROJECT FOR WHICH THEY HAVE BEEN PREPARED AND DEVELOPED WITHOUT THE WRITTEN CONSENT OF THIS OFFICE. VISUAL CONTACT WITH THESE DRAWINGS OR SPECIFICATIONS SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE DRAWINGS. WRITTEN DIMENSIONS ON THESE DRAWINGS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS. SHOP DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE PROCEEDING WITH FABRICATION. © 2025 RGLA SOLUTIONS, INC. © 2025 ROBERT G. LYON & ASSOCIATES, INC.



SUMMIT WOODS CROSSING

1744 NW CHIPMAN ROAD  
LEE'S SUMMIT, MO 64081




FITTING ROOM DETAILS

DRAWN BY	SLS
CHECKED BY	SL
JOB NUMBER	25303
SHEET NAME	A-1.2










9 STOCKROOM / OFFICE PLATFORM DETAIL


8 SENSORMATIC CHANNEL DETAIL

4 CONNECTION DETAILS




7 PANT WALL REVEAL DETAIL

6 PANT WALL REVEAL DETAIL




6 PANT WALL REVEAL DETAIL


5 PANT WALL DETAIL




5 PANT WALL DETAIL



2 PARTITION DETAIL - TOP TRACK



3 PARTITION DETAIL - SLOTTED TRACK



1 PARTITION DETAIL - TYPICAL BOTTOM TRACK AND AT DOOR OPENING

rgla solutions, inc.  
5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com

REVISIONS:  
ISSUE FOR PERMIT  
LANDLORD PRICING

DATE:  
06/18/25

robert g. lyon + associates, inc.  
retail architecture  
5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com

THE ABOVE DRAWINGS AND SPECIFICATIONS AND IDEAS, DESIGNS AND ARRANGEMENTS REPRESENTED THEREBY ARE AND SHALL REMAIN THE PROPERTY OF THIS OFFICE, AND NO PART THEREOF SHALL BE COPIED, DISCLOSED TO OTHERS OR USED IN THE CONNECTION WITH ANY WORK OR PROJECT OTHER THAN THE SPECIFIC PROJECT FOR WHICH THEY HAVE BEEN PREPARED AND DEVELOPED WITHOUT THE WRITTEN CONSENT OF THIS OFFICE. VISUAL CONTACT WITH THESE DRAWINGS OR SPECIFICATIONS SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS. WRITTEN DAMAGING OR OTHERS DRAWINGS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS. SHOP DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE PROCEEDING WITH FABRICATION.

© 2025 RGLA SOLUTIONS, INC.  
© 2025 ROBERT G. LYON & ASSOCIATES, INC.

SUMMIT WOODS CROSSING  
1744 NW CHIPMAN ROAD  
LEE'S SUMMIT, MO 64081


CONSTRUCTION DETAILS

DRAWN BY:  
SLS  
CHECKED BY:  
SL  
JOB NUMBER:  
25303  
SHEET NAME:  
A-1.4




<ul style="list-style-type: none"><li>THE FIRE ALARM/FIRE WARNING SYSTEM SHALL BE CERTIFIED BY UNDERWRITER'S LABORATORY (UL) AND SHALL BE MAINTAINED IN ACCORDANCE WITH CITY STANDARDS. PROOF OF CERTIFICATION SHALL BE PROVIDED PRIOR TO APPROVAL OF OCCUPANCY. ALL DIGITAL ALARM COMMUNICATION TRANSMITTERS SHALL REPORT DISTINCTIVE SIGNALS FROM THE SITE FOR WATER FLOW (BY BUILDING), GENERAL FIRE ALARM, SUPERVISORY, AND SYSTEM TROUBLE CONDITIONS.</li><li>THE LANDLORD WILL PROVIDE THE BASE BUILDING FIRE ALARM SYSTEM. THE TENANT SHALL PROVIDE WITHIN THE TENANT'S SPACE ALL REQUIRED DEVICES, CONDUIT AND WIRE AND CONNECT TO THE BASE BUILDING SYSTEM. THE DESIGN, PLAN-CHECK SUBMITTAL, SYSTEM MATERIAL AND INSTALLATION, SYSTEM REPROGRAMMING AND TESTING INCLUDING THE MODIFICATION TO THE BASE BUILDING SYSTEM AND THE WORK WITHIN TENANT'S SPACE SHALL BE PERFORMED BY A LANDLORD DESIGNATED FIRE ALARM CONTRACTOR AT THE TENANT'S EXPENSE.</li></ul>		<ul style="list-style-type: none"><li>ELECTRICAL CONTRACTOR TO PROVIDE AND INSTALL O.S. - OCCUPANCY SENSOR SWITCHES AT FITTING ROOMS AND TOILET ROOMS. SEE ELECTRICAL PLANS FOR MORE INFORMATION.</li><li>ELECTRICAL CONTRACTOR TO VERIFY LIGHTING IS IN WORKING CONDITION WHEN JOB IS COMPLETE.</li><li>NO DUCTWORK, PIPING, CONDUIT, ETC. SHALL BE SUSPENDED OR ATTACHED TO THE FLOOR DECK AND/OR ROOF DECK. ALL SUCH ITEMS MUST BE SUSPENDED ONLY FROM JOISTS AND/OR BEAMS.</li><li>BOTTOM OF SUSPENDED EMERGENCY LIGHTING TO BE MOUNTED AT SAME HEIGHT AS TRACK LIGHTING</li><li>SUPPLY AND RETURN HVAC DIFFUSERS SHOWN FOR REFERENCE / LOCATION ONLY REFER TO MECHANICAL PLANS.</li></ul>		<ul style="list-style-type: none"><li>SPRINKLER NOTES SHOWN ON THIS PLAN SHOULD SERVE AS A GUIDE ONLY AND THE CONTRACTOR SHOULD NOTIFY THE TENANT REPRESENTATIVE OF ANY SUBSTANTIAL CHANGE REQUIRED IN THE DESIGN TO COMPLY WITH REQUIRED PROTECTION STANDARDS.</li><li>ALL HEADS IN GYP. BD. OR ACT CEILING ARE TO BE FULLY RECESSED AND CONCEALED WITH WHITE CAPS.</li><li>PRIOR TO START OF WORK, CONTRACTOR SHALL SUBMIT TO THE TENANT REPRODUCIBLE COPIES OF THE FIRE SPRINKLER PLANS STAMPED WITH THE APPROVAL OF THE LOCAL FIRE OFFICIAL (AND LANDLORD'S INSURANCE UNDERWRITERS WERE REQUIRED). CONTRACTOR TO VERIFY.</li><li>ALL SOFFIT AREAS ARE TO BE FULLY SPRINKLERED AS REQUIRED BY CODE AND LANDLORD.</li><li>ALL WORK TO BE IN CONFORMANCE WITH LOCAL BUILDING CODES, LANDLORD'S UNDERWRITER AND ALL OTHER AGENCIES HAVING JURISDICTION AND IN STRICT ACCORDANCE WITH MANUFACTURES RECOMMENDATIONS AND INSTRUCTIONS. G.C. TO OBTAIN ALL NECESSARY PERMITS AND APPROVALS.</li><li>SPRINKLER HEADS ARE TO BE CENTERED ON ACOUSTIC TILE AND/OR LOCATED AS SHOWN ON APPROVED SPRINKLER SHOP DRAWINGS.</li></ul>		<ol style="list-style-type: none"><li>CENTER THIS TRACK LIGHTING ON THIS WALL, STRUCTURAL FRAME, OR WINDOW PANE</li><li>CENTER THIS LIGHT IN THE ROOM / SPACE.</li><li>NEW AIR CURTAIN. SEE MECHANICAL DRAWINGS.</li><li>GRAPHIC TRACK - SEE DETAIL 3/A2.1</li><li>OPEN TO STRUCTURE ABOVE 13'-0" A.F.F. PAINT ALL TRUSSES, JOISTS, BEAMS, DUCTS, CONDUITS, EQUIPMENT, STRUCTURE, ETC. (TYP. THROUGHOUT UNLESS NOTED)</li><li>SUSPENDED TRACK LIGHTING 6" FROM GLASS.</li><li>CENTER CEILING GRID IN CENTER OF ROOM</li><li>INSTALL OWNER SUPPLIED SCENT MACHINE @ 160" A.F.F.</li></ol>	
A	FIRE ALARM NOTES	B	GENERAL NOTES	C	SPRINKLER NOTES	-	KEY NOTES

NOTE: NOTIFY OWNER/PROJECT MANAGER IMMEDIATELY IF LIGHT FIXTURES AND CEILING HEIGHTS ARE NOT ACHIEVABLE



4 SUSPENDED TRACK LIGHT DETAIL

SCALE  
N.T.S.




3 GRAPHIC TRACK DETAIL

SCALE  
1 1/2\"=1'-0"

TAG	SYMBOL	DESCRIPTION	HEIGHT
A		HIGH BAY LIGHTING	BOTTOM @ 13'-0" A.F.F.
B		TRACK HEAD - LED SPOT	TRACK MOUNTED
C		TRACK HEAD - WALL WASHER	TRACK MOUNTED
E4		4FT LINEAR LED	12'-0" A.F.F.
E4E		4 FT LINEAR LED W/ EMERGENCY	12'-0" A.F.F.
K		6" RECESSED WET LOCATION RATED EMERGENCY W/ BATTERY BACK UP	RECESSED IN PORTAL
M		PENDANT LIGHT (FITTING ROOM)	BOTTOM AT 9'-0" A.F.F. (UNO)
T		1 CIRCUIT TRACK (LENGTH PER PLAN).	13'-0" A.F.F. (UNO)
TW		EXTERIOR EMERGENCY LIGHT	6" - 12" ABOVE OPENING
EM		EMERGENCY LIGHT WITH BATTERY BACK UP	12'-0" (UNO)
X		EXIT SIGN	10'-0" (UNO)

2 LIGHT FIXTURE SCHEDULE

1 REFLECTED CEILING PLAN



**RGLA**

rgla solutions, inc.

5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com

REVISIONS:	DATE:
ISSUE FOR PERMIT LANDLORD, PRICING	06/18/25

robert g. lyon + associates, inc.

retail architecture  
5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com

THE ABOVE DRAWINGS AND SPECIFICATIONS AND IDEAS, DESIGNS AND ARRANGEMENTS REPRESENTED THEREIN ARE AND SHALL REMAIN THE PROPERTY OF THIS OFFICE, AND NO PART THEREOF SHALL BE COPIED, DISCLOSED TO OTHERS OR USED IN THE CONNECTION WITH ANY WORK OR PROJECTS OTHER THAN THE SPECIFIC PROJECT FOR WHICH THEY HAVE BEEN PREPARED AND DEVELOPED WITHOUT THE WRITTEN CONSENT OF THIS OFFICE. VISUAL CONTACT WITH THESE DRAWINGS OR SPECIFICATIONS SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS. WRITTEN DIMENSIONS ON THESE DRAWINGS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTICED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS. SHOP DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE PROCEEDING WITH FABRICATION. © 2025 RGLA SOLUTIONS, INC.

carhartt

SUMMIT WOODS CROSSING

1744 NW CHIPMAN ROAD  
LEE'S SUMMIT, MO 64081

REFLECTED CEILING  
PLAN  
DETAILS & NOTES

DRAWN BY	SLS
CHECKED BY	SL
JOB NUMBER	25303
SHEET NAME	A-2.1



NEW EXTERIOR WORK IS LIMITED TO THE FOLLOWING

- STOREFRONT SIGNAGE
- FACADE (EIFS) REPAIR

00 River Road, Ste 125  
Miller Park, IL 60176  
847.671.7452  
847.671.4200  
www.rgla.com

**Robert G. Lyon + Associates, Inc.**  
retail architecture  
5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
[www.rglia.com](http://www.rglia.com)

### A-3.1

carhartt

55'-10 1/2"

LEASE LINE

SIGN CONTRACTOR TO PROVIDE  
RACEWAY @ REAR OF PARAPET  
TO CONCEAL WIRING

SEE ELEVATION

$$1'' = 1' - 0''$$

1. EXISTING FACADE TO REMAIN. PATCH/REPAIR FACADE AS REQUIRED TO A LIKE-NEW APPEARANCE. MATCH EXISTING PAINT (COORDINATE WITH LANDLORD FOR COLOR / FINISH)
2. COORDINATE WITH SIGN CONTRACTOR DRAWINGS.
3. APPROXIMATE LINE OF ROOF BEHIND PARAPET.
4. EXISTING STOREFRONT GLAZING SYSTEM TO REMAIN. GC SHALL CLEAN, INSPECT & NOTIFY ARCHITECT IMMEDIATELY OF ANY NECESSARY REPAIRS.
5. GC TO PROVIDE & INSTALL BLACK PAPER ON STOREFRONT GLAZING AS SHOWN. REMOVE AT END OF CONSTRUCTION.
6. VINYL GRAPHICS AS SHOWN. SEE SHEET F-2.1
7. EXISTING LANDLORD EXTERIOR LIGHT FIXTURE(S) TO BE REMAIN. NOTIFY ARCHITECT IMMEDIATELY IF NOT OPERATIONAL.
8. NEW EXTERIOR LIGHT. SEE A-2.1 & ELECTRICAL SHEETS.

#




Architectural elevation drawing of a storefront. The drawing includes dimensions and callouts for various components:

- Overall width: 55'-10 1/2"
- Overall height: 30'-2"
- Sign height: 3'-0"
- Sign width: 11'-10"
- Sign text: "carhartt" with the Carhartt logo.
- Callouts: 1 (Sign), 2 (Sign mounting), 3 (Side entrance), 4 (Window panes), 5 (Door), 6 (Door handle), 7 (Light fixture), 8 (Sign mounting bracket).
- Dimensions: 2'-3" (Sign height), 19'-6" (Storefront height), 11'-10" (Sign width), 5'-0" (Side entrance width), 5'-0" (Side entrance height).
- Labels: "EQ." (Equal), "LEASE LINE".

SCALE  
3/32" = 1'-0"

### A-3.1





RGLA

rgla solutions, inc.

5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com

REVISIONS:

DATE:

ISSUE FOR PERMIT:

06/18/25

LANDLORD PRICING:

robert g. lyon + associates, inc.

retail architecture  
5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com

JOSEPH A. SKEHAN JR.  
ARCHITECT  
NUMBER 22080816

THE ABOVE DRAWINGS AND SPECIFICATIONS AND IDEAS, DECISIONS AND ARRANGEMENTS REPRESENTED THEREBY ARE AND SHALL REMAIN THE PROPERTY OF THIS OFFICE, AND NO PART THEREOF SHALL BE COPIED, DISCLOSED TO OTHERS OR USED IN THE CONNECTION WITH ANY WORK OR PROJECT OTHER THAN THE SPECIFIC PROJECT FOR WHICH THEY HAVE BEEN PREPARED AND DEVELOPED WITHOUT THE WRITTEN CONSENT OF THIS OFFICE. VISUAL CONTACT WITH THESE DRAWINGS OR SPECIFICATIONS SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE INSTRUCTIONS. WRITTEN DIMENSIONS ON THESE DRAWINGS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTICED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS. SHOP DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE PROCEEDING WITH FABRICATION.  
© 2025 RGLA SOLUTIONS, INC.  
© 2025 ROBERT G. LYON & ASSOCIATES, INC.

carhartt

SUMMIT WOODS CROSSING

1744 NW CHIPMAN ROAD  
LEE'S SUMMIT, MO 64081

INTERIOR ELEVATIONS

DRAWN BY  
SLS


CHECKED BY  
SL

JOB NUMBER  
25303

SHEET NAME

A-4.1





- EXISTING STEEL COLUMNS. PAINT "P-2" THROUGHOUT SALES AREA.
- INSTALL "WC-2" FLOOR TO 4'-0". PAINT TO MATCH ADJACENT WALL.
- INSTALL "WC-2" FLOOR TO 8'-0". PAINT TO MATCH ADJACENT WALL.
- G.C. TO INSTALL A STRIPED PATH ON THE FLOORING. G.C. TO USE RED COLOR ON CONCRETE. 8" STRIPE / 8" UNPAINTED.
- WALLS SHALL BE PAINTED TO DECK. DO NOT PAINT DECK.


2 FLOOR TRANSITION - CONCRETE TO CARPET

SCALE  
6" = 1'-0"

KEY NOTES

#

NOTE:  
ALL WALLS AND SURFACES THAT ARE TO RECEIVE VINYL GRAPHICS MUST BE COMPLETE AT LEAST TEN (10) DAYS PRIOR TO THE END OF CONSTRUCTION. THIS INCLUDES PAINT TOUCH-UP.



1 FINISH PLAN

SCALE  
3/16" = 1'-0"


RGLA

rgla solutions, inc.

5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com

REVISIONS:	DATE:
ISSUE FOR PERMIT LANDLORD, PRICING	06/18/25

robert g. lyon + associates, inc.  
retail architecture  
5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com



THE ABOVE DRAWINGS AND SPECIFICATIONS AND IDEAS, DESIGNS AND ARRANGEMENTS REPRESENTED THEREIN ARE AND SHALL REMAIN THE PROPERTY OF THIS OFFICE, AND NO PART THEREOF SHALL BE COPIED, DISCLOSED TO OTHERS OR USED IN THE CONNECTION WITH ANY WORK OR PROJECT OTHER THAN THE SPECIFIC PROJECT FOR WHICH THEY HAVE BEEN PREPARED AND DEVELOPED WITHOUT THE WRITTEN CONSENT OF THIS OFFICE. VISUAL CONTACT WITH THESE DRAWINGS OR SPECIFICATIONS SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS. WRITTEN DIMENSIONS ON THESE DRAWINGS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTICED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS. SHOP DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE PROCEEDING WITH FABRICATION.  
© 2025 RGLA SOLUTIONS, INC.  
© 2025 ROBERT G. LYON & ASSOCIATES, INC.

carhartt

SUMMIT WOODS  
CROSSING

1744 NW CHIPMAN ROAD  
LEE'S SUMMIT, MO 64081


FINISH  
PLAN

DRAWN BY	SLS
CHECKED BY	SL
JOB NUMBER	253003
SHEET NAME	A-5.1











		<div>1. 3/4" THICK FIRE RATED PLYWOOD MOUNTING BOARD (PAINT TO MATCH WALL)</div> <div>2. MANAGERS AREA</div> <div>2.1. STANDARDS: CAPITOL HARDWARE - 2000-00649 - C-LINE CHROME SLOTTED STANDARDS</div> <div>2.2. BRACKETS: CAPITOL HARDWARE - 2001-01403 - BRACKET - 14" WITH THUMB SCREW - ZINC</div> <div>2.3. SHELF REST: CAPITOL HARDWARE - 2075-00001 - CENTER - FOR C-LINE BRACKETS - ZINC</div> <div>2.4. 14" DEEP SHELF - WHITE MELAMINE</div> <div>3. HANGBAR AREA:</div> <div>3.1. STANDARDS: CAPITOL HARDWARE - 2000-00649 - C-LINE CHROME SLOTTED STANDARDS</div> <div>3.2. BRACKETS: CAPITOL HARDWARE - 2001-01603 - BRACKET - 16" WITH THUMB SCREW, ZINC</div> <div>3.3. HANGRAIL ADAPTER: CAPITOL HARDWARE - 2039-30078 - ADAPTER WITH SPRING CLAMP FOR 1" DIAMETER ROUND TUBE - CHROME</div> <div>3.4. HANGRAIL: CAPITOL HARDWARE - 646-30847 - 1" DIAMETER ROUND TUBE</div> <div>3.5. END CAP: CAPITOL HARDWARE - 652-30047 - END CAP FOR 1" DIAMETER ROUND TUBE - CHROME</div> <div>4. PLASTIC LAMINATE COUNTERTOP - WHITE</div> <div>5. INSTALL OWNER SUPPLIED CORK BOARD HORIZONTALLY, WITH BOTTOM AT 42" A.F.F.</div> <div>6. NOT USED</div> <div>7. ALL POWER &amp; DATA @ DESK SHALL BE MOUNTED @ ~38"</div> <div>8. 2'-6" d. WHITE LAMINATED COUNTERTOP W/MATCH SUPPORTS.</div> <div>9. LAMINATE SUPPORTS AT EDGES OF COUNTERTOP</div> <div>10. PLASTIC LAMINATE FINISH. SHELF UNIT HUNG ON CONTINUOUS WOOD CLEARS AT WALL. REINFORCE W/ PLYWOOD BACKING AT WALL &amp; BLOCKING IN WALL-PLASTIC LAMINATE</div> <div>11. OUTLINE OF UNDER COUNTER REFRIGERATOR ( 20" w. x 35" h. x22" d)</div> <div>12. LOCATION OF 3" DIA. GROMMET W/ COVER (2 TYP.)</div> <div>13. ADJUSTABLE SHELF ON RECESSED PILASTER STANDARDS</div> <div>14. LOCATION OF VERTICAL FILING CABINET (15" W X 25" D X 29" H)</div> <div>15. LOCATION OF SAFE (20" W X 20" D X 20" H)</div>
7		ELEVATION KEY NOTES

4	BREAK COUNTER ELEVATION		5	BREAK COUNTER SECTION		6	BREAK COUNTER - REFERENCE PHOTO	
		SCALE 3/4"=1'-0"			SCALE 3/4"=1'-0"			NOTE: BREAK ROOM AND MANAGER'S DESK COUNTERTOPS MAY BE SOURCED FROM PRE-MANUFACTURED / IN-STOCK COUNTERTOPS IN A NEUTRAL COLOR AT LOCAL HOME IMPROVEMENT CENTER.
1	MANAGER'S DESK ELEVATION		2	MANAGER'S DESK SECTION		3	MANAGERS DESK - REFERENCE PHOTO	
		SCALE 1/2"=1'-0"			SCALE 1/2"=1'-0"			

RGLA

rgla solutions, inc.

5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com

REVISIONS:	DATE:
ISSUE FOR PERMIT LANDLORD PRICING	06/18/25

robert g. lyon + associates, inc.

retail architecture  
5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com

JOSEPH A. SCHIRGAN JR.  
ARCHITECT  
NUMBER 220805810

THE ABOVE DRAWINGS AND SPECIFICATIONS AND IDEAS, DESIGNS AND ARRANGEMENTS REPRESENTED THEREIN ARE AND SHALL REMAIN THE PROPERTY OF THIS OFFICE, AND NO PART THEREOF SHALL BE COPIED, DISCLOSED TO OTHERS OR USED IN THE CONNECTION WITH ANY WORK OR PROJECTS OTHER THAN THE SPECIFIC PROJECT FOR WHICH THEY HAVE BEEN PREPARED AND DEVELOPED WITHOUT THE WRITTEN CONSENT OF THIS OFFICE. VISUAL CONTACT WITH THESE DRAWINGS OR SPECIFICATIONS SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE DRAWINGS. WRITTEN DIMENSIONS ON THESE DRAWINGS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTOR SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS. SHOP DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE PROCEEDING WITH FABRICATION.

© 2025 RGLA SOLUTIONS, INC.  
© 2025 ROBERT G. LYON & ASSOCIATES, INC.

carhartt







SUMMIT WOODS CROSSING


1744 NW CHIPMAN ROAD  
LEE'S SUMMIT, MO 64081

FIXTURE DETAILS


DRAWN BY	SLS
CHECKED BY	SL
JOB NUMBER	253003
SHEET NAME	F-1.2



 <p>MOUNTING HOOK &amp; ASSOCIATED MOUNTING HARDWARE PROVIDED BY INTERIOR SIGN VENDOR</p> <p>GRAPHIC FRAMES &amp; GRAPHIC SUPPLIED BY OTHERS.</p> <p>VENDOR SIGN</p> <p>GRAPHIC TYPE 'A' - SECTION</p>		 <p>MOUNTING RAIL - BOTTOM @ 13'-0" AFF</p> <p>NYLON ROLLERS WITH HOOKS</p> <p>CABLE CUT AS REQUIRED TO ACHIEVE DESIRED DROP LENGTH</p> <p>OVERLAPPING GRAPHIC FRAMES</p> <p>EQ. 2</p> <p>EQ. 1</p> <p>GRAPHIC TYPE 'A' - FRONT ELEV.</p>		 <p>FRAMED SIGN (PROVIDED BY OTHERS) SEE A1.2 FOR PLACEMENT</p> <p>CLEATS MOUNTED TO SIGN (PROVIDED BY OTHERS)</p> <p>CLEATS MOUNTED TO WALL (PROVIDED BY OTHERS)</p> <p>GRAPHIC TYPE 'B'</p>		 <p>WALL OR FIXTURE NOTED ON PLAN</p> <p>WALL MOUNTED GRAPHIC. SEE A4.1/A1.2 FOR PLACEMENT. TRIM AS NEEDED.</p> <p>GRAPHIC TYPE 'C'</p>		 <p>CARHARTT LETTERS &amp; LOGO &amp; ASSOCIATED MOUNTING HARDWARE (PROVIDED BY OTHERS). SEE A4.1 FOR PLACEMENT.</p> <p>GRAPHIC TYPE 'D'</p>		 <p>GLASS</p> <p>GRAPHIC MOUNTED TO GLASS - 2ND SURFACE INSTALL FOR STOREFRONT GRAPHICS. 1ST SURFACE INSTALL FOR FITTING ROOM DOOR GRAPHICS &amp; STOREFRONT TEMPORARY GRAPHICS. SEE A-3.1 FOR STOREFRONT GRAPHIC LOCATIONS</p> <p>GRAPHIC TYPE 'E'</p>		<ol style="list-style-type: none"><li>1. SUSPENDED GRAPHIC FRAME : G.C. TO ASSEMBLE &amp; INSTALL SUSPENDED FRAME. SUSPEND FROM GRAPHIC RAIL NYLON ROLLERS ABOVE. SEE A/F2.1.</li><li>2. FRAMED SIGN : G.C. TO INSTALL FRAMED SIGNS. MOUNT WITH CLEATS. PROVIDE CONCEALED BLOCKING. SEE B/F2.1.</li><li>3. VINYL GRAPHICS ON WALL / WOOD DOOR : SEE C/F2.1</li><li>4. PROJECTED PIN MOUNTED SIGN : G.C. TO INSTALL PIN MOUNTED LETTERS &amp; LOGO ON WC-1. SEE D/F2.1</li><li>5. VINYL GRAPHIC ON GLAZING : SEE E/F2.1.</li><li>6. BACKWRAP GRAPHICS : SEE F/F2.1</li><li>7. VINYL GRAPHIC ON GLAZING : OWNER FURNISHED, G.C. INSTALLED WITHIN THE FIRST 5 DAYS OF CONSTRUCTION. SEE E/F2.1. G.C. SHALL REMOVE VINYL AT THE END OF CONSTRUCTION.</li></ol>				
A	HANGING GRAPHIC SIGN DETAIL	SCALE NONE	B	FRAMED SIGN DETAIL	SCALE NONE	C	WALL MOUNTED SIGN DETAIL	SCALE NONE	D	PIN MOUNTED SIGN DETAIL	SCALE NONE	E	GLAZING GRAPHICS DETAIL	SCALE NONE	2	KEY NOTES



F	BACKWRAP GRAPHIC SIGN DETAIL	SCALE 1/2" = 1'-0"
---	------------------------------	-----------------------




1	INTERIOR SIGNAGE & GRAPHICS PLAN	SCALE 3/16" = 1'-0"
---	----------------------------------	------------------------



**rgla solutions, inc.**  
5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com

REVISIONS:	DATE:
ISSUE FOR PERMIT	06/18/25
LANDLORD, PRICING	

**robert g. lyon + associates, inc.**  
retail architecture  
5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com



THE ABOVE DRAWINGS AND SPECIFICATIONS AND IDEAS, DESIGNS AND ARRANGEMENTS REPRESENTED THEREBY ARE AND SHALL REMAIN THE PROPERTY OF THIS OFFICE, AND NO PART THEREOF SHALL BE COPIED, DISCLOSED TO OTHERS OR USED IN THE CONNECTION WITH ANY WORK OR PROJECT OTHER THAN THE SPECIFIC PROJECT FOR WHICH THEY HAVE BEEN PREPARED AND DEVELOPED WITHOUT THE WRITTEN CONSENT OF THIS OFFICE. VISUAL CONTACT WITH THESE DRAWINGS OR SPECIFICATIONS SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS. WRITTEN DIMENSIONS ON THESE DRAWINGS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTICED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS. SHOP DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE PROCEEDING WITH FABRICATION.

© 2025 RGLA SOLUTIONS, INC.  
© 2025 ROBERT G. LYON & ASSOCIATES, INC.



**SUMMIT WOODS CROSSING**  
1744 NW CHIPMAN ROAD  
LEE'S SUMMIT, MO 64081

INTERIOR SIGNAGE & GRAPHIC PLAN & DETAILS

DRAWN BY	SLS
CHECKED BY	SL
JOB NUMBER	25303
SHEET NAME	F-2.1



OWNERSHIP OF INSTRUMENTS OF SERVICE  
The Consultant shall retain all common law, statutory and other reserved rights, including, without limitation, the copyright thereto.  
ownership of instruments of service shall remain the property of the Consultant. The Consultant shall retain all common law, statutory and other reserved rights, including, without limitation, the copyright thereto.

GENERAL ELECTRICAL INSTALLATION NOTES	
A.	CODE COMPLIANCE: PROVIDE ALL ELECTRICAL WORK COMPLIANT WITH ALL PREVAILING CODES.
B.	LISTINGS: PROVIDE MATERIALS, COMPONENTS AND ASSEMBLED COMPONENTS WITH LISTINGS AND LABELS FROM A NATIONALLY RECOGNIZED TESTING LABORATORY (NRTL), MANUFACTURED, LISTED AND LABELED FOR THEIR INTENDED USE.
C.	RATED BUILDING SURFACES: SEPARATE DEVICE BOXES BY A MINIMUM OF 6 INCHES WHERE INSTALLED BACK-TO-BACK WITHIN DEMISING WALLS TO MAINTAIN REQUIRED FIRE AND SOUND RATING (TYPICAL OF ALL DEVICE BOXES INSTALLED ON DEMISING WALLS). PROVIDE LISTED FIRE-RATED WRAPS AROUND ALL RECESSED OUTLET, DEVICE AND EQUIPMENT BOXES IN FIRE/SMOKE RATED WALLS, CEILINGS AND FLOORS TO MEET OR EXCEED THE RESPECTIVE FIRE/SMOKE RATING OF THE SURFACE.
D.	RATED PENETRATIONS: SEAL ALL PENETRATIONS THROUGH FIRE-RATED AND/OR SMOKE-RATED MEMBRANES (FLOORS, WALLS, CEILINGS, ETC.) USING SEALANT PRODUCTS THAT MEET OR EXCEED THE RATING OF THE RESPECTIVE MEMBRANE.
E.	GANGED DEVICES: INSTALL WIRING DEVICES GANGED WHEREVER POSSIBLE FOR INSTANCES WHERE THEY ARE SHOWN TOGETHER. THIS INCLUDES LOCATIONS ABOVE COUNTERS AND WORK SURFACES WHERE APPLICABLE.
F.	OUTLET BOXES NEAR CORNERS: INSTALL WALL-MOUNTED SWITCHES, CONTROLS, RECEPTACLES, OUTLETS, ETC. AT LEAST 6 INCHES FROM WALL CORNERS.
G.	CONCEALEMENTS: CONCEAL ALL CONDUIT DROPS AND RISES WITHIN WALLS, AND PROVIDE FLUSH-MOUNTED WALL OUTLET BOXES UNLESS OTHERWISE INDICATED.
H.	DOCUMENTS OF OTHER TRADES: REVIEW DOCUMENTS OF OTHER TRADES, INCLUDING ARCHITECTURAL PRIOR TO SUBMITTING A BID. PROVIDE ELECTRICAL WORK FOR EQUIPMENT, DEVICES, ETC. OF OTHER TRADES AS REQUIRED TO RENDER THEM FULLY OPERATIONAL. REFER TO ARCHITECTURAL ELEVATIONS FOR INTENDED LOCATIONS AND MOUNTING HEIGHTS FOR EQUIPMENT AND OUTLETS, ETC. PRIOR TO COMMENCING WITH ANY RELATED ROUGH-IN WORK.
I.	SCHEMATIC REPRESENTATIONS: CIRCUITING WORK SHOWN ON DRAWINGS IS FOR SCHEMATIC GENERAL GRAPHIC REPRESENTATION ONLY. DETERMINE SPECIFICS IN FIELD (POINT-TO-POINT ROUTING, HOME-RUN LOCATIONS, METHODS OF CONCEALMENT, ETC.), LOCATIONS AND ROUTING INDICATED ON PLANS ARE SCHEMATIC AND DIAGRAMMATIC IN NATURE. LAYOUT AND INSTALL ALL ELECTRICAL WORK IN STRICT COMPLIANCE WITH CHAPTER 1, PART I, ARTICLE 110.26 OF THE LATEST ADOPTED EDITION OF THE NATIONAL ELECTRICAL CODE (NFPA 70).
J.	HOME-RUN DESIGNATIONS: HOME-RUN DESIGNATIONS INDICATED ON PLANS ARE SCHEMATIC DESIGNATIONS ONLY. DETERMINE EXACT CIRCUIT ASSIGNMENTS IN FIELD BASED ON FIELD CONDITIONS. PROVIDE COLOR-CODED CONDUCTOR INSULATION ACCORDINGLY, CODED PROPERLY DEPENDING ON SYSTEM, PHASE, NEUTRAL, ETC. PROVIDE EQUIPMENT AND PANELBOARD SCHEDULES THAT ACCURATELY INDICATE INSTALLED CONDITIONS.
K.	LOCAL DISCONNECTS AND CONTROLS AT EQUIPMENT: LOCAL DISCONNECTS AND LOCAL CONTROLS SHOWN AT OR ON EQUIPMENT IN PLAN-VIEW ARE SHOWN FOR SCHEMATIC ASSOCIATIONS ONLY. AVOID INSTALLING DISCONNECTS OR CONTROLS ON EQUIPMENT ENCLOSURES. INSTALL ON ADJACENT WALLS OR BUILDING STRUCTURE, OR PROVIDE FIELD-FABRICATED UNISTRUT OR EQUIVALENT ASSEMBLIES AS NEEDED. PROVIDE FIELD COORDINATION WITH SITE CONDITIONS AND OTHER TRADES, AND PROVIDE ALL RELATED WORK IN STRICT COMPLIANCE WITH NFPA 70, INCLUDING ARTICLE 110.26. PROVIDE A PERMANENT LABEL ON LOCAL DISCONNECTS NOTING THE EQUIPMENT IT SERVES AND THE PANEL AND CIRCUIT NUMBER FEEDING THE EQUIPMENT PER NFPA 70, ARTICLE 110.22(A).
L.	EQUIPMENT & LOAD COORDINATION: REFER TO AND COORDINATE WITH POWER FLOOR PLANS, EQUIPMENT SCHEDULES (INCLUDING EQUIPMENT COORDINATION SCHEDULES), DRAWINGS OF ALL TRADES, ALL DIVISIONS AND SECTIONS OF SPECIFICATIONS AND INSTALLERS OF ALL TRADES. BASED ON ACTUAL EQUIPMENT BEING PROVIDED, DETERMINE AND PROVIDE APPROPRIATE BREAKERS, FUSES, CONDUCTORS, CONTROLS, POWER DISTRIBUTION EQUIPMENT, ETC. PERFORM THESE SERVICES PRIOR TO FURNISHING POWER DISTRIBUTION EQUIPMENT SUBMITTALS.
M.	EXTERIOR ELECTRICAL WORK AND WORK SUBJECT TO MOISTURE: EXTERIOR ELECTRICAL WORK SHALL BE WEATHERPROOF AND WATER-TIGHT, AND SHALL BE RUST-RESISTANT. PROVIDE XHHW-2 CONDUCTORS FOR ALL APPLICATIONS THAT ARE BELOW GRADE OR SUBJECT TO MOISTURE. PROVIDE MINIMUM NEMA 3R ENCLOSURES FOR ALL OUTDOOR EQUIPMENT AND ALL INDOOR EQUIPMENT THAT IS SUBJECT TO MOISTURE. PROVIDE NEMA 1 ENCLOSURES FOR ALL OTHER INDOOR EQUIPMENT.
N.	EQUIPMENT GROUNDING CONDUCTORS: PROVIDE EQUIPMENT GROUNDING CONDUCTORS IN STRICT COMPLIANCE WITH THE LATEST ADOPTED EDITION OF THE NATIONAL ELECTRICAL CODE (NFPA 70), INCLUDING ARTICLE 250 AND TABLE 250.122. THESE CONDUCTORS MAY OR MAY NOT BE INDICATED ON SINGLE-LINE DIAGRAMS OR ELSEWHERE, BUT SHALL BE PROVIDED UNDER BASE BID NEVERTHELESS.
O.	OVERHEAD WORK: HOLD ALL NEW OVERHEAD ELECTRICAL WORK AS TIGHTLY AS POSSIBLE TO THE BOTTOM OF THE OVERHEAD STRUCTURE. DO NOT INSTALL ANY ELECTRICAL WORK WITHIN SIX INCHES OF ROOF DECKING.
P.	COORDINATION DRAWINGS: LAYOUT ALL PROPOSED RACEWAY ROUTING, ELEVATIONS, INSTALLATION METHODS, ETC. ON COORDINATION DRAWINGS AND COORDINATE ALL PROPOSED RACEWAY ROUTING WITH ALL AFFECTED TRADES PRIOR TO COMMENCING WITH WORK. IN ADDITION, REVIEW THE INFORMATION WITH ARCHITECT, ENGINEER AND OWNER FOR ALL AREAS WHERE THE RACEWAYS WILL BE VISIBLE AFTER COMPLETION OF CONSTRUCTION.
Q.	JUNCTION AND PULL BOXES: LOCATE JUNCTION AND PULL BOXES SO THAT THEY REMAIN ACCESSIBLE AFTER ALL CONSTRUCTION WORK IS COMPLETE. COORDINATE ALL WORK WITH ALL OTHER TRADES PRIOR TO COMMENCEMENT OF THE WORK. LOCATE BOXES IN A MANNER THAT AVOIDS HAVING TO USE ACCESS PANELS. IF ACCESS PANELS ARE INEVITABLE, PROVIDE THEM RATED TO MEET OR EXCEED THE FIRE AND/OR SMOKE RATINGS OF THE RESPECTIVE CEILING OR WALL, AND OBTAIN APPROVAL OF DESIGN PROFESSIONALS FOR EACH LOCATION.
R.	CONDUCTOR TERMINATIONS: IN CASES WHERE CONDUCTOR SIZES ARE TOO LARGE TO FIT INTO LUGS/TERMINALS, PROVIDE APPROPRIATE FACTORY LUG KITS FOR AFFECTED EQUIPMENT IF AVAILABLE. ELSEWHERE, PROVIDE INSULATED BUTT SPLICES OR EQUIVALENT METHOD, WITH TAILS SIZED TO FIT LUGS/TERMINALS. PROVIDE SPLICES IN SEPARATE BOXES IF REQUIRED BASED ON FIELD CONDITIONS, BOX SIZE LIMITATIONS, ETC. CONCEAL BOXES IN ACCESSIBLE OVERHEAD JOIST SPACES IN FINISHED REGULARLY OCCUPIED AREAS.
S.	TYPE MC, AC, NM, SE CABLE: WHERE MORE THAN TWO TYPE MC, AC, NM, OR SE CABLES CONTAINING TWO OR MORE CURRENT CARRYING CONDUCTORS IN EACH CABLE ARE INSTALLED IN CONTACT WITH THERMAL INSULATION, CABLE, OR SEALING FOAM MAINTAIN SPACING BETWEEN CABLES.

EXISTING CONDITIONS - GENERAL NOTES	
A.	INTENT OF DOCUMENTS: EXISTING CONDITIONS SHOWN ON THE DRAWINGS ARE BASED ON VISUAL FIELD OBSERVATIONS AND THE REVIEW OF PREVIOUS DRAWINGS THAT MAY NOT HAVE BEEN CERTIFIED "AS-BUILT". IT IS NOT THE INTENT OF THE ELECTRICAL DOCUMENTS THAT EXISTING CONDITIONS BE ACCURATELY SHOWN. EXISTING ELECTRICAL WORK IS SHOWN TO A VERY LIMITED EXTENT ON THE DRAWINGS AND IS SHOWN FOR GENERAL PLANNING REFERENCE ONLY.
B.	PRE-BID SURVEY: PERFORM A DETAILED PRE-BID WALK-THROUGH FIELD INSPECTION AND SURVEY TO REVIEW THE EXISTING STRUCTURES AND PREMISES, TO ACCURATELY DETERMINE EXISTING CONDITIONS, AND TO DETERMINE SCOPE OF REQUIRED ELECTRICAL RELATED WORK. INCLUDE APPLICABLE ACCESSIBLE CEILING CAVITY AREAS IN THIS INSPECTION.
C.	REUSE OF REMOVED MATERIALS: DO NOT REUSE REMOVED ELECTRICAL MATERIALS UNLESS SPECIFICALLY INDICATED IN PROJECT DOCUMENTS. EXISTING WIRING SYSTEMS MAY BE UTILIZED ONLY TO THE EXTENT INDICATED IN PROJECT DOCUMENTS, OR AS DIRECTED BY OWNERS REPRESENTATIVE IN FIELD.
D.	EXISTING POWER DISTRIBUTION EQUIPMENT: WHERE MODIFICATIONS ARE MADE TO EXISTING POWER DISTRIBUTION EQUIPMENT, COMPLETELY RE-TYPE PANELBOARD DIRECTORIES USING ACCURATE "AS-BUILT" INFORMATION, WHEN ADDING COMPONENTS TO EXISTING POWER DISTRIBUTION EQUIPMENT, PROVIDE FULL SIZE (NO SPLIT OR TANDEM DEVICES) OVERCURRENT PROTECTION DEVICES (OCPDs) TO MATCH THOSE ALREADY IN PLACE, INCLUDING MANUFACTURER, MODEL/SERIES, SHORT CIRCUIT CURRENT (SCCR/IC) RATINGS, PROVIDE COMMON TRIPS (NO FIELD-INSTALLED HANDLE TIES) IN THE SAME GUTTER FOR MULTI-POLE DEVICES, PROVIDE SWITCHING DUTY (ISWD), HACR AND HID RATINGS WHERE APPLICABLE FOR LOADS. PROVIDE HANDLE LOCK-ON DEVICES FOR EMERGENCY AND CRITICAL LOADS.
E.	EXISTING BRANCH CIRCUITS: MAINTAIN, AND RECONNECT IF REQUIRED, BRANCH CIRCUITS THAT ARE EXISTING TO REMAIN, UNLESS NOTED OTHERWISE. ALL CIRCUIT DESIGNATIONS SHOWN ON THE DRAWINGS INDICATE NEW CIRCUIT ASSIGNMENTS, NOT EXISTING. WHERE COLOR CODING OF BRANCH CIRCUIT CONDUCTORS DOES NOT COMPLY WITH NFPA 70 OR IS NOT CONSISTENT WITH EXISTING CONDITIONS, MODIFY TO COMPLY.
F.	ADDED LOADS TO EXISTING CIRCUITS: IN CASES WHERE NEW LOADS ARE INDICATED TO BE CONNECTED TO EXISTING CIRCUITS WITH EXISTING LOADS, METER THE EXISTING CIRCUIT IN ADVANCE AND ENSURE THE EXISTING PLUS ADDED LOAD DOES NOT EXCEED 80 PERCENT OF THE SOURCE CIRCUIT BREAKER AMPERE RATING. IF THAT LOAD IS EXCEEDED, NOTIFY DESIGN PROFESSIONAL.
G.	REASSIGNMENT OF EXISTING CIRCUITS: IN CASES WHERE EXISTING CIRCUITS ARE REUSED (BASED ON INFORMATION SHOWN ON DRAWINGS OR BASED ON FIELD CONDITIONS) BUT MUST BE CONNECTED TO BREAKERS OTHER THAN THEIR ORIGINAL BREAKER, MODIFY COLOR CODING AS REQUIRED IF THE NEW BREAKER ASSIGNMENT IS CONNECTED TO A DIFFERENT LINE/PHASE THAN THE ORIGINAL ONE. USE MEANS AND METHODS COMPLIANT WITH NFPA 70 AND WITH AUTHORITIES HAVING JURISDICTION.
H.	ELECTRICAL WORK TO REMAIN OR BE RELOCATED: IF REQUIRED TO ACCOMMODATE CONSTRUCTION RELATED ACTIVITIES OR WHERE SPECIFICALLY SHOWN ON THE DRAWINGS, TEMPORARILY REMOVE, STORE IN PROTECTED LOCATION ON SITE, AND REINSTALL CONFLICTING ELECTRICAL EQUIPMENT, LUMINAIRES, OR DEVICES THAT ARE TO REMAIN OR TO BE RELOCATED.
I.	PROTECTIVE BARRIERS: PROVIDE AND MAINTAIN TEMPORARY PARTITIONS AND DUST BARRIERS ADEQUATE TO PREVENT THE SPREAD OF DUST AND DIRT TO ADJACENT FINISHED AREAS AND OTHER SYSTEM COMPONENTS. PROTECT ADJACENT INSTALLATIONS DURING CUTTING AND PATCHING OPERATIONS. REMOVE PROTECTION AND BARRIERS AFTER DEMOLITION OPERATIONS ARE COMPLETE. PREVENT AIRBORNE DUST AND PARTICULATE MATTER RESULTING FROM ELECTRICAL WORK FROM ENTERING OCCUPIED SPACES, AND FROM ENTERING AIR INTAKES TO OPERATING HVAC SYSTEMS. MEET WITH OWNER AND HVAC INSTALLER TO DETERMINE SPECTRAL INDOOR AIR QUALITY (IAQ) REQUIREMENTS RELATED TO ELECTRICAL THAT MAY APPLY TO THIS PROJECT. COOPERATE FULLY WITH HVAC IAQ REQUIREMENTS THAT AFFECT ELECTRICAL WORK AND ARE AFFECTED BY ELECTRICAL WORK.
J.	PENETRATIONS: MAKE REQUIRED ELECTRICAL OPENINGS THROUGH WALLS, FLOORS, ETC. IMMEDIATELY PRIOR TO INSTALLATION OF WORK. PROPERLY AND PERMANENTLY SEAL ELECTRICAL OPENINGS IMMEDIATELY AFTER INSTALLATION OF WORK. PROVIDE TEMPORARY SEALS FOR APPLICATIONS WHERE PENETRATIONS ARE MADE BUT CANNOT BE PERMANENTLY SEALED WITHIN FOUR HOURS.
K.	PRE-EXISTING CODE VIOLATIONS: INSPECT EXISTING ELECTRICAL WORK IN AREAS ACCESSED UNDER THIS PROJECT AND BRING INTO COMPLIANCE WITH NFPA 70. THIS APPLIES ONLY TO THE EXTENT THAT SUCH WORK IS UNCOVERED IN THE IMMEDIATE PROJECT AREAS AFFECTED BY CONSTRUCTION ACTIVITIES, AND ONLY TO THE LIMITED EXTENT THAT IT APPLIES TO PRE-EXISTING GENERAL INSTALLATION METHODS SUCH AS MISSING JUNCTION BOX PLATE, OPEN JUNCTION BOX KNOCKOUT, MINOR CONDUIT RE-ANCHORING AND MINOR EXPOSED WIRING CONNECTIONS. IF MORE EXTENSIVE CODE OR SAFETY VIOLATIONS ARE DISCOVERED, IMMEDIATELY BRING THEM TO THE ATTENTION OF THE OWNER'S REPRESENTATIVE (DETAILED IN WRITING) ALONG WITH PROPOSED COST FOR CORRECTIONS AND IMPACT (IF ANY) ON THE CONSTRUCTION SCHEDULE.
L.	TEMPORARY LIGHTING AND POWER: COMPLY WITH NFPA 70 (INCLUDING ARTICLE 590), NFPA 70E AND ALL OTHER PREVAILING CODES. PROVIDE SUFFICIENT LIGHTING AND POWER CENTERS THROUGHOUT INTERIOR OF NEW WORK OR RENOVATION SCOPE. PROVIDE GFCI PROTECTION FOR ALL WORK. COORDINATE WITH GENERAL CONTRACTOR AND OTHER TRADES, AND PROVIDE ANY REQUIRED TEMPORARY ELECTRICAL NEEDS THAT ARE REQUIRED. FULLY DEMOLISH TEMPORARY ELECTRIC BY END OF PROJECT. UPON RECEIVING WRITTEN PERMISSION FROM OWNER'S REPRESENTATIVE, TEMPORARY ELECTRICAL SERVICE(S) MAY BE DERIVED FROM EXISTING BUILDING ENERGIZED SERVICE. PROVIDE OVERCURRENT PROTECTION, DISCONNECTS, CABLES, CONDUCTORS, RACEWAY, ETC. ACCORDINGLY. PROVIDE TEMPORARY SERVICE FROM UTILITY IF PERMISSION TO USE EXISTING BUILDING POWER IS NOT GRANTED BY OWNER'S REPRESENTATIVE; ARRANGE WITH LOCAL UTILITY FOR TEMPORARY SERVICE AND PAY ASSOCIATED FEES FOR INSPECTIONS, CONNECTIONS, ETC., AND PAY FOR UTILITY ELECTRIC USAGE/CONSUMPTION COSTS. RESTORE ASSOCIATED SITE AND BUILDING MATERIALS TO THEIR PRE-CONSTRUCTION STATE AND CONDITION AFTER TEMPORARY LIGHTING AND POWER IS NO LONGER NEEDED.
M.	INTERIM LIFE-SAFETY PROVISIONS: PROVIDE INTERIM FIRE ALARM AND CODE MINIMUM LIGHTING IN DEMOLITION AND CONSTRUCTION AREAS. PROVIDE TEMPORARY PLASTIC COVERS, OBTAINED FROM SMOKE DETECTOR MANUFACTURER OR OBTAINED FROM A THIRD PARTY AND SPECIFICALLY APPROVED FOR SUCH USE BY SMOKE DETECTOR MANUFACTURER, OVER EXISTING SMOKE DETECTORS WITHIN PROJECT AREA, AND IN ADJACENT AREAS THAT ARE EXPOSED TO CONSTRUCTION RELATED DUST OR AIRBORNE PARTICULATES. REMOVE ALL TEMPORARY LIFE SAFETY WORK WHEN NO LONGER NEEDED.
N.	INTERIM EGRESS PATH PROVISIONS: PROVIDE TEMPORARY UL 924 COMPLIANT EXIT AND/OR EGRESS LIGHTING ALONG EGRESS ROUTES THAT MUST REMAIN ACCESSIBLE DURING CONSTRUCTION. PROVIDE TEMPORARY FIRE ALARM SYSTEM PULL STATIONS AND AUDIOVISUAL ALARM NOTIFICATION DEVICES ALONG ALL AFFECTED EGRESS ROUTES. REMOVE THIS SCOPE WHEN NO LONGER NEEDED.

ELECTRIC LEGEND		ELECTRIC LEGEND	
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION
LIGHTING AND LIGHTING CONTROLS			
	LUMINAIRE (REFER TO THE LUMINAIRE SCHEDULE) NOTE THAT OTHER SHAPES MAY ALSO BE USED TO REPRESENT LUMINAIRES		BRANCH CIRCUIT HOME RUN WITH PANEL NAME AND CIRCUIT NUMBER(S)
	SHADED LUMINAIRES DENOTE THOSE CONNECTED TO EMERGENCY OR STANDBY POWER AS APPLICABLE (UNSWITCHED LUMINAIRES ARE EGRESS LIGHTS AND/OR NIGHT-LIGHTS THAT OPERATE 24/7)		CABLING / RACEWAY INSTALLED CONCEALED IN WALLS OR ABOVE CEILING
	TRACK LIGHTING IN LENGTH SHOWN AND WITH NUMBER OF LUMINAIRE HEADS AS INDICATED PROVIDE ALL REQUIRED ACCESSORIES (FITTINGS, END CAPS, POWER FEEDS, ETC.)		CABLING / RACEWAY INSTALLED BELOW FLOOR OR GRADE
	SINGLE / DOUBLE SIDED EXIT SIGN CONNECT AHEAD OF SWITCHING & CONFIGURE ARROWS TO INDICATE DIRECTION OF EGRESS TRAVEL		CABLE TRAY
	EMERGENCY LIGHTING UNIT WITH 90-MINUTE BATTERY BACKUP AND ASSOCIATED REMOTE HEADS WHERE APPLICABLE. CONNECT TO LOCAL LIGHTING CIRCUIT AHEAD OF SWITCHING		FEEDER DUCT / BUS DUCT
	A = LUMINAIRE TYPE, NL = NIGHT-LIGHT (UNSWITCHED), a = SWITCHING DESIGNATION, EL = EGRESS LUMINAIRE (ILLUMINATES PATH OF EGRESS, UNSWITCHED UNLESS OTHERWISE NOTED)		JUNCTION BOX ABOVE ACCESSIBLE CEILING JUNCTION BOX AT OVERHEAD STRUCTURE IN AREAS WITH NO CEILING
	LIGHTING SWITCH (KEYS: 2 = 2-POLE, 3 = 3-WAY, 4 = 4-WAY, D=DIMMER, K=KEYED, T = TIMER SWITCH, M = MOMENTARY-CONTACT, P = SWITCH W/PILOT LIGHT)		FLUSH MOUNTED JUNCTION BOX OR PULL BOX AS APPLICABLE FOR APPLICATION
	CEILING-MOUNTED OCCUPANCY SENSOR. DUAL TECHNOLOGY UNLESS OTHERWISE NOTED BY TYPE. TYPE "IR" = INFRARED, TYPE "US" = ULTRASONIC		FLUSH MOUNTED PULL BOX
	WALL-MOUNTED OCCUPANCY SENSOR SWITCH. DUAL TECHNOLOGY UNLESS OTHERWISE NOTED BY TYPE. TYPE "IR"=INFRARED, TYPE "US"=ULTRASONIC, "V"=VACANCY SENSOR, "D" = DIMMED.		CONDUIT UP OR DOWN
RECEPTACLES AND MISCELLANEOUS OUTLETS		ABBREVIATIONS	
	SINGLE ("SIMPLEX"), DUPLEX, AND DOUBLE DUPLEX ("QUAD") RECEPTACLE RESPECTIVELY	42"	DISTANCE ABOVE FINISHED FLOOR / GRADE / PAVEMENT
	GFI / GFCI RECEPTACLES	AFCI	ARC-FAULT CIRCUIT INTERRUPTER
	RECEPTACLE ATTRIBUTES 42" = MOUNT RECEPTACLE AT THIS HEIGHT ABOVE GRADE / FINISHED FLOOR C = INSTALL ABOVE COUNTER AND BACKSPLASH H = INSTALL RECEPTACLE HORIZONTALLY L = LIT (PROVIDE ILLUMINATED FACE OR INDICATOR LIGHT TO INDICATE THERE IS POWER TO RECEPTACLE) SW = SPLIT WIRED W = WEATHER PROOF WHILE IN USE COVER AND WEATHER RESISTANT RECEPTACLE	ATS	AUTOMATIC TRANSFER SWITCH
	LOW VOLTAGE THERMOSTAT (LEFT) AND TEMPERATURE SENSOR (RIGHT)	BAS	BUILDING AUTOMATION SYSTEM
	LINE VOLTAGE THERMOSTAT (LEFT) AND REVERSE ACTING THERMOSTAT (RIGHT)	C.T.C.	WORK UNDER DIVISION 27 OR 28 AS APPLICABLE
	MOTOR RATED TOGGLE SWITCH, MANUAL STARTER WITH PILOT LIGHT, AND MANUAL STARTER WITH PILOT LIGHT WITH EXTERNAL RELAY FOR CONTROL OR MONITORING RESPECTIVELY - ALL MAY BE KEYED "K"	C/B	CIRCUIT BREAKER
	HEAVY DUTY DISCONNECT SWITCH (NON-FUSED) (LEFT) HEAVY DUTY DISCONNECT SWITCH (FUSED) (RIGHT)	C/H	COUNTER HEIGHT OR SPECIAL HEIGHT DEVICE
	CONTACTOR	DW	DISHWASHER
	ELECTRICAL PANELBOARD OR DISTRIBUTION BOARD (DIMENSIONS MAY VARY / FLUSH OR SURFACE MOUNTED AS INDICATED)	E.	EMERGENCY
	OIL FILLED TRANSFORMER	FBO	FURNISHED BY OTHERS - INSTALLED AND WIRED BY E.C.
SINGLE LINE DIAGRAM		FIBO	FURNISHED AND INSTALLED BY OTHERS - WIRED BY E.C.
	ELECTRIC UTILITY COMPANY METER AND ASSOCIATED CURRENT TRANSFORMERS	FP	FLAT PANEL DISPLAY
	CUSTOMER ELECTRIC METER AND ASSOCIATED CURRENT TRANSFORMERS HD = HIGH DENSITY METERING CABINET/BANK MOUNTED TO TIGHTLY GROUP ALL METERS TOGETHER	FWE	FURNISHED WITH EQUIPMENT BY OTHERS - INSTALLED AND WIRED BY E.C.
	HEAVY DUTY DISCONNECT SWITCH (NON-FUSED)(LEFT) (FUSED)(RIGHT) SIZES MAY BE SHOWN ONLY IN SCHEDULE	GD	GARBARGE DISPOSAL
	ELECTRICAL PANELBOARD OR DISTRIBUTION BOARD	GFEF	GROUND FAULT EQUIPMENT PROTECTION
	SURGE PROTECTIVE DEVICE	GF1 / GFCI	GROUND FAULT CIRCUIT INTERRUPTER DEVICE
PLAN-VIEW AND GRAPHIC LINE TYPES		GRD	GROUND
WORK SHOWN BOLD-CONTINUOUS INDICATES NEW WORK (UNLESS OTHERWISE INDICATED)		H.C.	WORK UNDER DIVISION 23 "HAND - OFF - AUTO" SWITCH
WORK SHOWN FADED INDICATES EXISTING WORK TO REMAIN OR NEW WORK BY OTHERS AS APPLICABLE (UNLESS OTHERWISE INDICATED)		H.O.A.	ISOLATED GROUND
WORK SHOWN BOLD-DASHED INDICATES SELECTIVE DEMOLITION WORK (UNLESS OTHERWISE INDICATED)		IG	ISOLATED GROUND
ELECTRONIC DRAWING REQUEST		ISC	SHORT CIRCUIT CURRENT
ELECTRONIC COPIES OF THESE DRAWINGS MAY BE REQUESTED AT: APPS.KLHENGRS.COM/DRAWINGREQUESTS.			

KOHR'S LONNEMANN HEIL ENGINEERS, INC.  
MECHANICAL/ELECTRICAL ENGINEERS  
WWW.KLHENGRS.COM

1538 ALEXANDRIA PIKE, SUITE 11  
FT. THOMAS, KENTUCKY 41075  
800-354-9783  
859-442-8650 FAX

LEXINGTON, KENTUCKY  
LOUISVILLE, KENTUCKY  
COLUMBUS, OHIO  
KLH JOB #: 27551

rgla solutions, inc.

5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com

NO.	REVISIONS:	DATE:
	BID, LL REVIEW, AND PERMIT	06.18.25

retail architecture

5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com

JEREMY A. TOY  
NUMBER  
PE-201044400

6/18/2025

SEAL:

THE ABOVE DRAWINGS AND SPECIFICATIONS AND ALL DESIGN AND ARRANGEMENTS REPRESENTED THEREIN ARE THE SOLE PROPERTY OF ROBERT G. LYON + ASSOCIATES, INC. AND NO PART THEREOF SHALL BE COPIED, DISCLOSED TO ANY OTHER OR USED IN THE CONNECTION WITH ANY OTHER PROJECT OTHER THAN THE SPECIFIC PROJECT FOR WHICH THEY HAVE BEEN PREPARED AND FOR WHICH THEY WERE SUBMITTED TO THE CLIENT. ANY VIOLATION OF THESE TERMS SHALL BE CONSIDERED A VIOLATION OF THE WRITTEN CONSENT OF THIS OFFICE. VISUAL CONTACT WITH THESE DRAWINGS OR SPECIFICATIONS SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS. WRITTEN INDEMNITY ON THESE DRAWINGS SHALL HAVE PRECEDENCE OVER SCALED INSTRUMENTS. CONTRACTORS SHALL VERIFY ALL INFORMATION ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY DISCREPANCIES IMMEDIATELY. SHOP DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE PROCEEDING WITH FABRICATION. © 2024 ROBERT G. LYON + ASSOCIATES, INC.

SUMMIT WOODS CROSSING  
1744 NW CHIPMAN ROAD  
LEE'S SUMMIT, MO 64081


ELECTRIC COVER SHEET

DRAWN BY	DJR
CHECKED BY	MPR
JOB NUMBER	253003
SHEET NAME	E-001



A. **EXIT-SIGN CONNECTIONS:** CONNECT ALL EXIT SIGNAGE AHEAD OF ANY SWITCHING.  
B. **INDOOR EGRESS LIGHTING:** CONNECT ALL INDOOR EGRESS LIGHTING, DESIGNATED "EL," AHEAD OF ANY SWITCHING. UNLESS CONTROL METHODS ARE INDICATED OTHERWISE FOR A GIVEN AREA.  
C. **BATTERY BACKUP DEVICES:** WHERE INDICATED IN DOCUMENTS, PROVIDE UL 924 LISTED BATTERY DEVICES, WHICH AUTOMATICALLY REVERT TO FULL ILLUMINATION FOR THE AFFECTED LUMINAIRE IN THE EVENT OF LOSS OF POWER FROM THE NORMAL POWER SUPPLY CIRCUIT. PROVIDE UNSWITCHED "HOT" SUCH COMPONENTS TO PROVIDE CONTINUOUS POWER EVEN IF LUMINAIRE IS TURNED OFF USING NORMAL LIGHTING CONTROLS.  
D. **TRANSFER/RELAY DEVICES:** WHERE INDICATED IN DOCUMENTS, PROVIDE TRANSFER/RELAY CONTROL DEVICES, WHICH AUTOMATICALLY REVERT TO FULL ILLUMINATION FOR THE AFFECTED LUMINAIRE IN THE EVENT OF LOSS OF POWER FROM THE NORMAL POWER SUPPLY CIRCUIT. PROVIDE UNSWITCHED "HOT" SUCH COMPONENTS, TO PROVIDE CONTINUOUS POWER EVEN IF LUMINAIRE IS TURNED OFF USING NORMAL LIGHTING CONTROLS.


L1	LOCATION OF MASTER SWITCH/BANK. SEE LIGHTING DETAILS FOR MORE INFORMATION.
L2	PROVIDE CEILING MOUNTED OCCUPANCY SENSOR TO OVERRIDE SALES AREA GENERAL LIGHTING FOR AFTER-HOURS USE. MOUNT OCCUPANCY SENSOR ON CEILING OF EACH FIXTURE IN THE SAME AREA. CENTER BETWEEN LIGHT FIXTURE. TYP. SEE LIGHTING CONTROL DESIGN INTENT DETAIL ON SHEET E-101 FOR MORE INFORMATION.
L4	SEE THE SWITCH BANK DETAIL. WHERE CIRCUIT IS SHOWN ON THE SWITCH BANK DETAIL. THE INTENT IS FOR ALL LIGHTING ON THAT CIRCUIT TO BE CONTROLLED BY THE SWITCH. A CONTACTOR CONTROLLED BY THE TIMECLOCK, EXCEPT FOR EMERGENCY AND EXIT LIGHTING, WHICH SHALL BE CONNECTED TO THE CIRCUIT AHEAD OF ALL SWITCHING.

[illegible]

SEAL:

**carhartt**   
SUMMIT WOODS CROSSING  
1744 NW CHIPMAN ROAD  
LEE'S SUMMIT, MO 64081

DRAWN BY
DJR
CHECKED BY
MPR
JOB NUMBER
25303
SHEET NAME
E-100



**OWNERSHIP OF INSTRUMENTS OF SERVICE**  
All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by the Consultant as instruments of service shall remain the property of the Consultant. The Consultant shall retain all common law, statutory and other reserved rights, including, without limitation, the copyright therein.



OWNERSHIP OF INSTRUMENTS OF SERVICE  
The Consultant shall retain all common law, statutory and other reserved rights, including, without limitation, the copyright thereto.

## ELECTRIC LUMINAIRE SCHEDULE

GENERAL NOTES:  
A. REFER TO "COMMENTS" COLUMN FOR MOUNTING TYPE, NUMBER OF FACES AND ARROWS OF EXIT SIGNS. VERIFY IN FIELD PRIOR TO INSTALLATION.  
B. VERIFY COMPATIBILITY WITH VOLTAGE, CONTROLS, ETC. FOR ALL LUMINAIRE COMPONENTS.  
C. COORDINATE EACH LUMINAIRE LOCATION WITH THE ARCHITECTURAL REFLECTED CEILING PLANS, CEILING INSTALLERS, ETC. AND PROVIDE APPROPRIATE MOUNTING SYSTEM REQUIRED FOR EACH LUMINAIRE. ALSO, PROVIDE PLASTER FRAMES, WALL BRACKETS, SUPPORTS, OR OTHER APPURTENANCES AS REQUIRED FOR PROPER AND COMPLETE INSTALLATIONS.  
D. WEAR CLEAN WHITE COTTON GLOVES WHEN HANDLING EXPOSED REFLECTIVE LUMINAIRE SURFACES. REMOVE PLASTIC SHIPPING BAGS ONLY AFTER INTERIOR WORK IS COMPLETE, AND CLEAN ALL SURFACES WITH CLEAN DRY CHEESECLOTH.  
E. MOUNTING HEIGHTS INDICATED ARE TO THE BOTTOM OF THE LUMINAIRE, UNLESS OTHERWISE NOTED.  
F. PRODUCTS: PROVIDE PRODUCTS INDICATED ON DRAWINGS AND SCHEDULES. WHERE MULTIPLE MANUFACTURER SERIES/MODEL NUMBERS ARE LISTED FOR A SINGLE LUMINAIRE, PROVIDE ONE OF THOSE LISTED. WHERE A SPECIFIC MANUFACTURER SERIES/MODEL NUMBER IS LISTED AS BASIS-OF-DESIGN, AND WHERE IT IS STATED THAT EQUIVALENTS WILL BE CONSIDERED, ANY PROPOSED NON-LISTED LUMINAIRES ARE SUBJECT TO REVIEW BY DESIGN PROFESSIONAL(S), SUBMITTALS FOR WHICH SHALL BE FURNISHED AT LEAST (10) DAYS PRIOR TO BID DUE DATE OR THEY WILL NOT BE CONSIDERED. THESE PRE-BID SUBMITTALS SHALL CLEARLY STATE EXACTLY WHAT IS BEING PROPOSED AND SHALL DEMONSTRATE COMPLIANT EQUIVALENCY.  
G. LIGHT FIXTURES AND LAMPS ARE TO BE PROVIDED BY THE GC. PURCHASE FROM OWNER REQUIRED SUPPLIER (SEE G0.0 FOR CONTACT INFORMATION).

TYPE	DESCRIPTION	MANUFACTURER	MODEL	MOUNTING	LIGHT SOURCE	LAMP QTY	DRIVER	DRIVER QTY	BATTERY	BATTERY TYPE	FINISH	LOAD (VA)	UNIVERSAL VOLTAGE (MVOLT)	VOLTAGE	Comments
A	HI BAY LIGHTING	SPECTRUM LIGHTING	ALDDH16LX-100L-35K-DS10X-CD72-AL16/MW-DR1 6D-CNFR-PT	PENDANT	LED	1	ELECTRONIC	1	No	NONE	PREMIUM SILVER	81 VA	Yes	120 V	MOUNT AT 13'-0" AFF
B	TRACK HEAD - LED SPOT	CONTECH	CTL2638-NAB	TRACK	LED	1	ELECTRONIC	1	No	NONE	BLACK	16 VA	Yes	120 V	
C	TRACK HEAD - WALL WASHER	CONTECH	CTL192H3D-B	LED	1	ELECTRONIC	1	No	NONE	BLACK	28 VA	Yes	120 V		
E4	LINEAR LED	NICOR	LSL-1-4-455-U-S-8	SURFACE	INTEGRAL LED	1	N/A	1	No	NONE	WHITE	45 VA	Yes	120 V	MOUNT AT 12'-0" AFF; PROVIDE 3500K MODEL
E4E	LINEAR LED	NICOR	LSL-1-4-455-U-S-EM8	SURFACE	INTEGRAL LED	1	N/A	1	Yes	INTEGRAL-90 MINUTE	WHITE	45 VA	Yes	120 V	MOUNT AT 12'-0" AFF; PROVIDE 3500K MODEL
EM	EMERGENCY LIGHTING UNIT	LITHONIA	ELM4L	PENDANT/SURFACE	LED	1	ELECTRONIC	1	Yes	INTEGRAL-90 MINUTE	WHITE	8 VA	Yes	120 V	
EX	EXIT SIGN WITH BATTERY BACK-UP	COOPER	APXEL-7-1-R	SURFACE	LED	1	ELECTRONIC	1	Yes	INTEGRAL-90 MINUTE	WHITE	3 VA	Yes	120 V	PROVIDE WITH 90 MINUTE BATTERY BACKUP.
M	HI BAY LIGHTING	DAC LIGHTING	DS242-LED35-120-AN-COIL	PENDANT	INTEGRAL LED	1	ELECTRONIC	1	No	NONE	SILVER	35 VA	No	120 V	MOUNT AT 9'-0" AFF
T4	TRACK	CONTECH	SINGLE CIRCUIT TRACK - BLACK	PENDANT/SURFACE	N/A	1	N/A	1	No	NONE	BLACK	0 VA	Yes	120 V	SURFACE MOUNT ON GYP BD CEILINGS. SUSPEND AT 13'-0" AFF IN OPEN TO DECK AREAS.
T6	TRACK	CONTECH	SINGLE CIRCUIT TRACK - BLACK	PENDANT/SURFACE	N/A	1	N/A	1	No	NONE	BLACK	0 VA	Yes	120 V	SURFACE MOUNT ON GYP BD CEILINGS. SUSPEND AT 13'-0" AFF IN OPEN TO DECK AREAS.
T8	TRACK	CONTECH	SINGLE CIRCUIT TRACK - BLACK	PENDANT/SURFACE	N/A	1	N/A	1	No	NONE	BLACK	0 VA	Yes	120 V	SURFACE MOUNT ON GYP BD CEILINGS. SUSPEND AT 13'-0" AFF IN OPEN TO DECK AREAS.
T10	TRACK	CONTECH	SINGLE CIRCUIT TRACK - BLACK	SURFACE	N/A	1	N/A	1	No	NONE	BLACK	0 VA	Yes	120 V	
T12	TRACK	CONTECH	SINGLE CIRCUIT TRACK - BLACK	PENDANT/SURFACE	N/A	1	N/A	1	No	NONE	BLACK	0 VA	Yes	120 V	SURFACE MOUNT ON GYP BD CEILINGS. SUSPEND AT 13'-0" AFF IN OPEN TO DECK AREAS.
TW	EXTERIOR EGRESS FIXTURE	TRACE LITE	SLW-15-4K-WH-EM-NS	WALL MOUNTED	LED	2	ELECTRONIC	1	Yes	INTEGRAL-90 MINUTE	WHITE	10 VA	Yes	120 V	
XEM	EXIT SIGN EMERGENCY LIGHT COMBO WITH BATTERY BACKUP	SURE-LITES	APC7RSQ	SURFACE	LED	2	ELECTRONIC	1	Yes	INTEGRAL-90 MINUTE	WHITE	4 VA	Yes	120 V	PROVIDE WITH 90 MINUTE BATTERY BACKUP; MOUNT AT 10'-0" AFF

**KLH ENGINEERS**  
KOHRS LONNEMANN HEIL ENGINEERS, INC.  
MECHANICAL/ELECTRICAL ENGINEERS  
WWW.KLHENGRS.COM

1538 ALEXANDRIA PIKE, SUITE 11  
FT. THOMAS, KENTUCKY 41075  
800-354-9783  
859-442-8050  
859-442-8058 FAX

LEXINGTON, KENTUCKY  
LOUISVILLE, KENTUCKY  
COLUMBUS, OHIO  
KLH JOB #: 27551

**RGLA**  
r gla solutions, inc.

5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com

NO.	REVISIONS:	DATE:
	BID, LL REVIEW, AND PERMIT	06.18.25

**robert g. lyon + associates, inc.**  
retail architecture

5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com

THE ABOVE DRAWINGS AND SPECIFICATIONS AND IDEAS, DESIGNS AND ARRANGEMENTS REPRESENTED THEREIN ARE AND SHALL REMAIN THE PROPERTY OF THE OFFICE AND NO PART THEREOF SHALL BE COPIED, DISCLOSED TO OTHERS OR USED BY THE CONTRACTOR WITH ANY WORK OR PROJECT OTHER THAN THE SPECIFIC PROJECT FOR WHICH THEY HAVE BEEN PREPARED AND DEVELOPED WITHOUT THE WRITTEN CONSENT OF THIS OFFICE. VISUAL CONTACT WITH THESE DRAWINGS OR SPECIFICATIONS SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS. WRITTEN ENDORSEMENT ON THESE DRAWINGS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY DISCREPANCIES FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS. SHOP DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE PROCEEDING WITH FABRICATION.  
© 2024 RGLA SOLUTIONS, INC.  
© 2024 ROBERT G. LYON & ASSOCIATES, INC.

JEREMY A. TOY  
NUMBER  
PE-2021044400  
6/18/2025  
SEAL:

## ELECTRIC CONTACTOR SCHEDULE

NOTES:  
1) PROVIDE A MINIMUM OF (2) SPARE CONTACTS IN EACH CONTACTOR UNLESS NOTED OTHERWISE.  
2) REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION.  
3) CONTACTOR DESIGNATIONS DO NOT INDICATE QUANTITY OF CONTACTORS, THEY INDICATE CONTACTOR GROUPING(S) AND COMMON CONTROL METHODS ONLY. PROVIDE QUANTITY OF CONTACTOR(S) NEEDED TO ACCOMMODATE NUMBER OF POLES SHOWN.


### CONTROL ZONE DESCRIPTION & CONTACTOR CONTROL METHOD

#### C1 - STOREFRONT

#### C2 - INTERIOR LIGHTING

#### C3 - EXTERIOR LIGHTING/SIGNAGE

SUPPLY	CIRCUIT NUMBER	NUMBER OF POLES	CONTACT CURRENT	LOAD NAME
C1				
A	29	1	3 A	LTG SALES 1
A	27	1	8 A	SHOW WINDOW RECEPTACLES
C2				
A	1	1	9 A	SALES GENERAL LTG
A	5	1	7 A	PERIMETER TRACK
A	11	1	8 A	PERIMETER TRACK
A	9	1	7 A	CENTER TRACK
A	7	1	5 A	CENTER TRACK
A	19	1	5 A	RIGHT FITTING ROOM AREA 2
A	3	1	8 A	SALES GENERAL LTG
C3				
A	8	1	10 A	SIGNAGE / CONTINUOUS
A	10	1	0 A	EXTERIOR LIGHTING




### KEYED NOTES:

1. PROVIDE ENGRAVED DESCRIPTION WITH BLACK REVEAL & +/- 3/16" HIGH LETTERING (TYPICAL).
2. SEE SPECIFICATIONS FOR WALL PLATE MATERIAL, STYLE AND TYPE (TYPICAL).
3. SWITCHING DESIGNATION (TYPICAL - SHOWN FOR REFERENCE ONLY, NOT TO BE ENGRAVED).
4. TYPE OF SWITCH (TYPICAL - SHOWN FOR REFERENCE ONLY, NOT TO BE ENGRAVED).
5. PROVIDE MASTER OVERRIDE SWITCH.

### MASTER SWITCH BANK DETAIL

SCALE: NONE



## LIGHTING CONTROL DESIGN INTENT

STOREFRONT SIGNAGE AND EXTERIOR LIGHTING:  
HARDWARE: TIMECLOCK AND CONTACTOR  
CONTROL INTENT: STOREFRONT SIGNAGE SHALL TURN "ON" AND "OFF" BASED ON THE TIME SCHEDULE(S) PROGRAMMED INTO THE TIMECLOCK.

SALES AREA DISPLAY LIGHTS:  
HARDWARE: WALL MOUNTED TOGGLE SWITCHES, LIGHTING CONTACTOR, TIMECLOCK, AND TIMER SWITCH.  
CONTROL INTENT: DURING BUSINESS HOURS (HOURS PROGRAMMED INTO TIMECLOCK) THE DISPLAY LIGHTS AND TRACK LIGHTING SHALL TURN "ON" AND "OFF" BASED ON THE TIME SCHEDULE(S) PROGRAMMED INTO THE TIMECLOCK.  
THE TIMER SWITCH SHALL OVERRIDE THE TIMECLOCK SCHEDULING (FOR A MAXIMUM OF 2-HOURS) AND ALLOW FOR AFTER HOURS CONTROL OF THE LIGHTING.

SALES AREA GENERAL LIGHTING:  
HARDWARE: WALL MOUNTED TOGGLE SWITCHES, TIMECLOCK/TIMER SWITCH, AND OCCUPANCY SENSOR.  
CONTROL INTENT: DURING BUSINESS HOURS (HOURS PROGRAMMED INTO TIMECLOCK) THE SALES AREA GENERAL LIGHTING SHALL TURN "ON" AND "OFF" BASED ON THE TIME SCHEDULE(S) PROGRAMMED INTO THE TIMECLOCK.  
THE TIMER SWITCH SHALL OVERRIDE THE TIMECLOCK SCHEDULING (FOR A MAXIMUM OF 2-HOURS) AND ALLOW FOR AFTER HOURS CONTROL OF THE LIGHTING. OCCUPANCY SENSORS SHALL ALLOW FOR AFTER HOURS GENERAL LIGHTING OVERRIDE WHENEVER THE CONTACTOR IS OFF.

STOREFRONT LIGHTING AND RECEPTACLES:  
HARDWARE: WALL MOUNTED TOGGLE SWITCH, LIGHTING CONTACTOR(S), AND TIMECLOCK.  
CONTROL INTENT: STOREFRONT LIGHTING, RECEPTACLES AND SIGNAGE SHALL TURN "ON" AND "OFF" BASED ON THE TIME SCHEDULE(S) PROGRAMMED INTO THE TIMECLOCK.

### KEYED NOTES:

1. PROVIDE TIME-BASED CONTROL FOR APPLICABLE CIRCUITS AS DEFINED ON TIMECLOCK SCHEDULE.
2. PROVIDE CONTACTOR CONTROL FOR APPLICABLE CIRCUITS AS DEFINED ON LIGHTING CONTACTOR SCHEDULE.


### LIGHTING CONTROL DESIGN INTENT

SCALE: NONE

## ELECTRIC LIGHTING - DETAILS

DRAWN BY
DJR
CHECKED BY
MPR
JOB NUMBER
25303
SHEET NAME
E-101



[illegible]

Technical drawing of a vertical structure, possibly a wall or a column, showing various markers and labels. The drawing includes a vertical line with several horizontal lines intersecting it. On the left side, there are labels: "23", "0° A-27", "E7", "0° A-27", "E7", "0° A-23", "0° A-27", "E7", "0° A-23", "E4", "SIGN", and "A-8". On the right side, there is a circular marker with a horizontal line through it. The drawing is a technical sketch, likely for a construction or engineering project.

THE ABOVE DRAWINGS AND SPECIFICATIONS AND IDEAS, DESIGNS AND ARRANGEMENTS REPRESENTED THEREBY ARE AND SHALL REMAIN THE PROPERTY OF THIS OFFICE. NO PART HEREOF IS TO BE REPRODUCED OR COPIED OR OTHERWISE USED IN THE CONNECTION WITH ANY WORK OR PROJECT OTHER THAN THE SPECIFIC PROJECT FOR WHICH IT HAS BEEN SUBMITTED. WRITTEN DIMENSIONS ON THE WRITTEN CONSTRUCTION OF THIS OFFICE, VISUAL CONTACT WITH THESE DRAWINGS OR SPECIFICATIONS SHALL NOT BE A BASIS FOR CONSIDERATION OF VARIANCE OF THESE RESTRICTIONS. WRITTEN DIMENSIONS ON THESE DRAWINGS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS. ALL DIMENSIONS MUST BE STATED IN FEET. RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS. SHOP DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE PROCEEDING WITH FABRICATION.

© 2024 ROBERT G. LYON & ASSOCIATES, INC.

DRAWN BY
DJR
CHECKED BY
MPR
JOB NUMBER
25303
SHEET NAME
E-200

**OWNERSHIP OF INSTRUMENTS OF SERVICE**  
All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by the Consultant as instruments of service shall remain the property of the Consultant. The Consultant shall retain all common law, statutory and other reserved rights, including, without limitation, the copyright thereto.



KLH

ENGINEERS

KOHR'S LONNEMANN HEIL ENGINEERS, INC.  
MECHANICAL/ELECTRICAL ENGINEERS  
WWW.KLHENGRS.COM

1538 ALEXANDRIA PIKE, SUITE 11  
FT. THOMAS, KENTUCKY 41075  
800-354-9783  
859-442-8050  
859-442-8058 FAX  
LEXINGTON, KENTUCKY  
LOUISVILLE, KENTUCKY  
COLUMBUS, OHIO  
KLH JOB #: 27551

RGLA

rgla solutions, inc.

5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com

NO.	REVISIONS:	DATE:
	BID, LL REVIEW, AND PERMIT	06.18.25

robert g. lyon + associates, inc.  
r e t a i l   a r c h i t e c t u r e  
5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com

ELECTRIC DISCONNECT SCHEDULE																				
NOTES: A. WIRES: THE NUMBER OF WIRES INDICATED INCLUDES A GROUNDED (NEUTRAL) CONDUCTOR UNLESS IT WAS VERIFIED DURING DESIGN THAT ONE IS NOT REQUIRED. THE GROUNDED CONDUCTOR MAY BE OMITTED IF NOT REQUIRED BY THE EQUIPMENT BEING SERVED. B. ENCLOSURE: WHERE FIELD IS BLANK, PROVIDE NEMA 1 ENCLOSURE FOR INDOOR INSTALLATIONS, NEMA 3R ENCLOSURE FOR OUTDOOR INSTALLATIONS OR INDOOR INSTALLATIONS SUBJECT TO MOISTURE, AND NEMA 4X FOR ALL KITCHEN AND WASH DOWN AREAS. C. SHORT CIRCUIT RATING: WHERE FIELD IS BLANK, PROVIDE A SHORT CIRCUIT RATING THAT EXCEEDS THE LISTED FAULT CURRENT.																				
EQUIPMENT	SPACE NUMBER	SPACE NAME	SUPPLY FROM	CIRCUIT NUMBER	VOLTAGE	PHASE	WIRES	TRIP RATING (A)	FRAME RATING (A)	DEMAND (A)	OCP TYPE	FEEDER OR BRANCH CIRCUIT			ULSE	GEC	ENCLOSURE	FAULT CURRENT (A)	SHORT CIRCUIT RATING (A)	COMMENTS
Disconnect - Toggle Switch																				
EF-1	5	TOILET ROOM	A	12	120 V	1	2	15	30	0 A		(2) #12 AWG CU, (1) #12 AWG CU GND. IN 3/4" CONDUIT 60C RATED						6879		
EX-WH	5	TOILET ROOM	A	4	120 V	1	2	20	30	14 A		(2) #12 AWG CU, (1) #12 AWG CU GND. IN 3/4" CONDUIT 60C RATED						3962		
Fused Switch																				
D1			WW	1	208 V	3	4	200	200	199 A	FUSED	EXISTING FEEDER, AT RATING INDICATED, TO REMAIN UNLESS NOTED OTHERWISE					NEMA 3R	42700	EXISTING	
Safety Switch																				
AC-1	1	SALES	B	23,25,27	208 V	3	4	60	60	43 A		(4) #4 AWG CU, (1) #10 AWG CU GND. IN 1-1/4" CONDUIT 60C RATED						3175		
EXRTU	1	SALES	A	14,16,18	208 V	3	4	80	100	58 A		(4) #8 AWG CU, (1) #8 AWG CU GND. IN 1-1/4" CONDUIT 60C RATED						3889		
RTU-2	1	SALES	A	20,22,24	208 V	3	4	40	60	26 A		(4) #8 AWG CU, (1) #10 AWG CU GND. IN 1" CONDUIT 60C RATED						1915		

HVAC ELECTRICAL COORDINATION SCHEDULE																													
ABBREVIATIONS					CONTRACTOR TYPE					MOTOR CONTROL TYPE					CONTROL TYPE					SHORT CIRCUIT RATING									
DC	LOCAL DISCONNECT	EC	ELECTRICAL CONTRACTOR	CS	COMBINATION STARTER	TC	TIMECLOCK	WHERE SHORT CIRCUIT RATING CODE REQUIRED VALUE INDICATES "YES" APPLICABLE EQUIPMENTS SHORT CIRCUIT RATING SHALL EXCEED THE AVAILABLE FAULT CURRENT VALUE INDICATED.																					
MC	MOTOR CONTROL (POWER)	EX	EXISTING	MCC	MOTOR CONTROL STARTER	CPT	CONTROL POWER TRANSFORMER																						
SD	DUCT SMOKE DETECTOR	FC	FIRE PROTECTION CONTRACTOR	MG	MAGNETIC STARTER OR CONTACT	BAS	BUILDING AUTOMATION SYSTEM																						
CN	CONTROLS	GC	GENERAL CONTRACTOR	MS	MANUAL STARTER	LOW	LOW VOLTAGE CONTROLS																						
TS	TOGGLE SWITCH	HC	HVAC CONTRACTOR	VFD	VARIABLE FREQUENCY DRIVE	LINE	LINE VOLTAGE CONTROLS																						
C/B	H.A.C.R. CIRCUIT BREAKER AT SOURCE PANELBOARD	MFR	MANUFACTURER	MSR	MANUAL STARTER W/ CONTROL RELAY	R/LINE	REVERSE ACTING LINE VOLTAGE THERMOSTAT																						
FUSE	FUSE AT LOCAL DISCONNECT (VERIFY FIELD RATING)	PC	PLUMBING CONTRACTOR	OV	OVERCURRENT PROTECTION	MAN	MANUAL																						
FLA	OPERATING FULL LOAD AMPS	OR	OWNER OR OTHERS			FA	FIRE ALARM																						
MCA	MINIMUM CIRCUIT AMPACITY					CO	CARBON MONOXIDE SENSOR																						
CP	HARD WIRED (WHEN INDICATED FOR DC TYPE)					INT	INTEGRAL TO EQUIPMENT																						
[BLANK]						AREA	AREA SMOKE DETECTOR																						
						DUCT	DUCT SMOKE DETECTOR																						
						ALARM	SHUTDOWN EQUIP ON GENERAL FIRE ALARM																						
						FLOW	SHUTDOWN ON SPRINKLER FLOW																						
						ANSUL	SHUTDOWN ON ANSUL ACTIVATION																						
CONNECTION MARK	DESCRIPTION	VOLTAGE	PHASE	EMERGENCY	HP	WATTS	HTG KW	FLA	MCA	OCP	FED FROM	DC TYPE	DC FURN	DC INST	DC WIRE	MC TYPE	MC FURN	MC INST	MC WIRE	CN TYPE	CN FURN	CN INST	CN WIRE	FA SHUTDOWN	SHORT CIRCUIT RATING CODE REQUIRED?	AVAILABLE FAULT CURRENT			
AC-1	AIR CURTAIN W/ELECTRIC HEAT	208 V	3	NO	0.4		8	47.3	60				EC	EC	EC	ECM	MFR	MFR	MFR	INT	MFR	MFR	MFR	NONE	No	3175			
EF-1	HVAC EXHAUST FAN	120 V	1	NO				0.4	15				EC	EC	EC	ECM	MFR	MFR	MFR	MAN	EC	EC	EC	NONE	No	6879			
EXRTU	PACKAGED ROOFTOP UNIT, GAS HEAT	208 V	3	NO				64	80				EC	EC	EC	ECM	MFR	MFR	MFR	LOW	HC	HC	HC	DUCT	Yes	3889			
RTU-2	PACKAGED ROOFTOP UNIT, GAS HEAT	208 V	3	NO				29	40				EC	EC	EC	ECM	MFR	MFR	MFR	LOW	HC	HC	HC	DUCT	Yes	1915			

ELECTRIC PANELBOARD AND SWITCHBOARD SCHEDULE																												
TYPICAL EQUIPMENT NAME NOMENCLATURE: 1 - POWER DISTRIBUTION SYSTEM (BLANK - NORMAL, E - EMERGENCY, S - STANDBY, L - LIFE SAFETY) 2 - DESCRIPTION (H - 480Y/277V, L - 208Y/120V) 3 - FLOOR / LEVEL 4 - SEQUENCE																												
ALL ALUMINUM BUSSING SHALL BE TIN-PLATED. ALL COPPER BUSSING SHALL BE EITHER TIN-PLATED OR SILVER-PLATED																												
EQUIPMENT	PHASE	SPACE NUMBER	SPACE NAME	SUPPLY FROM	POWER BRANCH	TYPE	VOLTAGE	PHASE	WIRES	DEMAND (KVA)	DEMAND (A)	MAINS RATING (A)	MAINS FRAME RATING (A)	MAINS TYPE	BUSSING (PLATED)	MOUNTING	FEEDER			LUGGS TYPE	SPD	ULSE	GEC	ENCLOSURE TYPE	FAULT CURRENT (A)	SHORT CIRCUIT RATING (A)	NOTES	
A	New Construction	4	STOCK ROOM	D1		Branch Panelboard	208	3	4	71692 VA	199 A	200	200	THERMAL MAGNETIC	COPPER OR ALUMINUM	SURFACE	(4) #30 AWG CU, (1) #6 AWG CU GND. IN 2" CONDUIT 75C RATED							NEMA 1	27177	42000		
B	New Construction	4	STOCK ROOM	A		Branch Panelboard	208	3	4	24290 VA	67 A	100	100	MAIN LUGGS ONLY	COPPER OR ALUMINUM	SURFACE	(4) #3 AWG CU, (1) #8 AWG CU GND. IN 1-1/4" CONDUIT 75C RATED							NEMA 1	24806	42000		
MDP	Existing	4		UTILITY		Distribution Panelboard	208	3	4	71692 VA	199 A	1200	1200	THERMAL MAGNETIC	COPPER OR ALUMINUM	SURFACE	EXISTING FEEDER, AT RATING INDICATED, TO REMAIN UNLESS NOTED OTHERWISE						Yes	Yes	NEMA 3R	46261	EXISTING	

ELECTRIC FEEDER SCHEDULE						
NOTES: ALL CONDUIT SIZES INDICATED ARE MINIMUM SIZES. INCREASE SIZES AS REQUIRED TO ACCOMMODATE CONDUCTOR PULLING EASE, FIELD CONDITIONS, ETC. "CU" = COPPER CONDUCTOR, "AL" = ALUMINUM CONDUCTOR ** WHERE THESE FIELDS ARE BLANK, PROVIDE INSULATION & CONDUIT MATERIAL PER THE...						
FEEDER ID NOMENCLATURE: * - INDICATES FEEDER SIZED TO COMPENSATE FOR VOLTAGE DROP 1 - GROUND TYPE (MAY BE BLANK) U = EQUIPMENT GROUND CONDUCTOR REMOVED FOR SERVICE ENTRANCE FROM UTILITY P = PARITY-SIZED EQUIPMENT GROUND CONDUCTOR X = EXISTING FEEDER TO REMAIN UNLESS OTHERWISE NOTED T = UPSIZED GROUND CONDUCTORS FOR TRANSFORMER SECONDARY 2 - CONDUCTOR AMPACITY 3 - TOTAL NUMBER OF PHASE AND GROUNDED ("NEUTRAL") CONDUCTORS 4 - CONDUCTOR MATERIAL: C = COPPER, A = ALUMINUM 5 - SPECIAL (MAY BE BLANK) I = ISOLATED GROUND (PROVIDE CONTINUOUS INSULATED EQUIPMENT GROUNDING CONDUCTOR(S) FROM INSULATED ISOLATED GROUND BAR(S) TO RESPECTIVE UPSTREAM SERVICE ENTRANCE OR DERIVED SYSTEM GROUNDING ELECTRODE CONDUCTOR AS APPLICABLE.						
SUPPLY TO	SUPPLY FROM	FEEDER ID	FEEDER	DEMAND (A)	VD %	NOTES
UTILITY	UTILITY	X1200	EXISTING FEEDER, AT RATING INDICATED, TO REMAIN UNLESS NOTED OTHERWISE	199 A	0.092	
MDP	MDP	X1200	EXISTING FEEDER, AT RATING INDICATED, TO REMAIN UNLESS NOTED OTHERWISE	199 A	0.102	
D1	WW	X200	EXISTING FEEDER, AT RATING INDICATED, TO REMAIN UNLESS NOTED OTHERWISE	199 A	0.135	
A	D1	200-4C	(4) #30 AWG CU, (1) #6 AWG CU GND. IN 2" CONDUIT 75C RATED	199 A	0.462	
B	A	100-4C	(4) #3 AWG CU, (1) #8 AWG CU GND. IN 1-1/4" CONDUIT 75C RATED	67 A	0.491	

REMOVE EXISTING ELECTRICAL PANELS DUE TO INSUFFICIENT FAULT CURRENT BRACING. REPLACE WITH NEW AS SHOWN IN THE SAME LOCATION. SEE POWER PLAN FOR EXACT LOCATION OF NEW PANEL.

NOTIFY ARCHITECT AND ENGINEER OF RECORD IMMEDIATELY IF 200A IS NOT AVAILABLE AT THE DISCONNECT.

PAD MOUNTED TRANSFORMER

UTILITY

56077 AIC

MDP

1200A MCB

46261 AIC  
EXISTING SCOR  
FED FROM:  
UTILITY  
X1200

WW

45376 AIC  
FED FROM: MDP  
X1200

D1

FED FROM: WW  
X200

200AF  
200AT

A

200A MCB

27177 AIC  
42000 SCOR  
FED FROM: D1  
200-4C

B

100A MLO

24806 AIC  
42000 SCOR  
FED FROM: A  
100-4C

SINGLE LINE - LAYOUT  
SCALE: NONE

STATE OF MISSOURI  
JEREMY A. TOY  
NUMBER  
PE-2021044400  
6/18/2025  
SEAL

THE ABOVE DRAWINGS AND SPECIFICATIONS AND DESIGN AND ARRANGEMENTS REPRESENTED THEREIN ARE AND SHALL REMAIN THE PROPERTY OF THE OFFICE AND NO PART THEREOF SHALL BE COPIED, DISCLOSED TO OTHERS OR USED IN THE CONSTRUCTION OF ANY WORK OR PROJECT OTHER THAN THE SPECIFIC PROJECT FOR WHICH THEY HAVE BEEN PREPARED AND ISSUED WITHOUT THE WRITTEN CONSENT OF THIS OFFICE. VISUAL CONTACT WITH THESE DRAWINGS OR SPECIFICATIONS SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS. WRITTEN INDEMNITY ON THESE DRAWINGS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY DISCREPANCIES FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS. SHOP DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE PROCEEDING WITH FABRICATION.  
© 2024 RGLA SOLUTIONS, INC.  
© 2024 ROBERT G. LYON & ASSOCIATES, INC.

carhartt

SUMMIT WOODS CROSSING  
1744 NW CHIPMAN ROAD  
LEE'S SUMMIT, MO 64081

ELECTRIC POWER - SINGLE  
LINE DIAGRAM


DRAWN BY  
DJR

CHECKED BY  
MPR

JOB NUMBER  
25303

SHEET NAME  
E-300



[illegible]

p: 847.671.7452  
f: 847.671.4200



THE ABOVE DRAWINGS AND SPECIFICATIONS AND IDEAS, DESIGNS AND ARRANGEMENTS REPRESENTED THEREBY ARE AND SHALL REMAIN THE PROPERTY OF THIS OFFICE; AND NO PART THEREOF SHALL BE COPIED, DISCLOSED TO OR USED BY ANY PERSON OR FIRM FOR ANY WORK OR PROJECT OTHER THAN THE SPECIFIC PROJECT FOR WHICH THEY HAVE BEEN PREPARED AND DEVELOPED WITHOUT THE WRITTEN CONSENT OF THIS OFFICE. VISUAL CONTACT WITH ANY OF THE DRAWINGS OR SPECIFICATIONS SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS. WRITTEN DIMENSIONS ON THESE DRAWINGS SHALL SUPERSEDE ANY DIMENSIONS OR DIMENSIONS; CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY DISCREPANCIES FROM THE DRAWINGS IMMEDIATELY AS SHOWN BY THESE DRAWINGS. SHOP DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE PROCEEDING WITH FABRICATION.

2024 REG. A SOLUTIONS

© 2024 ROBERT G. LYON & ASSOCIATES, INC.

**carhartt**  
SUMMIT WOODS CROSSING  
1744 NW CHIPMAN ROAD  
LEE'S SUMMIT, MO 64081

## ELECTRIC PANEL SCHEDULES

DRAWN BY

DJR

CHECKED BY \_\_\_\_\_

---

---

550

E-301

PANEL NAME: B

SUPPLY FROM: A

LOCATION: STOCK ROOM 4

DISTRIBUTION SYSTEM: 208/120V 3PH 4W

FEEDER: (4) #3 AWG CU, (1) #8 AWG CU GND, IN 1-1/4" CONDUIT 75C RATED

BUSSING: COPPER OR ALUMINUM

MAINS RATING (A): 100

MAINS TYPE: MAIN LUGS ONLY

FEEDER ID: 100-4C

MOUNTING: SURFACE

FAULT CURRENT (A): 24806

SHORT CIRCUIT RATING (A): 42000

LUGS TYPE:

ENCLOSURE TYPE: NEMA 1

PHASE: New Construction

SURGE SUPPRESSION:

ULSE:

200% NEUTRAL:

ISOLATED GROUND:

CKT	CIRCUIT DESCRIPTION	VD%	AWG	GND	TRIP	FRAME/POLE	A	B	C	POLE/FRAME	TRIP	GND	AWG	VD%	CIRCUIT DESCRIPTION	CKT	
1	SPARE	--	--	--	20 A	20 A	1	0.00	0.36			1	20 A	#12	0.136	RCPT STOCK ROOM 4	2
3	SPARE	--	--	--	20 A	20 A	1		0.00	0.00		1	20 A	20 A	--	SPARE	4
5	RCPT STOCK ROOM 4	0.126	#12	#12	20 A	20 A	1		0.36	0.36	1	20 A	20 A	#12	0.986	RCPT SALES 1	6
7	(->) BOH QUAD	0.162	#12	#12	20 A	20 A	1	1.08	0.00			1	20 A	20 A	--	SPARE	8
9	RCPT OFFICE 6	1.052	#12	#12	20 A	20 A	1		1.08	0.00		1	20 A	20 A	--	SPARE	10
11	(->) OFFICE QUAD	0.418	#12	#12	20 A	20 A	1		0.36	0.00	1	20 A	20 A	--	SPARE	12	
13	(->) BREAKROOM DUPLEX	0.261	#12	#12	20 A	20 A	1	0.18	0.00			1	20 A	20 A	--	SPARE	14
15	RCPT BREAK RM 7	0.842	#12	#12	20 A	20 A	1		0.54	0.00		1	20 A	20 A	--	SPARE	16
17	(->) BREAKROOM QUAD	0.471	#12	#12	20 A	20 A	1		0.36	0.26	1	20 A	20 A	#12	0.075	(->) RR RCPT	18
19	RCPT	0.159	#12	#12	20 A	20 A	1	0.18	0.00			1	20 A	20 A	--	SPARE	20
21	SPARE	--	--	--	20 A	20 A	1		0.00	0.00		1	20 A	20 A	--	SPARE	22
23										5.11	0.00	1	20 A	20 A	--	SPARE	24
25	AC-1   SALES 1	1.43	#4	#10	60 A	60 A	3	5.11	0.00			1	20 A	20 A	--	SPARE	26
27									5.11	0.00		1	20 A	20 A	--	SPARE	28
29	SPARE	--	--	--	20 A	20 A	1			0.00	0.00	1	20 A	20 A	--	SPARE	30
31	SPARE	--	--	--	20 A	20 A	1	0.00	0.00			1	20 A	20 A	--	SPARE	32
33	SPARE	--	--	--	20 A	20 A	1		0.00	0.00		1	20 A	20 A	--	SPARE	34
35	SPARE	--	--	--	20 A	20 A	1			0.00	0.00	1	20 A	20 A	--	SPARE	36
37	SPARE	--	--	--	20 A	20 A	1	0.00	0.00			1	20 A	20 A	--	SPARE	38
39	SPARE	--	--	--	20 A	20 A	1		0.00	0.00		1	20 A	20 A	--	SPARE	40
41	SPARE	--	--	--	20 A	20 A	1			0.00	0.00	1	20 A	20 A	--	SPARE	42

TOTAL CONNECTED LOAD: 6.9 kVA

6.7 kVA

6.8 kVA

LOAD CLASSIFICATION	CONNECTED LOAD	DEMAND FACTOR	ESTIMATED DEMAND	NOTES:	BREAKER QUANTITIES (NEW ONLY)
Continuous	15336 VA	125.00%	19170 VA		(39) 20A / 1P, (1) 60A / 3P
Non-Continuous	80 VA	100.00%	80 VA		
Receptacle	5040 VA	100.00%	5040 VA		

PANEL TOTALS

TOTAL CONNECTED LOAD: 20.5 kVA

DEMAND CALCULATION NOTES:

TOTAL DEMAND: 24.3 kVA

TOTAL DEMAND AMPS: 67 A

PANEL NAME: A

SUPPLY FROM: D1

LOCATION: STOCK ROOM 4

DISTRIBUTION SYSTEM: 208/120V 3PH 4W

FEEDER: (4) #30 AWG CU, (1) #6 AWG CU GND, IN 2" CONDUIT 75C RATED

BUSSING: COPPER OR ALUMINUM

MAINS RATING (A): 200

MAINS TYPE: THERMAL MAGNETIC

FEEDER ID: 200-4C

MOUNTING: SURFACE

FAULT CURRENT (A): 21777

SHORT CIRCUIT RATING (A): 42000

LUGS TYPE:

PHASE: New Construction

SURGE SUPPRESSION:

ULSE:

200% NEUTRAL:

ISOLATED GROUND:

CKT	CIRCUIT DESCRIPTION	VD%	AWG	GND	TRIP	FRAME	POLE	A	B	C	POLE	FRAME	TRIP	GND	AWG	VD%	CIRCUIT DESCRIPTION	CKT																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
1	SALES GENERAL LTG	1.372	#12	#12	20A	20A	1	1.07	0.72			1	20A	20A	#12	#12	0.475	(->)(G) DF1	2																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
3	SALES GENERAL LTG	1.266	#12	#12	20A	20A	1			0.93	1.65		1	20A	20A	#12	#12	0.721	(->) EX-WH   TOILET ROOM 5	4																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
5	PERIMETER TRACK	1.085	#12	#12	20A	20A	1					0.78	0.20	1	20A	20A	#12	#12	0.017	C1 C2 C3   STOCK ROOM 4	6																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																												
7	CENTER TRACK	0.778	#12	#12	15A	15A	1	0.57	1.20					1	20A	20A	*#10	*#10	2.543	SIGNAGE   CONTINUOUS	8																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																												
9	CENTER TRACK	1.305	#12	#12	15A	15A	1			0.82	0.02			1	20A	20A	#12	#12	0.011	EXTERIOR LIGHTING	10																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																												
11	PERIMETER TRACK	1.155	#12	#12	15A	15A	1					1.00	1.26	1	15A	15A	#12	#12	0.378	EF-1   LTG HALLWAY 3	12																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																												
13	RCPT SALES 1	1.243	#12	#12	20A	20A	1	0.72	6.92																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																								</

•	=	WIRE SIZED TO COMPENSATE FOR VOLTAGE DROP
•	=	REFER TO DRAWINGS FOR SPECIFICATIONS
(-)	=	NEW CIRCUIT TO EXISTING CIRCUIT BREAKER
(#)	=	CONNECT BRANCH CIRCUIT, WHICH WAS DISCONNECTED FROM ANOTHER SOURCE AS PART OF SELECTIVE DEMOLITION, TO POLE SPACE(S) INDICATED, DETERMINE EXACT POLE ASSIGNMENT(S) BASED ON EXISTING COLOR-CODING OF THE BRANCH CIRCUIT CONDUCTOR INSULATION. PROVIDE NEW BREAKER IF REQUIRED.
(A)	=	PROVIDE ARC FAULT CIRCUIT INTERRUPTER (AFCI) CIRCUIT BREAKER
(AG)	=	PROVIDE COMBINATION ARC FAULT (AFCI) / GROUND FAULT (GFCI) CIRCUIT INTERRUPTER CIRCUIT BREAKER
(AT)	=	EXISTING FUSIBLE SWITCH-CIRCUIT BREAKER WITH NEW FUSES/TRIP RATING
(B)	=	PROVIDE DRAW-OUT CIRCUIT BREAKER
(ERM)	=	PROVIDE ENERGY REDUCTION MAINTENANCE (REDUCED ENERGY) CIRCUIT BREAKER
(EX)	=	EXISTING CIRCUIT TO REMAIN

(F)	=	CIRCUIT FOR FUTURE USE. PROVIDE BREAKER INDICATED. LOAD SHOWN FOR REFERENCE ONLY.
(G)	=	PROVIDE GROUND-FAULT CIRCUIT INTERRUPTER (GFCI) CIRCUIT BREAKER
(GE)	=	PROVIDE GROUND-FAULT EQUIPMENT PROTECTION (GFEPE) CIRCUIT BREAKER
(GS)	=	PROVIDE SPECIAL PURPOSE GROUND-FAULT CIRCUIT INTERRUPTER (SPGFCI) CIRCUIT BREAKER
(H)	=	PROVIDE HANDLE TIE
(L)	=	PROVIDE LOCK-ON DEVICE
(LI)	=	PROVIDE ELECTRONIC LONG AND INSTANTANEOUS ADJUSTABILITY
(LS)	=	PROVIDE ELECTRONIC LONG, SHORT, AND INSTANTANEOUS ADJUSTABILITY
(LSIA)	=	PROVIDE ELECTRONIC LONG, SHORT, INSTANTANEOUS, AND GROUND-FAULT ALARM ADJUSTABILITY
(LSIG)	=	PROVIDE ELECTRONIC LONG, SHORT, INSTANTANEOUS, AND GROUND-FAULT ADJUSTABILITY
(LT)	=	PROVIDE LOCK-OUT/TAG-OUT DEVICE
(ST)	=	SEE THE SINGLE LINE DIAGRAM / SCHEDULE FOR WIRE SIZE AND VOLTAGE DROP
(S)	=	PROVIDE SHUNT TRIP CIRCUIT BREAKER

A. PROVIDE HACH RATED BREAKERS ON ALL MOTOR LOADS.  
B. ALL CONDUCTORS SHOWN ARE COPPER.  
C. ALL VOLTAGE DROP CALCULATIONS SHALL BE BASED ON COMPENSATED WIRE SIZES ARE BASED ON RIGHT ANGLE CIRCUIT LENGTHS.  
D. ACTUAL VOLTAGE DROP MAY VARY BASED ON INSTALLED WIRE LENGTH.  
E. VOLTAGE DROP CALCULATIONS AND WIRE SIZES SHOWN IN THE PANEL SCHEDULES ARE FOR HOMERUN CONDUCTORS ONLY. FOR CIRCUITS WITH MORE THAN 1 DEVICE, THESE SIZES ASSUME THE CONDUCTORS DOWNSTREAM OF THE FIRST DEVICE WILL BE THE SAME SIZE AS THE FIRST DEVICE. IF THIS IS NOT THE CASE, IT HAS BEEN INDICATED ON THE DRAWINGS. VOLTAGE DROP TO THE FARTHEST DEVICE HAS BEEN CALCULATED TO NEVER EXCEED 5%.  
F. HEAVY DUTY LOADS CALCULATED AT 100% OF FIRST 10KVA, 50% OF REMANDER. MOTOR LOADS CALCULATED AT 125% OF THE LARGEST MOTOR, 100% OF ALL OTHER MOTORS.











OWNERSHIP OF INSTRUMENTS OF SERVICE  
The Consultant shall retain the property of the Consultant. The Consultant shall retain all common law, statutory and other reserved rights, including, without limitation, the copyright thereto.

operational. Verify zone control requirements in field prior to rough-in. Provide 100-hour carryover.

Occupancy Sensors, Dual Technology Wall Switches: Provide Wattstopper DW-100 wall switch (or equivalent) and configure as manual on, auto off (vacancy sensor) unless otherwise specified on drawings. Provide with time delay as specified on drawings. If no time delay is specified, program to 10 minutes.

Occupancy Sensors, Dual Technology Ceiling Sensors: Provide Wattstopper DT-300 ceiling mounted occupancy sensor (or equivalent). Provide with time delay as specified on drawings. If no time delay is specified, program to 20 minutes. Adjust sensitivity based on field conditions and occupancy of room to provide 100% coverage without nuisance tripping. Provide Wattstopper BZ-150 universal voltage pack(s) as required to properly power all occupancy sensors and provide switching per the design intent. In areas where multiple occupancy sensors control a single zone together, interlock occupancy sensors/power packs per manufacturer instructions to meet control intent.

26 24 16.00 – PANELBOARDS

Submittal Requirements

Product Data

For each provide bus configuration, current ratings, voltage ratings, SCCR Ratings, overcurrent protective device(s), surge suppression device(s), accessory, and components indicated. Include dimensions and manufacturers' technical data on features, performance, electrical characteristics, ratings, accessories, and finishes.

Subject to compliance with requirements, provide panelboard products of one of the following (for each type and rating of panelboard and enclosure): Square D Company, GE/ABB, Siemens, Eaton/Cutler-Hammer.

Panelboards shall bear UL labels for their specific applications. Panelboards shall be suitable for service voltage with number of branch circuits of capacity scheduled. Refer to the drawings for bussing material. Where copper is specified provide silver or tin plating. Unless otherwise indicated, panelboards and sections thereof, if any, shall have main-lugs-only of capacity equal to, or greater than, the rating or setting of the over the current protective device next back on the line. All circuit breaker panelboard bus assemblies shall be of the distributed (sequence) bussing type throughout, so that any 2 adjacent single pole breakers and/or spaces shall be replaceable by a 2-pole internal common trip breaker, and any 3 adjacent single pole breakers and/or spaces shall be replaceable by a 3 pole internal common trip breaker, 15 amp through 70 amp inclusive, without disturbing any other breaker. All panelboards shall be UL listed and labeled for use as service entrance equipment where being used as such.

208Y/120V panelboards shall be equal to Square D NQ with bolt-on branch breakers

All branch circuit breakers shall be full ambient compensated thermal magnetic molded case with quick-make and quick-break action and positive handle trip indication, both on manual and on automatic operation. Breakers shall be of the over-the-center toggle operating type with the handle going to a position between "on" and "off" to indicate automatic tripping. All breakers shall be bolt-on type.

All circuit breakers shall be full size. "Tandem" or "split" breakers shall not be permitted. All multi-pole breakers shall have internal common trip with all load side box lugs of one breaker in the same gutter. All circuit breakers shall have sealed cases to prevent tampering. All 15 and 20 ampere branch circuit breakers shall be UL Listed as SWD (switching duty). All 15-70 ampere branch circuit breakers shall be HACR Type. All GFCI circuit breakers shall be UL Class A with maximum threshold of 5 mA. All branch circuit breakers serving all ballasted (fluorescent/HID) lighting loads shall be HID rated.

Provide all electrical distribution related equipment with appropriately braced bussing and properly rated breakers, fuses, etc. for the available fault currents. In existing buildings where fault current values are not indicated on drawings, coordinate with existing "upstream" distribution equipment provide equipment SCCR to meet or exceed same.

Provide barriers around any energized phase busbar or terminal supplied from a feeder tap, transformer, or service entrance conductors.

Fill out panelboard's circuit directory card upon completion of installation work. Directories shall be neatly typewritten. All panelboard directories shall include the actual room names/numbers that are selected for interior signage/designation.

All recessed panelboards shall be provided with a minimum of three 1-1/4" empty conduits terminated to a single 12" X 12" X 6" deep junction box above accessible ceiling.

26 27 26.00 - WIRING DEVICES

Submittal Requirements

Product Data

For each type include electrical characteristics, configurations, ratings, markings, colors, etc.

Unless specifically indicated otherwise, or directed otherwise in field, coordinate finishes for wiring devices with architect and owner prior to ordering. Where applicable, devices on different branches of power shall be a different color.

Provide grounded ("neutral") conductors in all wall switch, dimmer and other lighting control outlet boxes, even if not immediately utilized.

Provide wall plates with engraved legends where indicated on drawings and/or where required per 26 05 53.00 -

IDENTIFICATION FOR ELECTRICAL SYSTEMS Section. All device wall plates shall be standard size; "midway", "oversized" ("jumbo") or "extra deep" wall plates shall not be acceptable. Construct with metal screws for securing plates to devices; screw heads colored to match finish of plates. Except where/if indicated otherwise on drawings, wall plates in finished areas shall be commercial specification grade, satin finish stainless steel, with beveled edges, equal to Leviton Type 430 series. Wall plates in unfinished areas shall be galvanized steel unless otherwise noted. Refer to architectural finish schedules and owner representative for additional information.

Wall-Box Type Lighting Controls: Refer to specification 260923.00 – Local Lighting Controls for types not listed here.

Toggle Switches: Provide toggle switches equal to Leviton #122x-2 series in configurations shown on the drawings. Provide switches that are flush, self-grounding with green ground screw, back and side wired, and specification grade. 120/277V, 20A, AC quiet type.

Receptacles:

Special purpose receptacles shall be of the size, type and manufacturer as indicated on the plans or as determined in field.

Weather Resistant (WR) GFCI Receptacles: Provide for all receptacles installed in damp or wet locations. Any receptacle shown on the drawings with "WP/GFCI" next to it denoting exterior cover shall be installed with a WR GFCI receptacle. Provide duplex weather resistant receptacles equal to Leviton # W7899 series. Provide Weather-Resistant Receptacles with UL "WR" marking. For receptacle circuits protected with 15A breakers, provide NEMA 5-15R equivalents.

Self-Grounding Commercial Specification grade, Duplex Receptacles, Ground-Fault Circuit Interrupters: Feed-thru type, capable of protecting connected downstream receptacles on single circuit, grounding type UL-rated 943, Class A, Group 1, specification grade, 20-amperes rating (device and feed-thru), 125-volts, 60 Hz; with solid-state ground-fault sensing and signaling (maximum threshold of 5mA at 0.025 seconds maximum); equip with 20-ampere plug configuration, NEMA 5-20R. Provide ground fault circuit interrupter duplex receptacles equal to Leviton #8898 series. For receptacle circuits protected with 15A breakers, provide NEMA 5-15R equivalents. Where GFCI protected receptacles are shown on drawings, provide a separate GFCI receptacle for each one shown. Do not feed downstream receptacles from load-side (GFCI-protected) terminals of upstream receptacles.

26 51 00.00 - LIGHTING

Submittal Requirements

Product Data

For each type include detailed product information, light source, color temperature, color rendering index, lumen outputs, life, driver manufacturer, model and type, ceiling connection details, integral controls as applicable, drawings of custom fixtures, components, wiring diagrams, warranty, etc. Arrange luminaire submittals in booklet form with separate sheets for each luminaire, assembled by luminaire "type" in alphabetical order.

All recessed luminaires shall be equipped with necessary plaster frames and surface trim.

All junction boxes and serviceable components for recessed luminaires shall be readily accessible for service or replacement from below the ceiling, without removing any ceiling components (other than tiles).

All luminaires utilized for emergency and/or egress lighting shall be connected ahead of switching. All drivers of the same type shall be of the same manufacturer and catalog number. All LED modules of the same type shall be of the same manufacturer and catalog number.

Light Emitting Diode (LED) Systems: Provide factory installed LED modules that are specifically designed for, and matched and mated to, the respective luminaire in which they are used. Provide LED modules that can easily be replaced in the field and are readily accessible for replacement. Provide color temperature as indicated in Luminaire Schedule. Provide factory installed driver(s) for the LED source utilized that are specifically coordinated to the LED source and luminaire in which they are used. Provide driver(s) having specific operating characteristics defined in the Luminaire Schedule. Provide driver(s) that can easily be replaced in the field and are readily accessible for replacement. Provide specification sheet for the specific driver as part of the Luminaire Submittal. Provide Total Harmonic Distortion (THD) rating of less than 20 percent. Provide factory-installed integral filtering system to ensure THD does not exceed 20 percent regardless of quantities and/or mixes with other manufactured LED systems.

All surface and recessed ceiling luminaires installed on grid or tile ceilings shall be installed to agree with module of ceiling either displacing a tile, or unit on center of tile, or centered on grid lines.

Provide luminaires and/or luminaire outlet boxes with hangers to properly support luminaire weight. All luminaires installed in or on suspended ceiling systems shall be anchored directly to the building structural system above. Such anchoring shall be independent of the ceiling support system. All luminaires shall be installed plumb and level. Support surface mounted luminaires greater than 2 feet in length at a point in addition to the outlet box luminaire stud.

Occupancy Adjustments: When requested within 12 months of date of Substantial Completion, provide on-site assistance in adjusting aimable luminaires to suit actual occupied conditions. Provide up to two visits to Project during other-than-normal occupancy hours for this

purpose. Some of this work may be required after dark. Adjust aimable luminaires in the presence of Owner's Representative and Design Professionals.



KOHR'S LONNEMANN HEIL ENGINEERS, INC.  
MECHANICAL/ELECTRICAL ENGINEERS  
WWW.KLHENGERS.COM


1538 ALEXANDRIA PIKE, SUITE 11  
FT. THOMAS, KENTUCKY 41075  
800-354-9783  
859-442-8050  
859-442-8058 FAX  
LEXINGTON, KENTUCKY  
LOUISVILLE, KENTUCKY  
COLUMBUS, OHIO  
KLH JOB #: 27551



rgla solutions, inc.


5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com

NO.	REVISIONS:	DATE:
	BID, LL REVIEW, AND PERMIT	06.18.25



retail architecture

5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com



6/18/2025

SEAL:

THE ABOVE DRAWINGS AND SPECIFICATIONS AND ALL DECISIONS AND ARRANGEMENTS REPRESENTED THEREBY ARE AND SHALL REMAIN THE PROPERTY OF THIS OFFICE AND NO PART THEREOF SHALL BE COPIED, DISCLOSED TO OTHERS OR USED IN THE CONNECTION WITH ANY WORK OR PROJECT OTHER THAN THE SPECIFIC PROJECT FOR WHICH THEY HAVE BEEN PREPARED AND USED. WITHOUT THE WRITTEN CONSENT OF THIS OFFICE, VISUAL CONTACT WITH THESE DRAWINGS OR SPECIFICATIONS SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS. WRITTEN INQUIRIES ON THESE DRAWINGS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY DISCREPANCIES PRIOR TO THE BEGINNING AND CONCLUDING OF THE WORK. SHOP DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE PROCEEDING WITH FABRICATION.  
© 2024 RGLA SOLUTIONS, INC.  
© 2024 ROBERT G. LYON & ASSOCIATES, INC.

carhartt  
SUMMIT WOODS CROSSING  
1744 NW CHIPMAN ROAD  
LEE'S SUMMIT, MO 64081

ELECTRICAL  
SPECIFICATIONS

DRAWN BY
DJR
CHECKED BY
MPR
JOB NUMBER
25303
SHEET NAME
E-501



[illegible]

**associates, inc.**  
retail architecture

5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
[www.rgja.com](http://www.rgja.com)

STATE OF MISSOURI  
ROBERT A. LONNEMANN  
NUMBER  
PE-2003006449  
PROFESSIONAL ENGINEER

THE ABOVE DRAWINGS AND SPECIFICATIONS AND IDEAS, DESIGNS AND ARRANGEMENTS REPRESENTED THEREIN ARE AND SHALL REMAIN THE PROPERTY OF THIS OFFICE, AND NO PART THEREOF SHALL BE COPIED, DISCLOSED TO OTHERS OR USED IN THE CONNECTION WITH ANY WORK OR PROJECT OTHER THAN THE SPECIFIC PROJECT FOR WHICH THE DRAWINGS WERE PREPARED AND DEVELOPED WITHOUT THE WRITTEN CONSENT OF THIS OFFICE. VISUAL CONTACT WITH THESE DRAWINGS OR SPECIFICATIONS SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THE DRAWINGS. WRITTEN DIMENSIONS ON THESE DRAWINGS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MAY BE NOTIFIED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS. SHOP DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR APPROVAL, BEFORE ANY ORDERING OR MANUFACTURING.

© 2024 ROLTA SOLUTIONS, INC.  
© 2024 ROBERT G. LYON & ASSOCIATES, INC.

**carhartt**  
SUMMIT WOODS CROSSING  
1744 NW CHIPMAN ROAD  
LEE'S SUMMIT, MO 64081

MECHANICAL COVER  
SHEET

DRAWN BY

CHECKED BY  
A.IK

ICB NUMBER

25303
























SHEET NAME

M-001

## STANDARD HVAC ABBREVIATIONS

AV	AUTOMATIC AIR VENT	HA	HEAD	RO	REVERSE OSMOSIS
ACCESS	ACCESSORIES	HOA	HAND/OFF/AUTOMATIC	RPM	REVOLUTIONS PER MINUTE
AD	ACCESS DOOR	HP	HORSEPOWER	RS	REFRIGERANT SUCTION
AF	ABOVE FINISHED FLOOR	HPR	HIGH PRESSURE RETURN	SA	SUPPLY AIR
AMP	AMPERE	HST	(STEAM CONDENSATE)	SAT	SUPPLY AIR TEMPERATURE
AP	ACCESS PANEL	HSTAT	HUMIDISTAT	SC	SHADING COEFFICIENT
APD	AIR PRESSURE DROP	HTG	HEATING	SCD	SMOKE CONTROL DAMPER
AR	AIR CONDITIONING AND REFRIGERATION INSTITUTE	HTR	HEATING HOT WATER RETURN	SD	SMOKE DETECTOR
ASME	AMERICAN SOCIETY OF MECHANICAL ENGINEERS	HWS	HEATING HOT WATER SUPPLY	SENS	SENSIBLE HEAT
BA	BUILDING AUTOMATION SYSTEM	HVZ	HERTZ	SP	STATIC PRESSURE
BD	BACKDRAFT DAMPER	IO	INPUT/OUTPUT	TAB	TESTING, ADJUSTING, BALANCING
BHD	BRAKE HORSEPOWER	IAQ	INDOOR AIR QUALITY	TDH	TOTAL DYNAMIC HEAD
BTU	BRITISH THERMAL UNIT	IN HG	INCHES OF MERCURY	TDS	TOTAL DISSOLVED SOLIDS
BTUH	BRITISH THERMAL UNIT PER HOUR	IN WC	INCH WATER COLUMN	TSP	TOTAL STATIC PRESSURE
CD	CILING DIFFUSER	IN WG	INCH WATER GAUGE	TSSTAT	THERMOSTAT
CFM	CUBIC FEET PER HOUR	IP	INTERLOCKED PART LOAD VALUE	UL	UNDERWRITERS LABORATORY
CFM	CUBIC FEET PER MINUTE	IPST	INSTALLED	VAV	VARIABLE AIR VOLUME
CHWR	CHILLED WATER RETURN	KW	KILOWATT	VFD	VARIABLE FREQUENCY DRIVE
CHWS	CHILLED WATER SUPPLY	KWH	KILOWATT HOUR	WG	WET-BULB (TEMPERATURE)
CL	CAST IRON	LA	LEAVING AIR TEMPERATURE	W	WATER GAGE
CLG	COOLING	LBS/HR	POUNDS PER HOUR	WPD	WATER SIDE PRESSURE DROP
CO	CARBON MONOXIDE	LF	LINEAR FOOT (FEET)	WIRE	WIRED
CO2	CARBON DIOXIDE	LFR	LOW PRESSURE RETURN		
COP	COEFFICIENT OF PERFORMANCE		(STEAM CONDENSATE)		
CV	CONSTANT VOLUME	LPS	LOW PRESSURE STEAM		
CWR	CONDENSER WATER RETURN	LWT	LEAVING WATER TEMPERATURE		
CWS	CONDENSER WATER SUPPLY	MAX	MAXIMUM		
DB	DECIBELS	MBH	1000 BTUH		
DB	DRY-BULB TEMPERATURE	MCA	MINIMUM BRANCH CIRCUIT AMPACITY		
DC	DISCONNECT	MERV	MINIMUM EFFICIENCY REPORTING VALUE		
DDC	DIGITAL DIRECT CONTROLS	MIN	MINIMUM		
DEG	DEGREE DELTA (CHANGE IN TEMPERATURE)	MOD	MOTOR OPERATED DAMPER		
DI	DIAMETER	MPR	MEDIUM PRESSURE RETURN		
DIW	DEIONIZED WATER		(STEAM CONDENSATE)		
DP	DEW POINT TEMPERATURE	MPS	MEDIUM PRESSURE STEAM		
DX	DIRECT EXPANSION	MRI	MAGNETIC RESONANCE IMAGING		
EA	EXHAUST AIR	MVD	MANUAL VOLUME DAMPER		
EAT	ENTERING AIR TEMPERATURE	NA	NOT APPLICABLE		
EF	ENERGY EFFICIENCY RATIO	NC	NOISE CRITERIA		
EG	EXHAUST GRILLE	NC	NORMALLY CLOSED		
EMERG	EMERGENCY POWER	NO	NORMALLY OPEN		
ESP	EXTERNAL STATIC PRESSURE	NTS	NOT TO SCALE		
EW	ENTERING WATER TEMPERATURE	OA	OUTSIDE AIR		
EX	EXISTING	OC	OVER CURRENT PROTECTION		
F	FAHRENHEIT	PD	PRESSURE DROP		
F&T	FLOAT AND THERMOSTATIC	PPM	PARTS PER MILLION		
FA	FREE AREA	PRS	PRESSURE REGULATING (VALVE) STATION		
FD	FIRE DAMPER	PRV	PRESSURE REGULATING VALVE		
FMA	FULL LOAD AMPERES	PSI	POUNDS PER SQUARE INCH		
FLM	FEET PER MINUTE	PSIA	POUNDS PER SQUARE INCH - ABSOLUTE		
FS	FEET PER SECOND	PSIG	POUNDS PER SQUARE INCH - GAGE		
FT	FEET	RA	RETURN AIR		
FURN	FURNISHED	RET	RETURN AIR TEMPERATURE		
GA	GAUGE	REL	RELATIVE HUMIDITY		
GAL	GALLONS	RL	REFRIGERANT LIQUID LINE		
GPM	GALLONS PER MINUTE	RLA	RUN LOAD AMPERE		

## MECHANICAL LEGEND

SYMBOL		DESCRIPTION	
<b>PLAN-VIEW LINE TYPES</b>			
		WORK SHOWN FADED INDICATES EXISTING WORK TO REMAIN OR NEW WORK BY OTHERS AS APPLICABLE	
		WORK SHOWN BOLD-CONTINUOUS INDICATES NEW WORK	
<b>MECHANICAL AIR DEVICES</b>			
		SUPPLY REGISTER	
		CEILING DIFFUSER	
<b>MECHANICAL DUCTWORK</b>			
		SUPPLY DUCT WITH ELBOW TURNED UP	
		SUPPLY DUCT WITH ELBOW TURNED DOWN	
		RETURN DUCT WITH ELBOW TURNED UP	
		RETURN DUCT WITH ELBOW TURNED DOWN	
		EXHAUST DUCT WITH ELBOW TURNED UP	
		EXHAUST DUCT WITH ELBOW TURNED DOWN	
		SUPPLY DUCT	
		RETURN DUCT	
		EXHAUST DUCT	
		OUTSIDE AIR DUCT	
		BRANCH TAKEOFF	
		REDUCER, CONCENTRIC	
		REDUCER, NONCONCENTRIC	
<b>MECHANICAL DUCTWORK ACCESSORIES</b>			
		DUCT WITH MANUAL VOLUME DAMPER	
		DUCT MOUNTED SMOKE DETECTOR (HARD WIRE INTERLOCK TO FAN MOTOR BY E.C.) FURNISHED BY E.C., INSTALLED BY M.C.	
<b>MECHANICAL STATS &amp; SENSORS</b>			
		TEMPERATURE SENSOR	
		LOW VOLTAGE THERMOSTAT	
		LINE VOLTAGE THERMOSTAT	
<b>MECHANICAL MISCELLANEOUS</b>			
		CONNECT TO EXISTING (FIELD VERIFY EXISTING UTILITY SERVICE TYPE, PRIOR TO MAKING CONNECTION)	



### HVAC DEMOLITION GENERAL NOTES

- A. REMOVE EXISTING DUCTWORK, CONTROLS, AND MISCELLANEOUS HVAC EQUIPMENT NOT INTENDED FOR REUSE. FIELD VERIFY THE EXACT SCOPE PRIOR TO BID. COORDINATE ALL DEMOLITION WORK WITH THE LANDLORD AND GENERAL CONTRACTOR.

### FIELD VERIFY ALL CONDITIONS

DESIGN DRAWINGS ARE SCHEMATIC. THIS CONTRACTOR SHALL VISIT THE SITE PRIOR TO BIDDING OR AWARD OF CONTRACT TO INSPECT EXISTING FIELD CONDITIONS. THIS CONTRACT SHALL INCLUDE ALL LABOR AND MATERIALS NECESSARY FOR FIELD MODIFICATIONS DUE TO EXISTING CONDITIONS.

THE CONTRACTOR SHALL CONTACT THE ARCHITECT, ENGINEER OR OWNER PRIOR TO BIDDING FOR INTERPRETATIONS AND CLARIFICATIONS OF THE DESIGN AND INCLUDE IN HIS BID ALL COSTS TO MEET THE DESIGN INTENT. CLARIFICATIONS MADE BY THE ARCHITECT, ENGINEER OR OWNER AFTER BIDDING WILL BE FINAL AND SHALL BE IMPLEMENTED AT CONTRACTORS COST.

BIDDING CONTRACTORS SHALL HAVE A WORKING KNOWLEDGE OF LOCAL CODES AND ORDINANCES AND SHALL INCLUDE IN THEIR BIDS THE COSTS FOR ALL WORK INSTALLED IN STRICT ACCORDANCE WITH GOVERNING CODES, THE PLANS AND SPECIFICATIONS NOT WITHSTANDING, THE CONTRACTOR SHALL ALERT ARCHITECT, ENGINEER OR OWNER OF ANY APPARENT DISCREPANCIES BETWEEN GOVERNING CODES AND DESIGN INTENT.

### KEYED NOTES

- M01 PROVIDE NEW PROGRAMMABLE THERMOSTATS IN BACK OFFICE AREA WITH NEW REMOTE SENSORS RELOCATED TO LOCATIONS INDICATED ON PLANS. COORDINATE EXACT LOCATION WITH ARCHITECT AND SALES RACKS PRIOR TO INSTALLATION. REWIRE TO ROOFTOP UNIT PER MANUFACTURER'S PRINTED INSTRUCTIONS.
- M02 PROVIDE TRANSFER OPENING FULLY ABOVE 13'-0" IN WALL. EQUIVALENT SIZE AS NOTED IN SCHEDULES.
- M03 PROVIDE NEW CEILING MOUNTED EXHAUST FAN WITH INTEGRAL BACKDRAFT DAMPER AS SCHEDULED. BALANCE TO THE SCHEDULED AIRFLOW. EXTEND EXHAUST THROUGH ROOF AND TERMINATE WITH VENT CAP. MAINTAIN A MINIMUM OF 10'-0" FROM ANY BUILDING INTAKE. LANDLORD APPROVED ROOFING CONTRACTOR TO PERFORM ALL ROOF WORK AT THE GENERAL CONTRACTOR'S EXPENSE.
- M04 PROVIDE AND BALANCE NEW ROOFTOP UNIT AS SCHEDULED. PROVIDE NEW MANUFACTURER'S ROOF CURB. MAINTAIN ALL CODE AND MANUFACTURER REQUIRED CLEARANCES. OUTSIDE AIR INTAKE SHALL BE LOCATED A MINIMUM OF 10'-0" FROM ANY FLUE OR BUILDING EXHAUST. ALL ROOF WORK TO BE DONE BY A LANDLORD APPROVED ROOFING CONTRACTOR AT THE GENERAL CONTRACTOR'S EXPENSE.
- M05 PROVIDE PVC CONDENSATE TAILPIECE PER DETAIL AND TERMINATE AT ROOF.
- M06 COVER OPEN END OF RETURN DUCT WITH 1" MESH HARDWARE CLOTH IN A REMOVABLE METAL FRAME AND ELBOW UP FOR SOUND ATTENUATION.
- M07 PROVIDE NEW WALL MOUNTED, ELECTRIC HEAT AIR CURTAIN AT 12'-0" A.F.F.. INSTALL PER MANUFACTURER'S PUBLISHED INSTRUCTIONS. AIR CURTAIN SHALL INCLUDE MANUAL OVERRIDE OUT OFF SWITCH, INTERLOCK WITH DOOR SWITCH AND PROVIDE LINE VOLTAGE THERMOSTAT WITH TIME DELAY RELAY.
- M08 EXISTING ROOFTOP UNIT TO REMAIN. BALANCE TO THE SCHEDULED AIRFLOW. CLEAN AND VERIFY PROPER OPERATION; CLEAN COOLING, HEATING COILS. RECHARGE REFRIGERANT, REPLACE BELT, DRIVE, AND MOTOR AS REQUIRED, REPLACE FILTERS. CHECK COMPRESSOR AND FANS, REPLACE/REPAIR AS REQUIRED. PROVIDE OWNER WITH RECONDITIONING REPORT PRIOR TO TURNOVER. FIELD VERIFY EXACT LOCATION AND ORIENTATION PRIOR TO BID.



KOHR'S LONNEMANN HEIL ENGINEERS, INC.  
MECHANICAL/ELECTRICAL ENGINEERS  
WWW.KLHENGERS.COM

1538 ALEXANDRIA PIKE, SUITE 11  
FT. THOMAS, KENTUCKY 41075  
800-354-9783  
859-442-8050  
859-442-8058 FAX  
LEXINGTON, KENTUCKY  
LOUISVILLE, KENTUCKY  
COLUMBUS, OHIO  
KLH JOB #: 27551




rgla solutions, inc.

5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com

NO.	REVISIONS	DATE
BID, LL REVIEW, AND PERMIT		06.18.25

5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com

robert g. lyon + associates, inc.  
retail architecture



6/18/2025


THE ABOVE DRAWINGS AND SPECIFICATIONS AND SCALE, DESIGN AND ARRANGEMENTS REPRESENTED THEREBY ARE AND SHALL REMAIN THE PROPERTY OF THE OFFICE AND NO PART THEREOF SHALL BE COPIED, DISCLOSED TO OTHERS OR USED IN THE CONSTRUCTION OF ANY WORK OR PROJECT OTHER THAN THE SPECIFIC PROJECT FOR WHICH THEY HAVE BEEN PREPARED AND USED WITHOUT THE WRITTEN CONSENT OF THIS OFFICE. VISUAL CONTACT WITH THESE DRAWINGS OR SPECIFICATIONS SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS. WRITTEN DIMENSIONS ON THESE DRAWINGS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY DISCREPANCIES FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS. SHOP DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE PROCEEDING WITH FABRICATION.  
© 2024 RGLA SOLUTIONS, INC.  
© 2024 ROBERT G. LYON & ASSOCIATES, INC.



SUMMIT WOODS CROSSING  
1744 NW CHIPMAN ROAD  
LEE'S SUMMIT, MO 64081

MECHANICAL DUCTWORK PLAN

DRAWN BY	NMS
CHECKED BY	AJK
JOB NUMBER	25303
SHEET NAME	M-101



1 MECHANICAL PLAN - LEVEL 1  
1/4" = 1'-0"

OWNERSHIP OF INSTRUMENTS OF SERVICE  
The Consultant shall retain the ownership of the instruments of service, including, without limitation, the copyright therein.





COMcheck Software Version COMcheckWeb  
Mechanical Compliance Certificate

Project Information

Energy Code: 2018 IECC  
Project Title: Carhartt- Lee's Summit  
Location: Lees Summit, Missouri  
Climate Zone: 4a  
Project Type: Alteration

Construction Site: 1744 NW Chipman Road  
Lee's Summit, Missouri 64081  
Owner/Agent:  
Designer/Contractor: KLH Engineers  
153  
Fort Thomas, Kentucky 41075

Mechanical Systems List

QuantitySystem Type & Description

1 RTU-2: (Single Zone w/ PerimeterSystem):  
Heating: 1 each - Central Furnace, Gas, Capacity = 65 kBtu/h  
Proposed Efficiency = 81.00% Et, Required Efficiency: 80.00 % Et or 80% AFUE  
Cooling: 1 each - Packaged Terminal Unit, Capacity = 50 kBtu/h, Air-Cooled Condenser, Unknown Economizer  
Proposed Efficiency = 12.00 EER, Required Efficiency = 9.50 EER  
Proposed Part Load Efficiency = 0.00 , Required Part Load Efficiency = 0.00  
Fan System: RTU-2 -- Compliance (Motor nameplate HP and fan efficiency method) : Passes  
  
Fans:  
SUPPLY Supply, Constant Volume, 1470 CFM, 0.8 motor nameplate hp, 67.0 fan efficiency grade, 80.0 total fan efficiency, 70.0 design fan efficiency

Mechanical Compliance Statement

Compliance Statement: The proposed mechanical alteration project represented in this document is consistent with the building plans, specifications, and other calculations submitted with this permit application. The proposed mechanical systems have been designed to meet the 2018 IECC requirements in COMcheck Version COMcheckWeb and to comply with any applicable mandatory requirements listed in the Inspection Checklist.

Name - Title Signature Date

Project Title: Carhartt- Lee's Summit Report date: 06/10/25  
Data filename: Page 1 of 10

Section # & Req.ID	Plumbing Rough-In Inspection	Complies?	Comments/Assumptions
C404.5, C404.5.1, C404.5.2 [PL6] <sup>1</sup>	Heated water supply piping conforms to pipe length and volume requirements. Refer to section details.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	<b>Exception:</b> Requirement does not apply.
C404.6.3 [PL7] <sup>1</sup>	Pumps that circulate water between a heater and storage tank have controls that limit operation from startup to <= 5 minutes after end of heating cycle.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	<b>Exception:</b> Requirement does not apply.
C404.7 [PL8] <sup>1</sup>	Demand recirculation water systems have controls that start the pump upon receiving a signal from the action of a user of a fixture or appliance and limits the temperature of the water entering the cold-water piping to 104°F.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	<b>Exception:</b> Requirement does not apply.

Additional Comments/Assumptions:

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)  
Project Title: Carhartt- Lee's Summit Report date: 06/10/25  
Data filename: Page 4 of 10



COMcheck Software Version COMcheckWeb  
Inspection Checklist

Energy Code: 2018 IECC

Requirements: 100.0% were addressed directly in the COMcheck software

Text in the "Comments/Assumptions" column is provided by the user in the COMcheck Requirements screen. For each requirement, the user certifies that a code requirement will be met and how that is documented, or that an exception is being claimed. Where compliance is itemized in a separate table, a reference to that table is provided.

Section # & Req.ID	Plan Review	Complies?	Comments/Assumptions
C103.2 [PR2] <sup>1</sup>	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the mechanical systems and equipment and document where exceptions to the standard are claimed. Load calculations per acceptable engineering standards and handbooks.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.

Additional Comments/Assumptions:

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: Carhartt- Lee's Summit Report date: 06/10/25  
Data filename: Page 2 of 10

Section # & Req.ID	Mechanical Rough-In Inspection	Complies?	Comments/Assumptions
C402.2.6 [ME41] <sup>1</sup>	Thermally ineffective panel surfaces of sensible heating panels have insulation >= R-3.5.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.8.4 [ME142] <sup>1</sup>	Motors for fans that are not less than 1/12 hp and less than 1 hp are electronically commutated motors or have a minimum motor efficiency of 70 percent. These motors have the means to adjust motor speed.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	<b>Exception:</b> Requirement does not apply.
C403.8.5 [ME143] <sup>1</sup>	Each DX cooling system > 65 kBtu and chiller water/evaporative cooling system with fans > 1/4 hp are designed to vary the indoor fan airflow as a function of load and comply with detailed requirements of this section.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.12.1 [ME71] <sup>1</sup>	Systems that heat outside the building envelope are radiant heat systems controlled by an occupancy sensing device or timer switch.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	<b>Exception:</b> Requirement does not apply.
C403.2.3 [ME73] <sup>1</sup>	PTAC and PTHP with sleeves 16 in. by 42 in. labeled for replacement only as per Footnote b to Table C403.2.3(3).	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	
C403.5.5 [ME113] <sup>1</sup>	Fault detection and diagnostics installed with air-cooled unitary DX units having economizers.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.2 [ME59] <sup>1</sup>	Natural or mechanical ventilation is provided in accordance with International Mechanical Code Chapter 4, Mechanical ventilation has capability to reduce outdoor air supply to minimum per IMC Chapter 4.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	<b>Exception:</b> Requirement does not apply.
C403.7.1 [ME59] <sup>1</sup>	Demand control ventilation provided for spaces >500 ft2 and >25 people/1000 ft2 occupant density and served by systems with air side economizer, auto modulating outside air damper control, or design airflow >3,000 cfm.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	<b>Exception:</b> Requirement does not apply.
C403.7.2 [ME115] <sup>1</sup>	Enclosed parking garage ventilation has automatic contaminant detection and capacity to stage or modulate fans to 50% or less of design capacity.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	<b>Exception:</b> Requirement does not apply.
C403.7.6 [ME141] <sup>1</sup>	HVAC systems serving guestrooms in Group R-1 buildings with > 50 guestrooms; Each guestroom is provided with controls that automatically manage temperature setpoint and ventilation (see sections C403.7.6.1 and C403.7.6.2).	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	<b>Exception:</b> Requirement does not apply.
C403.7.4 [ME57] <sup>1</sup>	Exhaust air energy recovery on systems meeting Table C403.7.4(1) and C403.7.4(2).	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	<b>Exception:</b> Requirement does not apply.

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: Carhartt- Lee's Summit Report date: 06/10/25  
Data filename: Page 5 of 10

Section # & Req.ID	Footing / Foundation Inspection	Complies?	Comments/Assumptions
C403.12.2 C403.12.3 [FO9] <sup>1</sup>	Snow/ice melting system and freeze protection systems have sensors and controls configured to limit service for pavement temperature and outdoor temperature. future connection to controls.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	<b>Exception:</b> Requirement does not apply.

Additional Comments/Assumptions:

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: Carhartt- Lee's Summit Report date: 06/10/25  
Data filename: Page 3 of 10

Section # & Req.ID	Mechanical Rough-In Inspection	Complies?	Comments/Assumptions
C403.7.5 [ME116] <sup>1</sup>	Kitchen exhaust systems comply with replacement air and conditioned supply air limitations, and satisfy hood rating requirements and maximum exhaust rate criteria.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	<b>Exception:</b> Requirement does not apply.
C403.11.1 C403.11.2 [ME60] <sup>1</sup>	HVAC ducts and plenums insulated in accordance with C403.11.1 and constructed in accordance with C403.11.2, verification may need to occur during Foundation Inspection.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.5, C403.5.1, C403.5.2 [ME62] <sup>1</sup>	Air economizers provided where required, meet the requirements for design capacity, control signal, ventilation controls, high-limit shut-off integrated economizer control, and provide a means to relieve excess outside air during operation.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.5.3 3 [ME124] <sup>1</sup>	Air economizers automatically reduce outdoor air intake to the design minimum outdoor air quantity when outdoor air intake will not reduce cooling energy usage. See Table C403.5.3.3 for applicable device types and climate zones.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.5.3 4 [ME125] <sup>1</sup>	System capable of relieving excess outdoor air during air economizer operation to prevent overpressurizing the building. The relief air outlet located to avoid recirculation into the building.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.5.3 5 [ME126] <sup>1</sup>	Return, exhaust/relief and outdoor air dampers used in economizers have motorized dampers that automatically shut when not in use and meet maximum leakage rates. Reference section C403.7.7 for details.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.4.1 4 [ME63] <sup>1</sup>	Heating for vestibules and air curtains with integral heating include automatic controls that shut off the heating system when outdoor air temperatures > 45°F. Vestibule heating and cooling systems controlled by a thermostat in the vestibule with heating setpoint <= 60°F and cooling setpoint >= 80°F.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.3.3 [ME35] <sup>1</sup>	Hot gas bypass limited to: <=240 kBtu/h - 50% >240 kBtu/h - 25%	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.2 1 [ME53] <sup>1</sup>	Air outlets and zone terminal devices have means for air balancing.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.5, C403.5.1, C403.5.2 [ME123] <sup>1</sup>	Refrigerated display cases, walk-in coolers or walk-in freezers served by remote compressors and remote condensers not located in a condensing unit, have fan-powered condensers that comply with Sections C403.5.1 and refrigeration compressor systems that comply with C403.5.2.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	<b>Exception:</b> Requirement does not apply.

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: Carhartt- Lee's Summit Report date: 06/10/25  
Data filename: Page 6 of 10



KOHR'S LONNEMANN HEIL ENGINEERS, INC.  
MECHANICAL/ELECTRICAL ENGINEERS  
WWW.KLHENGERS.COM

1538 ALEXANDRIA PIKE, SUITE 11  
FT. THOMAS, KENTUCKY 41075  
800-354-9783  
859-442-8050  
859-442-8058 FAX  
LEXINGTON, KENTUCKY  
LOUISVILLE, KENTUCKY  
COLUMBUS, OHIO  
KLH JOB #: 27551




rgla solutions, inc.

5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com

NO.:	REVISIONS:	DATE:
	BID, LL REVIEW, AND PERMIT	06.18.25

robert g. lyon + associates, inc.  
retail architecture  
5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com



THE ABOVE DRAWINGS AND SPECIFICATIONS AND SCALE, DESIGN AND ARRANGEMENTS REPRESENTED THEREIN ARE AND SHALL REMAIN THE PROPERTY OF THE OFFICE AND NO PART THEREOF SHALL BE COPIED, DISCLOSED TO OTHERS OR USED BY THE CONTRACTOR WITH ANY WORK OR PROJECT OTHER THAN THE SPECIFIC PROJECT FOR WHICH THEY HAVE BEEN PREPARED AND USED WITHOUT THE WRITTEN CONSENT OF THIS OFFICE. VISUAL CONTACT WITH THESE DRAWINGS OR SPECIFICATIONS SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS. WRITTEN INDEMNITY ON THESE DRAWINGS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY DISCREPANCIES IMMEDIATELY. SHOP DETAILS MUST BE SHOWN BY THESE DRAWINGS. SHOP DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE PROCEEDING WITH FABRICATION.  
© 2024 RGLA SOLUTIONS, INC.  
© 2024 ROBERT G. LYON & ASSOCIATES, INC.

carhartt  
SUMMIT WOODS CROSSING  
1744 NW CHIPMAN ROAD  
LEE'S SUMMIT, MO 64081

ENERGY COMPLIANCE

DRAWN BY
NMS
CHECKED BY
AJK
JOB NUMBER
253003
SHEET NAME
M-401



OWNERSHIP OF INSTRUMENTS OF SERVICE  
The Consultant shall retain the ownership of the instruments of service. All data, notes, and other documents and instruments prepared by the Consultant as instruments of service shall remain the property of the Consultant. The Consultant shall retain all common law, statutory and other reserved rights, including, without limitation, the copyright therein.

Additional Comments/Assumptions:

1

High Impact (Tier 1)

2

Medium Impact (Tier 2)

3

Low Impact (Tier 3)

Project Title: Carhartt- Lee's SummitReport date: 06/10/25

Data filename:Page 7 of 10

Section # & Req.ID	Final Inspection	Complies?	Comments/Assumptions
C303.3, C408.2.5.3 [F18] <sup>1</sup>	Furnished O&M manuals for HVAC systems within 90 days of system acceptance.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.2 [F127] <sup>1</sup>	HVAC systems and equipment capacity does not exceed calculated loads.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.4.1 [F47] <sup>1</sup>	Heating and cooling to each zone is controlled by a thermostat control. Minimum one humidity control device per installed humidification/dehumidification system.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.4.1.2 [F138] <sup>1</sup>	Thermostatic controls have a 5 °F deadband.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.4.1.3 [F120] <sup>1</sup>	Temperature controls have setpoint overlap restrictions.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.4.2 [F139] <sup>1</sup>	Each zone equipped with setback controls using automatic time clock or programmable control system.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.4.2.1, C403.2.4.2.2 [F140] <sup>1</sup>	Automatic Controls: Setback to 55°F (heat) and 85°F (cool); 7-day clock, 2-hour occupant override, 10-hour backup	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C403.2.4.2.3 [F41] <sup>1</sup>	Systems include optimum start controls.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.1.1 [F157] <sup>1</sup>	Building operations and maintenance documents will be provided to the owner. Documents will cover manufacturers' information, specifications, programming procedures and means of illustrating to owner how building, equipment and systems are intended to be installed, maintained, and operated.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.1 [F128] <sup>1</sup>	Commissioning plan developed by registered design professional or approved agency.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.3.1 [F131] <sup>1</sup>	HVAC equipment has been tested to ensure proper operation.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.

1

High Impact (Tier 1)

2

Medium Impact (Tier 2)

3

Low Impact (Tier 3)

Project Title: Carhartt- Lee's SummitReport date: 06/10/25

Data filename:Page 9 of 10

Section # & Req.ID	Rough-In Electrical Inspection	Complies?	Comments/Assumptions
C405.6 [EL26] <sup>1</sup>	Low-voltage dry-type distribution electric transformers meet the minimum efficiency requirements of Table C405.6.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C405.7 [EL27] <sup>1</sup>	Electric motors meet the minimum efficiency requirements of Tables C405.7(1) through C405.7(4). Efficiency verified through certification under an approved certification program or the equipment efficiency ratings shall be provided by motor manufacturer (where certification programs do not exist).	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C405.8.2, C405.8.2.1 [EL28] <sup>1</sup>	Escalators and moving walks comply with ASME A17.1/CSA B44 and have automatic controls configured to reduce speed to the minimum permitted speed in accordance with ASME A17.1/CSA B44 or applicable local code when not conveying passengers.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	<b>Exception:</b> Requirement does not apply.
C405.9 [EL29] <sup>1</sup>	Total voltage drop across the combination of feeders and branch circuits <= 5%.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.

Additional Comments/Assumptions:

1

High Impact (Tier 1)

2

Medium Impact (Tier 2)

3

Low Impact (Tier 3)

Project Title: Carhartt- Lee's SummitReport date: 06/10/25

Data filename:Page 8 of 10

Section # & Req.ID	Final Inspection	Complies?	Comments/Assumptions
C408.2.3.2 [F10] <sup>1</sup>	HVAC control systems have been tested to ensure proper operation, calibration and adjustment of controls.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.3.3 [F132] <sup>1</sup>	Economizers have been tested to ensure proper operation.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.4 [F129] <sup>1</sup>	Preliminary commissioning report completed and certified by registered design professional or approved agency.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.5.1 [F17] <sup>1</sup>	Furnished HVAC as-built drawings submitted within 90 days of system acceptance.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.5.3 [F143] <sup>1</sup>	An air and/or hydronic system balancing report is provided for HVAC systems.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.
C408.2.5.4 [F130] <sup>1</sup>	Final commissioning report due to building owner within 90 days of receipt of certificate of occupancy.	<input type="checkbox"/> Complies <input type="checkbox"/> Does Not <input type="checkbox"/> Not Observable <input type="checkbox"/> Not Applicable	Requirement will be met.

Additional Comments/Assumptions:

1

High Impact (Tier 1)

2

Medium Impact (Tier 2)

3

Low Impact (Tier 3)

Project Title: Carhartt- Lee's SummitReport date: 06/10/25

Data filename:Page 10 of 10



KOHR'S LONNEMANN HEIL ENGINEERS, INC.  
MECHANICAL/ELECTRICAL ENGINEERS  
WWW.KLHENGERS.COM

1538 ALEXANDRIA PIKE, SUITE 11  
FT. THOMAS, KENTUCKY 41075  
800-354-9783  
859-442-8050  
859-442-8058 FAX


LEXINGTON, KENTUCKY  
LOUISVILLE, KENTUCKY  
COLUMBUS, OHIO  
KLH JOB #: 27551



rgla solutions, inc.

5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com

NO.:	REVISIONS:	DATE:
	BID, LL REVIEW, AND PERMIT	06.18.25



retail architecture

5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com



STATE OF MISSOURI  
ROBERT A. LONNEMANN  
NUMBER PE-200300849  
PROFESSIONAL ENGINEER  
6/18/2025  
SEAL:

THE ABOVE DRAWINGS AND SPECIFICATIONS AND SCALE DIMENSIONS AND ARRANGEMENTS REPRESENTED THEREBY ARE AND SHALL REMAIN THE PROPERTY OF THE OFFICE AND NO PART THEREOF SHALL BE COPIED, DISCLOSED TO OTHERS OR USED IN THE CONNECTION WITH ANY WORK OR PROJECT OTHER THAN THE SPECIFIC PROJECT FOR WHICH THEY HAVE BEEN PREPARED AND ISSUED WITHOUT THE WRITTEN CONSENT OF THIS OFFICE. VISUAL CONTACT WITH THESE DRAWINGS OR SPECIFICATIONS SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS. WRITTEN DIMENSIONS ON THESE DRAWINGS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY DISCREPANCIES FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS. SHOP DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE PROCEEDING WITH FABRICATION.  
© 2024 RGLA SOLUTIONS, INC.  
© 2024 ROBERT G. LYON & ASSOCIATES, INC.



SUMMIT WOODS CROSSING  
1744 NW CHIPMAN ROAD  
LEE'S SUMMIT, MO 64081

ENERGY COMPLIANCE

DRAWN BY

NMS

CHECKED BY

AJK

JOB NUMBER

25303

SHEET NAME

M-402



**SECTION 23 05 01.00 – COMMON REQUIREMENTS FOR HVAC**

General  
General Provisions of the Contract including General and Supplementary Conditions and General Requirements apply to work of this section.  
Scope

The base bid includes furnishing all materials, labor, tools, and equipment and the performance of all work required to install a complete heating and air conditioning system as outlined herein.  
Guarantee

The contractor shall provide a guarantee in written form stating that all work under this section shall be free of defective work, materials, or parts for a period of one year from the date of owner's final acceptance and shall repair, revise or replace at no cost to the owner any such defects occurring within the guarantee period. Contractor shall also state in written form that any items or occurrences arising during the guarantee period will be attended to in a timely manner and will in no case exceed four (4) working days from date of notification by owner.  
Quality Assurance

Provide a complete installation in conformance with the following standards.

AGA: American Gas Association  
ASHRAE: American Society of Heating, Refrigerating and Air Conditioning Engineers

NFPA: National Fire Protection Association  
SMACNA: Sheet Metal and Air Conditioning Contractors National Association

Statewide Building Code  
IMC: International Mechanical Code

Permits, Fees, Inspections, Laws and Regulations  
Permits and fees of every nature required in connection with this work shall be obtained and paid for by this contractor who shall also pay for all the installation fees and similar charges. Laws and regulations, which bear upon or affect the various branches of this work shall be complied with by this contractor and are hereby made a part of this contract. All work, which such laws require to be inspected, shall be submitted to the proper public official for inspection and a certificate of final approval must be furnished.

Work in Existing Spaces  
General: Care shall be taken when working in existing spaces so as not to damage existing walls and ceilings where work is being performed.

Ceilings: Where work is being performed above ceilings, and the architectural drawings do not indicate ceiling modifications by the general contractor, it shall be the responsibility of this contractor to remove and replace existing ceilings where work is being performed. In those instances, all repair and installation of new grid, ceiling panels, etc shall be the responsibility of this contractor. Match existing finishes.

Walls & Floors: It shall be the responsibility of this contractor to patch existing walls and floors and match existing finishes where work is being removed or installed and patching is being performed, unless noted otherwise on the architectural drawings.

Demolition  
Any Equipment to be demolished shall also include the demolition of any and all ductwork, piping etc serving or served by the equipment, all accessories, air devices, wiring, gas piping, venting, control wiring and power wiring associated with the equipment.

Demolition shall be coordinated with all trades. All materials shall be turned over to the owner or disposed at the owner's direction.

Contractor is responsible for reclaiming any refrigerant in association with the demolition in accordance with all local, state and federal regulations.  
Any roof or wall penetration shall be patched watertight to the satisfaction of the architect.

Tests and Adjustments  
No ducts, piping, fixtures or equipment shall be concealed or covered until they have been inspected and approved by the Architect and the inspector who shall be notified by the contractor when the work is ready for inspection.

Work shall be completely installed, tested and leak tight before inspection is required. All tests shall be repeated to the satisfaction of those making the inspection.  
Architectural coordination items

Cutting and Patching: Cut and drill all openings in walls and floors required for the installation. Secure approval of Engineer before cutting and drilling. Neatly patch all openings out.

Fire Caulking: Patching through fire rated walls and enclosures shall not diminish the rating of that wall or enclosure. Patch shall be equal to rockwool, firestop, caulk or approved "rated" patch.

Access Panels and Pathways: Furnish all access panels required for proper servicing of equipment. Provide access panels for all concealed valves, vents, controls, cleanout doors, and sprinkler devices required by NFPA. Provide access panels for all fire and/or fire & smoke dampers. Provide frames as required for finish. Furnish panels to General Contractor. Exact locations to be approved by the Architect. Minimum size to be 12" x 12", units to be 16 gauge steel, locking device shall be screwdriver cam locks.

project conditions  
Where new HVAC systems are required to be connected to existing HVAC systems, it is the contractor's responsibility to verify the location, size, pressure, condition, and they shall verify that the existing HVAC system is indeed the correct and appropriate HVAC system before any work is done. Provide all necessary camera scoping and dye testing as necessary. If there is any need for concern, if it is determined that the existing HVAC system is not a correct or appropriate HVAC system or not connected to a correct or appropriate HVAC system, if the condition of the existing HVAC system is not viable for re-use, or any other condition that would not allow the proper functioning of the new HVAC system, the contractor shall notify the engineer in writing immediately via RFI and wait for direction before proceeding.  
DELEGATED DESIGN

For equipment supports, this contractor shall retain a qualified professional engineer to provide support calculations of static and dynamic loading due to operating equipment weight. The signed and sealed calculations and details shall be submitted by the retained professional engineer.

MECHANICAL EQUIPMENT COMMON REQUIREMENTS

INSPECTION  
Examine areas and conditions under which mechanical equipment is to be installed. Do not proceed with work until unsatisfactory conditions have been corrected in manner acceptable to installer.

Uncrate equipment and inspect for damage. Verify that nameplate data corresponds with unit designation.

INSTALLATION  
General: Install mechanical equipment as indicated, and in accordance with manufacturer's installation instructions.

Location: Install each unit level/plumb and accurately in position indicated in relation to other work; and maintain sufficient clearance for normal service and maintenance, but in no case less than that recommended by manufacturer.

Coordinate with other trades to assure correct recess size for recessed units.  
Protect interior mechanical equipment with protective covers during balance of construction.

For ducted equipment, connect ductwork to units with flexible duct connections. Provide transitions to exactly match unit duct connection size. Provide 1" acoustic duct lining on return air side a minimum of 10' from fan. Provide trap at drain piping connection to unit sized per manufacturer's recommendations.

Access: Provide access space around and over mechanical equipment for service as indicated, but in no case less than that recommended by manufacturer or required by code in effect.

Access Panels: Furnish all access panels required for proper servicing of equipment. Provide access panels for all concealed valves, vents, controls and cleanout doors, and sprinkler devices required by NFPA. Provide frame as required for finish. Furnish panels to General Contractor. Exact locations to be approved by the Architect. Minimum size to be 12" x 12", units to be 16 gauge steel, locking device shall be screwdriver cam locks.

Rooftop mechanical equipment shall be installed a minimum of 10'-0" from any roof edge regardless of location indicated on plans, unless a screen wall or railing is installed per the local building code. See the architectural plans for coordination.

Roof Curbs: Furnish roof curbs to roofing installer for installation. Install and secure roof curb to roof structure, in accordance with National Roofing Contractor's Association (NRCA) installation recommendations and shop drawings. Install and secure units on curbs and coordinate roof penetrations and flashing. Install according to roofing manufacturer's recommendation and specifications.

Rooftop supports: Provide rooftop equipment rails for mechanical equipment located on the roof that spans two or more bar joists. Verify roof structure, mounting supports, and membrane installations are completed to the proper point to allow installation of roof mounted units.

ELECTRICAL COORDINATION ITEMS  
Electrical Wiring: Install electrical devices furnished by manufacturer but not specified to be factory-mounted. Furnish copy of manufacturer's wiring diagram submittal to Electrical Installer.

Verify that electrical wiring installation is in accordance with manufacturer's submittal and install in accordance with requirements of Division 26 sections. Do not proceed with equipment start-up until wiring installation is acceptable to equipment installer.  
Install electric heating terminal units including components in accordance with equipment manufacturer's written instructions, and with recognized industry practices, complying with applicable installation requirements of NEC and NECA's "Standard of Installation".

Tighten connectors and terminals, including screws and bolts, in accordance with equipment manufacturer's published torque tightening values for equipment connectors. Where manufacturer's torquing requirements are not indicated, tighten connectors and terminals to comply with tightening torques specified in UL Std 486A.

Grounding: Provide equipment grounding connections for electric heating terminals as indicated. Tighten connections to comply with tightening torque values specified in UL Std 486A to assure permanent and effective grounding.

FIELD QUALITY CONTROL  
Testing: After installation has been completed, test to demonstrate proper operation of mechanical equipment at performance requirements specified. When possible, field correct malfunctioning units, then retest to demonstrate compliance. Replace units, which cannot be satisfactorily corrected. Test controls and demonstrate compliance with requirements.

Cleaning: After construction is completed, including painting, clean unit exposed surfaces, vacuum clean coils and inside of cabinets. Clean factory-finished surfaces. Repair any marred or scratched surfaces with manufacturer's touch-up paint.

START-UP  
Provide the services of a factory-authorized service representative to start-up rooftop units, in accordance with manufacturer's written start-up instructions. Test controls and demonstrate compliance with requirements. Replace damaged or malfunctioning controls and equipment.

TRAINING OF OWNER'S PERSONNEL  
Provide services of manufacturer's technical representative for 1-half day to instruct Owner's personnel in operation and maintenance of units. Schedule training with Owner, provide at least 7-day notice to Contractor and Engineer of training date.

SPARE PARTS  
Provide one complete extra set of filters for each unit. Install new filters at completion of system and prior to testing, adjusting, and balancing work. Obtain receipt from Owner that new filters have been installed.

SEISMIC BRACING AND SUPPORT OF SYSTEMS AND COMPONENTS  
Seismic restraint designer shall coordinate all attachments with the structural engineer of record. Provide engineered stamped and signed drawings of seismic design.

Seismic restraint designer shall provide visual inspection after installation and approval installation of seismic design components.  
Design analysis shall include calculated dead loads, static seismic loads, and capacity of materials utilized for the connection of the equipment or systems to the structure.

Analysis shall detail anchoring methods, bolt diameter, and embedment depth.

All seismic restraint devices shall be designed to accept without failure the forces calculated per the applicable building code.

Friction from gravity loads shall not be considered resistance to seismic forces.

Fire protection systems shall meet the requirements of NFPA-13 and NFPA-14 for the building seismic requirements.

SEISMIC BRACING AND SUPPORT OF SYSTEMS AND COMPONENTS  
Seismic restraint designer shall coordinate all attachments with the structural engineer of record. Provide engineered stamped and signed drawings of seismic design.

Seismic restraint designer shall provide visual inspection after installation and approval installation of seismic design components.  
Design analysis shall include calculated dead loads, static seismic loads, and capacity of materials utilized for the connection of the equipment or systems to the structure.

Analysis shall detail anchoring methods, bolt diameter, and embedment depth.

All seismic restraint devices shall be designed to accept without failure the forces calculated per the applicable building code.

Friction from gravity loads shall not be considered resistance to seismic forces.

Fire protection systems shall meet the requirements of NFPA-13 and NFPA-14 for the building seismic requirements.

SEISMIC BRACING AND SUPPORT OF SYSTEMS AND COMPONENTS  
Seismic restraint designer shall coordinate all attachments with the structural engineer of record. Provide engineered stamped and signed drawings of seismic design.

Seismic restraint designer shall provide visual inspection after installation and approval installation of seismic design components.  
Design analysis shall include calculated dead loads, static seismic loads, and capacity of materials utilized for the connection of the equipment or systems to the structure.

Analysis shall detail anchoring methods, bolt diameter, and embedment depth.

All seismic restraint devices shall be designed to accept without failure the forces calculated per the applicable building code.

Friction from gravity loads shall not be considered resistance to seismic forces.

Fire protection systems shall meet the requirements of NFPA-13 and NFPA-14 for the building seismic requirements.

SEISMIC BRACING AND SUPPORT OF SYSTEMS AND COMPONENTS  
Seismic restraint designer shall coordinate all attachments with the structural engineer of record. Provide engineered stamped and signed drawings of seismic design.

Seismic restraint designer shall provide visual inspection after installation and approval installation of seismic design components.  
Design analysis shall include calculated dead loads, static seismic loads, and capacity of materials utilized for the connection of the equipment or systems to the structure.

Analysis shall detail anchoring methods, bolt diameter, and embedment depth.

All seismic restraint devices shall be designed to accept without failure the forces calculated per the applicable building code.

Include cover sheet / title page: The cover sheet shall include the information identified in the contract documents. It shall be included as the first page of each electronic and/or hardcopy document-based submittal. An editable and printable PDF form created with editable fields and specification compliant appearance is available from KLH upon request. It is also downloadable from the KLH website at [www.klhengrns.com](http://www.klhengrns.com).  
Include an index: The index shall enumerate the contents of the submittal.

Include checklists: Where checklists are included with the specifications, complete and include them within the appropriate submittal. Supply complete submittals: Complete submittals of each type are required. Partial submittals will be rejected. Where a section requires a product data submittal, all product data for that section shall be supplied together, at one time, as one complete submittal. Do not send half the product data as one submittal and the other half as a separate one. When resubmittal is required (e.g. Revise and Resubmit) the revised submittal shall be more complete, more accurate and more contract-compliant than its rejected predecessor. The submittal number (for each section and type) shall increment for each subsequent submittal (00 – Original submission, 01 – First Resubmission, 02 – Second Resubmission, etc.). Resubmittals shall include a copy of the reviewer's comments supplied with the prior submittal rejection and shall be amended with a description of the specific action taken to comply with the reviewer's comments. The absence of this on resubmittal is cause for rejection.

Name electronic files to match the submittal ID and cover sheet. The electronic file name of submittals shall match the submittal ID included on the submittals cover page. For example: The original/first product data submittal for Section 234116 would be labeled as "234116.00-PD-00"; the first resubmittal of same shall be labeled "234116.00-PD-01". The original/first shop drawings submittal file for the same section would be labeled "234116.00-SD-00"; the first resubmittal of same shall be labeled "234116.00-SD-01".

Use of Electronic Drawings from the Owner's Design Team  
Plan drawings for the Project were created with AutoCAD and Revit.

If expressly permitted by the Owner and the terms of the Contract, editable electronic versions of standard-scale, AutoCAD-based plan drawings may be made available for the creation of shop and as-built drawings.

Due to the proprietary nature of internal design systems, editable native-software versions of some drawings, including but not limited to system diagrams and details will not be made available in an editable form. In these cases, electronic versions of the drawings may be made available only in PDF, JPG or similar non-editable electronic form, at the sole discretion of the Design Professional.

The Request Drawings form can be accessed, filled out and submitted at the following internet address (scroll down to bottom of home page): <http://www.klhengrns.com>.

SEISMIC BRACING AND SUPPORT OF SYSTEMS AND COMPONENTS  
Seismic restraint designer shall coordinate all attachments with the structural engineer of record. Provide engineered stamped and signed drawings of seismic design.

Seismic restraint designer shall provide visual inspection after installation and approval installation of seismic design components.  
Design analysis shall include calculated dead loads, static seismic loads, and capacity of materials utilized for the connection of the equipment or systems to the structure.

Analysis shall detail anchoring methods, bolt diameter, and embedment depth.

All seismic restraint devices shall be designed to accept without failure the forces calculated per the applicable building code.

Friction from gravity loads shall not be considered resistance to seismic forces.

Fire protection systems shall meet the requirements of NFPA-13 and NFPA-14 for the building seismic requirements.

SEISMIC BRACING AND SUPPORT OF SYSTEMS AND COMPONENTS  
Seismic restraint designer shall coordinate all attachments with the structural engineer of record. Provide engineered stamped and signed drawings of seismic design.

Seismic restraint designer shall provide visual inspection after installation and approval installation of seismic design components.  
Design analysis shall include calculated dead loads, static seismic loads, and capacity of materials utilized for the connection of the equipment or systems to the structure.

Analysis shall detail anchoring methods, bolt diameter, and embedment depth.

All seismic restraint devices shall be designed to accept without failure the forces calculated per the applicable building code.

Friction from gravity loads shall not be considered resistance to seismic forces.

Fire protection systems shall meet the requirements of NFPA-13 and NFPA-14 for the building seismic requirements.

SEISMIC BRACING AND SUPPORT OF SYSTEMS AND COMPONENTS  
Seismic restraint designer shall coordinate all attachments with the structural engineer of record. Provide engineered stamped and signed drawings of seismic design.

Seismic restraint designer shall provide visual inspection after installation and approval installation of seismic design components.  
Design analysis shall include calculated dead loads, static seismic loads, and capacity of materials utilized for the connection of the equipment or systems to the structure.

Analysis shall detail anchoring methods, bolt diameter, and embedment depth.

All seismic restraint devices shall be designed to accept without failure the forces calculated per the applicable building code.

Friction from gravity loads shall not be considered resistance to seismic forces.

Fire protection systems shall meet the requirements of NFPA-13 and NFPA-14 for the building seismic requirements.

SEISMIC BRACING AND SUPPORT OF SYSTEMS AND COMPONENTS  
Seismic restraint designer shall coordinate all attachments with the structural engineer of record. Provide engineered stamped and signed drawings of seismic design.

Seismic restraint designer shall provide visual inspection after installation and approval installation of seismic design components.  
Design analysis shall include calculated dead loads, static seismic loads, and capacity of materials utilized for the connection of the equipment or systems to the structure.

Analysis shall detail anchoring methods, bolt diameter, and embedment depth.

All seismic restraint devices shall be designed to accept without failure the forces calculated per the applicable building code.

Friction from gravity loads shall not be considered resistance to seismic forces.

Fire protection systems shall meet the requirements of NFPA-13 and NFPA-14 for the building seismic requirements.

SEISMIC BRACING AND SUPPORT OF SYSTEMS AND COMPONENTS  
Seismic restraint designer shall coordinate all attachments with the structural engineer of record. Provide engineered stamped and signed drawings of seismic design.

Seismic restraint designer shall provide visual inspection after installation and approval installation of seismic design components.  
Design analysis shall include calculated dead loads, static seismic loads, and capacity of materials utilized for the connection of the equipment or systems to the structure.

Analysis shall detail anchoring methods, bolt diameter, and embedment depth.

All seismic restraint devices shall be designed to accept without failure the forces calculated per the applicable building code.

Friction from gravity loads shall not be considered resistance to seismic forces.

Fire protection systems shall meet the requirements of NFPA-13 and NFPA-14 for the building seismic requirements.

SEISMIC BRACING AND SUPPORT OF SYSTEMS AND COMPONENTS  
Seismic restraint designer shall coordinate all attachments with the structural engineer of record. Provide engineered stamped and signed drawings of seismic design.

Seismic restraint designer shall provide visual inspection after installation and approval installation of seismic design components.  
Design analysis shall include calculated dead loads, static seismic loads, and capacity of materials utilized for the connection of the equipment or systems to the structure.

Analysis shall detail anchoring methods, bolt diameter, and embedment depth.

All seismic restraint devices shall be designed to accept without failure the forces calculated per the applicable building code.

Friction from gravity loads shall not be considered resistance to seismic forces.

Fire protection systems shall meet the requirements of NFPA-13 and NFPA-14 for the building seismic requirements.

SEISMIC BRACING AND SUPPORT OF SYSTEMS AND COMPONENTS  
Seismic restraint designer shall coordinate all attachments with the structural engineer of record. Provide engineered stamped and signed drawings of seismic design.

Seismic restraint designer shall provide visual inspection after installation and approval installation of seismic design components.  
Design analysis shall include calculated dead loads, static seismic loads, and capacity of materials utilized for the connection of the equipment or systems to the structure.

Analysis shall detail anchoring methods, bolt diameter, and embedment depth.

balanced in accordance with the referenced standards; are an accurate representation of how the systems have been installed; are a true representation of how the systems are operating at the completion of the testing, adjusting, and balancing procedures; and are an accurate record of all final quantities measured, to establish normal operating values of the systems. Final Report: Upon verification and approval prepare final reports, type written, and organized and formatted as specified below. Submit 2 complete sets of final report to the landford.

General  
Test, adjust, and balance the following mechanical systems:

Supply air systems, all pressure ranges  
Return air systems, all pressure ranges  
Exhaust air systems.

Test systems for proper sound and vibration levels. Quality Assurance  
Codes and Standards:

AABC: "National Standards for Total System Balance".  
ASHRAE: ASHRAE Handbook, 2011 Applications, Chapter 38, Testing, Adjusting, and Balancing.

Qualifications  
The contractor shall procure the services of an independent Balance and Testing Agency, approved by the Engineer, and a member of Associated Air Balance Council (AABC) or NEBB, which specializes in the balancing and testing of heating, ventilating and air conditioning systems, to balance, adjust and test all air and water systems and equipment as herein specified. All work by this agency shall be done under direct supervision of a qualified heating and ventilating Engineer employed by this agency. All instruments used by this agency shall be accurately calibrated and maintained in good working order.

Sequencing and Scheduling  
Test, adjust and balance air conditioning systems during summer season and heating systems during winter season, including at least a period of operation at outside conditions within 5 deg F wet bulb temperature of maximum summer design condition, and within 10 deg F dry bulb temperature of minimum winter design condition. Take final temperature readings during seasonal operation.

Check all filters for cleanliness, provide new as required. Check dampers (volume and fire) for correct and locked position, and temperature control for completeness of installation before starting fans. Place outlet dampers in full open position. Lubricate all motors and bearings. Check fan belt tension. Check fan rotation.

Air balance and testing shall not begin until the system has been completed and is in full working order. The Contractor shall put all heating, ventilating and air conditioning systems and equipment into full operation and shall continue the operation of same during each working day of testing and balancing. The contractor shall submit within 30 days after receipt of contract, 8 copies of submittal data for the testing and balancing of the air conditioning, heating, and ventilating systems. The Air Balance and Testing Agency shall provide proof of having successfully completed at least five projects of similar size and scope.

The air balancing contractor shall include the additional cost to change every fan factory installed sheave, pulley and/or belt in of order to obtain the design air flows. Renovations: In areas where existing HVAC equipment is being utilized, balancing contractor shall include the cost to pre-check each equipment air flows, serving the area of work, prior to demolition, and re-check and adjust each air handler after new construction. Air flows of existing air handlers serving existing spaces shall be similar after project is complete.

Performing Testing, Adjusting and Balancing  
Perform testing and balancing procedures on each system identified, in accordance with the detailed procedures outlined in the referenced standards.

Cut insulation, ductwork, and piping for installation of test probes to the minimum extent necessary to allow adequate performance of procedures.

Patch insulation, ductwork, and housings, using materials identical to those removed.

Seal ducts and piping, and test for and repair leaks. Seal insulation to re-establish integrity of the vapor barrier.

Mark equipment settings, including damper control positions; valve indicators, fan speed control levers, and similar controls and devices, to show final settings. Mark with paint or other suitable, permanent identification materials.

Retest, adjust, and balance systems subsequent to significant system modifications, and resubmit test results.

SEISMIC BRACING AND SUPPORT OF SYSTEMS AND COMPONENTS  
Seismic restraint designer shall coordinate all attachments with the structural engineer of record. Provide engineered stamped and signed drawings of seismic design.

Seismic restraint designer shall provide visual inspection after installation and approval installation of seismic design components.  
Design analysis shall include calculated dead loads, static seismic loads, and capacity of materials utilized for the connection of the equipment or systems to the structure.

Analysis shall detail anchoring methods, bolt diameter, and embedment depth.

All seismic restraint devices shall be designed to accept without failure the forces calculated per the applicable building code.

Friction from gravity loads shall not be considered resistance to seismic forces.

Fire protection systems shall meet the requirements of NFPA-13 and NFPA-14 for the building seismic requirements.

SEISMIC BRACING AND SUPPORT OF SYSTEMS AND COMPONENTS  
Seismic restraint designer shall coordinate all attachments with the structural engineer of record. Provide engineered stamped and signed drawings of seismic design.

Seismic restraint designer shall provide visual inspection after installation and approval installation of seismic design components.  
Design analysis shall include calculated dead loads, static seismic loads, and capacity of materials utilized for the connection of the equipment or systems to the structure.

Analysis shall detail anchoring methods, bolt diameter, and embedment depth.

All seismic restraint devices shall be designed to accept without failure the forces calculated per the applicable building code.

Friction from gravity loads shall not be considered resistance to seismic forces.

Fire protection systems shall meet the requirements of NFPA-13 and NFPA-14 for the building seismic requirements.

SEISMIC BRACING AND SUPPORT OF SYSTEMS AND COMPONENTS  
Seismic restraint designer shall coordinate all attachments with the structural engineer of record. Provide engineered stamped and signed drawings of seismic design.

Seismic restraint designer shall provide visual inspection after installation and approval installation of seismic design components.  
Design analysis shall include calculated dead loads, static seismic loads, and capacity of materials utilized for the connection of the equipment or systems to the structure.

Analysis shall detail anchoring methods, bolt diameter, and embedment depth.

All seismic restraint devices shall be designed to accept without failure the forces calculated per the applicable building code.

Friction from gravity loads shall not be considered resistance to seismic forces.

Fire protection systems shall meet the requirements of NFPA-13 and NFPA-14 for the building seismic requirements.

SEISMIC BRACING AND SUPPORT OF SYSTEMS AND COMPONENTS  
Seismic restraint designer shall coordinate all attachments with the structural engineer of record. Provide engineered stamped and signed drawings of seismic design.

Seismic restraint designer shall provide visual inspection after installation and approval installation of seismic design components.  
Design analysis shall include calculated dead loads, static seismic loads, and capacity of materials utilized for the connection of the equipment or systems to the structure.

Analysis shall detail anchoring methods, bolt diameter, and embedment depth.

All seismic restraint devices shall be designed to accept without failure the forces calculated per the applicable building code.

Friction from gravity loads shall not be considered resistance to seismic forces.

Fire protection systems shall meet the requirements of NFPA-13 and NFPA-14 for the building seismic requirements.

SEISMIC BRACING AND SUPPORT OF SYSTEMS AND COMPONENTS  
Seismic restraint designer shall coordinate all attachments with the structural engineer of record. Provide engineered stamped and signed drawings of seismic design.

Seismic restraint designer shall provide visual inspection after installation and approval installation of seismic design components.  
Design analysis shall include calculated dead loads, static seismic loads, and capacity of materials utilized for the connection of the equipment or systems to the structure.

Analysis shall detail anchoring methods, bolt diameter, and embedment depth.

All seismic restraint devices shall be designed to accept without failure the forces calculated per the applicable building code.

Friction from gravity loads shall not be considered resistance to seismic forces.

Supply ductwork exposed in conditioned spaces excluding mechanical rooms, server rooms and electric equipment rooms  
Toilet exhaust, general exhaust and return ductwork in an insulated joist or attic space.

**SECTION 23 07 19.00 – HVAC PIPING INSULATION**

Submittal Requirements  
Product Data: For each type of product indicated.

Provide 3/4" Armaflex on refrigerant piping. Insulation shall have a minimum thickness as required by Code.

All insulation and adhesives shall have a flame spread index not more than 25 and a smoke developed index of not more than 50.

**SECTION 23 09 93.00 – SEQUENCE OF OPERATIONS FOR HVAC CONTROLS**

Submittal Requirements  
Product Data: Provide written sequences of operation for each controlled system and piece of equipment.

Packaged Rooftop Unit  
1. Startup  
The unit shall operate on a 7 day/night programmable thermostat.

During startup, the fan shall run with the dampers in the full recirculation position. Provide occupied changeover sequence with optimum start function. When the return air temperature reaches occupied setpoint (adjustable), the minimum outside air damper shall open to the controlled minimum outdoor air position.

2. Supply Fan Control  
The supply fan shall be two staged and modulate up and down based on a call for heating or cooling.

3. Space Temperature Control  
Provide 7-day programmable thermostat with digital display of space temperature and setpoint (+/- deg. F, adjustable), with override feature and remote space temperature sensor.

4. Minimum Outside Air Control  
During occupied mode, the minimum outside air damper shall be open to the scheduled minimum outdoor air flow and modulate proportionally with the supply fan speed to maintain the scheduled minimum outside airflow. When the supply fan speed is set to high, outside air damper shall be partially closed allowing minimum outside air flow as scheduled. As supply fan speed is set to low, damper shall fully open allowing minimum outside air flow as scheduled. Provide motor operated dampers.

5. Economizer Control  
Provide dual enthalpy economizer control. Economizer control shall be enabled whenever the outside air enthalpy is lower than the return air enthalpy. Enthalpy shall be calculated from sensors which are tied to the same controller for accuracy. During economizer mode, the outside air damper shall modulate to 100% open. The economizer damper shall modulate open on a call for cooling and modulate closed on a call for heating. The return damper shall modulate inversely with the economizer damper. Economizer shall have powered relief.

6. Cooling Control  
Cooling shall be controlled to maintain space temperature setpoint. On a call for cooling, the heating shall be off and supply fan speed shall be low. On a further call for cooling, the supply fan speed shall be high and energized second stage of cooling.

7. Heating Control  
Heating shall be controlled to maintain space temperature setpoint. On a call for heating, the mechanical cooling shall be off. On a further call for heating, the economizer control shall be disabled. On a further call for heating, the supply fan shall be set to low speed. On a further call for heating, the supply fan shall be set to high speed and the gas heating shall be staged on. On a further call for



OWNERSHIP OF INSTRUMENTS OF SERVICE  
The Consultant shall retain all common law, statutory and other reserved rights, including, without limitation, the copyright thereto.  
The Consultant shall retain all common law, statutory and other reserved rights, including, without limitation, the copyright thereto.

boxes, wiring, etc.) in accordance with Electrical Specifications requirements. All conduit shall be 3/4" minimum.  
Coordinate all thermostat/sensor locations in field (case by case) with Architect. Owner and Electrical Contractor to ensure that they are placed in locations that will not interfere with furniture, equipment, artwork, wall-hung specialties, room finishes, etc. All thermostat/sensor wall locations indicated on HVAC drawings are schematic only and must be verified case-by-case prior to rough-in.  
All electrical work as described on drawings and specifications shall be per the latest edition of the National Electrical Code (NEC) and per applicable state and local codes.  
Where "free-air" installation methods (either exposed above the ceilings, in bridge rings or in cable trays) are permitted under Electrical Specifications above ceilings, provide plenum-rated cables wherever plenum cables (if any) exist and install as defined under Electrical Specifications. Install low voltage circuits, located in concrete slabs and masonry walls, in inaccessible locations, or exposed in occupied areas, in electrical conduit regardless of what wiring methods are permitted under Electrical Specifications.  
Where cable trays or bridge rings are provided by the electrical contractor for low voltage cables, these raceways may be utilized for control wiring by this contractor (provide special color coded jackets, label cable jackets per Electrical Specifications and group control wiring cables together). Provide conduit drops from cable tray/bridge ring paths to wall outlet boxes and equipment unless directed otherwise under Electrical Specifications. Regardless of permitted methods in Electrical Specifications, all cables/wiring installed concealed by gypsum board, masonry or other inaccessible materials in walls or above ceilings shall be installed in conduit, 3/4" minimum.  
All conduit, bridge rings, raceway, outlet boxes, etc. necessary for complete operational installation of control wiring shall be provided (furnished and installed) by the temperature control contractor in strict compliance with Electrical Specifications documents. Coordinate all work with all other applicable trades including the electrical contractor.  
Provide all required conduit work to and between equipment in a manner compliant with that described above (i.e. between VAV boxes, to boilers, starters, condensing units, etc. as applicable).  
Install control wiring without splices between terminal points, color-coded. Install in neat workmanlike manner, securely fastened. Install in accordance with National Electrical Code and per Electrical Specifications.  
Install circuits over 25 volt with color-coded No. 12 wire in electrical metallic tubing, per Electrical Specifications. Install circuits under 25 volt with color-coded No. 18 wire with 0.031" high temperature (105 degs. F) plastic insulation on each conductor and plastic sheath over all. Install electronic circuits with color-coded No. 22 wire with 0.023" polyethylene insulation on each conductor with plastic-jacketed copper shield over all.

**SECTION 23 31 13.00 – METAL DUCTS**

Submittal Requirements  
Product Data: For liners, adhesives, sealants and gaskets.  
Shop Drawings: Sheet metal thickness, reinforcing details, duct layouts indicating sizes, configuration, liner material, elevation and static pressure class.

Ductwork Materials  
Exposed Ductwork Materials: Where ductwork is indicated to be exposed to view in occupied spaces, provide materials which are free from visual imperfections including pitting, seam marks, roller marks, stains and discolorations, and other imperfections, including those which would impair painting. Mechanical contractor shall confirm ductwork paint scope and color with architect.  
Exposed ductwork which is to be painted shall have paint grip applied and be oil free.  
Sheet Metal: Except as otherwise indicated, fabricate ductwork from galvanized sheet steel, lock forming quality, with G 90 zinc coating and mill phosphatized for exposed locations. Minimum gauge shall be 24.  
Miscellaneous Ductwork Materials  
Volume Dampers: Provide volume dampers in all branch ducts or as required for balancing to required air flows.  
Fittings: Provide radius type fittings fabricated of multiple sections with maximum 15 deg. change of direction per section. Unless specifically installed otherwise, use 45 deg. laterals and 45 deg. elbows for branch takeoff connections. Where 90 deg. branches are indicated, provide conical type tees.  
Duct Sealant: Non-hardening, non-migrating mastic or liquid elastic sealant, type applicable for fabrication/installation detail, as compounded and recommended by manufacturer specifically for sealing joints and seams in ductwork.  
Duct Cement: Non-hardening migrating mastic or liquid neoprene based cement, type applicable for fabrication/installation detail, as compounded and recommended by manufacturer specifically for cementing fitting components, or longitudinal seams in ductwork.  
Ductwork Support Materials: Except as otherwise indicated, provide hot-dipped galvanized steel fasteners, anchors, rods, straps, trim and angles for support of ductwork.  
Flexible Ducts  
Either spiral-wound spring steel with flameproof vinyl sheathing, or corrugated aluminum. Unless specifically mentioned, maximum length of flex duct on the supply equals 5 feet. Flex is not allowed for return, relief or exhaust applications. The flexible ducts indicated for use in the H.V.A.C. system shall conform to the requirements of UL 181 for Class 0 or Class 1 flexible air ducts and shall be so identified.  
Where installed in unconditioned spaces other than return air plenums, provide 1" thick 1-1/2 lb. continuous flexible fiberglass sheath with vinyl vapor barrier jacket. Installation is not permitted above drywall ceilings and inaccessible ceilings.  
Fabrication  
Shop fabricate ductwork in 4, 8, 10 or 12-ft lengths, unless otherwise indicated or required for complete runs. All ductwork shall be Pittsburgh Construction with a minimum of thickness of 24 gauge. In addition, ductwork used in systems over 3" W.G. shall have cold sealant applied. Shop fabricate ductwork of gauges and reinforcement complying with SMACNA "HVAC Duct Construction Standards".  
Field Duct  
Fabricate ductwork with duct liner in each section of duct where indicated. Laminate liner to internal surfaces of duct in accordance with instructions by manufacturers of lining and adhesive, and fasten with mechanical fasteners. Duct liner to be 3-lb density for acoustic requirements 1"

thick or as noted. Size of ductwork shown on the drawings is free net area, outside dimension of ducts will need to be increased if lined duct is used.  
Size of ductwork shown on the drawings is free net area, outside dimension of ducts will need to be increased if lined duct is used.  
Duct Liner: Fibrous glass of thickness indicated. 3-lb density. All liners, insulation and adhesives shall have a flame spread index not more than 25 and a smoke developed index of not more than 50.  
Duct Liner Adhesive: As recommended by insulation manufacturer and complying with NFPA 90A or NFPA 90B.  
Duct Liner Fasteners: Comply with SMACNA HVAC Duct Construction Standards.  
Installation of Metal Ductwork  
General: Assemble and install ductwork in accordance with recognized industry practices which will achieve air-tight (5% leakage for systems rated 3" and under; 1% for systems rated over 3") and noiseless (no objectionable noise) systems, capable of performing each indicated service. Install each run with minimum number of joints.  
Align ductwork accurately at connections, within 1/8" misalignment tolerance and with internal surfaces smooth.  
Support ducts rigidly with suitable ties, braces, hangers and anchors of type which will hold ducts true-to-shape and to prevent buckling. Support vertical ducts at every floor.  
Sealing: Seal all longitudinal seams, S's and drives and all joints with mastic or cement. Install according to SMACNA standards.  
Balancing Dampers: The sheet metal contractor shall be fully responsible for installing balancing dampers in the ductwork, (whether shown on the drawing or not) in order to arrive at the intended air flow. The balancing sub-contractor shall provide direction and assistance in determining locations where dampers are required.  
Additional dampers, if required shall be installed at no additional cost to the owner.  
Wall Penetrations: Seal and pack around all ducts and piping sleeves which pass through walls that extend to bottom side of structure and rated walls.  
Field Fabrication: Complete fabrication of work at project as necessary to match shop-fabricated work and coordinate with other trades and enclosure elements of building.  
Routing: Locate ductwork runs, except as otherwise indicated, vertically and horizontally and avoid diagonal runs wherever possible. Run ductwork in shortest route which does not obstruct useable space or block access for servicing building and its equipment. Hold ducts close to walls, overhead construction, columns, and other structural and peripheral enclosure elements of building. Limit clearance to 1/2" where furring is shown for enclosure or concealment of ducts, but allow for insulation thickness, if any. Where possible, locate insulated ductwork for 1" clearance outside of insulation. Wherever possible in finished and occupied spaces, conceal ductwork from view, by locating in mechanical shafts, hollow wall construction or above suspended ceilings. Do not encase horizontal runs in solid partitions, except as specifically shown.  
Coordinate layout with suspended ceiling and lighting layouts and similar finished work.  
Electrical Equipment Spaces: Do not route ductwork through transformer vaults and their electrical equipment spaces and enclosures.  
Penetrations: Where ducts pass through interior partitions and exterior walls, and are exposed to view, conceal space between construction opening and duct or duct insulation with sheet metal flanges of same gauge as duct. Overlap opening on 4 sides by at least 1-1/2". Fasten to duct and substrate.  
All dampers shall be low leakage with edge and blade seals. Damper manufacturers are subject to specification compliance. Provide products by one of the following: Greenheck Fan Corporation  
Nailor Industries  
Pottorff  
Ruskin Company  
Young Regulator Company  
Coordination: Coordinate duct installations with installation of accessories, dampers, coil frames, equipment, controls and other associated work of ductwork system.  
Installation of Duct Liner  
General: Install duct liner in accordance with SMACNA HVAC Duct Construction Standards. Size of ductwork shown on the drawings is free net area, outside dimension of ducts will need to be increased if lined duct is used.  
Store internally lined ductwork up off of the floor. Protect internally lined ductwork from water and dust.  
The following ductwork shall be lined in addition to that shown per plans:  
Return from open ceiling plenum return to HVAC unit.  
Supply and return ductwork 10 feet downstream of HVAC unit.  
Transfer air ducts.  
Butter the leading edge of all internal duct lining with the manufacturer's recommended adhesive.  
Inspect and repair all damaged lining prior to installation of ductwork.  
Installation of Flexible Ducts  
Maximum Length: For any duct run using flexible ductwork, do not exceed 5' - 0" extended length.  
Installation shall have smooth full radius turns down to diffuser.  
Installation not permitted above inaccessible ceilings.

**23 34 23.00 – HVAC POWER VENTILATORS**

Submittal Requirements  
Product Data: For each type of product indicated.  
Ceiling Ventilators  
Centrifugal Ceiling Exhausters: Provide centrifugal ceiling exhausters, designed for ceiling or wall mounting, of type, size and capacity as scheduled.  
Provide AMCA Certified Ratings Seal.  
Type: Provide galvanized steel housing lined with acoustical insulation, adaptable for ceiling or wall installation. Provide centrifugal fan wheels mounted on motor shaft with fan shrouds, all removable for service.  
Grille: Provide steel louvered grille with flange on intake with thumbscrew attachment to fan housing.  
Motor: Provide permanent split-capacitor motor, permanently lubricated.  
Accessories: Provide manufacturer's standard roof jack, wall cap, and transition fittings as indicated on drawings or schedules.  
Vibration Isolation: Provide spring floor isolators or hangers depending on type of installation.  
Duct Lining: Provide 1" thick density duct liner a minimum of 5' (five feet) up and down stream of fan.  
Manufacturer: Subject to compliance with requirements, provide centrifugal ceiling exhausters of one of the following:  
Acme

Cook (Loren) Co.  
Greenheck.  
Twin City Fan & Blower  
INSTALLATION  
Coordinate ventilator work with work of roofing, walls, and ceilings, as necessary for proper interfacing.  
Provide access door in duct below ventilator to service damper.  
Solder bottom joints and up 2" of side joints of duct under roof ventilator to retain any moisture entering ventilator.

**SECTION 23 34 33.00 – AIR CURTAINS**

Submittal Requirements  
Product Data: For each type of product indicated.

General  
General: Provide air doors of size and capacity as noted on drawings. Air doors shall operate at a low sound level and meet OSHA standards.  
Construction:  
Wheels: Talc-filled polypropylene or aluminum.  
Housing: Galvanized steel.  
Motorboard: Galvanized steel.  
Velocity Control: Provide adjustable louver damper controls for regulating rate of air flow. When louvers are completely closed air velocity shall reduce to sixty percent.  
Directional Control: Provide adjustable vanes at outlet nozzle for directing air where needed and readily set to compensate for possible draft conditions through door openings. Vanes shall have a forty percent girth sweep front to back.  
Motors: Provide totally enclosed shaded-pole, or permanent-split capacitor motors, Class "B" insulation, resiliently mounted, tap wound with built-in thermal overload protection, and with permanently lubricated type sleeve or ball bearings. Select motors with the voltage as scheduled.  
Extended Motor Oilers: Provide plastic tubes for lubricating motor bearings which are installed beneath grille.  
Motor Controls: Provide multi-speed motor control switch with OFF position, mounted behind access door.  
Fans: Provide double width, double inlet centrifugal fans, which are balanced statically and dynamically, of indicated capacity. Select fans with single or double extended motor shaft, with fan housing and motor fastened as an integral assembly to a motorboard.  
Electric Air Curtains  
Heating Elements: Except as otherwise indicated, provide structural and peripheral enclosure elements of type, sizes, capacities and ratings for duty indicated; consisting of resistance elements enclosed in steel sheath with extended fins, or with spirally finned sheath.  
Electric Heating Capacity: Size elements for indicated fan speed, CFM, room heating load (BTUH), entering air temperature, and electric input (watts, voltage, phase).  
Internal Electrical Wiring: Provide units with high temperature, electrical heat-resistant wiring in flexible metal conduit from terminal junction box to electrical devices. Provide fusing for motor and control circuit wiring. Provide all required control transformers.  
Devices: Provide air doors with the following devices: Thermally activated fan switch to keep fan motor operating until residual heat is dissipated.  
Disconnect switch.  
Automatic reset, high limit cut-out switch located in discharge air stream.  
Manual "Summer-OFF-Winter" switch.  
Unit-mounted line voltage thermostat  
Time delay relay  
Control Power Transformer  
Magnetic Contactor (Relay Kit)  
Manufacturers: Subject to compliance with requirements, provide electric air doors of one of the following:  
Berner  
Mars Sales Company, Inc.  
Powered Aire Inc.  
Raywall  
Schwank  
Installation  
Provide disconnect at side or unit for installation in recessed ceiling.  
Provide trim piece to finish linear slot supply in ceiling for recessed units.  
Coordinate with other electrical work, including wiring/cabling, as necessary to properly interface installation of heating terminal units with other work.  
Clean dust and debris from each heating terminal as it is installed to ensure cleanliness.  
Comb out damaged fins where bent or crushed before covering elements with enclosures.  
Touch-up scratched or marred heating terminal enclosure surfaces to match original finishes.  
Field Quality Control  
Upon completion of installation of electric heating terminals, and after building circuitry has been energized, test heating terminals to demonstrate capability and compliance with requirements.  
Replace electric heating terminals and accessories which are damaged and remove damaged items from construction site.

**23 37 13.00 – DIFFUSERS, REGISTERS AND LOUVERS**

Submittal Requirements  
Product Data: For each type of product indicated.

DIFFUSERS, GRILLES AND REGISTERS  
Manufacturer: Subject to compliance with requirements, provide diffusers of one of the following:  
Anemostat Products Div., Dynamics Corp. of America.  
Metal-Aire  
Titus Products Div., Philips Industries, Inc.  
Tuttle and Bailey.  
Price  
Louvers and dampers  
Provide louvers and dampers of size as noted.  
Manufacturer: Subject to compliance with requirements, provide diffusers of one of the following:  
Aerolite  
Prefco  
Protoluf  
Greenheck  
Ruskin

**23 74 33.00 – PACKAGED OUTDOOR ROOFTOP UNITS**

Submittal Requirements  
Product Data: For each type of product indicated.

Warranty  
Warranty on Compressor and Heat Exchanger: Provide written warranty, signed by manufacturer, agreeing to

replace/repair, within warranty period, compressors and heat exchangers with inadequate and defective materials and workmanship, including leakage, breakage, improper assembly, or failure to perform as required; provided manufacturer's instructions for handling, installing, protecting, and maintaining units have been adhered to during warranty period. Replacement is limited to component replacement only, and does not include labor for removal and reinstallation.  
Warranty Period: 5 years from date of owner acceptance.  
[ROOFTOP HEAT PUMP UNITS  
Unit Casing: Panels are of 20-gauge steel, cleaned, phosphatized and coated with resin primer and baked enamel finish.  
Access doors provide access to unit controls, filters, indoor coil, supply air fans and optional economizer supply/return air dampers. Inside air section is completely insulated with fireproof, permanent, odorless, glass fiber material. All removable panels and access doors have neoprene gaskets to prevent leakage. The unit base pan is insulated with polyurethane foam insulation. Knockouts are provided for utility and control connections. Drain connections are provided to accommodate indoor and outdoor coil water runoff. Lifting lugs are provided as an integral part of the unit.  
Compressor: All units have hermetically sealed, high efficiency reciprocating compressors designed for heat pump duty. Compressors are equipped with over temperature, over current and high pressure controls. Crankcase heaters are standard.  
Refrigerant Circuit: All units have expansion devices to provide proper refrigerant flow control in both heating and cooling. Heavy duty, high capacity solenoid type reversing (four-way) valve is standard to provide automatic refrigerant cycle changeover.  
Condenser Coil: Outdoor coils are specially designed for heat pump application with widely spaced, wavy-finned surface and staggered row copper tubing. 3/8-inch OD seamless copper tubing is mechanically bonded to aluminum fins. Each coil is factory pressure and leak tested.  
Evaporator Coil: Indoor coils are 3/8-inch OD seamless copper tubing mechanically bonded to aluminum fins and are factory pressure and leak tested.  
Condenser Fans and Motors - Shall be vertical discharge, balanced, direct-drive fans mounted on pan to de-energize unit upon detection of high condensate levels in primary condensate pan.  
Condenser Fan: Direct drive, statically and dynamically balanced propeller fans are used. All fans are weatherproof and UL listed for outdoor use. Permanently lubricated motors have built-in thermal overload protection.  
Evaporator Fan: Belt-driven, forward-curved, centrifugal type fans equipped with an adjustable motor sheave are standard. Fan and motor bearings are permanently lubricated. Fan motor has built-in overload protection. Fan drive components are mounted on rubber-in-shear isolators to reduce noise and vibration.  
Defrost Control: The demand defrost system compares precise temperature difference between the outdoor ambient temperature and outdoor coil fin surface temperature to assess outdoor coil heat transfer capacity. Solid-state comparator and defrost logic circuitry activates the reverse cycle defrost strictly on a demand basis to eliminate unnecessary defrost cycling. Logic circuitry has an integral time override to limit defrost cycle to a maximum of 8 minutes.  
Filters: Provide air filters to fit in filter box, with a Maximum filter face velocity of 500 fpm, of the following type: Disposable Type: Provide MERV 13 air filters, consisting of viscous coated fibers with filtering media encased in fiberboard cell sides having perforated metal grids on each side to provide media support.  
Outside Air Options:  
Economizer:  
Enthalpy Controlled Economizer: Provide return and outside air dampers, outside air filter, fully modulating electric control system with dry control, and adjustable mixed-air thermostat. System shall be capable of driving 100% closed for unoccupied mode, minimum outside air position and modulation to 100 percent open outside air capability. Provide automatic changeover through adjustable control device.  
Relief:  
Power Exhaust Fan – Shall be factory installed for units larger than 5 tons. Shall include relief damper section with mist eliminator. Dampers open to relieve positive pressure within the building. Available only with economizer.  
Accessories: Electric Supplemental Heaters: Slide-in heater module mounts in unit discharge air passage. Curb: Provide insulated roof curb under unit, constructed in accordance with NRCA Standards. Provide seal strip between curb and unit, and wood nailer for flashing. Thermostat: Provide thermostat assembly for 7 day/night setback staged heating and cooling with manual or automatic changeover on standard subbase.  
Hail Guards: Provide hail guards around the condenser coil to protect the condenser fins against hail.  
Manufacturer: Subject to compliance with requirements, provide rooftop units of one of the following:  
Aaon  
Carrier Air Conditioning; Div. of Carrier Corp.  
Trane Co.  
Bryant  
Lennox  
Daikin  
Johnson Controls]  
VARIABLE VOLUME ROOFTOP UNIT  
General: All units shall be completely factory assembled and tested, piped, internally wired, and fully charged with HFC Refrigerant. Cooling capacities shall be rated in accordance with A.R.I. Standard 360. All electrical wiring shall be in accordance with the National Electric Code. All units shall be suitable for outdoor rooftop or ground level installation.  
Unit Casing: All exterior surfaces shall be phosphatized, zinc-coated steel with enamel finish. Screws shall be coated with zinc-plus-zinc chromate and with neoprene washers where sealing shall be required. Doors shall provide access to control components, filters, outside/return air dampers, evaporator coil, and supply and exhaust fan sections. All access doors and removable panels shall have neoprene gaskets a 1/2-inch, dual density fiber insulation. Roof assembly shall have modified lock seam joints filled with sealant. Drain hole(s) shall be provided on each side of the condenser section. Unit base shall be one-piece welded assembly with 14-gauge formed, load bearing members and overhang roof curb to facilitate water runoff. Unit lifting lugs accept chains or cables for rigging.  
Roof Curb: The curb shall be constructed of 16-gauge, zinc-clad steel. The roof curb is designed to mate with unit and provide support and complete weathertight installation when properly installed. Wood nailer strip shall be factory installed, with gasketing provided to seal supply/return air openings. Design shall allow for

connection of ductwork to curb prior to setting of unit. Curb shall be 14 inches high and approved by the National Roofing Contractors Association. Roof curb ships knocked down for easy field assembly. Provide curb type and flashing per roofing manufacturer requirements. Electrical: All wiring shall be installed and tested in individual component assemblies, then rechecked during final factory run test.  
Refrigeration System:  
Compressors - All units shall have two or more 3,600 rpm, hermetically sealed compressors. Compressors shall be equipped with over-temperature, over-current and high-pressure controls. Compressors shall be variable capacity. Crankcase heaters and suction line accumulators shall be standard on all models. Provide compressor isolation service valves.  
Units shall also have:  
Cylinder unloader for capacity control, with minimum of two steps or as scheduled.  
[Hot-gas bypass valve and piping on the lead circuit.]  
Thermal expansion valves, filter dryers, sight glasses, liquid line service valves.  
Coils: Refrigeration Controls - Refrigeration controls shall include condenser fan, evaporator fan, compressor contactors, and fan safety controls. Each circuit of the unit shall have a separate set of refrigeration controls. Compressor safety controls are outlined in the section above. Evaporator Coil - All units shall have three independent circuits. Heavy-duty aluminum fins mechanically bonded to 1/2-inch seamless copper tubing shall be standard. Factory pressure and leak tested at 300 psi. Expansion valves shall be standard.  
High Capacity DX coil (Trane Intellipack)  
Condenser Coil - Factory pressure and leak tested at 425 psi. Aluminum fin surface mechanically bonded to 3/8-inch seamless copper tubing.  
Fans: Indoor Air Fan - Shall be two, double-inlet, direct drive, backward incline, centrifugal-type fans mounted on a common shaft with adjustable sheave drive. All fans statically and dynamically balanced and tested at the factory. Supply fan shall be run tested in the unit as part of unit run test. Unit reaches its rated rpm before the fan shaft passes through the first critical speed. Fan shaft shall be mounted on two self-aligning, permanently sealed ball bearings. Condenser Fans and Motors - Shall be vertical discharge, balanced, direct-drive fans mounted in full length, bell-mouth orifices. Fan motor shall be three-phase with permanently lubricated ball bearings and built-in thermal overload protection. Motors shall be line voltage, three phase and shall be equipped with rain shields to eliminate moisture.  
Control Fan: Provide a double sloping drain pan. Provide high condensate switch in primary condensate pan to de-energize unit upon detection of high condensate levels  
Gas Fired Heating:  
General - Shall be a completely assembled and wired gas-fired heating system with the unit. Test fired at the factory prior to shipment.  
Heat Exchanger - Shall be tubular two-pass design with 16-gauge aluminumized steel primary and 18-gauge secondary heat exchanger surfaces. Free-floating design eliminates contraction and expansion stresses and noises.  
Combustion Blower - Shall be centrifugal-type fan, which provides required air for efficient fuel combustion. Fan motor shall have built-in thermal overload protection.  
Gas Safety Controls - Shall have electronic flame safety controls, which require proving of combustion air prior to ignition sequence which includes 60-second prepurge cycle. Direct ignition spark to the burner. Positive ignition must occur within four seconds or heating cycle locks out. A 30-second delay occurs between first and second state gas valves. Continuous electronic flame supervision is standard. Combustion blower continues to operate for 60-seconds for a postpurge cycle.  
Burner - Shall be industrial-type power burner with air-proving switch. Automatic pressure sensing safety switch prevents burner operation if burner is open for maintenance or inspection. Ceramic burner cone shape flame to prevent to prevent impingement on sides of heat exchanger drum. Burner assembly houses ignition in monitoring electrodes. Burner shall be full modulating with a minimum turndown of 5:1.  
Exhaust Air Options:  
Powered Relief - Provide factory installed exhaust fan and duct, relief damper section with mist eliminator and building pressurization control. Dampers shall modulate open to relieve positive pressure within the building. Exhaust fan shall be sized for 100% of supply air CFM.  
Economizer:  
Enthalpy Controlled Economizer: Provide return and outside air dampers, outside air filter, fully modulating electric control system with dry control, and adjustable mixed-air thermostat. System shall be capable of driving 100% closed for unoccupied mode, minimum outside air position and modulation to 100 percent open outside air capability. Provide automatic changeover through adjustable control device.

Filters:  
Provide air filters to fit in filter box, with a Maximum filter face velocity of 500 fpm, of the following type:  
Filters: Provide 65%, efficient filters.  
Provide filters with clean resistance not exceeding 0.10" w.g. at face velocity of 300 fpm, and ASHRAE weight arrestance efficiency of 70-82%, based on final operating resistance of 0.5" w.g.  
Options:  
Hail guards protecting the condenser fins.  
Controls:  
Self Contained: Programmable Electronic Night Setback Thermostat - Shall provide heating setback and cooling setup with 7-day, programming capability. Optional remote sensor available.  
DDC Interface – Equipment manufacturer shall provide a factory installed communications card to allow transfer of digital information from equipment manufacturer controller to temperature controls system/BAS. Mechanical contractor to coordinate all controls and programming requirements with temperature controls contractor prior to bid.  
Manufacturers:  
Subject to compliance with requirements, provide rooftop units of one of the following:  
Aaon  
Carrier Air Conditioning, Div of Carrier Corp.  
Lennox  
Trane; a division of Ingersoll Rand.  
Daikin  
Johnson Controls



KOHR'S LONNEMANN HEIL ENGINEERS, INC.  
MECHANICAL/ELECTRICAL ENGINEERS  
WWW.KLHENGRS.COM

1538 ALEXANDRIA PIKE, SUITE 11  
FT. THOMAS, KENTUCKY 41075  
800-354-9783  
859-442-8050  
859-442-8050 FAX  
LEXINGTON, KENTUCKY  
LOUISVILLE, KENTUCKY  
COLUMBUS, OHIO  
KLH\_JOB # : 27551



rgla solutions, inc.

5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com

robert g. lyon + associates, inc.  
retail architecture


5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com

STATE OF MISSOURI  
ROBERT A. LONNEMANN  
NUMBER  
PE-200300849  
PROFESSIONAL ENGINEER

6/18/2025

SEAL:

THE ABOVE DRAWINGS AND SPECIFICATIONS AND IDEAS, DESIGN AND ARRANGEMENTS REPRESENTED THEREBY ARE AND SHALL REMAIN THE PROPERTY OF THE OFFICE AND NO PART THEREOF SHALL BE COPIED, DISCLOSED TO OTHERS OR USED IN THE CONSTRUCTION OF ANY WORK OR PROJECT OTHER THAN THE SPECIFIC PROJECT FOR WHICH THEY WERE PREPARED AND USED EXCEPT WITHOUT THE WRITTEN CONSENT OF THIS OFFICE. VISUAL CONTACT WITH THESE DRAWINGS OR SPECIFICATIONS SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS. WRITTEN ENDORSEMENT ON THESE DRAWINGS SHALL HAVE PRECEDENCE OVER SCALED ENDORSEMENTS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR THE ACCURACY OF ALL DIMENSIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY DISCREPANCIES IMMEDIATELY. SHOP DETAILS MUST BE SHOWN BY THESE DRAWINGS. SHOP DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE PROCEEDING WITH FABRICATION.  
© 2024 ROBERT G. LYON & ASSOCIATES, INC.




SUMMIT WOODS CROSSING  
1744 NW CHIPMAN ROAD  
LEE'S SUMMIT, MO 64081

DRAWN BY  
NMS  
CHECKED BY  
AJK  
JOB NUMBER  
25303  
SHEET NAME  
MECHANICAL  
SPECIFICATIONS  
M-502










5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
[www.rqla.com](http://www.rqla.com)

[illegible]

**architecture**  
5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
[www.rqia.com](http://www.rqia.com)



THE ABOVE DRAWINGS AND SPECIFICATIONS AND IDEAS, DESIGNS AND MANAGERMENTS REPRESENTED THEREIN ARE AND SHALL REMAIN THE PROPERTY OF THIS OFFICE, AND NO PART THEREOF SHALL BE COPIED, DISCLOSED TO OTHERS OR USED IN THE CONNECTION WITH ANY WORK OR PROJECT OF ANY OTHER OFFICE OR INDIVIDUAL, UNLESS THEY HAVE BEEN PREPARED AND DEVELOPED WITHOUT THE WRITTEN CONSENT OF THIS OFFICE. VISUAL CONTACT WITH ANY OF THE ABOVE DRAWINGS OR SPECIFICATIONS SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS. WRITTEN DIMENSIONS ON THESE DRAWINGS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS. THE CLIENT AND/OR ARCHITECT SHALL BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY CHANGES, OMISSIONS, ADDITIONS, OR DEVIATIONS SHOWN BY THESE DRAWINGS. SHOP DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE SUBMITTING WITH FABRICATION.

© 2014 ROBERT C. LYON & ASSOCIATES, INC.

**carhartt**  
SUMMIT WOODS CROSSING  
1744 NW CHIPMAN ROAD  
LEE'S SUMMIT, MO 64081

MECHANICAL - SCHEDULES

DRAWN BY

NIMS

A.IK

JOB NUMBER

SHEET NAME

M-602

PRODUCT							GENERAL	MISC					
MARK	DESCRIPTION	MANUFACTURER	MODEL	LENGTH (IN)	WIDTH (IN)	SECTION NUMBER	STATUS	HTG TYPE	MATERIAL TYPE	FINISH TYPE	DAMPER TYPE	BORDER STYLE	ACCESSORIES
CD-1	DIFFUSERS, REGISTERS AND GRILLES	TITUS	TMS	12	12	23 37 13.00	NEW	CEILING	STEEL	STANDARD WHITE	BUTTERFLY	SURFACE MOUNTED	..
SR-1	DIFFUSERS, REGISTERS AND GRILLES	TITUS	S300PL	4	26	23 37 13.00	NEW	DUCT	STEEL	STANDARD WHITE	SCOOP DAMPER	SURFACE MOUNTED	..
SR-2	DIFFUSERS, REGISTERS AND GRILLES	TITUS	S300PL	4	24	23 37 13.00	NEW	DUCT	STEEL	STANDARD WHITE	SCOOP DAMPER	SURFACE MOUNTED	..
SR-3	DIFFUSERS, REGISTERS AND GRILLES	TITUS	S300PL	3	12	23 37 13.00	NEW	DUCT	STEEL	STANDARD WHITE	SCOOP DAMPER	SURFACE MOUNTED	..
SR-4	DIFFUSERS, REGISTERS AND GRILLES	TITUS	S300PL	3	10	23 37 13.00	NEW	DUCT	STEEL	STANDARD WHITE	SCOOP DAMPER	SURFACE MOUNTED	..
SR-5	DIFFUSERS, REGISTERS AND GRILLES	TITUS	S300PL	3	20	23 37 13.00	NEW	DUCT	STEEL	STANDARD WHITE	SCOOP DAMPER	SURFACE MOUNTED	..
SR-6	DIFFUSERS, REGISTERS AND GRILLES	TITUS	S300PL	3	18	23 37 13.00	NEW	DUCT	STEEL	STANDARD WHITE	SCOOP DAMPER	SURFACE MOUNTED	..
TG-1	DIFFUSERS, REGISTERS AND GRILLES	TITUS	350RL	6	12	23 37 13.00	NEW	SIDEMALL	STEEL	BLACK FINISH G.C. TO FIELD PAINT TO MATCH CEILING OR WALLS	NONE	SURFACE MOUNTED	..
TG-2	DIFFUSERS, REGISTERS AND GRILLES	TITUS	350RL	6	24	23 37 13.00	NEW	SIDEMALL	STEEL	BLACK FINISH G.C. TO FIELD PAINT TO MATCH CEILING OR WALLS	NONE	SURFACE MOUNTED	..

[illegible]

THE HEATING AND COOLING LOAD CALCULATIONS ARE BASED ON THE RTS (RADIANT TUBE SERIES) METHOD. ASSUMPTIONS AND EXECUTION OF THESE METHODS ARE PER ASHRAE 183-2007 STANDARD FOR PEAK COOLING AND HEATING LOAD CALCULATIONS IN BUILDINGS EXCEPT LOW-RISE RESIDENTIAL BUILDINGS.																									
COOLING LOAD BREAKDOWN - SUMMER DESIGN ON TEMP: 97 F SUMMER DESIGN DB TEMP: 77 F															HEATING LOAD BREAKDOWN - WINTER DESIGN DB TEMP: 5 F										
EQUIPMENT NAME	ZONE	CHROF	CHALL	CFART	CGLASS	CSOLAR	CLIGHTS	CEQUIP	CPSPEN	CSSENS	CFAN	CSGLASS	CTSLAT	COAL	CTTOT	HHOOF	HMALL	HMART	HGLASS	HSGLAR	HSPACE	HDA	HTOT		
RTU-1	1	6.45	1.1	0	3.21	20.61	23.1	2.7	17.16	81.95	2	22.47	106.42	10.4	30.54	40.94	147.36	11.58	2.97	0	12.44	11.89	38.88	70.22	110.91
RTU-2	1	4.28	1.81	0	0	16.73	2.22	4.55	29.58	0.74	6.88	37.2	1.6	9.35	10.95	148.14	7.69	6.03	0	0	5.82	19.54	21.5	41.04	

PRODUCT										GENERAL		HEATING	ELECTRICAL	MISC	ELECTRICAL																PRODUCT	
MARK	DESCRIPTION	MANUFACTURER	MODEL	OPERATING VOLTAGE (V)	SECTION NUMBER	AREA SERVED	STATUS	NON Rtg CAP (µF)	EMERGENCY	ACCESSORIES	CONNECTION MARK	ELECTRIC CONNECTION SUMMARY				CH TYPE	CH FURNISHED BY	CH INSTALLED BY	CH WIRING BY	CH TYPE	CH FURNISHED BY	CH INSTALLED BY	CH WIRING BY	DC TYPE	DC FURNISHED BY	DC INSTALLED BY	DC WIRING BY	FA SHUTDOWN	REQUIRED TO TEST FAULT CURRENT	FAULT CURRENT	EMERGENCY	MARK
AC-1	AIR CURTAIN W/ELECTRIC HEAT	POWERED AIRE	EVE-2-72E	102	23 34 33.00	--	NEW	8	NO	--	AC-1	AC-1 - 208V/3PH, 60H MTP, 0.4 HP, 47.3 KVA, 60A OCP				INT	HFR	HFR	HFR	HFR	HFR	HFR	HFR	--	EC	EC	EC	NONE	FALSE	AC-1-3167	FALSE	AC-1

PRODUCT						GENERAL				AIRFLOW				ELECTRICAL		HISC		ELECTRICAL														PRODUCT			
MARK	DESCRIPTION	MANUFACTURER	MODEL	OPERATING WEIGHT (LBS)	SECTION NUMBER	AREA SERVED	STATUS	EA (FPM)	ESP (W.C.)	FAN BHP	FAN HTR (BHP)	EMERGENCY	ACCESSORIES	CONNECTION MARK	ELECTRIC CONNECTION SUMMARY				CN TYPE	CN FURNISHED BY	CN INSTALLED BY	CN MOVED BY	NC TYPE	NC FURNISHED BY	NC INSTALLED BY	NC MOVED BY	DC TYPE	DC FURNISHED	DC INSTALLED BY	DC MOVED BY	FA SHUTDOWN	REQUIRED TO MEET FAULT CURRENT	FAULT CURRENT	EMERGENCY	MARK
EF-1	RVAC EXHAUST FAN	GREENECKE	SP-LP0511-1	8	23 34 00.00	RESTROOM	NEW	80	4	0.01	773	NO	1, 3	EF-1	EF-1 - 120V/1PH, 0.25A FLA, 0.4 NCA, 15A OCP				NAN	EC	EC	EC	ECN	HFR	HFR	HFR	--	EC	EC	EC	NONE	FALSE	EF-1: 6879	FALSE	EF-1

PRODUCT						GENERAL		AIRFLOW							COOLING								HEATING									ELECTRICAL	MISC	ELECTRICAL																PRODUCT	
MARK	DESCRIPTION	MANUFACTURER	MODEL	OPERATING AIR FLOW UNIT (LBS)	SECTION NUMBER	AREA SERVED	STATUS	SA (CFM)	OA (CFM)	DOV MIN ALPHAM (CFM)	ESP INCH W.C.	FAN RPM	NOW CLG TONN	TOTAL CLG TNN	CALC CLG TNN	EAT CLG CLG	EAT CLG	LAT CLG	LAT CLG	NIN SEER	NIN SEER	CALC BTU HNH	EAT BTU	LAT BTU	FUEL TYPE	GAS IMPT	GAS OUT	NIN GAS PRESS	MAX GAS PRESS	NIN AFUE	EMERGENCY	ACCESSORIES	CONNECTION MARK	ELECTRIC CONNECTION SUMMARY	CM TYPE	CM FURNISHED BY	CM INSTALLED BY	CM INSTALLED BY	CM TYPE	CM FURNISHED BY	CM INSTALLED BY	CM WIRED BY	DC TYPE	DC FURNISHED	DC INSTALLED BY	DC WIRED BY	FA SHUTDOWN	REQUIRED TO TEST FAULT CURRENT	FAULT CURRENT	EMERGENCY	MARK
EXTTU	PACKAGED ROOFTOP UNIT, GAS HEAT	TRANE	YHD150P3RH01	1514	23 74 33.00	SALES	EXISTING	4000	1000	410.28	1	2.08	12.5	147.38	106.45	80	66	55	54	14.0	11.0	113.01	57	90	NATURAL GAS	250	203	4.5	14	81	NO	2,3,4,21	RTU-1	RTU-1 - 208V/3PH, 64 MCA, 80A OCP	LOW	HC	HC	HC	ECN	HFR	HFR	HFR	--	EC	EC	EC	DUCT	TRUE	RTU-1-3493	FALSE	RTU-1
RTU-2	PACKAGED ROOFTOP UNIT, GAS HEAT	TRANE	YSK048AS3SL	812	23 74 33.00	BOM	NEW	1470	306	177.29	1	0.8	4	47.81	36.86	80	66	55	54	14.0	12.0	47.72	58	90	NATURAL GAS	80	64.8	4.5	14	81	NO	2,3,4,21	RTU-2	RTU-2 - 208V/3PH, 29 MCA, 40A OCP	LOW	HC	HC	HC	ECN	HFR	HFR	HFR	--	EC	EC	EC	DUCT	TRUE	RTU-2-1915	FALSE	RTU-2

**ACCESSORIES:**

1. MOTOR DAMPER
2. ECONOMIZER
3. ROOF CURB
4. HAIL GUARDS

5. INTAKE HOOD
6. VIBRATION ISOLATION
7. FLAT FILTER
8. FILTER/MIXING BOX

9. ACCESS DOOR  
10. FLEX CONNECTIONS  
11. MOUNTING COLLAR  
12. HOT GAS BYPASS

- 13. FACE/BYPASS DAMPER
- 14. CONDENSATE PUMP
- 15. MOTOR GUARD
- 16. GREASE TRAP

- 17. DUCT FLANGES
- 18. BASE RAIL
- 19. HUMIDIFIER
- 20. CO2 SENSORS

- 21. ECON POWERED EXHAUST
- 22. ECON BAROMETRIC RELIEF
- 23. HOT GAS REHEAT COIL
- 24. SHAFT GROUNDING BRUSHES



OWNERSHIP OF INSTRUMENTS OF SERVICE  
The Consultant shall retain the property of the Consultant. The Consultant shall retain all common law, statutory and other reserved rights, including, without limitation, the copyright thereto.

OWNERSHIP OF INSTRUMENTS OF SERVICE  
The Consultant shall retain the property of the Consultant. The Consultant shall retain all common law, statutory and other reserved rights, including, without limitation, the copyright thereto.

STANDARD PLUMBING ABBREVIATIONS			
AAV	AIR ADMITTANCE VALVE	HW	DOMESTIC HOT WATER
AD	AREA DRAIN	HWR	HOT WATER RETURN
AFF	ABOVE FINISHED FLOOR	IE	INVERT ELEVATION
AFG	ABOVE FINISHED GRADE	IN WC	INCH WATER COLUMN
ANSI	AMERICAN NATIONAL STANDARDS INSTITUTE	KW	KILOWATT
APPROX	APPROXIMATE	KWH	KILOWATT HOUR
ASPE	AMERICAN SOCIETY OF PLUMBING ENGINEERS	LPG	LIQUID PROPANE GAS
AV	ACID VENT	LV	LAVATORY
AW	ACID WASTE	MAU	MAKEUP AIR UNIT
BAS	BUILDING AUTOMATION SYSTEM	MAX	MAXIMUM
BFP	BACKFLOW PREVENTER	MBH	1000 BTUH
BT	BATHTUB	MH	MANHOLE
BTU	BRITISH THERMAL UNIT	MIN	MINIMUM
BTUH	BRITISH THERMAL UNIT PER HOUR	MOC	MAXIMUM OVERCURRENT PROTECTION
BWV	BACK WATER VALVE	MS	MOP SINK
CA	COMPRESSED AIR	MV	MIXING VALVE
CB	CATCH BASIN	N	NITROGEN
CFH	CUBIC FEET PER HOUR	NC	NORMALLY CLOSED
CFM	CUBIC FEET PER MINUTE	NIC	NOT IN CONTRACT
CI	CAST IRON	NO	NITROUS OXIDE
CO	CLEAN OUT	NOM	NOMINAL
CO2	CARBON DIOXIDE	NTS	NOT TO SCALE
CP	CIRCULATION PUMP	O	OXYGEN
CW	DOMESTIC COLD WATER	OC	OVER CURRENT PROTECTION
DF	DRINKING FOUNTAIN	OD	OVERFLOW DRAIN
DI	DEIONIZED WATER	OI	OIL INTERCEPTOR
DIA	DIAMETER	PC	PLUMBING CONTRACTOR
DN	DOWN	PRV	PRESSURE REGULATING VALVE
DS	DOWNSPOUT	PSI	POUNDS PER SQUARE INCH
DSN	DOWNSPOUT NOZZLE	RD	ROOF DRAIN
EC	ELECTRICAL CONTRACTOR	RH	ROOF HYDRANT
ET	EXPANSION TANK	RO	REVERSE OSMOSIS
EW	ELECTRIC WATER COOLER	RPZ	REDUCED PRESSURE ZONE VALVE
EW	ELECTRIC WATER HEATER	RTU	ROOF TOP UNIT
EX	EXISTING	S	SANITARY
F	FAHRENHEIT	SI	SOLIDS INTERCEPTOR
FCO	FLOOR CLEAN OUT	SK	SINK
FD	FLOOR DRAIN	SOFT	SOFT WATER
FFE	FINISHED FLOOR ELEVATION	SPEC	SPECIFICATION
FLA	FULL LOAD AMPERES	SQ FT	SQUARE FOOT (FEET)
FS	FLOOR SINK	ST	STORM PIPING
FT	FEET	TD	TRENCH DRAIN
FW	FILTERED WATER	TEMP	TEMPERATURE
G	GAS	FEET	THERMOSTATIC MIXING VALVE
GCO	GRADE CLEAN OUT	TP	TRAP PRIMER
GWH	GAS FIRED WATER HEATER	UH	UNIT HEATER
GI	GREASE INTERCEPTOR	UR	URINAL
GPD	GALLONS PER DAY	VAC	VACUUM
GPH	GALLONS PER HOUR	VFD	VARIABLE FREQUENCY DRIVE
GPM	GALLONS PER MINUTE	VP	VACUUM PUMP
GPR	GAS PRESSURE REGULATOR	VTR	VENT THRU ROOF
GW	GREASE WASTE	WAGD	WASTE ANESTHESIA GAS
H&CW	HOT & COLD WATER	WB	WASHER BOX
HB	HOSE BIBB	WC	WATER CLOSET
HC	HVAC CONTRACTOR	WCO	WALL CLEAN OUT
HD	HUB DRAIN	WH	WALL HYDRANT
HP	HORSEPOWER	WF	WATER FILTER
		YH	YARD HYDRANT



KOHR'S LONNEMANN HEIL ENGINEERS, INC.  
MECHANICAL/ELECTRICAL ENGINEERS  
WWW.KLHENGERS.COM

1538 ALEXANDRIA PIKE, SUITE 11  
FT. THOMAS, KENTUCKY 41075  
800-354-9783  
859-442-8050  
859-442-8058 FAX

LEXINGTON, KENTUCKY  
LOUISVILLE, KENTUCKY  
COLUMBUS, OHIO  
KLH JOB #: 27551



rgla solutions, inc.

5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com

NO.	REVISIONS: BID, LL REVIEW, AND PERMIT	DATE: 06.18.25

robert g. lyon + associates, inc.

retail architecture


5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com



6/18/2025

SEAL:

THE ABOVE DRAWINGS AND SPECIFICATIONS AND SCALE  
DESIGNS AND ARRANGEMENTS REPRESENTED THEREBY  
ARE AND SHALL REMAIN THE PROPERTY OF THE OFFICE  
AND NO PART THEREOF SHALL BE COPIED, DISCLOSED TO  
OTHERS OR USED IN THE CONNECTION WITH ANY WORK OR  
PROJECT OTHER THAN THE SPECIFIC PROJECT FOR WHICH  
THEY HAVE BEEN PREPARED AND DEVELOPED WITHOUT  
THE WRITTEN CONSENT OF THIS OFFICE. VISUAL CONTACT  
WITH THESE DRAWINGS OR SPECIFICATIONS SHALL  
CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF  
THESE RESTRICTIONS. WRITTEN INQUIRIES ON THESE  
DRAWINGS SHALL HAVE PRECEDENCE OVER SCALED  
DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE  
RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON  
THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY  
DISCREPANCIES. SHOP DETAILS MUST BE  
SHOWN BY THESE DRAWINGS. SHOP DETAILS MUST BE  
SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE  
PROCEEDING WITH FABRICATION.  
© 2024 RGLA SOLUTIONS, INC.  
© 2024 ROBERT G. LYON & ASSOCIATES, INC.



SUMMIT WOODS CROSSING  
1744 NW CHIPMAN ROAD  
LEE'S SUMMIT, MO 64081

PLUMBING COVER SHEET

DRAWN BY
NMS
CHECKED BY
AJK
JOB NUMBER
25303
SHEET NAME
P-001



















### FIELD VERIFY ALL CONDITIONS

DESIGN DRAWINGS ARE SCHEMATIC. THIS CONTRACTOR SHALL VISIT THE SITE PRIOR TO BIDDING OR AWARD OF CONTRACT TO INSPECT EXISTING FIELD CONDITIONS. THIS CONTRACT SHALL INCLUDE ALL LABOR AND MATERIALS NECESSARY FOR FIELD MODIFICATIONS DUE TO EXISTING CONDITIONS.

THE CONTRACTOR SHALL CONTACT THE ARCHITECT, ENGINEER OR OWNER PRIOR TO BIDDING FOR INTERPRETATIONS AND CLARIFICATIONS OF THE DESIGN AND INCLUDE IN HIS BID ALL COSTS TO MEET THE DESIGN INTENT. CLARIFICATIONS MADE BY THE ARCHITECT, ENGINEER OR OWNER AFTER BIDDING WILL BE FINAL AND SHALL BE IMPLEMENTED AT CONTRACTORS COST.


BIDDING CONTRACTORS SHALL HAVE A WORKING KNOWLEDGE OF LOCAL CODES AND ORDINANCES AND SHALL INCLUDE IN THEIR BIDS THE COSTS FOR ALL WORK INSTALLED IN STRICT ACCORDANCE WITH GOVERNING CODES, THE PLANS AND SPECIFICATIONS NOT WITHSTANDING. THE CONTRACTOR SHALL ALERT ARCHITECT, ENGINEER OR OWNER OF ANY APPARENT DISCREPANCIES BETWEEN GOVERNING CODES AND DESIGN INTENT.

### PLUMBING LEGEND


SYMBOL	DESCRIPTION
PIPING LINE TYPES	
	SANITARY WASTE PIPING
	VENT PIPING
	DOMESTIC COLD WATER PIPING
	DOMESTIC HOT WATER PIPING (140°F)
	NATURAL GAS PIPING
ELECTRONIC DRAWING REQUEST	
ELECTRONIC COPIES OF THESE DRAWINGS MAY BE REQUESTED AT: APPS.KLHENGERS.COM/DRAWINGREQUESTS.	
PLUMBING ACCESSORIES	
	UNION
	PRESSURE GAUGE
	THERMOMETER
	EXPANSION TANK
PIPE VALVES	
	SHUT-OFF VALVE
	CHECK VALVE
	BALANCING VALVE
	DOUBLE CHECK VALVE BACKFLOW PREVENTER
PLUMBING SYMBOLS	
	PIPE UP
	PIPE DOWN
	PIPE TEE DOWN
	PIPE TEE UP
	CONNECT TO EXISTING (FIELD VERIFY EXISTING UTILITY SERVICE TYPE, PRIOR TO MAKING CONNECTION)




OWNERSHIP OF INSTRUMENTS OF SERVICE  
All data, notes, and other documents and instruments prepared by this Consultant as instruments of service shall remain the property of the Consultant. The Consultant shall retain all common law, statutory and other reserved rights, including, without limitation, the copyright therein.



1 ENLARGED PLUMBING SANITARY AND VENT PLAN  
1/2" = 1'-0"



2 ENLARGED PLUMBING WATER PLAN  
1/2" = 1'-0"



3 PLUMBING WATER & GAS PLAN - ROOF  
1/8" = 1'-0"

KEYED NOTES	
P01	DEMOLISH EXISTING COLD/HOT WATER SERVING EXISTING RESTROOM TO BE DEMOLISHED.
P02	NEW FIXTURE TO REPLACE EXISTING FIXTURE. EXTEND AND CONNECT NEW PIPING AS NECESSARY FOR REPLACEMENT. FIELD VERIFY EXISTING PIPE MATERIAL TYPE, SIZE, AND LOCATION PRIOR TO MAKING CONNECTION. REFER TO AND COORDINATE WITH ARCHITECTURAL DRAWINGS FOR PRECISE DIMENSIONS OF INTENDED LOCATION.
P03	PROVIDE NEW ASSE 1070 RATED THERMOSTATIC MIXING VALVE.
P04	EXTEND DOMESTIC WATER TO EXISTING 3/4" MIN. WATER MAIN. PROVIDE SHUT-OFF, BACKFLOW PREVENTER, PRESSURE REGULATING VALVE, METER, AND REMOTE READER IF REQUIRED. INSULATE ENTIRE LINE WITHIN BUILDING. FIELD VERIFY EXACT LOCATION OF EXISTING DOMESTIC WATER PRIOR TO INSTALLING ANY PIPING. REPORT DIFFERENCES TO ENGINEER PRIOR TO PROCEEDING WITH CONSTRUCTION.
P05	CONNECT NEW SANITARY PIPING TO NEAREST EXISTING 4" MINIMUM SANITARY MAIN. FIELD VERIFY EXACT LOCATION, INVERT, DIRECTION OF FLOW, AND SYSTEM TYPE PRIOR TO STARTING WORK. CONTACT ENGINEER WITH ANY DIFFERENCES OTHER THAN WHAT IS SHOWN ON PLAN. PROVIDE CAMERA SCOPING TO ENSURE PIPING SIZES AND LOCATION.
P06	CONNECT NEW VENT PIPING TO NEAREST EXISTING VENT MAIN. FIELD VERIFY EXACT LOCATION, INVERT, MATERIAL, SIZE AND SYSTEM TYPE PRIOR TO STARTING WORK. CONTACT ENGINEER WITH ANY DIFFERENCES OTHER THAN WHAT IS SHOWN ON PLAN.
P07	EXTEND AND CONNECT PREVIOUSLY EXISTING RTU NATURAL GAS SUPPLY PIPING TO NEW RTU.
P08	EXISTING WATER HEATER TO REMAIN AND SERVE EXISTING RESTROOM. 3/4" MIN. COLD AND HOT WATER MAINS TO REMAIN AND CONNECT TO NEW REPLACEMENT FIXTURES.
P09	EXISTING VENT AND SANITARY PIPING SERVING EXISTING EXISTING RESTROOM TO BE DEMOLISHED.

Pipe Type Legend		
Mark	System Name	Pipe Material
C1.6	C1 - Domestic Cold Water	6 - Copper - Type L - ASTM B88
S1.19	S1 - Sanitary	19 - PVC - Schedule 40 - ASTM D1785/D2665
V1.19	V1 - Vent	19 - PVC - Schedule 40 - ASTM D1785/D2665

**KLH ENGINEERS**  
KOHRS LONNEMANN HEIL ENGINEERS, INC.  
MECHANICAL/ELECTRICAL ENGINEERS  
WWW.KLHENGERS.COM

1538 ALEXANDRIA PIKE, SUITE 11  
FT. THOMAS, KENTUCKY 41075  
800-354-9783  
859-442-8050  
859-442-8058 FAX  
LEXINGTON, KENTUCKY  
LOUISVILLE, KENTUCKY  
COLUMBUS, OHIO  
KLH JOB #: 27551

**RGLA**  
r gla solutions, inc.

5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com

NO.	REVISIONS:	DATE:
	BID, LL REVIEW, AND PERMIT	06.18.25

**robert g. lyon + associates, inc.**  
retail architecture

5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com

STATE OF MISSOURI  
ROBERT A. LONNEMANN  
NUMBER PE-2003008449  
PROFESSIONAL ENGINEER  
6/18/2025  
SEAL:

THE ABOVE DRAWINGS AND SPECIFICATIONS AND SCALE, DESIGN AND ARRANGEMENTS REPRESENTED THEREBY ARE AND SHALL REMAIN THE PROPERTY OF THIS OFFICE AND NO PART THEREOF SHALL BE COPIED, DISCLOSED TO OTHERS OR USED IN THE CONNECTION WITH ANY WORK OR PROJECT OTHER THAN THE SPECIFIC PROJECT FOR WHICH THEY HAVE BEEN PREPARED AND USED. ANY VIOLATION OF THE WRITTEN CONSENT OF THIS OFFICE, VISUAL CONTACT WITH THESE DRAWINGS OR SPECIFICATIONS SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS. WRITTEN DIMENSIONS ON THESE DRAWINGS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY DISCREPANCIES FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS. SHOP DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE PROCEEDING WITH FABRICATION.  
© 2024 RGLA SOLUTIONS, INC.  
© 2024 ROBERT G. LYON & ASSOCIATES, INC.

**carhartt**  
SUMMIT WOODS CROSSING  
1744 NW CHIPMAN ROAD  
LEE'S SUMMIT, MO 64081

PLUMBING PLANS

DRAWN BY
NMS
CHECKED BY
AJK
JOB NUMBER
25303
SHEET NAME
P-101



OWNERSHIP OF INSTRUMENTS OF SERVICE  
The Consultant shall retain the property of the Consultant. The Consultant shall retain all common law, statutory and other reserved rights, including, without limitation, the copyright therein.

**SECTION 22 05 00.00 - COMMON WORK RESULTS FOR PLUMBING GENERAL.**

The General Provisions of the Contract including the General and Supplemental Conditions and General Requirements apply to the work in this section. Before submitting a bid, examine documents of all other trades, visit the site and get acquainted with all conditions that may in any way affect the execution of this contract. Contractor shall obtain and pay for all permits, certificates of inspection and approvals required. Submittal of a bid indicates that the contractor has examined the drawings, specifications, and had an opportunity to visit the site to be able to provide a comprehensive complete bid to include providing all materials, labor, tools, and equipment required to provide complete plumbing systems as outlined in Division-22. Clearly state all full lead amps (FLA), voltages and model numbers on all submittals. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories. Provide wiring diagrams: For power, signal, and control wiring.

**APPLICABLE STANDARDS**

The installation of all plumbing work shall conform to all the following, but not limited, applicable local and municipal utility standards, rules and regulations, plumbing codes and statutes having jurisdiction. All plumbing fixtures, equipment, accessories, and appearances shall be NSF/ANSI 61-372 compliant. 2018 International Building Code.

2018 International Plumbing Code; American Society for Test Materials (ASTM); National Sanitation Foundation (NSF); American Standards Association (ASA); Underwriters Laboratories (UL); National Fire Protection Association (NFPA); National Electric (NEC).

**PLANS AND SPECIFICATIONS**

Obtain the latest owner design and construction standards document(s). Comply with all owner-specific requirements in addition to requirements set forth in these specifications and accompanying drawings. Should there be a conflict, the owner's standards shall take precedence, unless prevailing codes and regulations mandate otherwise.

The drawings that accompany these specifications are diagrammatic. Wherever possible make use of submittal data and verify all dimensions on site. Provide additional fittings as required by site conditions and codes at no additional cost to conform to the structure, avoid obstructions, provide required service clearances and preserve headroom. Do not scale from drawings, all measurements should be taken in the field.

**EXISTING CONDITIONS**

Where new plumbing systems are required to be connected to existing plumbing systems, provide all camera scoping and dye testing necessary to verify the exact location, size, invert elevation, pressure, pipe integrity, and system type to ensure a proper connection is executed. The contractor shall notify the engineer immediately if it is found a proper connection cannot be executed.

**CUTTING, PATCHING AND DEMOLITION**

The contractor shall be responsible for damages to the grounds, walks, road, building, piping systems, electrical systems, and their equipment and contents, caused by leaks in the piping systems being installed or having been installed by him. The contractor shall repair at his expense all damaged so caused. All repair work shall be done as directed by and in such manner as satisfactory to the architect.

Owner reserves the right to make emergency repairs as required to keep equipment in operation without voiding the contractor's guarantee bond nor relieving the contractor of his responsibilities during the bonding period. Cut and drill all openings in roofs, walls, and floors required for the installation. Neatly patch all openings cut. Hold cutting and patching to a minimum by arranging with other contractors for all sleeves and openings before construction is started. When drilling/cutting concrete slabs, utilize ground penetrating radar (GPR) and/or X-ray scanning equipment to verify the location is free from obstructions, including but not limited to: structural rebar/strands/tendons, electrical conduit/wiring, and/or piping/ductwork.

**EXCAVATION AND BACKFILL**

Perform all excavation and backfilling required for this work. Contractor shall consult with utility company prior to beginning excavation. At a minimum, all piping shall be laid on a bed of sand, 6" deep, well tamped into place and properly graded to permit the pipe to have an even bearing throughout its entire length. Sand shall be installed around the piping in 6" lifts to a point 6" above the piping.

**WARRANTY**

This contractor shall warrant that all work under this section shall be free of defective work, materials and parts for a period of one year after acceptance of the work and shall repair, revise, and replace, at no cost to the owner, any such defects occurring within the warranty period. Use of Electronic Drawings from the Owner's Design Team If expressly permitted by the Owner and the terms of the Contract, editable electronic drawings may be made available for the creation of shop and as-built drawings upon request. Drawings will be made available at the discretion of the Engineer. "Request Drawings" form can be accessed, filled out and submitted at <http://www.klhengrs.com> (right hand side of page - Contractor Resources). Direct access to this form can be found here: <http://files.klhengrs.com/requestdrawings.html>

**22 05 03.00 - SUBMITTALS FOR PLUMBING**

Provide submittals in accordance with the Contract Documents. In addition to Division 01, the Contractor is advised to review and comply with the requirements articulated within each Division and within each section of that Division.

Some Divisions may include a division-specific "Submittal Requirements for ..." section. Where this section exists, it articulates additional requirements for submittals that apply to the work of that Division. The following requirements help to identify, track and keep the project organized for all parties involved. They are necessary to ensure a timely turnover and an appropriate technical review. Submittals that do not conform to the administrative requirements are rejected and returned, without technical review. Supply submittals for each section: Submittals shall be supplied on a section-by-section and type-by-type basis. For example, independent product data submittals shall be furnished for each section that requires product data submittals. Independent shop drawing submittals shall be furnished for each section that requires shop drawings.

Separate PDF file packages shall be supplied for each section, for each submittal type. Each PDF shall represent a single standalone submittal.

Include a transmittal: Transmittals shall enumerate each submittal for each section of each type and iteration. Include cover sheet / title page: The cover sheet shall include the information identified in the contract documents. It shall be included as the first page of each electronic and/or hardcopy document-based submittal. An editable and printable PDF form created with editable fields and specific information appearance is available from KLH upon request. It is also downloadable from the KLH website at [www.klhengrs.com](http://www.klhengrs.com). Include an index: The index shall enumerate the contents of the submittal. Include checklists: Where checklists are included with the specifications, complete and include them within the appropriate submittal. Supply complete submittals: Complete submittals of each type are required. Partial submittals will be rejected. Where a section requires a product data submittal, all product data for that section shall be supplied together, at one time, as one complete submittal. When resubmittal is required (e.g. Revise and Resubmit) the revised submittal shall be more complete, more accurate and more contract-compliant than its rejected predecessor. The submittal number (for each section and type) shall increment for each subsequent submittal (00 – Original submission, 01 – First Resubmission, 02 – Second Resubmission, etc...).

Resubmittals shall include a copy of the reviewers comments supplied with the prior submittal rejection and shall be amended with a description of the specific action taken to comply with the reviewer's comments. The absence of this on resubmittal is cause for rejection. Name electronic files to match the submittal ID and cover sheet: The electronic file name of submittals shall match the submittal ID included on the submittals cover page. For example, The original/first product data submittal for Section 220523 would be labeled as "220523.00-PD-00"; the first resubmittal of same shall be labeled "220523.00-PD-01". The original/first shop drawings submittal file for the same section would be labeled "220523.00-SD-00"; the first resubmittal of same shall be labeled "220523.00-SD-01".

If expressly permitted by the Owner and the terms of the Contract, editable electronic drawings may be made available for the creation of shop and as-built drawings upon request. Drawings will be made available at the discretion of the Engineer. "Request Drawings" form can be accessed, filled out and submitted at <http://www.klhengrs.com> (right hand side of page - Contractor Resources). Direct access to this form can be found here: <http://files.klhengrs.com/requestdrawings.html>

**22 05 17.00 – SLEEVES AND SLEEVE SEALS FOR PLUMBING PIPING**

**SLEEVES**

Steel Pipe: ASTM A 53, Type E, Grade B, Schedule 40, galvanized, plain ends.

**EXECUTION**

Install steel pipe sleeves two sizes larger than pipes passing through floors, rated walls, building foundation walls or masonry construction. Sleeves are not required for core drilled holes.

For sleeves that will have sleeve-seal systems installed, select sleeves of size large enough to provide 1-inch annular clear space between piping and concrete slabs and walls.

Install sleeves in concrete floors, concrete roof slabs, and concrete walls as new slabs and walls are constructed. Permanent sleeves are not required for holes in slabs formed by molded-PE or -PP sleeves.

Cut sleeves to length for mounting flush with both surfaces.

Exception: Extend sleeves installed in floors of mechanical equipment areas or other wet areas 2 inches above finished floor level.

Using grout, seal the space outside of sleeves in slabs and walls without sleeve-seal system.

Install sleeves for pipes passing through interior partitions. Cut sleeves to length for mounting flush with both surfaces.

Install sleeves that are large enough to provide 1/4-inch annular clear space between sleeve and pipe or pipe insulation.

Seal annular space between sleeve and piping or piping insulation: use joint sealants appropriate for size, depth, and location of joint.

Seal sleeves and piping with material rating equivalent to the wall rating. Maintain indicated fire rating of walls, partitions, ceilings, and floors at pipe penetrations. Seal pipe penetrations with firestop materials where required.

**22 05 23.00 - GENERAL DUTY VALVES**

**Submittal Requirements**

Product Data: For each type of product indicated.

**GENERAL**

Provide stops or isolation valves on domestic water supplies to isolate hot and cold water to each fixture, including all equipment and equipment provided by others. Access shall be provided to all valves. Provide fire-rated access panel(s) to maintain full access to concealed valves.

Ball valves - 2 inch and smaller: Lead-Free, 150 psi @ 250°F minimum pressure rating, cast bronze body, blowout-proof stem. Butterfly Valves - 3" and up: Ductile Iron Butterfly Valve, 200 WOG, Lug Body, Lever Operator.

Approved Manufacturers: Milwaukee Valve, NIBCO, and Watts Water Technologies Co.

Valves to conform to: MSS-SP-110 Type II MSS-SP-67 Type I, NSF/ANSI -61/372. Check valves - to be same size as system piping it accompanies. Lead-free, bronze body, 250 WOG, non-shock, spring check valve. Conforms to the following standard(s): MSS-SP-80 I, NSF/ANSI -61/372

**22 05 29.00 – HANGERS AND SUPPORTS FOR PLUMBING PIPING AND EQUIPMENT**

**GENERAL**

Provide hangers, supports, clamps, attachments, and structural steel members where required to support piping and equipment from building structure.

Support of piping from the decking or equipment is prohibited.

Arrange for grouping of parallel runs of horizontal piping supported together on field-fabricated, heavy-duty trapeze hangers where possible. Trapeze hangers shall conform to: MSS SP-69, Type 59. Horizontal-Piping Clamps: Provide Carbon- or Alloy-Steel, Double-Bolt Pipe Clamps (MSS Type 3) for suspension of pipes requiring clamp flexibility and up to 4 inches of insulation. Vertical-Piping Clamps: Provide extension pipe or Riser Clamps (MSS Type 8) for support of pipe risers. Hangers shall be sized to allow insulation to pass through unobstructed.

Hanger and support types:

Hangers: Provide adjustable, Steel Clevis Hangers (MSS Type 1) for suspension of noninsulated or insulated, stationary pipes.

Horizontal-Piping Clamps: Provide Carbon- or Alloy-Steel, Double-Bolt Pipe Clamps (MSS Type 3) for suspension of pipes requiring clamp flexibility and up to 4 inches of insulation.

Vertical-Piping Clamps: Provide extension pipe or Riser Clamps (MSS Type 8) for support of pipe risers. Hangers and supports shall be placed at all changes in direction, valves and equipment.

The maximum horizontal spacing of cast-iron pipe hangers can be 10' where 10-foot lengths of pipe are installed. Piping shall also be supported at each change in direction, valves and equipment.

Clevis-type hangers shall and supports shall conform to: MSS SP-58, Type 1-58.

**22 05 53.00 - IDENTIFICATION FOR PLUMBING PIPING AND EQUIPMENT PIPING**

Provide self-adhesive pipe labels with white background and black lettering, contact type with permanent adhesive backing. Include identification of piping service using same designations or abbreviations as used on the drawings and an arrow indicating flow direction.

**EQUIPMENT**

Provide self-adhesive plastic equipment labels with white background and black lettering, contact type with permanent adhesive backing, 160 degree F temperature. Include equipment's drawing designation and specification section number where equipment is specified.

**22 07 19.00 – PLUMBING SYSTEM INSULATION GENERAL**

Insulation shall be listed and labeled per ASTM E 84 for plenum installations employing slip on techniques. Provide insulation materials, accessories, and finishes with smooth, straight, and even surfaces; free of voids throughout the length of piping including fittings, valves, and specialties.

Surface Preparation: Clean and dry surfaces to receive insulation. Remove materials that will adversely affect insulation application. PIPING SYSTEMS REQUIRING INSULATION Insulate domestic cold water piping, associated fittings and valves with flexible elastomeric 1/2" wall thickness insulation.

Insulate domestic hot water piping, associated fittings and valves with 1" thick flexible elastomeric, 1-1/2" thick fiberglass insulation or per local energy code, whichever greater.

Insulate waste piping above ceilings that receive condensate with 1/2" wall thickness insulation.

Insulate exposed sanitary drains, domestic water, domestic hot water, and stops for plumbing fixtures for people with disabilities.

Insulate exposed sanitary drains, domestic water, domestic hot water, and stops for plumbing fixtures for people with disabilities.

Insulate exposed sanitary drains, domestic water, domestic hot water, and stops for plumbing fixtures for people with disabilities.

Insulate exposed sanitary drains, domestic water, domestic hot water, and stops for plumbing fixtures for people with disabilities.

Insulate exposed sanitary drains, domestic water, domestic hot water, and stops for plumbing fixtures for people with disabilities.

Insulate exposed sanitary drains, domestic water, domestic hot water, and stops for plumbing fixtures for people with disabilities.

Insulate exposed sanitary drains, domestic water, domestic hot water, and stops for plumbing fixtures for people with disabilities.

Insulate exposed sanitary drains, domestic water, domestic hot water, and stops for plumbing fixtures for people with disabilities.

Insulate exposed sanitary drains, domestic water, domestic hot water, and stops for plumbing fixtures for people with disabilities.

Insulate exposed sanitary drains, domestic water, domestic hot water, and stops for plumbing fixtures for people with disabilities.

Insulate exposed sanitary drains, domestic water, domestic hot water, and stops for plumbing fixtures for people with disabilities.

Insulate exposed sanitary drains, domestic water, domestic hot water, and stops for plumbing fixtures for people with disabilities.

Insulate exposed sanitary drains, domestic water, domestic hot water, and stops for plumbing fixtures for people with disabilities.

Insulate exposed sanitary drains, domestic water, domestic hot water, and stops for plumbing fixtures for people with disabilities.

Insulate exposed sanitary drains, domestic water, domestic hot water, and stops for plumbing fixtures for people with disabilities.

Insulate exposed sanitary drains, domestic water, domestic hot water, and stops for plumbing fixtures for people with disabilities.

Insulate exposed sanitary drains, domestic water, domestic hot water, and stops for plumbing fixtures for people with disabilities.

Insulate exposed sanitary drains, domestic water, domestic hot water, and stops for plumbing fixtures for people with disabilities.

Insulate exposed sanitary drains, domestic water, domestic hot water, and stops for plumbing fixtures for people with disabilities.

Insulate exposed sanitary drains, domestic water, domestic hot water, and stops for plumbing fixtures for people with disabilities.

Insulate exposed sanitary drains, domestic water, domestic hot water, and stops for plumbing fixtures for people with disabilities.

Insulate exposed sanitary drains, domestic water, domestic hot water, and stops for plumbing fixtures for people with disabilities.

Insulate exposed sanitary drains, domestic water, domestic hot water, and stops for plumbing fixtures for people with disabilities.

Provide water pressure regulators where necessary to limit the incoming water pressure to 80 psi around the building. DOMESTIC WATER PIPING ABOVE GRADE: Hard copper tube, ASTM B 88, Type L; wrought-copper, solder-joint fittings; and soldered joints. Solder Filler Metals: ASTM B 32, lead-free alloys. Flux: ASTM B 813, water flushable. Type "L": copper pressure-seal joint; and pressure-seal joint systems. CATHODIC PROTECTION Provide dielectric insulation at points where copper or brass pipe comes in contact with ferrous piping, reinforcing steel or other dissimilar metal in structure.

**22 11 19.00 – DOMESTIC WATER PIPING SPECIALTIES Submittal Requirements**

Product Data: For each type of product indicated. Manufacturers: Subject to compliance with requirements, available products that may be incorporated into the work include, and are limited to, the following: Conbraco Industries, Inc., Watts Water Technologies Co., Zurn Industries, LLC., Thermomegatch, Acom Engineering Co., and Caleffi, N. America, MIFAB, Inc., Precision Plumbing Products, Inc., Sioux Chief Manufacturing Company, Inc., Jay R. Smith Mfg. Co., Provent Systems, Rector Seal.

DUAL CHECK VALVE BACKFLOW PREVENTER Provide a dual check valve backflow preventer that complies with ASSE 1022 at connection of domestic water supply to any permanently connected potable water dispensing equipment such as ice makers, coffee machines, and beverage dispensers or where indicated in the contract documents.

Beverage dispensing equipment backflow preventer Provide a continuous pressure backflow preventer with stainless steel body, threaded connections and complies with ASSE 1022.

BALANCING VALVES Provide balancing valves where required for proper balancing of water systems as shown on the contract documents.

Balancing valves shall be equal to Red-White Valve Corporation model 9517AB (NPT) or model 9519 (solder). Valve shall have brass body, globe valve regulation and isolation properties, fixed orifice design for precise measurement, integral memory stop to ensure repeatable setting, full shutoff without affecting memory settings, high and low pressure metering points, precision indicator windows, rugged top set hand-wheel assembly, pressure rating of 300 psi, and temperature rating of 15 deg. F to 250 deg. F.

VACUUM BREAKERS Vacuum breakers shall be equal to Watts model LF288A for piping connections or Watts LF8 series for hose connections. Vacuum breakers shall comply with ASSE 1001 for piped connections, ASSE 1011 for hose connections, bronze body and threaded connections with rough bronze finish.

STRAINERS Provide lead-free wye-pattern strainer rated for 125 psig minimum, bronze body, threaded connections, stainless steel screen with round perforations of 0.020 inch and pipe plug drain. Provide strainers on supply side of each pressure reducing valve, solenoid valve and pump.

WATER HAMMER ARRESTERS Provide water-hammer arresters in water piping according to PDI-WH 201. Standard: ASSE 1010 or PDI-WH 201.

Type: Metal bellows or copper tube with piston. Size: ASSE 1010, sizes AA and A through F, or PDI-WH 201, sizes a through F.

22 13 16.00 - SANITARY, WASTE AND VENT PIPING SYSTEM Submittal Requirements

Product Data: For each type of product indicated.

GENERAL Provide a complete soil, waste and vent system in the building and on the site as indicated on the drawings and as specified herein.

Above ground soil, waste and vent piping within buildings including soil stacks, vent stacks, horizontal branches, traps, and connections to fixtures and drains.

Underground building drain piping including mains, branches, traps, connections to fixtures and drains, and connections to stacks, terminating at connection to existing sanitary sewer.

INTERIOR PIPING ABOVE GRADE No-Hub cast iron soil, waste, and vent piping and fittings 1-1/2" and larger shall conform to ASTM A-888. Pipe couplings shall conform to ASTM C 1277 and C18P1 310. Piping alignment shall be as indicated on the drawings using approved wye branches or eight bands for direction changes and shall be surely supported or secured to maintain such alignment.

Soil, waste and vent piping smaller than 1-1/2" shall be Type "M" copper and conform to ASTM B-306.

BELT AND GRADE PIPING Solid wall schedule 40 PVC pipe and fittings 2" and larger shall conform to ASTM D 2665 / ASTM D 1785 DWV. Fittings shall conform to ASTM D 2665, made to ASTM D, DWV patterns and fit schedule 40 pipe.

Piping alignment shall be as indicated on the drawings using approved wye branches or eight bands for direction changes and shall be surely set and buried to maintain such alignment.

Soil, waste and vent piping smaller 1-1/2" and smaller below grade shall not be permitted.

Slope piping according to local codes.

Protection shall be given to all footings and other structural elements during underground work adjacent to such items. Refer to architectural and/or structural drawings for locations.

Vent all fixtures, connect branch vents to main vent risers at least six inches above flood rim of fixtures. Pitch vent lines back to soil or waste pipe, free of drops and sags. Cleanouts shall be full size of pipe up to 4", and 4" for larger sizes. For underground and concealed lines, provide cleanouts in accessible positions at each right angle turn and at intervals not to exceed fifty feet. In floors, install flush with finish floor with extension pipe from cleanout wye.

22 16 13.00 - NATURAL GAS PIPING SYSTEMS Submittal Requirements

Product Data: For each type of product indicated.

GENERAL Plumbing contractor shall be responsible for installing gas piping run-outs to all gas-fired equipment, including equipment supplied by the HVAC and electric contractors. Piping shall be installed full-size (as indicated on the drawings) to each units' gas inlet connection, burner, regulator, etc. Plumbing subcontractor shall provide gas

cock and make final connections. Connections to each gas-fired equipment item shall include a drip leg and shutoff gas cock. Comply with equipment manufacturer's instruction. For connections to gas-fired rooftop equipment, plumbing contractor shall be responsible for the roof penetration and shall install the gas piping through the roof in a location that has been coordinated with the HVAC contractor. BUILDING DISTRIBUTION PIPING:

All piping from meter/regulator to gas fired equipment connections shall be black steel. Steel Pipe: ASTM A 53/A 53M, black steel, Schedule 40, Type E or S, Grade B. Pipe size 2" and smaller: Malleable-Iron Threaded Fittings Malleable-Iron Threaded Fittings: ASME B16.3, Class 150, standard pattern. Press-Connect fittings: Carbon steel, cold-pressed, ANSI LC4/CSSA 6.32.

GENERAL DUTY VALVES: Metallic valves 2 inches and smaller shall comply with ASME B16.33, cold working pressure of 125 psig. Provide one-piece ball valves with bronze body, chrome-plated brass ball, blowout proof stem and seat, and bronze trim complying with MSS SP-110.

Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, and limited to, the following: Milwaukee valve, NIBCO, and Watts Water Technologies co.

22 30 01.00 - POINT OF USE THERMOSTATIC MIXING VALVES Submittal Requirements

Product Data: For each type of product indicated.

GENERAL Thermostatic mixing valves shall be provided for all public hand washing sinks and lavatories and shall be ASSE 1070 listed, lead free, sweat connections, 125 psi operating pressure and have integral checks. Set outlet temperature of thermostatic mixing valve to 105 degrees F.

Point-of-use thermostatic mixing valves shall be equal to Powers LFG480. Route tempered water to hot water side of sink and lavatories.

Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the work include, and are limited to, the following: Symmons, Acom Engineering, Powers, Bradley

22 40 00.00 - PLUMBING FIXTURES Submittal Requirements

Product Data: For each type of product indicated.

GENERAL Refer to plumbing fixture schedule and install per the manufacturer's installation and operation manual.

Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the work include, and are limited to, the following: American Standard, Kohler Co., Zurn Industries, LLC.

**KLH ENGINEERS**  
KOHRS LONNEMANN HEIL ENGINEERS, INC.  
MECHANICAL/ELECTRICAL ENGINEERS  
WWW.KLHENGRS.COM  
1538 ALEXANDRIA PIKE, SUITE 11  
FT. THOMAS, KENTUCKY 41075  
800-354-9783  
859-442-8050  
859-442-8058 FAX  
LEXINGTON, KENTUCKY  
LOUISVILLE, KENTUCKY  
COLUMBUS, OHIO  
KLH\_JOB # 27551

**rgla solutions, inc.**  
5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com

NO.	REVISIONS:	DATE:
	BID, LL REVIEW, AND PERMIT	06.18.25

**robert g. lyon + associates, inc.**  
retail architecture  
5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com

STATE OF MISSOURI  
ROBERT A. LONNEMANN  
NUMBER  
PE-200308049  
6/18/2025  
SEAL:


THE ABOVE DRAWINGS AND SPECIFICATIONS AND SEAL DESIGN AND ARRANGEMENTS REPRESENTED THEREBY ARE AND SHALL REMAIN THE PROPERTY OF THE OFFICE AND NO PART THEREOF SHALL BE COPIED, DISCLOSED TO OTHERS OR USED BY THE CONTRACTOR WITH ANY WORK OR PROJECT OTHER THAN THE SPECIFIC PROJECT FOR WHICH THEY HAVE BEEN PREPARED AND USED EXCEPT WITHOUT THE WRITTEN CONSENT OF THIS OFFICE. VISUAL CONTACT WITH THESE DRAWINGS OR SPECIFICATIONS SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS. WRITTEN UNDERSIGNED ON THESE DRAWINGS SHALL HAVE PRECEDENCE OVER SCALED UNDERSIGNED. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR THE ACCURACY OF ALL DIMENSIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY DISCREPANCIES IMMEDIATELY. SHOP DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE PROCEEDING WITH FABRICATION.  
© 2024 ROBERT G. LYON & ASSOCIATES, INC.

**carhartt**  
SUMMIT WOODS CROSSING  
1744 NW CHIPMAN ROAD  
LEE'S SUMMIT, MO 64081

**PLUMBING - SPECIFICATIONS**


DRAWN BY  
NMS  
CHECKED BY  
AJK  
JOB NUMBER  
253003  
SHEET NAME  
P-501






SCALE: NONE

A. PIPING ARRANGEMENTS SHOWN ARE SCHEMATIC. ADJUST TO SUIT ACTUAL CONDITIONS. MAKE FINAL CONNECTION TO EQUIPMENT AS RECOMMENDED BY MANUFACTURER




SCALE: NONE

1. GAS SUPPLY.
2. APPROVED GAS SHUT OFF VALVE.
3. APPROVED UNITS WITHIN 6'-0" OF APPLIANCE OR EQUIPMENT SERVED.
4. MINIMUM 6" LONG SEDIMENT TRAP WITH THREADED CAP. INSTALL CAP WITH PROPER CLEARANCE TO PROVIDE SERVICABILITY.
5. TO UNIT INLET CONNECTION.



SCALE: NONE

1. HANGER ROD.
2. GALVANIZED STEEL PIPE SHIELD AND 360° CALCIUM SILICATE INSULATION HANGER SUPPORT.
3. PIPE INSULATION.
4. PIPE.
5. UNISTRUT CHANNEL.
6. CLEVIS HANGER.
7. TRAPEZE PIPE HANGER.



SCALE: NONE




5100 River Road, Ste 125  
Schiller Park, IL 60176  
p: 847.671.7452  
f: 847.671.4200  
www.rgla.com

[illegible]

**ciates, inc.**  
a r c h i t e c t u r e

**robert g. lyon + associates, inc.**



THE ABOVE DRAWINGS AND SPECIFICATIONS ARE IDEAS, CONCEPTS AND MANAGEMENT'S REPRESENTATIONS THEREOF AND SHALL REMAIN THE PROPERTY OF THIS OFFICE, AND NO PART THEREOF SHALL BE COPIED, DISCLOSED TO OTHERS OR USED IN THE CONNECTION WITH ANY WORKS, PROJECTS OR CONTRACTS OF ANY KIND, FOR WHATEVER PURPOSE, WITHOUT THE WRITTEN CONSENT OF THIS OFFICE. USUAL CONTRACT PROVISIONS REGARDING INTELLECTUAL PROPERTY RIGHTS SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS. WRITTEN DIMENSIONS ON THESE DRAWINGS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS. THE ARCHITECT SHALL BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY DISCREPANCIES OR OMISSIONS PRIOR TO ANY CONSTRUCTION. ANY DISCREPANCIES SHOWN BY THESE DRAWINGS, SHOP DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE PROCEEDING WITH FABRICATION.

2024 RIGBY & LYON ASSOCIATES, INC.  
© 2024 RIGBY & LYON ASSOCIATES, INC.

carhartt 

SUMMIT WOODS CROSSING  
1744 NW CHIPMAN ROAD  
LEE'S SUMMIT, MO 64081

## PLUMBING - DETAILS & SCHEDULES

DRAWN BY

NMS

CHECKED BY \_\_\_\_\_

AJK

JOB NUMBER \_\_\_\_\_

2530

2330

SHEET NAME

D. 00-5

P-60-

MOP SINK SCHEDULE															
PRODUCT					GENERAL		MISC	VALVE/FAUCET INFORMATION			FIXTURE UNITS			FLOW INFORMATION	TRAP INFORMATION
MARK	DESCRIPTION	MANUFACTURER	MODEL	SECTION NUMBER	LOCATION	STATUS	ACCESSORIES	FIXTURE NPG	FIXTURE MODEL	DPU	WSFU	OW SFU	HW SFU	FLUID FLOW	INTEGRAL TRAP
MS1	MOP SINK	FIAT	MSB102424	22 40 00.00	REFER TO PLAN	NEW	--	FIAT	830AA	2	3	2.25	2.25	--	NO

PRODUCT					FLOW INFORMATION	GENERAL		HISC	VALVE/FAUCET INFORMATION				FIXTURE UNITS				TRAP INFORMATION
MARK	DESCRIPTION	MANUFACTURER	MODEL	SECTION NUMBER	GALLONS PER FLUSH (GPF)	LOCATION	STATUS	ACCESSORIES	FIXTURE FPG	FIXTURE MODEL	FPU	WPU	CU FPU	IN FPU	INTEGRAL TRAP		
WC1	TANK TYPE WATER CLOSET	ZURN	Z5560	22 40 00.00	1.6	--	NEW	FURNISH ADA CLOSET AND TANK, ADA OPER FRONT SEAT, SELF SUSTAINING HINSE, FLOOR FLANGE, CLOSET BOLT AND CAPS, MAX 8 INGS, SUPPLY STOPS AND TUBE, FLUSH CONTROL MUST BE LOCATED ON THE VISE ACCESS SIDE OF THE WC (OPPOSITE OF THE WALL)	--	--	4	5	5	--	YES		

PRODUCT					GENERAL		NISC	VALVE/FAUCET INFORMATION				FIXTURE UNITS				FLOW INFORMATION	TRAP INFORMATION
MARK	DESCRIPTION	MANUFACTURER	MODEL	SECTION NUMBER	LOCATION	STATUS	ACCESSORIES	FIXTURE MPG	FIXTURE MODEL	DFU	MSFU	CM SFU	HM SFU	FLUID FLOW	INTEGRAL TRAP		
LV1	LAVATORY	AMERICAN STANDARD	0124024.020 CORRADE WALL-MOUNT SINK	22 40 00.00	REFER TO PLAN	NEW	FURNISH LAVATORY, SUPPLY STOPS AND TUBES, DRAIN AND AIR PIPING PROTECTION. PROVIDE TOUCHLESS FAUCET.	AMERICAN STANDARD	7025.103	1	2	1.5	1.5	--	NO		

PRODUCT						HISC		GENERAL		ELECTRICAL	DESIGN CONDITIONS		ELECTRICAL																PRODUCT	
MARK	DESCRIPTION	MANUFACTURER	MODEL	OPERATING VOLT (LBS)	SECTION NUMBER	ACCESSORIES	LOCATION	STATUS	EFFICIENCY	EMT	LMF	CONNECTION MARK	ELECTRIC CONNECTION SUMMARY	CN TYPE	CN FURNISHED BY	CN INST BY	CN WIRED BY	CN TYPE	CN FURNISHED BY	CN INST BY	CN WIRED BY	DC TYPE	DC FURNISHED	DC INST BY	DC WIRED BY	DC REQUIRED TO PERFORM FAULT CURRENT	FAULT CURRENT	EMERGENCY	MARK	
EX-MH	TANK TYPE GAS FIRED WATER HEATER	STATE	ES66S0MSK 200	80	22 34 00.00	6	EX	EX	EXISTING	..	40	140	EX-MH	EX-MH - 120V/PH, 1.650W HTG	EX	EX	EX	EX	..	..	..	..	..	EX	EX	EX	FALSE	EX-MH: ..	FALSE	EX-MH

PRODUCT					GENERAL		MISC	VALVE/FAUCET INFORMATION		FIXTURE UNITS				FLOW INFORMATION	TRAP INFORMATION	ELECTRICAL																PRODUCT	
MARK	DESCRIPTION	MANUFACTURER	MODEL	SECTION NUMBER	LOCATION	STATUS	ACCESSORIES	FIXTURE MFG	FIXTURE MODEL	DPU	MSPU	CU SPU	HW SPU	FLUID FLOW	INTEGRAL TRAP	CONNECTION MARK	ELECTRIC CONNECTION SUMMARY	CN TYPE	CN FURNISHED BY	CN INSTALLED BY	CN WIED BY	CN TYPE	NC FURNISHED BY	NC INSTALLED BY	NC WIED BY	DC TYPE	DC FURNISHED	DC INSTALLED BY	DC WIED BY	REQUIRED TO MEET FAULT CURRENT	FAULT CURRENT	EMERGENCY	MARK
DF1	DRINKING FOUNTAIN	ELKAY	L2SL6MSLK	22 40 00.00	REFER TO PLAN	NEW	WITH BOTTLE FILLER AND CANE APRON	--	--	0.5	0.25	0.25	--	0.13	NO	DF1	DF1 - 120V/1PH, 6A FLA	HAN	HFR	HFR	HFR	NG	HFR	HFR	HFR	CP	EC	EC	EC	FALSE	DF1: --	FALSE	DF1

**OWNERSHIP OF INSTRUMENTS OF SERVICE**  
All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by the Consultant as instruments of service shall remain the property of the Consultant. The Consultant shall retain all common law, statutory and other reserved rights, including, without limitation, the copyright thereto.