



## EAST HOSPITAL

# SAINT LUKE'S EAST HOSPITAL VAULT #2 LINEAR ACCELERATOR 100 NE SAINT LUKE'S BLVD. LEE'S SUMMIT, MO 64086

## PROJECT TEAM

### ARCHITECT

ACI BOLAND, INC.  
1710 WYANDOTTE STREET  
KANSAS CITY, MO 64108  
PHONE 816.763.9600



### STRUCTURAL ENGINEER

Professional Engineering Consultants  
623 Massachusetts Street, Suite 200  
Lawrence, KS 66044  
PHONE 785.842.6464

### STRUCTURAL ENGINEER

Structural Engineering Associates, Inc.  
1000 Walnut St, Suite 1570  
Kansas City, MO 64106  
PHONE 816.421.1042  
FAX 816.421.1061

## LOCATION PLAN



KEY PLAN

## SHEET INDEX

ARCHITECTURAL SHEETS	
A000	COVER SHEET
A010	PARTITION TYPES & DETAILS
AD201	ENLARGED DEMOLITION FLOOR PLAN
A220	ENLARGED PLAN
A320	ENLARGED REFLECTED CEILING PLAN
A701	FINISH FLOOR PLAN, SCHEDULES, LEGENDS, AND ELEVATIONS
A710	INTERIOR DETAILS


STRUCTURAL SHEETS	
S1.0	STRUCTURAL DETAILS

MECHANICAL, ELECTRICAL, PLUMBING SHEETS	
M-001	MECHANICAL COVER SHEET
M-101	FIRST FLOOR OVERALL PLAN
F-111	FIRST FLOOR FIRE PROTECTION ENLARGED PLAN
P-111	FIRST FLOOR PLUMBING ENLARGED PLAN
P-501	PLUMBING SCHEDULES & DETAILS
M-111	FIRST FLOOR MECHANICAL ENLARGED DEMO PLANS
M-112	FIRST FLOOR HVAC ENLARGED PLAN
M-501	HVAC SCHEDULES & DETAILS
E-001	ELECTRICAL GENERAL NOTES AND SYMBOLS
E-100	ELECTRICAL OVERALL PLAN
E-101	ELECTRICAL DEMOLITION PLAN
E-121	ELECTRICAL POWER PLAN
E-122	ELECTRICAL CONDUIT PLAN
E-132	ELECTRICAL LIGHTING PLAN
E-142	ELECTRICAL SYSTEMS PLAN
E-601	ELECTRICAL DETAILS
E-601	ELECTRICAL ONE-LINE DIAGRAM
E-611	ELECTRICAL SCHEDULES

VENDOR SHEETS	
V-1	VARIAN TRUEBEAM
V-2	VARIAN TRUEBEAM
V-3	VARIAN TRUEBEAM
VRT-1	VISION RT
VRT-2	VISION RT
ARJO-1	ARJO PATIENT LIFT
ARJO-2	ARJO PATIENT LIFT
ARJO-3	ARJO PATIENT LIFT
ARJO-4	ARJO PATIENT LIFT
ARJO-5	ARJO PATIENT LIFT
VAULT-1	NELCO VAULT DOOR
VAULT-2	NELCO VAULT DOOR
VAULT-3	NELCO VAULT DOOR
VAULT-4	NELCO VAULT DOOR
VAULT-5	NELCO VAULT DOOR
VAULT-6	NELCO VAULT DOOR

## ABBREVIATIONS

ABC	AGGREGATE BASE COURSE	G	GRAM	OBT	QUARRY BASE TILE
ACT	ACoustic CEILING TILE	GA	GAUGE	OT	QUARRY TILE
AC	AIR CONDITIONING	GAL V	GLASS V	QTZ	QUARTZ
ADD	ADDENDUM	GL	GLASS		
AF	ABOVE FINISH FLOOR	GLT	GLASS WALL TILE	R	RISER, RISERS
AG	AGGREGATE	GND	GROUND	RAD	RADIUS
ALT	ALTERNATE	GRL	GRILLE	RS	RESILIENT BASE
ALUM	ALUMINUM	GT	GROUT	RBF	RUBBER FLOOR
AP	ARCHITECT	GYP	GYPSPUM BOARD	RD	ROOF DRAIN
ARCH	ARCHITECTURAL SURFACE	GYP	GYPSPUM	REF	REFER TO
ASF	ASPHALT	H	HORSE BIB	REQ	REQUIRED
FINISH	FINISH	HOB	HARDWARE	REQD	REQUIRED
AWC	ACoustic WALLCOVERING	HOW	HARDWARE	RES	RESINOUS WALLCOVERING
AWP	ACoustic WALL PANEL	HM	HOLLOW METAL	REV	REVISION
@	AT	HM	HOLLOW METAL	RFG	ROOFING
		HORIZ	HORIZONTAL	RGM	ROUGH
BD	BOARD	HR	HANDRAIL	RND	ROUND
BLDG	BUILDING	HT	HEIGHT	RO	ROUGH OPENING
BLKG	BLOCKING	HTR	HEATER	RSF	RESILIENT SHEET FLOOR
BM	BEAM	HW	HOT WATER	RST	RUBBER STAIR TREAD
BO	BOTTOM OF	IB	INTEGRAL BASE	S	STAINLESS STEEL SINK
BR	BUMPER RAILS	IN	INCH	SC	SHOWER CURTAIN
BRG	BRUSHED CONCRETE	INCH	INCHES	SCHED	SCHEDULE
BSMT	BASEMENT	INSUL	INSULATION	SCN	SCREW
		INT	INTERIOR	SCT	SHOWER CURTAIN TRACK
CBT	CERAMIC BASE TILE	IS	INTEGRAL SINK	SDG	SECTION
CC	CUBICLE CURTAIN TRACK	JAN	JANITOR	SEL	SELECT
CEM	CEMENT/CEMENTITIOUS	JCT	JOINT	SE	SHEATHING
CER	CERAMIC	JST	JOIST	SHT	SHEET
CFT	CERAMIC FLOOR TILE	KP	KICK PLATE	SIM	SIMILAR
CHR	CHAIR RAIL	LAM	LAMINATED	SLDG	SLIDING
CHAN	CHANNEL	LAV	LAVATORY	SP	SAFETY PADDING
CIP	CAST IN PLACE	LB	POUND	SPEC	SPECIALTY CEILING
CJ	CONTROL JOINT	LG	LENGTH	SFF	SPECIFICATION
CL	CENTER LINE	LNM	LINEAL	SQ	SQUARE
CLG	CENTER LINE	LOC	LOCATION	SSE	SOLID SURFACE
CLOS	CLOSET	LT	LOCATION	SST	STAINLESS STEEL
CLP	COMPACT LAMINATE PANEL	LTV	LOUVER	STC	STANDARD
CLR	CLEAR	LWC	LIGHT WEIGHT CONCRETE	STD	STANDARD
CMU	CONCRETE MASONRY UNIT	M	METER	STN	STONE
COL	COLUMN	MAT	MATERIAL	STR	STRUCTURE
CONC	CONCRETE	MAX	MAXIMUM	SUSP	SUSPENDED
CONST	CONSTRUCTION	MB	MARKER BOARD	SW BD	SWITCHBOARD
CONT	CONTINUOUS	MECH	MECHANICAL	SYS	SYSTEM
CR	CRASH RAIL	MFR	MANUFACTURER		
CR	CONCRETE SEALER	MIN	MINIMUM	T	TREAD
CST	CULTURED STONE	MLDG	MOLDING	T8	TACK BOARD
CWT	CERAMIC WALL TILE	MO	MASONRY OPENING	TC	TOP OF CURB
		MOV	MOVABLE PARTITION	TCF	TEXTILE COMPOSITE FLOORING
DB	DECORATIVE GLASS PANEL	MT	METAL TRIM	TG	TEMPERED GLASS
DIA	DIAMETER	MTB	METAL BASE	TO	TOILET PARTITION
DIMG	DIMENSION	MTL	METAL	TR	TRANSITION STRIP
DISP	DISPENSER	MULL	MULLION	TRZ	TERRAZZO FLOORING
DN	DOWN	NF	NO FINISH	TSD	TOP OF STEEL DECK
DPC	DAMP PROOFING	NG	NATURAL GRADE	TUF	TURF
DPO	DYE D AND POLISHED	NOI	NOT IN CONTRACT	TV	TEACHERS WARDROBE TYPICAL</td
DR	DOWNPOUT	NOM	NOMINAL	TZB	TERRAZZO BASE
DWG	DRAWING	NTS	NOT TO SCALE	UNO	UNLESS NOTED OTHERWISE
EA	EACH	OBS	OBSOLETE	UPH	UPHOLSTERY
ELEC	ELECTRIC	OC	ON CENTER		
ELEV	ELEVATION	OPNG	OPENING	V	VENT
EQ	EQUAL	OVFL	OVERFLOW	VCT	VITREOUS CLAY PIPE
EQUIP	EQUIPMENT	OFS	OVERFLOW SCUPPER	VD	VERTICAL DRAIN
ETR	EXISTING TO REMAIN	OHD	OVERHEAD DOOR	VERT	VERTICAL
EW	ELECTRIC WATER COOLER	PBT	PORCELAIN BASE TILE	VEST	VESTIBULE
EXT	EXTERIOR	PCT	POLISHED CONCRETE	VET	VINYL ENHANCED TILE
EXPAN	EXPANSION	PDT	PAINT DETAIL	VGT	VINYL QUARTZ TILE
EXT	EXTERIOR	PFT	PORCELAIN FLOOR TILE	VW	VINYL WALLCOVERING
FA	FIRE ALARM	PL	PROPERTY LINE	WC	WALLCOVERING
FACP	FIRE ALARM CONTROL PANEL	PLAM	PLASTIC LAMINATE	WCT	WAINSCOT
FD	FLOOR DRAIN	PLBG	PLUMBING	WDB	WOOD BASE
FEC	FIRE EXTINGUISHER CABINET	PLYWD	PLYWOOD	WDC	WOOD CEILING
FHC	FIRE HOSE CAB	PNL	PANEL	WDF	WOOD FLOOR
FIN	FINISH	PR	PAIR	WDP	WOOD PANELS
FIKT	FIXTURE	PSE	POUNDS PER SQ FT	WDS	WOOD STAIR
FL	FLASHING	PSI	POUNDS PER SQ IN	WDV	WOOD VENEER
FLR	FLOOR	PSTR	PLASTER	WDM	WOOD MOLDING
FLR	FLOOR	PT-X	PAINT (No acronym after number always stands for eggshell finish)	WF	WATER FILM
FND	FOUNDATION	PT-XA	PAINT (X always stands for epoxy finish)	WH	WALK OFF CARPET
FR	FRAME	PT-XB	PAINT (B always stands for semi-gloss finish)	WOC	WALK OFF MAT
FRP	FIBERGLASS REINFORCED	PT-XC	PAINT (C always stands for flat finish)	WOP	WALL PROTECTION
FT	FEET / FOOT	PT-XD	PAINT (D as needed per project if not listed above)	WS	WALLGLASS SYSTEM
FTG	FOOTING	PTR	PARTITION	WTT	WINDOW TREATMENT
FV	FIELD VERIFY	PWT	PORCELAIN WALL TILE	WW	WELDED WIRE MESH
FVP	FABRIC WALL PANEL			WWM	WITH
				W/O	WITHOUT



First Floor Life Safety Plan - Building "F"  
1/16" = 1'-0"

## CODE FOOTPRINT LEGEND

PARTITION TYPES	
---	0 HR SMOKE PARTITION (SMOKE RESISTIVE)
----	1 HR SMOKE BARRIER
----	1 HR FIRE BARRIER
----	2 HR FIRE BARRIER
----	2 HR FIRE SMOKE BARRIER
----	3 HR FIRE BARRIER

## AREA DESIGNATIONS

---	CORRIDOR
---	HAZARDOUS ROOM
---	NOT IN ARCHITECTURAL SCOPE
---	EXIT ENCLOSURE
---	SHAFT






## SYMBOLS

96' / 100	OCCUPANT LOAD
60	LOAD FACTOR
12' / 36'	FIRE EXIT
60	OCCUPANT LOAD
12' / 36'	EXIT WIDTH PROVIDED
12' / 36'	EXIT WIDTH REQUIRED
FEC	NEW FIRE EXTINGUISHER CABINET
FEC	EXISTING FIRE EXTINGUISHER CABINET
124'	FIRE DOOR RATING
124'	TRAVEL DISTANCE

## CODE SUMMARY


<b>PROJECT CONSTRUCTION PURPOSE:</b> NEW LINEAR ACCELERATOR VAULT WITH CONTROL ROOM, TWO DRESSING ROOMS, AND NEW ADA RESTROOM. ALL CONSTRUCTION TO BE INTERIOR RENOVATION WORK OF EXISTING SHELL SPACE.	
<b>OWNER:</b> Saint Luke's East Hospital 100 NE Saint Luke's Blvd Lee's Summit, MO 64083	
<b>DESIGNER:</b> ACI BOLAND ARCHITECTS 1710 WYANDOTTE ST KANSAS CITY, MO 64108 PHONE: (816) 763-9600	
<b>LOCAL AUTHORITY:</b> RESPONDING FIRE SERVICE: CITY OF LEE'S SUMMIT MO LOCAL BUILDING INSPECTION: CITY OF LEE'S SUMMIT MO	
<b>CODE INFORMATION:</b> 2018 INTERNATIONAL BUILDING CODE 2018 INTERNATIONAL PLUMBING CODE 2018 INTERNATIONAL MECHANICAL CODE 2017 NATIONAL ELECTRICAL CODE (NFPA 70) 2018 INTERNATIONAL FIRE CODE 2012 LIFE SAFETY CODE (NFPA 101) CHAPTER 20 2009 ICC/ANSI A117.1 AS AMENDED AND ADOPTED BY THE CITY OF LEE'S SUMMIT 2010 ADA STANDARDS FOR ACCESSIBLE DESIGN / AMERICANS WITH DISABILITIES ACT OF 1990 STATE OF MISSOURI DEPT. OF HEALTH & ENVIRONMENT REFERENCES THE FOLLOWING CODES: 2012 NFPA 101 LIFE SAFETY CODE (LSC) 2018 FGI GUIDELINES FOR DESIGN & CONSTRUCTION OF HOSPITALS & OUTPATIENT FACILITIES 1978 19-CSR-30 NOTE: IF CODE REQUIREMENTS OVERLAP, THE MOST STRINGENT SHALL APPLY.	
<b>TYPE OF CONSTRUCTION:</b>	TYPE 1-A - SECTION 602.2 (TYPE 1 - 332 SPRINKLERED - SECTION 18.1.6.1)
<b>OCCUPANCY GROUP:</b>	I-2 - SECTION 308.3 (HEALTHCARE - SECTION 6.1.5)
<b>OCCUPANT LOAD:</b> TOTAL SQUARE FOOTAGE: 96' x 100' = 9,600 SF TOTAL NUMBER OF OCCUPANTS = 10	1,480+ SF 20'
<b>DEAD END CORRIDOR LENGTH LIMIT:</b>	20'
<b>EXIT ACCESS TRAVEL DISTANCE:</b>	200'
<b>AREA OF CONSTRUCTION:</b>	1,480+ SF
<b>REQUIRED FIRE RESISTANCE RATINGS (IN HOURS):</b> FIRE RATED GLASS & GLZ. EXTERIOR BEARING WALLS 3 HR INTERIOR BEARING WALLS 3 HR PRIMARY STRUCTURAL FRAME 3 HR FLOOR CONSTRUCTION 2 HR ROOF CONSTRUCTION 1 1/2 HR INTERIOR NON-BEARING WALLS 0 HR	
<b>PLUMBING FIXTURE CALCULATIONS:</b>	EXISTING TO REMAIN NO CHANGE IN OCCUPANCY
<b>ACTIVE FIRE SAFETY FEATURES:</b> - FIRE ALARM SYSTEM - THE FIRE ALARM SYSTEM IS SPECIFIED AS AN ADDRESSABLE TYPE SYSTEM. THE DEVICE TYPE AND LOCATIONS ARE PER THE APPLICABLE CODES AS WELL AS ADA REQUIREMENTS. - SMOKE CONTROL SYSTEM - ALL DUCTWORK PENETRATING SMOKE RATED WALLS WILL HAVE A SMOKE OR COMBINATION FIRE/SMOKE DAMPER AS INDICATED ON CONSTRUCTION DOCUMENTS. THESE DAMPERS WILL CLOSE UPON DETECTION OF SMOKE BY THE AREA SMOKE DETECTORS OR DUCT SMOKE DETECTORS IN THE AIR HANDLING UNITS. - FIRE SPRINKLER SYSTEM - SPECIFIED TO BE PER NFPA 13. THE SPRINKLER HEADS ARE SPECIFIED TO BE QUICK RESPONSE TYPE. - EMERGENCY LIGHTING AND POWER - EMERGENCY LIGHTING, LIFE SAFETY AND CRITICAL LOADS WILL RECEIVE POWER FROM A BACKUP GENERATOR LOCATED OUTSIDE THE MAIN ELECTRICAL ROOM. - ILLUMINATED EXIT SIGNS <b>PASSIVE FIRE SAFETY FEATURES:</b> - SMOKE COMPARTMENTS NO GREATER THAN 22,500 SF	











## PARTITION GENERAL NOTES

- UNLESS NOTED OTHERWISE, ALL INTERIOR METAL STUDS ARE 3/8" THICK. REFER TO SUFFIX SCHEDULE BELOW FOR LOCATIONS OF METAL STUDS OTHER THAN 3/8" THICK. NOTE: STUD THICKNESS (GAUGE) MUST CONFORM TO MANUFACTURER'S RECOMMENDATIONS FOR SPAN (HEIGHT OF STUD).
  - WHERE THE PARTITION TYPE INDICATION IS SHOWN WITH A NUMERICAL SUFFIX, THE METAL STUD THICKNESS SHALL BE AS SCHEDULED BELOW:
- | SUFFIX | MTL. STUD THICKNESS |
|--------|---------------------|
| 1      | 1-5/8" MTL. STUDS   |
| 2      | 2-1/2" MTL. STUDS   |
| 3      | 6" MTL. STUDS       |
- ALL STUDS ARE CONTINUOUS FROM FLOOR STRUCTURE TO CEILING STRUCTURE UNLESS NOTED OTHERWISE.
  - METAL STUDS ARE SPACED @ 16" O.C. MAX., UNLESS NOTED OTHERWISE.
  - UNLESS NOTED OTHERWISE, ALL GYPSUM BOARD IS TO BE 5/8" THICK "FIRECODE".
  - THE LOCATION OF A CHANGE IN THE PARTITION TYPE IS INDICATED BY A WALL TAG.
  - THE CORRESPONDING RATED ASSEMBLIES ARE INDICATED BELOW THE PARTITION TYPES.
  - PARTITION TYPE DESIGNATIONS ARE INDICATED ON THE FLOOR PLAN DRAWINGS.
  - PARTITION TYPES DO NOT INCLUDE APPLIED FINISHES CALLED FOR IN THE ROOM FINISH SCHEDULE.
  - AT PARTITION TYPES WHERE MTL. STUDS ARE EXPOSED ON ONE OR BOTH SIDES, CUT STUD 1/4" SHORT AND SCREW BOTH SIDES TO MTL. RUNNER TRACK.




## PARTITION TYPE DETAILS



## GENERAL NOTES

- ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH A.D.A. REQUIREMENTS AND ALL APPLICABLE LOCAL, STATE, AND FEDERAL BUILDING CODES AND REGULATIONS.
- THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL NECESSARY BUILDING PERMITS.
- THE GENERAL CONTRACTOR AND SUBCONTRACTORS SHALL FIELD VERIFY EXISTING CONDITIONS AND NOTIFY THE ARCHITECT OF ANY INCONSISTENCIES OR DISCREPANCIES WITH THE PROJECT DOCUMENTS. ACCESS TO THE SITE AND/OR SPACE UNDER CONSTRUCTION DURING BIDDING AND CONSTRUCTION SHALL BE COORDINATED WITH THE OWNER.
- DO NOT SCALE DRAWINGS.
- THE WORD "ALIGN" AND "EQUAL" AS USED IN THESE DOCUMENTS SHALL SUPERSEDE ANY DIMENSIONAL INFORMATION GIVEN.
- TYPICAL DIMENSIONS ARE TO FACE OF CONCRETE, DRYWALL, CURTAIN WALL, ETC., OR TO COLUMN CENTERLINE. DIMENSIONS AT WINDOWS ARE TYPICALLY TO FACE OF FRAME. REFER TO PLAN DETAILS FOR ADDITIONAL INFORMATION.
- THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR EXAMINING AND CONFIRMING ALL SUBSTRATE CONDITIONS WHERE NEW MATERIALS ARE APPLIED. THE SUBSTRATE SHALL BE SMOOTH AND FREE OF DEFECTS AND SHALL CONFORM TO THE REQUIREMENTS OF THE FINISHED MATERIAL MANUFACTURERS' RECOMMENDATIONS.
- THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR CLEAN-UP.
- THE GENERAL CONTRACTOR SHALL INSPECT AND CHECK THE ADEQUACY AND INSTALLATION OF THROUGH-WALL FLASHING PRIOR TO COVERING WITH FINISH MATERIALS. THIS SHALL INCLUDE, BUT IS NOT LIMITED TO INSPECTION AGAINST HOLES OR PENETRATIONS, APPROPRIATE LAPPING AND SEALING, AND OVERALL WORKMANSHIP IN CONFORMANCE WITH THE SPECIFICATIONS.



SAINT LUKE'S EAST LEE'S SUMMIT  
VAULT #2 LINEAR ACCELERATOR  
100 NE Saint Luke's Blvd.  
Lee's Summit, MO 64086

Date Job Number 3-25014  
Drawn By ME  
Checked By BRD

Revision  
Number Date Description
















INTERIOR ROOM FINISH SCHEDULE												
ROOM #	ROOM NAME	FLOOR	BASE	WALLS				CEILING	CASEWORK			Notes
				NORTH (PLAN)	EAST (PLAN)	SOUTH (PLAN)	WEST (PLAN)		BASE CABINETS	UPPER CABINETS	COUNTERT OPS	
02-1F128	CORR	ETR	ETR	ETR	ETR	ETR	ETR	ETR	-	-	-	
02-1F129	NEW CONTROL STATION #2	RSF-1	IB-1	PT-1	PT-1	PT-1	PT-1	ACT-1, PT-1C	-	-	SSF-1	
02-1F130	LINAC #2 NEW	RSF-1	IB-1	PT-1A	PT-1A	PT-1A	PT-1A	ACT-2, PT-1C	PLAM-1	PLAM-1	SSF-1	
02-1F153	NEW ADA DRESSING ROOM	LVT-1	RB-1	PT-1	PT-1	PT-1	PT-1	ACT-1	PLAM-1	-	-	
02-1F154	NEW DRESSING ROOM	LVT-1	RB-1	PT-1	PT-1	PT-1	PT-1	ACT-1	PLAM-1	-	-	
02-1F155	NEW RESTROOM	RSF-2	IB-2	PT-1A/CWT-1	CWT-1	PT-1A/CWT-1	PT-1A/CWT-1	ACT-1	-	-	-	
02-1F156	CORRIDOR	LVT-2	RB-1	PT-1/HR-1/WP-2	-	PT-1/HR-1/WP-2	-	ACT-1	-	-	-	

SPECIFIC ROOM FINISH SCHEDULE NOTES

- 1. REFER TO FINISH PLAN FOR CLARIFICATION ON WHERE NEW FINISHES AND EXISTING FINISHES ARE TO MEET AND STOP
- 2. REFER TO TYPICAL WALL TILE PATTERN ELEVATION AT A70

GENERAL ROOM FINISH SCHEDULE NOTES


- A. REFER TO FINISH PLAN AND INTERIOR ELEVATIONS FOR WALL FINISHES, WALL PROTECTION, CORNER GUARDS, WINDOW TREATMENTS, FLOOR FINISH APPLICATION AND LOCATIONS
- B. REFER TO TYPICAL ELEVATION OF WALL PROTECTION/CORNER GUARD ON SHEET A710 FOR INSTALLATION HEIGHTS. WALL PROTECTION SHALL NOT BE INSTALLED ON EXTERIOR WALLS UNDO
- C. ALL PLASTIC LAMINATE GRAIN SHALL BE VERTICALLY ORIENTED
- D. DOOR FRAMES, HOLLOW METAL WINDOW FRAMES TO BE PT-48
- E. WALL EXPANSION JOINTS TO BE PT-1 UNLESS OTHERWISE NOTED
- F. ALL ELECTRICAL PANELS AND METAL GRILLES SHALL BE PTD TO MATCH ADJACENT WALL SURFACE UNLESS OTHERWISE NOTED
- G. ALL COLUMNS SURROUND FINISHES TO MATCH ADJACENT WALL SURFACE UNLESS OTHERWISE NOTED
- H. WHERE A WALL IS INDICATED TO HAVE PARTIAL OR FULL HT WALL PROTECTION, THE ENTIRE WALL IS TO BE PTD PRIOR TO WALL PROTECTION INSTALLATION
- I. EXTEND ALL FINISHES BENEATH BEHIND, AROUND ALL CASEWORK, EQUIPMENT, SIGNAGE, ETC
- J. SUBMIT SAMPLES OF ALL FINISHES TO ARCHITECT FOR REVIEW PRIOR TO THE ORDERING OF MATERIAL
- K. NO IRREGULARITIES OR IMPERFECTIONS SHALL BE PRESENT IN ANY OF THE MATERIAL BEING INSTALLED. IF SUCH ITEMS ARE IDENTIFIED DURING APPLICATION, WORK SHALL BE STOPPED AND THE ARCHITECT NOTIFIED
- L. PROVIDE ALL MAINTENANCE MANUALS AND WARRANTY INFORMATION FOR EACH FINISH MATERIAL TO OWNER AT COMPLETION OF THE PROJECT
- M. FURNISH ALL LABOR, MATERIALS, AND EQUIPMENT NECESSARY TO COMPLETE WORK OF FINISH APPLICATIONS
- N. ALL FINISHES SHALL BE INSTALLED AND MAINTAINED PER MANUFACTURER'S RECOMMENDATION AND INDUSTRY STANDARDS
- O. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR EXAMINING AND CONFIRMING ALL SUBSTRATE CONDITIONS WHERE NEW MATERIALS ARE APPLIED. SUBSTRATE SHALL BE SMOOTH, FREE OF DEFECTS AND SHALL CONFORM TO THE REQUIREMENTS OF THE FINISHED MATERIAL MANUFACTURER'S RECOMMENDATIONS
- P. ALL MATERIAL TO COMPLY WITH FLAME SPREAD CLASSIFICATION EITHER CLASS (1) ONE OR CLASS A DEPENDING ON GOVERNING CODE IN EFFECT
- Q. SMOKE DEVELOPMENT RATING < 450 FOR ALL FINISHES




D6 EXISTING CONTROL ROOM 1/4" = 1'-0"

D5 TYPICAL WALL TILE PATTERN 1/4" = 1'-0"


D4 TYP. NEW DRESSING ROOM 1/4" = 1'-0"




C6 LINAC #2 - WEST 1/4" = 1'-0"




C5 LINAC #2 - SOUTH 1/4" = 1'-0"




B6 LINAC #2 - EAST 1/4" = 1'-0"



B5 LINAC #2 - NORTH 1/4" = 1'-0"




A6 CONTROL STATION SOUTH 1/4" = 1'-0"



A5 CONTROL STATION - NORTH 1/4" = 1'-0"

INTERIOR FINISH LEGEND							
MARK	ITEM	MANUFACTURER	MODEL / PATTERN	COLOR	SIZE	REMARKS	REV #
FLOOR							
LVT-1	LUXURY VINYL TILE	MANNINGTON	AMTICO WOOD	REGENCY WALNUT ARROW8200	4 1/2" X 36"	STRAIGHT EDGE ONLY, RANDOM OFFSET INSTALLATION	
RSF-1	RESILIENT SHEET FLOORING	MANNINGTON	AMTICO STONE	CORINTHIAN MARBLE AROSTV13	18" X 18"	STRAIGHT EDGE ONLY, ASHLAR INSTALLATION	
RSF-2	RESILIENT SHEET FLOORING	MOHAWK	MEDELLA HUES	H5311 NATURAL WHITE	6-7" ROLL	USE MATCHING WELD ROD, HOMOGENEOUS FLOORING	
TRS-1	FLOORING TRANSITION	SHAW CONTRACT	TERRAZO, REED 078/PV	PACDCA 96710	6-6" ROLL	USE MATCHING WELD ROD, HETEROGENEOUS FLOORING	
		SCHLUTER	VINPRO S	BRUSHED CHROME ANODIZED ALUMINUM	-	RE FINISH DETAILS ON SHEET A740	
BASE							
IB-1	INTEGRAL BASE	MOHAWK	MEDELLA HUES	H5311 NATURAL WHITE	6" COVE	J MOLD SCHLUTER STRIP AT TOP, TO BE USED WITH RSF-1	
IB-2	INTEGRAL BASE	SHAW	TERRAZO, REED 078/PV	PACDCA 96710	6" COVE	J MOLD SCHLUTER STRIP AT TOP, TO BE USED WITH RSF-2	
RB-1	RUBBER BASE	ROPPE	PINNACLE PLUS, PROFILE #65	#129 DOLPHIN	4.58"	-	
WALL							
AP-1	ACRYLIC PANEL	3FORM	VARIAN ESCORESIN	MATCH EXISTING	114" GAUGE	MATCH EXISTING FROM VAULT 1	
CG-1	CORNER GUARD	C/S ACROVYN	SM-20AN-ACROVYN-4000	#933 MISSION WHITE	3", HALF HEIGHT	90 DEGREE, ABOVE BASE TO CEILING. INCLUDE ALL TRIM AND ACCESSORY PIECES	
CG-2	CORNER GUARD	C/S ACROVYN	SSM-25AN-ACROVYN-4000	#933 MISSION WHITE	2", HALF HEIGHT	END WALL, ABOVE BASE TO CEILING. INCLUDE ALL TRIM AND ACCESSORY PIECES	
CG-3	CORNER GUARD	C/S ACROVYN	CO-8 STAINLESS STEEL	#44 STAIN	3.5" WINGS	ABOVE BASE TO CEILING	
CWT-1	CERAMIC WALL TILE	VIRGINIA TILE	AMERICAN OLEAN COLOR STORY	ICE WHITE POLISHED	4" X 12"	STACKED INSTALLATION, USE GT-1	
HR-1	HANDRAILS	C/S ACROVYN	HRB-20IN	#079 BRUSHED NICKEL	5.58" X 3"	RE FLOOR FINISH PLAN FOR LOCATIONS	
PT-1	PAINT	SHERWIN WILLIAMS	EGGSHELL	SW7008 ALABASTER	-	OVERALL PAINT	
PT-1A	PAINT	SHERWIN WILLIAMS	EPOXY MIX, EGGSHELL	SW7008 ALABASTER	-	OVERALL PAINT	
PT-4B	PAINT	SHERWIN WILLIAMS	SEMIGLOSS	SW7008 ANONYMOUS	-	ALL HOLLOW METAL DOOR AND WINDOW FRAMES	
WP-2	WALL PROTECTION	C/S ACROVYN	ACROVYN 4000	#933 MISSION WHITE	4" X 10' SHEETS, 40" THICK	INCLUDE ALL TRIM AND ACCESSORY PIECES. RE: TYP. WALL PROTECTION ELEVATION ON INT. DTL. SHEET	
CASEWORK							
IB-1	INTEGRAL SINK	WILSONART	AK1413 SQUARE	DESIGNER WHITE	17" X 15 3/8" X 8"	USE WITH SSF-1	
PLAM-1	PLASTIC LAMINATE	WILSONART	#7959C-12	WALNUT HEIGHTS	4" X 8' SHEET	CUSTOM 3MM PVC DOELLKEN WALNUT HEIGHTS #707ES, RUN VERTICALLY	
SSF-1	SOLID SURFACE	WILSONART	#1999MG	PEARL MIRAGE	1/2", 30" X 144", 36" X 144"	EASED EDGE, TO BE USED WITH PLAM-1	
CEILING							
ACT-1	ACOUSTIC CEILING TILE	USG	RADAR CLIMA PLUS #2210	WHITE	24" X 24"	SQUARE EDGE, DONN DX TEE 15/16" GRID SYSTEM	
ACT-2	ACOUSTIC CEILING TILE	USG	CLEAN ROOM CLIMA PLUS CLASS 100 #96099	WHITE	24" X 24"	VINYL FACED W SQUARE EDGE, DONN CE 15/16" GASKETED TEE GRID	
ICS-1	ILLUMINATED CEILING SYSTEM	SKY FACTORY	ECOPUS CLASSIC LUMINUS SKY CEILING EP22	T80 PATTERN, MATTE WHITE FRAME	24" X 24"	ILLUMINATED CEILING MURAL	
PT-1C	PAINT	SHERWIN WILLIAMS	FLAT	SW7008 ALABASTER	-	SOFFIT PAINT	
MISC.							
ETR	EXISTING TO REMAIN	-	-	-	-	RE: ROOM FINISH SCHEDULE	
GT-1	GROUT	ULTRACOLOR PLUS FA	#107 IRON	-	-	MINIMAL GROUT LINES	
INT-DR-1	INTERIOR DOOR	VT INDUSTRIES	HIGH PRESSURE DECORATIVE LAMINATE	WILSONART 7959C-12 WALNUT HEIGHTS	-	3MM PVC EDGES, LAMINATED TOPS AND BOTTOMS	
PTM	PATCH TO MATCH	-	-	-	-	-	



A3 ENLARGED FINISH PLAN - RAD. ONCOLOGY 1/4" = 1'-0"

ACI BOLAND ARCHITECTS

ACI/Boland, Inc.  
Kansas City | St. Louis  
1710 Wyandotte  
Kansas City, MO 64108  
T: 816.763.9600

Licensee's Certificate of Authority Number:

MEP ENGINEERS

PROFESSIONAL ENGINEERING CONSULTANT

623 MASSACHUSETTS STREET, SUITE 200  
LAWRENCE, KS 66044  
(785) 842-6464

Licensee's Certificate of Authority Number:

STRUCTURAL ENGINEERS

Structural Engineering Associates, Inc.

1000 Walnut, Suite 1570  
Kansas City, MO 64106  
816.421.1042

Licensee's Certificate of Authority Number:

#000396

SAINT LUKE'S EAST LEE'S SUMMIT  
VAULT #2 LINEAR ACCELERATOR  
100 NE Saint Luke's Blvd.  
Lee's Summit, MO 64086

Date  
Job Number  
Drawn By  
Checked By

3-25014  
ME  
BRD


Revision  
Number  
Date  
Description

A701


© 2024 ACI/BOLAND, Inc.

FINISH FLOOR PLAN, SCHEDULES, LEGENDS, AND ELEVATIONS







E6 TYPICAL SOLID SURFACE COUNTERTOP  
1 1/2" = 1'-0"




E5 TRANSITION STRIP DETAILS  
6" = 1'-0"




E4 TYP- ELEV- OF WALL PROTECTION-CORNER GUARD  
1" = 1'-0"




E3 TYP- ELEV- OF WALL PROTECTION-CORNER GUARD  
1" = 1'-0"




E2 TYP- ELEV- OF WALL PROTECTION-CORNER GUARD  
1" = 1'-0"




E1 TYP- ELEV- OF WALL PROTECTION-CORNER GUARD  
1" = 1'-0"




D6 DETAIL AT HANDRAIL  
3" = 1'-0"




D5 DETAIL AT BUILT IN BENCH  
1 1/2" = 1'-0"




D4 TYPICAL DOUBLE VINYL CORNER GUARD  
3" = 1'-0"




D3 SINGLE VINYL CORNER GUARD  
3" = 1'-0"




D2 DETAIL AT SHEET FLOORING COVE BASE TERMINATION  
3" = 1'-0"




D1 CASEWORK ISOMETRIC  
1 1/2" = 1'-0"




A6 DETAIL AT SINK BASE CABINET - SOLID SURFACE  
1 1/2" = 1'-0"




A5 DEATIL AT OPEN SHELVING CABINET  
1 1/2" = 1'-0"




A4 DETAIL AT SLAT CABINET  
1 1/2" = 1'-0"



A3 DETAIL AT OPEN FULL HT- CABINET  
1 1/2" = 1'-0"



A2 DETAIL AT FULL HT- CABINET  
1 1/2" = 1'-0"



A1 DETAIL AT CASEWORK  
1 1/2" = 1'-0"

RELEASED FOR CONSTRUCTION  
ACI/Boland Architects  
7/8/2025 04:08:52 PM  
License - Missouri #A-2011012130

ACI  
BOLAND  
ARCHITECTS

ACI/Boland, Inc.  
Kansas City | St. Louis  
1710 Wyandotte  
Kansas City, MO 64108  
T: 816.763.9600  
Licensee's Certificate of Authority Number:

MEP ENGINEERS

PROFESSIONAL ENGINEERING CONSULTANT  
623 MASSACHUSETTS STREET, SUITE 200  
LAWRENCE, KS 66044  
(785) 842-6464  
Licensee's Certificate of Authority Number:

STRUCTURAL ENGINEERS

Structural Engineering Associates, Inc.  
1000 Walnut, Suite 1570  
Kansas City, MO 64106  
816.421.1042  
Licensee's Certificate of Authority Number: #000396

SAINT LUKE'S EAST LEE'S SUMMIT  
VAULT #2 LINEAR ACCELERATOR  
100 NE Saint Luke's Blvd.  
Lee's Summit, MO 64086

Date  
Job Number  
Drawn By  
Checked By

3-25014  
ME  
BRD

Revision  
Number  
Date  
Description

A710

© 2024 ACI/BOLAND, Inc.  
INTERIOR DETAILS



6/25/2025 10:42:36 AM

E

D

C

B

A

C:\Users\lgisrcoe\Documents\XX-202502-R21\_difoxx.rvt

#### A. GENERAL

- Before executing anything herein shown, examine actual job conditions. Report any discrepancy, dimensional or otherwise, between mechanical and structural drawings and any other error, omission, or difficulty affecting the work to the Architect and to the Structural Engineer for review.
- The Owner or his Representative reserves the right to inspect any material, fabrication, or workmanship at any time in field or shop for conformance to the Specifications and Drawings.
- All details and sections are intended to be typical and shall be construed to apply to any similar situation elsewhere, except where a different detail is shown.

#### B. DESIGN

- Codes, specifications and standards (latest editions, unless noted otherwise)
  - All design and construction shall conform to the International Building Code (IBC 2021) as amended and adopted by the City of Lee's Summit, Missouri.
  - All construction shall comply with the provisions of the following codes, specifications and standards, except where noted to the contrary on drawings and specifications or where more stringent requirements are specified or shown: AISC "Specifications for Structural Steel for Buildings" Allowable Stress Design and Plastic Design" including the commentary thereto as issued.

#### C. CONCRETE

- Concrete used in the Work shall have the following minimum 28-day ultimate compressive strengths:
  - Slab on metal deck: 4,000 psi
  - Portland Cement: ASTM C 150, Type 1.
  - Reinforcing bars: ASTM A 615 Specifications, Grade 60, deformed. Bend bars cold.

#### D. STEEL

- Structural steel: ASTM A992 GR-50 - wide flange; ASTM A36 - channels, angles, plates and bars; ASTM A53, Grade B - pipes; and ASTM A 500, Grade B - tubes.
- Beam and column connections shall be as shown on plans.
- High Strength Bolts (steel-to-steel connections): snug-tightened - bearing type.
- Anchor bolts: ASTM A 307.
- Welded connections: AWS Standards and Specifications using E70xx electrodes, unless noted otherwise.
- Quality Assurance:
  - Installer Qualifications: A qualified installer who participates in the AISC Quality Certification Program and is designated an AISC-Certified Erector.
  - Fabricator Qualifications: A qualified fabricator who participates in the AISC Quality Certification Program and is designated an AISC-Certified Plant.
  - Shop-Painting Applicators: Qualified according to AISC's Sophisticated Paint Endorsement P1 or SSPC-QP 3, "Standard Procedure for Evaluating Qualifications of Shop Painting Applicators."
  - Welding: Quality procedures and personnel according to AWS D1.1, "Structural Welding Code - Steel." Primer
- Primer:
  - Fabricator's standard lead- and chromate-free, nonasphaltic, rust-inhibiting primer, color Gray.

#### E. CONSTRUCTION

- Provide adequate shoring and/or bracing to the structure during construction to resist forces such as wind and unbalanced loading during construction.
- See architectural and mechanical requirements for embedded items and sleeves not shown on the structural drawings and to verify size and location of all openings
- Coordinate the sizes and locations of all miscellaneous metal items required for mechanical and electrical.
- Requirements for embedded items, sleeves, block outs, duct openings, etc., in the concrete frame shall be submitted (plans and details) to the structural engineer for approval at least two weeks prior to the proposed date of casting concrete. No such items, other than those shown, shall be provided in the structure without the approval of the structural
- Field verify the location and depth (or height) of all utilities prior to beginning construction in order to provide adequate clearances and to insure noninterruption of service.
- During welding or any other construction activity that generates sparks intense heat, the contractor shall provide adequate fire protection to the existing structure and contents as a minimum:
  - Remove combustible materials from areas of welding and sparks.
  - Provide fireproof blankets and shields to contain sparks where combustible materials cannot be removed.
- Prior to drilling/coring into existing concrete slab, beams, columns, and walls scan and locate rebar. Do not cut or damage existing rebar in concrete. If core location cannot be shifted to miss rebar contact the Structural Engineer.

#### F. SPECIAL INSPECTION





- The following tests and inspection shall be performed by an independent inspection agency employed by the owner and approved by the structural engineer and the building official. Test and inspection reports shall be submitted to the owner, architect, structural engineer, and building official. Special inspection shall conform to Chapter 17 of the 2018 International Building Code.
- Concrete

	Continuous	Periodic
a. Placement of Reinforced Concrete	X	X
b. Testing of Reinforced Concrete	X	
c. Inspection of reinforcing steel		X
- Structural steel - 2018 IBC Table 1704.3

a. Material verification - structural steel, high-strength bolts, nuts, washers.		X
b. Inspection of high-strength bolting - bearing connections.		X
c. Inspection of steel frame.		X
d. Inspection of welding: <ol style="list-style-type: none"><li>Single pass fillet welds &gt;5/16".</li><li>Single pass fillet welds &lt;5/16".</li><li>Floor and Roof deck.</li><li>Complete and partial penetration groove welds.</li></ol>	X	X
e. In-plant steel inspection.		X

Note: In-plant inspection is not required if steel fabrication plant has AISC certification for steel and SJI certification for steel joists.
- Post-installed anchors in concrete and masonry.

	X	
--	---	--



RELEASED FOR CONSTRUCTION  
FOR NOTICE & COMMENT ONLY

Professional Engineer  
Krishna G. Saha  
Number PE-23862  
Expiry 12/31/2025

6/25/2025 10:42:36 AM  
Krishna G. Saha Engineer  
License - Missouri BE #023862

ACI  
BOLAND  
ARCHITECTS

ACI/Boland, Inc.  
Kansas City | St. Louis  
1710 Wyandotte  
Kansas City, MO 64108  
T: 816.763.9600  
Licensee's Certificate of Authority Number:

MEP ENGINEERS  
PROFESSIONAL ENGINEERING CONSULTANTS  
623 MASSACHUSETTS STREET, SUITE 200  
LAWRENCE, KS 66044  
(785) 842-6464  
Licensee's Certificate of Authority Number:

STRUCTURAL ENGINEERS  
Structural Engineering Associates, Inc.  
1000 Walnut, Suite 1570  
Kansas City, MO 64106  
816.421.1042  
Licensee's Certificate of Authority Number: #000396

SAINT LUKE'S EAST LEE'S SUMMIT  
VAULT #2 LINEAR ACCELERATOR  
100 NE Saint Luke's Blvd.  
Lee's Summit, MO 64086

Date 06/25/2025  
Job Number 3-25014  
Drawn By G.E.B.  
Checked By K.G.S.

Revision  
Number Date Description

S1.0

© 2024 ACI/BOLAND, Inc.  
PLANS, DETAILS & GENERAL NOTES



ABBREVIATIONS	
Ø	ROUND DIAMETER
ABV	ABOVE
AF	ABOVE FINISHED FLOOR
AFMS	AIRFLOW MEASURING STATION
AFUE	ANNUAL FUEL UTILIZATION EFFICIENCY
BAC	BUILDING AUTOMATION CONTROL
BAS	BUILDING AUTOMATION SYSTEM
BFF	BELOW FINISHED FLOOR
BFG	BELOW FINISHED GRADE
BLW	BELOW
BOD	BOTTOM OF DUCT ELEVATION ABOVE FLOOR
BOP	BOTTOM OF PIPE ELEVATION ABOVE FLOOR
BOS	BOTTOM OF STEEL
BP	BUILDING PRESSURE
BTU	BRITISH THERMAL UNITS
BTUH	BRITISH THERMAL UNITS PER HOUR
CAP	CAPACITY
CAV	CONSTANT AIR VOLUME
CFM	CUBIC FEET PER MINUTE
CM	CAST IRON
CO	CARBON MONOXIDE
CO2	CARBON DIOXIDE
COP	COEFFICIENT OF PERFORMANCE
DB	DECEBELS
DB	DRY BULB TEMPERATURE
DD	DIRECT DRIVE
DEMO	DEMOLISH
DIA	DIAMETER
DN	DOWN
DP	DIFFERENTIAL PRESSURE
DS	DOOR SWITCH
DSD	DUCT SMOKE DETECTOR
DSP	DUCT STATIC PRESSURE
DX	DIRECT EXPANSION
(E)	EXISTING COMPONENT DESIGNATION
EAT	EXHAUST AIR
EA	ENTERING AIR TEMPERATURE
EC	ELECTRICAL CONTRACTOR
ECM	ELECTRONICALLY COMMUNICATED MOTOR
ETR	EXISTING TO REMAIN
EWT	ENTERING WATER TEMPERATURE
*F	DEGREES FAHRENHEIT
FO	FLOOR CLEANOUT
FD	FLOOR DRAIN
FC	FIRE DEPARTMENT CONNECTION
FLR	FLOOR
FL	FLOW LINE
FOFS	FUEL OIL FLOW SWITCH
FOG	FUEL OIL GAUGE
FOV	FUEL OIL VENT
FS	FLOOR SINK
FS	FLOOR SINK
GAL	GALLON
GC	GENERAL CONTRACTOR
GPM	GALLONS PER MINUTE
HGB	HOT GAS BYPASS
HSL	HIGH STATIC PRESSURE LIMIT
IB	INTEGRAL FACE AND BYPASS
INV	INVERT
LAT	LEAVING AIR TEMPERATURE
LBHR	POUNDS PER HOUR
LWT	LEAVING WATER TEMPERATURE
MAT	MIXED AIR TEMPERATURE
MBH	ONE THOUSAND BTU PER HOUR
MC	MECHANICAL CONTRACTOR
MFR	MANUFACTURER
MCA	MINIMUM OUTSIDE AIR
MVSA	MEDIUM VELOCITY SUPPLY AIR
NC	NORMALLY CLOSED
NCR	NOISE CRITERIA RATING
NO	NORMALLY OPEN
N2	NITROGEN DIOXIDE
NTS	NOT TO SCALE
OA	OUTSIDE AIR
OAT	OUTSIDE AIR TEMPERATURE
OBD	OPPOSED BLADE DAMPER
OCC	OCCUPANCY
ORD	OVERFLOW ROOF DRAIN
PC	PLUMBING CONTRACTOR
PD	PRESSURE DROP
PI	POST INDICATOR VALVE
PSI	POUNDS PER SQUARE INCH
PSIG	POUNDS PER SQUARE INCH GAUGE
PVC	POLYVINYL CHLORIDE PIPE
PWR	POWER
(R)	RELOCATED COMPONENT DESIGNATION
RA	RETURN AIR
RD	ROOD DRAIN
RH	RELATIVE HUMIDITY
RP	ROOM PRESSURE
RPC	ROOM PRESSURE CONTROL
RPM	REVOLUTIONS PER MINUTE
SA	SUPPLY AIR
SAT	SUPPLY AIR TEMPERATURE
SF	SQUARE FOOT
SMP	SMOKE PURGE
SOI	SAND/OIL INTERCEPTOR
SP	STATIC PRESSURE
TA	TRANSFER AIR
TCC	TEMPERATURE CONTROL CONTRACTOR
TOP	TEMPERATURE CONTROL PANEL
TCV	TEMPERATURE CONTROL VALVE
TD	TRENCH DRAIN
TD	TOP OF DUCT ELEVATION ABOVE FLOOR
TO	TOP OF PIPE ELEVATION ABOVE FLOOR
UG	UNDERGROUND
UV	ULTRAVIOLET STERILE CONDITIONER
VAV	VARIABLE AIR VOLUME
VCP	VITRIFIED CLAY PIPE
VENT	VENTILATION
VFD	VARIABLE FREQUENCY DRIVE
VOC	VOLATILE ORGANIC COMPOUND
VTR	VENT THROUGH ROOF
VVT	VARIABLE VOLUME AND TEMPERATURE
WB	WET BULB TEMPERATURE
WFS	WATER FLOW SWITCH

GENERAL SYMBOLS	
	REFER TO PLAN NOTES
	EXISTING COMPONENT PEN WEIGHT
	DEMOLITION PEN WEIGHT - COMPONENT SHADED
	ROOM CALLOUT
	AREA NOT IN SCOPE HATCHING
	REVISION NUMBER
	CONNECT NEW TO EXISTING - VERIFY EXACT LOCATION
	DISCONNECT FROM EXISTING - VERIFY EXACT LOCATION
	PIPE / DUCT CONTINUATION SYMBOL
	DETAIL NUMBER
	SHEET NUMBER WHERE DRAWN
	SECTION LETTER
	SHEET NUMBER WHERE DRAWN
	UNIQUE I.D. (FAN COIL UNIT NO. 1)
	TYPICAL EQUIPMENT CALLOUT
	EQUIPMENT TYPE (FC-FAN COIL UNIT)

PIPE SYMBOLS	
	DIRECTION OF FLOW
	PIPE DROP / SIDE CONNECTION / PIPE RISE
	TEE OUTLET DOWN / TEE OUTLET UP
	BOTTOM / TOP CONNECTION, 45° OR 90°
	CAP / CAPPED OUTLET
	BALL VALVE / GLOBE VALVE
	CONCENTRIC / ECCENTRIC REDUCER OR INCREASER
	ANCHOR / FLEXIBLE CONNECTION
	BUTTERFLY VALVE
	CIRCUIT SETTER
	CHECK VALVE
	STRAINER / UNION
	BLIND FLANGE / FLOW METER
	BACKFLOW PREVENTER (BFP)
	PRESSURE REDUCING VALVE / PLUG VALVE
	WATER METER / IRRIGATION WATER METER
	PLUG VALVE / NEEDLE VALVE
	GAS COCK
	PRESSURE REGULATING VALVE / PETE'S PLUG
	WATER HAMMER ARRESTOR (WHA)
	SLEEVE / EXPANSION JOINT
	PIPE PITCH DOWN / PIPE RISE UP
	SOLENOID VALVE /
	PNEUMATIC 3-WAY CONTROL VALVE
	ELECTRIC 3-WAY / 2-WAY CONTROL VALVE
	MANUAL / EMERGENCY 3-WAY CONTROL VALVE
	THERMOMETER / PRESSURE GAUGE
	STEAM TRAP
	TEMPERATURE/PRESSURE RELIEF VALVE

MECH. PIPING SYMBOLS	
	HEATING WATER SUPPLY
	HEATING WATER RETURN
	CHILLED WATER RETURN
	CHILLED WATER RETURN
	REFRIGERANT LIQUID LINE (SUPPLY)
	REFRIGERANT SUCTION LINE (RETURN)
	EQUIPMENT CALLOUT
	WATER COIL FLOW (GPM)

HVAC DESIGN CONDITIONS									
REMARKS:									
1. AMBIENT CONDITIONS ARE BASED ON 2021 ASHRAE WEATHER DATA CONDITIONS, 99.6% HEATING AND 0.4% COOLING VALUES.									
2. HOT GAS REHEAT DEHUMIDIFICATION TO MAINTAIN 60% RELATIVE HUMIDITY.									
SPACE OR AREA	OUTDOOR AIR		INDOOR HEATING °F	INDOOR COOLING °F	RELATIVE HUMIDITY %RH	PRESSURE	CODE MIN ACH	ACTUAL DESIGN ACH	REMARKS
	SUMMER DB/WB °F	WINTER DB °F							
LINEAR ACCELERATOR	95.5/75.3	4.5	68	70	60	NR	6	15	1,2
RESTROOM	95.5/75.3	4.5	70	72	60	NEGATIVE	10	10.8	1,2

PLUMBING SYMBOLS	
	DOMESTIC COLD WATER (CW)
	DOMESTIC HOT WATER (HW)
	DOMESTIC HOT WATER RECIRC. (HWC)
	WASTE (W)
	BELOW GRADE WASTE (W)
	VENT (V)
	CONDENSATE DRAIN
	DRAIN
	CLEANOUT (FLOOR)
	2-WAY CLEANOUT (FLOOR/GRADE)
	WALL CLEANOUT / END OF LINE CLEANOUT

HVAC SYMBOLS	
	(UP) DUCT SECTION, POSITIVE PRESSURE - FIRST SIZE IS TOP DIM. (TYP.)
	(DOWN) DUCT SECTION, POSITIVE PRESSURE
	(UP) DUCT SECTION, NEGATIVE PRESSURE
	(DOWN) DUCT SECTION, NEGATIVE PRESSURE
	FLEXIBLE DUCT
	TURNING VANES
	DUCT SIZE, FIRST IS SIDE SHOWN CLEAR INSIDE DIM.
	DUCT CHANGE OF ELEVATION RISE(R) DROP(D)
	FLEXIBLE CONNECTION
	SIDE WALL SUPPLY REGISTER
	BALANCE DAMPER - MANUAL LOCKING QUADRANT RECT. OPPOSED BLADE / ROUND: BUTTERFLY
	BALANCE DAMPER - MOTORIZED LOCKING QUADRANT RECT. OPPOSED BLADE / ROUND: BUTTERFLY
	FIRE DAMPER (FD) IN WALL / FLOOR
	SMOKE DAMPER (SD) IN WALL / FLOOR
	COMBO FIRE/SMOKE DAMPER (FSD) IN WALL / FLOOR
	THERMOSTAT (TSTAT) / TEMPERATURE SENSOR
	HUMIDISTAT (HSTAT) / HUMIDITY SENSOR
	PRESSURE SENSOR
	MOTOR
	SUPPLY FLOW ARROW / RETURN FLOW ARROW
	EQUIPMENT CALLOUT
	EQUIPMENT AIRFLOW (CFM)
GRD CALLOUT SYMBOLS	
	ROUND SUPPLY DIFFUSER
	RECTANGULAR RETURN GRILLE
	SLOT DIFFUSER

MEDICAL GAS SYMBOLS	
	OXYGEN
	MEDICAL COMPRESSED AIR
	MEDICAL VACUUM
	WASTE ANESTHESIA GAS DISPOSAL
	NITROUS OXIDE
	CARBON DIOXIDE
	INSTRUMENT AIR
	NITROGEN
	ZONE VALVE BOX (ZVB)
	MEDICAL GAS OUTLET (MGO)

PRESSURE CLASS SCHEDULE				
AIR SYSTEM	PRESSURE CLASS	SEAL CLASS	LEAKAGE CLASS	
DISHWASHER AND LAUNDRY EXHAUST	2 INCH WG (500 PA)	A	3	6
GENERAL EXHAUST	2 INCH WG (500 PA)	A	3	6
LABORATORY EXHAUST DUCTWORK	6 INCH WG (1500 PA)	A	3	6
LOW-PRESSURE SUPPLY	2 INCH WG (500 PA)	A	6	12
MEDIUM PRESSURE SUPPLY (UPSTREAM OF VAV & CV BOXES)	6 INCH WG (1500 PA)	A	3	6
RETURN AND RELIEF	2 INCH WG (500 PA)	A	6	12

SEISMIC RESTRAINTS:	
THIS IS A LIFE SAFETY BUILDING WHICH MEANS IT SHALL REMAIN REASONABLY OPERATIONAL IN THE CASE OF A SEISMIC EVENT. THEREFORE ALL STATIONARY EQUIPMENT ON THE FLOOR AND ALL CONCRETE PADS SHALL BE FIXED RIGIDLY TO THE STRUCTURE. ALL ROTATING OR RECIPROCATING OR VIBRATING EQUIPMENT SHALL BE INSTALLED WITH EARTHQUAKE SNUBBERS TO LIMIT MOVEMENT. ALL HANGING EQUIPMENT, PIPING, AND DUCTWORK SHALL BE BRACED TO THE STRUCTURE. REFER TO SPECIFICATION SECTIONS 21 0548, 22 0548, AND 23 0548.	

GENERAL DEMO. NOTES	
1. VERIFY ALL EXISTING CONDITIONS PRIOR TO BEGINNING WORK. BRING ANY DISCREPANCIES FROM THE DRAWINGS AND NOTES TO THE ARCHITECT IMMEDIATELY. MINOR CHANGES IN THE SCOPE OF THE DEMOLITION WORK SHALL NOT JUSTIFY AN ADDITIONAL COST.	
2. REMOVAL OF EXISTING FIXTURES AND EQUIPMENT WILL REQUIRE ISOLATING THE PIPING RISERS OR MAINS VIA SHUT-OFF VALVES. INSTALL NEW ISOLATION VALVES WHERE REQUIRED FOR COMPLETION OF WORK.	
3. REMOVAL OF EXISTING DUCTWORK, DIFFUSERS, GRILLES, REGISTERS, PLUMBING FIXTURES, ETC. WILL REQUIRE TEMPORARY CAPPING AND SEALING EXISTING MAINS OR BRANCHES AS NECESSARY AND REQUIRED TO ALLOW THE REMAINING SYSTEMS TO FULLY OPERATE WITHOUT DEGRADATION.	
4. CONTRACTOR SHALL PROVIDE PROTECTIVE PLASTIC DROP CLOTHS TO PROTECT THE EXISTING OCCUPIED AREAS AND EQUIPMENT FROM DUST AND DEBRIS DURING THE CONSTRUCTION WORK, AND SHALL CLEAN THE AREAS OF ALL CONSTRUCTION DIRT DAILY, AND UPON COMPLETION OF THE WORK.	
5. ALL DRAINED PIPING RISERS AND MAINS SHALL BE REFILLED WITH PROPER FLUID AND PROPERLY VENTED BY THIS CONTRACTOR, ONCE NEW WORK HAS BEEN INSTALLED.	
6. COORDINATE WITH OWNER THE REMOVAL AND REPLACEMENT OF ALL EXISTING CEILINGS, WALLS, ETC. AS REQUIRED FOR MECHANICAL DEMOLITION WORK.	
7. EXISTING DUCTS, PIPING, AND EQUIPMENT, ETC., NOT TO BE UTILIZED IN THE COMPLETED BUILDING SHALL BE DISCONTINUED OR REMOVED AS REQUIRED. ALL ENDS OF DISCONTINUED DUCTS AND PIPING SHALL BE CAPPED IN THE NEAREST WALL, CEILING OR FLOOR SO THAT THEY ARE COMPLETELY CONCEALED. OPENINGS LEFT IN WALLS, CEILINGS, ETC., WHERE EQUIPMENT, PIPE, DUCTS, ETC., ARE REMOVED AND NOT REPLACED, SHALL BE PATCHED NEATLY WITH SIMILAR MATERIAL TO ADJACENT CONSTRUCTION.	
8. ALL ACCESSIBLE ABANDONED PIPING AND DUCTWORK SHALL BE REMOVED AND PROPERLY DISPOSED OF.	
9. EXISTING PIPING, FIXTURES AND EQUIPMENT THAT ARE NOT TO BE REUSED SHALL BE REMOVED AND SHALL REMAIN THE PROPERTY OF THE OWNER IF THEY WISH TO RETAIN OWNERSHIP OF SAME. IF NOT, EQUIPMENT SHALL BECOME THE PROPERTY OF THIS CONTRACTOR AND SHALL BE REMOVED FROM THE SITE AS SOON AS PRACTICAL AND DISPOSED OF IN ACCORDANCE WITH APPLICABLE LAWS AND REGULATIONS.	
10. ALL CUTTING AND CHANNELING OF EXISTING BUILDING SHALL BE ACCOMPLISHED IN A NEAT AND WORKMANLIKE MANNER WITHOUT REMOVAL OF EXCESS MATERIALS. THIS CONTRACTOR SHALL PATCH AND REPLACE WITH MATERIAL SIMILAR TO ADJACENT CONSTRUCTION.	
11. CUTTING OF STRUCTURAL MEMBERS IS NOT ALLOWED.	
12. PORTIONS OF EXISTING SYSTEMS MAY BE SHOWN FOR CLARITY EVEN THOUGH IT MAY NOT BE NECESSARY TO MODIFY OR REVISE THEM. ALL EXISTING SYSTEMS ARE SHOWN BASED ON ORIGINAL OR REMODEL BUILDING DRAWINGS. CONTRACTOR TO VERIFY ALL EXISTING CONDITIONS.	
13. WHERE EXISTING DUCTS, PIPING, AND EQUIPMENT, ETC. THAT ARE TO BE UTILIZED IN THE COMPLETED PROJECT CONFLICT WITH NEW CONSTRUCTION AND THE REQUIRED DEMOLITION, THEY SHALL BE RELOCATED AND RECONNECTED TO MAINTAIN THE DESIRED SERVICE. ALERT ENGINEER TO ANY MAJOR RELOCATIONS REQUIRED.	
14. ALL CONTRACTORS SHALL GIVE FULL COOPERATION TO THE OWNER IN THE SCHEDULING AND PROCEDURE OF WORK TO PROVIDE THE LEAST AMOUNT OF DISRUPTION AS POSSIBLE. CONTRACTORS SHALL TAKE EVERY PRECAUTION TO PREVENT DAMAGE FROM FREEZING TO EXISTING SYSTEMS AND SHALL MAINTAIN A CONDITIONED SPACE FOR ALL OWNER OCCUPIED AREAS DURING CONSTRUCTION.	

GENERAL NOTES	
1. ALL WORK IS TO CONFORM WITH APPLICABLE CODES AND STANDARDS.	
2. VERIFY JOB SITE CONDITIONS AND DIMENSIONS BEFORE BEGINNING WORK. PLANS ARE SCHEMATIC IN NATURE. LAYOUT IS BASED ON BEST AVAILABLE INFORMATION. CONTRACTOR SHALL FIELD VERIFY EXISTING CONDITIONS AND DIMENSIONS.	
3. NO PIPING, DUCTWORK, ETC. SHALL PENETRATE STRUCTURAL MEMBERS.	
4. PROVIDE MISCELLANEOUS CUTTING, PATCHING AND REPAIRING OF FINISHES, ROOF, WALLS, ETC., AS REQUIRED TO ACCOMMODATE THE NEW WORK. ALL CUTTING AND PATCHING SHALL BE CLOSELY COORDINATED WITH THE G.C.	
5. G.C. IS TO PATCH ANY OPENINGS IN CORRIDORS REQUIRED TO BE CONSTRUCTED TO LIMIT THE TRANSFER OF SMOKE AND IN SMOKE BARRIERS AS REQUIRED TO MEET CODE REQUIREMENTS. SEE ARCHITECTURAL DRAWINGS FOR LOCATIONS.	
6. IT IS THE CONTRACTOR'S RESPONSIBILITY TO FIELD VERIFY EXACT LOCATION, CONFIGURATION AND ROUTING OF EXISTING SYSTEMS REQUIRED TO REMAIN IN OPERATION DURING THE PROJECT TO PREVENT DAMAGE DURING DEMOLITION AND PHASING.	
7. REMOVE ALL EXISTING EQUIPMENT, DUCTWORK AND PIPING THAT IS NOT REQUIRED FOR A WORKING INSTALLATION.	
8. COORDINATE ALL WORK WITH OTHER TRADES PRIOR TO INSTALLATION.	
9. COORDINATE ROUTING OF PLUMBING, AND HVAC PIPING WITH DUCTWORK, LIGHTS, ARCHITECTURAL CEILING AND STRUCTURAL ELEMENTS. PIPING SHALL RISE AND DROP, JOG OR OFFSET AS REQUIRED TO AVOID CONFLICTS. DUCTWORK SHALL TAKE PRECEDENCE OVER ALL PIPING, EXCEPT WHERE GRADE MUST BE MAINTAINED FOR DRAINAGE. REWORK OF INSTALLED WORK TO RESOLVE CONFLICTS ARISING FROM LACK OF COORDINATION SHALL NOT JUSTIFY AN INCREASE IN THE CONTRACT AMOUNT.	
10. ALL PENETRATIONS THROUGH FIRE RATED ASSEMBLIES SHALL BE FIRE STOPPED BY THE TRADE MAKING THE PENETRATION. REFER TO ARCHITECTURAL DRAWINGS AND SPECIFICATIONS FOR REQUIREMENTS.	
11. DO NOT ROUTE PIPING OR DUCTWORK OVER ELECTRICAL PANELS OR EQUIPMENT. PIPING OR DUCTWORK SHALL NOT BE ROUTED THROUGH ELECTRICAL ROOMS, TELECOM ROOMS OR ELEVATOR EQUIPMENT ROOMS UNLESS SPECIFICALLY SERVING THAT ROOM. MAINTAIN N.E.C. CLEARANCES. COORDINATE WITH E.C. PROVIDE WATERTIGHT DRIP PAN WITH DRAIN TO NEAREST APPROVED RECEPTOR, WHERE REQUIRED.	
12. COORDINATE SIZE AND LOCATION OF ACCESS DOORS IN CONSTRUCTION REQUIRED FOR ACCESS TO MECHANICAL EQUIPMENT WITH G.C.	
13. COORDINATE SIZE AND LOCATION OF MECHANICAL EQUIPMENT PADS WITH G.C.	
14. ALL EQUIPMENT SUPPORT STANDS SHALL BE PRIMED AND PAINTED WITH EPOXY ENAMEL.	
15. TEMPERATURE CONTROLS CONTRACTOR (T.C.C.) SHALL FURNISH AND INSTALL ALL LOW VOLTAGE WIRING AND ASSOCIATED CONDUIT REQUIRED FOR MECHANICAL CONTROL SYSTEM. WIRING SHALL BE IN CONDUIT WHEN INSIDE WALLS, IN ROOMS WITH EXPOSED CEILINGS, AND ABOVE HARD CEILINGS. LINE VOLTAGE WIRING AND ASSOCIATED CONDUIT SHALL BE PROVIDED AND INSTALLED BY E.C. THE CONTROL SYSTEM SHALL BE INSTALLED IN ACCORDANCE WITH SPECIFICATIONS.	
16. ALL CONTROL DAMPERS SHALL BE FURNISHED BY T.C.C. AND INSTALLED BY THE M.C. MOTOR OPERATORS SHALL BE FURNISHED AND INSTALLED BY THE T.C.C.	
17. COORDINATE ACCESS TO EQUIPMENT AND VALVES INSTALLED ABOVE 'HARD' CEILINGS AND IN MASONRY CHASES WITH GENERAL CONTRACTOR. PROVIDE LOCKING ACCESS DOORS FOR INSTALLATION BY CONTRACTOR AS REQUIRED TO SERVICE CONCEALED DAMPERS, VALVES AND EQUIPMENT. CEILING ACCESS DOORS FOR FIRE DAMPERS, SMOKE DAMPERS AND FIRE SMOKE DAMPERS FURNISHED AND INSTALLED BY CONTRACTOR.	
18. CONTRACTOR TO INSTALL TEMPORARY FILTERS OVER ALL RETURN AND EXHAUST GRILLES IN WORK AREA DURING CONSTRUCTION.	
19. REFER TO ARCHITECTURAL DRAWINGS FOR LOCATIONS OF TEMPORARY PARTITIONS.	
20. TERMINAL UNITS, MANUAL BALANCE DAMPERS, HYDRONIC AND PLUMBING VALVES, CIRCUIT SETTERS AND OTHER ACCESSORIES REQUIRING ACCESS SHALL BE ACCESSIBLE VIA A STANDARD LADDER SO COMPONENTS MAY BE REPLACED, REPAIRED, OR UTILIZED WITHOUT THE NEED FOR EXTENSIVE CEILING REMOVAL, SCAFFOLDING OR A MAN LIFT. WHERE POSSIBLE NO MORE THAN 48" ABOVE THE FINISHED CEILING.	
21. THESE DRAWINGS ARE ACCOMPANIED BY SPECIFICATIONS. REFER TO SPECIFICATIONS FOR FURTHER INFORMATION.	
NOTE: ALL GENERAL NOTES ON THIS SHEET ARE TO BE APPLIED TO ALL OTHER DRAWINGS IN THIS SET. THE SYMBOLS AND ABBREVIATIONS SHOWN ON THIS SHEET MAY OR MAY NOT BE USED IN THIS SET OF DRAWINGS.	

MECHANICAL SHEET INDEX	
M-001	MECHANICAL COVER SHEET
M-101	FIRST FLOOR OVERALL PLAN
F-111	FIRST FLOOR FIRE PROTECTION ENLARGED PLAN
P-111	FIRST FLOOR PLUMBING ENLARGED PLAN
P-501	PLUMBING SCHEDULES & DETAILS
M-111	FIRST FLOOR MECHANICAL ENLARGED DEMO PLANS
M-112	FIRST FLOOR HVAC ENLARGED PLAN
M-501	HVAC SCHEDULES & DETAILS

SAINT LUKE'S EAST LEE'S SUMMIT  
VAULT #2 LINEAR ACCELERATOR  
100 NE Saint Luke's Blvd.  
Lee's Summit, MO 64086


Date	06.27.2025
Job Number	3-25014
Drawn By	VOC
Checked By	EKE

Revision		
Number	Date	Description



6/27/2025 1:28:40 PM


Autodesk Docs:/S-25014 Saint Luke's East Lee's Summit - Radiation Oncology\_Urlology/250290-000\_MECH\_R24.rvt



1

FIRST FLOOR OVERALL PLAN


0' 4' 8' 12' 1/8" = 1'-0"



HVAC GENERAL NOTES

- DUCT SIZES SHOWN ARE ACTUAL INSIDE CLEAR DIMENSIONS. INCREASE SHEET METAL DIMENSIONS AS REQUIRED TO ACCOMMODATE DUCT LINER, WHERE DUCT LINER IS SPECIFIED. DUCTWORK EXPOSED TO SPACE SHALL NOT HAVE EXTERIOR INSULATION.
- T-STATS, HUMIDISTATS AND CO2 SENSORS SHALL BE LOCATED NEXT TO LIGHT SWITCH WITHIN THE ROOM SHOWN. COORDINATE WITH GC AND ELECTRICAL CONTRACTOR TO MATCH HEIGHT AND LOCATION, BUT IN NO CASE HIGHER THAN 48 INCHES A.F.F. PER ADA REQUIREMENTS. COORDINATE EXACT HEIGHT WITH ARCHITECT PRIOR TO INSTALLATION.
- ALL SUPPLY DIFFUSERS, EXHAUST GRILLES, AND RETURN GRILLES WHERE AIRFLOW IS INDICATED, OR AS INDICATED OTHERWISE, SHALL HAVE MANUAL BALANCE DAMPERS WITH STANDOFF AND LOCKING QUADRANT IN AN ACCESSIBLE LOCATION. FOR PLAN CLARITY, NOT ALL DAMPERS MAY BE SHOWN. WHERE HARD LID CEILINGS PREVENT BALANCE DAMPER ACCESS, CONFIRM WITH GRD SCHEDULE OR CONFIRM WITH ENGINEER TO USE CBO'S OR REMOTE BALANCE DAMPERS IF NOT ALREADY INDICATED.
- REFER TO ARCHITECTURAL REFLECTED CEILING PLANS FOR EXACT LOCATION OF ALL CEILING MOUNTED AIR DISTRIBUTION DEVICES.
- ALL DIFFUSERS ARE 4-WAY BLOW UNLESS INDICATED OTHERWISE ON THE DRAWINGS.
- DUCT CONSTRUCTION SHALL COMPLY WITH SMACNA STANDARDS, WITH A MINIMUM HARD DUCT GAUGE THICKNESS OF 26 GAUGE. MINIMUM THICKNESS STATED SATISFIES APPLICABLE IBC LIFE SAFETY DAMPER EXCEPTIONS.
- SQUARE THROAT NOT ALLOWED ON RADIUS ELBOWS.
- FLEXIBLE DUCTWORK IS ALLOWED ON RUNOUTS TO SUPPLY DIFFUSERS ONLY. UTILIZE ONLY ABOVE LAY-IN ACCESSIBLE CEILINGS. DO NOT INSTALL FLEX DUCT ABOVE HARD CEILINGS OR WHERE EXPOSED. A MAXIMUM LENGTH OF 5'-0" MAY BE USED AT EACH CONNECTION.
- SEAL TRANSVERSE AND LONGITUDINAL JOINTS OF ALL DUCTWORK USING HARDCAST DT TPE AND FTA-20 ADHESIVE OR HARDCAST AFG-1402 "FOIL GRIP" PER MANUFACTURERS INSTRUCTIONS.
- ALL DUCTWORK SHALL BE ROUTED AS HIGH AS POSSIBLE WITHIN THE CEILING SPACE. UTILIZE JOIST SPACE WHERE POSSIBLE, ESPECIALLY WHEN CROSSING OTHER DUCT, PIPE, AND ELECTRICAL.
- PROVIDE FLEXIBLE DUCT AND PIPE CONNECTIONS TO ALL MOTORIZED EQUIPMENT.
- VERIFY ALL EQUIPMENT ACCESS PANELS WITH MANUFACTURER AND ARCHITECT. ACCESS PANELS SHALL BE 24X24 UNLESS NOTED OTHERWISE LOCATIONS SHALL BE COORDINATED WITH THE ARCHITECT AND THE LOCATIONS OF THE EQUIPMENT THEY SERVE.
- PAINT INSIDE OF DUCTWORK BLACK ANYWHERE VISIBLE THROUGH FACE OF GRILLE OR DIFFUSER.
- REFER TO GRD SCHEDULE FOR DUCT CONNECTION SIZES. REFER TO TERMINAL BOX SCHEDULE FOR INLET DUCT SIZES.
- CEILING COORDINATION OF ALL MEP SYSTEMS (LIGHTING, DUCTWORK, DIFFUSERS, ELECTRICAL, ETC.) MUST BE COMPLETED BY THE CONTRACTOR PRIOR TO THE START OF ANY NEW INSTALLATION.
- IT IS ASSUMED THAT MOST OF THE RETURN AIR AND EXHAUST MAINS ARE MOUNTED HIGH ABOVE THE CEILING. BALANCE DAMPERS IN THE BRANCH DUCTS FROM THESE MAINS SHALL BE IN THE VERTICAL RISE OF BRANCH NO MORE THAN 8' (WHERE POSSIBLE) ABOVE THE GRILLES AND REGISTERS (SO BALANCE TECHNICIANS CAN EASILY ACCESS THEM THROUGH THE CEILING).
- TERMINAL UNITS SHALL HAVE BOTTOM ELEVATION A MINIMUM 4" ABOVE TOP OF CEILING TILES AND AT MOST 24" ABOVE CEILING. ALL OTHER FLOOR PLANS DO NOT SHOW DUCT ELEVATIONS. FLOOR PLANS DO NOT SHOW ALL DROPS AND RISERS REQUIRED.

RELEASED FOR CONSTRUCTION  
ACI/Boland, Inc. 6/27/2025  
Development Services Department  
Lee's Summit, Missouri  
6/27/2025



ACI  
BOLAND  
ARCHITECTS

ACI/Boland, Inc.  
Kansas City | St. Louis  
1710 Wyandotte  
Kansas City, MO 64108  
T: 816.763.9600

Licensee's Certificate of Authority Number:  
Missouri: #000958

SAINT LUKE'S EAST LEE'S SUMMIT  
VAULT #2 LINEAR ACCELERATOR  
100 NE Saint Luke's Blvd.  
Lee's Summit, MO 64086

Date 06.27.2025  
Job Number 3-25014  
Drawn By VOC  
Checked By EKE

Revision		
Number	Date	Description

PEC PROFESSIONAL ENGINEERING CONSULTANTS, P.A.  
623 MASSACHUSETTS ST SUITE 200, LAWRENCE, KS 66044  
785-842-6464 www.pec.com  
250290-000


M-101

© 2025 ACI/BOLAND, Inc.  
FIRST FLOOR OVERALL PLAN



Autodesk Docs:/5-25014 Saint Luke's East Lee's Summit - Radiation Oncology\_Urlology/250290-000\_MECH\_R24.rvt



6/27/2025 1:28:44 PM



2

## FIRST FLOOR MECHANICAL PIPING DEMO ENLARGED PLAN


0' 4' 8' 12' 1/4" = 1'-0"



1

## FIRST FLOOR HVAC DEMO ENLARGED PLAN

0' 4' 8' 12' 1/4" = 1'-0"



### TEST AND BALANCE NOTE

TAB CONTRACTOR TO TEST AND BALANCE SUPPLY AND RETURN DEVICES AND VAV BOXES PRIOR TO DEMOLITION TO ENSURE AS-BUILT DESIGN CONDITIONS.

### HVAC DEMO NOTES

1. PLANS ARE SCHEMATIC IN NATURE. LAYOUT IS BASED ON BEST AVAILABLE INFORMATION. CONTRACTOR SHALL FIELD VERIFY EXISTING CONDITIONS AND DIMENSIONS, BRING ANY DISCREPANCIES FROM THE DRAWINGS AND NOTES TO THE OWNER'S REPRESENTATIVE IMMEDIATELY. MINOR CHANGES IN THE SCOPE OF THE DEMOLITION WORK SHALL NOT JUSTIFY AN ADDITIONAL COST.
2. DEMOLISH ALL DUCTWORK, PIPING, AND EQUIPMENT SHOWN SHDED, DASHED AND IN A DARK LINE WEIGHT.

### # SHEET KEYNOTES

1. DEMOLISH EXISTING DUCTWORK AND SUPPORTS BACK TO POINT SHOWN. PREPARE DUCTWORK CONNECTIONS TO BE RECONNECTED IN NEW WORK.
2. EXISTING VAV UNIT, PIPING, DUCTWORK, AND ASSOCIATED CONTROLS TO REMAIN. CLEAN AND ENSURE OPERATION IS IN GOOD WORKING ORDER.
3. EXISTING AIR HANDLING UNIT, PIPING, AND ASSOCIATED CONTROLS TO REMAIN.
4. EXISTING DUCTWORK STUBBED INTO SPACE. PREPARE DUCTWORK CONNECTIONS TO BE CONNECTED IN NEW WORK.
5. EXISTING CHILLED WATER PIPING TO REMAIN.
6. EXISTING HEATING HOT WATER PIPING TO REMAIN.
7. REFRIGERANT PIPING TO REMAIN.
8. DEMOLISH EXISTING CHILLER AND DISCONNECT EXISTING PIPING AND PREPARE FOR CONNECTION TO NEW CHILLER.
9. DEMOLISH EXISTING QUICK CONNECT PANELS (QUANTITY TWO STACKED) AND DISCONNECT EXISTING PIPING AND PREPARE FOR CONNECTION TO NEW QUICK CONNECT PANELS IN SAME PLACE.
10. DEMOLISH EXISTING QUICK CONNECT PANELS (QUANTITY TWO STACKED). SEE PIPING DEMOLITION PLAN FOR ADDITIONAL INFORMATION.
11. DEMOLISH EXISTING CHILLER. SEE PIPING DEMOLITION PLAN FOR ADDITIONAL INFORMATION.

SAINT LUKE'S EAST LEE'S SUMMIT  
VAULT #2 LINEAR ACCELERATOR  
100 NE Saint Luke's Blvd.  
Lee's Summit, MO 64086

Date 06.27.2025  
Job Number 3-25014  
Drawn By VOC  
Checked By EKE

Revision  
Number Date Description

PEC PROFESSIONAL ENGINEERING CONSULTANTS, P.A.  
623 MASSACHUSETTS ST SUITE 200, LAWRENCE, KS 66044  
785-842-5664 www.pec.com  
PEC PROJECT NUMBER: 250290-000

M-111  
© 2025 ACI/BOLAND, Inc.

FIRST FLOOR MECHANICAL  
ENLARGED DEMO PLANS


ACI  
BOLAND  
ARCHITECTS

ACI/Boland, Inc.  
Kansas City | St. Louis  
1710 Wyandotte  
Kansas City, MO 64108  
T: 816.763.9600  
Licensee's Certificate of Authority Number:  
Missouri: #000958



RELEASED FOR  
CONSTRUCTION  
At Notice To Proceed  
Development Services Department  
Lee's Summit, Missouri  
06/27/2025







2

## FIRST FLOOR MECHANICAL PIPING ENLARGED PLAN


0' 4' 8' 12' 1/4" = 1'-0"



1

## FIRST FLOOR HVAC ENLARGED PLAN

0' 4' 8' 12' 1/4" = 1'-0"



### # SHEET KEYNOTES

- EXISTING CONDENSING UNIT, PIPING, AND ASSOCIATED CONTROLS TO REMAIN.
- EXISTING VAV UNIT, PIPING, DUCTWORK, AND ASSOCIATED CONTROLS TO REMAIN. CLEAN AND ENSURE OPERATION IS IN GOOD WORKING ORDER.
- INSTALL EXISTING THERMOSTAT ON SITE 48" AFF TO LOCATION SHOWN ON PLAN. EXTEND CONTROL WIRING AS NECESSARY.
- PROVIDE NEW DIFFUSER/GRILLE. RECONNECT TO EXISTING DUCTWORK AND BALANCE TO AIRFLOW SHOWN ON PLAN.
- PROVIDE EXHAUST WALL CAP, BACKDRAFT DAMPER, AND FLASHING ON EXTERIOR WALL. MAINTAIN 25'-0" MINIMUM DISTANCE FROM INTAKES.
- EXISTING CHILLED WATER PIPING TO REMAIN.
- EXISTING HEATING HOT WATER PIPING TO REMAIN.
- REFRIGERANT PIPING TO REMAIN.
- PROVIDE NEW AIR COOLED CHILLER AND INSTALL ON EXISTING CONCRETE PAD. CHILLER WILL REPLACE EXISTING CHILLER CH-RO-1. CONTRACTOR SHALL COORDINATE DOWNTIME WITH OWNER'S REPRESENTATIVE TO MINIMIZE DOWNTIME. RECONNECT TO EXISTING ASSOCIATED PIPING, POWER, ETC AS REQUIRED. COORDINATE EXACT LOCATION WITH EXISTING CONDITIONS AND MAINTAIN ALL REQUIRED MANUFACTURER CLEARANCES.
- RELOCATE EXISTING GRILLE TO BE IN NEW CEILING GRID. EXTEND NEW DUCTWORK/FLEX FROM EXISTING BRANCH AS NEEDED.
- UNDERCUT DOOR 1" FOR TRANSFER AIR.
- PROVIDE CEILING-MOUNTED EXHAUST FAN AND ALL ACCESSORIES PER SCHEDULE.
- EXISTING AIR HANDLING UNIT, PIPING, AND ASSOCIATED CONTROLS TO REMAIN.
- PROVIDE NEW DUCTWORK AND CONNECT TO EXISTING DUCTWORK MATCH SEAL CLASS.
- PROVIDE NEW QUICK CONNECT CHILLER PANELS IN PLACE OF DEMOLISHED ONES. RECONNECT TO EXISTING POWER, CHILLER PIPING, DRAINAGE PIPING, ETC. AS REQUIRED FOR FULL INSTALLATION. QUICK CONNECT PANEL SHALL BE FILTRINE QCP 1.0-ASX OR EQUIVALENT TO MATCH CHILLER REQUIREMENTS. QUICK CONNECT PANEL IS POWERED FROM CHILLER.

### HVAC GENERAL NOTES

- DUCT SIZES SHOWN ARE ACTUAL INSIDE CLEAR DIMENSIONS. INCREASE SHEET METAL DIMENSIONS AS REQUIRED TO ACCOMMODATE DUCT LINER WHERE DUCT LINER IS SPECIFIED. DUCTWORK EXPOSED TO SPACE SHALL NOT HAVE EXTERIOR INSULATION.
- 1-STATS, HUMIDISTATS AND CO2 SENSORS SHALL BE LOCATED NEXT TO LIGHT SWITCH WITHIN THE ROOM SHOWN. COORDINATE WITH GC AND ELECTRICAL CONTRACTOR TO MATCH HEIGHT AND LOCATION, BUT IN NO CASE HIGHER THAN 48 INCHES A.F.F. PER ADA REQUIREMENTS. COORDINATE EXACT HEIGHT WITH ARCHITECT PRIOR TO INSTALLATION.
- ALL SUPPLY DIFFUSERS, EXHAUST GRILLES, AND RETURN GRILLES WHERE AIRFLOW IS INDICATED, OR AS INDICATED OTHERWISE, SHALL HAVE MANUAL BALANCE DAMPERS WITH STANDOFF AND LOCKING QUADRANT IN AN ACCESSIBLE LOCATION. FOR PLAN CLARITY, NOT ALL DAMPERS MAY BE SHOWN. WHERE HARD LID CEILINGS PREVENT BALANCE DAMPER ACCESS, CONFIRM WITH GRD SCHEDULE OR CONFIRM WITH ENGINEER TO USE OBD'S OR REMOTE BALANCE DAMPERS IF NOT ALREADY INDICATED.
- REFER TO ARCHITECTURAL REFLECTED CEILING PLANS FOR EXACT LOCATION OF ALL CEILING MOUNTED AIR DISTRIBUTION DEVICES.
- ALL DIFFUSERS ARE 4-WAY BLOW UNLESS INDICATED OTHERWISE ON THE DRAWINGS.
- DUCT CONSTRUCTION SHALL COMPLY WITH SMACNA STANDARDS, WITH A MINIMUM HARD DUCT GAUGE THICKNESS OF 26 GAUGE. MINIMUM THICKNESS STATED SATISFIES APPLICABLE IBC LIFE SAFETY DAMPER EXCEPTIONS.
- SQUARE THROAT NOT ALLOWED ON RADIUS ELBOWS.
- FLEXIBLE DUCTWORK IS ALLOWED ON RUNOUTS TO SUPPLY DIFFUSERS ONLY. UTILIZE ONLY ABOVE LAY-IN ACCESSIBLE CEILINGS. DO NOT INSTALL FLEX DUCT ABOVE HARD CEILINGS OR WHERE EXPOSED. A MAXIMUM LENGTH OF 5'-0" MAY BE USED AT EACH CONNECTION.
- SEAL TRANSVERSE AND LONGITUDINAL JOINTS OF ALL DUCTWORK USING HARDCAST DT TAPPE AND FTA-20 ADHESIVE OR HARDCAST AFG-1402 "FOIL GRIP" PER MANUFACTURERS INSTRUCTIONS.
- ALL DUCTWORK SHALL BE ROUTED AS HIGH AS POSSIBLE WITHIN THE CEILING SPACE. UTILIZE JOIST SPACE WHERE POSSIBLE, ESPECIALLY WHEN CROSSING OTHER DUCT, PIPE, AND ELECTRICAL.
- PROVIDE FLEXIBLE DUCT AND PIPE CONNECTIONS TO ALL MOTORIZED EQUIPMENT.
- VERIFY ALL EQUIPMENT ACCESS PANELS WITH MANUFACTURER AND ARCHITECT. ACCESS PANELS SHALL BE 24X24 UNLESS NOTED OTHERWISE. LOCATIONS SHALL BE COORDINATED WITH THE ARCHITECT AND THE LOCATIONS OF THE EQUIPMENT THEY SERVE.
- PAINT INSIDE OF DUCTWORK BLACK ANYWHERE VISIBLE THROUGH FACE OF GRILLE OR DIFFUSER.
- REFER TO GRD SCHEDULE FOR DUCT CONNECTION SIZES. REFER TO TERMINAL BOX SCHEDULE FOR INLET DUCT SIZES.
- CEILING COORDINATION OF ALL MEP SYSTEMS (LIGHTING, DUCTWORK, DIFFUSERS, ELECTRICAL, ETC.) MUST BE COMPLETED BY THE CONTRACTOR PRIOR TO THE START OF ANY NEW INSTALLATION.
- IT IS ASSUMED THAT MOST OF THE RETURN AIR AND EXHAUST MAINS ARE MOUNTED HIGH ABOVE THE CEILING. BALANCE DAMPERS IN THE BRANCH DUCTS FROM THESE MAINS SHALL BE IN THE VERTICAL RISE OF BRANCH NO MORE THAN 8' WHERE POSSIBLE ABOVE THE GRILLES AND REGISTERS (SO BALANCE TECHNICIANS CAN EASILY ACCESS THEM THROUGH THE CEILING).
- TERMINAL UNITS SHALL HAVE BOTTOM ELEVATION A MINIMUM 4" ABOVE TOP OF CEILING TILES AND AT MOST 2" ABOVE CEILING. ALL OTHER FLOOR PLANS DO NOT SHOW DUCT ELEVATIONS. FLOOR PLANS DO NOT SHOW ALL DROPS AND RISERS REQUIRED.

### MECH. PIPING GENERAL NOTES

- PIPING ON EXTERIOR WALLS OR PRE-CAST CONCRETE WALLS TO BE ROUTED IN FRAMED WALL ON INTERIOR SIDE OF INSULATION.
- PROVIDE FLEXIBLE PIPE CONNECTIONS TO ALL MOTORIZED EQUIPMENT.
- VERIFY ALL EQUIPMENT ACCESS PANELS WITH MANUFACTURER AND ARCHITECT.
- REFER TO TERMINAL BOX SCHEDULE FOR ALL BRANCH HEATING WATER PIPE SIZES.
- ALL VALVES SHALL BE INSTALLED ABOVE DROP-IN CEILINGS IN AN ACCESSIBLE LOCATIONS, OR WITH ACCESS PANELS IN HARD LID CEILINGS. ACCESS PANELS SHALL BE 24X24 UNLESS NOTED OTHERWISE. COORDINATE PANEL LOCATIONS WITH ARCHITECT.
- WHERE HYDRONIC RUNOUT SIZES ARE NOT INDICATED, SIZE PER THE FOLLOWING:  
UP TO 3 GPM - 3/4"; UP TO 6 GPM - 1"; UP TO 10 GPM - 1-1/4"; UP TO 17 GPM - 1-1/2"
- HYDRONIC PIPING SHALL BE MAINTAINED FULL SIZE UP TO COIL CONNECTIONS. SHUT-OFF VALVES, STRAINERS, BALANCE VALVES, ETC. WILL NOT BE ALLOWED TO REDUCE FROM LINE/RUNOUT SIZE. CONTROL VALVES MAY BE DOWN SIZED FOR FLOW RATE. NOT TO EXCEED 4 PSIG PRESSURE DROP AT DESIGN FLOW.
- CONTRACTOR SHALL MAINTAIN MINIMUM 4" CLEAR ABOVE LAY-IN CEILINGS.
- COORDINATE ROUTING OF CONDENSATE DRAIN LINES WITH ARCHITECT PRIOR TO INSTALLATION.

ACI  
BOLAND  
ARCHITECTS

ACI/Boland, Inc.  
Kansas City | St. Louis  
1710 Wyandotte  
Kansas City, MO 64108  
T: 816.763.9600

Licensee's Certificate of Authority Number:  
Missouri: #000958

SAINT LUKE'S EAST LEE'S SUMMIT  
VAULT #2 LINEAR ACCELERATOR  
100 NE Saint Luke's Blvd.  
Lee's Summit, MO 64086

Date 06.27.2025  
Job Number 3-25014  
Drawn By VOC  
Checked By EKE

Revision  
Number Date Description

PROFESSIONAL ENGINEERING CONSULTANTS, P.A.  
623 MASSACHUSETTS ST SUITE 200, LAWRENCE, KS 66044  
785-842-6664 www.pec1.com

PEC PROJECT NUMBER: 250290-000

M-112

© 2025 ACI/BOLAND, Inc.  
FIRST FLOOR HVAC ENLARGED PLAN




## CHILLER - AIR COOLED


### REMARKS:

- AIR-COOLED DUAL SCROLL COMPRESSOR. PROVIDE WITH HIGH/LOW PRESSURE STAT, FREEZE CONTROL, PUMP-DOWN SOLENOID VALVE, HEAD AND SUCTION GAUGES, THERMOSTATIC EXPANSION VALVE, AND REFRIGERANT SIGHT GLASS AND DEHYDRATOR. UNIT SHALL BE ABLE TO COMMUNICATE WITH THE EXISTING TEMPERATURE CONTROL SYSTEM.
- PROVIDE WITH INTERNAL 170 GALLON STORAGE COOLING TANK.
- PROVIDE WITH INTERNAL PUMPS, SERVICE VALVES, AND MANUAL BYPASS VALVE.
- PROVIDE WITH AUTOSWITCHOVER TO CITY WATER.
- PROVIDE WEATHER-RESISTANT OUTDOOR INSTALLATION.


MARK	MFR	MODEL	TYPE	FLOW (GPM)	CAP (TONS)	EWT (°F)	LWT (°F)	AMBIENT OA TEMP (°F)	PUMP	COMPRESSOR		CONDENSING FAN		ELECTRICAL			REMARKS
										RLA (EACH)	QTY	FLA (EACH)	QTY	VOLT	PH	FLA	
CH-RO-2	FILTRENE	PCP-1500G-A-WP-DUC	SELF-CONTAINED AIR COOLED	16	15	60	45	95	2@ 2HP	17	2	1.1	4	460	3	30	1-5



### 5 DUCTWORK SUPPORT DETAIL NO SCALE



### 4 EXHAUST FAN DETAIL - CEILING NO SCALE



### 3 DUCT TAKEOFF DETAILS NO SCALE

## VAV TERMINAL UNIT SCHEDULE (FOR REFERENCE ONLY)

### REMARKS:

- EXISTING VAV TERMINAL UNIT TO REMAIN. REBALANCE TO NEW AIRFLOWS AND HEATING WATER GPMs.

MARK	MFR	MODEL	UNIT SIZE	INLET SIZE (INCH)	PRIMARY AIRFLOW		HEATING COIL		REMARKS
					MAX (CFM)	MIN (CFM)	AIR EAT (°F)	HOT WATER COIL LAT (°F)	
VAV-R-14	TITUS	DESV	10	10	1100	1100	55	85	1
VAV-R-18	TITUS	DESV	10	10	750	375	55	85	1
VAV-R-19	TITUS	DESV	12	12	1500	1500	55	85	1

## EXHAUST FAN SCHEDULE

### REMARKS:

- ALL EXHAUST FANS SHALL HAVE PERMANENTLY LUBRICATED BEARINGS AND DISCONNECT SWITCH PROVIDED AND INSTALLED BY EC.
- INLINE EXHAUST FANS SHALL BE PROVIDED WITH ECM/VFD MOTOR, DISCONNECT SWITCH, FAN SPEED CONTROLLER, WIRING PIGTAIL, BACKDRAFT DAMPER, AND VIBRATION ISOLATORS.

A. EXHAUST FAN SHALL OPERATE WITH ROOM LIGHTS BY E.C.

MARK	MFR	MODEL	SERVES	TYPE	MIN. CAPACITY		FAN RPM	DRIVE	MOTOR (BY M.C.)			WT LBS	REMARKS
					CFM	ESP (IN)			NEC FLA (A)	VOLTAGE (V)	PHASE		
EF-1	GREENHECK	SP-A125	SINGLE RESTROOM	CEILING EXHAUST FAN	110	0.13	989	DIRECT	0.2	115 V	1	17	1,2A

## GRILLE, REGISTER, AND DIFFUSER SCHEDULE


### FIRST LETTER IN MARK:

S = SUPPLY DIFFUSER  
R = RETURN GRILLE  
P = PLENUM RETURN GRILLE  
E = EXHAUST GRILLE  
L = SLOT DIFFUSER  
M = LAMINAR FLOW SUPPLY  
C = DIFFUSER  
U = SECURITY GRILLE...


### NOTES:

- PROVIDE SQUARE TO ROUND ADAPTERS AS REQUIRED TO ACCOMMODATE ROUND RUNOUTS.
- PROVIDE ALL LAY-IN GRDs WITH 24x24 LAY-IN PANEL AS REQUIRED.
- FINISH TO BE WHITE UNLESS OTHERWISE SPECIFIED. COORDINATE AND VERIFY ALL FINISHES WITH ARCHITECT.
- ALL SELECTIONS ARE BASED ON A MAXIMUM NC OF 25 UNLESS NOTED OTHERWISE.
- CONTRACTOR SHALL VERIFY ALL CEILING TYPES AND ASSOCIATED BORDER TYPES.
- MARKS USED MAY NOT BE IN SEQUENCE.
- LOUVERED GRILLES TO HAVE FRONT BLADES PARALLEL TO LONG DIMENSION UNLESS WALL MOUNTED.
- WALL MOUNTED LOUVERED GRILLES TO HAVE FRONT BLADES PARALLEL TO FLOOR.

MARK	TYPE	BASED ON		MOUNT	PANEL SIZE (FACE SIZE)	MATERIAL	COLOR	REMARK
		MFR	MODEL					
RB	RETURN GRILLE	TITUS	23RL	LAY-IN	24x24	ALUMINUM	WHITE	--
SJ	SUPPLY DIFFUSER	TITUS	OMNI-AA	LAY-IN	24x24	ALUMINUM	WHITE	--
SM	SUPPLY DIFFUSER	TITUS	TMS-AA	LAY-IN	24x24	ALUMINUM	WHITE	LOUVERED FACE
SM	SUPPLY DIFFUSER	TITUS	TMS-AA	LAY-IN	12x12	ALUMINUM	WHITE	LOUVERED FACE





### 1 DIFFUSER INSTALLATION DETAIL NO SCALE



- NOTES:
- INSULATE PIPING PER SPECIFICATIONS AND PROVIDE PROTECTIVE ALUMINUM JACKET WHERE EXPOSED TO WEATHER.
  - MECH. CONTRACTOR SHALL COORDINATE REQUIREMENTS OF MANUFACTURER RECOMMENDED CLEARANCES FOR SCREEN WALL CONSTRUCTION. CLEARANCES SHALL BE MAINTAINED.
  - EXISTING PIPING SHALL BE RECONNECTED. PROVIDE NEW PIPING ACCESSORIES AS REQUIRED FOR PIPING SHOWN IN ABOVE DETAIL AS NEEDED IF PORTIONS WERE DEMOLISHED WHEN OLD CHILLER WAS REMOVED.

### 2 CHILLER DETAIL - AIR COOLED NO SCALE





1

FIRST FLOOR FIRE PROTECTION ENLARGED PLAN

0' 4' 8' 12' 1/4" = 1'-0"

FIRE PROTECTION NOTES

1. PIPING TO BE BLACK IRON WITH SCREWED MALLEABLE IRON FITTINGS OR MECHANICAL GROOVE FITTINGS. SEE SPECIFICATIONS FOR DETAILS AND APPLICATIONS.
2. PIPE HANGERS TO BE UL LISTED AND MOUNTED IN ACCORDANCE WITH NFPA-13.
3. DO NOT OBSTRUCT SPRINKLERS WITH OTHER UTILITIES.
4. SEE SPECIFICATIONS FOR SPRINKLER HEAD TYPES AND APPLICATIONS. ALL SPRINKLER HEADS TO BE QUICK-RESPONSE TYPE. ALL SPRINKLER HEADS SHALL BE LOCATED IN EXACT CENTER OF CEILING TILES.
5. FIRE SPRINKLER DESIGN IS THE RESPONSIBILITY OF THE FIRE SPRINKLER CONTRACTOR. FINAL DESIGN SHALL BE SEALED BY A REGISTERED LICENSED ENGINEER IN THIS STATE. FIRE MARSHALL APPROVED SHOP DRAWINGS SHALL BE SUBMITTED TO THE DESIGN ENGINEER FOR APPROVAL.
6. COORDINATE PIPE ROUTING AND HEAD LOCATIONS WITH OTHER TRADES. PIPING AND HEADS NOT COORDINATED SHALL BE MOVED AT THE CONTRACTOR'S EXPENSE TO ACCOMPLISH CEILING HEIGHTS AS CALLED OUT ON THE ARCHITECT'S DRAWINGS.
7. COORDINATE CLOSELY WITH ALL OTHER TRADES PRIOR TO CONSTRUCTION AND PROVIDE BIM MODEL TO CONSTRUCTION MANAGER FOR COORDINATION AMONG DISCIPLINES IF APPLICABLE.
8. FIRE PROTECTION ENGINEER OF RECORD SHALL DETERMINE HAZARD CLASSIFICATIONS.

HATCH LEGEND:

- [NO HATCH] [WET] LIGHT HAZARD
- [DIAGONAL HATCH] [WET] ORDINARY HAZARD GROUP 1
- [CROSS-HATCH] [DRY] SPRINKLER SYSTEM

NOTE:  
FIRE PROTECTION ENGINEER TO CONFIRM SYSTEM TYPES AND BOUNDARIES.

SAINT LUKE'S EAST LEE'S SUMMIT  
VAULT #2 LINEAR ACCELERATOR  
100 NE Saint Luke's Blvd.  
Lee's Summit, MO 64086

Date 06.27.2025  
Job Number 3-25014  
Drawn By VOC  
Checked By EKE

Revision  
Number Date Description

F-111

© 2025 ACI/BOLAND, Inc.  
FIRST FLOOR FIRE PROTECTION  
ENLARGED PLAN

ACI  
BOLAND  
ARCHITECTS


ACI/Boland, Inc.  
Kansas City | St. Louis  
1710 Wyandotte  
Kansas City, MO 64108  
T: 816.763.9600

Licensee's Certificate of Authority Number:  
Missouri: #000958




PEC  
PROFESSIONAL ENGINEERING CONSULTANTS, P.A.  
623 MASSACHUSETTS ST SUITE 200, LAWRENCE, KS 66044  
785-842-6664 www.pec1.com  
PEC PROJECT NUMBER: 250200-000





**2 FIRST FLOOR PLUMBING ENLARGED DEMO PLAN**  
0' 4' 8' 12' 1/4" = 1'-0"



**1 FIRST FLOOR PLUMBING ENLARGED PLAN**  
0' 4' 8' 12' 1/4" = 1'-0"

- PLUMBING GENERAL NOTES**
1. REFER TO THE PLUMBING FIXTURE SCHEDULE FOR PIPE SIZES TO INDIVIDUAL FIXTURES.
  2. NOT ALL REQUIRED CLEANOUTS ARE NECESSARILY SHOWN ON THESE PLANS. PROVIDE CLEANOUTS ON WASTE, VENT AND STORM PIPING AS REQUIRED BY CODE AND FOR REASONABLE MAINTENANCE BASED ON ACTUAL FIELD INSTALLATION.
  3. PIPING ON EXTERIOR WALLS OR PRE-CAST WALLS TO BE ROUTED IN FRAMED WALL ON INTERIOR SIDE OF INSULATION.
  4. TERMINATE PLUMBING VENTS NOT LESS THAN 12" ABOVE ROOF AND A MINIMUM OF 25'-0" FROM MECHANICAL OUTDOOR AIR INTAKES.
  5. AVOID ROUTING OVER ELECTRICAL ROOMS AND ELECTRICAL PANELS. MAINTAIN N.E.C. CLEARANCES. COORDINATE ROUTING WITH ELECTRICAL CONTRACTOR.
  6. ROUTE DOMESTIC HOT WATER RECIRCULATION PIPES DOWN THE WALL TO WITHIN 2' OF ALL PUBLIC LAVATORIES WITH A 1/2" RUNOUT. IF TWO OR MORE LAVATORIES SHARE A 1/2" OR LARGER BRANCH PIPE, THE HOT WATER RECIRCULATION PIPE SHALL CONNECT TO WITHIN 6" OF EACH LAVATORY.
  7. ALL VALVES SHALL BE INSTALLED ABOVE DROP-IN CEILING IN ACCESSIBLE LOCATIONS, OR WITH ACCESS PANELS IN HARD LID CEILINGS.
  8. ACCESS PANELS SHALL BE 24x24, UNLESS NOTED OTHERWISE. LOCATIONS SHOWN ARE APPROXIMATE. EXACT LOCATIONS SHALL BE COORDINATED WITH THE ARCHITECTURAL DRAWINGS AND EQUIPMENT LOCATIONS. PROVIDE RATED ACCESS PANELS WHEREVER REQUIRED BY APPLICABLE CODES.
  9. ALL PIPING SHALL BE ROUTED AS HIGH AS POSSIBLE IN THE CEILING SPACE. UTILIZE JOIST SPACE WHEN POSSIBLE, ESPECIALLY WHERE CROSSING OTHER PIPES, DUCTS AND ELECTRICAL.
  10. PROVIDE ACCESSIBLE SHUT-OFF VALVES TO ALL APPLIANCES AND EQUIPMENT.
  11. TRAP PRIMERS OR TRAP GUARDS SHALL BE INSTALLED AT ALL FLOOR RECEPTORS. INSTALL IN ACCORDANCE WITH IPC.
  12. COORDINATE ROUTING OF CONDENSATE DRAIN LINES WITH OTHER TRADES PRIOR TO INSTALLATION TO ENSURE SLOPE CAN BE MET.
  13. VERIFY AND REFER TO ARCHITECTURAL DIMENSIONAL FLOOR PLAN FOR EXACT LOCATIONS OF ALL FIXTURES AND EQUIPMENT.


- MED GAS GENERAL NOTES**
1. PLANS ARE SCHEMATIC IN NATURE. LAYOUT IS BASED ON BEST AVAILABLE INFORMATION. CONTRACTOR SHALL FIELD VERIFY EXISTING CONDITIONS AND DIMENSIONS.
  2. ALL CUTTING, PATCHING, AND DEMOLITION WORK SHALL BE CLOSELY COORDINATED WITH THE EXISTING CONDITIONS AND THE REQUIRED NEW WORK. G.C. SHALL PATCH AND FINISH PENETRATIONS OF EXISTING SURFACES TO MATCH ADJACENT SURFACES.
  3. FIELD VERIFY BEST ROUTING FOR NEW PIPING AND DUCTWORK. COORDINATE WITH EXISTING EQUIPMENT, PIPING, AND DUCTWORK. PIPING SHALL RISE AND DROP, JOG OR OFFSET AS REQUIRED TO AVOID CONFLICTS. DUCTWORK SHALL TAKE PRECEDENCE OVER ALL PIPING EXCEPT WHERE GRADE MUST BE MAINTAINED FOR DRAINAGE. ANY EXPENSES RISING FROM LACK OF COORDINATION SHALL BE MADE AT THE CONTRACTOR'S EXPENSE.
  4. REFER TO ARCHITECTURAL SPECIFICATIONS AND PLANS FOR PHASING OF DEMOLITION AND NEW WORK. ADJACENT AREAS ARE OCCUPIED AND CONTRACTOR SHALL WORK CLOSELY WITH OWNER TO SCHEDULE DEMOLITION AND CONSTRUCTION TO BE AS LEAST DISRUPTIVE AS POSSIBLE.
  5. MEDICAL GAS ALARM CABLING SHALL BE PROVIDED AND INSTALLED BY E.C. VERIFY REQUIREMENTS WITH MEDICAL GAS SUPPLIER. ALL MEDICAL GAS WIRING SHALL BE IN CONDUIT.

- # SHEET KEYNOTES**
1. EXISTING MEDICAL GASES CAPPED FOR FUTURE TO REMAIN.
  2. CIRCUIT SETTER TO MAINTAIN 110 DEG F CIRCULATING TEMPERATURE. SET FLOW TO 1 GPM.
  3. DEMOLISH EXISTING HWC PIPING BACK TO POINT SHOWN. PREPARE PIPE CONNECTIONS TO BE RECONNECTED IN NEW WORK.
  4. ROUTE 1/2" CW DOWN IN WALL AND CONNECT TO DF-1.
  5. ROUTE 2" WASTE UP IN WALL AND CONNECT TO DF-1.




PLUMBING FIXTURE SCHEDULE

MARK	DESCRIPTION	MANUFACTURER	MODEL	DIMENSIONS	ADA COMPLIANT	MATERIAL AND FINISH	TRIM					FLOW		PIPE RUNOUT SIZES				SPECIFICATION
							MANUFACTURER	MODEL	FINISH	CONTROL TYPE	POWER	GALLONS PER MINUTE (GPM)	GALLONS PER FLUSH (GPF)	COLD WATER	HOT WATER	WASTE	VENT	
LV-1	LAVATORY - WALL HUNG - SENSOR	KOHLER	K-2031 "GREENWICH"	20-3/4" x 18-1/4", 15" x 10" BOWL	YES	WHITE VITREOUS CHINA	CHICAGO FAUCET CO	116.222.AB.1T	CHROME	SENSOR	BATTERY	0.5	--	1/2"	1/2"	2"	1-1/2"	WALL HUNG LAVATORY WITH CENTERED SINGLE FAUCET HOLE - DRILLED FOR CONCEALED ARM CARRIER - BATTERY POWERED SENSOR FAUCET WITH INTEGRAL ASSE 1070 THERMOSTATIC MIXING VALVE SET TO 105°F, LAMINAR FLOW DEVICE IN BASE OF SPOUT - DRAIN WITH GRID STRAINER - CHROME PLATED WALL SUPPLIES WITH LOOSE KEY QUARTER TURN STOPS - 1-1/4" CHROME PLATED CAST BRASS P-TRAP - FLOOR-MOUNTED CONCEALED ARM CARRIER - INSULATE P-TRAP AND HOT WATER SUPPLY
SK-1	SINK - SINGLE BOWL - INTEGRAL WITH COUNTERTOP	--	--	21-1/2" x 18-1/2" x 5-3/8", 19" x 16" x 5-3/8" BOWL	NO	STAINLESS STEEL, 18 GA	CHICAGO FAUCET CO	116.223.AB.1T	CHROME	SENSOR	BATTERY	1.5	--	1/2"	1/2"	2"	1-1/2"	INTEGRAL COUNTERTOP SINK, COORDINATE NUMBER OF HOLES AND LOCATION WITH G.C. - GOOSENECK DECK MOUNTED SINGLE FAUCET WITH USER ADJUSTABLE TEMPERATURE CONTROL MIXER - ASSE 1070 THERMOSTATIC MIXING VALVE SET TO 110°F, LAMINAR FLOW DEVICE IN BASE OF SPOUT - PROVIDE WITH DUO STRAINER WITH NEOPRENE STOPPER - WALL SUPPLIES WITH LOOSE KEY QUARTER TURN STOPS - 1-1/2" CHROME PLATED CAST BRASS P-TRAP - AMERICAN STANDARD NO. 2411.015 PERFORATED GRID STRAINER DRAIN - DEARBORN NO. 510 1-1/2" 17 GAUGE P-TRAP WITH ADAPTER
DF-1	ELECTRIC WATER COOLER - SINGLE BOTTLE FILLER	ELKAY	LZWSM8K	38-7/8" SPOUT HEIGHT	NO	STAINLESS STEEL	--	--	--	--	PLUG-IN	1.1	--	1/2"	--	2"	1-1/2"	FILTERED (EMF3000) - CAPACITY OF 8 GPH OF 60 DEGREE WATER AT ARI CONDITIONS - 1-1/2" CAST BRASS P-TRAP - CHROME PLATED SUPPLIES WITH LOOSE KEY QUARTER TURN STOP - INWALL FRAME/PLATE (MFWS100)
FD-1	FLOOR DRAIN	WATTS	FD-100-A	6"ø STRAINER TOP	--	EPOXY COATED CAST IRON	--	--	--	--	--	--	--	--	--	2"	1-1/2"	EPOXY COATED CAST IRON FLOOR DRAIN WITH ANCHOR FLANGE - REVERSIBLE CLAMPING COLLAR WITH PRIMARY AND SECONDARY WEEPHOLES - ADJUSTABLE ROUND HEEL PROOF NICKLE BRONZE STRAINER - NO HUB OUTLET
WC-1	WATER CLOSET - FLUSH VALVE - FLOOR MOUNTED - ADA	AMERICAN STANDARD	3461.160 "MADERA"	16-1/8" SEAT HEIGHT	YES	WHITE VITREOUS CHINA	--	--	CHROME HANDLE	MANUAL	--	--	1.6	1-1/4"	--	4"	2"	AMERICAN STANDARD ELONGATED BOWL - WATER SAVER FLUSH VALVE - SIPHON JET FLUSH QUIET OPERATION - WHITE, SOLID PLASTIC ELONGATED OPEN FRONT SEAT - FLOOR OUTLET - 1-1/2" TOP SPOUD - MOUNT FLUSH VALVE HANDLE ON OPEN SIDE OF ROOM



- NOTES:
1. OMIT COMPRESSION RESISTANT INSULATING MATERIAL ON PIPES 1-1/2" AND SMALLER.
  2. REFER TO SPECIFICATIONS FOR GUIDANCE ON HANGER SELECTION, APPLICATION, AND INSTALLATION.

1 INSULATED PIPE AT HANGER DETAIL  
NO SCALE



2 FLOOR DRAIN WITH 'TRAP GUARD' DETAIL  
NO SCALE

MEDICAL GAS OUTLET SCHEDULE


REMARKS:					
1. MINIMUM RUNOUT SIZE TO BRANCH MAIN TO BE 1/2" FOR OXYGEN AND MED AIR; 3/4" FOR VAC.					
2. OUTLETS/INLETS SHALL MATCH EXISTING MANUFACTURER STYLE CURRENTLY BEING USED IN FACILITY.					
3. LOCATE A VACUUM SLIDE NEXT TO EACH VACUUM WALL TERMINAL.					
4. SEE ARCHITECTURAL ELEVATIONS FOR EXACT LOCATION OF MEDICAL GAS OUTLETS ON WALL.					
MARK	DESCRIPTION	OXYGEN (O2)	VAC (VAC)	MEDICAL AIR (MA)	REMARKS
MGO-01	WALL OUTLET	1	1	1	1-4









Autodesk Docs/13-25014 Saint Luke's East Lee's Summit - Radiation Oncology\_Urology/250290-000\_ELEC\_R24.rvt 6/27/2025 10:53:59 AM



E6 ENLARGED PLAN - ELECTRICAL ROOM 1F012  
1/4" = 1'-0"



EXISTING BUILDING


PROJECT SCOPE AREA

APPROXIMATE LOCATION OF  
DISTRIBUTION PANEL DP-F1-F-LN.

A4 ELECTRICAL OVERALL PLAN  
1/32" = 1'-0"



PROFESSIONAL ENGINEERING CONSULTANTS, P.A.  
623 MASSACHUSETTS STREET, SUITE 200, LAWRENCE, KS 66044  
785-842-4864 www.pec1.com  
PEC PROJECT NUMBER: 250290-000 PEC AUTHORITY NUMBER: EEC 00466F



SAINT LUKE'S EAST LEE'S SUMMIT  
VAULT #2 LINEAR ACCELERATOR  
100 NE Saint Luke's Blvd.  
Lee's Summit, MO 64086

Date	06.27.2025
Job Number	3-25014
Drawn By	JGM
Checked By	JLW

Number	Date	Description

E-100  
© 2025 ACI/BOLAND, Inc.  
ELECTRICAL OVERALL PLAN

ACI  
BOLAND  
ARCHITECTS

ACI/Boland, Inc.  
Kansas City | St. Louis  
1710 Wyandotte  
Kansas City, MO 64108  
T: 816.763.9600  
Licensee's Certificate of Authority Number:  
Missouri: #000958





6/27/2025 10:54:00 AM

Autodesk Docs://3-25014 Saint Luke's East Lee's Summit - Radiation Oncology\_Urology/250290-000\_ELEC\_R24.rvt

**A5 ELECTRICAL DEMOLITION PLAN**  
1/4" = 1'-0"



**DEMOLITION GENERAL NOTES**

- DEMOLITION PLANS SHOW THE GENERAL EXTENT OF THE ELECTRICAL DEMOLITION WORK. THE ELECTRICAL CONTRACTOR SHALL DISCONNECT ELECTRICAL SERVICES TO ALL EQUIPMENT BEING REMOVED. SEE MECHANICAL PLANS. OWNER SHALL HAVE THE OPTION TO RETAIN REUSABLE ITEMS, SUCH AS COVERPLATES, RECEPTACLES, LIGHTS, PANELS, ETC. NOT BEING USED IN THE FINISHED WORK. COORDINATE WITH OWNER PRIOR TO STARTING DEMOLITION. PROPERLY AND LEGALLY DISPOSE OF ALL EQUIPMENT AND MATERIALS BEING REMOVED.
- REMOVE ALL CONDUIT LEFT EXPOSED BY REMOVAL OF WALLS AND CEILINGS IN REMODELED AREAS. PLUG BOTH ENDS OF REMAINING CONDUIT IN WALL OR FLOOR WHERE CUT.
- ELECTRICAL OUTLETS, ETC. POSSIBLY CONCEALED BY STORAGE SHELVING, CASEWORK, FURNITURE, ETC. ARE NOT SHOWN AND MAY REQUIRE REMOVAL.
- GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR PATCHING ALL OPENINGS IN EXISTING CONSTRUCTION AFTER REMOVAL OF EQUIPMENT, RACEWAY SYSTEMS, OUTLET BOXES, ETC.
- WHERE EQUIPMENT AND OTHER DEVICES ARE BEING REMOVED, THE CIRCUITING SHALL BE REMOVED, IF POSSIBLE, BACK TO POINT OF SUPPLY. WHERE REQUIRED, CIRCUITING SHALL BE EXTENDED TO MAINTAIN CONTINUITY OF THE CIRCUIT OR OPERATION OF THE SYSTEM.
- ALL DEVICES SHOWN DASHED ON THE DEMOLITION PLAN(S) SHALL BE REMOVED, UNLESS NOTED OTHERWISE.
- PROVIDE MATCHING BLANK COVERPLATES WHERE DEVICES ARE BEING REMOVED FROM FLUSH-MOUNTED OUTLET BOXES IN EXISTING WALLS TO REMAIN.
- FIELD VERIFY ALL EXISTING CONDITIONS AND DIMENSIONS PRIOR TO BEGINNING WORK.

**# SHEET KEYNOTES**

- D1 REMOVE DEVICE AND PROTECT DURING CONSTRUCTION FOR REINSTALLATION. REFER TO A5/E-132 AND A5/142 FOR NEW LOCATION(S).
- D2 REMOVE QUAD RECEPTACLE AND DATA OUTLET FOR INSTALLATION OF NEW SLIDING DOOR. RECONFIGURE RECEPTACLE CIRCUIT SUCH THAT REMAINING DEVICES ON CIRCUIT REMAIN ACTIVE AFTER DEMOLITION.
- E3 (8) 3/4" AND (1) 2" EXISTING CONDUITS ROUTED THROUGH VAULT WALL AND STUBBED FOR FUTURE USE. NEW CIRCUITS ARE TO BE ROUTED THROUGH EXISTING CONDUITS WHERE POSSIBLE.

SHADED AREA NOT IN SCOPE OF WORK UNLESS NOTED OTHERWISE.

**PEC**  
PROFESSIONAL ENGINEERING CONSULTANTS, P.A.  
623 MASSACHUSETTS STREET, SUITE 200, LAWRENCE, KS 66044  
785-842-6864 www.pec1.com  
PEC PROJECT NUMBER: 250290-000  
PEC AUTHORITY NUMBER: EGC 00466F

Revision		
Number	Date	Description

Date 06.27.2025  
Job Number 3-25014  
Drawn By JGM  
Checked By JLW

**SAINT LUKE'S EAST LEE'S SUMMIT  
VAULT #2 LINEAR ACCELERATOR**  
100 NE Saint Luke's Blvd.  
Lee's Summit, MO 64086


**ACI  
BOLAND  
ARCHITECTS**

ACI/Boland, Inc.  
Kansas City | St. Louis  
1710 Wyandotte  
Kansas City, MO 64108  
T: 816.763.9600  
Licensee's Certificate of Authority Number:  
Missouri: #000958





6/27/2025 10:54:01 AM  
Autodesk Docs/3-25014 Saint Luke's East Lee's Summit - Radiation Oncology\_ Urology/250290-000\_ELEC\_R24.rvt



A5 ELECTRICAL POWER PLAN - ENLARGED VIEW  
1/4" = 1'-0"



## IMAGING GENERAL NOTES

- REFER TO IMAGING MANUFACTURER'S FINAL SITE SPECIFIC INSTALLATION DRAWINGS FOR CABLE TRAY, DUCTS, CONDUITS, CONDUCTORS, EPO SWITCHES, AND ALL DEVICES REQUIRED FOR A COMPLETE AND FUNCTIONAL SYSTEM.
- CONTRACTOR TO REUSE EXISTING CONDUITS AND RACEWAYS TO THE MAXIMUM EXTENT POSSIBLE. ALL CONDUITS AND RACEWAYS SHALL BE FIELD VERIFIED.
- CONTRACTOR SHALL COORDINATE PRECONSTRUCTION MEETING WITH VARIAN TO REVIEW PRODUCT PLANNING GUIDE AND VARIAN CHECKLIST EXPECTATIONS.
- PER VARIAN REQUIREMENTS, PROVIDE MINIMUM #12 GROUND TO VARIAN WALL AND CEILING COMPONENTS INCLUDING RELAY JUNCTION BOX (T05), POSITIONING LASER (T06) PLATES, IN-ROOM MONITOR (T07) POST, LIVE-VIEW CAMERA (T10) PLATE, AND OPTICAL IMAGING CAMERA (T20) POST.
- FIELD VERIFY ALL CEILING POST AND CEILING CAMERA LOCATIONS WITH OWNER PRIOR TO ROUGH-IN.
- PER VARIAN REQUIREMENTS, ALL CONDUITS SHALL BE DRY, CLEAN, AND HAVE PULL STRINGS. CLEAN OUT AND VACUUM EXISTING CONDUITS AND IN-FLOOR BOXES AS REQUIRED.
- CONTRACTOR TO REUSE EXISTING CONDUITS AND RACEWAYS TO THE MAXIMUM EXTENT POSSIBLE. ALL CONDUITS AND RACEWAYS SHALL BE FIELD VERIFIED.

## POWER GENERAL NOTES

- BRANCH CIRCUITS ARE INDICATED AS ONE CIRCUIT HOME RUNS WITH INDIVIDUAL NEUTRALS. A MAXIMUM OF THREE CIRCUITS (MAXIMUM OF THREE PHASE CONDUCTORS) MAY BE GROUPED IN A SINGLE CONDUIT. WHERE MULTIPLE CIRCUITS ARE LOCATED IN THE SAME RACEWAY, JUNCTION BOX OR ENCLOSURE, NEUTRALS SHALL BE MARKED OR LABELED TO INDICATE WHICH CIRCUIT THEY ARE ASSOCIATED WITH. SEE SPECIFICATION SECTION "LOW VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES" FOR ADDITIONAL INFORMATION.
- A GROUND CONDUCTOR SIZED PER N.E.C. ARTICLE 250 IS REQUIRED IN ALL CONDUITS.
- FOR CONNECTION REQUIREMENTS TO MECHANICAL UNITS, SEE MECHANICAL EQUIPMENT CONNECTION SCHEDULE.
- REFER TO THE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS FOR LOCATIONS OF FIRE RATED WALLS AND CEILINGS AND THE ASSOCIATED U.L. ASSEMBLY NUMBERS.
- FOR ALL PENETRATIONS IN FIRE RATED WALLS AND CEILINGS, PROVIDE AN ASTM E814 COMPLIANT, U.L. LISTED THROUGH PENETRATION FIRE STOPPING SYSTEM THAT IS SPECIFIC TO THE WALL OR CEILING CONSTRUCTION ASSEMBLY. INSTALL SYSTEM IN STRICT COMPLIANCE WITH THE U.L. ASSEMBLY INDICATED IN THE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS.
- ALL PIPING, CONDUIT, AND OUTLET BOXES (ELECTRIC, TELEPHONE, COMPUTER, ETC.) IN FIRE RATED WALLS OR CEILINGS SHALL BE CONSTRUCTED OF NON-COMBUSTIBLE MATERIAL.
- OUTLET BOXES (ELECTRIC, TELEPHONE, COMPUTER, ETC.) ON OPPOSITE SIDES OF FIRE RATED WALLS SHALL BE SEPARATED BY A HORIZONTAL DISTANCE OF 24 INCHES OR PROTECTED BY OTHER MEANS ALLOWED BY THE SPECIFIC U.L. ASSEMBLY.
- REFER TO ARCHITECTURAL DRAWINGS FOR LOCATIONS OF STC RATED WALLS. OUTLET BOXES (ELECTRIC, TELEPHONE, COMPUTER, ETC.) ON OPPOSITE SIDES OF STC RATED WALLS SHALL BE LIMITED TO TWO OUTLET BOXES PER STUD SPACE AND COVERED WITH "PUTTY PAD" TYPE MOLDABLE FIRE BARRIER.
- FIELD VERIFY THE EXACT LOCATION OF ALL FLOOR BOXES AND POKE THROUGH WITH ARCHITECT PRIOR TO ROUGH-IN.
- PROVIDE ALL ISOLATED GROUND CIRCUITS WITH INDIVIDUAL NEUTRAL CONDUCTORS AND EQUIPMENT GROUND CONDUCTORS.

## # SHEET KEYNOTES

- P1 CONTRACTOR TO PROVIDE 7000AVS SERIES TRANSECTOR 50 KVA POWER CONDITIONER, 480V INPUT, 480V OUTPUT, MODEL NO. 8DNX-50K-700AVS.
- P2 ALTERNATE BID NO. 1: CONTRACTOR TO REPLACE EXISTING POWER CONDITIONER. TRANSECTOR
- P3 FLUSH MOUNT DUPLEX RECEPTACLE IN CEILING TILE FOR PATIENT LIFT POWER. COORDINATE WITH VENDOR'S INSTALLED LOCATION SO RECEPTACLE IS WITHIN 3' OF RAIL END.
- P4 MAIN DISCONNECT PANEL (T13), PROVIDED BY VARIAN, INSTALLED BY THE ELECTRICAL CONTRACTOR.
- P5 ROUTE (4) #1 AWG & (1) #4 GROUND IN 2-1/2" C. TO EXISTING 80A:3P CIRCUIT BREAKER IN DISTRIBUTION PANEL DP-F1-17-HA LABELED "FUTURE-TRUEBEAM". ALSO, ROUTE(4) #1 AWG & (1) #4 GROUND IN 2-1/2" C. TO MAIN DISTRIBUTION PANEL LOCATED IN CONTROL ROOM (KEYNOTE P4).
- P6 RELAY JUNCTION BOX (T05) TO BE FURNISHED BY VARIAN AND INSTALLED BY THE ELECTRICAL CONTRACTOR. MOUNT AT EYE LEVEL AT APPROXIMATELY 6' BELOW CEILING. EXTEND (2) 2" STUBBED UP CONDUITS TO RELAY BOX. VERIFY LOCATION WITH VARIAN PRIOR TO INSTALLATION AND WIRE PER VARIAN REQUIREMENTS.
- P7 POWER TO POSITIONING LASER (T06) TO BE PROVIDED VIA RELAY BOX (T05). COORDINATE LOCATION SO THAT RECEPTACLE IS WITHIN 3' OF LASER. VERIFY EXACT LOCATION WITH VARIAN PRIOR TO ROUGH-IN.
- P8 FLUSH MOUNT DUPLEX RECEPTACLE IN CEILING TILE FOR POWER TO IN-ROOM MONITOR (T07) AND MICROPHONE (T08). COORDINATE LOCATION SO RECEPTACLE IS WITHIN 4' OF MONITOR AND PLACE IN ADJACENT CEILING TILE TO WHERE THE MOUNTING POST PASSES THROUGH CEILING.
- P9 POWER TO CCTV CAMERA (T09). COORDINATE LOCATION SO THAT RECEPTACLE IS WITHIN 1' OF CAMERA. FIELD VERIFY EXACT LOCATION AND MOUNTING HEIGHT WITH VARIAN PRIOR TO ROUGH-IN.
- P10 FURNISH AND INSTALL ACCESSORY PULLBOX (CP04) SIZED FOR APPLICATION FOR VARIAN IDENTIFY SYSTEM. LOCATION SHOWN IS FOR DRAWING CLARITY. ADJUST LOCATION AS REQUIRED AND IF POSSIBLE AVOID CONDUIT BENDS WITH BOX PLACEMENT. EXTEND (2) 2" AND (1) 3" STUBBED UP CONDUITS TO PULLBOX LOCATION.
- P11 INTERLOCK DOOR WITH RELAY BOX (T05) PER VARIAN REQUIREMENTS.
- P12 CONTRACTOR TO INSTALL A DUPLEX RECEPTACLE AND EMPTY DOUBLE GANG JUNCTION BOX ABOVE COUNTER FOR OWNER PROVIDED STREAMING DEVICE THAT WILL PLUG INTO AN AUXILIARY PORT ON THE BACK SIDE OF THE LINEAR ACCELERATOR KEYBOARD WITHIN CONTROL ROOM. VERIFY LOCATION WITH OWNER PRIOR TO INSTALLATION.
- P13 SWITCH FOR OVERNIGHT SHUT-OFF OF LASERS PROVIDE THERMAL TRANSFER STYLE LABEL TO INDICATE SWITCH FUNCTION. VERIFY SWITCH LOCATION WITH OWNER PRIOR TO INSTALLATION.
- P14 POWER TO OPTICAL IMAGING CAMERA (T09). COORDINATE LOCATION SO THAT RECEPTACLE IS WITHIN 1' OF CAMERA. FIELD VERIFY EXACT LOCATION AND MOUNTING HEIGHT WITH VARIAN PRIOR TO ROUGH-IN.
- P15 24" X 20" X 6-5/8" VAULT DOOR CONTROL BOX AND 24VDC BATTERY BACKUP BY NELCO. CONDUIT, 120V POWER WIRING, AND JUNCTION BOXES TO OPERATOR TO BE FURNISHED AND INSTALLED BY EC. VERIFY ALL REQUIREMENTS WITH MANUFACTURER'S RECOMMENDATIONS.
- P16 EC TO PROVIDE 90VDC WIRING TO MOTOR. CONNECTIONS TO BE MADE BY NELCO. VERIFY FINAL WIRING REQUIREMENTS AND LOCATION WITH MANUFACTURER.

## SPECIAL OUTLETS

MARK	DESCRIPTION
IEC60309	IEC 60309 30A 250VAC 2P FURNISHED BY VARIAN, INSTALLED BY CONTRACTOR. PURCHASE FROM VARIAN IF NOT INCLUDED IN LINEAR ACCELERATOR PACKAGE. LOCATE ADJACENT TO CONSOLE CABINET. DO NOT INSTALL DIRECTLY BEHIND CONSOLE CABINET. FIELD VERIFY LOCATION WITH VARIAN AND ADJUST LOCATION AS REQUIRED.

PROFESSIONAL ENGINEERING CONSULTANTS, P.A.  
632 MASSACHUSETTS ST. SUITE 200, LAWRENCE, KS 66044  
785-842-3864 www.pec1.com  
PEC PROJECT NUMBER: 250290-000  
PEC AUTHORITY NUMBER: ESC 004067



**ACI**  
**BOLAND**  
**ARCHITECTS**

ACI/Boland, Inc.  
Kansas City | St. Louis  
1710 Wyandotte  
Kansas City, MO 64108  
T: 816.763.9600  
Licensee's Certificate of Authority Number:  
Missouri: #000958

**SAINT LUKE'S EAST LEE'S SUMMIT**  
**VAULT #2 LINEAR ACCELERATOR**  
**100 NE Saint Luke's Blvd.**  
**Lee's Summit, MO 64086**


Date 06.27.2025  
Job Number 3-25014  
Drawn By JGM  
Checked By JLW

Revision  
Number Date Description

**E-121**

© 2025 ACI/BOLAND, Inc.  
ELECTRICAL POWER PLAN





- IMAGING GENERAL NOTES
1.

REFER TO IMAGING MANUFACTURER'S FINAL SITE SPECIFIC INSTALLATION DRAWINGS FOR CABLE TRAY, DUCTS, CONDUITS, CONDUCTORS, EPO SWITCHES, AND ALL DEVICES REQUIRED FOR A COMPLETE AND FUNCTIONAL SYSTEM.
2.

CONTRACTOR TO REUSE EXISTING CONDUITS AND RACEWAYS TO THE MAXIMUM EXTENT POSSIBLE. ALL CONDUITS AND RACEWAYS SHALL BE FIELD VERIFIED.
3.

CONTRACTOR SHALL COORDINATE PRECONSTRUCTION MEETING WITH VARIAN TO REVIEW PRODUCT PLANNING GUIDE AND VARIAN CHECKLIST EXPECTATIONS.
4.

PER VARIAN REQUIREMENTS, PROVIDE MINIMUM #12 GROUND TO VARIAN WALL AND CEILING COMPONENTS INCLUDING RELAY JUNCTION BOX (T05), POSITIONING LASER (T06) PLATES, IN-ROOM MONITOR (T07) POST, LIVE-VIEW CAMERA (T10) PLATE, AND OPTICAL IMAGING CAMERA (T20) POST.
5.

FIELD VERIFY ALL CEILING POST AND CEILING CAMERA LOCATIONS WITH OWNER PRIOR TO ROUGH-IN.
6.

PER VARIAN REQUIREMENTS, ALL CONDUITS SHALL BE DRY, CLEAN, AND HAVE PULL STRINGS. CLEAN OUT AND VACUUM EXISTING CONDUITS AND IN-FLOOR BOXES AS REQUIRED.
7.

CONTRACTOR TO REUSE EXISTING CONDUITS AND RACEWAYS TO THE MAXIMUM EXTENT POSSIBLE. ALL CONDUITS AND RACEWAYS SHALL BE FIELD VERIFIED.

- CONDUIT PLAN GENERAL NOTES
1.

ALL CONDUIT SHOWN IN A LIGHT LINE IS EXISTING TO REMAIN, ROUTED OVERHEAD.
2.

ALL CONDUIT SHOWN IN A DARK LINE IS NEW WORK UNDER THIS CONTRACT, ROUTED OVERHEAD.
3.

ALL ELECTRICAL EQUIPMENT AND WIRING SHOWN IN A LIGHT DASHED LINE IS NEW WORK UNDER THIS CONTRACT, ROUTED UNDERGROUND.
4.

ALL ELECTRICAL EQUIPMENT AND WIRING SHOWN IN A DARK DASHED LINE IS NEW WORK UNDER THIS CONTRACT, ROUTED UNDERGROUND.

- # SHEET KEYNOTES
- E1

APPROXIMATE LOCATION OF EXISTING ACCESS PANEL/RECESSED FLOOR BOX BELOW VARIAN MODULATOR (T03) FOR ACCESS TO EXISTING (3) 4" CONDUITS TO STAND (T01) AND (2) 2" CONDUITS TO MDP (T13).
- E2

APPROXIMATE LOCATION OF EXISTING ACCESS PANEL/RECESSED FLOOR BOX BELOW STAND (T01) FOR ACCESS TO EXISTING (4) 4" CONDUITS TO PULL BOX (CP01), (3) 4" CONDUITS TO MODULATOR (T03), AND (2) 2" CONDUITS STUBBED WITHIN VAULT SPACE.
- E3

(8) 3/4" AND (1) 2" EXISTING CONDUITS ROUTED THROUGH VAULT WALL AND STUBBED FOR FUTURE USE. NEW CIRCUITS ARE TO BE ROUTED THROUGH EXISTING CONDUITS WHERE POSSIBLE.

VARIAN ACCELERATOR CONDUIT SCHEDULE						
FROM	TO	QTY	SIZE	UNDERGROUND OR OVERHEAD	EXISTING	DETAILED ON SHEET
BASEFRAME PULL BOX (CP02)	CONTROL EQUIPMENT PULL BOX	4	4"	UNDERGROUND	YES	E-122
	MODULATOR PULL BOX	3	4"	UNDERGROUND	YES	E-122
	RELAY JUNCTION BOX	2	2"	UNDERGROUND	YES	E-122
MODULATOR PULL BOX (CP03)	MAIN DISCONNECT PANEL	2	2"	UNDERGROUND	YES	E-122
RELAY JUNCTION BOX (T05)	WARNING LIGHTS	1	1/2"	OVERHEAD	NO	E-132
	DOOR INTERLOCK	1	1/2"	OVERHEAD	NO	E-142
ACCESSORY BOX (CP04)	EXTEND EXISTING IN-FLOOR CONDUITS FROM CONTROL RM.	2	2"	UNDERGROUND	YES	E-122
		1	3"	UNDERGROUND	YES	E-122
	OPTICAL IMAGING CAMERA	1	3"	OVERHEAD	NO	E-142
	IN-ROOM MONITOR	1	2"	OVERHEAD	NO	E-142
	MICROPHONE (CEILING)	1	1-1/4"	OVERHEAD	NO	E-142
	CCTV CAMERA (QTY 4)	1	1"	OVERHEAD	NO	E-142
	WALL SPEAKER (QTY 2)	1	1"	OVERHEAD	NO	E-142
	USB HUB	1	1"	OVERHEAD	NO	E-142
MAIN DISCONNECT PANEL (T13)	LIVE-VIEW CAMERA	1	1-1/4"	OVERHEAD	NO	E-142
	CONTROL CONSOLE	1	2"	OVERHEAD	NO	E-122
	IEC 60309 RECEPTACLE	1	2"	OVERHEAD	NO	E-121
NETWORK (DATA)		1	1"	OVERHEAD	NO	E-142
EXPERIMENTAL PHYSICS ACCESS	TREATMENT ROOM	1	4"	UNDERGROUND	YES	E-122

A5-ELECTRICAL CONDUIT PLAN  
1/4" = 1'-0"



ACI  
BOLAND  
ARCHITECTS


ACI/Boland, Inc.  
Kansas City | St. Louis  
1710 Wyandotte  
Kansas City, MO 64108  
T: 816.763.9600  
Licensee's Certificate of Authority Number:  
Missouri: #000958

SAINT LUKE'S EAST LEE'S SUMMIT  
VAULT #2 LINEAR ACCELERATOR  
100 NE Saint Luke's Blvd.  
Lee's Summit, MO 64086


Date 06.27.2025  
Job Number 3-25014  
Drawn By JGM  
Checked By JLW

Revision  
Number Date Description

PROFESSIONAL ENGINEERING CONSULTANTS, P.A.  
623 MASSACHUSETTS ST SUITE 200, LAWRENCE, KS 66044  
785-842-4864 www.pec1.com  
PEC PROJECT NUMBER: 250290-000  
PEC AUTHORITY NUMBER: ESC 00466F







### IMAGING GENERAL NOTES

- REFER TO IMAGING MANUFACTURER'S FINAL SITE SPECIFIC INSTALLATION DRAWINGS FOR CABLE TRAY, DUCTS, CONDUITS, CONDUCTORS, EPO SWITCHES, AND ALL DEVICES REQUIRED FOR A COMPLETE AND FUNCTIONAL SYSTEM.
- CONTRACTOR TO REUSE EXISTING CONDUITS AND RACEWAYS TO THE MAXIMUM EXTENT POSSIBLE. ALL CONDUITS AND RACEWAYS SHALL BE FIELD VERIFIED.
- CONTRACTOR SHALL COORDINATE PRECONSTRUCTION MEETING WITH VARIAN TO REVIEW PRODUCT PLANNING GUIDE AND VARIAN CHECKLIST EXPECTATIONS.
- PER VARIAN REQUIREMENTS, PROVIDE MINIMUM #12 GROUND TO VARIAN WALL AND CEILING COMPONENTS INCLUDING RELAY JUNCTION BOX (T05), POSITIONING LASER (T06) PLATES, IN-ROOM MONITOR (T07) POST, LIVE-VIEW CAMERA (T10) PLATE, AND OPTICAL IMAGING CAMERA (T20) POST.
- FIELD VERIFY ALL CEILING POST AND CEILING CAMERA LOCATIONS WITH OWNER PRIOR TO ROUGH-IN.
- PER VARIAN REQUIREMENTS, ALL CONDUITS SHALL BE DRY, CLEAN, AND HAVE PULL STRINGS. CLEAN OUT AND VACUUM EXISTING CONDUITS AND IN-FLOOR BOXES AS REQUIRED.
- CONTRACTOR TO REUSE EXISTING CONDUITS AND RACEWAYS TO THE MAXIMUM EXTENT POSSIBLE. ALL CONDUITS AND RACEWAYS SHALL BE FIELD VERIFIED.

### LIGHTING GENERAL NOTES

- BRANCH CIRCUITS ARE INDICATED AS ONE CIRCUIT HOME RUNS WITH INDIVIDUAL NEUTRALS. A MAXIMUM OF THREE CIRCUITS (MAXIMUM OF THREE PHASE CONDUCTORS) MAY BE GROUPED IN A SINGLE CONDUIT. WHERE MULTIPLE CIRCUITS ARE LOCATED IN THE SAME RACEWAY, JUNCTION BOX OR ENCLOSURE, NEUTRALS SHALL BE MARKED OR LABELED TO INDICATE WHICH CIRCUIT THEY ARE ASSOCIATED WITH. SEE SPECIFICATION SECTION "LOW VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES" FOR ADDITIONAL INFORMATION.
- A GROUND CONDUCTOR SIZED PER N.E.C. ARTICLE 250 IS REQUIRED IN ALL CONDUITS.
- REFER TO THE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS FOR LOCATIONS OF FIRE RATED WALLS AND CEILINGS AND THE ASSOCIATED U.L. ASSEMBLY NUMBERS.
- FOR ALL PENETRATIONS IN FIRE RATED WALLS AND CEILINGS, PROVIDE AN ASTM E814 COMPLIANT, U.L. LISTED THROUGH PENETRATION FIRE STOPPING SYSTEM THAT IS SPECIFIC TO THE WALL OR CEILING CONSTRUCTION ASSEMBLY. INSTALL SYSTEM IN STRICT COMPLIANCE WITH THE U.L. ASSEMBLY INDICATED IN THE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS.
- ALL PIPING, CONDUIT, AND OUTLET BOXES (ELECTRIC, TELEPHONE, COMPUTER, ETC.) IN FIRE RATED WALLS OR CEILINGS SHALL BE CONSTRUCTED OF NON-COMBUSTIBLE MATERIAL.
- OUTLET BOXES (ELECTRIC, TELEPHONE, COMPUTER, ETC.) ON OPPOSITE SIDES OF FIRE RATED WALLS SHALL BE SEPARATED BY A HORIZONTAL DISTANCE OF 24 INCHES OR PROTECTED BY OTHER MEANS ALLOWED BY THE SPECIFIC U.L. ASSEMBLY.
- REFER TO ARCHITECTURAL DRAWINGS FOR LOCATIONS OF STC RATED WALLS. OUTLET BOXES (ELECTRIC, TELEPHONE, COMPUTER, ETC.) ON OPPOSITE SIDES OF STC RATED WALLS SHALL BE LIMITED TO TWO OUTLET BOXES PER STUD SPACE AND COVERED WITH "PUTTY PAD" TYPE MOLDABLE FIRE BARRIER.
- REFER TO ARCHITECTURAL REFLECTED CEILING PLANS FOR EXACT LIGHT FIXTURE LOCATIONS. VERIFY ALL DISCREPANCIES WITH ARCHITECT PRIOR TO ROUGH-IN.

### # SHEET KEYNOTES

- |    |  |
|----|--|
| L1 | CONNECT TO EMERGENCY CIRCUIT PORTION OF EXISTING LIGHTING CIRCUIT.   |
| L2 | INTERLOCK BEAM-ON LIGHT (CP06) WITH RELAY BOX (T05) PER MANUFACTURER'S INSTRUCTIONS (EACH SIGN REQUIRES SEPARATE CONNECTION).                          |
| L3 | INTERLOCK XRAY-ON LIGHT (CP06) WITH RELAY BOX (T05) PER MANUFACTURER'S INSTRUCTIONS (EACH SIGN REQUIRES SEPARATE CONNECTION).                          |
| L4 | INTERLOCK ROOM LIGHTS WITH RELAY BOX (T05) PER MANUFACTURER'S INSTRUCTIONS.  |
| L5 | FIELD COORDINATE REMOTE DRIVER LOCATIONS FOR FIXTURE TYPES 'HD' AND 'HDE' WITH VARIAN. LOCATE ABOVE ACCESSIBLE CEILING OUTSIDE OF RADIATION BEAM PATH. |

A5 ELECTRICAL LIGHTING PLAN

1/4" = 1'-0"



PLAN NORTH

PROFESSIONAL ENGINEERING CONSULTANTS, P.A.  
623 MASSACHUSETTS ST SUITE 200, LAWRENCE, KS 66044  
785-842-4864 www.pec1.com  
PEC PROJECT NUMBER: 250290-000  
PEC AUTHORITY NUMBER: EEC 00466F



SAINT LUKE'S EAST LEE'S SUMMIT  
VAULT #2 LINEAR ACCELERATOR  
100 NE Saint Luke's Blvd.  
Lee's Summit, MO 64086

Date	06.27.2025
Job Number	3-25014
Drawn By	JGM
Checked By	JLW

Number	Date	Description




ACI  
BOLAND  
ARCHITECTS

ACI/Boland, Inc.  
Kansas City | St. Louis  
1710 Wyandotte  
Kansas City, MO 64108  
T: 816.763.9600  
Licensee's Certificate of Authority Number:  
Missouri: #000958



Autodesk Docs://3-25014 Saint Luke's East Lee's Summit - Radiation Oncology\_Urlology/250290-000\_ELEC\_R24.rvt 6/27/2025 10:54:03 AM



A5 ELECTRICAL SYSTEMS PLAN  
1/4" = 1'-0"

IMAGING GENERAL NOTES

1. REFER TO IMAGING MANUFACTURER'S FINAL SITE SPECIFIC INSTALLATION DRAWINGS FOR CABLE TRAY, DUCTS, CONDUITS, CONDUCTORS, EPO SWITCHES, AND ALL DEVICES REQUIRED FOR A COMPLETE AND FUNCTIONAL SYSTEM.
2. CONTRACTOR TO REUSE EXISTING CONDUITS AND RACEWAYS TO THE MAXIMUM EXTENT POSSIBLE. ALL CONDUITS AND RACEWAYS SHALL BE FIELD VERIFIED.
3. CONTRACTOR SHALL COORDINATE PRECONSTRUCTION MEETING WITH VARIAN TO REVIEW PRODUCT PLANNING GUIDE AND VARIAN CHECKLIST EXPECTATIONS.
4. PER VARIAN REQUIREMENTS, PROVIDE MINIMUM #12 GROUND TO VARIAN WALL AND CEILING COMPONENTS INCLUDING RELAY JUNCTION BOX (T05), POSITIONING LASER (T06) PLATES, IN-ROOM MONITOR (T07) POST, LIVE-VIEW CAMERA (T10) PLATE, AND OPTICAL IMAGING CAMERA (T20) POST.
5. FIELD VERIFY ALL CEILING POST AND CEILING CAMERA LOCATIONS WITH OWNER PRIOR TO ROUGH-IN.
6. PER VARIAN REQUIREMENTS, ALL CONDUITS SHALL BE DRY, CLEAN, AND HAVE PULL STRINGS. CLEAN OUT AND VACUUM EXISTING CONDUITS AND IN-FLOOR BOXES AS REQUIRED.
7. CONTRACTOR TO REUSE EXISTING CONDUITS AND RACEWAYS TO THE MAXIMUM EXTENT POSSIBLE. ALL CONDUITS AND RACEWAYS SHALL BE FIELD VERIFIED.

SYSTEMS GENERAL NOTES

1. REFER TO THE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS FOR LOCATIONS OF FIRE RATED WALLS AND CEILINGS AND THE ASSOCIATED U.L. ASSEMBLY NUMBERS.
2. FOR ALL PENETRATIONS IN FIRE RATED WALLS AND CEILINGS, PROVIDE AN ASTM E814 COMPLIANT, U.L. LISTED THROUGH PENETRATION FIRE STOPPING SYSTEM THAT IS SPECIFIC TO THE WALL OR CEILING CONSTRUCTION ASSEMBLY. INSTALL SYSTEM IN STRICT COMPLIANCE WITH THE U.L. ASSEMBLY INDICATED IN THE ARCHITECTURAL DRAWINGS AND SPECIFICATIONS.
3. ALL PIPING, CONDUIT, AND OUTLET BOXES (ELECTRIC, TELEPHONE, COMPUTER, ETC.) IN FIRE RATED WALLS OR CEILINGS SHALL BE CONSTRUCTED OF NON-COMBUSTIBLE MATERIAL.
4. OUTLET BOXES (ELECTRIC, TELEPHONE, COMPUTER, ETC.) ON OPPOSITE SIDES OF FIRE RATED WALLS SHALL BE SEPARATED BY A HORIZONTAL DISTANCE OF 24 INCHES OR PROTECTED BY OTHER MEANS ALLOWED BY THE SPECIFIC U.L. ASSEMBLY.
5. REFER TO ARCHITECTURAL DRAWINGS FOR LOCATIONS OF STC RATED WALLS. OUTLET BOXES (ELECTRIC, TELEPHONE, COMPUTER, ETC.) ON OPPOSITE SIDES OF STC RATED WALLS SHALL BE LIMITED TO TWO OUTLET BOXES PER STUD SPACE AND COVERED WITH "PUTTY PAD" TYPE MOLDABLE FIRE BARRIER.
6. WHERE THE SAME DEVICE IS SHOWN IN THE SAME LOCATION ON BOTH THE POWER AND SYSTEMS PLAN, ONLY ONE DEVICE IS REQUIRED. PROVIDE BOTH POWER AND SYSTEMS WIRING AS SHOWN.
7. THE FIRE ALARM SYSTEM SHOWN HAS BEEN DESIGNED PER THE REQUIREMENTS OF NFPA 72. DEVICES SHOWN INDICATE THE DESIGN INTENT AND SHALL BE THE MINIMUM PROVIDED. SYSTEM SUPPLIER SHALL PROVIDE ANY ADDITIONAL CODE REQUIRED DEVICES OR DEVICES REQUIRED BY THE AUTHORITY HAVING JURISDICTION.

# SHEET KEYNOTES

- E3 (8) 3/4" AND (1) 2" EXISTING CONDUITS ROUTED THROUGH VAULT WALL AND STUBBED FOR FUTURE USE. NEW CIRCUITS ARE TO BE ROUTED THROUGH EXISTING CONDUITS WHERE POSSIBLE.
- S1 MOTIONVIEW CCTV CAMERAS (T09) FURNISHED AND INSTALLED BY VARIAN. CAMERA HOUSING IS FURNISHED BY VARIAN, INSTALLED BY CONTRACTOR. FIELD VERIFY LOCATION AND QUANTITY WITH VARIAN AND OWNER PRIOR TO ROUGH-IN. PROVIDE 1" CONDUIT ROUTED TO CCTV MONITOR (T18) VIA EXISTING UNDERGROUND CONDUIT BETWEEN PULL BOXES (CP01) AND (CP04).
- S2 WALL MOUNT SPEAKER (T11) FURNISHED BY VARIAN, INSTALLED BY CONTRACTOR. PROVIDE 1" CONDUIT ROUTED TO CONTROL CONSOLE (T17) VIA EXISTING UNDERGROUND CONDUIT BETWEEN PULL BOXES (CP01) AND (CP04). LOCATE OUTSIDE OF PRIMARY BEAM PATH. FIELD VERIFY LOCATION WITH OWNER PRIOR TO ROUGH-IN. PROVIDE CABLE ACCESS WITH 6" OF SPEAKER.
- S3 LIVE VIEW CAMERA (T10) FURNISHED AND INSTALLED BY VARIAN. WALL MOUNTING POST IS VARIAN PROVIDED AND CONTRACTOR INSTALLED. URNISH AND INSTALL 2 GANG ELECTRICAL BOX WITH 1-1/4" CONDUIT ROUTED TO CONSOLE CABINET (T14) VIA EXISTING UNDERGROUND CONDUIT BETWEEN PULL BOXES (CP01) AND (CP04). LOCATE ON EITHER SIDE OF ISOCENTER WITH CABLE ACCESS WITHIN 6". FIELD VERIFY LOCATION WITH VARIAN PRIOR TO ROUGH-IN.
- S4 DOOR SWITCHES (CP05) FURNISHED AND INSTALLED BY NELCO. PROVIDE 1-1/2" CONDUIT ROUTED TO MODULATOR VIA RELAY JUNCTION BOX (T05) AND INTERLOCK AS REQUIRED.
- S5 MICROPHONE (T08) FURNISHED AND INSTALLED BY VARIAN. PROVIDE 1-1/4" CONDUIT ROUTED TO CONTROL CONSOLE (T17) VIA PULL BOX (CP01).
- S6 IN-ROOM MONITOR (T07) FURNISHED AND INSTALLED BY VARIAN. PROVIDE 2" CONDUIT ROUTED TO CONSOLE CABINET (T14).
- S7 1-GANG ROUGH-IN BOX FOR VARIAN CABLING TO USB HUB (T12). PROVIDE 1" CONDUIT ROUTED TO CONSOLE CABINET (T14) VIA EXISTING UNDERGROUND CONDUIT BETWEEN PULL BOXES (CP01) AND (CP04).
- S8 OPTICAL IMAGING CAMERA (T20) AND WIRING FURNISHED AND INSTALLED BY VARIAN. MOUNTING POST INSTALLED BY CONTRACTOR. PROVIDE 3" CONDUIT ROUTED TO CONSOLE CABINET (T14). FIELD VERIFY EXACT LOCATION WITH VARIAN PRIOR TO ROUGH-IN.
- S9 FURNISH AND INSTALL EMERGENCY OFF BUTTON (CP07), ALLEN-BRADLEY 800T-FX6AV OR EQUIVALENT WITH FACEPLATE IN PLEXIGLASS ENCLOSURE. CONNECT TO RELAY BOX (T05) PER VARIAN REQUIREMENTS. VERIFY EXACT LOCATIONS WITH ARCHITECT PRIOR TO INSTALLATION. FURNISH ALL COMPONENTS FOR A COMPLETE INSTALLATION.
- S10 DOOR CONTROL PUSH-BUTTON STATIONS, BACKBOXES TO BE SUPPLIED BY NELCO AND INSTALLED BY EC. VERIFY LOCATION WITH ARCHITECT PRIOR TO ROUGH-IN.

RELEASED FOR CONSTRUCTION  
As Noted - As Shown  
Development Services Department  
Missouri  
BRETT M. WALBRIDGE  
NUMBER  
PE-201903607  
06/27/2025

ACI  
BOLAND  
ARCHITECTS  
ACI/Boland, Inc.  
Kansas City | St. Louis  
1710 Wyandotte  
Kansas City, MO 64108  
T: 816.763.9600  
Licensee's Certificate of Authority Number:  
Missouri: #000958

SAINT LUKE'S EAST LEE'S SUMMIT  
VAULT #2 LINEAR ACCELERATOR  
100 NE Saint Luke's Blvd.  
Lee's Summit, MO 64086

Date06.27.2025  
Job Number3-25014  
Drawn ByJGM  
Checked ByJLW


Revision  
NumberDateDescription

PROFESSIONAL ENGINEERING CONSULTANTS, P.A.  
823 MASSACHUSETTS ST SUITE 200, LAWRENCE, KS 66044  
785-842-4864 www.pec1.com  
PEC PROJECT NUMBER: 250290-000  
PEC AUTHORITY NUMBER: EEC 004667


PEC  
250290-000

E-142  
© 2025 ACI/BOLAND, Inc.  
ELECTRICAL SYSTEMS PLAN







**B6** TYPICAL TELECOM OUTLET MOUNTING DETAIL  
NO SCALE




**B5** TYPICAL RECEPTACLE MOUNTING DETAIL  
NO SCALE




**B4** TYPICAL LAY-IN FIXTURE INSTALLATION  
NO SCALE



**B2** TYPICAL NAMEPLATES AND LABELS  
NO SCALE



**A6** NURSE CALL MOUNTING DETAIL  
1/4" = 1'-0"



**A3** FIRE ALARM DEVICE MOUNTING DETAIL  
NO SCALE

# ACI BOLD ARCHITECTS


ACI/Boland, Inc.  
Kansas City | St. Louis  
1710 Wyandotte  
Kansas City, MO 64108  
T: 816.763.9600  
Licensee's Certificate of Authority Number:  
Missouri: #000958

SAINT LUKE'S EAST LEE'S SUMMIT  
VAULT #2 LINEAR ACCELERATOR  
100 NE Saint Luke's Blvd.  
Lee's Summit, MO 64086


Date 06.27.2025  
Job Number 3-25014  
Drawn By JGM  
Checked By JLV

Revision  
Number Date Description

PROFESSIONAL ENGINEERING CONSULTANTS, P.A.  
622 MASSACHUSETTS ST. SUITE 200, LAWRENCE, KS 66044  
785-842-4364 www.pec1.com  
PEC PROJECT NUMBER: 250290-000  
PEC AUTHORITY NUMBER: EEC 00406F







A4-ELECTRICAL ONE-LINE DIAGRAM  
NO SCALE

## FEEDER SCHEDULE

DESIG.	EQUIPMENT SERVED	CONDUCTORS			GROUND SIZE PER SET	ISOLATED GROUND SIZE	CONDUIT SIZE PER SET	SPARE CONDUIT
		SETS	NO.	SIZE				
[E]	EXIST FEEDER TO REMAIN	--	--	--	--	--	--	--
[0]	REF. CONNECTION SCHEDULE	--	--	--	--	--	--	--
[1]	POWER CONDITIONER	1	4	#1 AWG CU	#1	--	2-1/2"	--
[2]	MAIN DISCONNECT PANEL:MDP	1	4	#1 AWG CU	#1	--	2-1/2"	--
[3]	MODULATOR CABINET	1	4	#1 AWG CU	#1	--	2-1/2"	--
[4]	PANELBOARD:F1-7-LN	1	4	#1 AWG CU	#8	--	2"	--

## ONE-LINE DIAGRAM GENERAL NOTES

1. UNLESS OTHERWISE NOTED, ALL CIRCUIT BREAKERS AND/OR SWITCHES ARE THREE POLE.
2. ALL ELECTRICAL EQUIPMENT AND WIRING SHOWN IN A LIGHT LINE, IS EXISTING TO REMAIN.
3. ALL ELECTRICAL EQUIPMENT AND WIRING SHOWN IN A DARK LINE, IS NEW WORK UNDER THIS CONTRACT.
4. ALL ELECTRICAL EQUIPMENT AND WIRING SHOWN IN A DARK DASHED LINE, IS TO BE REMOVED UNDER THIS CONTRACT. -----

## # SHEET KEYNOTES

ACI  
BOLAND  
ARCHITECTS

ACI/Boland, Inc.  
Kansas City | St. Louis  
1710 Wyandotte  
Kansas City, MO 64108  
T: 816.763.9600  
Licensee's Certificate of Authority Number:  
Missouri: #000958

SAINT LUKE'S EAST LEE'S SUMMIT  
VAULT #2 LINEAR ACCELERATOR  
100 NE Saint Luke's Blvd.  
Lee's Summit, MO 64086

Date 06.27.2025  
Job Number 3-25014  
Drawn By JGM  
Checked By JLV

Revision  
Number Date Description

PROFESSIONAL ENGINEERING CONSULTANTS, P.A.  
623 MASSACHUSETTS ST SUITE 200, LAWRENCE, KS 66044  
785-842-4864 www.pec1.com  
PEC PROJECT NUMBER: 250290-000  
PEC AUTHORITY NUMBER: EGC 004667

PEC

E-601  
© 2025 ACI/BOLAND, Inc.  
ELECTRICAL ONE-LINE DIAGRAM



①

EXIST. PANEL: F1-6-LN

208Y/120 VOLTS, 3 PHASE, 4 WIRE

225 AMP MAIN BKR, SURFACE MTD.

10000 AIC LABELED

WGRO. BUS

CIRC NO.	LOAD V. A.	LOAD TYPE	LOAD DESCRIPTION	P	AMP SIZE	WIRE SIZE	AMP SIZE	LOAD DESCRIPTION		LOAD TYPE	LOAD V. A.	CIRC NO.
1			REC - GENERAL	1	20	A	20	1 REC - 1F109, 1F108, 1F104				2
3			REC - GENERAL	1	20	B	20	1 REC - 1F111, 1F107, 1F148, 1F119				4
5			ICE WATER - 1F100	1	20	C	20	1 REC - 1F112				6
7			REC - 1F128, 1F129	1	20	A	20	1 REC - 1F107				8
9			REC - 1F145	1	20	B	20	1 BANDSAW - 1F107				10
11			MICROWAVE - 1F145	1	20	C	20	1 DRILL PRESS - 1F107				12
13			REC - 1F112	1	20	A	20	1 REC - 1F106				14
15			REC - 1F120	1	20	B	20	1 REC - 1F105				16
17			REC - 1F120	1	20	C	20	1 REC - 1F110				18
19			REC - 1F100	1	20	A	20	1 LRP-F1-1				20
21			COFFEE MAKER - 1F100	1	20	B	20	1 WLC IT APC NETWORK RACK				22
23			REC - 1F105, 1F106	1	20	C	20	1 WLC IT APC PATCH PANEL RACK				24
25			REC - 1F007, 1F019, A115	1	20	A	20	1 WLC IT APC PATCH PANEL RACK				26
27			REC - 1F148	1	20	B	20	1 WLC IT APC PATCH PANEL RACK				28
29			REC - 1F149	1	20	C	20	1 REC - 1F142				30
31			REC - 1F150	1	20	A	20	1 PLUGMOLD - 1F142				32
33			REC - 1F150	1	20	B	20	1 PLUGMOLD - 1F142				34
35			REC - 1F151	1	20	C	20	1 REC - 1F131				36
37			REC - 1F012, 1F014	1	20	A	20	1 REC - 1F131				38
39			PDU - APC #8941	2	30	B	20	1 REC - 1F131				40
41	****	**	*****	-	1	C	20	1 REC - 1F144				42
43			REC - 1F121	1	20	A	20	1 REC - 1F144				44
45			REC - 1F122	1	20	B	20	1 REC - 1F144				46
47			PLUGMOLD - 1F107	1	20	C	20	1 REC - STORAGE				48
49			PLUGMOLD - 1F107	1	20	A	20	1 REC - 1F141				50
51			REC - 1F141A	1	20	B	20	1 COPIER - 1F141A				52
53			REC - 1F137	1	20	C	20	1 REC - 1F116				54
55			MFD - 1F137	1	20	A	20	1 REC - 1F119				56
57			UC LTG - RAD ONCOLOGY	1	20	B	20	1 REC - 1F118, 1F108, 1F140, 1F128				58
59			REC - 1F118	1	20	C	20	1 REC - 1F152				60
61			REC - 1F114	1	20	A	20	1 REC - 1F152				62
63			REC - 1F115	1	20	B	20	1 REC - 1F131				64
65			LTG - LINAC #1	1	20	C	20	1 REC - 1F131				66
67			REC - 1F011	1	20	A	20	1 REC - 1F131				68
69			REC - 1F208	1	20	B	20	1 LTG - LINAC #1				70
71			XVB & UC REF - 1F206	1	20	C	20	1 PLUGMOLD - 1F206				72
73			LTG - 1F200	1	20	A	20	1 PLUGMOLD - 1F206				74
75			LAB - 1F200	1	20	B	20	1 PLUGMOLD - 1F206				76
77			REC - 1F151	1	20	C	20	1 REC - 1F151				78
79			REC - 1F151	1	20	A	20	1 REC - 1F151				80
81			REC - 1F151	1	20	B	20	1 REC - 1F151				82
83	20	MOTR	EF-1	1	20	C	20	1 SPARE				84
85	800	RCPT	REC - 1S153, 1F154, 1S155, 1F128	1	20	A	20	1 FURNITURE - 151				86
87			REC - RAD ONC WAITING	1	20	B	20	1 REC - 151				88
89			REC - CHECK-IN 1F201	1	20	C	20	1 REC - BREAK 1F208				90
91			REC - LINAC #1 CONTROL 1F131A	1	20	A	20	1 REC - LINAC #1 CONTROL 1F131A				92
93			REC - LINAC #1 CONTROL 1F131A	1	20	B	20	1 REC - LINAC #1 CONTROL 1F131A				94
95			REC - LINAC #1 CONTROL 1F131A	1	20	C	20	1 REC - LINAC #1 CONTROL 1F131A				96
97			REC - LINAC #1 CONTROL 1F131A	1	20	A	20	1 REC - LINAC 1F132				98
99			REC - LINAC #1 CONTROL 1F131A	1	20	B	20	1 REC - LINAC 1F132				100
101			REC - TRAY ROOM 1F214 STERILIZER	1	20	C	20	1 REC - LINAC 1F132				102
103			REC - 1F216	1	20	A	20	1 REC - 1F204				104
105			REC - 1F215	1	20	B	20	1 REC - 1F203				106
107			REC - 1F205, 1F207, 1F209	1	20	C	20	1 REC - 1F204				108
109			REC - 1F212	1	20	A	20	1 MICROWAVE - 1F208				110
111			REC - 1F210	1	20	B	20	1 REC - 1F208				112
113			REC - 1F215	1	20	C	20	1 COFFEE 1F208				114
115			REC - 1F213	1	20	A	20	1 REC - 1F217				116
117			REC - 1F007A	1	20	B	20	1 MFD - 1F217				118
119			REC - 1F201, 1F202	1	20	C	20	1 REC - 1F217				120
121			MFD - 1F201	1	20	A	20	1 REC - 1F214				122
123			REC - 1F200	1	20	B	20	1 PLUGMOLD - 1F214				124
125			REC - 1F200	1	20	C	20	1 PLUGMOLD - 1F214				126

②

②

- ① ALL EXISTING CIRCUIT BREAKERS AND LOADS ARE EXISTING TO REMAIN UNLESS NOTED OTHERWISE. UPDATE PANEL DIRECTORY TO REFLECT ALL CHANGES.
- ② CONNECT TO EXISTING SPARE CIRCUIT BREAKER.

EXIST. PANEL: F1-15-LC							208Y/120 VOLTS, 3 PHASE, 4 WIRE 225 AMP MAIN BKR, SURFACE MTD. 10000 AIC LABELED			
W/GRD. BUS										
CIRC NO.	LOAD V. A.	LOAD TYPE	LOAD DESCRIPTION	AMP P	AMP S	AMP SIZE	LOAD DESCRIPTION	LOAD TYPE	LOAD V. A.	CIRC NO.
1			REC - ELEC ROOMS	1	20	A 20	1 CUH - F1001			2
3			UNIT HEATER - FIRST FLOOR	1	20	B 20	1 CUH - F1011			4
5			REC - MOD RM F1127	1	20	C 20	1 REC - F1148, A19			6
7			MFD - F1101	1	20	A 20	1 FRIDGE - F1145			8
9			BLANKET WARMER - F1122	1	20	B 20	1 ICE MAKER - F1145			10
11			REC - F1101	1	20	C 20	1 COMPRESSOR - F1006			12
13			DIVERTER - 1ST FLR XFR UNIT	1	20	A 20	1 REC - IT ROOM F1014			14
15			JC XFMR - F1012	1	20	B 20	1 REC - F1122			16
17			PARKING GATE CONTROL	1	20	C 20	1 NC CABINET - IT ROOM F1014			18
19			UPS - IT ROOM	2	100	A 20	1 REC - F1122			20
21	----	--	-----	---	1	B 20	1 PNEUMATIC TUBE STAT			22
23	351	LIGHT	LTG - LINAC #2	1	20	C 20	1 CRASH CART - F1140, F1146			24
25			REC - F1121	1	20	A 20	1 IMAGING WARNING LIGHTS			26
27	500	POWER	SUB-ASSEMBLY - LINAC #2	1	20	B 20	SPACE			28
29			SPACE			C 20	1 REC - NS F1112			30
31			SPACE			A 20	1 REC - NS F1137			32
33			REC - ABOVE CEILING F1205	1	20	B 20	1 LTG REC - GAS MANIFOLD RM			34
35			EF - GAS MANIFOLD RM	1	20	C 20	1 VAULT ACCESS CONTROL PANEL			36
37			REC - F1211 L6-30	2	30	A 20	1 REC - F1211			38
39	----	--	-----	---	1	B 20	1 REC - F1211			40
41			FRIDGE - F1208	1	20	C 20	1 REC - AF201			42

- ① ALL EXISTING CIRCUIT BREAKERS AND LOADS ARE EXISTING TO REMAIN UNLESS NOTED OTHERWISE. UPDATE PANEL DIRECTORY TO REFLECT ALL CHANGES.
- ② PROVIDE AND INSTALL CIRCUIT BREAKER IN EXISTING SPACE. CIRCUIT BREAKER SHALL MATCH EXISTING CIRCUIT BREAKERS AND SHALL BE RATED FOR THE MAX AIC RATING WITHIN THE EXISTING PANEL. VERIFY ALL REQUIREMENTS IN FIELD.

(1)(2)(3)(4)

(P.E.C.)

LIGHTING FIXTURE SCHEDULE

1. GENERAL CONTRACTOR SHALL PROVIDE FIREPROOFING AROUND RECESSED FIXTURES INSTALLED IN FIRE RATED CEILING PER U.L. REQUIREMENTS. ELECTRICAL CONTRACTOR WILL COORDINATE.

2. MANUFACTURERS LISTED IN THIS SCHEDULE OR APPROVED BY WRITTEN ADDENDUM WILL BE THE ONLY APPROVED MANUFACTURERS TO BID THE LIGHTING FIXTURES FOR THIS PROJECT. CONTRACTORS AND SUPPLIERS USING PRICING FROM MANUFACTURERS NOT LISTED ON SCHEDULE OR BY ADDENDUM DO SO AT THEIR OWN RISK.

3. LIGHT FIXTURE SELECTIONS ARE BASED ON THE MANUFACTURER IN THE LEFT MOST COLUMN AS LISTED IN THE SCHEDULE. FIXTURES APPROVED AS EQUALS IN THIS SCHEDULE OR BY ADDENDUM SHALL BE EQUAL TO THE UNIT SPECIFIED IN THE LEFT MOST COLUMN, I.E: SPRING LOADED LATCHES, POST PAINTED FINISH, PHOTOMETRICS.

4. ALL LIGHT FIXTURES SHALL BE SECURED TO THE CEILING FRAMING SYSTEM BY MECHANICAL MEANS (SUCH AS BOLTS, SCREWS, OR RIVETS) OR BY CLIPS IDENTIFIED FOR USE WITH THE TYPE OF CEILING FRAMING MEMBER AND LIGHT FIXTURE.

5. LIGHT FIXTURES SHALL BE PROVIDED WITH 0-10V DIMMING DRIVERS. DRIVERS SHALL BE CAPABLE OF DIMMING TO A MINIMUM OF 10% TOTAL LIGHT OUTPUT. LED DRIVERS SHALL HAVE A DISCONNECTING MEANS MEETING THE REQUIREMENTS OF NEC SECTION 410.130(G), EXCEPT FOR THOSE INSTALLED IN CORD AND PLUG CONNECTED FIXTURES. WHERE APPLICABLE, WHEN DIMMING SWITCHES ARE NOT PROVIDED AS PART OF THE DESIGN, CONTRACTOR SHALL CAP OFF THE 0-10V DIMMING WIRES FOR FUTURE EXTENSION BY THE OWNER.

6. PROVIDE ARROWS AND FACES AS INDICATED ON THE DRAWINGS.

7. TO COMPLY WITH NEC SECTION 410.130(G), ALL EXISTING OR RELOCATED LIGHT FIXTURES WITHOUT A BALLAST OR DRIVER DISCONNECTING MEANS SHALL HAVE A BALLAST OR DRIVER DISCONNECTING MEANS INSTALLED UNDER ANY OF THE FOLLOWING CONDITIONS:

a. WHEN AN EXISTING BALLAST OR DRIVER IS REPLACED.

b. WHEN AN EXISTING LIGHT FIXTURE IS RELOCATED.

c. WHEN AN EXISTING LIGHT FIXTURE IS RECIRCUITED.

MARK	DESCRIPTION	MANUFACTURER 1 CATALOG NUMBER	LIGHT SOURCE			LENS/LOUVER/FINISH	DIMENSIONS			REF. NOTE	REMARKS
			#	TYPE	WATTS		VOLTS	W	L		
E	EXISTING FIXTURE TO REMAIN		1		0						
ED	EXISTING FIXTURE TO BE REMOVED		1		0						
ER	EXISTING FIXTURE TO BE RELOCATED		1		0						
HD	6" RECESSED DOWNLIGHT W/LENS	WILLIAMS 6DR-TL-L30/835-DIM-UNV-LW-OF-WH-MWT-N-F1	1	LED	27	UNV	SEMI-CLEAR	1.17	1.32	0.63	3000LM; 3500K; 80CRI; PROVIDE W/ REMOTE DRIVER
HDE	6" RECESSED DOWNLIGHT W/LENS W/BATTERY	WILLIAMS 6DR-TL-L30/835-DIM-UNV-LW-OF-WH-MWT-N-F1-EM/10W	1	LED	27	UNV	SEMI-CLEAR	1.17	1.32	0.63	3000LM; 3500K; 80CRI; PROVIDE W/ REMOTE DRIVER; PROVIDE W/ EM BATTERY.
K2	2X4 LAY-IN	WILLIAMS PT-24-L49/835-RA-DIM-UNV	1	LED	37	UNV	ACRYLIC	2.0	4.0	0.33	4900LM; 3500K; 80CRI
KA	2X2 LAY-IN	WILLIAMS PT-22-L43/835-RA-DIM-UNV	1	LED	32	UNV	ACRYLIC	2.0	2.0	0.33	4300LM; 3500K; 80CRI
L5	LUMINOUS SKY CEILING	BY OTHERS	1	LED	0	UNV	ACRYLIC	2.0	2.0	0.33	FURNISHED BY GC AND WIRED BY EC. MAKE ALL CONNECTIONS AS REQUIRED.
U2	2" UNDER CABINET	WILLIAMS 1SF-2-2'-835-DMA-DIM-UNV	1	LED	11	UNV	ACRYLIC	0.38	2.0	0.08	742 LUMENS; 90CRI; 3500K
X3	BEAM-ON LIGHT	LITHONIA LE-P-1-R-SW19	1	LED	5	UNV	CAST ALUMINUM	0.63	1.0	0.13	RED W/OUT BATT., SIGN READS "BEAM ON".
X4	X-RAY ON LIGHT	LITHONIA LE-P-1-R-SW16	1	LED	5	UNV	CAST ALUMINUM	0.63	1.0	0.13	RED W/OUT BATT., SIGN READS "X-RAY IN USE".

1

2

3

EQUIPMENT CONNECTION SCHEDULE

SCHEDULE

MECHANICAL EQUIPMENT CONNECTIONS

UNIT DESIGN	UNIT VOLTAGE	LOAD			PANEL DEVICE				DEVICE AT UNIT				S T S	FEEDER DESCRIPTION OR SEE THE FEEDER SCHEDULE	REMARKS OR SEE THE INDICATED NOTES BELOW		
		H.P.	FLA	KVA	CIRCUIT BREAKER NOMPS	SW. NOMPS	FUSE NOMPS	NEMA START SIZE	NEMA STOP SIZE	SW. NOMPS	FUSE NOMPS	NEMA START SIZE				NEMA STOP SIZE	OTHER
EF	EXHAUST FAN																
		120/1	0.17A	0.2	0.02	F1-6LX83	20		1					FUSTAT	1	2 #12 AWG THWN; #12 AWG GRD; 1/2C.	CONTROL WITH LIGHTS
CHRO	CHILLER																
2		480/3	7.5	28.8	23.94	DPF1-174K3	40		3		60	35	3	NEMA-3R	1	3 #8 AWG THWN; #10 AWG GRD; 3/4C.	

1

2

3

ALL CONNECTIONS AND ELECTRICAL EQUIPMENT LISTED IN SCHEDULE SHALL BE PROVIDED AND INSTALLED BY THE ELECTRICAL CONTRACTOR. FIELD VERIFY CONNECTION REQUIREMENTS AND EQUIPMENT PROVIDED BY OTHERS PRIOR TO ROUGH-IN.

REFER TO MECHANICAL DRAWINGS AND SPECIFICATIONS FOR THE REQUIREMENTS ASSOCIATED WITH WIRING AND CONNECTIONS OF INTERLOCKING, THERMOSTAT LOCATIONS, EXHAUST FAN CONTROL SWITCHES, AND OTHER CONTROLS OF MECHANICAL EQUIPMENT.

SIZE FUSES FOR MOTOR FUSTATS BASED ON 125% OF MANUFACTURER'S NAMEPLATE FULL LOAD AMPERAGE UNLESS OTHERWISE NOTED ON THE DRAWINGS.

PANELBOARD: F1-7-LN

208Y/120 VOLTS, 3 PHASE, 4 WIRE  
100 AMP MLO, SURFACE MTD.  
10000 AIC LABELED

WGRD. BUS

CIRC. NO.	LOAD V. A.	LOAD TYPE	LOAD DESCRIPTION	AMP P.	WGRD. SIZE	AMP SIZE P.	LOAD DESCRIPTION	LOAD TYPE	LOAD V. A.	CIRC. NO.		
1	800	RCPT	REC - CONTROL #2 1F129 COUNTER	1	20	A	20	1	LINAC #2 AIMING LASERS/CAMERAS	POWER	1400	2
3	1200	RCPT	REC - CONTROL #2 1F129 NORTH	1	B	B	20	1	LINAC #2 VISION MONITOR	POWER	500	4
5	1200	RCPT	REC - CONTROL #2 1F129 SOUTH	1	C	C	20	1	LINAC #2 CAMERAS	POWER	800	6
7	500	POWER	STREAMING - CONTROL #2 1F129	1	C	A	20	1	REC - LINAC #2 COUNTER	RCPT	1000	8
9	500	POWER	LINAC #2 DOOR RELAY	1	B	B	20	1	LINAC #2 USB HUB	POWER	200	10
11	500	POWER	LINAC #2 DOOR CONTROLLER	1	C	C	20	1	LINAC #2 IN-ROOM MONITOR	POWER	500	12
13	120	POWER	BOTTLE FILLER - CORR 02-1F-128	1	C	A	20	1	SPARE			
15			SPARE	1	B	B	20	1	SPARE			14
17			SPARE	1	C	C	20	1	SPARE			16
19			SPARE	1	A	B	20	1	SPARE			18
21			SPACE			B			SPARE			20
23			SPACE			C			SPACE			22
25			SPACE			A			SPACE			24
27			SPACE			B			SPACE			26
29			SPACE			C			SPACE			28

- ① GFCI BREAKER SHALL PROVIDE GROUND FAULT PERSONEL PROTECTION PER NEC.

PANELBOARD: F1-7-1LN											
	CONNECTED KVA:				DEMAND		CONT. FACT	SIZING AMPS:			
	PH-A	PH-B	PH-C	TOTAL	FACTOR	KVA		TOTAL	PH-A	PH-B	PH-C
Receptacle	1.8	1.2	1.2	4.2	1	4.2	1	11.7	15.0	10.0	10.0
Power	2.0	1.2	1.8	5.0	1	5.0	1	13.9	16.8	10.0	15.0
Spare					0.2	1.8	1	5.1	5.1	5.1	5.1
TOTAL KVA:	3.8	2.4	3.0	9.2		11.1		TOTAL AMPS:	PH-A	PH-B	PH-C
TOTAL AMPS:	31.8	20.0	25.0	25.6				30.7	37.0	25.1	30.1