


1. REVIEW AND COORDINATE WITH ALL DETAIL PAGES REFERENCED ON THIS PLAN, NOTIFY ARCHITECT AND OWNER OF DISCREPANCIES
2. **RELATED DRAWING SHEETS:** REFER TO THE FOLLOWING:
 - AL-101: FOR BUILDING LOCATION ON SITE
 - AL-601: FOR INFORMATION RELATING TO SIGNAGE
 - A-101: PRIMARY FLOOR PLAN FOR CONSTRUCTION LAYOUT
 - A-121: ROOF PLAN/ROOF TOP EQUIPMENT
 - A-601: DOOR & WINDOW SCHEDULES AND NOTES
 - S-101: FOOTINGS AND FOUNDATIONS
 - S-102: ROOF TRUSSES
3. **WORKING POINT:** THE WORKING POINT (*WP*) INDICATED ON THE DRAWINGS IS REF. TO THE FACE OF SHEATHING ON THE EXTERIOR WALL AND IS A COMMON POINT OF REFERENCE WHERE EVER USED IN THESE DRAWINGS
4. ALL VENT PENETRATIONS ON BACK OF BACKSIDE OF ROOF.



 	
Casey's	
CASEY'S CONSTRUCTION DIVISION One Convenience Blvd., P.O. Box 3001, Ankeny, Ia. 50021 515-965-6100	
PROJECT: 2025 "U4" STYLE STORE V.01 FLAT ROOF	POLISHED: 06/10/25 REVISIONS ON:
ORDERING INFORMATION: EXTERIOR ELEVATIONS	
PROTOTYPE AND VERSION: 2025 - U4 - V.01 DRAWN BY: Arlon Golofrit III CHECKED BY: 	
A-201	


General Notes

- 1. REVIEW AND COORDINATE WITH ALL DETAIL PAGES REFERENCED ON THIS PLAN, NOTIFY ARCHITECT AND OWNER OF DISCREPANCIES
- 2. **RELATED DRAWING SHEETS:** REFER TO THE FOLLOWING:
AL-101: FOR BUILDING LOCATION ON SITE
AL-601: FOR INFORMATION RELATING TO SIGNAGE
A-101: PRIMARY FLOOR PLAN FOR CONSTRUCTION LAYOUT
A-121: ROOF PLAN/ROOF TOP EQUIPMENT
A-601: DOOR & WINDOW SCHEDULES AND NOTES
S-101: FOOTINGS AND FOUNDATIONS
S-102: ROOF TRUSSES
- 3. **WORKING POINT:** THE WORKING POINT (*WP*) INDICATED ON THE DRAWINGS IS RELATIVE TO THE FACE OF SHEATHING ON THE EXTERIOR WALL AND IS A COMMON POINT OF REFERENCE WHERE EVER USED IN THESE DRAWINGS
- 4. ALL VENT PENETRATIONS ON BACK OF BACKSIDE OF ROOF.



2 Exterior Elevation - Right Side of Building
1/4"=1'-0"

3 Ladder Bracket
1/2"=1'-0"



1 Exterior Elevation - Back of Building
1/4"=1'-0"

Screening


			
CASEY'S CONSTRUCTION DIVISION			
One Convenience Blvd., P.O. Box 3001, Ankeny, Ia. 50021 515-965-6100			
PROJECT:	PUBLISHED: 06/10/25	DRAWING INFORMATION:	
2025 "U4" STYLE STORE V.01 FLAT ROOF	REVISED ON:	EXTERIOR ELEVATIONS	
PROTOTYPE AND VERSION:		A-202	
2025 - U4 - V.01			
DRAWN BY:			
Arlon Goforth III	CHECKED BY:		

****VERIFY ALL SIGNAGE WITH SIGN PERMITS****


Canopy										
Sign #	Sign	Type	Location	Illumination	Dimensions			Height	Area Ft²	Quantity
					Bottom	Top	Width			
5	House Logo	Surface	Canopy Side	Internal	17' 3-1/2"	21' 3-1/2"	5' 8-7/8"	4' 0"	17.49	2
5	House Logo	Surface	Canopy Front	Internal	17' 3-1/2"	21' 3-1/2"	5' 8-7/8"	4' 0"	17.49	1
4	Snap Frame	Advertising	Canopy Column	N/A	3' 0"	7' 0-1/2"	2' 4"	3' 8"	8.56	8
Total									120.95	

General Notes


- RELATED SHEETS:** FOR ADDITIONAL INFORMATION NOT DIRECTLY REFERENCED, SEE THE FOLLOWING SHEETS:
G-001 FOR GENERAL PROJECT NOTES
AL-101 FOR GENERAL SITE PLAN
Sign Packet FOR SIGNAGE SCHEDULE AND NOTES
QF-Series FOR DESIGN AND DETAILS RELATED TO FUELING FACILITY
- GASOLINE ISLAND CANOPY:** REVIEW SHOP DRAWINGS PROVIDED BY CANOPY SUPPLIER AND ADVISE CASEY'S CONSTRUCTION MANAGER OF ANY DISCREPANCIES
- EMERGENCY GAS SHUT OFFS:** REFER TO SHEETS A-201, AQ-101 & E-101 FOR EMERGENCY SHUT OFF LOCATIONS.




4 Pump Island Canopy - (Street Side)
1/8" = 1'-0"




3 Pump Island Canopy - Right Side Elevation
1/8" = 1'-0"



2 Pump Island Canopy - (Store Side)
1/8" = 1'-0"



1 Pump Island Canopy - Left Side Elevation
1/8" = 1'-0"



5 Canopy Layout Plan
Not To Scale

Keyed Canopy Layout Plan Notes

- 1 FUEL ISLANDS
- 2 FUEL DISPENSERS: SUPPLIED BY OWNER
- 3 CANOPY COLUMN: SUPPLIED BY CANOPY MFG.
- 4 EDGE OF CANOPY: ABOVE
- 5 STEEL GUARD PIPE: SET INTO CONC SLAB AS INDICATED IN DETAIL ELEVATIONS (2 PER ISLAND)
- 6 INTERNAL DOWNSPOUTS: ROUTE THROUGH COLUMNS AND UNDERGROUND TO STORM SEWER OR DETENTION IF APPLICABLE
- 7 TRASH CAN AND WASH BUCKETS
- 8 PUMP LABELS: MOUNTED ON CANOPY COLUMNS

5 DISPENSERS - IN-A-ROW - H.I.I.

CASEY'S CONSTRUCTION DIVISION One Convenience Blvd., Ankeny, IA. 50021 515-965-6100	
PROJECT: 2025 Standard Site Details	DATE: 04/03/25 REVISIONS: CONSTRUCTION DIVISION DRAWN BY: B. RAHN
DRAWING INFORMATION: GASOLINE ISLAND CANOPY ELEVATIONS AL-201	


General Notes

1. RELATED SHEETS: FOR ADDITIONAL INFORMATION NOT DIRECTLY REFERENCED, SEE THE FOLLOWING SHEETS:


G-001 FOR GENERAL PROJECT NOTES
AL101 FOR GENERAL SITE PLAN

Construction Notes


- 1) ALL DOMES ON FENCE POSTS ARE TO BE FASTENED SO THAT THEY CAN NOT BE REMOVED.
- 2) VERIFY SCREENING WITH LOCAL AUTHORITY.
- 3) CONTRACTOR TO PRIME ALL 6" BOLLARDS PRIOR TO FINISHED PAINT COAT.
- 4) DUMPSTER ENCLOSURE WALLS WILL BE 4" BLOCK PURCHASED BY CONTRACTOR




6 Gate Open Holder
No Scale




7 Bollard Detail
No Scale




5 Dumpster Enclosure - Elevation
1/4" = 1'-0"




4 Dumpster Enclosure - Elevation
1/4" = 1'-0"




3 Dumpster Enclosure - Elevation
1/4" = 1'-0"




2 Dumpster Enclosure - Elevation
1/4" = 1'-0"



8 Spread Footing Detail
No Scale




9 Adjustable Dumpster Wall Cap
No Scale



1 Dumpster Plan
1/4" = 1'-0"

Brick Enclosure w/ Metal Gates

CASEY'S CONSTRUCTION DIVISION One Convenience Blvd., Ankeny, IA. 50021 515-965-6100	
PROJECT: 2025 Standard Site Details	DATE: 04/03/25 REVISIONS: CONSTRUCTION DIVISION DRAWN BY: B. RAHN
DRAWING INFORMATION: DUMPSTER ENCLOSURE	
AL-401	



1 Floor Plan
1/4"=1'-0"

General Notes

- REVIEW AND COORDINATE WITH ALL DETAIL PAGES REFERENCED ON THIS PLAN, NOTIFY ARCHITECT AND OWNER OF DISCREPANCIES
- RELATED DRAWING SHEETS:** REFER TO THE FOLLOWING:
A-100: WALL BLOCKING PLAN AND NOTES
A-601: DOOR, WINDOW & FINISH SCHEDULES AND NOTES
A-701: FLOOR FINISH PLAN
AQ-101: EQUIPMENT AND FIXTURE INSTALLATION PLAN AND SCHEDULE
S-101: FOOTINGS AND FOUNDATIONS PLAN
S-102: FIRST FLOOR BEARING WALL AND SHEAR WALL FRAMING
P-101: COORDINATE WITH UNDER SLAB SANITARY WORK
P-102: COORDINATE WITH UNDER SLAB PLUMBING WORK
- WORKING POINT:** THE WORKING POINT (WP) INDICATED ON THE DRAWINGS IS RELATIVE TO THE FACE OF SHEATHING ON THE EXTERIOR WALL AND IS A COMMON POINT OF REFERENCE WHERE EVER USED IN THESE DRAWINGS

4. INDICATES WALL AND HEADER HEIGHTS

5. KNEE WALL FRAMING ABOVE COOLER / FREEZER TO BE INSTALLED FLUSH WITH FRONT FACE OF COOLER / FREEZER.

6. WINDOW FRAME ELEVATIONS - REFER TO PLAN SHEET A-601, DETAIL 1

7. DOOR TYPES - REFER TO PLAN SHEET A-601, DETAIL 2

Framing Notes

- FRAMING INSTRUCTIONS:**
1.1 ALL PERIMETER FRAMED WALLS, 2x6 WD STUDS @ 16" OC. VERIFY HEIGHTS; INSULATED WITH 6"x16" WIDE FRICTION FIT INSULATION, EXCEPT AS DIRECTED BY KEYED NOTES.
1.2 FRONT WALL SAME AS ABOVE, EXCEPT 2x6 WD STUDS, SEE STRUCTURAL DRAWINGS FOR FRAMING ELEVATION AND DETAILS.
1.3 ALL INTERIOR FRAMED PARTITION WALLS, 2x4 WD STUDS @ 16" OC. VERIFY HEIGHTS; EXCEPT AS DIRECTED BY KEYED NOTES.
1.4 ALL FRAMING MATERIAL: CONSTRUCTION GRADE OR BETTER.
1.5 USE TREATED (WOLMANIZED) BOTTOM PLATE, WHEREVER MEETS CONCRETE, SEAL TO CONC FLOOR WITH CONSTRUCTION ADHESIVE.
1.6 ALL BACKING/BLOCKING 2x6, FLUSH W/ ROUGH FRAMING; HEIGHTS INDICATED ON PLANS (BK @ xx") ARE FROM FLOOR (AFF) CENTER OF BLOCKING.
1.7 EXTERIOR NON-COMBUSTIBLE WALL, 2x6, 18 GAGE STEEL STUDS, ENTIRE END WALL, USING STEEL TOP AND BOTTOM PLATES.
- SEAL ALL CABINETS AND SALES COUNTER TO FLOOR.
- ALL EXTERIOR WALLS ARE SUPPLIED BY OWNER
- ALL INTERIOR WALL MATERIALS SUPPLIED WITH BUILDING PACKAGE TO BE BUILT BY CONTRACTOR ON-SITE.

Key - Wall Type

- G 3 1/2" WOOD STUD (TYPICAL UNLESS NOTED OTHERWISE). RE: A-601, FINISH SCHEDULE FOR WALL FINISH MATERIAL.
- G1 5 1/2" WOOD STUD. RE: A-601, FINISH SCHEDULE FOR WALL FINISH MATERIAL.
- G2 3 1/2" WOOD STUD FUR OUT OF EXTERIOR WALL FOR PLUMBING.
- G3 5 1/2" METAL STUD. RE: A-601, FINISH SCHEDULE FOR WALL FINISH MATERIAL.
- G4 7 1/2" WOOD STUD. RE: A-601, FINISH SCHEDULE FOR WALL FINISH MATERIAL.
- G5 3 1/2" METAL STUD HOOD WALL FRAMED TO BOTTOM OF TRUSS. RE: A-601, FINISH SCHEDULE FOR WALL FINISH MATERIALS.
- G6 5-1/2" NON-COMBUSTIBLE METAL STUD WALL FRAMED TO BOTTOM OF TRUSS. RE: A-601, FINISH SCHEDULE FOR WALL FINISH MATERIAL.
- G7 5 1/2" WOOD STUD. FUR OUT OF EXTERIOR WALL FOR PLUMBING.
- Gh1 5 1/2" WOOD STUD. FINISH HEIGHT = 5'-2" A.F.F. CORNER BEAD ALL OUTSIDE CORNERS. WOOD CAP AND COVE ON TOP OF WALL.
- Gh2 3 1/2" WOOD STUD SHEAR WALL. SHEET BOTH SIDES WITH 1/2" OSB.
- Gh3 2"x4" WOOD FLOOR TYPE TRUSS BEAM SUPPLIED BY STRUCTURAL COMPONENT SYSTEMS. CONTRACTOR TO SHEET SALES AREA SIDE WITH 3/4" PLYWOOD BEFORE FINISHING. RE: A-601, FINISH SCHEDULE FOR WALL FINISH MATERIAL. RE: A-401, DETAIL 4 & 6, INTERIOR ELEVATIONS.
- Gh4 3 1/2" WOOD STUD (FRAMING HEIGHT 7'-5") BULKHEAD BUILT ACROSS OPENINGS FOR GRAPHICS ATTACHMENT. FACE BOTH SIDES, REFER TO FINISH SCHEDULE (A-601) FOR FACE MATERIAL AND FINISH.

CASEY'S CONSTRUCTION DIVISION One Convenience Blvd., P.O. Box 3001, Ankeny, Ia. 50021 515-965-6100			
PROJECT: 2025 "U4" STYLE STORE V.01 FLAT ROOF	DATE: 06/10/25 REVISION: 06/10/25	DRAWING INFORMATION: FLAT ROOF PLAN	
PROTOTYPE AND VERSION: 2025 - U4 - V.01		DRAWN BY: Arion Goforth III	

A-101