







ADDITIONAL EROSION CONTROL MEASURES SHALL BE PROVIDED AT THE DISCRETION OF THE CITY INSPECTOR OR ENGINEER.

THE CONTRACTOR IS RESPONSIBLE

FOR VERIFYING ALL EXISTING UTILITY

LOCATIONS PRIOR TO EXCAVATION.

EROSION CONTROL NOTES:

1. Remove and dispose of sediment deposits when the deposit

2. Replace and reshape as necessary to maintain function

approaches ½ the height of the ditch check.

and integrity of installation.

3. PROJECT PHASING

d. STREET CONSTRUCTION

e. SITE CLEANUP & STABILIZATION

1. THIS PROJECT CONSISTS OF THE CONSTRUCTION OF STREETS AND SEWERS NEEDED FOR A COMMERCIAL SUBDIVISION. 2. TOTAL DISTURBED AREA IS APPROXIMATELY 9.89 ACRES.

a. SANITARY CONSTRUCTION b. STORM SEWER CONSTRUCTION c. MASS GRADING

4. ALL DISTURBED AREAS SHALL BE SEEDED AND MULCHED IMMEDIATELY AFTER CONSTRUCTION IS COMPLETE. 5. ALL SLOPES STEEPER THAN 6:1 SHALL BE IMMEDIATELY SEEDED AND MULCHED WITH EROSION CONTROL BLANKETS

ROCK DITCH CHECKS

Modified from 2015 Overland Park Standard Details for Erosion and Sediment Control.

KANSAS CITY

METRO CHAPTER

TANDARD DRAWING NUMBER ESC-IO
ADOPTED:

10/24/2016

6. STOCKPILES OF TOPSOIL TO BE LOCATED IN AREAS WHERE EROSION WILL NOT LEAVE SITE OR ENTER STORM SEWER.

PREPARED BY: MARK ALLEN BREUER NUMBER PE-2009007268

Mark Allen Breuer, P.E.

MO# PE-2009007268

QUIPMENT MENT MIS OLEMAN L DEVELC ОШ – Ш

EROSION CONTROL

DETAILS

SHEET

PERMIT SET