



Notes

1. Contractor is responsible for verifying all existing utility locations prior to excavation
2. There are no known natural or artificial water storage detention areas, or wetlands in the area designated for construction
3. No part of the project lies within the 100 year flood plain
4. All erosion and sediment control measures need to be implemented prior to construction
5. Additional erosion control may be required by the City Engineer, Design Engineer or Owner at any time problematic areas are noted in the field or existing measures are found to be ineffective
6. Soil Stabilization of disturbed areas shall be completed within 14 days of construction inactivity
7. Contractor responsible for all density testing of roadway subgrade and granular base.

Master Drainage Plan 1 of 3:  
Grading Plan  
Construction Plans for:  
Park Ridge - 6th Plat  
Lee's Summit, Jackson County, Missouri

Project: PARK RIDGE  
Sheet: 6TH  
Issue Date:  
November 17, 2017

Park Ridge - 6th Plat  
Lee's Summit, Jackson County, Missouri

Professional Registration  
Missouri  
Engineering 2005002188-D  
Surveying 200500319-D  
Kansas  
Engineering E-1895  
Surveying LS-219  
Oklahoma  
Engineering 6254  
Nebraska  
Engineering CA2821



Matthew J. Schlicht  
MO PE 2006019708  
KS PE 19071  
OK PE 25526  
REVISIONS