

**LEGEND**

- CONSTRUCTION ENTRANCE
- USE 3"-6" ROCK
- SILT FENCE
- INLET PROTECTION

UPON COMPLETION CONTRACTOR SHALL SEED AND MULCH DISTURBED AREAS AND REMOVE ALL TRASH AND DEBRIS.



**PHOENIX ENGINEERING & SURVEYING, LLC**  
 3634 S. NORTHERN BLVD.  
 INDEPENDENCE, MO 64062  
 (816) 743-9000 FAX: (816) 743-9700  
 ENGINEERING CERTIFICATE NO.: MO E-2000151302-D KS: E-853  
 SURVEYING CERTIFICATE NO.: MO LS-2000151303-D KS: LS-138

**WHISPERING WOODS**  
 LEE'S SUMMIT, JACKSON COUNTY, MO  
**STREET & STORM SEWER PLANS**  
 ESC - PLAN



DESIGNED	BLG
DRAWN	JRT
SCALE	NOTED
DATE	09-01-2018
JOB NO.	04078
SHEET	29

**NOTE**  
 EROSION CONTROL FEATURES NED TO BE INSTALLED PRIOR TO LAND DISTURBANCE AND MAINTAINED THROUGHOUT THE DURATION OF OPERATIONS. WE NEED TO CONTAIN THE SILT TO THIS SITE AND KEEP THE ADJACENT STREETS FREE OF MUD AND DEBRIS AT ALL TIMES (WHICH MAY INCLUDE ADDITIONAL EROSION CONTROL FEATURES NOT INCLUDED IN THIS PLAN IF IT IS DETERMINED THAT THE CURRENT PLAN IS INADEQUATE.

EROSION & SEDIMENT CONTROL MEASURES IN PLACE SHALL BE CHECKED & MAINTAINED WEEKLY OR WITHIN 24 HOURS FOLLOWING A RAIN MEASURING GREATER THAN 0.5 INCHES IN 24 HOURS AS RECORDED AT KCI AIRPORT.

**NOTE**  
 SEDIMENT TRAPS TO BE REMOVED AFTER THE SITE IS ESTABLISHED WITH VEGETATION. FINISH ELEVATIONS WILL BE IN ACCORDANCE WITH GRADING PLAN AND DETENTION DETAILS.

**NOTE**  
 ALL SLOPES GREATER THAN 4:1 WILL BE EVALUATED FOR USE OF MATS/BLANKETS



REVISION

THE SEAL(S) AND SIGNATURE(S) APPLY ONLY TO THE DOCUMENT TO WHICH THEY ARE AFFIXED. AND EXPRESSLY DISCLAIM ANY RESPONSIBILITY FOR ALL OTHER PLANS, SPECIFICATIONS, ESTIMATES, REPORTS, OR OTHER DOCUMENTS OR INSTRUMENTS RELATING TO OR INTENDED TO BE USED FOR ANY PART OR PARTS OF THE ENGINEERING OR SURVEYING PROJECT.