PA Sectio

SUMMARY OF QUANTITIES

No.	DESCRIPTION	UNIT	QUANTITY
1	Fill (15% shrinkage)	С.Ү.	400,008*
2	Cut (Unadjusted)	<i>C.Y.</i>	70,094
3	Sediment Fence	<i>L.F.</i>	5,044
4	Rock Check Dam	EA.	8
5	Straw Wattle	<i>L.F.</i>	1,613
6	Turf Reinforcement Mat (TRM)	<i>S.Y.</i>	16,150
7	Temporary Construction Entrance	EA.	4
8	5'x4' Curb Inlet	EA.	2
9	7'x4' Curb Inlet	EA.	1
10	8'x4' Curb Inlet	EA.	1
11	9'x4' Curb Inlet	EA.	1
12	7'x4' Junction Box	EA.	1
13	8'x4' Junction Box	EA.	1
14	18" HDPE	<i>L.F.</i>	75
15	30" RCP	<i>L.F.</i>	116.55
16	42" RCP	<i>L.F.</i>	128.77
17	48" RCP	<i>L.F.</i>	117.11
18	60" RCP	<i>L.F.</i>	215.58
19	72" RCP	<i>L.F.</i>	204.00
20	8'x8'x166' RCB	Ea.	1
21	30" RCP End Section w/ Conc. Toewall	Ea.	1
22	30" RCP Headwall w/ Conc. Toewall and Flapgate	Ea.	1
23	42" RCP End Section w/ Conc. Toewall	Ea.	1
24	48" RCP End Section w/ Conc. Toewall	Ea.	1
25	60" RCP End Section w/ Conc. Toewall	Ea.	1
26	60" RCP Headwall w/ Conc. Toewall and Flapgate	Ea.	1
27	72" RCP End Section w/ Conc. Toewall	Ea.	2
28	Caged Reinforced Concrete Encasement	<i>L.F.</i>	110
29	Adjust Existing Sanitary Sewer Manhole	Ea.	6
30	Riprap	<i>S.Y.</i>	450
31	Seeding (Temporary)	LS	1
32	Seeding (Permanent)	Ac.	3.2

* Base Earthwork: 400,008 CY Fill, 70,094 CY Cut

Floodway: 57,100 CY Fill

Topsoil Removed by Clearing Plan: 46,500 CY Fill

Total Fill Required: 433,514 CY

UTILITY CONTACTS

Sanitary Sewers	Mr. Jeff Thorn, PE City of Lee's Summit Water Utilities 220 SE Green Street Lee's Summit, MO 64063 (816) 969–1922 email: jeff.thorn@cityofLS.net	Gas	Mr. Donnie Richards Missouri Gas Energy 7500 E 35th Terrace Kansas City, MO 64129 (816) 472–9464 Fax (816) 472–3488 email: donnie.richards@sug.com
	Mr. Jeff Shook Little Blue Valley Sewer District 21101 East 78 Highway Independence, MO 64057 (816) 285—1522 email: jshook@lbvsd.net	Cable Television	Mr. Greg Thomas Time Warner Cable 8221 W. 119th Street Overland Park, KS 66213 (913) 643–1950 email: greg.thomas@twcable.cor
Water	Mr. Jeff Thorn, PE City of Lee's Summit Water Utilities 220 SE Green Street Lee's Summit, MO 64063 (816) 969–1922 email: jeff.thorn@cityofLS.net	Telephone	Ms. Glenda Charles AT&T 1425 Oak Street Kansas City, MO 64106 (816) 365–1669
Electric Service	Mr. Nathan Michael Kansas City Power & Light P.O. Box 418679 Kansas City, MO 64141 (816) 220–5210 Fax (816) 245–3623 email: Nathan.Michael@kcpl.com		Fax (816) 275–1109 email: gc6954@att.com


٧V

Scale: 1"=1000'

MASS GRADING PLANS FOR PARAGON STAR DEVELOPMENT

Sections 33 & 34-Township 48-Range 32 City of Lee's Summit

Jackson County, Missouri



VICINITY MAP Section 33 & 34-T48N-R32W

> DEVELOPED AND OWNED BY: PARAGON STAR LLC 801 NORTHWEST COMMERCE CENTER LEE'S SUMMIT, MISSOURI 64086 PHONE: (816) 802-6801 CONTACT: Mr. Flip Short EMAIL: fshort@legacytouch.com

PREPARED & SUBMITTED BY: GEORGE BUTLER ASSOCIATES, INC. 9801 RENNER BOULEVARD LENEXA, KANSAS 66219 PHONE: 913-492-0400 FAX: 913-577-8312 CONTACT: BRAD BURTON P.E. EMAIL: BBURTON@GBATEAM.COM

PROJECT BENCHMARK:

BM #11 – Chiseled "L" on top Northeast corner of concrete guardrail at the Northeast corner of 1470 bridge spanning View High Drive. EL=833.80

INDEX OF SHEETS

Sht. No.	Description
1	Title Sheet
2	General Notes
3	General Layout
4-6	Grading Plan
7	Floodway Grading Plan
9	Utility Plan
10-12	Storm Sewer Enlargements
13	Storm Sewer Profiles
14	Drainage Map
15	Drainage Calculations
16-17	Construction Details
18	Headwall Details
19	Structural General Notes
20-22	RCB Details
23	Special Curb Inlet Details
24-25	Pre-Construction Erosion Control-Phase 1
26-27	Erosion Control-Phase 2
28-29	Erosion Control-Phase 3
30-31	Erosion Control Details
32	Seeding Plan
33	Typical Sections (for reference only)



PROJECT ENGINEER:

DATE:

DATE:

APPROVED:

CITY ENGINEER:



9801 Renner Boulevard Lenexa, Kansas 66219 9 1 3 . 4 9 2 . 0 4 0 0 www.gbateam.com

Revised Field Elevations 5/15/18 1/10/17

EROSION AND SEDIMENT CONTROL NOTES

The layout of erosion control best management practices (BMPs) shown on the engineering plans is intended to control erosion and minimize, if not eliminate, the transport of sediment from the disturbed areas. The Contractor shall be responsible for the evaluation of existing surface drainage patterns and for making adjustments to the BMP locations to best control erosion and minimize, if not eliminate, the transport of sediment from the disturbed areas. The following are measures to achieve the control of erosion and sediment.

- 1. Stabilization Practices Stabilization practices are very effective at preventing erosion by shielding the soil surface from the impact of rain, slowing the velocity of runoff, holding soils in place, and increasing infiltration of runoff and allowing the soil to absorb more rainfall.
 - a. Temporary Seeding Stabilization During acceptable growing periods (see Table 1 below); temporary seeding of annual vegetation with a straw mulch cover shall be used as a temporary cover until permanent vegetation is established. If there is a possibility that a vegetative cover will be required to control erosion for more than 1 year, then consider the addition of a perennial/permanent grass species as part of a seeding mixture.

Table 1. Temporary Seeding Dates and Minimum Application Rates

Seeding Dates	Temporary Seed Species	Minimum Application Rates (pure live seed Ibs. per acre)	Straw Mulch (tons per acre)
Jan. 1 – Jan. 31	None	Not Applicable	2.5
Feb. 1 – May 31	Annual Ryegrass	120	1.5
June 1 – Aug.4	None	Not Applicable	2.5
Aug. 15 – Nov. 15	Cereal/Winter Rye	120	1.5
Nov. 16 – Dec. 31	None	Not Applicable	2.5

Seedbed Preparation – For broadcast seeding or drilling, loosen soil to depth of 3 inches. For no till drilling, loosen soil if it is compacted. Loosen compacted, hard or crusted soil surfaces with a disk, ripper, chisel, harrow or other tillage equipment. Avoid preparing the seedbed under excessively wet conditions. For establishment and long-term growth, apply a complete fertilizer at rates recommended by soil tests or as specified in plans and specifications. If soil pH is less than 6.0, apply lime according to soil tests. Incorporate necessary lime and fertilizer to a depth of 3 to 6 inches of soil.

Installation – For the best results use certified seed. Apply seed uniformly using a cyclone seeder, drop-type spreader, drill, cultipacker seeder or hydroseeder. When using a drill seeder, plant rye or other grains about 1 inch deep and plant grasses no more than $\frac{1}{2}$ inch. A vegetative straw mulch cover shall be applied over the seed mixture to help germinate and establish plant cover, control weeds, and protect seed mixture against temperature extremes. Follow straw mulch preparation and application procedures described herein.

b. Temporary Mulch Stabilization – During non-growing periods, a straw mulch cover shall be applied in unseeded areas to protect against erosion until temporary or permanent vegetation is established.

Site Preparation – Divert runoff water from areas above the site that will be mulched. Remove stumps, roots and other debris from the construction area. Grade area as needed to permit the use of equipment for seeding, mulching and maintenance. Shape area so that it is relatively smooth

Application — Spread straw mulch uniformly over the area with a power blower, hydroseeder, or by hand. No more than 25% of the ground surface should be visible after spreading. Apply straw mulch at a rate of 1.5 tons per acre as a seed cover or 2.5 tons per acre as a stand alone cover. The straw should be dry, unchopped, unweathered; free of weed seeds and rot. In areas of steep slopes or high winds, or in critical areas such as swales, mulching may need to be secured to the ground with a binder, netting, or tacking.

c. Permanent Seeding Stabilization – All disturbed areas shall be permanently seeded with a cool season grass mixture as specified in the Standards and Specifications of the City of Lee's Summit, Missouri.

Seedbed Preparation - loosen soil to depth of 3 inches. For no till drilling, loosen soil if it is compacted. Loosen compacted, hard or crusted soil surfaces with a disk, ripper, chisel, harrow or other tillage equipment. Avoid preparing the seedbed under excessively wet conditions. For establishment and long-term growth, apply a complete fertilizer at rates recommended by soil tests or as specified in plans and specifications. If soil pH is less than 6.0, apply lime according to soil tests. Incorporate necessary lime and fertilizer to a depth of 3 to 6 inches of soil.

Installation - For the best results use certified seed. Apply seed uniformly using a hydroseeder. A vegetative straw mulch cover shall be applied over the seed mixture to help germinate and establish plant cover, control weeds, and protect seed mixture against temperature extremes. Follow straw mulch preparation and application procedures described in the Standards and Specifications of the City of Lee's Summit, Missouri.

2. Structural Practices

a. Silt Fence – A temporary sediment barrier consisting of a geotextile fabric shall be installed as shown on the attached engineering plans and details. Silt fencing shall be installed to maintain sediment onsite.

Minimum Requirements:

Location - Fence should be built on a nearly level grade and at least 10 feet from the toe of the slope to provide a broad shallow sediment pool. Install on the contour, where fence can intercept runoff as a sheet flow; not located crossing channels, waterways or other concentrated flow paths; not attached to existing trees.

Spacing of Support Posts – 10 feet maximum for fence supported by wire; 6 feet maximum for high strength fabric without supportive wire backing. Support posts should be driven into the ground a minimum of 10 inches deep.

Trench – Bottom 1 foot of fence must be buried minimum of 4 inches deep.

- b. Inlet Protection When installation of the storm drainage system is complete, gravel curb inlet sediment traps will be placed at the drainage system inlets. Construction shall be in accordance with attached engineering plans and details.
- c. Stockpiles The toe of stockpiles shall be placed a minimum of 10 feet from erosion control measures. If stockpiles are to remain for more than 14 days, they shall be temporarily stabilized with vegetative mulch and temporary seeding.
- 3. Maintenance The contractor shall repair all erosion control measures or re-seed areas that are disturbed or damaged as a result of weather or other situations, within 2 days after the occurrence. This will include all areas bare of vegetation.

EROSION CONTROL GENERAL NOTES

- 1. The Contractor is responsible for erosion control during construction and until the Owner and City accepts the work as complete. The erosion control measures shown on this plan are a typical minimum installation. The Contractor shall be responsible for adjusting or adding to these measures as necessary during the phasing of the construction to assure adequate control.
- 2. Clearing and grubbing within 50' of a defined drainage course should be avoided when possible. Where changes to a defined drainage course occur, work should be delayed until all materials and equipment necessary to protect and complete the drainage change are on site. Changes shall be completed as quickly as possible once the work has been initiated. The area impacted by the construction activities shall be revegetated or protected from erosion as soon as possible, areas within 50' of a defined drainage ways should be recontoured as needed or otherwise protected within five (5) working days after grading has ceased.
- 3. Where soil disturbing activities cease in an area for more than 14 days, the disturbed areas shall be protected from erosion by stabilizing the area with mulch or other similarly effective erosion control measures. If the slope of the area is greater than 3:1 or if the slope is greater than 3% and greater than 150 feet in length, then the disturbed areas shall be protected from erosion by stabilizing the area with mulch or other similarly effective erosion control measures if activities cease for more than seven (7) days.
- 4. Existing vegetation shall be preserved to the extent and where practical. In no case shall disturbed areas remain without vegetative ground cover for a period in excess of 60 days.
- 5. Additional site management practices which shall be adhered to during the construction process shall include:

-Solid and hazardous waste management including providing trash containers and regular site clean up for proper disposal of solid waste such as building and construction material, product/material shipping waste, food containers and cups, and providing containers for the proper disposal of waste paints solvents, and cleaning compounds.

-Provisions of portable toilets for proper disposal of sanitary sewage.

-Storage of construction materials away from drainage courses and low areas.

-Installation of containment berms and use of drip pans at petroleum product and liquid storage tanks and containers.

6. All disturbed areas shall be seeded, fertilized and mulched, or sodded, in accordance with the Standards and Specifications adopted by the City of Lee's Summit. Missouri and acod enaineering

practices. This shall be completed within fourteen (14) days after completing the work, in any area. If this is outside of the seeding period, silt barriers or other similarly effective measures shall be provided until such time that the areas can be seeded.

- 7. All erosion control measures, temporary or permanent, require maintenance to preserve their effectiveness. All erosion control devices shall be inspected immediately after each heavy rainstorm and at least daily during prolonged rainfall. Any required repairs should be made immediately. All costs associated with the repair work including related incidentals will be the contractor's responsibility and shall be included in the Contractor's bid for the proposed work. Only after the project is complete and accepted can the erosion control be removed.
- 8. Seeding shall be done before the proposed seedbed becomes eroded, crusted over, or dried out and shall not be done when the ground is frozen, or covered with snow. The seed shall comply with requirements of the Missouri Seed Law and the Federal Seed Act. Also, it shall contain no seed of any plant on the Federal Noxious Weed List. Other weed seed shall not exceed one percent by weight of mix.
- 9. During the dates Dec. 15 through May 30 ALL lime, fertilizer, seed, and mulch shall be applied to finished slopes of disturbed areas. During the months of June, July, October, and November 1st through December 15th, lime, fertilizer, seed, and mulch shall be applied at the following rates:

Lime – 100% of the specified quantity Fertilizer - 75% of the specified quantity Seed – 50% of the specified quantity Mulch – 100% of the specified quantity

10. Mulch shall be Vegetative type, cereal straw form stalks of oats, rye, or barley, or approved equal. The straw shall be free of prohibited weed seed and relatively free of all other noxious and undesirable seed. Apply straw mulch at a rate of 1.5 tons per acre as a seed cover or 2.5 tons per acre as a stand alone cover. Mulch shall be embedded by a mulch anchoring tool or disk type roller having flat serrated disks spaced not more than 10 inches apart and cleaning scrapers shall be provided.

General Notes:

- satisfaction.
- reaulations.
- 10. All concrete shall be KCMMB 4.000 psi.

Permitting:

Erosion Control:

<u>Earthwork:</u>

- referenced Geotechnical reports.
- the recommendations of the Reports.

- Star Development" for details.
- with the temporary seed mix.

- 29. Final tolerance for graded areas shall be +/- 0.2'.

<u>Utility:</u>

- as required.

Storm Sewer:

- 34. All RCP shall be Class III.
- and approval.

AND HERE AND A		DATE:	1/10/17
SE OF MISS	GBA	DESIGN BY:	CEL
VO		DRAWN BY:	DRV
BRADLEY D.	architects	PROJECT NO.:	12720
BURTON R	engineers	SHEET NO.	TOTAL SHEETS
01 F125882 980 ESSIONAL 5 21 18	9801 Renner Boulevard Lenexa, Kansas 66219 9 1 3 4 9 2 0 4 0 0 w w w .gbateam.com	2	33
Bradley D. Burton Professional Engineer License No. 25862	Mass Grad. Paragon Star Lee's Summ	Ďeveloj	oment
NO. DATE	REVISIONS		BY APPROVED
5/15/18	Revised Field Elevations		

1. All Construction shall conform to the City of Lee's Summit Technical Specifications in effect at the time of the City's approval date shown on the approved plans and incorporated herein by reference. 2. All traffic control shall be the responsibility of the Contractor and shall be in conformance with the Manual of Uniform Traffic Control Devices (MUTCD).

3. Property Corners and/or Section corners disturbed or damaged by construction activities shall be reset by a Registered Land Surveyor licensed in the state of Missouri, at the Contractor's expense. 4. The Contractor shall be responsible for the restoration of the Right-of-Way and for damaged improvements such as curbs, driveways, sidewalks, street light and traffic signal junction boxes, traffic signal equipment, irrigation systems, etc. Damaged improvements shall be repaired in conformance with the latest City standards and to the City's

5. All work shall be confined within easements and/or construction limits as shown on the plans. 6. The Contractor shall, prior to the commencement of work, investigate surface and subsurface conditions to be encountered across the site and notify the Engineer if any discrepancies or changed conditions are noted. 7. All trash and debris identified on site shall be properly handled and disposed of in accordance with state of Missouri

8. All measurements on these plans are horizontal distances, not slope distances. 8. This project will include numerous activities occurring on site including storm sewer, sanitary sewer, grading, erosion control, etc. Contractor shall coordinate his work with other contractors on site. 9. Initial construction staking will be performed by GBA - Refer to Bid Documents.

11. Contractor is responsible for obtaining all required permits, paying all fees, and for otherwise complying with all applicable regulations governing the work. 12. No work shall be completed within the existing floodway until the CLOMR has been issued.

13. No work shall be completed within the delineated wetland or regulatory stream channels until the U.S. Corps of Engineers Section 404 permit is issued. All work shall adhere to the terms and conditions of this permit. 14. All work within KCMO city limits shall adhere to KCMO Site disturbance reauirements.

15. The Contractor is responsible for providing erosion and sediment control BMP's to prevent sediment from reaching paved areas, storm sewer systems, drainage courses, and adjacent properties. In the event the prevention measures are not effective, the contractor shall remove any debris, silt, or mud and restore the Right-Of-Way, or adjacent properties to original or better condition.

16. Contractor shall ensure that all construction shall conform to the requirements of the Stormwater Pollution Prevention Plan (SWPPP) a copy of which shall be maintained and updated on site by the Contractor. 17. The Contractor shall sod all disturbed areas within the Public Street Right-of-Way unless otherwise noted in the plans. 18. No trees shall be damaged or removed without prior authorization from owner unless otherwise shown on this plan

19. Slopes shall be constructed to a maximum slope of 3:1 (Horiz:Vert) unless specifically noted otherwise in the

20. Refer to "Geotechnical Engineering Report – Paragon Star Rogdways and Borrow Site" Dated December 8. 2016 – along with Addendum #1 dated 1/4/17. and "Geotechnical Engineering Report - Soccer Fields" Dated July 27. 2016 prepared by Terracon Consultants, Inc. for grading recommendations and boring logs. All earthwork shall conform to

21. Unless otherwise noted, all spot elevations and contours are shown to "finish" arade surface.

22. All temporary slopes and excavations should conform to Occupational Safety and Health Administration (OSHA) standards for the Construction Industry (29 CFR part 1026, subpart P).

23. Existing contours depicted on plans do not reflect topsoil root zone stripping completed under tree clearing scope. Existing grade will be approximately 4.5" average depth lower than shown. Refer to "Tree Clearing Plans for Paragon

24. Earthwork Quantities shown on plans do not account for stripped topsoil from previously issued Tree Clearing Plans. 25. Earthwork for this phase of development is intended to balance. Contractor to cut only enough fill material from the borrow source at the north end of the project as required to accomplish the fills shown on this plan set. 26. All Permanent seeded shall be dressed with 12" topsoil and permanent seed. All other disturbed areas shall be seeded

27. Shale fill shall be capped with a minimum of 24" of clay material.

28. All Soccer fields shall be provided with a minimum 24" of clay above shale or 3" minus material.

30. The west borrow area at the NW portion of the site is considered the primary borrow area and shall be cut and graded to the contours shown. Cuts shown in this area must be performed to completion before utilizing the eastern borrow area for the balance of fill required on the project.

31. Earthwork quantities shown on the plans assume 15% shrinkage for all fill material. The Contractor shall perform the fill to achieve the grades shown on the drawings. The determination of the actual adjustment of fill required due to shrink/swell of various materials shall be the responsibility of the Contractor.

32. All Manholes, Catch Basins, Utility Valves, Meter Pits, and other utility equipment shall be adjusted or rebuilt to grade 33. Prior to beginning work, the Contractor shall notify all utility companies who have facilities in the vicinity of the project area of the work to be performed.


35. Pipe Lengths are called out from center of structure to center of structure.

36. Drainage across the project site during construction shall be the Contractor's responsibility. Surface drainage shall be controlled to reduce or prevent the flow of surface water onto adjacent grounds. Contractor shall control downstream erosion and silting during construction. Flexibility is given to to the Contractor to make minor grading revisions along roads or between building pads to improve drainage during construction, with prior approval of the engineer. 37. Prior to ordering precast storm sewer structures, Contractor shall provide shop drawings to the Engineer for review









PROJECT BENCHMARK:

BM #11 – Chiseled "L" on top Northeast corner of concrete guardrail at the Northeast corner of I470 bridge spanning View High Drive. EL=833.80

> Total Disturbed Area: 68.69 Ac.




Boundary Description:


All that part of the Northwest Quarter of Section 34, Township 48 North, Range 32 West, of the 5th P.M., and all of GRAHAM COMMERCIAL CENTER, a subdivision in the in the City of Lee's Summit, Jackson County, Missouri, being more particularly described as follows: BEGINNING at the Northwest corner of said Northwest Quarter of Section 34; thence South 86°33'45" East, along the North line of said Northwest Quarter, a distance of 2611.91 feet, to a point on the Westerly Right-of-Way line of Union Pacific Railroad, as now established; thence South 18°46'13" West, departing said North line, along said Westerly Right-of-Way line, a distance of 76.95 feet, to a point of curvature; thence Southwesterly and Southeasterly, continuing along said Westerly Right-of-Way line, along a curve to the left, having a radius of 2508.01 feet, and a central angle of 28°06'45", a distance of 1230.57 feet, to a point of tangency; thence South 09°20'32" East, continuing along said Westerly Right-of-Way line, a distance of 30.31 feet, to a point on the South line of the North half of said Northwest Quarter; thence South 86°26'21" East, continuing along said Westerly Right-of-Way line, and along said South line of the North half of the Northwest Quarter, a distance of 16.41 feet; thence South 09°20'32" East, departing said South line of the North half of the Northwest Quarter, continuing along said Westerly Right—of—Way line, a distance of 354.98 feet, to a point on the East line of said Northwest Quarter; thence South 02°29'17" West, continuing along said Westerly Right-of-Way line, and along said East line of the Northwest Quarter, a distance of 468.48 feet, to a point on the North Right-of-Way line of Interstate 470, as now established; thence North 85°05'37" West, departing said Westerly Right—of—Way line, along said North Right—of—Way line of Interstate 470, a distance of 899.87 feet; thence North 75°10'03" West, continuing along said North Right-of-Way line, a distance of 203.04 feet; thence South 77°15'22" West, continuing along said North Right-of-Way line, a distance of 228.93 feet, to a point on the East line of the Southwest Quarter of said Northwest Quarter, said point also being the Southeast corner of said GRAHAM COMMERCIAL CENTER; thence continuing South 77°15'22" West, continuing along said North Right-of-Way line, and along the South line of said subdivision, a distance of 1.94 feet; thence South 88'33'58" West, continuing along said North Right-of-Way line, and along said South line of said subdivision, a distance of 181.11 feet; thence North 85°01'31" West, continuing along said North Right-of-Way line, and said South line of said subdivision, a distance of 100.18 feet; thence North 60°06'43" West, continuing along said North Right-of-Way line, and said South line of said subdivision, a distance of 165.44 feet; thence North 85°08'16" West, continuing along said North Right-of-Way line, and said South line of said subdivision, a distance of 199.96 feet; thence South 60°28'02" West, continuing along said North Right-of-Way line, and said South line of said subdivision, a distance of 97.23 feet; thence North 69°50'05" West, continuing along said North Right—of—Way line, and said South line of said subdivision, a distance of 342.03 feet, to the Southwest corner of said subdivision; thence North 30°28'52" West, continuing along said North Right-of-Way line, and along the West line of said subdivision, a distance of 87.88 feet; thence North 07°21'08" East, continuing along said North Right-of-Way line and it's transition to the East Right-of-Way line of View High Drive, as now established, and said West line of said subdivision, a distance of 106.53 feet; thence North 20°25'39" East, departing said West line of said subdivision, continuing along said East Right-of-Way line of View High Drive, a distance of 185.39 feet; thence North 45°30'34" West, continuing along said East Right-of-Way line, a distance of 129.40 feet; thence North 12°40'32" West, continuing along said East Right-of-Way line, a distance of 278.96 feet, to a point on said South line of the North half of the Northwest Quarter; thence North 86°26'21" West, continuing along said East Right-of-Way line, and along said South line of the North half of the Northwest Quarter, a distance of 130.00 feet, to the Southwest corner of said North half of the Northwest Quarter; thence North 02°25'47" East, along the West line of said Northwest Quarter, a distance of 1316.45 feet, to the POINT OF BEGINNING, containing 5,217,462.56 square feet or 119.78 acres, more or less.


FLOODPLAIN NOTE:


According to FEMA Flood Insurance Rate Map (FIRM) Community Panel No. 290173 0070 B, revised August 5, 1986, the tract lies partially within an area designated as Zone B and partially within an area designated as Zone AH. Zone B is defined as an area of moderate flood hazard, such as areas protected by levees from 100-year flood, or shallow flooding areas with average depths of less than one foot or drainage areas less than 1 square mile. Zone AH is defined areas with a 1% annual chance of shallow flooding, usually in the form of a pond, with an average depth ranging from 1 to 3 feet. Base flood elevations derived from detailed analyses are shown at selected intervals within Zone AH. On FIRM Community Panel No. 290173 0070 B, Zone AH elevations are shown as 726 FT. The site is protected by the Birmingham District Levee. The proposed elevation of the finished floor is 734 FT, above the 726 FT elevation of FIRM Zone AH.





General Layout












































Legend



Compacted Fill to be placed prior to excavation



Storm Sewer Profiles





Image Image <th< th=""><th>Comments Comments Tie in from Line 200 Connect to Line 100 Tie in from Line 400 35 degree bend South</th></th<>	Comments Comments Tie in from Line 200 Connect to Line 100 Tie in from Line 400 35 degree bend South			
1 1	Connect to Line 100 Tie in from Line 400			
Image Image <th< td=""><td>Connect to Line 100 Tie in from Line 400</td></th<>	Connect to Line 100 Tie in from Line 400			
Image: bit	Connect to Line 100 Tie in from Line 400			
Link link link Link link	Connect to Line 100 Tie in from Line 400			
Image: bit in the line linte line in the line in the line in the line in the li	Connect to Line 100 Tie in from Line 400			
Image: 1 = 1 Image: 1 = 1<	Tie in from Line 400			
Image: bit	Tie in from Line 400			
Image: bit in the state in the sta	Tie in from Line 400			
Line 20 203 0.00 v 0.55 0.00 7.75 0.00 Mannbel v <th< td=""><td>Tie in from Line 400</td></th<>	Tie in from Line 400			
202 1.28 0 0.0 0.24 0.01	Tie in from Line 400			
201 0.68 0.67 1.00 5.00 7.33 3.3 Cub held m<	Tie in from Line 400			
Image: bit in the state of the sta	Tie in from Line 400			
Image: 100 mm m				
100 0 0.0 0.0 0.0 0.0 0.0 0.0 1.25 0.0 10.32 0.0 35 bend 4.0 0.0 0 0.0 0 0.0 0 0.00 0 0.00 0 0.00 0 0.00 0 0.00 0 0.00 0 0.00 0 0.00 0 0.00 0 0.00 0 0.00 0 0.00 0 0.00 0 0.00 0 0.00 0 0.00 0 0.00 0<	35 degree bend South			
Image: bit im				
401 2.66 0.57 1.00 5.00 0.12 7.35 11.1 RCP 78.00 3.00 24 0.013 39.29 3.14 12.51 10.73 0.9 0.65 805.36 806.80 803.52 801.18 606.14 0.00 0.00 0.00 0.00 0.00 0.00 7.35 4.6 Curb Inlet 0.00 2.00 7.35 4.6 Curb Inlet 0.013 39.29 3.14 12.51 11.78 1.2 1.20 799.52 806.14 797.18 797.10 806.14 806.14 811.00 401 0.01 3.36 0.64 1.00 5.12 0.10 7.32 15.7 RCP 69.39 3.00 2.4 0.013 39.29 3.14 12.51 11.78 1.2 1.20 799.52 806.14 797.18 795.10 806.14 804.94 60.30 4106 80.40 0.51 1.25 5.01 7.35 RCP 60.30 7.2 <t< td=""><td></td></t<>				
All 0.70 0 0.90 1.00 5.00 7.35 4.6 Curb Intel 0 0 0 0 0.10 5.00 7.35 4.6 Curb Intel 0 0 0 0 0.10 5.12 0.10 7.32 15.7 RCP 69.39 3.00 24 0.13 39.29 3.14 12.51 11.78 1.20 799.52 806.14 797.18 795.10 60.40 </td <td></td>				
Image: Normal Sector Normal Sector Image: Normal Sector Normal Sector Normal Sector Normal Sector Normal Sector <t< td=""><td>Connect to Line 300</td></t<>	Connect to Line 300			
Line 500 (100 Yr) 500 80.40 0.51 1.25 25.00 0.18 5.71 292.9 RCP 204.00 1.50 72 0.013 520.09 28.27 18.39 18.90 1.4 4.15 806.07 801.87 797.78 794.72 797.72 797.72 797.72 797.72	Connect to Line 300			
100 Yr) 500 80.40 0.51 1.25 25.00 0.18 5.71 292.9 RCP 204.00 1.50 72 0.013 520.09 28.27 18.39 18.40 1.4 4.15 806.07 801.87 797.72 797.72 (100 Yr) 500 50.09 28.27 18.39 1.4 4.15 806.07 801.87 797.72 797.72 797.72				
709 18.09 0.51 1.25 18.92 6.61 76.2 End Section 827.48 828.00				
708 18.09 0.51 1.25 18.92 0.14 6.61 76.2 RCP 114.23 2.00 48 0.013 203.69 12.57 16.21 13.74 1.0 1.40 822.09 827.48 817.94 815.66 826.08 0				
708 1.03 9 0.67 1.25 5.50 10.12 8.7 Curb Inlet 6 6 6 6 6 6 6 6 827.82 6 1 826.08 827.32 707 1 1.912 0.52 1.25 1.906 0.12 6.59 81.7 RCP 78.01 2.00 48 0.013 203.69 1.25 16.21 1.030 1.1 1.34 819.02 826.08 814.66 813.10 824.74 0.017 0.017 0.011 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.012 0.013 <				
707 3.01 7.09 0.51 1.25 6.21 9.84 18.9 Curb Inlet 6 6 6 6 6 6 827.82 1 824.74 827.32 707 706 29.22 0.54 1.25 19.18 0.02 RCP 235.90 1.00 48 0.013 14.40 12.57 11.46 13.74 1.7 6.28 819.05 824.74 812.10 809.74 818.46 1				
706 0.12 0.67 1.25 5.50 10.12 1.00 Cub Inlet - - - - - - - - 820.00 - 0.50 818.46 819.50 705 29.34 0.54 1.25 19.46 0.32 6.52 129.9 RCP 210.34 1.00 54 0.013 19.718 15.90 1.24 1.09 1.3 3.27 814.91 818.46 809.24 807.13 815.19 -				
The form The form <th< td=""><td>Tie in from Line 800</td></th<>	Tie in from Line 800			
7/04 0.68 2.00 0.81 1.25 8.11 9.17 6.3 Curb linet 6.3 Curb linet 6.3 Curb linet 6.3 810.93 814.00 703 45.65 0.57 1.25 20.06 0.12 6.42 210.5 RCP 110.83 0.80 60 0.013 233.57 19.63 11.90 15.71 1.6 3.74 806.24 810.93 798.31 797.42 807.19 0 0 0 0 0 0 0.013 233.57 19.63 11.90 15.71 1.6 3.74 806.24 810.93 798.31 797.42 807.19 0				
703 0.17 0.81 1.25 5.00 10.32 1.8 Curb Inter Curb Inter< Curb Inter< Curb Inter< Curb Inter< Curb Inter< Curb Inter Curb Inter <th< td=""><td></td></th<>				
702 0.17 0.81 1.25 5.00 10.32 1.8 Curb Inlet 69.47 0.60 6.013 23.57 19.63 1.90 1.90 804.54 813.74 0.03 804.54 813.74 701 45.99 0.58 1.25 20.21 0.09 6.40 211.9 RCP 69.47 0.80 60 0.013 233.57 19.63 11.90 12.62 1.6 3.19 804.54 796.55 796.00 795.37 0 795.37 0	Tie in from Line 3500			
701 0.00 1.25 5.00 10.32 0.0 Junction Box r <t< td=""><td></td></t<>				
789.31				
803 2.03 0.61 1.25 5.00 10.32 15.9 Area Inlet - - - - - 810.01 810.01 810.41 810.50 802 2.03 0.61 1.25 5.00 0.83 10.32 15.9 HDPE 355.09 0.80 36 0.01 77.76 7.07 11.00 7.11 0.7 0.54 808.77 810.41 806.55 803.71 809.87				
802 2.03 7.09 0.61 1.25 5.00 10.32 15.9 Area Inlet - - - - - - 801 - 80.3 80.9.87 810.50 100 10000 801 11.14 0.62 1.25 14.58 0.63 7.45 64.0 HDPE 268.59 0.50 42 0.01 92.73 9.62 9.64 7.11 1.2 3.22 807.52 809.87 803.41 802.07 806.65 - -				
100 Yr) 2.49 0.61 1.25 5.00 1.03 1.96 Area Inlet 1.06 4.2 0.61 1.17 0.62 0.61 0.61 0.61 0.60 0.60 0.66 810.50 705 13.63 0.62 1.25 15.21 0.19 7.31 76.7 HDPE 79.72 0.80 42 0.01 117.30 9.62 12.19 7.11 1.4 2.21 806.65 804.90 801.77 801.13 802.69 60.65 804.90 801.77 801.13 802.69 60.65 804.90 801.77 801.13 802.69 60.65 804.90 801.77 801.13 802.69 60.65 804.90 801.77 801.13 802.69 60.65 804.90 801.77 801.13 802.69 60.65 804.90 801.77 801.13 802.69 60.65 804.90 801.77 801.13 802.69 60.65 804.90 801.77 801.13 802.69 60.65 801.81 802.69	Connect to Line 700			
Image: Comparison of the second se				
902 2.17 0.51 1.25 12.13 8.02 11.1 Area Inlet - - - - - - 812.00 - - - 809.71 811.50 1 in a conder 901 2.17 0.51 1.25 12.13 0.89 8.02 11.1 HDPE 268.65 0.50 30 0.01 37.81 4.91 7.70 5.01 0.8 0.53 809.57 809.71 806.35 809.19 -				
Line 900 901 2.92 2.00 0.62 1.25 13.02 1.55 7.80 42.9 HDPE 466.78 0.50 42 0.01 92.73 9.62 9.64 5.01 0.9 2.25 809.19 807.56 806.05 803.71 805.31	Connect to Line 800			
101 1.05 0.02 1.25 1.00 1.00 42.5 1.00 42.5 1.00 42.5 1.00 1.00 42.5 1.00 <th1< td=""><td>Connect to Line 000</td></th1<>	Connect to Line 000			
1203 4.52 0.51 1.00 8.33 6.45 14.9 End Section 809.54 813.50				
1202 4.52 0.51 1.00 8.33 0.03 6.45 14.9 RCP 20.19 3.00 30 0.013 71.24 4.91 14.51 11.45 0.8 0.23 809.54 804.82 807.50 806.89 804.59 804.59 813.51	Tie in from Line 3300			
Line 1202 0.12 2.39 0.67 1.00 6.35 0.67 0.00 6.35 0.66 Curb milet 43.11 1.00 30 0.013 41.13 4.91 8.38 11.62 1.2 1.05 804.23 804.59 0.61 0.6 60.68 0.68 0.64 2.9 RCP 43.11 1.00 30 0.013 41.13 4.91 8.38 11.62 1.2 1.05 804.23 804.59 0.61 0.61 0.61 0.61 0.61 0.61 0.61 0.61	ing in hom Ling 3000			
1201 0.12 0.67 1.00 5.00 7.35 0.66 Curb met 6 <th< td=""><td></td></th<>				
1301 0.08 0.90 1.00 5.00 7.35 0.5 Area later				
Line 1301 0.08 0 0.90 1.00 5.00 0.41 7.35 0.5 Area milet 179.4 2.00 15 0.01 1.91 1.23 9.70 7.29 0.7 0.03 809.11 803.44 808.27 804.68 808.27 804.68 808.41 810.50 100 100 100 100 100 100 100 100 100 1	Connect to Line 3300			
5U3.41				
Jacob 0.09 0.67 1.00 5.00 7.35 0.4 Curb Inlet - - - - - 811.00 - 805.18 810.50 0.09 0.09 0.67 1.00 5.00 0.16 7.35 0.4 RCP 34.00 1.00 15 0.013 6.48 1.23 5.28 3.63 0.7 0.01 805.18 804.34 804.00 804.62 - <td>Connect to Line 3300</td>	Connect to Line 3300			
3200 300 0.00 0.00 0.00 0.00 0.00 0.00 0				
3305 0.00 0.64 1.00 5.50 7.20 0.00 Area Inlet - - - - - - - 812.50 - 810.01 812.00 3304 0.00 0.64 1.00 5.50 0.69 7.20 0.0 HDPE 266.64 0.80 18 0.01 12.25 1.77 6.93 6.44 0.7 0.00 810.01 809.56 809.01 809.56 60.01 10.00 810.01 809.56 809.01 809.56 60.01 10.00 810.01 809.56 809.01 809.56 60.01 10.00 810.01 809.56 809.01 809.56 60.01 10.00 810.01 809.56 809.01 809.56 60.01 10.00 810.01 809.56 10.00 800.56 809.01 809.56 10.00 800.56 10.00 800.56 10.00 800.56 10.00 800.56 10.00 800.56 10.00 800.56 10.00 800.56 <td< td=""><td></td></td<>				
3304 1.59 0.08 0.67 1.00 5.92 7.08 7.5 Area Inlet 7 6.93 6.17 1.2 3.09 809.56 809.56 809.56 809.56 809.56 809.56 811.50 3304 1.59 0.68 1.67 0.68 1.00 5.92 7.08 7.5 Area Inlet 7 7 6.93 6.17 1.2 3.39 809.56 806.57 804.68 806.17 7 6.93 6.17 1.2 3.39 809.56 806.57 804.68 806.17 7 6.93 6.17 1.2 3.39 809.56 806.57 804.68 806.17 7 6.93 6.17 1.2 3.39 809.56 806.57 804.68 806.17 7 6.93 6.17 1.2 3.39 809.56 806.57 804.68 806.17 7 6.93 6.17 1.2 3.39 809.56 806.57 804.68 806.17 7 6.93 6.17 1.2	Tie In from Line 1300			
Line 3303 1.14 0.61 1.00 8.11 6.50 4.5 Manhole 1 6.				
3300 3302 0.09 0.09 0.09 0.09 0.07 1.00 6.66 6.87 0.4 Curb Inlet 6	Tie in from Line 3200			
3301 2.99 0.65 1.00 6.94 0.29 6.80 13.3 HDPE 129.65 0.80 24 0.01 25.38 3.14 8.40 7.40 1.0 1.32 805.55 805.52 803.50 802.46 804.20	0			
1202 2.99 0.65 1.00 7.23 0.17 6.72 13.1 HDPE 74.59 0.80 24 0.01 26.38 3.14 8.40 7.38 1.0 0.88 804.20 803.44 802.16 801.56 802.56 802.56 6.00 802.56 802.56 6.00	Connect to Line 1200			
Line 3401 2.00 0.67 1.25 11.72 8.12 13.6 Area Inlet - - - - - - 812.00 812.00 808.40 811.50 3400 901 2.00 0.67 1.25 11.72 0.61 8.12 13.6 HDPE 266.28 0.50 24 0.01 20.85 3.14 6.64 7.23 1.0 2.48 808.40 806.26 804.92 805.92 - - -	Connect to Line 900			




Note: Shaded storm sewer lines are shown for reference only, they will be part of a future plan set.






Construction Details



Construction Details





DESIGN SPECIFICATIONS:

<u>GENERAL:</u>

1. THE CONTRACTOR SHALL NOTIFY THE ENGINEER OF ANY OBSERVED DISCREPANCIES IN DIMENSIONS, DETAILING, OR OTHER ITEMS AS SHOWN ON THE PLANS OR SPECIFIED PRIOR TO PROCEEDING WITH WORK RELATING TO SAID DISCREPANCIES.

2. THE CONTRACTOR SHALL NOT ALTER OR MODIFY WORK SHOWN ON THE STRUCTURAL DRAWINGS WITHOUT RECEIVING WRITTEN APPROVAL FROM THE ENGINEER.

3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR SUPPLYING SHOP DRAWINGS REINFORCING STEEL, HANDRAILS AND POST-INSTALLED ANCHORS. SHOP DRAWINGS MUST BE REVIEWED FOR CONFORMANCE WITH THE MEANS, METHODS, TECHNIQUES, SEQUENCES, AND OPERATIONS OF CONSTRUCTION, AND SAFETY PRECAUTIONS AND PROGRAMS INCIDENTAL THERETO, ALL OF WHICH ARE THE SOLE RESPONSIBILITY OF THE CONTRACTOR, AND SHALL BE STAMPED "APPROVED" BY THE CONTRACTOR PRIOR TO SUBMITTAL. SHOP DRAWINGS SUBMITTED WITHOUT THE CONTRACTOR'S STAMPED APPROVAL WILL BE RETURNED REJECTED. ALL SHOP DRAWINGS SHALL BE REVIEWED BY THE STRUCTURAL ENGINEER PRIOR TO CONSTRUCTION.

4. THE STRUCTURAL SYSTEMS SHOWN ON THESE DOCUMENTS HAVE BEEN DESIGNED FOR THE FINAL IN PLACE USAGE OF THE STRUCTURE BASED ON THE INTENDED OCCUPANCY AND CODE REQUIREMENTS. WHILE GENERAL CONSTRUCTABILITY HAS BEEN CONSIDERED, THE STRUCTURAL SYSTEMS HAVE NOT BEEN DESIGNED TO ACCOMMODATE SPECIFIC CONSTRUCTION MEANS AND METHODS THAT MIGHT BE UTILIZED BY THE CONTRACTOR.

5. THE CONTRACT STRUCTURAL DRAWINGS AND SPECIFICATIONS REPRESENT THE FINISHED STRUCTURE, AND EXCEPT WHERE SPECIFICALLY SHOWN, DO NOT INDICATE THE METHOD OR MEANS OF CONSTRUCTION. THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, PROCEDURES, TECHNIQUES, SEQUENCE, AND SAFETY PRECAUTIONS AND PROGRAMS. THE ENGINEER WILL NOT BE RESPONSIBLE FOR THE ACTS OR OMISSION OF THE CONTRACTOR, SUBCONTRACTOR, OR ANY OTHER PERSONS PERFORMING ANY OF THE WORK, OR FOR THE FAILURE OF ANY OF THEM TO CARRY OUT THE WORK IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.

6. PERIODIC SITE OBSERVATION BY FIELD REPRESENTATIVES OF GBA, IF PROVIDED, IS SOLELY FOR THE PURPOSE OF DETERMINING IF THE WORK OF THE CONTRACTOR IS PROCEEDING IN GENERAL ACCORDANCE WITH THE STRUCTURAL CONTRACT DOCUMENTS. THIS LIMITED SITE OBSERVATION SHOULD NOT BE CONSTRUED AS EXHAUSTIVE OR CONTINUOUS TO CHECK THE QUALITY OR QUANTITY OF THE WORK, BUT RATHER PERIODIC IN AN EFFORT TO GUARD THE OWNER AGAINST DEFECTS OR DEFICIENCIES IN THE WORK OF THE CONTRACTOR.

7. MODOT SPECIFICATIONS SHALL APPLY TO ALL ITEMS NOT SPECIFICALLY ADDRESSED IN THESE PLANS.

FOUNDATIONS:

1. FOUNDATIONS FOR THIS PROJECT HAVE BEEN DESIGNED IN ACCORDANCE WITH REQUIREMENTS SET FORTH IN A SOILS REPORT PREPARED BY TERRACON CONSULTANTS, INC. DEC. 8, 2016 (TERRACON PROJ. NO. 02165208). WALLS HAVE BEEN DESIGNED FOR AN ALLOWABLE SOIL BEARING VALUE OF 1500 PSF. THE CONTRACTOR SHALL REFER TO SOIL REPORT FOR ALL REQUIREMENTS AND RECOMMENDATIONS PERTINENT TO THIS PROJECT.

CONCRETE AND REINFORCING STEEL:

1. CONCRETE MIX DESIGNS SHALL MEET THE FOLLOWING REQUIREMENTS: (TAKEN FROM ACI 211.1)

MINIMUM COMPRESSIVE STRENGTH (psi)	MAXIMUM AGGREGATE SIZE (IN.)	MIN. CEMENT (LBS.)	MAXIMUM WATER/CEMENT RATIO	MAXIMUM SLUMP (IN.)	AIR ENTRAINMENT PERCENT (%)
4000	3⁄4	611	.48	4	6±1

NOTE: DO NOT ADD WATER TO CONCRETE DURING DELIVERY, AT PROJECT SITE, OR DURING PLACEMENT. THE INTENT OF THESE SPECIFICATIONS IS THAT THE CONTRACTOR SUPPLY CONCRETE MIXES WITH A MINIMUM AMOUNT OF MIX WATER IN ORDER TO LIMIT PLASTIC SHRINKAGE CRACKING. IT IS EXPECTED THAT WORKABILITY FOR CONCRETE MIXES WILL REQUIRE THE ADDITION OF WATER-REDUCING AND/OR SUPER-PLASTICIZING ADMIXTURES.

2. LAP SPLICE LENGTHS FOR HORIZONTAL #4 AND #5 BARS ARE 2'-0" AND 2'-6" RESPECTIVELY.

3. ALL CONCRETE IS REINFORCED UNLESS SPECIFICALLY CALLED OUT AS UN-REINFORCED. REINFORCE ALL CONCRETE NOT OTHERWISE SHOWN WITH SAME STEEL AS IN SIMILAR SECTIONS OR AREAS.

4. NO ALUMINUM ITEMS SHALL BE EMBEDDED IN ANY CONCRETE OR PLACED IN CONTACT WITH CONCRETE.

5. CAST-IN-PLACE CONCRETE CONSTRUCTION SHALL CONFORM TO THE LATEST AMERICAN CONCRETE INSTITUTE DOCUMENTS. ACI301, 305, 306, 315, 318, AND 347 UNLESS OTHERWISE NOTED IN THESE CONTRACT DOCUMENTS.

6. PRIOR TO PLACING CONCRETE IN ANY LOCATION, IT IS THE RESPONSIBILITY OF THE GENERAL CONTRACTOR TO HAVE THOROUGHLY CHECKED AND COORDINATED ALL DIMENSIONS, ELEVATIONS, OPENINGS, RECESSES, AND BLOCKOUTS SHOWN ON THE ARCHITECTURAL, STRUCTURAL AND MECHANICAL/ELECTRICAL/PLUMBING DRAWINGS. IN THE EVENT ERRORS, CONFLICTS, OR OMISSIONS EXIST, IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO CONTACT THE ARCHITECT OR ENGINEER FOR NECESSARY CORRECTIVE ACTION.

7. REINFORCING BARS #4 AND LARGER (EXCEPT TIES AND STIRRUPS) SHALL MEET ASTM A615 WITH SUPPLEMENTARY REQUIREMENTS (S1), GRADE 60. SMALLER BARS SHALL BE GRADE 40.

8. CONCRETE COVERAGE OF REINFORCEMENT SHALL HAVE THE FOLLOWING CLEAR DISTANCES UNLESS NOTED OTHERWISE ON THE DRAWINGS:

CAST AGAINST EARTH3"	
FORMED CONCRETE EXPOSED	

TO EARTH OR WEATHER_____2"

EXPOSED	ΤO	EARTH			
•	XPOSED	XPOSED TO	XPOSED TO EARTH	XPOSED TO EARTH	XPOSED TO EARTH

OR WEATHER______1" SLABS, 1-1/2" BEAMS AND COLUMNS

9. EMBEDDED AND ALL REINFORCING BARS MARKED CONTINUOUS SHALL BE EMBEDDED TO DEVELOP THE FULL TENSION CAPACITY OF THE BAR. LAPS SHALL BE CLASS B TENSION LAPS UNLESS SPECIFIED OTHERWISE ON THE DRAWINGS.

10. ALL BARS ARE TO BE SUPPORTED IN FORMS AND SPACED WITH WIRE BAR SUPPORTS PER ACI "MANUAL OF STANDARD PRACTICE FOR DETAILING CONCRETE STRUCTURES" (LATEST EDITION). BARS SHALL BE SECURELY WIRED PER LATEST EDITION OF CRSI'S "RECOMMENDED PRACTICE FOR PLACING REINFORCING BARS." ACCESSORIES FOR EXPOSED CONCRETE SHALL BE PLASTIC OR HAVE PLASTIC-TIPPED FEET.

11. CONCRETE PLACED DURING <u>COLD WEATHER</u> SHALL CONFORM TO THE REQUIREMENTS OF ACI 306R-88. COLD WEATHER IS DEFINED AS A PERIOD WHEN, FOR MORE THAN 3 SUCCESSIVE DAYS, THE MEAN DAILY TEMPERATURE DROPS BELOW 40°F.

12. CONCRETE PLACED DURING HOT WEATHER SHALL CONFORM TO THE REQUIREMENTS OF ACI 305R-99. HOT WEATHER IS DEFINED AS THAT COMBINATION OF AIR TEMPERATURE, RELATIVE HUMIDITY AND WIND SPEED THAT WILL CAUSE A RATE OF EVAPORATION OF 0.2 LB/SQ.FT./HR. OR MORE AS DEFINED BY FIGURE 2.1.5 OF ACI 305R-99.

13. CHAMFER ALL EXPOSED CORNERS OF CONCRETE SLABS, WALLS, BEAMS AND COLUMNS $\frac{3}{4}$ ", UNLESS NOTED OTHERWISE ON DETAILS.

POST-INSTALLED ANCHORS AND REBAR:

1. POST-INSTALLED ANCHORS AND REBAR SHALL BE INSTALLED USING AN ADHESIVE UNLESS SPECIFICALLY NOTED OTHERWISE. ANCHORS SHALL CONSIST OF THE FOLLOWING ANCHOR TYPES, AS PROVIDED BY HILTI, INC.:

- a) ANCHORAGE TO CONCRETE
 (1) HILTI HIT-HY 200 SAFE SET SYSTEM WITH HILTI HOLLOW DRILL BIT (TE-CD OR TE-YD)
 (2) STEEL ANCHOR ELEMENT SHALL BE HILTI HAS-E THREADED ROD PER ICC ESR-3187.
- b) REBAR DOWELING INTO CONCRETE
- (1) HILTI HIT-HY 200 SAFE SET SYSTEM WITH HILTI HOLLOW DRILL BIT (TE-CD OR TE-YD) AND CONTINUOUSLY DEFORMED REBAR PER ICC ESR-3187.

2. CONTACT HILTI AT (800) 879-8000 FOR PRODUCT RELATED QUESTIONS.

3. IF THE CONTRACTOR CHOOSES TO SUBMIT A SUBSTITUTION FOR APPROVAL, THEY MUST ATTACH CALCULATIONS SIGNED AND SEALED BY A PROFESSIONAL ENGINEER LICENSED IN THE JURISDICTION WHERE THE PROJECT IS LOCATED SHOWING THAT THE SUBSTITUTION IS "EQUAL". THE ICC-ES EVALUATION REPORT FOR THE "EQUAL" PRODUCT MUST ALSO BE SUBMITTED FOR REVIEW. THE CONTRACTOR SHALL NOTE THAT THE ICC-REPORT MAY INDICATE ADDITIONAL SPECIAL INSPECTION REQUIREMENTS. ANY ADDITIONAL SPECIAL INSPECTION REQUIREMENTS MUST BE PERFORMED AT NO ADDITIONAL COST TO THE OWNER.

4. INSTALL ANCHORS PER THE MANUFACTURER INSTRUCTIONS, AS INCLUDED IN THE ANCHOR PACKAGING.

5. THE CONTRACTOR SHALL ARRANGE AN ANCHOR MANUFACTURER'S REPRESENTATIVE TO PROVIDE ONSITE INSTALLATION TRAINING FOR ALL OF THEIR ANCHORING PRODUCTS SPECIFIED. THE STRUCTURAL ENGINEER OF RECORD MUST RECEIVE DOCUMENTED CONFIRMATION THAT ALL OF THE CONTRACTOR'S PERSONNEL WHO INSTALL ANCHORS ARE TRAINED PRIOR TO THE COMMENCEMENT OF INSTALLING ANCHORS.


6. OVERHEAD ADHESIVE ANCHORS MUST BE INSTALLED USING THE HILTI PROFI SYSTEM.


7. ANCHOR CAPACITY IS DEPENDANT UPON SPACING BETWEEN ADJACENT ANCHORS AND PROXIMITY OF ANCHORS TO EDGE OF CONCRETE. INSTALL ANCHORS IN ACCORDANCE WITH SPACING AND EDGE CLEARANCES INDICATED ON THE DRAWINGS.


8. EXISTING REINFORCING BARS IN THE CONCRETE STRUCTURE MAY CONFLICT WITH SPECIFIC ANCHOR LOCATIONS. UNLESS NOTED ON THE DRAWINGS THAT THE BARS CAN BE CUT, THE CONTRACTOR SHALL REVIEW THE EXISTING STRUCTURAL DRAWINGS AND SHALL UNDERTAKE MEASURES TO LOCATE THE POSITION OF THE EXISTING REINFORCING BARS AT THE LOCATIONS OF THE CONCRETE ANCHORS. BY HILTI FERROSCAN, GPR, X-RAY, OR OTHER MEANS.

OF MIS	GBA	DATE: DESIGN BY:	1/10/17 CEL
9° "1		DRAWN BY:	DRV
BRADLEY D.	architects	PROJECT NO.:	12720
BURTON 来 NUMBER 房	engineers	SHEET NO.	TOTAL SHEETS
PROFESSIONAL 5/21/18	9801 Renner Boulevard Lenexa, Kansas 66219 9 1 3 . 4 9 2 . 0 4 0 0 www.gbateam.com	19	33
Bradley D. Burton Professional Engineer License No. 25862	Mass Gradi Paragon Star Lee's Summi	Develo	oment
NO. DATE	REVISIONS		BY APPROVED
5/15/18	Revised Field Elevations		

Structural General Notes








SCALE : 3/4" = 1'-0"

DOWNSTREAM HEADWALL REINFORCEMENT


<u>3</u> 19 19

REINFORCENTENT

5 19 19



TYPICAL RCB REINFORCEMENT IN BEND SECTION SCALE : 3/4" = 1'-0"




6 19 19

SCALE : N.T.S.

GENERAL NOTES:

- 1. MINIMUM CLEARANCE TO REINFORCING STEEL SHALL BE 1½".
- 2. MODOT SPECIFICATIONS SHALL APPLY TO ALL ITEMS NOT SPECIFICALLY ADDRESSED IN THESE PLANS.
- SPLICE LENGTHS FOR #4 BARS SHALL BE 2'-0", UNLESS SPECIFICALLY SHOWN OTHERWISE.

RCB Details






LAP LENGTH TABL		
Bar Size	Length	
HORIZ. #4	24"	
VERT. #4	17"	

2"Ø STL. TUBE POSTS. WELD TO PLATE ALL THE WAY


POST ANCHOR PL 7x7x3/3

 $-\frac{1}{2}$ "ø SS ADHESIVE ANCHOR


RCB Details








CURB INLET OR JUNCTION BOX PLAN





- 7. RING & COVER TO BE NEENAH R-1537. CLAY & BAILEY #2020, DEETER #2016, OR APPROVED EQUAL. (CASTING MAY VARY BY MUNICIPALITY, REFER TO PLANS & CONTRACT DOCUMENTS.)
- 8. MODOT SPECS SHALL APPLY TO ALL ITEMS NOT SPECIFICALLY ADDRESSED IN THESE PLANS.
- 9. ALL WELDS SHALL BE PERFORMED IN ACCORDANCE WITH APPROPRIATE AWS SPECIFICATIONS & PROCEDURES.
- 10. ALL WELDS ON EXPOSED SURFACES SHALL BE DRESSED SO AS TO PROVIDE A PLEASING FINISHED APPEARANCE.
- 11. THE ENTIRE FRAME SHALL BE PAINTED A SINGLE COAT OF CHEM-PRIME #37–77 PRIMER (RED) OR EQUAL.

THE PROJECT PLANS ARE LISTED AT THE INSIDE FACE OF THE WALL. 2. FLOOR OF INLET SHALL BE SHAPED WITH INVERT TO PROVIDE SMOOTH FLOW.


1. THE FIRST DIMENSION LISTED IN THE CONSTRUCTION NOTES IS THE "L"


DIMENSION. THE SECOND DIMENSION IS THE "W" DIMENSION. FL'S LISTED ON

3. LOCATE MH RING AND COVER OVER OUTLET.


GENERAL NOTES:

- 4. STEPS SHALL BE SPACED AT 1'-4" O.C. VERTICALLY.
- 5. BEVEL ALL EXPOSED EDGES WITH $\frac{3}{4}$ " CHAMFER OR $\frac{1}{2}$ " TOOLED EDGE.
- 6. ON-GRADE INLETS SHALL CONFORM TO THE STREET GRADE AND SUMP INLETS SHALL BE LEVEL.








SPECIAL CURB INLET AND JUNCTION BOX DETAILS





BMP Plan Ref. No.	BMP Description	May Remove after Stage	Notes
1	Const. Entrance & Staging Area	С	
2	Install Orange Construction Fence	С	
3	Perimeter Silt Fence	С	
4	Silt Fence	С	
5	Ditch Check	С	
6	Straw Wattles	С	Wattles to be kept on hand for perimeter control where needed.
7	Seed & Mulch or Blanket or Sod		Erosion control blanket to be installed w/ seed. Check approved seeding dates and install temporary stabilization if out of seeding season. Install blanket according to manufacturer's instructions and stapling pattern.


















Erosion Control Details

fence required.

than 2 percent.





Erosion Control Details







<u>Legend</u>




Denotes 12" of Topsoil with Permanent Seeding

<u>NOTE:</u> All other disturbed areas to be temporary seeded.







Typical Sections (for reference only)