

STOP! **CALL BEFORE YOU DIG** MISSOURI ONE CALL SYSTEM 1-800-344-7483 or 811 (@ least 72 hours prior to digging)







SITE MAP-GENERAL NOTES

- 1. CONTRACTOR IS SOLELY RESPONSIBLE FOR SELECTION, IMPLEMENTATION, MAINTENANCE, AND EFFECTIVENESS OF ALL SWPPP CONTROLS - CONTROLS SHOWN ON THIS SITE MAP ARE SUGGESTED
- 2. CONTRACTOR SHALL RECORD INSTALLATION, MAINTENANCE OR MODIFICATION, AND REMOVAL DATES FOR EACH BMP EMPLOYED (WHETHER CALLED OUT ON ORIGINAL SWPPP OR NOT) DIRECTLY ON THE SITE MAP.
- 4. TEMPORARY AND PERMANENT STABILIZATION PRACTICES AND BMP'S SHALL BE INSTALLED AS PER THE STORM WATER POLLUTION PREVENTION PLAN. AS AN EXAMPLE, PERIMETER SILT FENCE SHALL BE INSTALLED BEFORE COMMENCEMENT OF ANY GRADING ACTIVITIES. OTHER BMP'S SHALL BE INSTALLED AS SOON AS PRACTICABLE AND SHALL BE MAINTAINED UNTIL FINAL SITE STABILIZATION IS ATTAINED. CONTRACTOR SHALL ALSO REFERENCE CIVIL AND LANDSCAPE PLANS SINCE PERMANENT STABILIZATION IS PROVIDED BY LANDSCAPING, THE BUILDING(S), AND SITE PAVING.
- 5. BMP'S HAVE BEEN LOCATED AS INDICATED ON THIS PLAN IN ACCORDANCE WITH GENERALLY ACCEPTED ENGINEERING PRACTICES IN ORDER TO MINIMIZE SEDIMENT TRANSFER. FOR EXAMPLE: SILT FENCES

EROSION CONTROL SCHEDULE AND SEQUENCING

- A. NOTIFY ALL APPLICABLE AUTHORITIES AT LEAST 48 HOURS PRIOR TO BEGINNING ANY WORK; CALL THE 'MISSOURI ONE CALL CENTER' AT1-800-344-7482 FOR UTILITY LOCATIONS.
- INSTALL TEMPORARY EROSION CONTROLS AND TREE PROTECTION FENCING PRIOR TO ANY CLEARING AND
- DEMOLISH AREAS INDICATED ON EXISTING CONDITIONS AND REMOVAL ITEMS SHEET. (IF APPLICABLE)
- CLEAR AND GRUB AND STRIP TOPSOIL. STOCKPILE TOPSOIL FOR LATER USE. CONSTRUCT TEMPORARY RETENTION/DETENTION POND. (IF APPLICABLE)
- ROUGH GRADE SITE PER GRADING PLAN.
- INSTALL STORM SEWER LINES AND APPURTENANCES. INSTALL TEMPORARY EROSION/SEDIMENTATION Controls ON NEW STORM SEWER INLETS.
- INSTALL WATER AND WASTE WATER LINES AND APPURTENANCES. ENSURE THAT ALL UNDERGROUND UTILITY CROSSINGS ARE COMPLETED.
- RAISE MANHOLE FRAMES AND COVERS TO TOP OF NATURAL GROUND.
- CONSTRUCT PAVED AREAS, CURBS. ISLANDS AND INSTALL INLET EROSION PROTECTION. M. COMPLETE RESTORATION OF SITE VEGETATION.
- WRITE CONCURRENCE LETTER AND SCHEDULE FINAL INSPECTION WITH INSPECTOR.
- REMOVE AND DISPOSE OF TEMPORARY EROSION CONTROLS WHEN RESTORATION HAS BEEN ACCEPTED. COMPLETE ANY NECESSARY FINAL DRESS UP OF AREAS DISTURBED BY ITEM "O"

TOTAL STATION LAYOUT


KIMLEY-HORN WILL PROVIDE AN AUTOCAD FILE OF THIS PLAN TO THE CONTRACTOR'S SURVEYOR TO USE FOR LAYOUT, VIA TOTAL STATION.


SITE MAP-SITE SPECIFIC NOTES

- CONSTRUCTION ENTRANCE SHALL BE LOCATED SO AS TO PROVIDE THE LEAST AMOUNT OF DISTURBANCE TO THE FLOW OF TRAFFIC IN AND OUT OF THE SITE. ADDITIONALLY, CONSTRUCTION ENTRANCE SHALL BE LOCATED TO COINCIDE WITH THE PHASING OF THE PAVEMENT REPLACEMENT.
- . THE NATURE OF THIS SITE'S CONSTRUCTION CONSISTS OF:
- A. DEMOLITION PRELIMINARY GRADING
- UTILITY INSTALLATION PAVEMENT CONSTRUCTION
- FINAL GRADING AND STABILIZATION
- CONTRACTOR TO REFERENCE GEOTECHNICAL REPORT PREPARED BY INTERTEK PSI (PROJECT NO. 03381842 DATED DECEMBER 14, 2018) FOR SOIL CONDITIONS. . ALL STORM WATER ON-SITE WILL SHEET FLOW INTO THE ON-SITE UNDERGROUND STORM DRAINAGE SYSTEM
- OR CONTINUE ALONG EXISTING DRAINAGE ROUTE
- NO SEDIMENTATION BASINS HAVE BEEN PROVIDED ON THIS SITE BECAUSE THE AREA OF DISTURBANCE IS LESS THAN 10.0 ACRES.
- POST CONSTRUCTION STORM WATER POLLUTION CONTROL MEASURES INCLUDE STABILIZATION BY
- PERMANENT PAVING, DRAINAGE SYSTEM STRUCTURE, OR LANDSCAPING.
- VELOCITY DISSIPATION DEVICES (RIP-RAP) WILL NOT BE USED.
- DISTURBED PORTIONS OF SITE MUST BE STABILIZED. STABILIZATION PRACTICES MUST BE INITIATED WITHIN 14 DAYS IN PORTIONS OF THE SITE WHERE CONSTRUCTION HAS BEEN EITHER TEMPORARILY OR PERMANENTLY CEASED, UNLESS EXCEPTED WITHIN THE NPDES PERMIT. CONTRACTOR SHALL REMOVE TEMPORARY EROSION CONTROL DEVICES UPON COMPLETION OF STABILIZATION OR PERMANENT DRAINAGE FACILITIES.
- PER FIRM MAP NO. 29095C0417G EFFECTIVE 01-20-2017, THE SITE IS LOCATED WITHIN FEMA DESIGNATED "X"
-). CONTRACTOR IS RESPONSIBLE FOR MODIFYING THE SWPPP/SITE MAP TO INCLUDE BMP'S FOR ANY OFF-SITE MATERIAL WASTE, BORROW OR EQUIPMENT STORAGE AREAS.
- 1. CONTRACTOR SHALL INSPECT DISTURBED AREAS, MATERIAL STORAGE AREAS EXPOSED TO PRECIPITATION, STRUCTURAL CONTROL MEASURES, AND VEHICLE ENTRY AND EXIT AREAS AT LEAST ONCE EVERY 14 CALENDAR DAYS AND WITHIN 24 HOURS OF A STORM EVENT OF 0.5 INCHES OR GREATER.

95% REVIEW SET FOR REVIEW ONLY **Kimley** »Horn KEVIN S. GASKEY

P.E. No. 28441 Date MAY 2019






-Wire Reinforced Silt Fence-Top of silt fence below top of downstream berm to (See Silt Fence Detail for Installation Requirements) * — Contractor shall field verify that Ponded Water Depth will not cause excessive unintended flooding. prevent bypass Proposed —/ Finished Grade (Typical all sides) - Wire Reinforced Silt Fence Place biodegradable log, staked wattles or other approved sediment control device in front of each inlet opening. (Not to be placed in throat of inlet). Plan

Not to Scale vated Area for (Area inlets at final grade and existing inlets) Early Stage Area Inlet Sediment Barrier to be installed immediately after inlet or junction box is constructed. Remove deposited sediment from excavated storage areas when available storage has been reduced by 20%. 2. Remove deposited sediment from filter socks or similar when any 2. Silt fence shall remain in place until excavated area is removed and Late Stage Area Inlet is being installed. accumulation of sediment is visible. Not to Scale Backfill excavated area ONLY after final grading of the site. Stabilization of the site is to immediately follow. 3. Repair or replace as necessary to maintain function and integrity AMERICAN PUBLIC WORKS ASSOCIATION Wire reinforced silt fence may be used in place of silt fence attached to wood frame. EARLY STAGE AREA INLET (All open boxes and inlets not at final grade) KANSAS CITY METRO CHAPTER AREA INLET AND NUMBER ESC-07
ADOPTED: Modified from 2015 Overland Park Standard Details for Erosion and Sediment Control. JUNCTION BOX PROTECTION

CHAIN LINK FENCE FABRIC IS TO BE 11 GAUGE HOT DIPPED ZINC COATED (GALVANIZED) IRON OR STEEL 8'-0" HIGH W/2 1/2" SQUARE DIAMOND. USE 8'-0" x 1 5/8" DIA. O.D. GALVANIZED IRON POSTS. CORNER AND GATE POSTS WILL BE 8'-0" x 2 3/4" DIA. O.D. ALL NON-MOVABLE FENCE POSTS TO BE SET IN A MIN. 2'-0" IN GROUND OR SET IN 4" THICK CONCRETE PAD 2'-0" SQUARE OR 2'-6" ROUND W/CORNER & GATE POSTS ADEQUATELY BRACED.



CONSTRUCTION FENCE
N.T.S. CRITICAL ROOT

- (1) EXISTING TREE(S) TO REMAIN.
- (2) DRIPLINE OF EXISTING TREE (TYP) (3) CONTINUOUS NYLON TIE STRING TIED TO STAKE TOPS W/ 2' TUNDRA WEIGHT

ORANGE STREAMERS @ 3' O.C.

- $\left(ext{ 4 }
 ight)$ 8' METAL T-STAKES: 8' O.C. MIN., DRIVEN 2' INTO GROUND AT (OR OUTSIDE) TREE DRIPLINE
- (5) 4' MIN. HEIGHT ORANGE PLASTIC FENCING INSTALLED PER MANF. RECOMMENDATIONS (TYP). SUPPLEMENT W/ SILT FENCE FABRIC @ PRUNING TRENCH AS REQ'D.
- (6) EXISTING GRADE TO BE DISTURBED.
- (7) ROOT PRUNING TRENCH 12" OUTSIDE FENCE -SEE NOTES.
- (8) EXISTING GRADE TO REMAIN.

- 1. PERFORM ROOT PRUNING ON ALL EXISTING TREES TO REMAIN WHERE CONSTRUCTION ACTIVITY FALLS WITHIN DRIP LINE OF EXISTING TREES.
- 2. ROOT PRUNING METHOD: 2 MONTHS MIN. PRIOR TO EXCAVATION & CONSTRUCTION ACTIVITIES, HAND CUT ROOTS BY DIGGING A 18"-24" DEEP x 8" WIDE TRENCH ALONG THE OUTSIDE PERIMETER OF EXISTING TREE(S) ADJACENT TO CONSTRUCTION AREAS. MAXIMIZE PRUNING TRENCH DISTANCE FROM TRUNK TO THE FULLEST EXTENT POSSIBLE, W/ THE ROOT PRUNING LINE PLACED @ THE EDGE OF CONSTRUCTION LIMITS.

TREE PROTECTION DETAIL

VEGETATIVE STABILIZATION REQUIREMENTS

<u>APPLICATION</u>

TEMPORARY SEEDING ALL DISTURBED AREAS WHICH WILL BE LEFT DORMANT FOR GREATER THAN 14 DAYS SHALL BE SEEDED WITH FAST— GERMINATING TEMPORARY VEGETATION IMMEDIATELY FOLLOWING GRADING OPERATIONS. SELECTION OF THE SEED WILL DEPEND ON THE TIME OF YEAR IT IS APPLIED (SEE DESCRIPTIONS IN TABLE 2). REFERENCE LANDSCAPE PLAN FOR PERMANENT STABILIZATION REQUIREMENTS. VEGETATION TABLE*

VEGETATION TABLE		
TEMPORARY SEEDING		
<u>SPECIES</u>	PLANTING RATE	PLANTING-DA
CRIMSON CLOVER	7#/ACRE	8/15 - 11/30
MILLET, FOXTAIL	30#/ACRE	5/1 - 8/3
RYEGRASS, ANNUAL	30#/ACRE	8/15 - 9/30
SPRANGLETOP, GREEN	2.5#/ACRE	2/1 - 5/1
TALL FESCUE	7#-10#/1000 SF	9/1 - 10/15

*USE ONLY USDA CERTIFIED SEED.


9/1 - 10/15

SURFACE PREPARATION FOR TEMPORARY SEEDING

- 1. INSTALL EROSION STRUCTURES SUCH AS DIKES, DIVERSIONS, ETC. PRIOR TO SEEDING.
- 2. FURROW SLOPES STEEPER THAN 3:1 ON THE CONTOUR LINE BEFORE SEEDING.
- 3. ENSURE SEED BED IS PULVERIZED, LOOSE, AND UNIFORM.

- 1. WHEN HYDROMULCHING IS USED, DO NOT MIX SEED AND FERTILIZER MORE THAN 30 MINUTES PRIOR TO APPLICATION.
- 2. APPLY SEED EVENLY USING PROPER EQUIPMENT AND WATER TO AID VEGETATION GROWTH.
- 3. EROSION CONTROL NETTING SHALL BE INSTALLED OVER FILL SLOPES WHICH HAVE BEEN BROUGHT TO FINAL GRADE AND HAVE BEEN SEEDED TO PROTECT AGAINST EROSION. MULCH (STRAW OR FIBER) SHALL BE USED ON RELATIVELY FLAT SLOPES.


95% REVIEW SET FOR REVIEW ONLY Not for construction or permit purposes Kimley»Horn Engineer KEVIN S. GASKEY
P.E. No. 28441 Date MAY 2019




95% REVIEW SET FOR REVIEW ONLY
Not for construction or permit purposes. **Kimley**Horn | Engineer | KEVIN S. GASKEY | P.E. No. | 28441 | Date | MAY 2019 |





FOR REVIEW ONLY
Not for construction or permit purposes. **Kimley**»Horn





95% REVIEW SET FOR REVIEW ONLY Not for construction or permit purposes. **Kimley** »Horn












0

95% REVIEW SET FOR REVIEW ONLY Not for construction or permit purpose Kimley»Horn Engineer KEVIN S. GASKEY
P.E. No. 28441 Date MAY 2019



HORIZONTAL SCALE: 1"= 40' VERTICAL SCALE: 1"= 4'

CONTRACTOR TO ADJUST ALL RIM ELEVATIONS TO MATCH FINISHED GRADE

13455 Noel Road, Suite 700, Dallas, Texas 75240
PHONE: 214-420-5600 FAX: 214-420-5680
www.KIMLEY-HORN.COM
MISSOURI REGISTRATION NUMBER 001512

95% REVIEW SET

FOR REVIEW ONLY
Not for construction or permit purposes.

Kimley» Horn

Engineer KEVIN S. GASKEY
P.E. No. 28441 Date MAY 2019

SUMMIT WAVES
WAVE POOL ADDITION
LEE'S SUMMIT, MO

UTILITY PROFILES

Shecked by: SEG
Shecked by: SEG
Shecked by: O64538700

SHEET



STA: 1+00.00 PRIVATE STORM LINE A

STA: 1+90.04 PRIVATE STORM LINE A

STA: 2+00.23 PRIVATE STORM LINE A

PRIVATE STORM LINE A

POOL DRAIN

1-4" 45° BEND

Δ=65°34'46"-

R=140.00'

BLUE PARKWAY

CB=S82°29'40"W

FL 4" PVC: 1051.3

STA: 2+40.90 PRIVATE STORM LINE C

CONNECTION LOCATION OF

WINTERIZATION DRAIN

FL 4" PVC: 1051.60

STA: 2+20.44 PRIVATE STORM LINE C

CONTRACTOR TO REFERENCE SP SHEETS

FOR EXACT HORIZONTAL AND VERTICAL

1-VORTSENTRY STRUCTURE

FL 12" RCP OUT: 1049.56

1-12" 45° BEND FL 12" RCP: 1049.51

INSTALL:

RIM: 1058.09 FL 12" IN: 1049.56

1-TYPE S HEADWALL.

FL 12" RCP IN: 1049.07

FL 12" RCP OUT: 1049.07

STA: 1+84.36 PRIVATE STORM LINE A

STA: 1+27.79 PRIVATE STORM LINE C

= STA: 1+00, STORM LINE C

1-4" 30° BEND

STA: 1+65.71 PRIVATE STORM LINE C

FL 4" PVC: 1050.18

INSTALL

1-4" 30° BEND

STA: 1+90.00 PRIVATE STORM LINE C

STA: 4+25.09 PRIVATE STORM LINE B

REFERENCE DECK DRAINAGE PLAN

DECK DRAINAGE CONNECTION

FOR CONTINUATION FL 24" RCP: 1052.27

BIORETENTION AREA

1-4" 30° BEND

BIORETENTION AREA -


FL 4" PVC: <u>1050.96</u>

FL 4" PVC: 1050.65

1-12"X4" 45° WYE

FL 12" RCP: 1049.48

SEE SHEET C-12 FOR DETAIL



LEGEND

— W — EXISTING WATER LINE

——— SAN ——— EXISTING SEWER LINE

EXISTING WATER VALVE

EXISTING SS MANHOLE

PROPOSED SS MANHOLE

EXISTING FIRE HYDRANT

PROPOSED STORM LINE


PROPOSED SS LINE

PROPOSED UGE LINE

PROPOSED GATE VALVE

— 2" W — PROPOSED WATER LINE

DETENTION OUTFALL JUNCTION BOX DETAILS



WEIR CALCULATIONS: **ORIFICE CALCULATIONS:**

 $Q = C*L*H^{1.5}$ C = 3.0

 $g = 32.2 FT/S^2$ OPENING #2 **OPENING #3** H = 7.0 INH = 2.0 INL = 6.0 IND = 5.0 IN

C = 0.6

 $Q = C*A*(2*g*H)^{0.5}$

L = 0.75 IN $A = 0.004 \text{ FT}^2$ **INVERT ELEVATION = 1050.30** HEAD = WSEL - CENTROID

OPENING #1 (WQV)

H = 0.75 IN

 $A = 0.29 \text{ FT}^2$ $A = 0.07 \text{ FT}^2$ INVERT ELEVATION = 1051.79 INVERT ELEVATION = 1053.10 HEAD = WSEL - CENTROID

HEAD = WSEL - CENTROID

	Outfall Structure Summary											
	Volume	Elevation	Op	ening #1			Opening #2	2	(Opening #3	1	Total
Design Storm	(ac-ft)	(ft)	Weir	Orifice	Actual	Weir	Orifice	Actual	Weir	Orifice	Actual	Actual
WQV	0.08	1051.79	0.34	0.02	0.02	0.00	0.00	0.00	0.00	0.00	0.00	0.02
2-year	0.10	1051.97	0.40	0.02	0.02	0.12	0.00	0.12	0.00	0.00	0.00	0.14
10-year	0.16	1053.02	0.84	0.03	0.03	2.06	1.36	1.36	0.00	0.00	0.00	1.39
100-year	0.24	1054.30	1.50	0.04	0.04	5.98	2.09	2.09	1.64	0.35	0.35	2.48

	Elevation Discharge Summary Table										
Elevation	Elevation				Opening #2		Opening #3			Total	
Elevation	Weir	Orifice	Actual	Weir	Orifice	Actual	Weir	Orifice	Actual	Actual	
1050.3	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
1051.3	0.19	0.02	0.02	0.00	0.00	0.00	0.00	0.00	0.00	0.02	
1052.3	0.53	0.03	0.03	0.55	0.66	0.55	0.00	0.00	0.00	0.58	
1053.3	0.97	0.03	0.03	2.80	1.55	1.55	0.11	0.11	0.11	1.70	
1054.3	1.50	0.04	0.04	5.98	2.09	2.09	1.64	0.35	0.35	2.48	
1054.80	1.79	0.04	0.04	7.85	2.32	2.32	2.77	0.43	0.43	2.78	

Stage Stor	rage Summ	nary Table
Elevation	Volume	
(ft)	(ac)	(ac-ft)
1050.30	0.06	0.00
1054.80	0.06	0.25

- CONTRACTOR TO FIELD VERIFY LOCATION AND THE FLOWLINES OF ALL EXISTING UTILITIES. 2. WATER & WASTEWATER SERVICE TO BE PROVIDED
- BY CITY OF LEE'S SUMMIT CONTRACTOR TO COORDINATE WITH M.E.P. PLANS AT ALL UTILITY STUBOUTS.
- 3. CONTRACTOR TO ENSURE NO FIRE HYDRANTS. METERS OR VALVES ARE PLACED IN SIDEWALKS.

STA: 3+39.56 PRIVATE STORM LINE A

STA: 3+43.47 PRIVATE STORM LINE A CONNECT TO UNDERGROUND

(SEE SHEET C-13 FOR DETAILS)

- STORMTRAP UNDERGROUND DETENTION SYSTEM

STA: 1+00.00 PRIVATE STORM LINE B

STA: 1+23.24 PRIVATE STORM LINE B

REFERENCE DECK DRAINAGE PLAN

STA: 1+32.71 PRIVATE STORM LINE B

UNDERGROUND DETENTION FL 24" RCP IN: 1050.66

DECK DRAINAGE CONNECTION

FOR CONTINUATION

POINT OF CURVATURE

STA: 1+53.56 PRIVATE STORM LINE B

STA: 1+82.09 PRIVATE STORM LINE B

REFERENCE DECK DRAINAGE PLAN

STA: 2+02.18 PRIVATE STORM LINE B DECK DRAINAGE CONNECTION REFERENCE DECK DRAINAGE PLAN

DECK DRAINAGE CONNECTION

DECK DRAINAGE CONNECTION

REFERENCE DECK DRAINAGE PLAN

L 24" RCP: 1050.82

FOR CONTINUATION FL 24" RCP: 1050.92

FOR CONTINUATION

FL 24" RCP: 1051.06

FOR CONTINUATION FL 24" RCP: 1051,16

STA: 2+24.24 PRIVATE STORM LINE B DECK DRAINAGE CONNECTION REFERENCE DECK DRAINAGE PLAN

STA: 2+46.81 PRIVATE STORM LINE B

POINT OF TANGENCY FL 24" RCP: 1051.24

FOR CONTINUATION FL 24" RCP: 1051,27

INSTALL:

1-24" 30° BEND

POINT OF CURVATUR

FOR CONTINUATION

FL 24" RCP: 1051.47

FL 24" RCP: 1051.38

DECK DRAINAGE CONNECTION REFERENCE DECK DRAINAGE PLAN

STA: 2+64.85 PRIVATE STORM LINE B

STA: 2+18.50 PRIVATE STORM LINE B

FL 24" RCP: 1050.77

CONNECT TO

INSTALL:

RIM: 1060.41

Δ=24°34'35"— R=200.00'

/ L=85/79'

C=85.13'

CB=S7°24'59"W

DETENTION OUTFALL

JUNCTION BOX PER

DETAIL (THIS SHEET)

DETENTION POND

FL 3'X3' RCB: 1050.30

FL 3'X3' RCB IN: 1050.28


FL 12" RCP OUT: 1050.28

- 1. CONTRACTOR TO FIELD VERIFY LOCATION AND THE FLOWLINES OF ALL EXISTING UTILITIES.
- 2. WATER AND WASTEWATER SERVICE TO BE PROVIDED BY THE CITY.
- 3. CONTRACTOR TO COORDINATE WITH MEP PLANS AT ALL UTILITY STUBOUTS.
- 4. CONTRACTOR TO ENSURE NO METERS OR VALVES ARE PLACED IN SIDEWALKS.
- 5. CONTRACTOR TO REFERENCE GEOTECHNICAL REPORT PREPARED BY INTERTEK PSI (PSI PROJECT NO. 03381842 DATED DECEMBER 14, 2018 FOR UTILITY TRENCH RECOMMENDATIONS

- . THE LOCATION AND / OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES, AND WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CONTACT THE APPROPRIATE UTILITY COMPANIES AT LEAST 72 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATION OF EXISTING UTILITIES ON SITE OR IN RIGHT-OF-WAY. CONTRACTOR SHALL NOTIFY THE UTILITY AUTHORITIES INSPECTORS 72 HOURS BEFORE CONNECTION TO ANY EXISTING LINES.
- CONTRACTOR SHALL COORDINATE AND SCHEDULE TIE-INS/CONNECTIONS WITH ALL UTILITY COMPANIES ALL UNDERGROUND LINES SHALL BE INSTALLED, INSPECTED AND APPROVED PRIOR TO BACKFILLING.
- ALL NECESSARY INSPECTION AND/OR CERTIFICATIONS REQUIRED BY CODES AND/OR UTILITY SERVICE COMPANIES SHALL BE PERFORMED PRIOR TO ANNOUNCED BUILDING POSSESSION AND THE FINAL CONNECTION OF SERVICE.
- GENERAL CONTRACTOR IS TO COORDINATE WITH APPROPRIATE UTILITY COMPANIES PRIOR TO CONSTRUCTION, ADJUSTMENT, OR
- RELOCATION OF EXISTING UTILITIES AS DESIGNATED ON PLANS. ALL SEWER LINES TO HAVE 48" COVER MINIMUM.
- ALL WATERLINES AND SANITARY SEWER LINES, AND WATERLINES AND STORM SEWER LINES SHOULD BE KEPT TEN FEET (10') APART WHEN PARALLEL OR 24" VERTICAL CLEARANCE WHEN CROSSING (OUTSIDE OF PIPE TO OUTSIDE OF PIPE). IF 24" OF VERTICAL CLEARANCE CAN NOT BE MAINTAINED, SANITARY SEWER LINE TO BE ENCASED IN CONCRETE FOR 20' CENTERED ON CROSSING.
- ALL TRENCHING, PIPE LAYING AND BACKFILLING SHALL BE IN ACCORDANCE WITH FEDERAL OSHA REGULATIONS ALL MATERIALS, CONSTRUCTION, AND INSPECTION FOR WATER AND SANITARY SEWER LINES SHALL BE PER CITY OF ST. CHARLES
- STANDARD SPECIFICATIONS. 10. DAMAGE TO ALL EXISTING CONDITIONS TO REMAIN WILL BE REPLACED AT THE CONTRACTORS EXPAND.
- 11. CONTRACTOR SHALL REFER TO MEP PLANS AND SP SHEETS FOR EXACT UTILITY ENTRANCE/CONNECTION LOCATIONS. 12. GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TAP AN TIE ON FEES REQUIRED. AS WELL AS COSTS OF UNDERGROUND SERVICE CONNECTIONS TO BE BUILDINGS.
- 13. THE CONTRACTOR SHALL INCLUDE IN THE BID PRICE THE DAILY RECORD KEEPING OF THE AS-BUILT CONDITION OF ALL THE UNDERGROUND UTILITIES.

95% REVIEW SET FOR REVIEW ONLY Kimley»Horn

Engineer KEVIN S. GASKEY
P.E. No. 28441 Date MAY 2019



HORIZONTAL SCALE: 1"= 40' VERTICAL SCALE: 1"= 4'

CONTRACTOR TO ADJUST ALL RIM ELEVATIONS TO MATCH FINISHED GRADE

Hor

95% REVIEW SET FOR REVIEW ONLY
Not for construction or permit purposes **Kimley**Horn Engineer KEVIN S. GASKEY
P.E. No. 28441 Date MAY 2019

E POOL ADDITION S'S SUMMIT, MO SUMMIT WAVE POOL LEE'S SUN


STORM PROFILES

SHEET

SHEET

HYDROLOGIC CALCULATIONS - EXISTING CONDITIONS

Existing Condition Hydrologic Parameters DA Area (ac) Area (mi²) CN TC (min) T_{lag} (min) Q_{2yr} (cfs) Q_{10yr} (cfs) Q_{100yr} (cfs) 75.2 4.52 2.71 | 2.2 | 5.7 | 0.13 0.00020 4.58 0.00059 5.91 1.42 0.00222 7.20 4.32 6.1 11.6 75.5 2.4




	Project: Lee's Su	mmit Simulation R	tun: 002 Existing	
End	t of Run: 07Mar 2019 of Run: 10Mar 2019 pute Time: 22May 2019	.00:00 Mete , 09:37:31 Conf	n Model: Existing eorologic Model: 002-Year trol Specifications:72-Hour	
ow Elements: All Element	v v	olume Units: () IN	AC-FT So	rting: Hydrologic 🗸
Hydrologic Element	Drainage Area (MI2)	Peak Discharge (CFS)	Time of Peak	Volume (AC-FT)
	0.00222	2.4	07Mar 2019, 12:06	0.14
	0.00222	2.4	07Mar2019, 12:06	0.14
	0.00059	0.7	07Mar2019, 12:05	0.04
	0.00020	0.2	07Mar2019, 12:06	0.01
	0.00079	0.9	07Mar2019, 12:05	0.05
	0.00025	0.3	07Mar2019, 12:04	0.02
	0.00025	0.3	07Mar2019, 12:04	0.02
	0.00183	2.2	07Mar2019, 12:04	0.11
	0.00183	2.2	07Mar2019, 12:04	0.11

End	rt of Run: 07Mar2019 i of Run: 10Mar2019 npute Time:22May2019	,00:00 Met	n Model: Existing eorologic Model: 010-Year trol Specifications:72-Hour	
Show Elements: All Elemen	nts 🗸	olume Units: O IN	AC-FT Sort	ing: Hydrologic ∨
Hydrologic Element	Drainage Area (MI2)	Peak Discharge (CFS)	Time of Peak	Volume (AC-FT)
)	0.00222	6.1	07Mar 2019, 12:05	0.36
J-D	0.00222	6.1	07Mar 2019, 12:05	0.36
C2	0.00059	1.7	07Mar 2019, 12:05	0.09
C1	0.00020	0.6	07Mar 2019, 12:06	0.03
1-C	0.00079	2.3	07Mar 2019, 12:05	0.13
В	0.00025	0.8	07Mar 2019, 12:04	0.04
1 - B	0.00025	0.8	07Mar 2019, 12:04	0.04
Δ,	0.00183	5.6	07Mar 2019, 12:04	0.29
J-A	0.00183	5.6	07Mar 2019, 12:04	0.29

	Start of Run: 07Mar2019 End of Run: 10Mar2019 Compute Time: 22May2019	, 00:00 Mete	Model: Existing orologic Model: 100-Year rol Specifications: 72-Hour O AC-FT Sort	ina: Hvdrologic 🤍
Hydrologic Element	Drainage Area (MI2)	Peak Discharge (CFS)	Time of Peak	Volume (AC-FT)
D	0.00222	11.6	07Mar2019, 12:05	0.74
J-D	0.00222	11.6	07Mar2019, 12:05	0.74
C2	0.00059	3.2	07Mar2019, 12:05	0.20
C1	0.00020	1.1	07Mar2019, 12:06	0.07
J-C	0,00079	4.3	07Mar2019, 12:05	0.26
В	0.00025	1.5	07Mar2019, 12:04	0.08
J - B	0.00025	1.5	07Mar2019, 12:04	0.08
A	0.00183	10.8	07Mar2019, 12:04	0.60
J-A	0.00183	10.8	07Mar2019, 12:04	0.60

HYDROLOGIC CALCULATIONS - PROPOSED CONDITIONS

			Proposed Co	ondition H	ydrologic F	Parameters	3		
POI	DA	Area (ac)	Area (mi²)	CN	TC (min)	T _{lag} (min)	Q _{2yr} (cfs)	Q _{10yr} (cfs)	Q _{100yr} (cfs)
	A1	0.86	0.00134	75.7	3.97	2.38	1.8	4.3	8.1
	A2	0.07	0.00011	98.0	5.00	3.00	0.3	0.5	0.8
A	А3	0.24	0.00038	92.0	5.23	3.14	1.0	1.7	2.7
^	A4	0.23	0.00036	98.0	5.35	3.21	1.0	1.7	2.6
	A5	0.32	0.00050	88.3	5.98	3.59	1.1	2.0	3.3
	A6	0.11	0.00017	89.3	5.62	3.37	0.4	0.7	1.1
В	В	0.13	0.00020	75.8	4.09	2.45	0.3	0.6	1.2
С	C1	0.14	0.00022	87.7	7.49	4.49	0.4	0.8	1.3
	C2	0.05	0.00008	83.6	5.00	3.00	0.2	0.3	0.5
D	D	0.88	0.00138	76.5	7.24	4.35	1.6	3.9	7.3
-	Pool	0.22	0.00034	98.0	5.19	3.11	1.0	1.6	2.4



End	ort of Run: 07Mar2019, d of Run: 10Mar2019, mpute Time:22May2019	, 00:00 Mete	n Model: Proposed eorologic Model: 002-Year trol Spedifications: 72-Hour	ting: Hydrologic V
Hydrologic	Drainage Area	Peak Discharge	Time of Peak	Volume
Element	(MI2)	(CFS)		(AC-FT)
	0.00050	1.1	07Mar2019, 12:05	0.06
	0.00038	0.9	07Mar2019, 12:04	0.05
	0.00036	1.0	07Mar2019, 12:04	0.06
	0.00017	0.4	07Mar2019, 12:05	0.02
	0.00141	0.5	07Mar2019, 12:29	0.18
	0.00141	0.5	07Mar2019, 12:29	0.18
	0.00141	0.5	07Mar2019, 12:29	0.18
	0.00011	0.3	07Mar2019, 12:04	0.02
	0.00152	0.5	07Mar2019, 12:23	0.20
	0.00152	0.5	07Mar2019, 12:23	0.20
	0.00134	1.7	07Mar2019, 12:04	0.08
	0.00286	2.2	07Mar2019, 12:04	0.28
	0.00138	1.6	07Mar2019, 12:06	0.09
	0.00138	1.6	07Mar2019, 12:06	0.09
	0.00034	1.0	07Mar2019, 12:04	0.05
	0.00034	1.0	07Mar2019, 12:04	0.05
	0.00022	0.4	07Mar2019, 12:06	0.02
	0.00008	0.1	07Mar2019, 12:04	0.01
	0.00030	0.6	07Mar 2019, 12:05	0.03
	0.00020	0.3	07Mar2019, 12:04	0.01
	0.00020	0.3	07Mar2019, 12:04	0.01

Enc Cor	rt of Run: 07Mar2019, d of Run: 10Mar2019, mpute Time:22May2019	, 00:00 Mete , 09:34:54 Cont	n Model: Proposed corologic Model: 010-Year rol Specifications:72-Hour	
Show Elements: All Elements	Drainage Area	olume Units: () IN Peak Discharge	AC-FT: Sort Time of Peak	ing: Hydrologic ∨
Element	(MI2)	(CFS)		(AC-FT)
A5	0.00050	2.0	07Mar 2019, 12:05	0.11
A3	0.00038	1.7	07Mar 2019, 12:04	0.10
44	0.00036	1.7	07Mar 2019, 12:04	0.10
46	0.00017	0.7	07Mar 2019, 12:04	0.04
Detention	0.00141	1.4	07Mar 2019, 12:19	0.35
]-1	0.00141	1.4	07Mar 2019, 12:19	0.35
₹-1	0.00141	1.4	07Mar 2019, 12:19	0.35
A2	0.00011	0.5	07Mar 2019, 12:04	0.03
1-2	0.00152	1.5	07Mar2019, 12:16	0.38
₹-2	0.00152	1.5	07Mar 2019, 12:16	0.38
A1	0.00134	4.3	07Mar 2019, 12:04	0.22
J- A	0.00286	5.6	07Mar 2019, 12:04	0.60
)	0.00138	3.9	07Mar 2019, 12:05	0.23
1-D	0.00138	3.9	07Mar 2019, 12:05	0.23
Pool	0.00034	1.6	07Mar 2019, 12:04	0.10
J-A1	0.00034	1.6	07Mar 2019, 12:04	0.10
G1	0.00022	0.8	07Mar2019, 12:05	0.05
C2	0.00008	0.3	07Mar 2019, 12:04	0.02
J-C	0.00030	1.1	07Mar 2019, 12:05	0.07
3	0.00020	0.6	07Mar 2019, 12:04	0.03
1-8	0.00020	0.6	07Mar 2019, 12:04	0.03

Hydrologic Element	Drainage Area (MI2)	Peak Discharge (CFS)	Time of Peak	Volume (AC-FT)
A5	0.00050	3.3	07Mar2019, 12:05	0.21
A3	0.00038	2.6	07Mar 2019, 12:04	0.17
A4	0.00036	2.6	07Mar 2019, 12:04	0.17
A6	0.00017	1.1	07Mar2019, 12:04	0.07
Detention	0.00141	3.4	07Mar 2019, 12:14	0.62
J-1	0.00141	3.4	07Mar 2019, 12:14	0.62
R-1	0.00141	3.4	07Mar 2019, 12:14	0.62
A2	0.00011	0.8	07Mar 2019, 12:04	0.05
J- <u>2</u>	0.00152	3.7	07Mar 2019, 12:13	0.67
R-2	0.00152	3.7	07Mar 2019, 12:13	0.67
A1	0.00134	8.1	07Mar 2019, 12:04	0.45
J-A	0.00286	10.8	07Mar 2019, 12:04	1.12
D	0.00138	7.3	07Mar 2019, 12:05	0.47
J-D	0.00138	7.3	07Mar 2019, 12:05	0.47
Pool	0.00034	2.4	07Mar 2019, 12:04	0.16
J-A1	0.00034	2.4	07Mar 2019, 12:04	0.16
C1	0.00022	1.3	07Mar 2019, 12:05	0.09
C2	0.00008	0.5	07Mar 2019, 12:04	0.03
J-C	0.00030	1.8	07Mar 2019, 12:05	0.12
В	0.00020	1.2	07Mar 2019, 12:04	0.07
J-B	0.00020	1.2	07Mar 2019, 12:04	0.07

Project: Lee's Summit Simulation Run: 100 Proposed

Start of Run: 07Mar2019, 00:00 Basin Model: Proposed End of Run: 10Mar2019, 00:00 Meteorologic Model: 100-Year

Project: Lee's Summit Simulation Run: 100 Proposed

Start of Run: 07Mar2019, 00:00 Basin Model: Proposed End of Run: 10Mar2019, 00:00 Meteorologic Model: 100-Year Compute Time: 22May2019, 09:33:03 Control Specifications: 72-Hour

		199-19		0.00	100001100
Pr		it Simulatio servoir: Deter	on Run: 002 Propose ntion	ed	
End of Run:	n: 07Mar2019, 00 10Mar2019, 00 ne:22May2019, 00 Volume U	0:00	Basin Model: Meteorologic Model: Control Specification AC-FT		ar
Computed Results					
Peak Inflow: Peak Discharge: Inflow Volume: Discharge Volume	0.5 (CFS) 0.18 (AC-FT)		_		, 12:29 T)

74

98

 $CN_{PostWeighted} = 75.8$

Grass

Pavement 0.01

0.12

 $CN_{PreWeighted} = 75.5$

CN CN*A

CN*A


0.98

0.98

	Pro		mit Simula eservoir: Det	tion Run: 010 Propo tention	osed
	End of Run:	07Mar2019, 0 10Mar2019, 0 e:22May2019, 0 Volume I	00:00	Basin Model: Meteorologic Mod Control Specificat	
uted R	tesults				
Pe	ak Inflow: ak Discharge: flow Volume:	6.0 (CFS) 1.4 (CFS) 0.35 (AC-FT)		e of Peak Discharg	07Mar2019, 12:0 e:07Mar2019, 12:1 0.15 (AC-FT)

Compute Time: 22May2019, 09:34:54 Control Specifications: 72-Hour	Compute Time: 22May 2019, 09:33:03 Control Specifications: 72-Hour
Volume Units: ○ IN	Volume Units: ○ IN ● AC-FT Computed Results
Peak Inflow: 6.0 (CFS) Date/Time of Peak Inflow: 0.7Mar2019, 12:04 Peak Discharge: 1.4 (CFS) Date/Time of Peak Discharge:0.7Mar2019, 12:19 Inflow Volume: 0.35 (AC-FT) Peak Storage: 0.15 (AC-FT) Discharge Volume: 0.35 (AC-FT) Peak Elevation: 1052.4 (FT)	Peak Inflow: 9.6 (CFS) Date/Time of Peak Inflow: 07Mar2019, 12:04 Peak Discharge: 3.4 (CFS) Date/Time of Peak Discharge:07Mar2019, 12:14 Inflow Volume: 0.62 (AC-FT) Peak Storage: 0.22 (AC-FT) Discharge Volume:0.62 (AC-FT) Peak Elevation: 1053.4 (FT)

lunction	2 YR			10 YR			100 YR			
Junction	Existing	Proposed	Difference	Existing	Proposed	Difference	Existing	Proposed	Difference	
J-A	2.2	2.2	0.0	5.6	5.6	0.0	10.8	10.8	0.0	
J-B	0.3	0.3	0.0	0.8	0.6	-0.2	1.5	1.2	-0.3	
J-C	0.9	0.6	-0.3	2.3	1.1	-1.2	4.3	1.8	-2.5	
J-D	2.4	1.6	-0.8	6.1	3.9	-2.2	11.6	7.3	-4.3	



WATER QUALITY CALCULATIONS - PROPOSED CONDITIONS

Water Quality Calculations - Outfall A (Disturbed Area):

Land Use	Area	CN	CN*A		
Grass	1.27	74	93.98		
Pavement	0.01	98	0.98		
	CN _{PreWeighted} =				

B. Postdevelopment CN							
Area	CN	CN*A					
0.32	74	23.68					
0.75	98	73.5					
CN _{PostWeighted} =							
	Area 0.32 0.75	Area CN 0.32 74 0.75 98					

C. Level of Service (LS) Calculation CN_{PreWeighted} = 74.2 CN_{PostWeighted} = 90.8 Difference = 16.6 LS Requried (Table 4.2)=


DA	Cover/BMP Description	Treatment Area	VR	VR*Area
A1 (Bypass, Disturbed)	None	0.10	0.00	0.00
A2 (Bypass)	None	0.07	0.00	0.00
А3	Extended Dry Detention + Hydrodynamic Seperator	0.24	8.00	1.92
A4	Extended Dry Detention + Hydrodynamic Seperator	0.23	8.00	1.84
A5	Bioretention, Extended Dry Detention, + Hydrodynamic	0.32	16.50	5.28
A6	Bioretention, Extended Dry Detention, + Hydrodynamic	0.11	16.50	1.82
			Total =	10.86
		Weig	hted VR =	10.14
		Requ	uired VR =	8.00


% Site Impervious	70%
Rv	0.68
WQV (in)	0.93
WQV (ac-ft)	0.08
Release Rate (hr)	40
Q _{WQV} (cfs)	0.03

Water Quality (Calculat	ions - Outfall D	<u>):</u>	Water Quality C	<u>alculat</u>	ions - Outfall B	<u>:</u>
A. Predevelopn	nent CN	I		A. Predevelopm	ent CN	J	
Land Use	Area	CN	CN*A	Land Use	Area	CN	C
Grass	1.33	74	98.42	Grass	0.15	74	
Pavement	0.09	98	8.82	Pavement	0.01	98	
		CN _{PreWeighted} =	75.5			CN _{PreWeighted} =	
B. Postdevelop	ment C	N		B. Postdevelopr	nent C	N	
Land Use	Area	CN	CN*A	Land Use	Area	CN	C
							Г

Postdevelop	ment C	N	
Land Use	Area	CN	CN*A
Grass	0.80	74	59.2
Pavement	0.09	98	8.82
		CN _{PostWeighted} =	76.4

C. Level of Service	e (LS)	Calculation	C. Level of Servi	ce (LS)	Calculation
$CN_{PreWeighted} =$	75.5		$CN_{PreWeighted} =$	75.5	
CN _{PostWeighted} =	76.4		CN _{PostWeighted} =	75.8	
Difference =	0.9		Difference =	0.3	
LS Requried	2/2		LS Requried	2/2	
LS Requried (Table 4.2)=	11/a		LS Requried (Table 4.2)=	n/a	







0


95% REVIEW SET FOR REVIEW ONLY Not for construction or permit purpos **Kimley Horn**


Engineer KEVIN S. GASKEY
P.E. No. 28441 Date MAY 2019


ONSTRUCTION














13455 Noel Road, Suite 700, Dallas, Texas 75240
PHONE: 214420-5600 FAX: 214420-5680
WWW.KIMLEY-HORN.COM

95% REVIEW SET

FOR REVIEW ONLY
Not for construction or permit purposes.

Kimley» Horn

Engineer KEVIN S. GASKEY
P.E. No. 28441 Date MAY 2019


SUMMIT WAVES

AVE POOL ADDITION
LEE'S SUMMIT, MO

ONSTRUCTION DETAILS

by: ABO
ad by: SEG
MAY 2019
No. 064538700

SHEET



Del Road, Suite 700, Dallas, Texas 75240

VE: 214-420-5600 FAX: 214-420-5680

WWW.KIMLEY-HORN.COM

URI REGISTRATION NUMBER 001512

95% REVIEW SET

FOR REVIEW ONLY
Not for construction or permit purposes.

Kimley>Horn

Engineer
P.E. No. 28441 _____ Date _____MAY 2019

VES DDITION T MO

SUMMIT WAV WAVE POOL AD

FENTION DETAILS

ABO


by: SEG

MAY 2019

. 064538700

Checked by:
Date:
Project No.

SHEET



13455 Noel Road, Suite 700, Dallas, Texas 75240
PHONE: 214-420-5600 FAX: 214-420-5680
WWW.KIMLEY-HORN.COM

95% REVIEW SET

FOR REVIEW ONLY
Not for construction or permit purposes.

Kimley» Horn

SET

KEVIN S. GASKEY

Jobe MAY 2019

SUMMIT WAVES

WAVE POOL ADDITIO
LEE'S SUMMIT, MO

DETENTION DETAILS


d by: SEG

MAY 2019

No. 064538700

Checked by:
Date:
Project No.

:_14



13455 Noel Road, Suite 700, Dallas, Texas 75240
PHONE: 214-420-5600 FAX: 214-420-5680
WWW.KIMLEY-HORN.COM
MISSOURI REGISTRATION NUMBER 001512

95% REVIEW SET

FOR REVIEW ONLY
Not for construction or permit purposes.

Kimley >>> Horn

Engineer KEVIN S. GASKEY
P.E. No. 28441 Date MAY 2019

SUMMIT WAVES
WAVE POOL ADDITION
LEE'S SUMMIT, MO

DETENTION DETAILS

ecked by: SEG

ecked by: SEG


e: MAY 2019

ject No. 064538700

SHEET

MATCHLINE

MATCHLINE



TRAFFIC CONTROL NOTES

1. ALL TRAFFIC CONTROL SHALL CONFORM TO THE LATEST VERSION OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD). FIELD MODIFICATIONS MAY BE MADE TO ADDRESS LOCAL CONDITIONS WITH THE APPROVAL OF THE ENGINEER.

2. DESIGN SPEED ON JEFFEROSN STREET IS 35 MPH. MINIMUM SIGN SPACING, CHANNELIZATION DEVICE SPACING AND TAPER LENGTHS ARE AS SHOWN.

3. CONTRACTOR IS RESPONSIBLE FOR INSTALLATION, MAINTENANCE, AND REMOVAL OF TRAFFIC CONTROL DEVICES. TRAFFIC CONTROL DEVICES SHOULD BE INSPECTED DAILY AND REPAIRED OR REPLACED AS NECESSARY. AFTER REMOVAL, CONTRACTOR IS RESPONSIBLE FOR RESTORATION OF MODIFICATIONS TO ROADWAY AND SIDEWALK SURFACES, ROADWAY MARKINGS, AND SIGNAGE DUE TO TRAFFIC CONTROL DEVICES OR CONSTRUCTION ACTIVITY.


4. CHANNELIZATION DRUMS ARE THE MINIMUM LEVEL OF CHANNELIZATION DEVICE WHICH SHALL BE USED ON THE OUTSIDE EDGES OF THE TRAVEL LANES. NARROW CHANNELIZATION DEVICES ON THE CENTERLINE SEPARATING OPPOSITE LANES OF TRAFFIC SHALL BE VERTICAL PANELS, TABULAR MARKERS, OR NAVIGATOR/NAVICADE DELINEATORS OR EQUIVALENT 12"-WIDE DEVICES. OPPOSING TRAFFIC LANE DIVIDER (OTLD) DEVICES WITH CW6-4 "TWO WAY TRAFFIC" SIGNS SHALL BE USED


5. IF THE TCP IS ACTIVE DURING THE HOURS OF DARKNESS, ALL CHANNELIZATION DEVICES SHALL HAVE A TYPE "C" STEADY-BURN WARNING LIGHT OR EQUIVALENT REFLECTOR, AND ALL WARNING SIGNS SHALL HAVE A TYPE "A" LOW-INTENSITY FLASHING WARNING LIGHT, AS REQUIRED IN ACCORDANCE WITH THE

6. TWO-WAY VEHICULAR TRAFFIC FLOW AND ACCESS TO ALL OCCUPIED PROPERTIES SHALL BE MAINTAINED AT ALL TIMES UNLESS NOTED.

7. PEDESTRIAN PATHWAYS SHALL BE PROVIDED ACROSS OR AROUND THE WORK AREA IN ACCORDANCE WITH THE MUTCD. CONTRACTOR SHALL PROVIDE SIDEWALK CLOSURE, CROSSWALK CLOSURE, AND/OR WALKWAY BYPASS WHEREVER PEDESTRIAN MOVEMENTS ARE AFFECTED BY CONSTRUCTION ACTIVITIES. ALL SIDEWALKS AND CROSSWALKS SHALL BE ACCESSIBLE WHEN CONTRACTOR IS NOT WORKING UNLESS OTHERWISE APPROVED BY THE CITY TRAFFIC ENGINEER.

8. WHEN THE TCP IS NOT IN EFFECT, ALL CHANNELIZING DEVICES SHALL BE REMOVED FROM THE TRAVEL LANES AND ALL SIGNS SHALL BE COVERED OR TURNED AWAY FROM THE DIRECTION OF TRAFFIC. THE TRAVEL LANE SURFACES SHALL BE RESTORED WITH STEEL PLATES OR TEMPORARY PAVEMENT. WHERE A SAW CUT OR PAVEMENT REMOVAL RESULTS IN MORE THAN A 2" DROP-OFF ADJACENT TO AN ACTIVE TRAVEL LANE, THE EDGE SHALL BE MARKED WITH VERTICAL PANELS OR CHANNELIZATION DRUMS AT 25' SPACING, AND WARNING SIGN CW 8-9a "SHOULDER DROP-OFF" SHALL BE POSTED 240' IN ADVANCE OF





STOP!

CALL BEFORE YOU DIG MISSOURI ONE CALL SYSTEM 1-800-344-7483 or 811 (@ least 72 hours prior to digging)

Z

95% REVIEW SET FOR REVIEW ONLY
Not for construction or permit purposes. **Kimley**Horn | Engineer | KEVIN S. GASKEY | P.E. No. | 28441 | Date | MAY 2019 |

SHEET C-16