

Stormwater Management Plan

Streets of West Pryor
Lee's Summit, MO

April 23, 2020
Revised July 9, 2020

Prepared By:

SM Engineering
5507 High Meadow Circle
Manhattan, KS 66503



Samuel D. Malinowsky, P.E.

Table of Contents

1. Introduction.....	3
2. Drainage Analysis.....	4
3. Proposed Drainage Plan.....	5
4. Stormwater Treatment.....	5
5. Conclusion.....	6

Appendix A – Construction Plans

Appendix B – Hydrology Studio Printouts

INTRODUCTION

This Stormwater report has been prepared to address the proposed revisions to the outlet structure and overflow weir related to the existing south detention/retention pond in the Streets of West Pryor commercial development. The location of the site is shown in Figure 1 below. Figure 2 depicts the actual location of the pond as illustrated in the Mass Grading & Storm Sewer Improvements for Streets Of West Pryor construction plans.




Figure 1: Site Location Map




Figure 2: Pond Location

The purpose of the study is to analyze the effects of raising the permanent pool elevation in the pond to elevation 970.50. This will necessitate revising the primary outlet structure and raising the elevation of the emergency spillway in order to be 0.5 feet above the 100 yr WSE as required by the City of Lee's Summit storm drainage criteria.

DRAINAGE ANALYSIS METHODS AND CALCULATIONS

The drainage analysis was prepared using Hydrology Studio software to analyze the revised outlet structure. (the Hydrology Studio report pages are included in the appendix). This pond was originally analyzed and designed based on the "Final Stormwater Report for Streets of West Pryor" prepared by Kaw Valley Engineering (KVE) in January of 2016. The rainfall input perimeters we used closely matched those shown in the KVE report as evidenced by the peak flows for the existing conditions listed below.

Pre-developed Release Rates

Storm	KVE Rate	SME Rate
2 yr	41 cfs	41.35 cfs
10 yr	80 cfs	80.23 cfs
100 yr	161 cfs	160.8cfs

The SCS method for determining runoff was used per APWA Section 5600, Storm Drainage Systems and Facilities – Kansas Metropolitan Chapter.

PROPOSED PLAN

Currently the primary outlet for the pond is a 5'x5' riser with a grate inlet. The riser has a 36" x 18" opening at elevation 970', 3-8" orifices at elevation 968 and one 2.5" orifice at elevation 966. The proposed plan is to raise the permanent pool elevation to 970.5'. In order to achieve this there will be plans showing to modify the 36" x 18" opening to be 6" x 12" and to close off all the orifices. The 6' x 12" opening will have an opening elevation of 970.5 to establish the permanent pool. The outside walls of the primary outlet structure will also be raised to an elevation 973.90 feet from the constructed elevation of 973.00 feet. In order to maintain the 6" freeboard above the new 100 yr water surface elevation of 974.98, the emergency overflow will be regraded to provide for a new emergency overflow elevation of 975.5. As part of that construction the existing concrete walking trail will also be reconstructed. This results in raising the emergency overflow from 973.50' to 975.50'.

PROPOSED DRAINAGE PLAN

As discussed above we have closely matched the KVE reports input data and reran the hydrology using the revised outlet structure. The plan sheet for the pond revisions is included in the appendix.

As shown below the total release rate, from the combination of the undetained runoff and the runoff routed through the pond, is less than or slightly greater than what is allowed per APWA. The only rain event that is over the allowed is the 100 yr outflow and it is within 2.3% of what is allowed. Considering the evaporation rate for the pond and the inconsistency of rainfall events this overage will not affect the functionality of the pond. Also included in the chart are the values for the undetained runoff from the KVE report. The Hydrology Studio printouts are included in the appendix.

Summary of Discharge Rates

Storm	KVE Undetained	SME Undetained	Combined release rate (undetained + pond) South Outflow	Allowable Release Rate
2 yr	9.70 cfs	9.61 cfs	11.87 cfs	12 cfs
10 yr	14.80 cfs	14.66 cfs	17.95 cfs	48 cfs
100 yr	24.56 cfs	24.33 cfs	73.65	72 cfs

STORMWATER TREATMENT

Per APWA the pond is required to provide 40-hour extended detention of the runoff from the runoff of the 90% mean annual event. The water quality volume for this drainage area is 32,770 cubic feet as calculated in the KVE report. As shown on the Stage-Storage Summary the water quality volume is realized at approximately stage 1.3 ft. Comparing that to the Pond Drain Time in the report this equates to 42 hour drain time, which exceeds the 40 hr required.

EXISTING POND INFLOW

The existing 54" pipe draining into the pond has an outflow of 966', which corresponds to the existing permanent pool elevation. Upon completion of the improvements this pipe will be partially submerged with the new permanent pool elevation being at 970.5. In order to understand how the existing pipe network will operate under the new conditions we ran the pipe network for the 100 year storm, assuming a tail water of 975.3. This corresponds to the elevation just prior to overtopping the emergency spillway. The pipe profiles showing the hydraulic grade line and the energy grade line are included in Appendix B. As seen on these profiles the energy grade line is never above ground thus at all time, during the 100 year storm event, the storm water is contained within the pipe.

CONCLUSION

As shown above if constructed as proposed the pond improvements will result in a higher permanent pool elevation while maintaining operational characteristics as originally designed. If constructed as proposed there will be no increase in the potential for downstream flooding.

Appendix A

- Construction Plans

STREETS OF WEST PRYOR

FOR

SOUTH POND IMPROVEMENTS

LEE'S SUMMIT, MO

UTILITIES
Electric Service
Evergy
Nathan Michael
913-347-4310
Nathan.michael@evergy.com

Gas Service
Spire
Katie Darnell
816-969-2247
Katie.darnell@spireenergy.com


Water/Sanitary Sewer
Water Utilities Department
1200 SE Hamblen Road
Lee's Summit, Mo 64081
Jeff Thorn
816-969-1900
jeff.thorn@cityofls.net

Communication Service
AT&T Carrie Cilke
816-703-4386
cc3527@att.com

Time Warner Cable
Steve Baxter
913-643-1928
steve.baxter@charter.com

Comcast
Ryan Alkire
816-795-2218
ryan.alkire@cable.comcast.com

Google Fiber
Becky Davis
913-725-8745
rebeccadavis@google.com



LOCATION MAP

UTILITY STATEMENT:
THE UNDERGROUND UTILITIES SHOWN HEREON ARE FROM FIELD SURVEY INFORMATION OF ONE-CALL LOCATED UTILITIES, FIELD SURVEY INFORMATION OF ABOVE GROUND OBSERVABLE EVIDENCE, AND/OR THE SCALING AND PLOTTING OF EXISTING UTILITY MAPS AND DRAWINGS AVAILABLE TO THE SURVEYOR AT THE TIME OF SURVEY. THE SURVEYOR MAKES NO GUARANTEE THAT THE UNDERGROUND UTILITIES SHOWN COMPRISE ALL SUCH UTILITIES IN THE AREA, EITHER IN SERVICE OR ABANDONED. FURTHERMORE, THE SURVEYOR DOES NOT WARRANT THAT THE UNDERGROUND UTILITIES SHOWN ARE IN THE EXACT LOCATION INDICATED ALTHOUGH HE DOES CERTIFY THAT THEY ARE LOCATED AS ACCURATELY AS POSSIBLE FROM INFORMATION AVAILABLE. THE SURVEYOR HAS NOT PHYSICALLY LOCATED THE UNDERGROUND UTILITIES BY EXCAVATION UNLESS OTHERWISE NOTED ON THIS SURVEY.
SAFETY NOTICE TO CONTRACTOR
IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICE, THE CONTRACTOR WILL BE SOLELY AND COMPLETELY RESPONSIBLE FOR CONDITIONS OF THE JOB SITE, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY DURING PERFORMANCE OF THE WORK. THIS REQUIREMENT WILL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS.

WARRANTY/DISCLAIMER
THE DESIGNS REPRESENTED IN THESE PLANS ARE IN ACCORDANCE WITH ESTABLISHED PRACTICES OF CIVIL ENGINEERING FOR THE DESIGN FUNCTIONS AND USES INTENEDED BY THE OWNER AT THIS TIME. HOWEVER, NEITHER SM ENGINEERING NOR ITS PERSONNEL CAN OR DO WARRANTY THESE DESIGNS OR PLANS AS CONSTRUCTED, EXCEPT IN THE SPECIFIC CASES WHERE SM ENGINEERING PERSONNEL INSPECT AND CONTROL THE PHYSICAL CONSTRUCTION ON A CONTEMPORARY BASIS AT THE SITE.

CAUTION- NOTICE TO CONTRACTOR
THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND, WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL THE APPROPRIATE UTILITY COMPANY AT LEAST 72 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATION OF UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH PROPOSED IMPROVEMENTS SHOWN ON THE PLANS. THE CONTRACTOR SHALL EXPOSE EXISTING UTILITIES AT LOCATIONS OF POSSIBLE CONFLICTS PRIOR TO ANY CONSTRUCTION.

ALL EXISTING TOPOGRAPHIC DATA AND INFRASTRUCTURE IMPROVEMENTS SHOWN BASED ON INFORMATION BY KAW VALLEY ENGINEERING

BENCHMARKS:
#1 CHISELED "SQUARE" ON TOP OF CURB POINT OF INTERSECTION OF WEST PARK PARKING LOT AT EAST DRIVE ENTRANCE
ELEVATION 985.05

#2 CHISELED "SQUARE" ON NORTHWEST CORNER AREA INLET, 25' EAST OF CURB LINE AND ON-LINE WITH SOUTH CURB OF LOWENSTEIN DRIVE AT 90° BEND IN ROAD
ELEVATION 971.06

INDEX OF SHEETS

- C-1 COVER SHEET
- C-2 POND IMPROVEMENTS
- F1.00-F6.00 FOUNTAIN AND WATERFALL IMPROVEMENTS
- E1 FOUNTAIN CONTROL PANEL

DEVELOPER

SWP III, LLC
C/O DRAKE DEVELOPMENT, LLC
7200 W 132nd ST, SUITE 150
OVERLAND PARK, KS 66213
913-662-2630

ENGINEER

SM ENGINEERING
SAM MALINOWSKY
5507 HIGH MEADOW CIRCLE
MANHATTAN KANSAS, 66503
SMCIVILENGR@GMAIL.COM
785.341.9747



SAMUEL D. MALINOWSKY
PROFESSIONAL ENGINEER



SM Engineering
5507 High Meadow Circle
Manhattan Kansas, 66503
smcivilengr@gmail.com
785.341.9747

Drawings and/or Specifications are original proprietary work and property of the Engineer and intended specifically for this project. Use of items contained herein without consent of the Engineer is prohibited. Drawings illustrate best information available to the Engineer. Field verification of actual elements, conditions, and dimensions is required.



Revisions
5-7-20 REVISED FOUNTAIN
5-11-20 SPILLWAY
7-9-20 SPILLWAY

STREETS OF WEST PRYOR
LEE'S SUMMIT, MISSOURI

s h e e t
C1.0
Civil
COVER SHEET
permit
11 MAY 2020



PLACE 2 COURSES ON SPLIT FACE BLOCK ON ALL 4 SIDES OF EXISTING STRUCTURE. ADJUST MORTAR JOINT AS REQUIRED TO ACHIEVE TOP ELEVATION. BLOCK TO BE INTEGRALLY COLORED, WITH COLOR SELECTED BY OWNER. #4 REBAR VERTICAL IN EACH CELL GROUTED FULL. REBAR SHALL BE IMBEDDED INTO EXISTING STRUCTURE A MINIMUM OF 4" WITH EPOXY. TOP COUSE SHALL BE BOND BEAM SHAPE. GROUT SOLID WITH CEMENT WASH ON TOP. MORTAR COLOR TO MATCH CMU.



PROPOSED OVERFLOW (SOUTH BASIN)

SM Engineering
SME
5507 High Meadow Circle
Manhattan Kansas, 66503
smcivilengr@gmail.com
785.341.9747

Drawings and/or Specifications are original proprietary work and property of the Engineer and intended specifically for this project. Use of items contained herein without consent of the Engineer is prohibited. Drawings illustrate best information available to the Engineer. Field verification of actual elements, conditions, and dimensions is required.

Revisions
5-7-20 REVISED FOUNTAIN
5-11-20 SPILLWAY
7-9-20 SPILLWAY

STREETS OF WEST PRYOR
LEE'S SUMMIT, MISSOURI

sheet
C2.0
Civil
POND IMPROVEMENTS
permit
11 MAY 2020

Appendix B


- Hydrology Studios Printout

Basin Model

Hydrology Studio v 3.0.0.14

Project Name: SOWP South Pond

07-09-2020



Hydrograph by Return Period

Project Name: SOWP South Pond

Hydrology Studio v 3.0.0.14

07-09-2020

[illegible]

Hydrograph 2-yr Summary

Project Name: SOWP South Pond

Hydrology Studio v 3.0.0.14

07-09-2020

[illegible]

Hydrograph Report

Project Name: SOWP South Pond


Hydrology Studio v 3.0.0.14

07-09-2020

Pre Developed

Hyd. No. 1

Hydrograph Type	= NRCS Runoff	Peak Flow	= 41.35 cfs
Storm Frequency	= 2-yr	Time to Peak	= 12.08 hrs
Time Interval	= 1 min	Runoff Volume	= 131,134 cuft
Drainage Area	= 24.0 ac	Curve Number	= 77
Tc Method	= User	Time of Conc. (Tc)	= 20.0 min
Total Rainfall	= 3.60 in	Design Storm	= Type II
Storm Duration	= 24 hrs	Shape Factor	= 484



Hydrograph Report

Project Name: SOWP South Pond


Hydrology Studio v 3.0.0.14

07-09-2020

Post To Pond

Hyd. No. 2

Hydrograph Type	= NRCS Runoff	Peak Flow	= 48.05 cfs
Storm Frequency	= 2-yr	Time to Peak	= 11.98 hrs
Time Interval	= 1 min	Runoff Volume	= 117,121 cuft
Drainage Area	= 11.0 ac	Curve Number	= 94
Tc Method	= User	Time of Conc. (Tc)	= 10.0 min
Total Rainfall	= 3.60 in	Design Storm	= Type II
Storm Duration	= 24 hrs	Shape Factor	= 484



Hydrograph Report

Project Name: SOWP South Pond


Hydrology Studio v 3.0.0.14

07-09-2020

Post Undetained

Hyd. No. 3

Hydrograph Type	= NRCS Runoff	Peak Flow	= 9.610 cfs
Storm Frequency	= 2-yr	Time to Peak	= 11.98 hrs
Time Interval	= 1 min	Runoff Volume	= 23,424 cuft
Drainage Area	= 2.2 ac	Curve Number	= 94
Tc Method	= User	Time of Conc. (Tc)	= 10.0 min
Total Rainfall	= 3.60 in	Design Storm	= Type II
Storm Duration	= 24 hrs	Shape Factor	= 484



Hydrograph Report

Project Name: SOWP South Pond

Hydrology Studio v 3.0.0.14

07-09-2020

South Pond


Hyd. No. 4

Hydrograph Type	= Pond Route	Peak Flow	= 3.072 cfs
Storm Frequency	= 2-yr	Time to Peak	= 12.75 hrs
Time Interval	= 1 min	Hydrograph Volume	= 102,963 cuft
Inflow Hydrograph	= 2 - To Pond	Max. Elevation	= 972.63 ft
Pond Name	= South Pond	Max. Storage	= 72,018 cuft

Pond Routing by Storage Indication Method

Center of mass detention time = 5.78 hrs

Qp = 3.07 cfs



Pond Report


Project Name: SOWP South Pond

Hydrology Studio v 3.0.0.14

07-09-2020

South Pond

Stage-Storage

[illegible]

Pond Report

Project Name: SOWP South Pond

Hydrology Studio v 3.0.0.14


07-09-2020

South Pond

Stage-Discharge

Culvert / Orifices	Culvert	Orifices			Orifice Plate
		1*	2	3	
Rise, in	36	12			Orifice Dia, in
Span, in	36	6			No. Orifices
No. Barrels	1	1			Invert Elevation, ft
Invert Elevation, ft	960.00	970.50			Height, ft
Orifice Coefficient, Co	0.60	0.60			Orifice Coefficient, Co
Length, ft	50				
Barrel Slope, %	.01				
N-Value, n	0.013				
Weirs	Riser*	Weirs			Ancillary
		1	2	3	
Shape / Type	Box				Exfiltration, in/hr
Crest Elevation, ft	973.9				
Crest Length, ft	20				
Angle, deg					
Weir Coefficient, Cw	3.3				

*Routes through Culvert.



Pond Report

Project Name: SOWP South Pond

Hydrology Studio v 3.0.0.14

07-09-2020

South Pond


Stage-Storage-Discharge Summary

[illegible]

Suffix key: ic = inlet control, oc = outlet control, s = submerged weir

South Pond

Pond Drawdown



Hydrograph Report

Project Name: SOWP South Pond


Hydrology Studio v 3.0.0.14

07-09-2020

South Outflow

Hyd. No. 5

Hydrograph Type	= Junction	Peak Flow	= 11.87 cfs
Storm Frequency	= 2-yr	Time to Peak	= 11.98 hrs
Time Interval	= 1 min	Hydrograph Volume	= 126,388 cuft
Inflow Hydrographs	= 3, 4	Total Contrib. Area	= 2.2 ac



Hydrograph 10-yr Summary

Project Name: SOWP South Pond

Hydrology Studio v 3.0.0.14

07-09-2020

Hyd. No.	Hydrograph Type	Hydrograph Name	Peak Flow (cfs)	Time to Peak (hrs)	Hydrograph Volume (cuft)	Inflow Hyd(s)	Maximum Elevation (ft)	Maximum Storage (cuft)
1	NRCS Runoff	Pre Developed	80.23	12.08	250,547	----		
2	NRCS Runoff	Post To Pond	73.31	11.98	183,844	----		
3	NRCS Runoff	Post Undetained	14.66	11.98	36,769	----		
4	Pond Route	South Pond	4.839	12.68	169,383	2	973.93	113,162
5	Junction	South Outflow	17.95	11.98	206,152	3, 4		

Hydrograph Report

Project Name: SOWP South Pond


Hydrology Studio v 3.0.0.14

07-09-2020

Pre Developed

Hyd. No. 1

Hydrograph Type	= NRCS Runoff	Peak Flow	= 80.23 cfs
Storm Frequency	= 10-yr	Time to Peak	= 12.08 hrs
Time Interval	= 1 min	Runoff Volume	= 250,547 cuft
Drainage Area	= 24.0 ac	Curve Number	= 77
Tc Method	= User	Time of Conc. (Tc)	= 20.0 min
Total Rainfall	= 5.30 in	Design Storm	= Type II
Storm Duration	= 24 hrs	Shape Factor	= 484



Hydrograph Report

Project Name: SOWP South Pond


Hydrology Studio v 3.0.0.14

07-09-2020

Post To Pond

Hyd. No. 2

Hydrograph Type	= NRCS Runoff	Peak Flow	= 73.31 cfs
Storm Frequency	= 10-yr	Time to Peak	= 11.98 hrs
Time Interval	= 1 min	Runoff Volume	= 183,844 cuft
Drainage Area	= 11.0 ac	Curve Number	= 94
Tc Method	= User	Time of Conc. (Tc)	= 10.0 min
Total Rainfall	= 5.30 in	Design Storm	= Type II
Storm Duration	= 24 hrs	Shape Factor	= 484



Hydrograph Report

Project Name: SOWP South Pond


Hydrology Studio v 3.0.0.14

07-09-2020

Post Undetained

Hyd. No. 3

Hydrograph Type	= NRCS Runoff	Peak Flow	= 14.66 cfs
Storm Frequency	= 10-yr	Time to Peak	= 11.98 hrs
Time Interval	= 1 min	Runoff Volume	= 36,769 cuft
Drainage Area	= 2.2 ac	Curve Number	= 94
Tc Method	= User	Time of Conc. (Tc)	= 10.0 min
Total Rainfall	= 5.30 in	Design Storm	= Type II
Storm Duration	= 24 hrs	Shape Factor	= 484



Hydrograph Report

Project Name: SOWP South Pond


Hydrology Studio v 3.0.0.14

07-09-2020

South Pond

Hyd. No. 4

Hydrograph Type	= Pond Route	Peak Flow	= 4.839 cfs
Storm Frequency	= 10-yr	Time to Peak	= 12.68 hrs
Time Interval	= 1 min	Hydrograph Volume	= 169,383 cuft
Inflow Hydrograph	= 2 - To Pond	Max. Elevation	= 973.93 ft
Pond Name	= South Pond	Max. Storage	= 113,162 cuft



Hydrograph Report

Project Name: SOWP South Pond


Hydrology Studio v 3.0.0.14

07-09-2020

South Outflow

Hyd. No. 5

Hydrograph Type	= Junction	Peak Flow	= 17.95 cfs
Storm Frequency	= 10-yr	Time to Peak	= 11.98 hrs
Time Interval	= 1 min	Hydrograph Volume	= 206,152 cuft
Inflow Hydrographs	= 3, 4	Total Contrib. Area	= 2.2 ac



Hydrograph 100-yr Summary

Project Name: SOWP South Pond

Hydrology Studio v 3.0.0.14

07-09-2020

Hyd. No.	Hydrograph Type	Hydrograph Name	Peak Flow (cfs)	Time to Peak (hrs)	Hydrograph Volume (cuft)	Inflow Hyd(s)	Maximum Elevation (ft)	Maximum Storage (cuft)
1	NRCS Runoff	Pre Developed	160.8	12.08	507,689	----		
2	NRCS Runoff	Post To Pond	121.7	11.98	314,599	----		
3	NRCS Runoff	Post Undetained	24.33	11.98	62,920	----		
4	Pond Route	South Pond	60.36	12.10	300,920	2	974.98	149,014
5	Junction	South Outflow	73.65	12.08	363,839	3, 4		

Hydrograph Report

Project Name: SOWP South Pond


Hydrology Studio v 3.0.0.14

07-09-2020

Pre Developed

Hyd. No. 1

Hydrograph Type	= NRCS Runoff	Peak Flow	= 160.8 cfs
Storm Frequency	= 100-yr	Time to Peak	= 12.08 hrs
Time Interval	= 1 min	Runoff Volume	= 507,689 cuft
Drainage Area	= 24.0 ac	Curve Number	= 77
Tc Method	= User	Time of Conc. (Tc)	= 20.0 min
Total Rainfall	= 8.60 in	Design Storm	= Type II
Storm Duration	= 24 hrs	Shape Factor	= 484



Hydrograph Report

Project Name: SOWP South Pond


Hydrology Studio v 3.0.0.14

07-09-2020

Post To Pond

Hyd. No. 2

Hydrograph Type	= NRCS Runoff	Peak Flow	= 121.7 cfs
Storm Frequency	= 100-yr	Time to Peak	= 11.98 hrs
Time Interval	= 1 min	Runoff Volume	= 314,599 cuft
Drainage Area	= 11.0 ac	Curve Number	= 94
Tc Method	= User	Time of Conc. (Tc)	= 10.0 min
Total Rainfall	= 8.60 in	Design Storm	= Type II
Storm Duration	= 24 hrs	Shape Factor	= 484



Hydrograph Report

Project Name: SOWP South Pond


Hydrology Studio v 3.0.0.14

07-09-2020

Post Undetained

Hyd. No. 3

Hydrograph Type	= NRCS Runoff	Peak Flow	= 24.33 cfs
Storm Frequency	= 100-yr	Time to Peak	= 11.98 hrs
Time Interval	= 1 min	Runoff Volume	= 62,920 cuft
Drainage Area	= 2.2 ac	Curve Number	= 94
Tc Method	= User	Time of Conc. (Tc)	= 10.0 min
Total Rainfall	= 8.60 in	Design Storm	= Type II
Storm Duration	= 24 hrs	Shape Factor	= 484



Hydrograph Report

Project Name: SOWP South Pond

Hydrology Studio v 3.0.0.14

07-09-2020

South Pond


Hyd. No. 4

Hydrograph Type	= Pond Route	Peak Flow	= 60.36 cfs
Storm Frequency	= 100-yr	Time to Peak	= 12.10 hrs
Time Interval	= 1 min	Hydrograph Volume	= 300,920 cuft
Inflow Hydrograph	= 2 - To Pond	Max. Elevation	= 974.98 ft
Pond Name	= South Pond	Max. Storage	= 149,014 cuft

Pond Routing by Storage Indication Method

Center of mass detention time = 3.64 hrs

Qp = 60.36 cfs



Hydrograph Report

Project Name: SOWP South Pond

Hydrology Studio v 3.0.0.14

07-09-2020

South Outflow

Hyd. No. 5

