

PROPOSED INLET PROTECTION
VEHICLE TRACKING CONTROL, INSTALLED PER APWA STANDARD DETAIL ESC-20

RICHARD DALE
CANNY &
LINDA SUE -
TRUSTEES
DOC. NO. 2011E096894
ZONED AGRICULTURE
1700 SW HOOK
ROAD

ROBERT D.
GARDNER & WIFE
BOOK 1723,
PAGE 1934
ZONED AGRICULTURE
1628 SW HOOK
ROAD

FLOYD W. &
SHARRE A.
ESKINA
BOOK 12334,
PAGE 922
ZONED AGRICULTURE
1622 SW HOOK
ROAD

TOM RAINY ACRES
DOC. NO. 20040010488
(SUBDIVISION)
WILLIAM H. & JEAN M.
BARNARD
ZONED AGRICULTURE
1516 SW HOOK
ROAD

EROSION CONTROL PLAN - CONSTRUCTION
1. CONTRACT TO INSTALL 12" FENCE PER
APWA STANDARD DETAIL ESC-10-11, REMOVE
AND RELOCATE AS NECESSARY FOR
CONSTRUCTION.
2. APPROXIMATE LOCATION OF VEHICLE
TRACKING CONTROL, CONTRACTOR TO
INSTALL PER APWA STANDARD DETAIL
PAGE 547
NEEDED FOR CONSTRUCTION.
3. CONTRACTOR TO PROVIDE INLET
PROTECTION PER APWA STANDARD DETAILS,
1508 SW HOOK

NOTE:
EROSION CONTROL FEATURES NEED TO BE INSTALLED PRIOR TO LAND DISTURBANCE AND
SHALL BE MAINTAINED THROUGHOUT CONSTRUCTION. EROSION CONTROL FEATURES NOT INCLUDED IN
THIS PLAN MAY INCLUDE ADDITIONAL EROSION CONTROL FEATURES NOT INCLUDED IN
THIS PLAN. THE LOCATION OF THE EROSION CONTROL FEATURES SHALL BE DETERMINED BY THE
ENGINEER. EROSION CONTROL MEASURES IN PLACE SHALL BE CHECKED & MAINTAINED
IN 24 HOURS AS RECORDED AT EACH MEETING.

PROJECT NO. 1200484.11
SHEET 6


WHISPERING WOODS 2ND PLAT
STREET & STORM SEWER PLANS

EROSION CONTROL PLAN

LEE'S SUMMIT, MO

SNYDER & ASSOCIATES
ENGINEERS & PLANNERS, INC.
www.snyder-associates.com

802 FRANCIS STREET
ST. JOSEPH, MO 64501
816-364-5222



| MARK | REVISION | DATE | BY |
|---|----------------|----------------|----|
| Engineer: SD | Checked By: SD | Scale: 1"= 50' | |
| Technician: JS | Date: 7-28-20 | Field Bk: Pg: | |
| Snyder & Associates Engineers & Planners, Inc. Missouri State Certificate of Authority #2008005544 | | Sheet 6 | |