



**HIGHLAND MEADOWS
5TH PLAT
3/4/2021**

**SANITARY SEWER
ENGINEERS OPINION OF PROBABLE COSTS**

NO.	ITEM	UNIT	UNIT QUANTITY	UNIT PRICE (\$)	UNIT TOTAL
9.0	SANITARY SEWER				
9.01	CONNECT TO EX. MANHOLE	EA	2.0	\$1,000.00	\$2,000.00
9.02	8" PVC SEWER MAIN	LF	1,576.2	\$60.00	\$94,572.00
9.03	4" PVC LATERAL	LF	1,075.0	\$22.00	\$23,650.00
9.04	SEWER SERVICE WYE CONNECTION TO MAIN	EA	25.0	\$25.00	\$625.00
9.05	TRENCH CHECKS	EA	25.0	\$10.00	\$250.00
9.06	TRACER WIRE	LF	1,075.0	\$2.00	\$2,150.00
9.07	4' DIA. MANHOLE	EA	8	\$3,800.00	\$30,400.00
9.08	4' DIA. SHALLOW MANHOLE	EA	1	\$3,000.00	\$3,000.00
SANITARY SEWER SUB-TOTAL					\$156,647.00
ESTIMATE DOES NOT INCLUDE: LANDSCAPING, ROCK EXCAVATION, IRRIGATION, UTILITY(GAS, COMM, ELEC) FEES				SUB-TOTAL \$	156,647
				5% CONTINGENCY \$	7,832
				TOTAL \$	164,479

