

MEMORADUM

TO:

City of Lee's Summit Engineering Department

FROM:

Ronald L. Cowger, PE (AGC Engineers, Inc)

RE:

Stormwater Detention Memo

Lot 4, Oakview

Lee's Summit, Missouri

DATE:

April 5, 2021

This memorandum is to compare the previously approved Final Stormwater Management Plan prepared by Schlagel & Associates, PA (dated July 20, 2018) to the proposed site development plan for Lot 4, Oakview.

The majority of Lot 4, Oakview drains to the Southwest [underground] Detention Basin while the NW corner of Lot 4 drains to the northwest. The proposed Lot 4 improvements are generally consistent with the originally proposed improvements with overall curve numbers less than 2% difference from the previously approved Final Stormwater Management Plan (STUDY). The Lot 4 CN is 93.5 while the STUDY used a CN of 92 globally for the entire 3.06-acre watershed. This minor increase in CN is offset by the time of concentration increase from that used in the STUDY; thereby, decreasing the peak runoff. The STUDY utilitzed a Tc equal to 5 minutes, the master development construction plans prepared by Schlagel & Associates used 5.9 minutes for the enclosed pipe system. We estimate a Tc equal to 7 minutes to the Southwest Detention Basin

Comparison runoff calculations (based on the entire 3.06-acre drainage area):

STUDY

Tc = 5 min --> I = 10.3 CN 92 $Q_{100} = 32.18$ cfs

Tc based on Schlagel Storm Pipe Calculations

Tc = 5.9 min --> I = 10.0 CN 93.5 $Q_{100} = 32.52$ cfs

Proposed Lot 4, Oakview

Tc = 7 min --> I = 9.6 CN 93.5 $Q_{100} = 31.05$ cfs (less than the STUDY)

Please advised if you have any questions or comments regarding the above responses.

