

ENGINEERING COST ESTIMATE

ENGINEERING SOLUTIONS

50 SE 30TH STREET
LEE'S SUMMIT, MO

DATE:
4/20/2021

PROJECT NAME:

PARK RIDGE 8TH PLAT - Public Sanitary

APPLICATION # PL2021100

SITE LOCATION:

NE Longhill Rd
Lee's Summit, MO

ITEM AND DESCRIPTION	UNIT	ESTIMATED QUANTITY	LABOR AND MATERIAL COST PER UNIT	COST PER ITEM
SANITARY				
4" PVC SDR 26 Service Line	LF	671.53	\$ 23.60	\$ 15,848.11
8" PVC SDR 26	LF	706.17	\$ 32.00	\$ 22,597.44
4' DIA Manhole	EA	3.00	\$ 4,000.00	\$ 12,000.00
TEES, BENDS, WYES	LS	19.00	\$ 500.00	\$ 9,500.00
CONNECTION TO EXISTING SANITARY SEWER	LS	1.00	\$ 500.00	\$ 500.00
TRACER WIRE AND EQUIPMENT	L.F.	706.17	\$ 1.00	\$ 706.17
TOTAL COST = \$				59,945.55