

USER: bworthley

DWG: F:\2019\4001-4500\019-4059-A\40-Design\AutoCAD\Final Plans\Sheets\GNCV\Site Grading & Site Disturbance Plans\C_TTL01_A194059.dwg
DATE: May 05, 2021 4:13pm
XREFS: C_PTBK_A194059
C_PBNY_A194059

GENERAL NOTES

- 1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ENSURING THAT THE PLANS IN THEIR POSSESSION ARE THE MOST CURRENT VERSION ISSUED, ARE FULLY COORDINATED WITH ALL SUBCONTRACTORS, AND PRESENT ON SITE AT ALL TIMES. CURRENT PLANS PREPARED BY OLSSON MAY BE OBTAINED AT THE DIRECTION OF OLSSON'S CLIENT. DIRECT REQUESTS TO OLSSON MAY REQUIRE ADDITIONAL AUTHORIZATIONS, AGREEMENTS, AND/OR FEES. PLEASE CONTACT THE ENGINEER FOR INFORMATION.
2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DEVIATIONS FROM THESE PLANS UNLESS WRITTEN APPROVAL FROM ENGINEER, OWNER, AND DEVELOPER.
3. ALL WORK AND MATERIALS SHALL BE SUBJECT TO INSPECTION AND APPROVAL BY THE OWNER OR THE OWNER'S REPRESENTATIVE.
4. ALL ESTIMATES OF QUANTITIES ARE FOR INFORMATIONAL PURPOSES ONLY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING QUANTITIES AND ITEMS OF WORK.
5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ALL LABOR, MATERIALS, AND EQUIPMENT REQUIRED TO COMPLETE THE WORK SHOWN IN THE PLANS.
6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL REQUIRED PERMITS, PAYING ALL FEES, AND FOR OTHERWISE COMPLYING WITH ALL APPLICABLE REGULATIONS GOVERNING THE WORK.
7. THE CONTRACTOR SHALL NOT ENGAGE IN ACTIVITIES THAT MAY ENCROACH ON WATERS OF THE U.S., INCLUDING WETLANDS, UNTIL ANY NECESSARY PERMITS MAY BE OBTAINED. THE CONTRACTOR SHALL REVIEW AND COMPLY WITH ALL CONDITIONS DESCRIBED IN THE PERMIT.
8. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR CONDITIONS OF THE JOB SITE, THE SAFETY OF ALL PERSONS INCLUDING VISITORS AND THE GENERAL PUBLIC, AND PROPERTY DURING PERFORMANCE OF THE WORK. THIS REQUIREMENT WILL APPLY CONTINUOUSLY THROUGHOUT THE PROJECT AND NOT BE LIMITED BY WORKING HOURS. ANY CONSTRUCTION OBSERVATION BY THE ENGINEER OF THE CONTRACTOR'S PERFORMANCE IS NOT INTENDED TO INCLUDE REVIEW OF THE ADEQUACY OF THE CONTRACTOR'S SAFETY MEASURES.
9. PRIOR TO COMMENCEMENT OF WORK THE CONTRACTOR SHALL NOTIFY AND COORDINATE WITH ALL UTILITY COMPANIES AND OBTAIN ANY RELEVANT INFORMATION. NOTIFY ENGINEER OF ANY DISCREPANCIES.
10. THE CONTRACTOR IS RESPONSIBLE FOR THE PROTECTION OF ALL BOUNDARY CORNERS AND SECTION CORNERS. ANY BOUNDARY CORNER AND/OR SECTION CORNER DISTURBED OR DAMAGED BY CONSTRUCTION ACTIVITIES SHALL BE RESET BY A LAND SURVEYOR LICENSED IN THE STATE OF MISSOURI, AT THE CONTRACTOR'S EXPENSE.
11. THE CONTRACTOR IS RESPONSIBLE FOR THE PROTECTION OF ADJACENT PROPERTIES AND SHALL TAKE ALL PRECAUTIONS NECESSARY TO PREVENT DAMAGE DURING CONSTRUCTION. THE CONTRACTOR IS ALSO RESPONSIBLE FOR REPAIRING ANY DAMAGE RESULTING FROM CONSTRUCTION ACTIVITIES.
12. PRIOR TO MOVING OFF THE JOB THE CONTRACTOR SHALL NOTIFY THE OWNER AND ENGINEER TO PERFORM A FINAL WALK-THROUGH OF THE CONSTRUCTION SITE.

REFERENCES

- 1. UNLESS EXPLICITLY DESCRIBED OTHERWISE WITHIN THESE PLANS THE FOLLOWING SHALL APPLY:
A. ALL CONSTRUCTION, INCLUDING THOSE LISTED BELOW, SHALL CONFORM TO THE LATEST CODES AND ORDINANCES OF LEE'S SUMMIT, MISSOURI.
B. ALL CONSTRUCTION IN MODOT RIGHT-OF-WAY SHALL CONFORM TO THE LATEST SPECIFICATIONS ADOPTED BY U.S. DEPARTMENT OF TRANSPORTATION AND MODOT.
C. ALL TRAFFIC CONTROL SIGNAGE SHALL CONFORM WITH THE CURRENT EDITION OF THE MANUAL FOR UNIFORM TRAFFIC CONTROL DEVICES (MUTCD).
D. ALL UTILITY EXTENSIONS AND CONSTRUCTION SHALL CONFORM TO THE STANDARDS AND SPECIFICATIONS OF THE UTILITY COMPANIES..
E. ALL EXTERIOR PAVEMENT (PCC, ASPHALT, ETC.) SHALL BE IN CONFORMANCE WITH THE SPECIFICATIONS OF LEE'S SUMMIT, MISSOURI AND THE RECOMMENDATIONS OF THE GEOTECHNICAL REPORT.
4. THE CONTRACTOR IS RESPONSIBLE FOR CONTACTING THE DELIVERY MANAGER AND COORDINATING ANY MAILBOXES THAT MAY BE DISTURBED. FAILURE TO DO SO MAY SUBJECT THE CONTRACTOR TO PROSECUTION BY THE FEDERAL GOVERNMENT.

EXISTING CONDITIONS

- 1. THE CONTRACTOR SHALL VISIT THE SITE AND BECOME FAMILIAR WITH THE EXISTING CONDITIONS OF THE PROJECT AREA.
2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PERFORMING THEIR OWN INVESTIGATIONS AND MAKING THEIR OWN ASSUMPTIONS REGARDING SITE SURFACE AND SUBSURFACE CONDITIONS. THIS INCLUDES THE LOCATION AND CONSISTENCY OF ANY EXISTING ROCK LAYERS UNDERLYING THE PROJECT SITE. CONTACT THE ENGINEER REGARDING ANY DISCREPANCIES THAT MAY AFFECT THE ABILITY TO CONSTRUCT FROM THESE PLANS AS DESIGNED.
3. EXISTING CONDITIONS WERE DETERMINED THROUGH A VARIETY OF METHODS THAT MAY INCLUDE SURVEY, AERIAL IMAGERY, AVAILABLE RECORDS, GIS DATA, ETC. SUBSURFACE CONDITIONS ARE APPROXIMATE AND MAY NOT INCLUDE ALL UTILITIES AND OTHER SITE IMPROVEMENTS PRESENT ON SITE. THE CONTRACTOR SHALL MAKE EXPLORATION EXCAVATIONS AND LOCATE EXISTING UNDERGROUND UTILITIES SUFFICIENTLY AHEAD OF CONSTRUCTION TO PERMIT REVISIONS TO PLANS WHEN CONFLICTS AND DISCREPANCIES ARE FOUND.

CONSTRUCTION

- 1. THE CONTRACTOR SHALL INSTALL TRAFFIC CONTROL WHILE WORKING IN THE PUBLIC RIGHT-OF-WAY AS SHOWN IN THESE PLANS. IF PLANS ARE NOT PROVIDED, CONTRACTOR SHALL COORDINATE AND PROVIDE CONTROLS TO THE SATISFACTION OF THE RIGHT-OF-WAY OWNER.
2. THE CONTRACTOR SHALL PROTECT ALL TREES OVER 3" CALIPER FROM DAMAGE. NO TREE SHALL BE REMOVED WITHOUT PERMISSION OF THE OWNER, UNLESS SHOWN OTHERWISE ON THESE PLANS.
3. THE CONTRACTOR SHALL DISPOSE ALL WASTE MATERIAL RESULTING FROM THE PROJECT OFF-SITE AND IN STRICT CONFORMANCE WITH ALL LOCAL CODES AND ORDINANCES.
4. ALL MANHOLES, CATCH BASINS, UTILITY VALVES AND METER PITS ARE TO BE ADJUSTED OR REBUILT TO GRADE AS REQUIRED. NOT ALL ADJUSTMENTS ARE INDICATED IN THE PLANS.
5. THE CONTRACTOR SHALL STREET SWEEP OR OTHERWISE CLEAN ALL ACCESS ROUTES TO THE SITE AT CONCLUSION OF THE PROJECT.

SHOP DRAWINGS

- 1. THE CONTRACTOR SHALL SUBMIT SHOP DRAWINGS A MINIMUM OF 7 DAYS PRIOR TO THE REQUESTED DATE OF APPROVAL. ENGINEER SHALL REVIEW SHOP DRAWINGS OR SAMPLES IN CONFORMANCE WITH THE DESIGN FOR THIS PROJECT AS DESCRIBED IN THE PLANS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ERRORS OR OMISSIONS IN SHOP DRAWINGS. THE ENGINEER'S REVIEW SHALL NOT EXTEND TO MEANS OR METHODS OF CONSTRUCTION. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY VARIATION FROM THE REQUIREMENTS OF THE CONTRACT DOCUMENTS UNLESS CONTRACTOR HAS NOTIFIED ENGINEER OF EACH SUCH VARIATION AT THE TIME OF SUBMISSION, AND OBTAINED ENGINEER'S WRITTEN APPROVAL OF EACH SUCH VARIATION. PRIOR TO SUBMITTING EACH SHOP DRAWING OR SAMPLE, CONTRACTOR SHALL HAVE REVIEWED AND VERIFIED:
A. ALL FIELD MEASUREMENTS, QUANTITIES, DIMENSIONS, SPECIFIED PERFORMANCE CRITERIA, INSTALLATION REQUIREMENTS, MATERIALS, CATALOG NUMBERS AND SIMILAR INFORMATION WITH RESPECT THERETO;
B. ALL MATERIALS WITH RESPECT TO INTENDED USE, FABRICATION, SHIPPING, HANDLING, STORAGE, ASSEMBLY AND INSTALLATION PERTAINING TO THE PERFORMANCE OF THE WORK;
C. ALL INFORMATION RELATIVE TO MEANS, METHODS, TECHNIQUES, SEQUENCES AND PROCEDURES OF CONSTRUCTION AND SAFETY PRECAUTIONS AND PROGRAMS INCIDENT THERETO;
D. CONTRACTOR SHALL ALSO HAVE REVIEWED AND COORDINATED EACH SHOP DRAWING OR SAMPLE WITH OTHER SHOP DRAWINGS AND SAMPLES, AND WITH THE REQUIREMENTS OF THE WORK AND THE CONTRACT DOCUMENTS.
E. ALL SUBMITTED SHOP DRAWINGS SHALL BEAR A STAMP OR SPECIFIC WRITTEN INDICATION AND SIGNATURE THAT CONTRACTOR HAS FULLY COMPLETED THE ABOVE TASKS.
2. SHOP DRAWINGS AS DESCRIBED ABOVE ARE REQUIRED FOR, BUT NOT LIMITED TO, THE FOLLOWING:
A. ALL STORM SEWER STRUCTURES TO BE INSTALLED WITH THIS PROJECT.
B. ANY ITEMS IN THESE PLANS THAT ALLOW FOR AN 'APPROVED EQUAL' ALTERNATIVE.

GENERAL NOTES:

1. THE INTENT OF THIS LAND DISTURBANCE PLAN IS TO ASSIST THE DEVELOPER IN HIS RESPONSIBILITY TO PROVIDE ALL MATERIALS, TOOLS, EQUIPMENT AND LABOR NECESSARY TO CONTROL EROSION, SILTATION AND DISCHARGES OF SOIL MATERIAL (SEDIMENT) INTO DOWNSTREAM SYSTEMS OR RECEIVING CHANNELS. THIS SHALL BE REQUIRED DURING ALL PHASES OF CONSTRUCTION AND UNTIL SUITABLE GROUND COVER IS ESTABLISHED FOR ALL DISTURBED AREAS. IF ANY METHOD OF CONTROL FAILS, THE DEVELOPER SHALL NOTIFY THE OWNER IMMEDIATELY, SO THAT THE OWNER OR HIS AGENT CAN REVIEW THE DEVELOPER'S PROPOSED METHOD OF REPAIR.

THIS PLAN INDICATES THE CRITICAL AREA(S) OF CONCERN AND THESE AREA(S) WILL BE CONTROLLED AS A MINIMUM. THE CONTROL MAY CONSIST OF TEMPORARY CONTROL MEASURES AS SHOWN ON THE PLANS OR ORDERED BY THE OWNER DURING THE LIFE OF THE CONTRACT TO CONTROL EROSION OR WATER POLLUTION, THROUGH THE USE OF BERMS, DIKES, DAMS, SEDIMENT BASINS, FIBER MATS, NETTING, STRAW BALES, GRAVEL, MULCHES, GRASSES, SLOPE DRAINS, DIVERSION SWALES OR OTHER EROSION CONTROL DEVICES OR METHODS. THE OWNER HAS THE AUTHORITY TO LIMIT THE SURFACE AREA OF ERODIBLE EARTH MATERIAL EXPOSED BY THE CONSTRUCTION OPERATIONS AND TO DIRECT THE DEVELOPER TO PROVIDE IMMEDIATE PERMANENT OR TEMPORARY POLLUTION CONTROL MEASURES TO PREVENT CONTAMINATION OF ADJACENT STREAMS OR OTHER WATER COURSES, LAKES, PONDS, OR OTHER AREAS OF WATER IMPOUNDMENT OR CONVEYANCES.

THE TEMPORARY POLLUTION CONTROL PROVISIONS CONTAINED HEREIN SHALL BE COORDINATED WITH ANY PERMANENT EROSION CONTROL FEATURES SPECIFIED ELSEWHERE IN THE CONTRACT TO THE EXTENT PRACTICAL TO ASSURE ECONOMICAL, EFFECTIVE AND CONTINUOUS EROSION CONTROL THROUGHOUT THE CONSTRUCTION AND POST CONSTRUCTION PERIOD.

- 2. THIS SEDIMENTATION CONTROL PLAN MAKES USE OF THE FOLLOWING APPLICATIONS:
___PRESERVATION OF EXISTING VEGETATION
_X SEDIMENT BARRIERS
_X SEDIMENT TRAPS
_X INLET PROTECTION
___OUTLET PROTECTION
___SOIL RETAINING SYSTEMS
___SLOPE DRAINS
___SUBSURFACE DRAINS

PHYSICAL DESCRIPTION OF EACH SPECIFIC SEDIMENT CONTROL DEVICE TO BE UTILIZED IS CALLED OUT ON THE PLANS WITH INSTALLATION PROCEDURES, CONSTRUCTION SPECIFICATIONS AND MAINTENANCE ARRANGEMENT AS CALLED FOR ON THE DETAIL SHEET. IN ADDITION TO THE MEASURES SPECIFIED, THE FOLLOWING GENERAL PRACTICES SHALL BE ADHERED TO WHEN APPLICABLE.

A) CLEARING AND GRUBBING WITHIN 50' OF A DEFINED DRAINAGE COURSE SHOULD BE AVOIDED WHEN POSSIBLE. WHERE CHANGES TO A DEFINED DRAINAGE COURSE OCCUR, WORK SHOULD BE DELAYED UNTIL ALL MATERIALS AND EQUIPMENT NECESSARY TO PROTECT AND COMPLETE THE DRAINAGE CHANGE ARE ON SITE. CHANGES SHALL BE COMPLETED AS QUICKLY AS POSSIBLE ONCE THE WORK HAS BEEN INITIATED. THE AREA IMPACTED BY THE CONSTRUCTION ACTIVITIES SHALL BE REVEGETATED OR PROTECTED FROM EROSION AS SOON AS POSSIBLE, AREAS WITHIN 50' OF A DEFINED DRAINAGE WAYS SHOULD BE RECONTOURED AS NEEDED OR OTHERWISE PROTECTED WITHIN FIVE (5) WORKING DAYS AFTER GRADING HAS CEASED.

B) WHERE SOIL DISTURBING ACTIVITIES CEASE IN AN AREA FOR MORE THAN 14 DAYS, THE DISTURBED AREAS SHALL BE PROTECTED FROM EROSION BY STABILIZING THE AREA WITH MULCH OR OTHER SIMILARLY EFFECTIVE EROSION CONTROL MEASURES. IF THE SLOPE OF THE AREA IS GREATER THAN 3:1 OR IF THE SLOPE IS GREATER THAN 3% AND GREATER THAN 150 FEET IN LENGTH, THEN THE DISTURBED AREAS SHALL BE PROTECTED FROM EROSION BY STABILIZING THE AREA WITH MULCH OR OTHER SIMILARLY EFFECTIVE EROSION CONTROL MEASURES IF ACTIVITIES CEASE FOR MORE THAN SEVEN (7) DAYS.

C) EXISTING VEGETATION SHALL BE PRESERVED TO THE EXTENT AND WHERE PRACTICAL. IN NO CASE SHALL DISTURBED AREAS REMAIN WITHOUT VEGETATIVE GROUND COVER FOR A PERIOD IN EXCESS OF 60 DAYS.

D) ADDITIONAL SITE MANAGEMENT PRACTICES WHICH SHALL BE ADHERED TO DURING THE CONSTRUCTION PROCESS SHALL INCLUDE:

SOLID AND HAZARDOUS WASTE MANAGEMENT INCLUDING PROVIDING TRASH CONTAINERS AND REGULAR SITE CLEAN UP FOR PROPER DISPOSAL OF SOLID WASTE SUCH AS BUILDING MATERIAL, PRODUCT/MATERIAL SHIPPING WASTE, FOOD CONTAINERS AND CUPS, AND PROVIDING CONTAINERS FOR THE PROPER DISPOSAL OF WASTE PAINTS SOLVENTS, AND CLEANING COMPOUNDS.

PROVISIONS OF PORTABLE TOILETS FOR PROPER DISPOSAL OF SANITARY SEWAGE.

STORAGE OF CONSTRUCTION MATERIALS AWAY FROM DRAINAGE COURSES AND LOW AREAS.

INSTALLATION OF CONTAINMENT BERMS AND USE OF DRIP PANS AT PETROLEUM PRODUCT AND LIQUID STORAGE TANKS AND CONTAINERS.

3. ALL DISTURBED AREAS SHALL BE SEEDED, FERTILIZED AND MULCHED, OR SODDED, IN ACCORDANCE WITH THE STANDARDS AND SPECIFICATIONS ADOPTED BY THE CITY OF LEE'S SUMMIT AND GOOD ENGINEERING PRACTICES. THIS SHALL BE COMPLETED WITHIN FOURTEEN (14) DAYS AFTER COMPLETING THE WORK, IN ANY AREA. IF THIS IS OUTSIDE OF THE SEEDING PERIOD, SILT BARRIERS OR OTHER SIMILARLY EFFECTIVE MEASURES SHALL BE PROVIDED UNTIL SUCH TIME THAT THE AREAS CAN BE SEEDED.

4. THE CONSTRUCTION COVERED BY THESE PLANS SHALL CONFORM TO ALL CURRENT STANDARDS AND SPECIFICATIONS ADOPTED BY THE CITY OF LEE'S SUMMIT. THE DEVELOPER WILL BE RESPONSIBLE FOR DETERMINING ALL ADDITIONAL STANDARDS, SPECIFICATIONS OR REQUIREMENTS WHICH ARE REQUIRED BY GOVERNING AGENCIES (INCLUDING LOCAL, STATE AND FEDERAL AUTHORITIES) HAVING JURISDICTION OVER THE WORK PROPOSED BY THESE CONSTRUCTION DRAWINGS.

5. ALL EROSION CONTROL MEASURES, TEMPORARY OR PERMANENT, REQUIRE MAINTENANCE TO PRESERVE THEIR EFFECTIVENESS. ALL EROSION CONTROL DEVICES SHALL BE INSPECTED IMMEDIATELY AFTER EACH HEAVY RAINSTORM AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REQUIRED REPAIRS SHOULD BE MADE IMMEDIATELY. ALL COSTS ASSOCIATED WITH THE REPAIR WORK INCLUDING RELATED INCIDENTALS WILL BE THE DEVELOPER'S RESPONSIBILITY AND SHALL BE INCLUDED IN THE DEVELOPER'S BID FOR THE PROPOSED WORK.

6. ALL EROSION CONTROL MEASURES TO BE PER APWA KANSAS CITY METRO CHAPTER STANDARD DETAILS.

7. THE DEVELOPER MUST REMOVE AT HIS COST ANY BAD SUBSURFACE SOIL WHICH WOULD NOT BE ABLE TO SUPPORT ANY PROPOSED PUBLIC IMPROVEMENT. BACKFILL SHALL BE ACCOMPLISHED IN ACCORDANCE WITH THE CITY OF LEE'S SUMMIT DESIGN AND CONSTRUCTION MANUAL SECTIONS 2100 AND 2201 ENTITLED "GRADING AND SITE PREPARATION" AND "SUBGRADE PREPARATION".

8. THE CONTRACTOR SHALL CONTACT THE CITY'S DEVELOPMENT SERVICES ENGINEERING INSPECTORS 48 HOURS PRIOR TO ANY LAND DISTURBANCE WORK AT (816) 969-1200

9. TREE CLEARING TO HAPPEN BETWEEN NOVEMBER 1 AND MARCH 31. TREES CLEARED BETWEEN APRIL 1 AND OCTOBER 31 MUST BE TREES GREATER THAN 1,000 FEET FROM FORESTED OR WOODED AREAS OR TREES LESS THAN 3 INCHES IN DIAMETER, AT BREST HEIGHT, AND NOT MIXED WITH LARGER TREES. IF LARGER TREES NEED TO BE CLEARED, A SURVEY OF THE TREES MUST BE CONDUCTED TO MAKE SURE THERE ARE NO BAT ROOSTS IN THE TREES. TREE CLEARING TO BE CONDUCTED BY CUTTING DOWN AND MULCHING OR BY PUSHING OVER AND MULCHING. TREES SHALL NOT BE BURNED DOWN.

ESTIMATE OF QUANTITIES table with columns: ITEM NO., DESCRIPTION, UNIT, QUANTITY, AS-BUILT. Rows include PRIVATE GRADING, SITE DISTURBANCE, EXCAVATION, EMBANKMENT, CONSTRUCTION ENTRANCE, CONCRETE WASHOUT, CURB INLET PROTECTION, AREA INLET PROTECTION, SILT FENCE, DIVERSION BERM, ROCK DITCH CHECK, SEDIMENT TRAP, SEDIMENT BASIN, DISTURBED AREA, TREE CLEARING, PERMANENT SEEDING.

SUMMARY OF QUANTITIES AS INDICATED ABOVE AND ANY QUANTITIES AS SHOWN WITHIN THE PLANS HAVE BEEN PROVIDED FOR PERMITTING PURPOSES ONLY AND ARE NOT INTENDED FOR USE IN PREPARATION OF CONTRACT DOCUMENTS. QUANTITIES INTENDED FOR, BUT NOT LIMITED TO, THE PREPARATION OF PROPOSALS AND BID DOCUMENTS SHALL BE INDEPENDENTLY EVALUATED BY THE ESTIMATING PARTY BASED UPON THE CONTENTS OF THESE PLANS.

olsson logo and contact information: Olsson - Civil Engineering Missouri Certificate of Authority #001592 1301 Burlington Street North Kansas City, MO 64116 TEL 816.361.1177 FAX 816.361.1888 www.olsson.com




Table with columns: REVISIONS DESCRIPTION, DATE, REV. NO. and rows for revision tracking.


GENERAL NOTES SITE GRADING & SITE DISTURBANCE PLANS THE RETREAT AT HOOK FARMS SECOND PLAT LEE'S SUMMIT, MO 2021

drawn by: B.M.W./A.A. checked by: B.M.W. designed by: B.M.W./A.A. J.E.S. QA/QC by: J.E.S. project no.: A19-4059 date: 05-05-2021

DWG: F:\2019\4001-4500\019-4059-A\40-Design\AutoCAD\Final Plans\Sheets\GNCV\Site Grading & Site Disturbance Plans\C_GRD002_A194059.dwg
 DATE: May 05, 2021 4:17pm XREFS: C_XBASE_B194061 C_PBNDY_B194061 C_PUTIL_B194061 C_PBASE_B194061 USER: bworthley C_PTLBK_A194059

GENERAL NOTES:


- CONTRACTOR SHALL ADHERE TO THE "DESIGN AND CONSTRUCTION MANUAL" SECTION 2100 AS ADOPTED BY THE CITY OF LEE'S SUMMIT (LATEST EDITION), FOR EXCAVATION AND EMBANKMENT WORK WITHIN THE PROPOSED RIGHT-OF-WAY.
- AREAS OF CONSTRUCTION SHALL BE STRIPPED OF ALL VEGETATION, ORGANIC MATTER AND TOPSOIL TO A DEPTH AS RECOMMENDED BY GEOTECHNICAL ENGINEER AND OR TESTING AGENCY. SOILS REMOVED DURING SITE STRIPPING SHOULD BE EVALUATED TO DETERMINE IF PORTIONS OF THE TOPSOIL STRATUM MAY BE UTILIZED AS STRUCTURAL FILL WITHIN PAVEMENT AREAS. ANY MATERIAL NOT DEEMED AS SUITABLE FILL MATERIAL BY THE GEOTECHNICAL ENGINEER AND OR TESTING AGENCY SHALL BE REMOVED FROM THE JOB SITE BY THE CONTRACTOR AT HIS EXPENSE.
- ALL EMBANKMENT OUTSIDE OF RIGHT-OF-WAY SHOULD BE PLACED IN CONTROLLED LIFTS HAVING A MAXIMUM LOOSE LIFT THICKNESS OF 8". EMBANKMENT SHOULD BE COMPACTED TO A MINIMUM OF 95% OF THE MATERIALS MAXIMUM DRY DENSITY AS DETERMINED BY ASTM D-698 (STANDARD PROCTOR COMPACTION). MOISTURE CONTENT OF THE FILL AT THE TIME OF COMPACTION SHALL BE WITHIN A RANGE OF -0 TO +4 PERCENT OF OPTIMUM MOISTURE CONTENT.



EARTHWORK QUANTITIES		
LOCATION	CUT (C.Y.)	FILL (C.Y.)
FUTURE PHASE	0	54,547

FUTURE PHASE EARTHWORK CONTRIBUTIONS	
LOCATION	FILL (C.Y.)
HOOK FARMS 2ND PLAT	42,194
RETREAT AT HOOK FARMS 2ND PLAT	9,872
EXCESS	2,481

- EARTHWORK QUANTITIES NOTES:**
- EARTHWORK QUANTITIES BASED ON FINISHED GRADE SURFACE AND DO NOT INCLUDE ADJUSTMENTS FOR TOPSOIL AND SHRINKAGE.
 - EARTHWORK QUANTITIES DO NOT TAKE INTO CONSIDERATION EXCAVATION, REMOVAL AND DISPOSAL OF MATERIAL DEEMED UNSUITABLE BY A GEOTECHNICAL ENGINEER. THE EARTHWORK CONTRACTOR IS RESPONSIBLE FOR EXCAVATION, REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL AND FOR REPLACING IT WITH SUITABLE MATERIAL.



LEGEND	
---100---	EXISTING INDEX CONTOURS
- - -100-	EXISTING INTERMEDIATE CONTOURS
---100---	PROPOSED INDEX CONTOURS
- - -100-	PROPOSED INTERMEDIATE CONTOURS
---100---	HOOK FARMS 2ND PLAT INDEX CONTOURS
- - -100-	HOOK FARMS 2ND PLAT INTERMEDIATE CONTOURS

olsson

Olsson - Civil Engineering
 Missouri Certificate of Authority #001592
 1301 Burlington Street
 North Kansas City, MO 64116
 TEL 816.361.1177
 FAX 816.361.1888
 www.olson.com

STATE OF MISSOURI
 JULIE ELAINE SELLERS
 NUMBER PE-2017000367
 5/5/21
 PROFESSIONAL ENGINEER

REV. NO.	DATE	REVISIONS DESCRIPTION	BY







GRADING PLAN
 SITE GRADING & SITE DISTURBANCE PLANS
 THE RETREAT AT HOOK FARMS
 SECOND PLAT



LEE'S SUMMIT, MO 2021

drawn by: B.M.W./A.A.
 checked by: B.M.W./A.A.
 designed by: B.M.W./A.A.
 QA/QC by: J.E.S.
 project no.: A19-4059
 date: 05-05-2021

SHEET C405

DWG: F:\2019\4001-4500\019-4059-A 40-Design\AutoCAD\Final Plans\Sheets\GNCV\Site Grading & Site Disturbance Plans\C_ERC01_A194059.dwg USER: bworthley
 DATE: May 05, 2021 4:18pm XREFS: C_PTBK_A194059 C_XBASE_A194059 C_PEROS_A194059 C_DBASE_A194059 C_PENDY_A194059

LEGEND	
PHASE A	
	SILT FENCE
	TEMPORARY DIVERSION BERM
	TEMPORARY STONE CONSTRUCTION ENTRANCE
	TURF REINFORCEMENT MAT
	TREE CLEARING
	DRAINAGE AREA TO BASIN/TRAP



EROSION CONTROL STAGING CHART				
PROJECT STAGE	EROSION CONTROL BMP REFERENCE NO.	BMP DESCRIPTION	REMOVE AFTER STAGE	NOTES:
A - PRE-MASS GRADING	A1	CONSTRUCTION ENTRANCE	C	INSTALL PER APWA DETAIL ESC-01
	A2	CONCRETE WASHOUT	C	INSTALL PER APWA DETAIL ESC-01
	A3	SILT FENCE	C	INSTALL PER APWA DETAIL ESC-03
	A4	DIVERSION BERM	C	INSTALL PER APWA DETAIL ESC-05
	A5	SEDIMENT TRAP	C	INSTALL PER APWA DETAIL ESC-08
	A6	SEDIMENT BASIN	C	INSTALL PER APWA DETAIL ESC-11&12
	A7	TEMPORARY STREAM CROSSING	C	INSTALL PER APWA DETAIL ESC-13
B - INTERIM	B1	SILT FENCE	C	INSTALL PER APWA DETAIL ESC-03
	B2	DIVERSION BERM	C	INSTALL PER APWA DETAIL ESC-05
	B3	CURB INLET PROTECTION	C	INSTALL PER APWA DETAIL ESC-06
	B4	AREA INLET PROTECTION	C	INSTALL PER APWA DETAIL ESC-07
	B5	ROCK DITCH CHECK	C	INSTALL PER APWA DETAIL ESC-10
C - DISTURBED AREA STABILIZATION	C1	SEED, SOD AND STABILIZE ALL DISTURBED AREAS AND INSTALL ALL PLANTINGS PER SHEET C412		SEE SHEET C412 FOR DETAILS ON SOD AND PLANTINGS; SEED ALL OTHER DISTURBED AREAS
D - FINAL STABILIZATION	D1	SEED, SOD AND STABILIZE ALL DISTURBED AREAS BY REMOVAL OF SEDIMENT TRAPS		SEE SHEET C414 FOR DETAILS ON SOD AND PLANTINGS; SEED ALL OTHER DISTURBED AREAS
	D2	REMOVE SEDIMENT BASIN RISER AND PIPE AND CONVERT TO WATER QUALITY BASIN		SEE NOTE 2 BELOW. SEE SHEET C128 OF STREET & STORM SEWER PLANS FOR WATER QUALITY BASIN DETAILS

NOTE:
 1. THE SITE DISTURBANCE PLANS INDICATES THE FINAL PLACEMENT OF EROSION CONTROL DEVICES. THE CONTRACTOR(S) MAY PROCEED WITH THE CONSTRUCTION PRIOR TO THE FINAL PLACEMENT OF THESE DEVICES BY PROVIDING ADDITIONAL DEVICES TO CONTROL EROSION ON THEIR ITEMS OF WORK. THESE DEVICES SHALL BE MAINTAINED UNTIL THE FINAL DEVICES ARE IN PLACE.
 2. CONTRACTOR TO OVER-EXCAVATE SEDIMENT BASIN, FULLY REMOVING ALL SILT, AND FILLING IN CONTROLLED LIFTS TO PREVENT VOIDS OR EXCESSIVE SETTLING THAT COULD IMPACT BUILDING FOUNDATIONS.

olsson
 Olsson - Civil Engineering
 Missouri Certificate of Authority #001592
 1301 Burlington Street
 North Kansas City, MO 64116
 TEL 816.361.1177
 FAX 816.361.7888
 www.olsson.com

STATE OF MISSOURI
 JULIE ELAINE SELLERS
 PROFESSIONAL ENGINEER
 NUMBER PE-2017000367
 5/5/21

REV. NO.	DATE	REVISIONS DESCRIPTION







SITE DISTURBANCE PLAN - PHASE A
 SITE GRADING & SITE DISTURBANCE PLANS
 THE RETREAT AT HOOK FARMS
 SECOND PLAT
 LEE'S SUMMIT, MO

2021



drawn by: B.M.W./A.A.
 checked by: B.M.W./A.A.
 designed by: B.M.W./A.A.
 QA/QC by: J.E.S.
 project no.: A19-4059
 date: 05-05-2021

SHEET C406

DWG: F:\2019\4001-4500\019-4059-A 40-Design\AutoCAD\Final Plans\Sheets\GNC\Site Grading & Site Disturbance Plans\ERC01-OFFSITE_A194059.dwg
 DATE: May 05, 2021 4:20pm XREFS: C_XBASE_B194061 C_PENDY_B194061 C_PBASE_B194061 C_PTBK_A194059 C_PBASE_B194061 C_PUTIL_B194061
 USER: bworthley C_PBASE_B194061

LEGEND	
PHASE A	
	SILT FENCE
	TEMPORARY DIVERSION BERM
	TEMPORARY STONE CONSTRUCTION ENTRANCE
	TURF REINFORCEMENT MAT
	TREE CLEARING
	DRAINAGE AREA TO BASIN/TRAP

NOTE:
 THIS SHEET IS SHOWN FOR REFERENCE ONLY. REFER TO THE HOOK FARMS 2ND PLAT SITE GRADING & SITE DISTURBANCE PLANS FOR MORE DETAILS.



olsson
 Olsson - Civil Engineering
 Missouri Certificate of Authority #001592
 1301 Burlington Street
 North Kansas City, MO 64116
 TEL 816.361.1177
 FAX 816.361.7888
 www.olson.com

STATE OF MISSOURI
 JULIE ELAINE SELLERS
 NUMBER PE-2017000367
 5/5/21
 PROFESSIONAL ENGINEER


REV. NO.	DATE	REVISIONS DESCRIPTION

SITE DISTURBANCE PLAN - PHASE A
 SITE GRADING & SITE DISTURBANCE PLANS
 THE RETREAT AT HOOK FARMS
 SECOND PLAT
 LEE'S SUMMIT, MO
 2021


drawn by: B.M.W./A.A.
 checked by: B.M.W./A.A.
 designed by: B.M.W./A.A.
 QA/QC by: J.E.S.
 project no.: A19-4059
 date: 05-05-2021

SHEET C407


DWG: F:\2019\4001-4500\019-4059-A 40-Design\AutoCAD\Final Plans\Sheets\GNCV\Site Grading & Site Disturbance Plans\C-ERC01_A194059.dwg
 DATE: May 05, 2021 4:22pm XREFS: C:\PTBLK_A194059 C:\XBASE_A194059 C:\PEROS_A194059 C:\DBASE_A194059 C:\PBNY_A194059 USER: bworthey




SEDIMENT BASIN DESIGN DATA SUMMARY			
TITLE:	The Retreat at Hook Farms 2nd Plat		
JOB #:	A19-4059		
Design Item:	Basin #1	Units	Notes:
Site Data:			
Tributary Drainage Area to Pond:	13.01	Acres	
Disturbed Tributary Drainage Area to Pond:	13.01	Acres	
50% (2 yr) Design Flow:	37.39	cfs	
4% (25 yr) Design Flow:	66.07	cfs	
Pond Data:			
Minimum Sediment Storage Volume:	1744	cu. yd.	134 cy/acre minimum
Provided Sediment Storage Volume:	1838	cu. yd.	
Bottom Elevation:	939.50	Ft	
Sediment Cleanout Elevation:	941.19	Ft	Elevation Equal to 20% of Original Design Volume.
Top of Riser Elevation:	942.10	Ft	Top of Dry Storage Volume
Emergency Spillway Elevation:	943.50	Ft	At or above Q-2 elev. 1.0 ft min above principal spillway
Q-2 year Elevation:	943.49	Ft	
Q-25 year Elevation:	944.00	Ft	
Top of Dam Elevation:	945.00	Ft	1.0 ft min above Q-25 elev.
Basin Shape Data:			
A= Area at Normal Pool	8692	SF	
L = Length of Flow Path	280	Ft	
We = Effective Width = A/L	31.04	Ft	
Length to Width Ratio = L/We	9.02		If Length to Width Ratio is less than 2, baffles are required
Principal Spillway Data:			
Riser Pipe Diameter or Length x Width:	30	in	15-inch min. Size for 2 year flow minimum
Barrell Pipe Diameter:	24	in	15-inch min. Size for 2 year flow minimum
Riser Pipe Base Size:	5.43	cu. yd.	Size to Prevent Flotation. 1.25 safety factor required.
**Skimmer Size:	2.50	in	Skimmer sized to dewater in 48 to 72 hours
**Orifice Diameter (if reduced from standard):	-	in	**Based on ASP Enterprises Faircloth Skimmer Design Guide
Emergency Spillway Data:			
Design Width of Spillway:	60.00	Ft	
Design Flow Depth in Spillway:	0.56	Ft	Use $Q_{25yr} = C_s b H^{3/2}$ where $C_s = 2.63$, b is the Width of Spillway
Design Velocity in Spillway:	2.20	Ft/sec	
Lining Material:	TRM	N/A	




SEDIMENT TRAP DESIGN SUMMARY												
TRAP	TRIBUTARY AREA (AC.)	REQUIRED VOLUME (C.F.)	BERM HEIGHT "H" (FT.)	SPILLWAY HEIGHT "H _s " (FT.)	STORAGE VOLUME (C.F.)	BERM TOP WIDTH "W" (FT.)	BOTTOM ELEVATION (FT.)	SPILLWAY ELEVATION (FT.)	TOP OF BERM ELEVATION (FT.)	MIN. SPILLWAY LENGTH (FT.)	SEDIMENT CLEANOUT VOLUME (C.F.)	SEDIMENT CLEANOUT ELEVATION (FT.)
1 - Phase A	4.19	7542	2	1	9253	2	940	942	944	26	1851	941.13
1 - Phase B	4.78	8604	2	1	9253	2	940	942	944	29	1851	941.13





Olsson - Civil Engineering
 Missouri Certificate of Authority #001592
 1301 Burlington Street
 North Kansas City, MO 64116
 TEL 816.361.1177
 FAX 816.361.1888
 www.olsson.com



REV. NO.	DATE	REVISIONS DESCRIPTION	BY

2021


LEE'S SUMMIT, MO

SITE DISTURBANCE PLAN - PHASE A DETAILS
 SITE GRADING & SITE DISTURBANCE PLANS
 THE RETREAT AT HOOK FARMS
 SECOND PLAT


drawn by: B.M.W./A.A.
 checked by: B.M.W./A.A.
 designed by: B.M.W./A.A.
 QA/QC by: J.E.S.
 project no.: A19-4059
 date: 05-05-2021

SHEET
C408

DWG: F:\2019\4001-4059-A\40-Design\AutoCAD\Final Plans\Sheets\GNCV\Site Grading & Site Disturbance Plans\ERC01-OFFSITE_A194059.dwg
 DATE: May 05, 2021 4:24pm XREFS: C:\BASE_B194061 C:\PBDY_B194061 C:\PEROS_B194061 C:\DBASE_B194061 C:\PTBLK_A194059 C:\PUTIL_B194061 C:\PBASE_B194061 USER: bworthley



SEDIMENT TRAP 4
SCALE: 1"=20'



SEDIMENT TRAP 5
SCALE: 1"=20'

SEDIMENT TRAP DESIGN SUMMARY												
TRAP	TRIBUTARY AREA (AC.)	REQUIRED VOLUME (C.F.)	BERM HEIGHT "H" (FT.)	SPILLWAY HEIGHT "H ₀ " (FT.)	STORAGE VOLUME (C.F.)	BERM TOP WIDTH "W" (FT.)	BOTTOM ELEVATION (FT.)	SPILLWAY ELEVATION (FT.)	TOP OF BERM ELEVATION (FT.)	MIN. SPILLWAY LENGTH (FT.)	SEDIMENT CLEANOUT VOLUME (C.F.)	SEDIMENT CLEANOUT ELEVATION (FT.)
4	3.91	7045.87	2	1	7984.01	2	932	934	936	24	1596.80	933.67
5	5.48	9871.45	2	1	10415.42	2	933	935	937	33	2083.08	934.46

olsson
 Olsson - Civil Engineering
 Missouri Certificate of Authority #001592
 1301 Burlington Street
 North Kansas City, MO 64116
 TEL 816.361.1177
 FAX 816.361.7888
 www.olsosn.com


STATE OF MISSOURI
 JULIE ELAINE SELLERS
 PROFESSIONAL ENGINEER
 NUMBER PE-2017000367
 5/5/21

REV. NO.	DATE	REVISIONS DESCRIPTION	BY

SITE DISTURBANCE PLAN - PHASE A DETAILS
 SITE GRADING & SITE DISTURBANCE PLANS
 THE RETREAT AT HOOK FARMS
 SECOND PLAT
 LEE'S SUMMIT, MO
 2021

DWG: F:\2019\4001-4500\019-4059-A 40-Design\AutoCAD\Final Plans\Sheets\GNC\Site Grading & Site Disturbance Plans\C_ERC02_A194059.dwg
 DATE: May 05, 2021 4:25pm XREFS: C_PTLBK_A194059 C_XBASE_A194059 C_PEROS_A194059 USER: bworthley


LEGEND		
PHASE A	PHASE B	
[Symbol]	[Symbol]	SILT FENCE
[Symbol]	[Symbol]	TEMPORARY DIVERSION BERM
[Symbol]	[Symbol]	STORM DRAIN INLET PROTECTION
[Symbol]	[Symbol]	ROCK CHECK DAM
[Symbol]	[Symbol]	TEMPORARY STONE CONSTRUCTION ENTRANCE
[Symbol]	[Symbol]	TURF REINFORCEMENT MAT
[Symbol]	[Symbol]	TREE CLEARING
[Symbol]	[Symbol]	DRAINAGE AREA TO BASIN/TRAP



EROSION CONTROL STAGING CHART				
PROJECT STAGE	EROSION CONTROL BMP REFERENCE NO.	BMP DESCRIPTION	REMOVE AFTER STAGE	NOTES:
A - PRE-MASS GRADING	A1	CONSTRUCTION ENTRANCE	C	INSTALL PER APWA DETAIL ESC-01
	A2	CONCRETE WASHOUT	C	INSTALL PER APWA DETAIL ESC-01
	A3	SILT FENCE	C	INSTALL PER APWA DETAIL ESC-03
	A4	DIVERSION BERM	C	INSTALL PER APWA DETAIL ESC-05
	A5	SEDIMENT TRAP	C	INSTALL PER APWA DETAIL ESC-08
	A6	SEDIMENT BASIN	C	INSTALL PER APWA DETAIL ESC-11&12
B - INTERIM	B1	TEMPORARY STREAM CROSSING	C	INSTALL PER APWA DETAIL ESC-13
	B2	SILT FENCE	C	INSTALL PER APWA DETAIL ESC-03
	B3	DIVERSION BERM	C	INSTALL PER APWA DETAIL ESC-05
	B4	CURB INLET PROTECTION	C	INSTALL PER APWA DETAIL ESC-06
	B5	AREA INLET PROTECTION	C	INSTALL PER APWA DETAIL ESC-07
C - DISTURBED AREA STABILIZATION	C1	ROCK DITCH CHECK	C	INSTALL PER APWA DETAIL ESC-10
		SEED, SOD AND STABILIZE ALL DISTURBED AREAS AND INSTALL ALL PLANTINGS PER SHEET C412		SEE SHEET C412 FOR DETAILS ON SOD AND PLANTINGS; SEED ALL OTHER DISTURBED AREAS
D - FINAL STABILIZATION	D1	SEED, SOD AND STABILIZE ALL DISTURBED AREAS BY REMOVAL OF SEDIMENT TRAPS		SEE SHEET C414 FOR DETAILS ON SOD AND PLANTINGS; SEED ALL OTHER DISTURBED AREAS
	D2	REMOVE SEDIMENT BASIN RISER AND PIPE AND CONVERT TO WATER QUALITY BASIN		SEE NOTE 2 BELOW. SEE SHEET C128 OF STREET & STORM SEWER PLANS FOR WATER QUALITY BASIN DETAILS

UPON REMOVAL CONTRACTOR TO OVER-EXCAVATE SEDIMENT TRAPS, FULLY REMOVING ALL SILT, AND FILLING IN CONTROLLED LIFTS TO PREVENT VOIDS OR EXCESSIVE SETTLING THAT COULD IMPACT BUILDING FOUNDATIONS.

NOTE:
 1. THE SITE DISTURBANCE PLANS INDICATES THE FINAL PLACEMENT OF EROSION CONTROL DEVICES. THE CONTRACTOR(S) MAY PROCEED WITH THE CONSTRUCTION PRIOR TO THE FINAL PLACEMENT OF THESE DEVICES BY PROVIDING ADDITIONAL DEVICES TO CONTROL EROSION ON THEIR ITEMS OF WORK. THESE DEVICES SHALL BE MAINTAINED UNTIL THE FINAL DEVICES ARE IN PLACE.
 2. CONTRACTOR TO OVER-EXCAVATE SEDIMENT BASIN, FULLY REMOVING ALL SILT PRIOR TO GRADING WATER QUALITY BASIN BOTTOM AND INSTALLING OUTLET PIPE.



Olsson - Civil Engineering
 Missouri Certificate of Authority #001592
 1301 Burlington Street
 North Kansas City, MO 64116
 TEL 816.361.1177
 FAX 816.361.7888
 www.olsson.com

BY _____

DATE _____

REV. NO. _____

SITE DISTURBANCE PLAN - PHASE B
 SITE GRADING & SITE DISTURBANCE PLANS

TRACT K

THE RETREAT AT HOOK FARMS 1ST PLAT₅₃

THE RETREAT AT HOOK FARMS SECOND PLAT

LEE'S SUMMIT, MO

REVISIONS

NO.	DATE	DESCRIPTION

drawn by: B.M.W./A.A.
 checked by: B.M.W./A.A.
 designed by: B.M.W./A.A.
 QA/QC by: J.E.S.
 project no.: A19-4059
 date: 05-05-2021



2021

SHEET C410

DWG: F:\2019\4001-4500\019-4059-A 40-Design\AutoCAD\Final Plans\Sheets\GNCA\Site Grading & Site Disturbance Plans\ERC02-OFFSITE_A194059.dwg
 DATE: May 05, 2021 4:28pm XREFS: C_XBASE_B194061 C_PBDY_B194061 C_PUTIL_B194061 C_PBASE_B194061 C_PEROS_B194061 C_PTBLK_A194059

LEGEND		
PHASE A	PHASE B	
		SILT FENCE
		TEMPORARY DIVERSION BERM
		STORM DRAIN INLET PROTECTION
		ROCK CHECK DAM
		TEMPORARY STONE CONSTRUCTION ENTRANCE
		TURF REINFORCEMENT MAT
		TREE CLEARING
		DRAINAGE AREA TO BASIN/TRAP

NOTE:
 THIS SHEET IS SHOWN FOR REFERENCE ONLY. REFER TO THE HOOK FARMS 2ND PLAT SITE GRADING & SITE DISTURBANCE PLANS FOR MORE DETAILS.



olsson
 Olsson - Civil Engineering
 Missouri Certificate of Authority #001592
 1301 Burlington Street
 North Kansas City, MO 64116
 TEL 816.361.1177
 FAX 816.361.7888
 www.olson.com

STATE OF MISSOURI
 JULIE ELAINE SELLERS
 PE-2017000367
 5/5/21
 PROFESSIONAL ENGINEER

REV. NO.	DATE	REVISIONS DESCRIPTION	BY

SITE DISTURBANCE PLAN - PHASE B
 SITE GRADING & SITE DISTURBANCE PLANS
 THE RETREAT AT HOOK FARMS
 SECOND PLAT
 LEE'S SUMMIT, MO
 2021

drawn by: B.M.W./A.A.
 checked by: B.M.W./A.A.
 designed by: B.M.W./A.A.
 QA/QC by: J.E.S.
 project no.: A19-4059
 date: 05-05-2021

DWG: F:\2019\4001-4059-A 40-Design\AutoCAD\Final Plans\Sheets\GNCV\Site Grading & Site Disturbance Plans\C_ERC03_A194059.dwg
 DATE: May 05, 2021 4:29pm XREFS: C_PUTIL_A194059 C_XBASE_A194059 C_PBRD_A194059 C_PBASE_A194059
 USER: bworthley C_PBRD_A194059 C_PBASE_A194059



LEGEND		
PHASE A&B	PHASE C	
[Symbol]	[Symbol]	SILT FENCE
[Symbol]	[Symbol]	TEMPORARY DIVERSION BERM
[Symbol]	[Symbol]	STORM DRAIN INLET PROTECTION
[Symbol]	[Symbol]	ROCK CHECK DAM
[Symbol]	[Symbol]	TEMPORARY STONE CONSTRUCTION ENTRANCE
[Symbol]	[Symbol]	TURF REINFORCEMENT MAT
[Symbol]	[Symbol]	TREE CLEARING
[Symbol]	[Symbol]	DRAINAGE AREA TO BASIN/TRAP
[Symbol]	[Symbol]	TURF GRASS SEEDING

GENERAL NOTES:
 SEED & MULCH NOTES:
 SEEDING SHALL BE DONE BEFORE THE PROPOSED SEEDBED BECOMES ERODED, CRUSTED OVER, OR DRIED OUT AND SHALL NOT BE DONE WHEN THE GROUND IS FROZEN, OR COVERED WITH SNOW. THE SEED SHALL COMPLY WITH THE REQUIREMENTS OF THE MISSOURI SEED LAW AND THE FEDERAL SEED ACT. ALSO, IT SHALL CONTAIN NO SEED OF ANY PLANT ON THE FEDERAL NOXIOUS WEED LIST. OTHER WEED SEED SHALL NOT EXCEED ONE PERCENT BY WEIGHT OF MIX.

SEED & FERTILIZER RATE:
 MIX I - RYE GRASS / BLUE GRASS -----100 LBS. PER ACRE
 MIX II - TALL FESCUE / BLUE GRASS -----195 LBS. PER ACRE
 FERTILIZER -----800 TO 1200 LBS. PER ACRE
 (25 LBS. PER 1000 SQ. FT.)

DURING THE DATES DECEMBER 15TH THROUGH MAY 31 ALL LIME, FERTILIZER, SEED, AND MULCH SHALL BE APPLIED TO FINISHED SLOPES OF DISTURBED AREAS. DURING THE MONTHS OF JUNE, JULY, OCTOBER, AND NOVEMBER 1ST THROUGH DECEMBER 15TH, LIME, FERTILIZER, SEED, AND MULCH SHALL BE APPLIED AT THE FOLLOWING RATES:
 LIME - 100 % OF SPECIFIED QUANTITY
 FERTILIZER - 75 % OF THE SPECIFIED QUANTITY
 SEED - 50 % OF THE SPECIFIED QUANTITY
 MULCH - 100 % OF THE SPECIFIED QUANTITY
 MULCH SHALL BE VEGETATIVE TYPE, CEREAL STRAW FROM STALKS OF OATS, RYE, OR BARLEY, OR APPROVED EQUAL. THE STRAW SHALL BE FREE OF PROHIBITED WEED SEED AND RELATIVELY FREE OF ALL OTHER NOXIOUS AND UNDESIRABLE SEED. MULCH SHALL BE APPLIED AT THE RATE OF 2 TONS PER ACRE, (70 TO 90 LBS. PER 1000 SQ. FT.). MULCH SHALL BE EMBEDDED BY A MULCH ANCHORING TOOL OR DISK TYPE ROLLER HAVING FLAT SERRATED DISKS SPACED NOT MORE THAN 10 INCHES APART AND CLEANING SCRAPERS SHALL BE PROVIDED.

THE SITE DISTURBANCE PLANS INDICATES THE FINAL PLACEMENT OF EROSION CONTROL DEVICES. THE CONTRACTOR(S) MAY PROCEED WITH THE CONSTRUCTION PRIOR TO THE FINAL PLACEMENT OF THESE DEVICES BY PROVIDING ADDITIONAL DEVICES TO CONTROL EROSION ON THEIR ITEMS OF WORK. THESE DEVICES SHALL BE MAINTAINED UNTIL THE FINAL DEVICES ARE IN PLACE.



EROSION CONTROL STAGING CHART				
PROJECT STAGE	EROSION CONTROL BMP REFERENCE NO.	BMP DESCRIPTION	REMOVE AFTER STAGE	NOTES:
A - PRE-MASS GRADING	A1	CONSTRUCTION ENTRANCE	C	INSTALL PER APWA DETAIL ESC-01
	A2	CONCRETE WASHOUT	C	INSTALL PER APWA DETAIL ESC-01
	A3	SILT FENCE	C	INSTALL PER APWA DETAIL ESC-03
	A4	DIVERSION BERM	C	INSTALL PER APWA DETAIL ESC-05
	A5	SEDIMENT TRAP	C	INSTALL PER APWA DETAIL ESC-08
	A6	SEDIMENT BASIN	C	INSTALL PER APWA DETAIL ESC-11&12
B - INTERIM	B1	SILT FENCE	C	INSTALL PER APWA DETAIL ESC-03
	B2	DIVERSION BERM	C	INSTALL PER APWA DETAIL ESC-05
	B3	CURB INLET PROTECTION	C	INSTALL PER APWA DETAIL ESC-06
	B4	AREA INLET PROTECTION	C	INSTALL PER APWA DETAIL ESC-07
	B5	ROCK DITCH CHECK	C	INSTALL PER APWA DETAIL ESC-10
C - DISTURBED AREA STABILIZATION	C1	SEED, SOD AND STABILIZE ALL DISTURBED AREAS AND INSTALL ALL PLANTINGS PER SHEET C412		SEE SHEET C412 FOR DETAILS ON SOD AND PLANTINGS; SEE ALL OTHER DISTURBED AREAS
D - FINAL STABILIZATION	D1	SEED, SOD AND STABILIZE ALL DISTURBED AREAS BY REMOVAL OF SEDIMENT TRAPS		SEE SHEET C414 FOR DETAILS ON SOD AND PLANTINGS; SEE ALL OTHER DISTURBED AREAS
	D2	REMOVE SEDIMENT BASIN RISER AND PIPE AND CONVERT TO WATER QUALITY BASIN		SEE NOTE 2 BELOW. SEE SHEET C128 OF STREET & STORM SEWER PLANS FOR WATER QUALITY BASIN DETAILS

NOTE:
 1. THE SITE DISTURBANCE PLANS INDICATES THE FINAL PLACEMENT OF EROSION CONTROL DEVICES. THE CONTRACTOR(S) MAY PROCEED WITH THE CONSTRUCTION PRIOR TO THE FINAL PLACEMENT OF THESE DEVICES BY PROVIDING ADDITIONAL DEVICES TO CONTROL EROSION ON THEIR ITEMS OF WORK. THESE DEVICES SHALL BE MAINTAINED UNTIL THE FINAL DEVICES ARE IN PLACE.
 2. CONTRACTOR TO OVER-EXCAVATE SEDIMENT BASIN, FULLY REMOVING ALL SILT PRIOR TO GRADING WATER QUALITY BASIN BOTTOM AND INSTALLING OUTLET PIPE.

Olsson - Civil Engineering
 Missouri Certificate of Authority #001592
 1301 Burlington Street
 North Kansas City, MO 64116
 TEL 816.361.1177
 FAX 816.361.7888
 www.olsson.com

REV. NO.	DATE	REVISIONS DESCRIPTION

SITE DISTURBANCE PLAN - PHASE C
 SITE GRADING & SITE DISTURBANCE PLANS
 THE RETREAT AT HOOK FARMS
 SECOND PLAT

REVISIONS

2021

LEE'S SUMMIT, MO

SHEET
 C412

drawn by: B.M.W./A.A.
 checked by: B.M.W./A.A.
 designed by: B.M.W./A.A.
 QA/QC by: J.E.S.
 project no.: A19-4059
 date: 05-05-2021


DWG: F:\2019\4001-4500\019-4059-A\40-Design\AutoCAD\Final Plans\Sheets\GNCV\Site Grading & Site Disturbance Plans\ERC03-OFFSITE_A194059.dwg
 DATE: May 05, 2021 4:31pm XREFS: C_XBASE_B194061 C_PENDY_B194061 C_PUTILL_B194061 C_PBASE_B194061 C_PITBLK_A194059

LEGEND		
PHASE A&B	PHASE C	
		SILT FENCE
		TEMPORARY DIVERSION BERM
		STORM DRAIN INLET PROTECTION
		ROCK CHECK DAM
		TEMPORARY STONE CONSTRUCTION ENTRANCE
		TURF REINFORCEMENT MAT
		TREE CLEARING
		DRAINAGE AREA TO BASIN/TRAP
		TURF GRASS SEEDING

GENERAL NOTES:
SEED & MULCH NOTES:
 SEEDING SHALL BE DONE BEFORE THE PROPOSED SEEDBED BECOMES ERODED, CRUSTED OVER, OR DRIED OUT AND SHALL NOT BE DONE WHEN THE GROUND IS FROZEN, OR COVERED WITH SNOW. THE SEED SHALL COMPLY WITH THE REQUIREMENTS OF THE MISSOURI SEED LAW AND THE FEDERAL SEED ACT. ALSO, IT SHALL CONTAIN NO SEED OF ANY PLANT ON THE FEDERAL NOXIOUS WEED LIST. OTHER WEED SEED SHALL NOT EXCEED ONE PERCENT BY WEIGHT OF MIX.
SEED & FERTILIZER RATE:
 MIX I - RYE GRASS / BLUE GRASS -----100 LBS. PER ACRE
 MIX II - TALL FESCUE / BLUE GRASS -----195 LBS. PER ACRE
 FERTILIZER -----800 TO 1200 LBS. PER ACRE (25 LBS. PER 1000 SQ. FT.)
DURING THE DATES DECEMBER 15TH THROUGH MAY 31 ALL LIME, FERTILIZER, SEED, AND MULCH SHALL BE APPLIED TO FINISHED SLOPES OF DISTURBED AREAS. DURING THE MONTHS OF JUNE, JULY, OCTOBER, AND NOVEMBER 1ST THROUGH DECEMBER 15TH, LIME, FERTILIZER, SEED, AND MULCH SHALL BE APPLIED AT THE FOLLOWING RATES:
 LIME - 100 % OF SPECIFIED QUANTITY
 FERTILIZER - 75 % OF THE SPECIFIED QUANTITY
 SEED - 50 % OF THE SPECIFIED QUANTITY
 MULCH - 100 % OF THE SPECIFIED QUANTITY
 MULCH SHALL BE VEGETATIVE TYPE, CEREAL STRAW FROM STALKS OF OATS, RYE, OR BARLEY, OR APPROVED EQUAL. THE STRAW SHALL BE FREE OF PROHIBITED WEED SEED AND RELATIVELY FREE OF ALL OTHER NOXIOUS AND UNDESIRABLE SEED. MULCH SHALL BE APPLIED AT THE RATE OF 2 TONS PER ACRE, (70 TO 90 LBS. PER 1000 SQ. FT.). MULCH SHALL BE EMBEDDED BY A MULCH ANCHORING TOOL OR DISK TYPE ROLLER HAVING FLAT SERRATED DISKS SPACED NOT MORE THAN 10 INCHES APART AND CLEANING SCRAPERS SHALL BE PROVIDED.

THE SITE DISTURBANCE PLANS INDICATES THE FINAL PLACEMENT OF EROSION CONTROL DEVICES. THE CONTRACTOR(S) MAY PROCEED WITH THE CONSTRUCTION PRIOR TO THE FINAL PLACEMENT OF THESE DEVICES BY PROVIDING ADDITIONAL DEVICES TO CONTROL EROSION ON THEIR ITEMS OF WORK. THESE DEVICES SHALL BE MAINTAINED UNTIL THE FINAL DEVICES ARE IN PLACE.

NOTE:
 THIS SHEET IS SHOWN FOR REFERENCE ONLY. REFER TO THE HOOK FARMS 2ND PLAT SITE GRADING & SITE DISTURBANCE PLANS FOR MORE DETAILS.



olsson

Olsson - Civil Engineering
 Missouri Certificate of Authority #001592
 1301 Burlington Street
 North Kansas City, MO 64116
 TEL 816.361.1177
 FAX 816.361.7888
 www.olsson.com

STATE OF MISSOURI
 JULIE ELAINE
 SELLERS
 NUMBER
 PE-2017000367
 5/5/21
 PROFESSIONAL ENGINEER

REV. NO.	DATE	REVISIONS DESCRIPTION

SITE DISTURBANCE PLAN - PHASE C
 SITE GRADING & SITE DISTURBANCE PLANS

THE RETREAT AT HOOK FARMS
 SECOND PLAT

2021

drawn by: B.M.W./A.A.
 checked by: B.M.W./A.A.
 designed by: B.M.W./A.A.
 QA/QC by: J.E.S.
 project no.: A19-4059
 date: 05-05-2021

LEE'S SUMMIT, MO

DWG: F:\2019\4001-4500\019-4059-A 40-Design\AutoCAD\Final Plans\Sheets\GNCV\Site Grading & Site Disturbance Plans\C_ERC04_A194059.dwg
 DATE: May 05, 2021 4:33pm XREFS: C_PUTIL_A194059 C_XBASE_A194059 C_PBRDY_A194059 C_PBASE_A194059
 USER: bworthley C_PBRDY_A194059 C_PBASE_A194059



LEGEND		
PHASE A,B&C	PHASE D	
		SILT FENCE
		TEMPORARY DIVERSION BERM
		STORM DRAIN INLET PROTECTION
		ROCK CHECK DAM
		TEMPORARY STONE CONSTRUCTION ENTRANCE
		TURF REINFORCEMENT MAT
		TREE CLEARING
		DRAINAGE AREA TO BASIN/TRAP
		TURF GRASS SEEDING

GENERAL NOTES:
 SEED & MULCH NOTES:
 SEEDING SHALL BE DONE BEFORE THE PROPOSED SEEDBED BECOMES ERODED, CRUSTED OVER, OR DRIED OUT AND SHALL NOT BE DONE WHEN THE GROUND IS FROZEN, OR COVERED WITH SNOW. THE SEED SHALL COMPLY WITH THE REQUIREMENTS OF THE MISSOURI SEED LAW AND THE FEDERAL SEED ACT. ALSO, IT SHALL CONTAIN NO SEED OF ANY PLANT ON THE FEDERAL NOXIOUS WEED LIST. OTHER WEED SEED SHALL NOT EXCEED ONE PERCENT BY WEIGHT OF MIX.

SEED & FERTILIZER RATE:
 MIX I - RYE GRASS / BLUE GRASS -----100 LBS. PER ACRE
 MIX II - TALL FESCUE / BLUE GRASS -----195 LBS. PER ACRE
 FERTILIZER -----800 TO 1200 LBS. PER ACRE (25 LBS. PER 1000 SQ. FT.)

DURING THE DATES DECEMBER 15TH THROUGH MAY 31 ALL LIME, FERTILIZER, SEED, AND MULCH SHALL BE APPLIED TO FINISHED SLOPES OF DISTURBED AREAS. DURING THE MONTHS OF JUNE, JULY, OCTOBER, AND NOVEMBER 1ST THROUGH DECEMBER 15TH, LIME, FERTILIZER, SEED, AND MULCH SHALL BE APPLIED AT THE FOLLOWING RATES:
 LIME - 100 % OF SPECIFIED QUANTITY
 FERTILIZER - 75 % OF THE SPECIFIED QUANTITY
 SEED - 50 % OF THE SPECIFIED QUANTITY
 MULCH - 100 % OF THE SPECIFIED QUANTITY
 MULCH SHALL BE VEGETATIVE TYPE, CEREAL STRAW FROM STALKS OF OATS, RYE, OR BARLEY, OR APPROVED EQUAL. THE STRAW SHALL BE FREE OF PROHIBITED WEED SEED AND RELATIVELY FREE OF ALL OTHER NOXIOUS AND UNDESIRABLE SEED. MULCH SHALL BE APPLIED AT THE RATE OF 2 TONS PER ACRE, (70 TO 90 LBS. PER 1000 SQ. FT.). MULCH SHALL BE EMBEDDED BY A MULCH ANCHORING TOOL OR DISK TYPE ROLLER HAVING FLAT SERRATED DISKS SPACED NOT MORE THAN 10 INCHES APART AND CLEANING SCRAPERS SHALL BE PROVIDED.

THE SITE DISTURBANCE PLANS INDICATES THE FINAL PLACEMENT OF EROSION CONTROL DEVICES. THE CONTRACTOR(S) MAY PROCEED WITH THE CONSTRUCTION PRIOR TO THE FINAL PLACEMENT OF THESE DEVICES BY PROVIDING ADDITIONAL DEVICES TO CONTROL EROSION ON THEIR ITEMS OF WORK. THESE DEVICES SHALL BE MAINTAINED UNTIL THE FINAL DEVICES ARE IN PLACE.



EROSION CONTROL STAGING CHART				
PROJECT STAGE	EROSION CONTROL BMP REFERENCE NO.	BMP DESCRIPTION	REMOVE AFTER STAGE	NOTES:
A - PRE-MASS GRADING	A1	CONSTRUCTION ENTRANCE	C	INSTALL PER APWA DETAIL ESC-01
	A2	CONCRETE WASHOUT	C	INSTALL PER APWA DETAIL ESC-01
	A3	SILT FENCE	C	INSTALL PER APWA DETAIL ESC-03
	A4	DIVERSION BERM	C	INSTALL PER APWA DETAIL ESC-05
	A5	SEDIMENT TRAP	C	INSTALL PER APWA DETAIL ESC-08
	A6	SEDIMENT BASIN	C	INSTALL PER APWA DETAIL ESC-11&12
B - INTERIM	B1	SILT FENCE	C	INSTALL PER APWA DETAIL ESC-03
	B2	DIVERSION BERM	C	INSTALL PER APWA DETAIL ESC-05
	B3	CURB INLET PROTECTION	C	INSTALL PER APWA DETAIL ESC-06
	B4	AREA INLET PROTECTION	C	INSTALL PER APWA DETAIL ESC-07
	B5	ROCK DITCH CHECK	C	INSTALL PER APWA DETAIL ESC-10
C - DISTURBED AREA STABILIZATION	C1	SEED, SOD AND STABILIZE ALL DISTURBED AREAS AND INSTALL ALL PLANTINGS PER SHEET C412		SEE SHEET C412 FOR DETAILS ON SOD AND PLANTINGS; SEED ALL OTHER DISTURBED AREAS
D - FINAL STABILIZATION	D1	SEED, SOD AND STABILIZE ALL DISTURBED AREAS BY REMOVAL OF SEDIMENT TRAPS		SEE SHEET C414 FOR DETAILS ON SOD AND PLANTINGS; SEED ALL OTHER DISTURBED AREAS
	D2	REMOVE SEDIMENT BASIN RISER AND PIPE AND CONVERT TO WATER QUALITY BASIN		SEE NOTE 2 BELOW. SEE SHEET C128 OF STREET & STORM SEWER PLANS FOR WATER QUALITY BASIN DETAILS

NOTE:
 1. THE SITE DISTURBANCE PLANS INDICATES THE FINAL PLACEMENT OF EROSION CONTROL DEVICES. THE CONTRACTOR(S) MAY PROCEED WITH THE CONSTRUCTION PRIOR TO THE FINAL PLACEMENT OF THESE DEVICES BY PROVIDING ADDITIONAL DEVICES TO CONTROL EROSION ON THEIR ITEMS OF WORK. THESE DEVICES SHALL BE MAINTAINED UNTIL THE FINAL DEVICES ARE IN PLACE.
 2. CONTRACTOR TO OVER-EXCAVATE SEDIMENT BASIN, FULLY REMOVING ALL SILT PRIOR TO GRADING WATER QUALITY BASIN BOTTOM AND INSTALLING OUTLET PIPE.

Olsson - Civil Engineering
 Missouri Certificate of Authority #001592
 1301 Burlington Street
 North Kansas City, MO 64116
 TEL 816.361.1177
 FAX 816.361.7888
 www.olsson.com

REV. NO.	DATE	REVISIONS DESCRIPTION

**SITE DISTURBANCE PLAN - PHASE D
 SITE GRADING & SITE DISTURBANCE PLANS**

THE RETREAT AT HOOK FARMS
 SECOND PLAT

LEE'S SUMMIT, MO

2021

drawn by: B.M.W./A.A.
 checked by: B.M.W./A.A.
 designed by: B.M.W./A.A.
 QA/QC by: J.E.S.
 project no.: A19-4059
 date: 05-05-2021

SHEET C414

DWG: F:\2019\4001-4500\019-4059-A\40-Design\AutoCAD\Final Plans\Sheets\GNCV\Site Grading & Site Disturbance Plans\ERC04-OFFSITE_A194059.dwg
 DATE: May 05, 2021 4:35pm XREFS: C_XBASE_B194061 C_PENDY_B194061 C_PUTIL_B194061 C_PBASE_B194061 C_PBLK_A194059

LEGEND		
PHASE A,B&C	PHASE D	
		SILT FENCE
		TEMPORARY DIVERSION BERM
		STORM DRAIN INLET PROTECTION
		ROCK CHECK DAM
		TEMPORARY STONE CONSTRUCTION ENTRANCE
		TURF REINFORCEMENT MAT
		TREE CLEARING
		DRAINAGE AREA TO BASIN/TRAP
		TURF GRASS SEEDING


NOTE:
 THIS SHEET IS SHOWN FOR REFERENCE ONLY. REFER TO THE HOOK FARMS 2ND PLAT SITE GRADING & SITE DISTURBANCE PLANS FOR MORE DETAILS.

GENERAL NOTES:
SEED & MULCH NOTES:
 SEEDING SHALL BE DONE BEFORE THE PROPOSED SEEDBED BECOMES ERODED, CRUSTED OVER, OR DRIED OUT AND SHALL NOT BE DONE WHEN THE GROUND IS FROZEN, OR COVERED WITH SNOW. THE SEED SHALL COMPLY WITH THE REQUIREMENTS OF THE MISSOURI SEED LAW AND THE FEDERAL SEED ACT. ALSO, IT SHALL CONTAIN NO SEED OF ANY PLANT ON THE FEDERAL NOXIOUS WEED LIST. OTHER WEED SEED SHALL NOT EXCEED ONE PERCENT BY WEIGHT OF MIX.

SEED & FERTILIZER RATE:
 MIX I - RYE GRASS / BLUE GRASS -----100 LBS. PER ACRE
 MIX II - TALL FESCUE / BLUE GRASS -----195 LBS. PER ACRE
 FERTILIZER -----800 TO 1200 LBS. PER ACRE (25 LBS. PER 1000 SQ. FT.)

DURING THE DATES DECEMBER 15TH THROUGH MAY 31 ALL LIME, FERTILIZER, SEED, AND MULCH SHALL BE APPLIED TO FINISHED SLOPES OF DISTURBED AREAS. DURING THE MONTHS OF JUNE, JULY, OCTOBER, AND NOVEMBER 1ST THROUGH DECEMBER 15TH, LIME, FERTILIZER, SEED, AND MULCH SHALL BE APPLIED AT THE FOLLOWING RATES:
 LIME - 100 % OF SPECIFIED QUANTITY
 FERTILIZER - 75 % OF THE SPECIFIED QUANTITY
 SEED - 50 % OF THE SPECIFIED QUANTITY
 MULCH - 100 % OF THE SPECIFIED QUANTITY
 MULCH SHALL BE VEGETATIVE TYPE, CEREAL STRAW FROM STALKS OF OATS, RYE, OR BARLEY, OR APPROVED EQUAL. THE STRAW SHALL BE FREE OF PROHIBITED WEED SEED AND RELATIVELY FREE OF ALL OTHER NOXIOUS AND UNDESIRABLE SEED. MULCH SHALL BE APPLIED AT THE RATE OF 2 TONS PER ACRE, (70 TO 90 LBS. PER 1000 SQ. FT.). MULCH SHALL BE EMBEDDED BY A MULCH ANCHORING TOOL OR DISK TYPE ROLLER HAVING FLAT SERRATED DISKS SPACED NOT MORE THAN 10 INCHES APART AND CLEANING SCRAPERS SHALL BE PROVIDED.

THE SITE DISTURBANCE PLANS INDICATES THE FINAL PLACEMENT OF EROSION CONTROL DEVICES. THE CONTRACTOR(S) MAY PROCEED WITH THE CONSTRUCTION PRIOR TO THE FINAL PLACEMENT OF THESE DEVICES BY PROVIDING ADDITIONAL DEVICES TO CONTROL EROSION ON THEIR ITEMS OF WORK. THESE DEVICES SHALL BE MAINTAINED UNTIL THE FINAL DEVICES ARE IN PLACE.



olsson

Olsson - Civil Engineering
 Missouri Certificate of Authority #001592
 1301 Burlington Street
 North Kansas City, MO 64116
 TEL 816.361.1177
 FAX 816.361.7888
 www.olsson.com

STATE OF MISSOURI
 JULIE ELAINE
 SELLERS
 NUMBER
 PE-2017000367
 5/5/21
 PROFESSIONAL ENGINEER

REV. NO.	DATE	REVISIONS DESCRIPTION

SITE DISTURBANCE PLAN - PHASE D
 SITE GRADING & SITE DISTURBANCE PLANS

THE RETREAT AT HOOK FARMS
 SECOND PLAT

2021

drawn by: B.M.W./A.A.
 checked by: B.M.W./A.A.
 designed by: B.M.W./A.A.
 QA/QC by: J.E.S.
 project no.: A19-4059
 date: 05-05-2021

LEE'S SUMMIT, MO

SHEET
 C415

Notes for Concrete Washout:

- Concrete washout areas shall be installed prior to any concrete placement on site.
- Concrete washout area shall include a flat suburface pit sized relative to the volume of concrete to be placed on site. The slope leading out of the suburface pit shall be 2:1. The entire tracking pool shall be sloped towards the concrete washout area.
- Vehicle tracking control is required at the access point to all concrete washout areas.
- Slope shall be placed at the construction site entrance, washout area and wherever as necessary to clearly indicate the location(s) of the concrete washout area(s) to operators of concrete truck and pump rigs.
- A one-way vehicular flow may be required along the bottom and sides of the suburface pit in sandy or gravelly soils.

Maintenance for Concrete Washout:

- Concrete washout materials shall be removed once the materials have filled the washout to approximately 75% full.
- Concrete washout areas shall be enlarged as necessary to maintain capacity for washed concrete.
- Concrete washout water, washed pieces of concrete and all other debris in the suburface pit shall be transported from the job site in a water-tight container and disposed of properly.
- Concrete washout areas shall remain in place until all concrete for the project is placed.
- When concrete washout areas are removed, excavations shall be filled with suitable compacted backfill and tamped; any disturbed area associated with the installation, maintenance, and/or removal of the concrete washout areas shall be restored.

Notes for Construction Entrance:

- Avoid locating on steep slopes, or curves on public roads, or downhill of disturbed areas.
- Remove all vegetation and other unsuitable material from the foundation area, grade, and crown for positive drainage.
- If slope intersects the public road access 2K, construct a 6- to 8-inch high ridge with 3K-TV side slopes across the foundation approximately 15 feet from the edge of the public road to divert runoff from it.
- Install pipe under the entrance if needed to maintain drainage ditches along public roads.
- Place stone to dimensions and grade as shown on plans. Lower surface sloped for drainage.
- Divert all surface runoff and drainage from the entrance to a sediment control device.
- If conditions warrant, place geotextile fabric on the graded foundation to improve stability.

Maintenance for Construction Entrance:

- Reshape entrance as needed to maintain function and integrity of installation. Top dress with clean aggregate as needed.

CONCRETE WASHOUT

CONSTRUCTION ENTRANCE

AMERICAN PUBLIC WORKS ASSOCIATION
KANSAS CITY METRO CHAPTER
CONSTRUCTION ENTRANCE AND CONCRETE WASHOUT
STANDARD DRAWING NUMBER ESC-01 ADOPTED: 10/24/2016

General Notes:

- APWA Specifications 2150 and Design Guidance 5100 shall be referenced to select type of blanket or mat to be used.
- Typical anchors and softeners/spacing shall be installed according to the manufacturer's instructions.
- LONGITUDINAL SEAMS: The edges of the blanket or mat should overlap each other a minimum of 6 inches, with anchors catching the edges of both blankets.

Maintenance:

- Turn or degraded product shall be repaired or replaced, unless such degradation is within the functional longevity specified by the manufacturer.
- Edges of seams that are loose or frayed shall be secured.

Notes for Installation in Channels:

- Erosion Control Blankets and TRMs shall be laid in the direction of the flow, with the first course of the centerline of channel, where applicable. In order for the mat to be in contact with the soil, lay blanket loosely, avoiding stretching.
- ANCHOR FOLDS: The top of the mat should be folded under, buried and secured with wood or other approved anchors placed 6 inches apart. The top edge of the mat should be buried in a slot 6 inches wide x 6 inches deep, anchored in the bottom of the slot, backfilled, and the mat folded over the top as shown in detail.
- SPURCE SEAM: When splices are necessary, overlap and a minimum of 12 inches in direction of water flow. Stagger splice seams.
- CHECK SLOTS: Establish check slots transverse to slope every 30 feet. The slots should be 6 inches wide x 6 inches deep. The mat shall be cut to a length 12 inches beyond the slot. The top of the downstream mat shall be secured in, secured and buried similar to the edge anchor fold. The upstream mat shall then cover the slot and be anchored as shown.
- EDGE ANCHORS: Lay outside edge of mat into trench at top of the slope and anchor.
- TERMINUS: The bottom edge of the mat shall be anchored.

Critical Points:

- A - Overlaps and seams;
- B - Projected water line;
- C - Channel bottom / side slope vertices;

Notes for Installation on Slopes:

- Erosion Control Blankets and TRMs shall be laid in the direction of the slope in order for blanket to be in contact with the soil, lay blanket loosely, avoiding stretching.
- ANCHOR SLOTS: The top of the blanket should be "lapped in" at the top of the slope and anchored in place with anchors 6 inches apart. The slots should be 6 inches wide x 6 inches deep with the blanket anchored in the bottom of the slot, then backfilled, tamped and sealed.
- SPURCE SEAM: When splices are necessary, overlap and a minimum of 8 inches in direction of water flow. Stagger splice seams.
- TERMINAL FOLD: The bottom edge of the blanket shall be turned under a minimum of 4 inches, then anchored in place with anchors 9 inches apart.

CONCRETE WASHOUT

AMERICAN PUBLIC WORKS ASSOCIATION
KANSAS CITY METRO CHAPTER
EROSION CONTROL BLANKETS AND TURF REINFORCEMENT MATS
STANDARD DRAWING NUMBER ESC-02 ADOPTED: 10/24/2016

Notes:

- In order to contain water, the ends of the silt fence must be turned uphill (Figure A).
- Long perimeter runs of silt fence must be limited to 100'. Runs should be broken up into several smaller segments to minimize water concentrations (Figure A).
- Long slopes should be broken up with intermediate rows of silt fence to slow runoff velocities.
- Attach fabric to upstream side of post.
- Install posts a minimum of 2' into the ground.
- Trenching will only be allowed for small or difficult installation, where slicing machine cannot be reasonably used.

Maintenance:

- Remove and dispose of sediment deposits when the deposit approaches 1/2 the height of silt fence.
- Repair as necessary to maintain function and structure.

CONCRETE WASHOUT

AMERICAN PUBLIC WORKS ASSOCIATION
KANSAS CITY METRO CHAPTER
SILT FENCE
STANDARD DRAWING NUMBER ESC-03 ADOPTED: 10/24/2016

Notes for Diversion Berm:

- Slope drains are optional but may be required by the engineer if the berm is at the top of a steep slope.
- Diversion berms must be installed as a first step in the land-disturbing activity and must be functional prior to upstream land disturbance.
- The berms should be adequately compacted to prevent failure.
- Temporary or permanent seeding and mulch shall be applied to the berm immediately following its construction.
- Place the berm so to minimize damages by construction operations and traffic.
- The berm must discharge to a temporary sediment trap or stabilized area.
- All trees, brush, stumps, obstructions and other objectionable material shall be removed and disposed of so as not to interfere with the proper functioning of diversion.
- Fill shall be compacted as needed to prevent unequal settlement that would cause damage in the completed diversion. Fill shall be composed of soil which is free from excessive organic debris, rocks or other objectionable materials.

Maintenance:

- Berm shall be reshaped, compacted, and stabilized as necessary to maintain its function.
- Breaches in the berm shall be repaired immediately.

Notes for Slope Drain:

- Slope Drain and Diversion Berm may be used on either project foreslopes or project backlopes.
- Discharge of Slope Drains shall be into stabilized ditch or area, or into Sediment Basin.
- Pipe shall be secured in place as approved by Engineer.

Maintenance:

- Accumulation of any visible sediment at the inlet and outlet shall be removed promptly.
- Outlet conditions shall be repaired if scour is observed. Leaking or damaged section of pipe shall be repaired immediately.
- Barriers directing water to the inlet shall be monitored for continually and effectiveness.

CONCRETE WASHOUT

AMERICAN PUBLIC WORKS ASSOCIATION
KANSAS CITY METRO CHAPTER
DIVERSION BERMS AND SLOPE DRAINS
STANDARD DRAWING NUMBER ESC-05 ADOPTED: 10/24/2016

olsson
Olsson - Civil Engineering
Missouri Certificate of Authority #001592
1301 Burlington Street
North Kansas City, MO 64116
TEL 816.361.1177
FAX 816.361.1888
www.olsson.com

JULIE ELAINE SELLERS
Professional Engineer
NUMBER PE-2017000367
5/5/21

STATE OF MISSOURI
PROFESSIONAL ENGINEER

BY: _____
DATE: _____
REV. NO. _____

REVISIONS DESCRIPTION





2021

LEE'S SUMMIT, MO

DETAIL SHEET
SITE GRADING & SITE DISTURBANCE PLANS
THE RETREAT AT HOOK FARMS
SECOND PLAT

drawn by: B.M.W./A.A.
checked by: B.M.W./A.A.
designed by: B.M.W./A.A.
QA/QC by: J.E.S.
project no.: A19-4059
date: 05-05-2021

SHEET C416



olsson
 Olsson - Civil Engineering
 Missouri Certificate of Authority #001592
 1301 Burlington Street
 North Kansas City, MO 64116
 TEL 816.361.1177
 FAX 816.361.1888
 www.olsson.com

STATE OF MISSOURI
 JULIE ELAINE SELLERS
 PROFESSIONAL ENGINEER
 NUMBER PE-2017000367
 5/5/21

BY: _____
 DATE: _____
 REV. NO. _____
 REVISIONS DESCRIPTION




DETAIL SHEET
 SITE GRADING & SITE DISTURBANCE PLANS
 THE RETREAT AT HOOK FARMS
 SECOND PLAT
 LEE'S SUMMIT, MO
 2021

drawn by: B.M.W./A.A.
 checked by: B.M.W./A.A.
 designed by: B.M.W./A.A.
 QA/QC by: J.E.S.
 project no.: A19-4059
 date: 05-05-2021

APWA KANSAS CITY METRO CHAPTER
 STANDARD DRAWING NUMBER ESC-10 ADOPTED: 10/24/2016
 SHEET C417

USER: bworthley

DWG: F:\2019\4001-4500\019-4059-A 40-Design\AutoCAD\Final Plans\Sheets\GNCV\Site Grading & Site Disturbance Plans\C_DTL01_A194059.dwg
DATE: May 05, 2021 4:36pm XREFS: C_PTBK_A194059



olsson
Olsson - Civil Engineering
Missouri Certificate of Authority #001592
1301 Burlington Street
North Kansas City, MO 64116
TEL 816.361.1177
FAX 816.361.1888
www.olsson.com

JULIE ELAINE SELLERS
Professional Engineer
NUMBER PE-2017000367
5/5/21

AMERICAN PUBLIC WORKS ASSOCIATION
KANSAS CITY METRO CHAPTER
STANDARD DRAWING NUMBER ESC-12 ADOPTED 10/24/2016
SEDIMENT BASIN - DETAILS

BY: _____
DATE: _____
REV. NO.: _____

REVISIONS DESCRIPTION

2021

LEE'S SUMMIT, MO

drawn by: B.M.W./A.A.
checked by: B.M.W./A.A.
designed by: B.M.W./A.A.
QA/QC by: J.E.S.
project no.: A19-4059
date: 05-05-2021

SHEET C418