

NOTES:

1. ALL PLANT MATERIAL SHALL BE WARRANTED FOR A MINIMUM OF ONE CALENDAR YEAR FROM THE TIME OF PROJECT COMPLETION.
2. ALL TREES SHALL RECEIVE 3" DEPTH HARDWOOD MULCH RING. SHRUBS INSTALLED SHALL INCLUDED AMENDED SOIL LIGHTLY COMPACTED IN PLACE AND 3" DEPTH HARDWOOD MULCH.
3. THE BACKFILLED SOIL WITHIN THE LILY POND WALLS SHALL BE A MIX OF 70% TOPSOIL AND 30% SAND.
4. NATIVE GRASS MIX: "LOW MOW" FROM CRITICAL SITE CONSTRUCTION PRODUCTS [CRITSITE] AT 16245 South Hwy. 71, Belton, MO 64012 [Tel: (816) 331-9738].

PLANT SCHEDULE

SYM.	QTY.	LATIN NAME	COMMON NAME	SIZE	TYPE
SHADE TREES					
GB	6	<i>Ginkgo biloba</i> 'Princeton Sentry'	Princeton Sentry Ginkgo	2"	Deciduous, shade tree
ORNAMENTAL TREES					
SM	16	<i>Syringa meyeri</i> 'Palibin' STD	Palibin Lilac	#15	Grafted, standard
SHRUBS / GRASSES / GROUNDCOVER / PERENNIALS / VINES					
IV	69	<i>Itea virginica</i> 'Sprich'	'Little Henry' Sweetspire	#3	Deciduous shrub
BG	46	<i>Bouteloua gracilis</i> 'Blonde Ambition'	Blue Grama	#1	Ornamental grass
SN	18	<i>Salvia nemorosa</i> 'Lyrical Blues'	Glossy Abelia	#1	Purple flowering perennial
LM	08	<i>Liriope muscari</i> 'Big Blue'	Big Blue Liriope	#1	Perennial
WF	36	<i>Wisteria frutescens</i>	Wisteria	Pot	Deciduous vine

