UTILITIES Electric Service Evergy Nathan Michael 913-347-4310 Nathan.michael@evergy.com

Gas Service
Spire
Katie Darnell
816-969-2247
Katie.darnell@spireenergy.com

Water/Sanitary Sewer
Water Utilities Department
1200 SE Hamblen Road
Lee's Summit, Mo 64081
Jeff Thorn
816-969-1900
jeff.thorn@cityofls.net

Communication Service AT&T Carrie Cilke 816-703-4386 cc3527@att.com

Time Warner Cable Steve Baxter 913-643-1928 steve.baxter@charter.com

Comcast Ryan Alkire 816-795-2218 ryan.alkire@cable.comcast.com

Google Fiber
Becky Davis
913-725-8745
rebeccadavis@google.com



UTILITY STATEMENT:

THE UNDERGROUND UTILITIES SHOWN HEREON ARE FROM FIELD SURVEY INFORMATION OF ONE-CALL LOCATED UTILITIES, FIELD SURVEY INFORMATION OF ABOVE GROUND OBSERVABLE EVIDENCE, AND/OR THE SCALING AND PLOTTING OF EXISTING UTILITY MAPS AND DRAWINGS AVAILABLE TO THE SURVEYOR AT THE TIME OF SURVEY. THE SURVEYOR MAKES NO GUARANTEE THAT THE UNDERGROUND UTILITIES SHOWN COMPRISE ALL SUCH UTILITIES IN THE AREA, EITHER IN SERVICE OR ABANDONED. FURTHERMORE, THE SURVEYOR DOES NOT WARRANT THAT THE UNDERGROUND UTILITIES SHOWN ARE IN THE EXACT LOCATION INDICATED ALTHOUGH HE DOES CERTIFY THAT THEY ARE LOCATED AS ACCURATELY AS POSSIBLE FROM INFORMATION AVAILABLE. THE SURVEYOR HAS NOT PHYSICALLY LOCATED THE UNDERGROUND UTILITIES BY EXCAVATION UNLESS OTHERWISE NOTED ON THIS SURVEY.

SAFETY NOTICE TO CONTRACTOR

IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICE, THE CONTRACTOR WILL BE SOLELY AND COMPLETELY RESPONSIBLE FOR CONDITIONS OF THE JOB SITE, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY DURING PERFORMANCE OF THE WORK. THIS REQUIREMENT WILL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS.

WARRANTY/DISCLAIMER


THE DESIGNS REPRESENTED IN THESE PLANS ARE IN ACCORDANCE WITH ESTABLISHED PRACTICES OF CIVIL ENGINEERING FOR THE DESIGN FUNCTIONS AND USES INTENEDED BY THE OWNER AT THIS TIME. HOWEVER, NEITHER SM ENGINEERING NOR ITS PERSONNEL CAN OR DO WARRANTY THESE DESIGNS OR PLANS AS CONSTRUCTED, EXCEPT IN THE SPECIFIC CASES WHERE SM ENGINEERING PERSONNEL INSPECT AND CONTROL THE PHYSICAL CONSTRUCTION ON A CONTEMPORARY BASIS AT THE SITE.

CAUTION- NOTICE TO CONTRACTOR

THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND, WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL THE APPROPRIATE UTILITY COMPANY AT LEAST 72 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATION OF UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH PROPOSED IMPROVEMENTS SHOWN ON THE PLANS. THE CONTRACTOR SHALL EXPOSE EXISTING UTILITIES AT LOCATIONS OF POSSIBLE CONFLICTS PRIOR TO ANY CONSTRUCTION.

FINAL DEVELOPMENT PLAN FOR LOT 7B TOWNHOMES PHASE 1 STREETS OF WEST PRYOR

LEE'S SUMMIT, MO



LOCATION MAP

LEGAL DESCRIPTION: LOT 7 & TRACT C STREET OF WEST PRYOR LOTS 1 THRU 14, TRACTS A, B, C, & D TO LEE'S SUMMIT, MO, JACKSON COUNTY MISSOURI

ALL EXISTING TOPOGRAPHIC DATA AND INFRASTRUCTURE IMPROVEMENTS SHOWN BASED ON INFORMATION BY KAW VALLEY ENGINEERING

BENCHMARKS:

#1 CHISELED "SQUARE" ON TOP OF CURB POINT OF INTERSECTION OF WEST PARK PARKING LOT AT EAST DRIVE ENTRANCE ELEVATION 985.05

#2 CHISELED "SQUARE" ON NORTHWEST CORNER AREA INLET, 25' EAST OF CURB LINE AND ON-LINE WITH SOUTH CURB OF LOWENSTEIN DRIVE AT 90° BEND IN ROAD ELEVATION 971.06

FLOODPLAIN NOTE:

SUBJECT PROPERTY IS SHOWN TO BE LOCATED IN "OTHER AREAS ZONE X" ON THE FLOOD INSURANCE RATE MAP FOR JACKSON COUNTY, MISSOURI AND INCORPORATED AREAS. COMMUNITY PANEL NO. 29095C0416G, REVISED JANUARY 20, 2017. "OTHER AREAS ZONE X" IS DEFINED AS "AREAS DETERMINED TO BE OUTSIDE THE 0.2% ANNUL CHANCE FLOODPLAIN". LOCATION DETERMINED BY A SCALED GRAPHICAL PLOT OF THE FLOOD INSURANCE RATE MAP.

INDEX OF SHEETS

- C-1 COVER SHEET
- C-2 EXISTING CONDITIONS
- C-3 OVERALL SITE PLAN
 C-4 SITE PLAN
- C-5 UTILITY PLAN
- C-6 GRADING PLAN
- C-7 EROSION CONTROL PLAN
- C-8 SANITARY LINE C
- C-9 LANDSCAPE PLAN
- C-10 LANDSCAPE PLAN C-11 DETAILS
- C-12 DETAILS

DEVELOPER

STREETS OF WEST PRYOR & VANGUARD VILLAS, LLC C/O DRAKE DEVELOPMENT, LLC 7200 W 132nd ST, SUITE 150 OVERLAND PARK, KS 66213 913-662-2630

ENGINEER

SM ENGINEERING
SAM MALINOWSKY
5507 HIGH MEADOW CIRCLE
MANHATTAN KANSAS, 66503
SMCIVILENGR@GMAIL.COM
785.341.9747

ALL CONSTRUCTION SHALL FOLLOW THE CITY OF LEE'S SUMMIT DESIGN AND CONSTRUCTION MANUAL AS ADOPTED BY ORDINANCE 5813. WHERE DISCREPANCIES EXIST BETWEEN THESE PLANS AND THE DESIGN AND CONSTRUCTION MANUAL, THE MORE STRINGENT SHALL PREVAIL.



SAMUEL D. MALINOWSKY PROFESSIONAL ENGINEEER SM Engineering

5507 High Meadow Circ

5507 High Meadow Circle Manhattan Kansas, 66503 smcivilengr@gmail.com 785.341.9747

Drawings and/or Specifications are original proprietary work and property of the Engineer and intended specifically for this project. Use of items contained herein without consent of the Engineeris prohibited. Drawings illustrate best information available to the Engineer. Fie verification of actual elements, conditions and dimensions is required.

Revisions 8-19-21 CITY COMMENTS

9-13-21 CITY COMMENTS


REETS OF W. PRYOR B TOWNHOMES PHASE Lee's SUMMITT, MO.

sheet


Civil

Site Improvement PLan


permit 8 JULY 2021



Manhattan Kansas, 66503



sheet




Site Data																
		LOT AREA	LOT AREA	BLDG AREA SF		NUMBER OF	DWELLING UNITS	# OF		PARKING	PARKING	ADA SPACES	ADA SPACES	PAVEMENT	IMPERVIOUS	OPEN
LOT	USE	(SF)	ACRES	(ENVELOPE)	TOTAL SF	DWELLING UNITS	PER ACRE	FLOORS	3 BDRM	REQUIRED	PROVIDED	REQ (VAN)	PROV (VAN)	AREA (SF)	COVERAGE	SPACE
Lot 7B Phase 1	Townhomes	86,249	1.98	19,494	38,988	18	9.4	2	18	41	47	*1(1)	* 0	22,271	41,765	44,484
* BASED ON NUMBER OF VISITOR PARKING REQUIRED FOR BOTH PHASES. ADA SPACE IS IN PHASE 2																

5507 High Meadow Circle Manhattan Kansas, 66503 smcivilengr@gmail.com 785.341.9747

SM Engineering

Drawings and/or Specifications are original proprietary work and property of the Engineer and intended specifically for this project. Use of items contained herein without consent of the Engineeris prohibited. Drawings illustrate best information available to the Engineer. Field verification of actual elements, conditions, and dimensions is required.




Revisions 8-19-21 CITY COMMENTS 9-13-21 CITY COMMENTS


STREETS OF W. PRYOR OT 7B TOWNHOMES PHASE 1

sheet

Civil SITE PLAN permit 8 JULY 2021

1"=20' 0 10' 20'






5507 High Meadow Circle Manhattan Kansas, 66503

5507 High Meadow Circle Manhattan Kansas, 66503 smcivilengr@gmail.com 785.341.9747

Drawings and/or Specifications are original proprietary work and property of the Engineer and intended specifically for this project. Use of items contained herein without consent of the Engineeris prohibited. Drawings illustrate best information available to the Engineer. Field verification of actual elements, conditions, and dimensions is required.



Revisions 8-19-21 CITY COMMENTS 9-13-21 CITY COMMENTS

STREETS OF W. PRYOR LOT 7B TOWNHOMES PHASE 1
Left summit, MO.

Sheei


Civil

GRADING PLAN

permit

8 JULY 2021

1"=30' 0 15' 30'



- 2. REMOVE EXISTING PAVEMENT AND INSTALL TEMPORARY CONSTRUCTION ENTRANCE AS SHOWN
- 3. INSTALL EROSION CONTROL MEASURES AS SHOWN PRIOR TO BEGINNING PAVEMENT REMOVAL.
- 4. REMOVE EROSION CONTROL MEASURES AFTER VEGETATION HAS BEEN ESTABLISHED PER NOTES BELOW.

EROSION CONTROL NOTES

- 1. THE CONTRACTOR SHALL PROVIDE ALL MATERIALS, TOOLS, EQUIPMENT, AND LABOR AS NECESSARY TO INSTALL AND MAINTAIN ADEQUATE EROSION CONTROL, KEEP THE STREETS CLEAN OF MUD AND DEBRIS, AND PREVENT SOIL FROM LEAVING THE PROJECT SITE. THE CONTRACTOR'S EROSION CONTROL MEASURES SHALL CONFORM TO THE CITY OF LEE'S SUMMIT CRITERIA
- 2. THE CONTRACTOR SHALL INSTALL SILT FENCE, CONSTRUCTION ENTRANCE AND FILTER SOCKS AS SHOWN PRIOR TO STARTING ANY CONSTRUCTION ACTIVITY
- 3. EXCAVATED MATERIAL THAT IS NOT IMMEDIATELY LOADED AND HAULED OFF SITE SHALL BE STOCKPILED ON SITE. CONTRACTOR SHALL PROVIDE WADDLES OR OTHER SIMILAR MEASURE FULLY SURROUNDING THE STOCKPILE AREA TO PROTECT ADJACENT INLETS OR AREAS, UNTIL SUCH TIME THAT STOCKPILE IS REMOVED FROM THE SITE.
- 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ADDITIONAL EROSION CONTROL MEASURES OR MODIFICATIONS IF THE PLAN FAILS TO SUBSTANTIALLY CONTROL EROSION OR OFFSITE SEDIMENTATION.
- 5. THE CONTRACTOR SHALL INSPECT EROSION CONTROL DEVICES EVERY 7 DAYS AND WITHIN 24 HOURS OF A STORM OF 0.5 INCHES OR MORE. THE CONTRACTOR SHALL REPAIR DAMAGE, CLEAN OUT SEDIMENT, AND ADD ADDITIONAL EROSION CONTROL DEVICES AS NEEDED, AS SOON AS PRACTICABLE AFTER INSPECTION.
- 6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING EROSION CONTROL DEVICES AND REMOVING SEDIMENT UNTIL A MINIMUM OF 70% OF PERMANENT VEGETATION HAS BECOME STABILIZED AND ESTABLISHED. EROSION CONTROL DEVICES SHALL REMAIN IN PLACE UNTIL THE 70% ESTABLISHED VEGETATION IS MET, OR THE DURATION OF THE PROJECT, WHICHEVER IS THE LATER DATE.

— II— SILT FENCE




INLET PROTECTION

1"=30' 0 15' 30' 5507 High Meadow Circle Manhattan Kansas, 66503 smcivilengr@gmail.com

SM Engineering

785.341.9747

Drawings and/or Specifications are original proprietary work and property of the Engineer and intended specifically for this project. Use of items contained herein without consent of the Engineeris prohibited. Drawings illustrate best information available to the Engineer. Field verification of actual elements, conditions, and dimensions is required.



Revisions 8-19-21 CITY COMMENTS 9-13-21 CITY COMMENTS

7


LOT 7B TOWNHOMES PHASE

sheet


Civil

EROSION CONTROL

permit 8 JULY 2021



NOTE: COMPACTED FILL SHALL BE PLACED TO A MINIMUM OF 18" ABOVE THE TOP OF THE PIPE PRIOR TO INSTALLATION




1010 1010 Sta. 3+46.67, SANITARY 4' Dia. PRIVATE MH, C-2 Top Elev. = 987.37 Sta. 9+22.09, SANITARY I 4' Dia. PUBLIC MH, A-5 Top Elev. = 983.00 1000 1000 STA 0+99.89, PRIVATE LINE C STORM LINE G F/L 980.54 990 990 980 980 PROPOSED GRADE 102.03 LF 6:000 Slope 8" PVC Pipe 8" PVC Pipe 8" PVC Pipe 16:000 Slope EXISTING GRADE 970 970 244.64 LF F/L OUT (NW): 975 F/L IN (E): 975.82 F/L IN (S): 976.00 8" PVC Pipe @ 1.25% Slope LIMITS OF COMPACTED 960 960 FILL SEE NOTE SANITARY LINE C 950 950 0+00 0+50 3+50 4+00 -0+50 1+00 1+50 2+00 2+50 3+00

		TABLE (OF SERVICE	LOCATI	ONS	
			LINE C	;		
STUB	CONNECTION TYPE	STATION	DIST. FROM D.S. M.H.	STUB LENGTH	FLOW AT MAIN	END OF STUB ELEVATION
1	"Y"	0+85.12	85'	15'	977.06	977.36
2	"Y"	3+10.22	66′	15'	980.97	981.27
3	"Y"	3+35.22	91	20'	981.62	982.02
		ALL SERVICE CO				

5507 High Meadow Circle Manhattan Kansas, 66503

Manhattan Kansas, 66503 smcivilengr@gmail.com 785.341.9747

Drawings and/or Specifications are original proprietary work and property of the Engineer and intended specifically for this project. Use of items contained herein without consent of the Engineeris prohibited. Drawings illustrate best information available to the Engineer. Field verification of actual elements, conditions, and dimensions is required.



Revisions 8-19-21 CITY COMMENTS 9-13-21 CITY COMMENTS

STREETS OF W. PRYOR OT 7B TOWNHOMES PHASE 1 Lee's SUMMIT, MO.

sheet


Civil


SANITARY LINE C

PLAN AND PROFILE

permit

8 JULY 2021





As Shown

As Shown

As Shown

As Shown

Skyline Honeylocust

Golden Raintree

Golden Raintree

Canaert Juniper

Gleditsia Triacanthos 'Skyline'

Juniperus Virginiana 'Canaertii'

Koelreuteria Paniculata

Koelreuteria Paniculata

3" cal

3"cal

3"cal

8' ht

SHADE

SHRUB

ORNAMENTAL

BLACK TWIG CIRCLE

STREET TREES 1/30'

EVERGREEN

REQUIRED:

PROVIDED: **SHADE TREES**

SHRUBS

SHRUBS 2/20'

= 4

= 10

628'

= 63

= 14

= 43

LANDSCAPE NOTES

CONTRACTOR REQUIRED TO LOCATE ALL UTILITIES BEFORE INSTALLATION TO BEGIN.

Contractor shall verify all landscape material quantities and shall report any discrepancies to the Landscape Architect prior to installation.

No plant material substitutions are allowed without Landscape Architect or Owners

Contractor shall guarantee all landscape work and plant material for a period of one year from date of acceptance of the work by the Owner. Any plant material which dies during the one year guarantee period shall be replaced by the contractor during normal planting seasons.

Contractor shall be responsible for maintenance of the plants until completion of the job and acceptance by the Owner.

All plant material shall be specimen quality stock as determined in the "American Standards For Nursery Stock" published by The American Association of Nurseryman, free of plant diseases and pest, of typical growth of the species and having a healthy, normal root system.

Sizes indicated on the plant list are the minimum, acceptable size. In no case will sizes less than specified be accepted.

All shrub beds within lawn areas to receive a manicured edge.

All shrub beds shall be mulched with 6" of shredded cedar mulch with weed mat.

All areas to be fertilized & sodded with a Turf-Type-Tall Fescue seed blend.

- 1. Successful landscape contractor shall be responsible for design that complies with minimum irrigation requirements, and installation of an irrigation system. Irrigation system to be approved by the owner before starting any installation.
- 2. Irrigation system shall provide a constant on on zone for fountain
- 3. Irrigation controller to be mounted on outside wall of building. Provide temporary support prior to building construction.
- 4. Landscaping along Lowenstien shall not be irrigated.

MOWING NOTE

1. Contractor shall be responsible for the first 2 mowings of all areas of grass.

150' SIGHT TRIANGLE

64,529sf OPEN SPACE

1 / 5,000sf = 13 PROVIDED SHADE TREES **ORNAMENTALS**

REQUIRED

OPEN SPACE SHRUBS REQUIRED = 26 2 / 5,000sf PROVIDED = 30

Free Standing Against Wall Transformer

Typical Utility Box Screening Details


UTILITY BOXES SHALL BE CLUSTERED AS MUCH AS POSSIBLE

No Scale





Small Box




LANDSCAPE PLAN 0 15' 30'

SM Engineering 5507 High Meadow Circle Manhattan Kansas, 66503 smcivilengr@gmail.com

> wings and/or Specifications are original proprietary work and property of the Engineer and intended specifically for this project. Use of items contained herein without consent of the Engineeris prohibited. Drawings illustrate best nation available to the Engineer. Field rification of actual elements, conditions, and dimensions is required.

785.341.9747





Revisions 8-19-21 CITY COMMENTS 9-13-21 CITY COMMENTS


7 20 WNHOME LEE'S SUMMITT, MO.


shee C9.0 Civil

> permit 8 JULY 2021









CONTRACTION JOINTS SPACED @ 5'-0" CNTRS 5-0' Alig a same a a same **TYP** SECTION A-A BASE COURSE TO BE COMPACTED TO 90% NOTE: WHERE SIDEWALKS ARE INTEGRAL STD. PROCTOR (TYP) WITH DRIVE ENTRANCES INCREASE DEPTH TO 6" AND PROVIDE REINFORCING USING 6x6 #10 WIRE MINIMUM. SLOPE 2% TOWARD STREET SEE SITE PLAN 3/8" R

CONCRETE SIDEWALK CW2

SECTION B-B

NOTE: CONCRETE SHALL BE CLASS A WITH f'c = 3000 PSI.

1/2"-3/4" CLEAN AGGREGATE, HAND TAMPED OR MECHANICALLY COMPACTED IN MAX. 4" LIFTS INITIAL BACKFILL -UNDER PAVED AREAS OR WITHIN 4" HORIZONTAL OF PAVED AREAS

COMPACTED IN MAX. 4" LIFTS -UNDER OPEN AREAS 1/2"-3/4" CLEAN AGGREGATE, HAND TAMPED OR MECHANICALLY

1/2"-3/4" CLEAN AGGREGATE, HAND TAMPED OR MECHANICALLY


COMPACTED IN MAX. 4" LIFTS FINAL BACKFILL

-UNDER PAVED AREAS OR WITHIN 4" HORIZONTAL OF PAVED AREAS ON-SITE OR IMPORTED MATERIAL FREE OF MUCK, FROZEN MATERIAL, EXCESS MOISTURE, ORGANICS, TOPSOIL, RUBBISH, CONSTRUCTION DEBRIS, ROCK OR BRICK LARGER THAN 8". COMPACTED TO 95% OF STANDARD DENSITY PER ASTM D-698 -UNDER OPEN AREAS ON-SITE OR IMPORTED MATERIAL FREE OF MUCK, FROZEN MATERIAL, EXCESS MOISTURE, ORGANICS, TOPSOIL, RUBBISH,

> CONSTRUCTION DEBRIS, ROCK OR BRICK LARGER THAN 8". COMPACTED TO 90% OF STANDARD DENSITY PER ASTM D-698

BEDDING DEPTH BELOW PIPE PIPE DIAMETER IN SOIL IN ROCK 24" AND LESS

27" THRU 60"



PIPE BEDDING DETAIL NOT TO SCALE

5507 High Meadow Circle Manhattan Kansas, 66503 smcivilengr@gmail.com 785.341.9747

SM Engineering

rawings and/or Specifications are original proprietary work and property of the Engineer and intended specifically for this project. Use of items contained herein without consent of the Engineeris prohibited. Drawings illustrate best ormation available to the Engineer. Field erification of actual elements, conditions, and dimensions is required.


Revisions 8-19-21 CITY COMMENTS 9-13-21 CITY COMMENTS


 \searrow


shee


DETAILS permit

8 JULY 2021









s h e e

DETAILS

permit 8 JULY 2021

SM Engineering

785.341.9747

without consent of the Engineeris

prohibited. Drawings illustrate best

and dimensions is required.

Revisions

STANDARD DRAWING

10/24/2016

NUMBER ESC-03

ADOPTED:

SILT FENCE

Modified from 2015 Overland Park Standard Details