

### Village Multi-Family Mass Grading Engineer's Estimate

<b>Item No.</b>	<b>Description</b>	<b>Unit</b>	<b>Approx. Unit Quantity</b>	<b>Unit Price</b>	<b>Unit Total</b>
1	Mobilization	LS	1	\$20,000.00	\$20,000.00
2	Fill (Unadjusted)	CY	26,922	\$4.00	\$107,688.00
3	Cut (Unadjusted)	CY	2,507	\$10.00	\$25,070.00
4	Sediment Fence	LF	1,803	\$2.00	\$3,606.00
5	Inlet Protection	EA	3	\$100.00	\$300.00
6	Straw Wattle	LF	861	\$2.00	\$1,722.00
7	Temporary Construction Entrance	EA	1	\$1,000.00	\$1,000.00
8	Curb Inlet - 6'x4'	EA	2	\$7,500.00	\$15,000.00
9	Storm Manhole - 6' Dia.	EA	1	\$5,500.00	\$5,500.00
10	Storm Manhole - 6' Dia. Shallow w/Grate	EA	1	\$6,500.00	\$6,500.00
11	24" RCP	LF	218	\$125.00	\$27,250.00
12	30" RCP	LF	220	\$140.00	\$30,800.00
13	24" RCP Headwall w/ Conc. Toewall and Flapgate	EA	1	\$10,000.00	\$10,000.00
14	30" RCP Headwall w/ Conc. Toewall and Flapgate	EA	1	\$14,500.00	\$14,500.00
15	Riprap (D50=12")	SY	59	\$85.00	\$5,015.00
16	Seeding (Temporary)	LS	1	\$5,000.00	\$5,000.00
17	Retaining Wall	SF	3,951	\$45.00	\$177,795.00
	<b>Total</b>				<b>\$456,746.00</b>