

DWG: F:\2020\0001-0500\020-0103\40-Design\AutoCAD\Final Plans\Sheets\GNV\CONSTRUCTION DOCUMENTS\C\_GEN01\_0200103.dwg  
DATE: Dec 01, 2021 6:52am XREFS: C\_XBASE\_0200103 C\_PBASE\_0200103 C\_PBLK\_0200103 T\_PAS\_0200103 V\_XALT\_00103  
USER: bkimmich

Sheet List Table		
Sheet Number		Sheet Title
C1000		COVER SHEET
C1001		GENERAL NOTES
C1002		GENERAL LAYOUT PLAN
C1003		SITE DIMENSION PLAN
C1004		SITE DIMENSION PLAN
C1005		SITE DIMENSION PLAN
C1006		SITE DIMENSION PLAN
C1007		SITE DIMENSION PLAN
C1008		SITE DIMENSION PLAN
C1009		SITE DIMENSION PLAN
C1010		SITE DIMENSION PLAN
C1011		SITE DIMENSION PLAN
C1012		GRADING PLAN
C1013		GRADING DETAILS
C1014		GRADING DETAILS
C1015		GRADING DETAILS
C1016		GRADING DETAILS
C1017		GRADING DETAILS
C1018		GRADING DETAILS
C1019		GRADING DETAILS
C1020		GRADING DETAILS
C1021		GRADING DETAILS
C1022		GRADING DETAILS
C1022A		GRADING DETAILS
C1023		GRADING DETAILS
C1024		GRADING DETAILS
C1025		GRADING DETAILS
C1025A		GRADING DETAILS
C1026		UTILITY PLAN
C1026A		UTILITY PLAN
C1027		UTILITY PLAN
C1028		UTILITY PLAN
C1028A		FIRE PROTECTION PROFILES
C1028B		FIRE PROTECTION PROFILES
C1028C		SANITARY SEWER SERVICE PROFILES
C1029		STORM SEWER PLAN & PROFILE - LINE A
C1030		STORM SEWER PLAN & PROFILE - LINE A
C1030A		STORM SEWER PLAN & PROFILE - LINE B
C1031		STORM SEWER PLAN & PROFILE - LINE C
C1032		STORM SEWER PLAN & PROFILE - LINE C
C1033		STORM SEWER PLAN & PROFILE - LINE CC
C1034		STORM SEWER PLAN & PROFILE - LINE D
C1035		STORM SEWER PLAN & PROFILE - LINE E
C1036		STORM SEWER PLAN & PROFILE - LINE E
C1037		STORM SEWER PLAN & PROFILE - LINE E
C1038		STORM SEWER PLAN & PROFILE - LINE E
C1039		STORM SEWER PLAN & PROFILE - LINE F
C1040		STORM SEWER PLAN & PROFILE - LINE F
C1041		STORM SEWER PLAN & PROFILE - LINE G
C1042		STORM SEWER PLAN & PROFILE - LINE G AND GG
C1043		STORM SEWER PLAN & PROFILE - LINE G
C1044		STORM SEWER PLAN & PROFILE - LINE H AND J
C1045		STORM SEWER PLAN & PROFILE - LINE K AND L
C1046		STORM SEWER PLAN & PROFILE - LINE M AND N
C1047		DRAINAGE PLAN
C1048		DRAINAGE CALCULATIONS - 100 YEAR
C1049		DRAINAGE CALCULATIONS - 10 YEAR
C1050		STANDARD DETAILS
C1051		STANDARD DETAILS
C1052		STANDARD DETAILS
C1053		STANDARD DETAILS
C1054		STANDARD DETAILS
C1055		STANDARD DETAILS
C1056		STANDARD DETAILS
C1057		STANDARD DETAILS
C1058		STANDARD DETAILS
C1058A		STANDARD DETAILS
C1059		DETENTION BASIN DETAIL
C1060		DETENTION BASIN DETAIL
C1061		DETENTION BASIN DETAIL




NOT TO SCALE

LEGAL DESCRIPTION:

All that part of Northeast Quarter of Section 16, Township 47 North, Range 31 West, in the City of Lee's Summit, Jackson County, Missouri, as described by Timothy Blair Wiswell, Missouri Professional Licensed Surveyor, PLS-2009000067, and being more particularly described as follows:

COMMENCING at the Northwest corner of the Northeast Quarter, of said Section 16-T47N-R31W; thence South 02 degrees 20 minutes 19 seconds West, along the West line of said Northeast Quarter, a distance of 20.00 feet, to a point on the South Right-of-Way line of Bailey Road as now established, said point also being the Northeast corner of Lot 164 of Newberry Second Plat, Lots 1-65, 163 and 164, a subdivision in the City of Lee's Summit, Jackson County, Missouri; thence South 88 degrees 07 minutes 48 seconds East, on the South Right-of-Way line of said Bailey Road, a distance of 1,350.00 feet, to a point; thence South 35 degrees 20 minutes 58 seconds West, departing the South Right-of-Way line of said Bailey Road, a distance of 517.08 feet, to a point; thence South 07 degrees 56 minutes 53 seconds West, a distance of 320.18 feet, to a point; thence South 12 degrees 12 minutes 42 seconds West, a distance of 1,168.07 feet, to a point; thence South 27 degrees 41 minutes 50 seconds West, a distance of 480.35 feet, to a point on a line that is 300.00 feet North of and parallel to the South line of said Northeast Quarter; thence North 88 degrees 04 minutes 43 seconds West, on said parallel line, a distance of 630.96 feet, to a point on the West line of said Northeast Quarter, said point also being on the East line of Newberry Fourth Plat, a subdivision in the City of Lee's Summit, Jackson County, Missouri; thence North 02 degrees 20 minutes 19 seconds East, on the West line of said Northeast Quarter, and on the East line of said Newberry Fourth Plat, and on the East line of Newberry Third Plat, a subdivision in the City of Lee's Summit, Jackson County, Missouri, and on the East line of said Newberry Second Plat, Lots 1-65, 163 and 164, a distance of 2,330.63 feet, to the POINT OF BEGINNING, containing 2,250,248 square feet or 51.6586 acres, more or less.

DEVELOPMENT TEAM CONTACT INFORMATION	
OWNER/DEVELOPER	
KYLE GORRELL DIRECTOR, LEE'S SUMMIT SCHOOL DISTRICT	502 SE TRANSPORT DRIVE LEE'S SUMMIT, MO 64081 816.986-2420
CIVIL ENGINEER	
TERRY PARSONS OLSSON	7301 W. 133RD STREET SUITE 200 OVERLAND PARK, KS 66213 PH: 913.381.1170 FAX: 913.381.1174 tparsons@olsson.com



SECTION 16, T.47N., R.31W.  
VICINITY MAP  
SCALE: 1" = 2000'

DWG: F:\2020\0001-0500\020-0103\40-Design\AutoCAD\Final Plans\Sheets\GNVC\CONSTRUCTION DOCUMENTS\C\_GEN01\_0200103.dwg  
DATE: Dec 01, 2021 6:52am XREFS: C:\XBASE\_0200103 C:\PBLK\_0200103 T\_PBASE\_0200103 T\_PASAS\_0200103 V\_XALT\_00103 USER: blumlich

GENERAL NOTES:

1. THE EXISTING UTILITY LOCATIONS SHOWN ON THE PLANS ARE APPROXIMATE AND MAY NOT INCLUDE ALL LINES PRESENT. THE CONTRACTOR SHALL BE RESPONSIBLE TO CALL 1-800-DIG-RITE, 1(800)344-7483 OR 811 AND COORDINATE FIELD LOCATION OF EXISTING UNDERGROUND UTILITIES PRIOR TO BEGINNING GRADING ACTIVITIES. 11STOP! CALL BEFORE YOU DIG!
2. THE CONTRACTOR SHALL NOT CHANGE OR DEViate FROM THE PLANS WITHOUT FIRST OBTAINING WRITTEN APPROVAL FROM THE OWNER AND ENGINEER.
3. ALL WORK AND MATERIALS SHALL BE SUBJECT TO INSPECTION AND APPROVAL BY THE OWNER OR THE OWNER'S REPRESENTATIVE.
4. ALL ESTIMATES OF QUANTITIES ARE FOR INFORMATION PURPOSES ONLY. CONTRACTOR AND SUBCONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING ALL QUANTITIES AND FOR BRINGING THE PROJECT TO THE LINES AND GRADES SHOWN HEREIN. CONTRACTOR SHALL PROVIDE ALL WORK AND MATERIALS REQUIRED TO FULFILL THE PLANS IT IS THE CONTRACTOR'S SOLE RESPONSIBILITY TO DETERMINE EARTHWORK QUANTITIES AND TO ACCOUNT FOR HAUL IN OR HAUL OFF OF MATERIAL AS NECESSARY TO MEET THE LINES AND GRADES OF THE PLANS EVEN IF QUANTITY ESTIMATES ARE SHOWN WITHIN THESE DOCUMENTS. NO ADDITIONAL PAYMENTS WILL BE MADE FOR IMPORT OR EXPORT OF MATERIAL OR FOR ADJUSTMENTS TO QUANTITY ESTIMATES.
5. ALL CONSTRUCTION SHALL CONFORM TO THE LATEST STANDARDS AND SPECIFICATIONS OF THE AMERICAN PUBLIC WORKS ASSOCIATION -- KANSAS CITY METROPOLITAN CHAPTER (APWA-KC) AND THE CITY OF LEE'S SUMMIT, MO, EXCEPT WHERE SHOWN OTHERWISE. NOTIFY ENGINEER OF DISCREPANCIES.
6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL REQUIRED PERMITS, PAYING ALL FEES AND FOR OTHERWISE COMPLYING WITH ALL APPLICABLE REGULATIONS GOVERNING THE WORK.
7. THE CONTRACTOR SHALL ADHERE TO THE PROVISIONS OF MISSOURI STATE LAW WHICH REQUIRES THAT ANY PERSON OR FIRM DOING EXCAVATION ON PUBLIC RIGHT--OF-WAY DO SO ONLY AFTER GIVING NOTICE TO, AND OBTAINING INFORMATION FROM UTILITY COMPANIES.
8. PRIOR TO COMMENCEMENT OF WORK, THE CONTRACTOR SHALL NOTIFY ALL THOSE COMPANIES WHICH HAVE FACILITIES IN THE NEAR VICINITY OF THE CONSTRUCTION TO BE PERFORMED.
9. THE CONTRACTOR SHALL LIMIT THE REMOVAL OF TREES TO THE LIMITS OF DEMOLITION SHOWN ON THE DEMOLITION PLAN.
10. CLEARING AND GRUBBING OPERATIONS AND DISPOSAL OF ALL DEBRIS THEREFROM SHALL BE PERFORMED BY THE CONTRACTOR IN STRICT ACCORDANCE WITH ALL LOCAL CODES AND ORDINANCES.
11. ALL WASTE MATERIAL RESULTING FROM THE PROJECT SHALL BE DISPOSED OF OFF-SITE BY THE CONTRACTOR.
12. ALL MANHOLES, CATCH BASINS, UTILITY VALVES AND METER PITS ARE TO BE ADJUSTED OR REBUILT TO GRADE AS REQUIRED.
13. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONTROL OF SURFACE EROSION DURING CONSTRUCTION AND UNTIL THE OWNER ACCEPTS THE WORK AS COMPLETE. EROSION CONTROL MEASURES INCLUDING, BUT NOT LIMITED TO, THE SILT FENCES AND GRAVEL FILTER BAGS SHOWN ON THE EROSION CONTROL PLAN SHALL BE IN PLACE FOR THE DURATION OF THE SITE IMPROVEMENTS.
14. ALL HDPE PIPE SHALL BE ADS (N-12) OR APPROVED EQUAL, AND CONFORM TO AASHTO M294 SPECIFICATIONS. ALL PIPE LENGTHS ARE MEASURED FROM CENTER OF STRUCTURE TO CENTER OF STRUCTURE.
15. IF PRECAST CONCRETE STORM SEWER STRUCTURES ARE TO BE USED ON THIS PROJECT, THE CONTRACTOR SHALL SUBMIT SHOP DRAWINGS AND HAVE THEM APPROVED BY THE ENGINEER PRIOR TO FABRICATION OF THE STRUCTURES. FAILURE TO DO SO SHALL BE CAUSE FOR REJECTION.
19. EXISTING TOPSOIL SHALL BE STRIPPED TO A POINT WHERE ALL VEGETATION IS REMOVED. REFER TO THE GEOTECHNICAL REPORT PROVIDED BY CFS ENGINEERS, PROJECT NO. 20-1074 AND DATED JUNE 8, 202 AND ALL ADDENDUMS FOR ADDITIONAL REQUIREMENTS.
20. THE CONTRACTOR SHALL, BY HIS OWN INVESTIGATION, AND PRIOR TO COMMENCING WORK, SATISFY HIMSELF AS TO THE SURFACE AND SUBSURFACE CONDITIONS TO BE ENCOUNTERED.
21. THE CONTRACTOR IS RESPONSIBLE FOR THE PROTECTION OF ALL BOUNDARY CORNERS AND SECTION CORNERS. ANY BOUNDARY CORNER AND/OR SECTION CORNER DISTURBED OR DAMAGED BY CONSTRUCTION ACTIVITIES SHALL BE RESET BY A LAND SURVEYOR LICENSED IN THE STATE OF MISSOURI, AT THE CONTRACTOR'S EXPENSE.
22. NO FEDERALLY OWNED MAILBOX MAY BE DISTURBED. THE CONTRACTOR SHALL GIVE AT LEAST TWENTY-FOUR (24) HOURS ADVANCE NOTICE TO THE MANAGER OF DELIVERY AND COLLECTIONS. TAMPERING WITH FEDERAL MAIL FACILITIES MAY SUBJECT THE CONTRACTOR TO PROSECUTION BY THE FEDERAL GOVERNMENT.
23. THE CONTOUR LINES SHOWN ARE FOR MASS GRADING PURPOSES.
24. EXISTING CONTOURS REPRESENT MASS FINISH GRADE ELEVATIONS.
25. THE CONTRACTOR SHALL FINISH GRADE SLOPES AS SHOWN NO STEEPER THAN 1 FOOT VERTICAL IN 3 FEET HORIZONTAL UNLESS OTHERWISE SHOWN BY CONTOURS OR SPOT ELEVATIONS.
26. THE CONTRACTOR SHALL GRADE LANDSCAPED AREAS TO PROVIDE POSITIVE DRAINAGE IN THE BORROW AREA.
27. THE CONTRACTOR SHALL MAKE HIS OWN ASSUMPTIONS ON THE LOCATION AND CONSISTENCY OF ANY EXISTING ROCK LAYERS UNDERLYING THE PROJECT SITE. ALL ROCK EXCAVATION AND REMOVAL SHALL BE INCLUDED IN THE CONTRACTORS' BID.
28. CONTRACTOR TO FIELD VERIFY ELEVATIONS AND LOCATIONS OF EXISTING UTILITIES AND INFRASTRUCTURE PRIOR TO CONSTRUCTION. NOTIFY ENGINEER OF ANY DISCREPANCIES BETWEEN PLANS AND FIELD CONDITIONS.
29. BY ACCEPTING AND UTILIZING ANY ELECTRONIC FILE OF ANY DRAWING, REPORT OR DATA TRANSMITTED BY OLSSON (OLSSON), THE RECIPIENT AGREES FOR ITSELF, ITS SUCCESSORS, ASSIGNS, INSURERS AND ALL THOSE CLAIMING UNDER OR THROUGH IT, THAT BY USING ANY OF THE INFORMATION CONTAINED IN THE ELECTRONIC FILE, ALL USERS AGREE TO BE BOUND BY THE FOLLOWING TERMS. ALL OF THE INFORMATION CONTAINED IN THIS ELECTRONIC FILE IS THE WORK PRODUCT AND INSTRUMENT OF SERVICE OF OLSSON, WHO SHALL BE DEEMED THE AUTHOR, AND SHALL RETAIN ALL COMMON LAW, STATUTORY LAW AND OTHER RIGHTS, INCLUDING COPYRIGHTS, UNLESS THE SAME HAVE PREVIOUSLY BEEN TRANSFERRED IN WRITING TO THE RECIPIENT. THE INFORMATION CONTAINED IN THE ELECTRONIC FILE IS PROVIDED FOR THE CONVENIENCE OF THE RECIPIENT AND IS PROVIDED IN "AS IS" CONDITION. THE RECIPIENT IS AWARE THAT DIFFERENCES MAY EXIST BETWEEN THE ELECTRONIC FILES AND THE PRINTED HARD-COPY ORIGINAL SIGNED AND SEALED DRAWINGS OR REPORTS. IN THE EVENT OF A CONFLICT BETWEEN THE SIGNED AND SEALED ORIGINAL DOCUMENTS PREPARED BY OLSSON AND THE ELECTRONIC FILES TRANSFERRED HEREWTH, THE SIGNED AND SEALED ORIGINAL DOCUMENTS SHALL GOVERN. OLSSON SPECIFICALLY DISCLAIMS ALL WARRANTIES, EXPRESSED OR IMPLIED, INCLUDING WITHOUT LIMITATION, ANY WARRANTY OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE, WITH RESPECT TO ELECTRONIC FILES. IT SHALL BE THE RECIPIENT'S RESPONSIBILITY TO CONFIRM THE ACCURACY OF THE INFORMATION CONTAINED IN THE ELECTRONIC FILE AND THAT IF ACCURATELY REFLECTS THE INFORMATION NEEDED BY THE RECIPIENT. THE RECIPIENT SHALL NOT RETRANSMIT THE ELECTRONIC FILE, OR ANY PORTION THEREOF, WITHOUT INCLUDING THIS DISCLAIMER AS PART OF ANY SUCH TRANSMISSION. IN ADDITION, THE RECIPIENT AGREES, TO THE FULLEST EXTENT PERMITTED BY LAW, TO INDEMNIFY AND HOLD HARMLESS OLSSON, ITS OFFICERS, DIRECTORS, EMPLOYEES AND SUBCONSULTANTS AGAINST ANY AND ALL DAMAGES, LIABILITIES, CLAIMS OR COSTS, INCLUDING REASONABLE ATTORNEY'S AND EXPERT WITNESS FEES AND DEFENSE COSTS, ARISING FROM ANY CHANGES MADE BY ANYONE OTHER THAN OLSSON OR FROM ANY REUSE OF THE ELECTRONIC FILES WITHOUT THE PRIOR WRITTEN CONSENT OF OLSSON.
30. DESIGN PROFESSIONAL SHALL REVIEW SHOP DRAWINGS OR SAMPLES FOR GENERAL CONFORMANCE WITH THE DESIGN CONCEPTS ON THE PROJECT AND FOR COMPLIANCE WITH THE INFORMATION GIVEN IN THE CONTRACT DOCUMENTS, AND SHALL NOT EXTEND TO MEANS OR METHODS OF CONSTRUCTION. THE DESIGN PROFESSIONAL'S REVIEW SHALL NOT RELIEVE CONTRACTOR FROM RESPONSIBILITY FOR ANY VARIATION FROM THE REQUIREMENTS OF THE CONTRACT DOCUMENTS UNLESS CONTRACTOR HAS IN WRITING CALLED DESIGN PROFESSIONAL'S ATTENTION TO EACH SUCH VARIATION AT THE TIME OF SUBMISSION, AND DESIGN PROFESSIONAL HAS GIVEN WRITTEN APPROVAL OF EACH SUCH VARIATION BY SPECIFIC WRITTEN NOTATION THEREOF INCORPORATED INTO OR ACCOMPANYING THE SHOP DRAWING OR SAMPLE, NOR WILL ANY APPROVAL BY THE DESIGN PROFESSIONAL RELIEVE CONTRACTOR FROM RESPONSIBILITY FOR ERRORS OR OMISSIONS IN SHOP DRAWINGS WITH CONFORMANCE TO CONTRACT DOCUMENTS.
31. GENERAL CONSTRUCTION NOTE REGARDING SEQUENCING OF EROSION CONTROL -- ALL PERIMETER SILT FENCE, EARTH DIKES, SEDIMENT BASINS, AND ROCK CONSTRUCTION ENTRANCES WILL BE INSTALLED BEFORE GRADING OPERATIONS BEGIN, EXCEPT THAT SILT FENCE WHICH IS TO BE PLACED ALONG THE BACK OF CURB FOR PROTECTION OF THE STREET, SILT FENCE AND EARTH DIKES THAT ARE PLACED BEFORE GRADING BEGINS WILL BE MAINTAINED BY THE GRADING CONTRACTOR UNTIL ALL UTILITIES ARE IN PLACE, THE SILT FENCE THAT IS PLACED ALONG THE BACK OF THE CURB OR RIGHT --OF-WAY WILL BE INSTALLED IMMEDIATELY AFTER THE CURB IS CONSTRUCTED. EROSION AND SEDIMENTATION CONTROLS ARE TEMPORARY AND MUST BE REMOVED BY THE CONTRACTOR AFTER CONSTRUCTION IS COMPLETE AND THE DISTURBED AREA IS AT LEAST 70% PERMANENTLY VEGETATED.
32. HANDICAP PARKING STALLS SHALL BE SIGNED WITH CITY/ADA APPROVED SIGNAGE AND CONSTRUCTED IN STRICT ACCORDANCE WITH THE LATEST STANDARDS AND SPECIFICATIONS OF THE APWA-KC, CITY OF LEE'S SUMMIT ADA STANDARDS, AND SHALL NOT EXCEED 2.00 PERCENT IN ANY DIRECTION. ACCESSIBLE SIDEWALKS HAVE A MAXIMUM CROSS SLOPE OF 2 PERCENT AND A MAXIMUM LONGITUDINAL SLOPE OF 5 PERCENT.
33. ALL WATER LINES SHALL BE INSTALLED PER THE LATEST STANDARDS AND SPECIFICATIONS OF THE APWA-KC AND THE CITY OF LEE'S SUMMIT, MO. ALL WATER LINES SHALL BE A MINIMUM OF 48 INCHES BELOW THE FINISHED GRADE ELEVATIONS SHOWN HEREIN.
34. ALL WATER LINES SHALL BE INSTALLED PER CITY STANDARDS. ALL WATER LINES SHALL BE A MINIMUM OF 48 INCHES BELOW THE FINISHED GRADE ELEVATIONS SHOWN HEREIN.
35. ALL EXTERIOR CONCRETE SHALL BE KCMMB-4K AND HAVE A MINIMUM 28-DAY COMPRESSIVE STRENGTH OF 4000 PSI, SHALL MEET KCMMB STANDARDS AND SPECIFICATIONS, AND SHALL BE AIR ENTRAINED. FLYASH IS NOT A SUITABLE REPLACEMENT FOR PORTLAND CEMENT.
36. ALL ON-SITE WIRING AND CABLES SHALL BE PLACED UNDERGROUND.
37. CONCRETE PAVEMENT JOINTS SHALL BE CONSTRUCTED AS FOLLOWS (REFER TO HARDSCAPE PLANS FOR SPECIFIC TREATMENT OF THESE AREAS):
  - A. CONTROL JOINTS SPACED AT INTERVALS NOT GREATER THAN 12 FEET AND TOOLED TO 1/3 THE SLAB THICKNESS.
  - B. CONSTRUCTION JOINTS AT THE END OF EACH POUR AND WHEN PAVING OPERATIONS ARE SUSPENDED FOR 30 MINUTES OR MORE.
  - C. ISOLATION JOINTS PLACED WHERE THE PAVEMENT ABUTS THE BUILDING, DRAINAGE STRUCTURES AND OTHER FIXED STRUCTURES, CONSTRUCTED WITH A 1/2" NONEXTRUDING FILLER, CLOSED-CELL FOAMSEAL RUBBER OR A BITUMEN-TREATED FIBER-BOLSSONDR, AND WITH A THICKENED EDGE, INCREASED BY 20 PERCENT, TAPERED TO THE REGULAR THICKNESS IN 5 FEET.
  - D. ALL EXPANSION JOINTS SHALL BE FILLED AND SEALED WITH A PLASTIC JOINT SEALANT MATERIAL.
35. TELEPHONE AND COMMUNICATION SERVICE ROUTING AND CONDUITS NOT SHOWN ON PLANS. CONTRACTOR SHALL INSTALL NECESSARY CONDUIT PRIOR TO PAVEMENT INSTALLATION. CONTRACTOR SHALL COORDINATE ROUTING AND INSTALLATION SCOPE WITH SERVICE PROVIDER.
36. ANY CONTRACTOR BIDDING ANY PORTION OF THIS WORK SHALL HAVE IN HIS OR HER POSSESSION A COMPLETE SET OF CONSTRUCTION DOCUMENTS AND BE FAMILIAR WITH ALL SCOPES OF WORK AND TRADES TO UNDERSTAND THEIR INTERACTIONS.
37. EXISTING TOPSOIL SHALL BE STRIPPED TO A POINT WHERE ALL VEGETATION IS REMOVED. REFER TO THE GEOTECHNICAL REPORT PROVIDED BY OLSSON DATED 01/09/2019 AND ALL ADDENDUMS.
38. SITE PREPARATION, GRADING AND EXCAVATION PROCEDURES SHALL CONFORM TO THE RECOMMENDATIONS AS OUTLINED IN THE GEOTECHNICAL REPORT PREPARED BY OLSSON DATED 01/09/2019 AND ALL ADDENDUMS.

GENERAL UTILITY NOTES

39. THE SIZE AND LOCATION OF SERVICES SHALL BE VERIFIED WITH THE ARCHITECTURAL AND MEP PLANS PRIOR TO CONSTRUCTION. IF DISCREPANCIES EXIST, THE ENGINEER SHALL BE NOTIFIED IMMEDIATELY.
40. IRRIGATION CONTRACTOR SHALL BE RESPONSIBLE FOR INSTALLING SLEEVING UNDER PAVING AREAS WHERE NECESSARY.
41. INSTALL ALL PIPE LENGTHS, BENDS AND FITTINGS NECESSARY FOR UTILITY CONNECTIONS.
42. CONTRACTOR SHALL VERIFY ALL CROSSING ELEVATIONS AND LOCATIONS, SIZES, AND ELEVATIONS OF EXISTING UTILITIES PRIOR TO CONSTRUCTION OF STORM LINES AND ALL UTILITY SERVICE CONNECTIONS. ANY CONFLICTS SHALL BE MADE KNOWN TO THE ENGINEER AND RESOLVED PRIOR TO CONSTRUCTION.
43. CONTRACTOR TO VERIFY FIRE SERVICE SIZE WITH SPRINKLER DESIGNER/CONTRACTOR PRIOR TO CONSTRUCTION AND INSTALLATION OF METER/BACKFLOW PREVENTER AND SERVICES. NOTIFY ENGINEER OF ALTERATIONS.
44. LOCATION FOR POWER SHOWN IS APPROXIMATE AND SUBJECT TO CHANGE. CONTRACTOR TO VERIFY FINAL LOCATION AND DESIGN WITH UTILITY COMPANY PRIOR TO CONSTRUCTION.
45. REFERENCE MEP PLANS FOR BUILDING CONNECTIONS.
46. CONTRACTOR TO REPAIR ALL AREA DAMAGED BY CONSTRUCTION TO EXISTING CONDITIONS OR BETTER.
47. BACK FLOW PREVENTION TO BE PROVIDED INSIDE BUILDING. SEE MEP AND ARCHITECTURAL PLANS FOR DETAILS.
48. LOCATION FOR POWER SHOWN IS APPROXIMATE AND SUBJECT TO CHANGE. CONTRACTOR TO VERIFY FINAL LOCATION AND DESIGN WITH UTILITY COMPANY PRIOR TO CONSTRUCTION.
49. CONTRACTOR TO COORDINATE LIGHT POLE LOCATIONS WITH OWNER, STORM SEWER INSTALLATION AND UTILITY COMPANIES PRIOR TO INSTALLATION TO AVOID CONFLICTS. NOTIFY ENGINEER AND ARCHITECT OF ANY CONFLICTS PRIOR TO INSTALLATION.
50. WATER METER CANNOT BE INSTALLED IN THE BUILDING.
51. CONTRACTOR SHALL COORDINATE CABLE/FIBER OPTIC CONDUIT AND SERVICE INSTALLATION WITH UTILITY COMPANY.
52. ALL TAPS AND CONNECTIONS FOR FIRE AND DOMESTIC WATER SERVICES ARE TO BE IN ACCORDANCE WITH THE CITY OF LEE' SUMMIT, MO, STANDARDS AND SPECIFICATIONS.
53. CONTRACTOR TO COORDINATE POWER ROUTING TO MONUMENT SIGNS NOT SHOWN ON PLANS.
54. ALL ROOF DRAIN AND DOWNSPOUT HEADER PIPES SHALL BE 12" HDPE PIPE AND INSTALLED AT 1.00% MINIMUM SLOPE UNLESS OTHERWISE NOTED WITHIN THIS PLAN. ALL BENDS AND FITTINGS NEEDED TO BUILD ROUTING AS SHOWN SHALL BE INCLUDED IN BID.
55. CONTRACTOR SHALL PROVIDE AND INSTALL ALL NECESSARY FITTINGS TO COMPLETE ROOF DRAIN AND DOWNSPOUT CONNECTIONS TO BUILDINGS. ALL ROOF DRAIN AND DOWNSPOUT CONNECTIONS / FITTINGS, INCLUDING BUT NOT LIMITED TO BENDS AND TEES, SHALL BE MADE OF HDPE PIPE UNLESS OTHERWISE NOTED WITHIN THIS PLAN.

PAVEMENT MARKING NOTES:

1. PAVEMENT MARKING PAINT: LATEX, WATER-BASE EMULSION, READY-MIXED, COMPLYING WITH FS TT-P-1952 WITH DRYING TIME OF LESS THAN 45 MINUTES.
2. DO NOT APPLY PAVEMENT MARKING PAINT UNTIL LAYOUT, COLORS AND PLACEMENT HAVE BEEN VERIFIED WITH THE ARCHITECT.
3. ALLOW PAVING TO AGE FOR 24 HOURS BEFORE MARKING.
4. SWEEP AND CLEAN SURFACE PRIOR TO INSTALLING PAVEMENT MARKINGS.
5. APPLY PAINT WITH MECHANICAL EQUIPMENT TO PRODUCE MARKINGS WITH UNIFORM STRAIGHT EDGES. PROVIDE A MINIMUM WET FILM THICKNESS OF 15 MILS.
6. THIS WORK SHALL CONSIST OF FURNISHING AND APPLYING PAINT ON PAVEMENT SURFACES, IN TRAFFIC LANES, PARKING BAYS, AREAS RESTRICTED TO HANDICAPPED PERSONS, CROSSWALKS, AND OTHER DETAIL PAVEMENT MARKINGS, IN ACCORDANCE WITH THE DETAILS SHOWN ON THE DRAWINGS.
7. DETAILS NOT SHOWN SHALL BE IN CONFORMITY WITH THE STATE STANDARDS FOR TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS, AND SIMILAR REQUIREMENTS ESTABLISHED BY THE U.S. DEPARTMENT OF TRANSPORTATION, FEDERAL HIGHWAY ADMINISTRATION.
8. ALL PARKING LOT STRIPING SHALL BE SINGLE LINE 4" WIDE AS PER THE SITE PLANS.
9. PAINT FOR MARKING PAVEMENT SHALL CONFORM TO FEDERAL HIGHWAY MARKING STANDARDS. USE SHERWIN WILLIAMS PROMAR TRAFFIC MARKING PAINT, COLORS TO MATCH THE EXISTING ADJACENT INSTALLATIONS. USE FLAT BLACK, WHITE OR YELLOW, WHERE APPROPRIATE. UNLESS OTHERWISE DIRECTED, USE THE FOLLOWING:
  - A. BLACKTOP OR BITUMINOUS ASPHALT PAVING: USE WHITE COLOR.
  - B. PORTLAND CEMENT CONCRETE PAVING: USE YELLOW COLOR.
  - C. HANDICAPPED ACCESSIBLE PARKING AND ENTRYWAYS: USE WHITE COLOR WITH WHITE STRIPES.
  - D. PROVIDE PAINTED CURBS AT FIRE LANE DESIGNATIONS PER FIRE MARSHAL REQUIREMENTS.
10. APPLY ALL MARKINGS USING APPROVED MECHANICAL EQUIPMENT (WITH PROVISIONS FOR CONSTANT AGITATION OF PAINT), CAPABLE OF APPLYING THE MARKING WIDTHS AS SHOWN. USE PNEUMATIC SPRAY GUNS FOR HAND APPLICATION OF PAINT. ALL PAINTING EQUIPMENT AND OPERATIONS SHALL BE UNDER THE CONTROL OF EXPERIENCED TECHNICIANS THOROUGHLY FAMILIAR WITH EQUIPMENT AND MATERIALS AND MARKING LAYOUTS.
11. DETAIL PAVEMENT MARKINGS SHALL BE THAT MARKING, EXCLUSIVE OF ACTUAL TRAFFIC LANE MARKING, AT EXIT AND ENTRANCE ISLANDS AND TURNOUTS, ON CURBS, AT CROSSWALKS, AT PARKING BAYS AND AT SUCH OTHER LOCATIONS AS SHOWN. HANDICAPPED PARKING SPACES SHALL BE MARKED BY THE INTERNATIONAL HANDICAPPED SYMBOL AT INDICATED PARKING SPACES. USE A SUITABLE TEMPLATE THAT WILL PROVIDE A PAVEMENT MARKING WITH TRUE, SHARP EDGES AND ENDS.

CONTROL INFORMATION:

BASIS OF COORDINATES SHOWN HEREON ARE BASED ON MISSOURI STATE PLANE COORDINATE SYSTEM, WEST ZONE, AND SCALED TO GROUND COORDINATES UTILIZING A COMBINED ADJUSTMENT FACTOR OF 0.9998986, HOLDING JACKSON COUNTY GPS CONTROL POINT JA-45 AS A BASE POINT. DISTANCES SHOWN HEREON ARE GROUND DISTANCES IN US SURVEY FEET.

MO DNR JA-45:  
KC METRO ALUMINUM GRS DISK SET IN CONCRETE ±3" BELOW PAVEMENT ON SHOULDER EAST OF SE RANSON RD. STAMPED "JA-45".  
N: 994990.346  
E: 2834265.611  
ELEV.: 1046.26'

OLSSON #100:  
SET 1/2" REBAR WITH OLSSON CONTROL CAP. SET IN THE GRASS ON THE NORTH SIDE OF SE BAILEY RD.  
N: 993598.83  
E: 2831586.70  
ELEVATION: 1032.16'  
TIES:  
1. SW 66.88' TO THE NE CORNER OF THE CONCRETE SIDEWALK ON THE SOUTH SIDE OF SE BAILEY RD.  
2. SSW 82.19' TO THE CENTER OF A POWER POLE ON THE SOUTH SIDE OF SE BAILEY RD.  
3. EAST 254.38' TO THE NW CORNER OF A CONCRETE CURB INLET ON THE NORTH SIDE OF SE BAILEY RD.  
4. EAST ±298' TO THE CENTERLINE OF COUNTRY LN. ON THE NORTH SIDE OF SE BAILEY RD.

OLSSON #101:  
SET 1/2" REBAR WITH OLSSON CONTROL CAP. SET IN THE GRASS ON THE NORTH SIDE OF SE BAILEY RD.  
N: 993561.11  
E: 2832755.84  
ELEVATION: 1014.26'  
TIES:  
1. EAST 80.94' TO THE NW CORNER OF A CONCRETE CURB INLET ON THE NORTH SIDE OF SE BAILEY RD.  
2. SE 91.53' TO THE SW CORNER OF A CONCRETE CURB INLET ON THE SOUTH SIDE OF SE BAILEY RD.  
3. NE 94.82' TO THE SW CORNER OF A CONCRETE OVERFLOW STRUCTURE ON THE SOUTH SIDE OF A POND ON THE NORTH SIDE OF SE BAILEY RD.  
4. WEST ±871' TO THE CENTERLINE OF COUNTRY LN. ON THE NORTH SIDE OF SE BAILEY RD.

OLSSON #102:  
SET 1/2" REBAR WITH OLSSON CONTROL CAP. SET IN THE GRASS ±58' EAST OF THE EAST END OF SE 15TH ST.  
N: 992084.37  
E: 2831530.63  
ELEVATION: 1012.56'  
TIES:  
1. NW 67.97' TO THE CENTER OF A WATER VALVE ON THE NORTH SIDE OF SE 15TH ST.  
2. WEST 59.33' TO THE CENTER OF A SANITARY MANHOLE ON THE SOUTH SIDE OF SE 15TH ST.  
3. WSW 57.28' TO THE SE CORNER OF THE EAST END OF THE CONCRETE SIDEWALK ON THE SOUTH SIDE OF SE 15TH ST.  
4. NORTH ±15' TO THE EASTERLY PROLONGATION OF THE CENTERLINE OF SE 15TH ST.

OLSSON #103:  
SET 1/2" REBAR WITH OLSSON CONTROL CAP. SET IN THE GRASS ±62' EAST OF THE EAST END OF SE CAPE DR.  
N: 991553.72  
E: 2831514.48  
ELEVATION: 1000.43'  
TIES:  
1. NW 76.12' TO THE CENTER OF A TELEPHONE PEDESTAL ON THE NORTH SIDE OF SE CAPE DR.  
2. SW 67.00' TO THE CENTER OF A WATER VALVE ON THE SOUTH SIDE OF SE CAPE DR.  
3. SW 70.06' TO THE SE CORNER OF THE EAST END OF THE CONCRETE SIDEWALK ON THE SOUTH SIDE OF SE CAPE DR.  
4. NORTH ±4' TO THE EASTERLY PROLONGATION OF THE CENTERLINE OF SE CAPE DR.

BASIS OF ELEVATIONS SHOWN HEREON ARE BASED UPON NAVD '88 UTILIZING MDOOT'S CONTINUOUSLY MONITORED GNSS SYSTEM AND HOLDING THE ELEVATION OF JA-45 ELEVATION 1046.26'

OLSSON BENCHMARK #1:  
SET CHISELED SQUARE CUT ON CENTER FRONT FACE OF A CURB INLET ON NORTH SIDE OF SE BAILEY RD. ±42' WEST OF COUNTRY LN.  
ELEVATION: 1028.43'

OLSSON BENCHMARK #2:  
SET CHISELED SQUARE CUT ON SE CORNER OF OVERFLOW STRUCTURE ON SOUTH SIDE OF POND ON NORTH SIDE OF SE BAILEY RD. ±962' EAST OF COUNTRY LN.  
ELEVATION: 1017.13'

OLSSON BENCHMARK #3:  
SET CHISELED "4" CUT ON SSE FLANGE BOLT OF FIRE HYDRANT IN THE NW QUADRANT OF THE INTERSECTION OF SE 15TH ST. AND SE DALTON DR.  
ELEVATION: 1016.27'



OLSSON BENCHMARK #4:  
SET CHISELED SQUARE CUT ON EDGE OF SIDEWALK AT THE WEST CENTER OF A CURB INLET IN THE NW QUADRANT OF THE INTERSECTION OF SE CAPE DR. AND SE DALTON DR.  
ELEVATION: 999.24'

NOTE:  
ACCORDING TO MDNR STATE OIL & GAS COUNSEL THERE ARE NO OIL AND GAS WELLS LOCATED WITHIN OR ADJACENT TO THE PROPERTY.

THE ENTIRE PROPERTY IS DESIGNATED "ZONE X -- AREA OF MINIMAL FLOOD HAZARD" AS DEFINED BY FEMA PANEL 29095C0438G -- EFFECTIVE DATE JANUARY 20, 2017



THE CONTRACTOR SHALL ADHERE TO THE PROVISIONS OF THE SENATE BILL NUMBER 583, 78TH GENERAL ASSEMBLY OF THE STATE OF MISSOURI. THE BILL REQUIRES THAT ANY PERSON OR FIRM DOING EXCAVATION ON PUBLIC RIGHT--OF-WAY DO SO ONLY AFTER GIVING NOTICE TO, AND OBTAINING INFORMATION FROM, UTILITY COMPANIES. STATE LAW REQUIRES 48 HOURS ADVANCE NOTICE. CALL 1-800-DIG-RITE.



LEE'S SUMMIT MIDDLE SCHOOL #4  
LEE'S SUMMIT R-7 SCHOOL DISTRICT  
1001 SE BAILEY ROAD  
LEE'S SUMMIT, MO 64881


PACKAGE 2-  
STRUCTURAL & SITE  
UTILITIES  
ISSUED FOR PERMIT  
08/28/20

13-20102-00


GENERAL NOTES

C1001






- 01 HEAVY DUTY CONCRETE PAVEMENT. RE: DETAILS
- 02 SPEED TABLE. RE: DETAILS
- 03 DETENTION BASIN. RE: DETAILS
- 04 REMOVABLE CONCRETE BOLLARD. RE: LANDSCAPE PLANS
- 05 ADA PARKING, STRIPING AND SIGNAGE. RE: DETAILS
- 06 CONCRETE STAIRS AND HANDRAIL – BOTH SIDES.  
RE: LANDSCAPE PLANS
- 07 ADA RAMP WITH HANDRAIL – BOTH SIDES.  
RE: DETAILS.
- 08 ADA RAMP. RE: DETAILS
- 09 CAST IN PLACE RETAINING WALL WITH GUARD RAIL.  
RE: STRUCTURAL PLANS
- 10 MODULAR BLOCK RETAINING WALL WITH FENCE.  
RE: STRUCTURAL AND ARCH
- 11 MODULAR BLOCK RETAINING WALL
- 12 TRASH DUMPSTER
- 13 PUBLIC IMPROVEMENTS – RE: PUBLIC IMPROVEMENT PLANS
- 14 PRE-FABRICATED METAL STAIRS AND HANDRAIL. RE: ARCH
- 15 CONCRETE STOPPING BLOCK RE: DETAILS
- 16 PAVEMENT STRIPING RE: DETAILS
- 17 HANDSCAPE JOINT PATTERN RE: ARCH
- 18 2-FOOT WIDE CONCRETE VALLEY GUTTER. RE: DETAILS
- 19 LIGHT POLE. RE: MEP
- 20 CONCRETE PAVEMENT. RE: ARCH
- 21 CURB. RE: LANDSCAPE
- 22 FLAGPOLE. RE: LANDSCAPE



**LEGEND**


- PROPERTY LINE
- CONCRETE CURB & GUTTER TYPE "CG-1"
- CONCRETE CURB & GUTTER TYPE "CG-1 DRY"
- SAWCUT PAVEMENT FULL DEPTH
- COMMERCIAL ENTRANCE 8" PCC CONCRETE PAVEMENT
- 6" PCC CONCRETE PAVEMENT
- CONCRETE SIDEWALK PAVEMENT
- ASPHALT PAVEMENT - HEAVY DUTY
- ASPHALT PAVEMENT - LIGHT DUTY
- ADA CONCRETE SIDEWALK AND RAMP. RE: DETAILS
- PARKING STALLS
- STORM SEWER RE: STORM SEWER PLAN & PROFILE

- CONSTRUCTION KEYNOTES:**
- 01 HEAVY DUTY CONCRETE PAVEMENT. RE: DETAILS
  - 02 SPEED TABLE. RE: DETAILS
  - 03 DETENTION BASIN. RE: DETAILS
  - 04 REMOVABLE CONCRETE BOLLARD. RE: LANDSCAPE PLANS
  - 05 ADA PARKING, STRIPING AND SIGNAGE. RE: DETAILS
  - 06 CONCRETE STAIRS AND HANDRAIL - BOTH SIDES. RE: LANDSCAPE PLANS
  - 07 ADA RAMP WITH HANDRAIL - BOTH SIDES. RE: DETAILS
  - 08 ADA RAMP. RE: DETAILS
  - 09 CAST IN PLACE RETAINING WALL WITH GUARD RAIL. RE: STRUCTURAL PLANS
  - 10 MODULAR BLOCK RETAINING WALL WITH FENCE. RE: STRUCTURAL AND ARCH
  - 11 MODULAR BLOCK RETAINING WALL
  - 12 TRASH DUMPSTER
  - 13 PUBLIC IMPROVEMENTS - RE: PUBLIC IMPROVEMENT PLANS
  - 14 PRE-FABRICATED METAL STAIRS AND HANDRAIL. RE: ARCH
  - 15 CONCRETE STOPPING BLOCK RE: DETAILS
  - 16 PAVEMENT STRIPING RE: DETAILS
  - 17 HARDSCAPE JOINT PATTERN RE: ARCH
  - 18 2-FOOT WIDE CONCRETE VALLEY GUTTER. RE: DETAILS
  - 19 LIGHT POLE. RE: MEP
  - 20 CONCRETE PAVEMENT. RE: ARCH
  - 21 CURB. RE: LANDSCAPE
  - 22 FLAGPOLE. RE: LANDSCAPE
- CONTRACTOR SHALL REFER TO LANDSCAPE PLANS FOR DECORATIVE CONCRETE



DWG: F:\2020\0001-0500\020-0103\40-Design\AutoCAD\Final Plans\Sheets\GNV\CONSTRUCTION DOCUMENTS\C\_SIT01\_0200103.dwg  
DATE: Dec 01, 2021 6:55am  
USER: bkmimich  
T\_PBASE\_0200103  
T\_PSAS\_0200103  
V\_XALT\_00103


DWG: F:\2020\0001-0500\020-0103\40-Design\AutoCAD\Final Plans\Sheets\GNV\CONSTRUCTION DOCUMENTS\C\_SIT01\_0200103.dwg  
DATE: Dec 01, 2021 6:55am  
USER: bkmnich  
T\_PBASE\_0200103  
C\_PBLK\_0200103  
C\_PSURF\_0200103  
T\_PBASE\_0200103  
V\_XALT\_00103  
F:\2020\0001-0500\020-0103\40-Design\AutoCAD\Final Plans\Sheets\GNV\CONSTRUCTION DOCUMENTS\C\_SIT01\_0200103.dwg  
DATE: Dec 01, 2021 6:55am  
USER: bkmnich  
T\_PBASE\_0200103  
C\_PBLK\_0200103  
C\_PSURF\_0200103  
T\_PBASE\_0200103  
V\_XALT\_00103




**LEGEND**

- PROPERTY LINE
- CONCRETE CURB & GUTTER TYPE "CG-1"
- CONCRETE CURB & GUTTER TYPE "CG-1 DRY"
- SAWCUT PAVEMENT FULL DEPTH
- COMMERCIAL ENTRANCE 8" PCC CONCRETE PAVEMENT
- 6" PCC CONCRETE PAVEMENT
- CONCRETE SIDEWALK PAVEMENT
- ASPHALT PAVEMENT - HEAVY DUTY
- ASPHALT PAVEMENT - LIGHT DUTY
- ADA CONCRETE SIDEWALK AND RAMP. RE: DETAILS
- PARKING STALLS
- STORM SEWER RE: STORM SEWER PLAN & PROFILE

- CONSTRUCTION KEYNOTES:**
- 01 HEAVY DUTY CONCRETE PAVEMENT. RE: DETAILS
  - 02 SPEED TABLE. RE: DETAILS
  - 03 DETENTION BASIN. RE: DETAILS
  - 04 REMOVABLE CONCRETE BOLLARD. RE: LANDSCAPE PLANS
  - 05 ADA PARKING, STRIPING AND SIGNAGE. RE: DETAILS
  - 06 CONCRETE STAIRS AND HANDRAIL - BOTH SIDES. RE: LANDSCAPE PLANS
  - 07 ADA RAMP WITH HANDRAIL - BOTH SIDES. RE: DETAILS
  - 08 ADA RAMP. RE: DETAILS
  - 09 CAST IN PLACE RETAINING WALL WITH GUARD RAIL. RE: STRUCTURAL PLANS
  - 10 MODULAR BLOCK RETAINING WALL WITH FENCE. RE: STRUCTURAL AND ARCH
  - 11 MODULAR BLOCK RETAINING WALL
  - 12 TRASH DUMPSTER
  - 13 PUBLIC IMPROVEMENTS - RE: PUBLIC IMPROVEMENT PLANS
  - 14 PRE-FABRICATED METAL STAIRS AND HANDRAIL. RE: ARCH
  - 15 CONCRETE STOPPING BLOCK RE: DETAILS
  - 16 PAVEMENT STRIPING RE: DETAILS
  - 17 HARDSCAPE JOINT PATTERN RE: ARCH
  - 18 2-FOOT WIDE CONCRETE VALLEY GUTTER. RE: DETAILS
  - 19 LIGHT POLE. RE: MEP
  - 20 CONCRETE PAVEMENT. RE: ARCH
  - 21 CURB. RE: LANDSCAPE
  - 22 FLAGPOLE. RE: LANDSCAPE
- CONTRACTOR SHALL REFER TO LANDSCAPE PLANS FOR DECORATIVE CONCRETE






**LEGEND**

- PROPERTY LINE
- CONCRETE CURB & GUTTER TYPE "CG-1"
- CONCRETE CURB & GUTTER TYPE "CG-1 DRY"
- SAWCUT PAVEMENT FULL DEPTH
- COMMERCIAL ENTRANCE 8" PCC CONCRETE PAVEMENT
- 6" PCC CONCRETE PAVEMENT
- CONCRETE SIDEWALK PAVEMENT
- ASPHALT PAVEMENT - HEAVY DUTY
- ASPHALT PAVEMENT - LIGHT DUTY
- ADA CONCRETE SIDEWALK AND RAMP. RE: DETAILS
- PARKING STALLS
- STORM SEWER RE: STORM SEWER PLAN & PROFILE

**CONSTRUCTION KEYNOTES:**

- 01 HEAVY DUTY CONCRETE PAVEMENT. RE: DETAILS
- 02 SPEED TABLE. RE: DETAILS
- 03 DETENTION BASIN. RE: DETAILS
- 04 REMOVABLE CONCRETE BOLLARD. RE: LANDSCAPE PLANS
- 05 ADA PARKING, STRIPING AND SIGNAGE. RE: DETAILS
- 06 CONCRETE STAIRS AND HANDRAIL - BOTH SIDES. RE: LANDSCAPE PLANS
- 07 ADA RAMP WITH HANDRAIL - BOTH SIDES. RE: DETAILS
- 08 ADA RAMP. RE: DETAILS
- 09 CAST IN PLACE RETAINING WALL WITH GUARD RAIL. RE: STRUCTURAL PLANS
- 10 MODULAR BLOCK RETAINING WALL WITH FENCE. RE: STRUCTURAL AND ARCH
- 11 MODULAR BLOCK RETAINING WALL
- 12 TRASH DUMPSTER
- 13 PUBLIC IMPROVEMENTS - RE: PUBLIC IMPROVEMENT PLANS
- 14 PRE-FABRICATED METAL STAIRS AND HANDRAIL. RE: ARCH
- 15 CONCRETE STOPPING BLOCK RE: DETAILS
- 16 PAVEMENT STRIPING RE: DETAILS
- 17 HARDSCAPE JOINT PATTERN RE: ARCH
- 18 2-FOOT WIDE CONCRETE VALLEY GUTTER. RE: DETAILS
- 19 LIGHT POLE. RE: MEP
- 20 CONCRETE PAVEMENT. RE: ARCH
- 21 CURB. RE: LANDSCAPE
- 22 FLAGPOLE. RE: LANDSCAPE

CONTRACTOR SHALL REFER TO LANDSCAPE PLANS FOR DECORATIVE CONCRETE



DLR Group

© DLR Group, Inc. a Missouri corporation.  
8020 DLR Group, Inc. a Missouri corporation.  
Missouri State Certificate of Authority #00939

**olsson**

OLSSON, CIVIL ENGINEERING  
MISSOURI CERTIFICATE OF AUTHORITY #001592  
7301 West 133rd Street, Suite 200  
Overland Park, KS 66213-4750  
TEL 913.381.1170  
www.olsson.com

LEE'S SUMMIT MIDDLE SCHOOL #4  
LEE'S SUMMIT R-7 SCHOOL DISTRICT  
1001 SE BAILEY ROAD  
LEE'S SUMMIT, MO 64081


PACKAGE 2-  
STRUCTURAL & SITE  
UTILITIES  
ISSUED FOR PERMIT  
08/28/20

PR002R 01.14.21  
PR-16 10.12.21

13-20102-00

SITE DIMENSION  
PLAN


C1006



**LEGEND**

- PROPERTY LINE
- CONCRETE CURB & GUTTER TYPE "CG-1"
- CONCRETE CURB & GUTTER TYPE "CG-1 DRY"
- SAWCUT PAVEMENT FULL DEPTH
- COMMERCIAL ENTRANCE 8" PCC CONCRETE PAVEMENT
- 6" PCC CONCRETE PAVEMENT
- CONCRETE SIDEWALK PAVEMENT
- ASPHALT PAVEMENT - HEAVY DUTY
- ASPHALT PAVEMENT - LIGHT DUTY
- ADA CONCRETE SIDEWALK AND RAMP. RE: DETAILS
- PARKING STALLS
- STORM SEWER RE: STORM SEWER PLAN & PROFILE

- CONSTRUCTION KEYNOTES:**
- 01 HEAVY DUTY CONCRETE PAVEMENT. RE: DETAILS
  - 02 SPEED TABLE. RE: DETAILS
  - 03 DETENTION BASIN. RE: DETAILS
  - 04 REMOVABLE CONCRETE BOLLARD. RE: LANDSCAPE PLANS
  - 05 ADA PARKING, STRIPING AND SIGNAGE. RE: DETAILS
  - 06 CONCRETE STAIRS AND HANDRAIL - BOTH SIDES. RE: LANDSCAPE PLANS
  - 07 ADA RAMP WITH HANDRAIL - BOTH SIDES. RE: DETAILS
  - 08 ADA RAMP. RE: DETAILS
  - 09 CAST IN PLACE RETAINING WALL WITH GUARD RAIL. RE: STRUCTURAL PLANS
  - 10 MODULAR BLOCK RETAINING WALL WITH FENCE. RE: STRUCTURAL AND ARCH
  - 11 MODULAR BLOCK RETAINING WALL
  - 12 TRASH DUMPSTER
  - 13 PUBLIC IMPROVEMENTS - RE: PUBLIC IMPROVEMENT PLANS
  - 14 PRE-FABRICATED METAL STAIRS AND HANDRAIL. RE: ARCH
  - 15 CONCRETE STOPPING BLOCK RE: DETAILS
  - 16 PAVEMENT STRIPING RE: DETAILS
  - 17 HARDSCAPE JOINT PATTERN RE: ARCH
  - 18 2-FOOT WIDE CONCRETE VALLEY GUTTER. RE: DETAILS
  - 19 LIGHT POLE. RE: MEP
  - 20 CONCRETE PAVEMENT. RE: ARCH
  - 21 CURB. RE: LANDSCAPE
  - 22 FLAGPOLE. RE: LANDSCAPE
- CONTRACTOR SHALL REFER TO LANDSCAPE PLANS FOR DECORATIVE CONCRETE



**DLR Group**

© DLR Group  
8000 DLR Group, Inc., a Missouri corporation,  
Missouri State Certificate of Authority #00399

**olsson**

OLSSON, CIVIL ENGINEERING  
MISSOURI CERTIFICATE OF AUTHORITY #001992  
7301 West 133rd Street, Suite 200  
Overland Park, KS 66213-4750  
TEL 913.381.1170  
www.olson.com

**LEE'S SUMMIT MIDDLE SCHOOL #4**

LEE'S SUMMIT R-7 SCHOOL DISTRICT

1001 SE BAILEY ROAD  
LEE'S SUMMIT, MO 64881

PACKAGE 2-  
STRUCTURAL & SITE  
UTILITIES  
ISSUED FOR PERMIT  
08/28/20



PR002R 01.14.21  
AS/25 07.26.21  
PR-16 10.12.21

13-20102-00

SITE DIMENSION  
PLAN


**C1007**

DWG: F:\2020\0001-0500\020-0103\40-Design\AutoCAD\Final Plans\Sheets\GNV\CONSTRUCTION DOCUMENTS\C\_SIT01\_0200103.dwg  
DATE: Dec 01, 2021 6:56am  
USER: bkimnich  
T\_PBASE\_0200103  
C\_PBLK\_0200103  
C\_PSURF\_0200103  
T\_PSAS\_0200103  
V\_XALT\_00103




CONTRACTOR SHALL REFER TO LANDSCAPE PLANS  
FOR DECORATIVE CONCRETE

C1008




LEGEND	
	PROPERTY LINE
	CONCRETE CURB & GUTTER TYPE "CG-1"
	CONCRETE CURB & GUTTER TYPE "CG-1 DRY"
	SAWCUT PAVEMENT FULL DEPTH
	COMMERCIAL ENTRANCE 8" PCC CONCRETE PAVEMENT
	6" PCC CONCRETE PAVEMENT
	CONCRETE SIDEWALK PAVEMENT
	ASPHALT PAVEMENT - HEAVY DUTY
	ASPHALT PAVEMENT - LIGHT DUTY
	ADA CONCRETE SIDEWALK AND RAMP. RE: DETAILS
	PARKING STALLS
	STORM SEWER RE: STORM SEWER PLAN & PROFILE

- CONSTRUCTION KEYNOTES:
- 01 HEAVY DUTY CONCRETE PAVEMENT. RE: DETAILS
  - 02 SPEED TABLE. RE: DETAILS
  - 03 DETENTION BASIN. RE: DETAILS
  - 04 REMOVABLE CONCRETE BOLLARD. RE: LANDSCAPE PLANS
  - 05 ADA PARKING, STRIPING AND SIGNAGE. RE: DETAILS
  - 06 CONCRETE STAIRS AND HANDRAIL - BOTH SIDES.  
RE: LANDSCAPE PLANS
  - 07 ADA RAMP WITH HANDRAIL - BOTH SIDES.  
RE: DETAILS
  - 08 ADA RAMP. RE: DETAILS
  - 09 CAST IN PLACE RETAINING WALL WITH GUARD RAIL.  
RE: STRUCTURAL PLANS
  - 10 MODULAR BLOCK RETAINING WALL WITH FENCE.  
RE: STRUCTURAL AND ARCH
  - 11 MODULAR BLOCK RETAINING WALL
  - 12 TRASH DUMPSTER
  - 13 PUBLIC IMPROVEMENTS - RE: PUBLIC IMPROVEMENT PLANS
  - 14 PRE-FABRICATED METAL STAIRS AND HANDRAIL. RE: ARCH
  - 15 CONCRETE STOPPING BLOCK RE: DETAILS
  - 16 PAVEMENT STRIPING RE: DETAILS
  - 17 HARDSCAPE JOINT PATTERN RE: ARCH
  - 18 2-FOOT WIDE CONCRETE VALLEY GUTTER. RE: DETAILS
  - 19 LIGHT POLE. RE: MEP
  - 20 CONCRETE PAVEMENT. RE: ARCH
  - 21 CURB. RE: LANDSCAPE
  - 22 FLAGPOLE. RE: LANDSCAPE
- CONTRACTOR SHALL REFER TO LANDSCAPE PLANS  
FOR DECORATIVE CONCRETE




DWG: F:\2020\0001-0500\020-0103\40-Design\AutoCAD\Final Plans\Sheets\GNV\CONSTRUCTION DOCUMENTS\C\_SIT01\_0200103.dwg  
DATE: Dec 01, 2021 6:58am XREFS: C\_XBASE\_0200103 C\_PBASE\_0200103 C\_PBLK\_0200103 C\_PPSURF\_0200103 T\_PBASE\_0200103 T\_PPSAS\_0200103 V\_XALT\_00103  
USER: bkimnich T\_PBASE\_0200103




LEGEND	
	PROPERTY LINE
	CONCRETE CURB & GUTTER TYPE "CG-1"
	CONCRETE CURB & GUTTER TYPE "CG-1 DRY"
	SAWCUT PAVEMENT FULL DEPTH
	COMMERCIAL ENTRANCE 8" PCC CONCRETE PAVEMENT
	6" PCC CONCRETE PAVEMENT
	CONCRETE SIDEWALK PAVEMENT
	ASPHALT PAVEMENT - HEAVY DUTY
	ADA CONCRETE SIDEWALK AND RAMP. RE: SHEET XX AND XX
	PARKING STALLS
	STORM SEWER RE: SHEETS XX

CONSTRUCTION KEYNOTES:

- 01 HEAVY DUTY CONCRETE PAVEMENT. RE: DETAILS
- 02 SPEED TABLE. RE: DETAILS
- 03 DETENTION BASIN. RE: DETAILS
- 04 REMOVABLE CONCRETE BOLLARD. RE: LANDSCAPE PLANS
- 05 ADA PARKING, STRIPING AND SIGNAGE. RE: DETAILS
- 06 CONCRETE STAIRS AND HANDRAIL - BOTH SIDES. RE: LANDSCAPE PLANS
- 07 ADA RAMP WITH HANDRAIL - BOTH SIDES. RE: DETAILS
- 08 ADA RAMP. RE: DETAILS
- 09 CAST IN PLACE RETAINING WALL WITH GUARD RAIL. RE: STRUCTURAL PLANS
- 10 MODULAR BLOCK RETAINING WALL WITH FENCE. RE: STRUCTURAL AND ARCH
- 11 MODULAR BLOCK RETAINING WALL
- 12 TRASH DUMPSTER
- 13 PUBLIC IMPROVEMENTS - RE: PUBLIC IMPROVEMENT PLANS
- 14 PRE-FABRICATED METAL STAIRS AND HANDRAIL. RE: ARCH
- 15 CONCRETE STOPPING BLOCK RE: DETAILS
- 16 PAVEMENT STRIPING RE: DETAILS
- 17 HARDSCAPE JOINT PATTERN RE: ARCH
- 18 2-FOOT WIDE CONCRETE VALLEY GUTTER. RE: DETAILS
- 19 LIGHT POLE. RE: MEP
- 20 CONCRETE PAVEMENT. RE: ARCH
- 21 CURB. RE: LANDSCAPE
- 22 FLAGPOLE. RE: LANDSCAPE
- CONTRACTOR SHALL REFER TO LANDSCAPE PLANS FOR DECORATIVE CONCRETE







**LEGEND**

- PROPERTY LINE
- CONCRETE CURB & GUTTER TYPE "CG-1"
- CONCRETE CURB & GUTTER TYPE "CG-1 DRY"
- SAWCUT PAVEMENT FULL DEPTH
- COMMERCIAL ENTRANCE 8" PCC CONCRETE PAVEMENT
- 6" PCC CONCRETE PAVEMENT
- CONCRETE SIDEWALK PAVEMENT
- ASPHALT PAVEMENT - HEAVY DUTY
- ASPHALT PAVEMENT - LIGHT DUTY
- ADA CONCRETE SIDEWALK AND RAMP. RE: DETAILS
- PARKING STALLS
- STORM SEWER RE: STORM SEWER PLAN & PROFILE

- CONSTRUCTION KEYNOTES:**
- 01 HEAVY DUTY CONCRETE PAVEMENT. RE: DETAILS
  - 02 SPEED TABLE. RE: DETAILS
  - 03 DETENTION BASIN. RE: DETAILS
  - 04 REMOVABLE CONCRETE BOLLARD. RE: LANDSCAPE PLANS
  - 05 ADA PARKING, STRIPING AND SIGNAGE. RE: DETAILS
  - 06 CONCRETE STAIRS AND HANDRAIL - BOTH SIDES. RE: LANDSCAPE PLANS
  - 07 ADA RAMP WITH HANDRAIL - BOTH SIDES. RE: DETAILS
  - 08 ADA RAMP. RE: DETAILS
  - 09 CAST IN PLACE RETAINING WALL WITH GUARD RAIL. RE: STRUCTURAL PLANS
  - 10 MODULAR BLOCK RETAINING WALL WITH FENCE. RE: STRUCTURAL AND ARCH
  - 11 MODULAR BLOCK RETAINING WALL
  - 12 TRASH DUMPSTER
  - 13 PUBLIC IMPROVEMENTS - RE: PUBLIC IMPROVEMENT PLANS
  - 14 PRE-FABRICATED METAL STAIRS AND HANDRAIL. RE: ARCH
  - 15 CONCRETE STOPPING BLOCK RE: DETAILS
  - 16 PAVEMENT STRIPING RE: DETAILS
  - 17 HARDSCAPE JOINT PATTERN RE: ARCH
  - 18 2-FOOT WIDE CONCRETE VALLEY GUTTER. RE: DETAILS
  - 19 LIGHT POLE. RE: MEP
  - 20 CONCRETE PAVEMENT. RE: ARCH
  - 21 CURB. RE: LANDSCAPE
  - 22 FLAGPOLE. RE: LANDSCAPE
- CONTRACTOR SHALL REFER TO LANDSCAPE PLANS FOR DECORATIVE CONCRETE



DWG: F:\2020\0001-0500\020-0103\40-Design\AutoCAD\Final Plans\Sheets\GNV\CONSTRUCTION DOCUMENTS\C\_SIT01\_0200103.dwg  
DATE: Dec 01, 2021 6:59am XREFS: C\_XBASE\_0200103 C\_PBASE\_0200103 C\_PBLK\_0200103 C\_PPSURF\_0200103 T\_PBASE\_0200103 T\_PPSAS\_0200103 V\_XALT\_00103  
USER: bkimnich



**LEGEND**

--- PROPERTY LINE  
--- 995 --- EXISTING MAJOR CONTOUR  
--- 995 --- EXISTING MINOR CONTOUR  
--- 998 --- PROPOSED MAJOR CONTOUR  
--- 998 --- PROPOSED MINOR CONTOUR

▨ RAMP

┌ CONCRETE CURB &  
└ GUTTER TYPE "CG-1"

┌ CONCRETE CURB &  
└ GUTTER TYPE "CG-1 DRY"


┌ CONCRETE CURB  
└ TYPE "C-1" MODIFIED

- NOTES:**
1. CONTRACTOR TO REMOVE AND REPLACE ALL SIDEWALK NECESSARY FOR CONNECTION TO EXISTING.
  2. ALL ADA ACCESSIBLE SIDEWALK CROSS SLOPES SHALL HAVE A MAXIMUM CROSS SLOPE OF 2.00% AND MAXIMUM LONGITUDINAL SLOPE OF 5.00%.
  3. ALL ADA ACCESSIBLE PARKING AREAS SHALL NOT EXCEED 2.00% IN ANY DIRECTION.

**SPOT ELEVATION LEGEND**

ALL SPOT ELEVATIONS ARE TOP OF PAVEMENT ELEVATION UNLESS NOTED OTHERWISE. RE: PLAN VIEW, LEGEND AND DETAILS FOR CURB TYPE AND TO CALCULATE TOP OF CURB ELEVATION.

TC= TOP OF CURB  
FG= FINISHED GRADE WITHIN GREENSPACE  
TS= TOP OF STRUCTURE  
TP=TC= CURB DEPRESSED TO BE FLUSH WITH ADJACENT PAVEMENT  
HP= HIGH POINT  
LP= LOW POINT  
MATCH EX.= MATCH EXISTING  
FFE= FINISH FLOOR ELEVATION AT TOP OF SLAB



DWG: F:\2020\0001-0500\020-0103\40-Design\AutoCAD\Final Plans\Sheets\GNCA\CONSTRUCTION DOCUMENTS\C\_GRD020\_0200103.dwg  
DATE: Dec 01, 2021 7:01am XREFS: C\_XBASE\_0200103 V\_XBOL\_00103 C\_PBASE\_0200103 T\_PBASE\_0200103 T\_PBASE\_0200103 C\_PBASE\_0200103  
USER: blkmimich

MATCHLINE  
SEE SHEET C1015



#### LEGEND

- PROPERTY LINE
- - - 995 EXISTING MAJOR CONTOUR
- - - 995 EXISTING MINOR CONTOUR
- - - 998 PROPOSED MAJOR CONTOUR
- - - 998 PROPOSED MINOR CONTOUR
- ▨ RAMP
- └─ CONCRETE CURB & GUTTER TYPE "CG-1"
- └─ CONCRETE CURB & GUTTER TYPE "CG-1 DRY"
- └─ CONCRETE CURB TYPE "C-1" MODIFIED
- ⊗ GRADING DETAIL DESIGNATION RE: SHEET C5.1 THRU C5.5
- RIDGE
- VALLEY


#### NOTES:

- CONTRACTOR TO REMOVE AND REPLACE ALL SIDEWALK NECESSARY FOR CONNECTION TO EXISTING.
- ALL ADA ACCESSIBLE SIDEWALK CROSS SLOPES SHALL HAVE A MAXIMUM CROSS SLOPE OF 2.00% AND MAXIMUM LONGITUDINAL SLOPE OF 5.00%.
- ALL ADA ACCESSIBLE PARKING AREAS SHALL NOT EXCEED 2.00% IN ANY DIRECTION.


#### SPOT ELEVATION LEGEND

ALL SPOT ELEVATIONS ARE TOP OF PAVEMENT ELEVATION UNLESS NOTED OTHERWISE. RE: PLAN VIEW, LEGEND AND DETAILS FOR CURB TYPE AND TO CALCULATE TOP OF CURB ELEVATION.

- TC= TOP OF CURB
- FG= FINISHED GRADE WITHIN GREENSPACE
- TS= TOP OF STRUCTURE
- TP=TC= CURB DEPRESSED TO BE FLUSH WITH ADJACENT PAVEMENT
- HP= HIGH POINT
- LP= LOW POINT
- MATCH EX.= MATCH EXISTING
- FFE= FINISH FLOOR ELEVATION AT TOP OF SLAB



DWG: F:\2020\0001-0500\020-0103\40-Design\AutoCAD\Final Plans\Sheets\GNV\CONSTRUCTION DOCUMENTS\C\_GR020\_0200103.dwg USER: blmmich DATE: Dec 01, 2021 7:02am C\_PBASE\_0200103 V\_XBOL\_00103 C\_PBASE\_0200103 T\_PBASE\_0200103 T\_PSAS\_0200103 C\_PSURF\_0200103




- LEGEND**
- PROPERTY LINE
  - - - 995 --- EXISTING MAJOR CONTOUR
  - - - 995 --- EXISTING MINOR CONTOUR
  - - - 998 --- PROPOSED MAJOR CONTOUR
  - - - 998 --- PROPOSED MINOR CONTOUR
  - RAMP
  - CONCRETE CURB & GUTTER TYPE "CG-1"
  - CONCRETE CURB & GUTTER TYPE "CG-1 DRY"
  - CONCRETE CURB TYPE "C-1" MODIFIED
  - GRADING DETAIL DESIGNATION RE: SHEET C5.1 THRU C5.5


- NOTES:**
1. CONTRACTOR TO REMOVE AND REPLACE ALL SIDEWALK NECESSARY FOR CONNECTION TO EXISTING.
  2. ALL ADA ACCESSIBLE SIDEWALK CROSS SLOPES SHALL HAVE A MAXIMUM CROSS SLOPE OF 2.00% AND MAXIMUM LONGITUDINAL SLOPE OF 5.00%.
  3. ALL ADA ACCESSIBLE PARKING AREAS SHALL NOT EXCEED 2.00% IN ANY DIRECTION.

- SPOT ELEVATION LEGEND**
- ALL SPOT ELEVATIONS ARE TOP OF PAVEMENT ELEVATION UNLESS NOTED OTHERWISE. RE: PLAN VIEW, LEGEND AND DETAILS FOR CURB TYPE AND TO CALCULATE TOP OF CURB ELEVATION.
- TC= TOP OF CURB
  - FG= FINISHED GRADE WITHIN GREENSPACE
  - TS= TOP OF STRUCTURE
  - TP=TC= CURB DEPRESSED TO BE FLUSH WITH ADJACENT PAVEMENT
  - HP= HIGH POINT
  - LP= LOW POINT
  - MATCH EX.= MATCH EXISTING
  - FFE= FINISH FLOOR ELEVATION AT TOP OF SLAB

**MATCHLINE**  
SEE SHEET C1016



DWG: F:\2020\0001-0500\020-0103\40-Design\AutoCAD\Final Plans\Sheets\GNCA\CONSTRUCTION DOCUMENTS\C\_GRD020\_0200103.dwg USER: bklmitch  
DATE: Dec 01, 2021 7:02am XREFS: C\_XBASE\_0200103 V\_XBOL\_00103 T\_PBASE\_0200103 T\_PSAS\_0200103 C\_PSURF\_0200103



**LEGEND**

--- PROPERTY LINE  
--- EXISTING MAJOR CONTOUR  
--- EXISTING MINOR CONTOUR  
--- PROPOSED MAJOR CONTOUR  
--- PROPOSED MINOR CONTOUR

▨ RAMP

CONCRETE CURB & GUTTER TYPE "CG-1"

CONCRETE CURB & GUTTER TYPE "CG-1 DRY"

CONCRETE CURB TYPE "C-1" MODIFIED

(X) GRADING DETAIL DESIGNATION RE: SHEET C5.1 THRU C5.5

- NOTES:**
- CONTRACTOR TO REMOVE AND REPLACE ALL SIDEWALK NECESSARY FOR CONNECTION TO EXISTING.
  - ALL ADA ACCESSIBLE SIDEWALK CROSS SLOPES SHALL HAVE A MAXIMUM CROSS SLOPE OF 2.00% AND MAXIMUM LONGITUDINAL SLOPE OF 5.00%.
  - ALL ADA ACCESSIBLE PARKING AREAS SHALL NOT EXCEED 2.00% IN ANY DIRECTION.

**SPOT ELEVATION LEGEND**

ALL SPOT ELEVATIONS ARE TOP OF PAVEMENT ELEVATION UNLESS NOTED OTHERWISE. RE: PLAN VIEW, LEGEND AND DETAILS FOR CURB TYPE AND TO CALCULATE TOP OF CURB ELEVATION.

TC= TOP OF CURB  
FG= FINISHED GRADE WITHIN GREENSPACE  
TS= TOP OF STRUCTURE  
TP=TC= CURB DEPRESSED TO BE FLUSH WITH ADJACENT PAVEMENT  
HP= HIGH POINT  
LP= LOW POINT  
MATCH EX.= MATCH EXISTING  
FFE= FINISH FLOOR ELEVATION AT TOP OF SLAB

**DLR Group**  
© DLR Group  
80320 DLR Group, Inc., a Missouri corporation,  
Missouri State Certificate of Authority #00939

**olsson**  
OLSSON, CIVIL ENGINEERING  
MO. CERTIFICATE OF AUTHORITY #001992  
7301 West 133rd Street, Suite 200  
Overland Park, KS 66213-4750  
TEL 913.381.1170  
www.olsson.com

**LEE'S SUMMIT MIDDLE SCHOOL #4**  
LEE'S SUMMIT R-7 SCHOOL DISTRICT  
1001 SE BAILEY ROAD  
LEE'S SUMMIT, MO 64081

PACKAGE 2-  
STRUCTURAL & SITE  
UTILITIES  
ISSUED FOR PERMIT  
08/28/20


PR002R 01.14.21  
ASI--030 09.02.21

13-20102-00

GRADING DETAILS

**C1015**

DWG: F:\2020\0001-0500\020-0103\40-Design\AutoCAD\Final Plans\Sheets\GNVC\CONSTRUCTION DOCUMENTS\C\_GR020\_0200103.dwg USER: bklmmich DATE: Dec 01, 2021 7:03am XREFS: C\_XBASE\_0200103 V\_XBOL\_00103 C\_PBASE\_0200103 T\_PBASE\_0200103 T\_PAS\_0200103 C\_PSURF\_0200103




**MATCHLINE**  
SEE SHEET C1014

**LEGEND**

- PROPERTY LINE
- EXISTING MAJOR CONTOUR
- EXISTING MINOR CONTOUR
- PROPOSED MAJOR CONTOUR
- PROPOSED MINOR CONTOUR
- RAMP
- CONCRETE CURB & GUTTER TYPE "CG-1"
- CONCRETE CURB & GUTTER TYPE "CG-1 DRY"
- CONCRETE CURB TYPE "C-1" MODIFIED
- GRADING DETAIL DESIGNATION RE: SHEET C5.1 THRU C5.5

- NOTES:**
- CONTRACTOR TO REMOVE AND REPLACE ALL SIDEWALK NECESSARY FOR CONNECTION TO EXISTING.
  - ALL ADA ACCESSIBLE SIDEWALK CROSS SLOPES SHALL HAVE A MAXIMUM CROSS SLOPE OF 2.00% AND MAXIMUM LONGITUDINAL SLOPE OF 5.00%.
  - ALL ADA ACCESSIBLE PARKING AREAS SHALL NOT EXCEED 2.00% IN ANY DIRECTION.
- SPOT ELEVATION LEGEND**
- ALL SPOT ELEVATIONS ARE TOP OF PAVEMENT ELEVATION UNLESS NOTED OTHERWISE. RE: PLAN VIEW, LEGEND AND DETAILS FOR CURB TYPE AND TO CALCULATE TOP OF CURB ELEVATION.
- |            |   |
|------------|---|
| TC=        | TOP OF CURB                                       |
| FG=        | FINISHED GRADE WITHIN GREENSPACE                  |
| TS=        | TOP OF STRUCTURE                                  |
| TP=TC=     | CURB DEPRESSED TO BE FLUSH WITH ADJACENT PAVEMENT |
| HP=        | HIGH POINT  |
| LP=        | LOW POINT   |
| MATCH EX.= | MATCH EXISTING                                    |
| FFE=       | FINISH FLOOR ELEVATION AT TOP OF SLAB             |



MATCHLINE  
SEE SHEET C1015

MATCHLINE  
SEE SHEET C1019

#### LEGEND

- PROPERTY LINE
- - - - - EXISTING MAJOR CONTOUR
- - - - - EXISTING MINOR CONTOUR
- - - - - PROPOSED MAJOR CONTOUR
- - - - - PROPOSED MINOR CONTOUR
- RAMP
- CONCRETE CURB & GUTTER TYPE "CG-1"
- CONCRETE CURB & GUTTER TYPE "CG-1 DRY"
- CONCRETE CURB TYPE "C-1" MODIFIED
- GRADING DETAIL DESIGNATION RE: SHEET C5.1 THRU C5.5

#### NOTES:


- CONTRACTOR TO REMOVE AND REPLACE ALL SIDEWALK NECESSARY FOR CONNECTION TO EXISTING.
- ALL ADA ACCESSIBLE SIDEWALK CROSS SLOPES SHALL HAVE A MAXIMUM CROSS SLOPE OF 2.00% AND MAXIMUM LONGITUDINAL SLOPE OF 5.00%.
- ALL ADA ACCESSIBLE PARKING AREAS SHALL NOT EXCEED 2.00% IN ANY DIRECTION.

#### SPOT ELEVATION LEGEND

ALL SPOT ELEVATIONS ARE TOP OF PAVEMENT ELEVATION UNLESS NOTED OTHERWISE. RE: PLAN VIEW, LEGEND AND DETAILS FOR CURB TYPE AND TO CALCULATE TOP OF CURB ELEVATION.






- TC= TOP OF CURB
- FG= FINISHED GRADE WITHIN GREENSPACE
- TS= TOP OF STRUCTURE
- TP=TC= CURB DEPRESSED TO BE FLUSH WITH ADJACENT PAVEMENT
- HP= HIGH POINT
- LP= LOW POINT
- MATCH EX.= MATCH EXISTING
- FEE= FINISH FLOOR ELEVATION AT TOP OF SLAB





MATCHLINE  
SEE SHEET C1017

MATCHLINE  
SEE SHEET C1022

- |   |     |  |
|---|-----|--|
| ---   | --- | PROPERTY LINE  |
| ---   | 995 | EXISTING MAJOR CONTOUR                                   |
| ---   | 995 | EXISTING MINOR CONTOUR                                   |
| ---   | 998 | PROPOSED MAJOR CONTOUR                                   |
| ---   | 998 | PROPOSED MINOR CONTOUR                                   |
|   |     |  |
|  |     | RAMP   |
|   |     |  |
|  |     | CONCRETE CURB &<br>GUTTER TYPE "CG-1"                    |
|   |     |  |
|  |     | CONCRETE CURB &<br>GUTTER TYPE "CG-1 DRY"                |
|   |     |  |
|  |     | CONCRETE CURB<br>TYPE "C-1" MODIFIED                     |
|   |     |  |
|  |     | GRADING DETAIL DESIGNATION<br>RE: SHEET C.5.1 THRU C.5.5 |


) NOTES:

1. CONTRACTOR TO REMOVE AND REPLACE ALL SIDEWALK NECESSARY FOR CONNECTION TO EXISTING.
2. ALL ADA ACCESSIBLE SIDEWALK CROSS SLOPES SHALL HAVE A MAXIMUM CROSS SLOPE OF 2.00% AND MAXIMUM LONGITUDINAL SLOPE OF 5.00%.
3. ALL ADA ACCESSIBLE PARKING AREAS SHALL NOT EXCEED 2.00% IN ANY DIRECTION.

## SPOT ELEVATION LEGEND

ALL SPOT ELEVATIONS ARE TOP OF PAVEMENT ELEVATION  
UNLESS NOTED OTHERWISE, RE: PLAN VIEW, LEGEND AND  
DETAILS FOR CURB TYPE AND TO CALCULATE TOP OF  
CURB ELEVATION.

TC= TOP OF CURB  
FG= FINISHED GRADE WITHIN GREENSPACE  
TS= TOP OF STRUCTURE  
TP=TC= CURB DEPRESSED TO BE FLUSH WITH ADJACENT PAVEMENT  
HP= HIGH POINT  
LP= LOW POINT  
MATCH EX.= MATCH EXISTING  
FFE= FINISH FLOOR ELEVATION AT TOP OF SLAB



DWG: F:\2020\0001-0500\020-0103\40-Design\AutoCAD\Final Plans\Sheets\GNV\CONSTRUCTION DOCUMENTS\C\_GR020\_0200103.dwg USER: bklmitch  
DATE: Dec 01, 2021 7:05am XREFS: C\_XBASE\_0200103 V\_XBOL\_00103 C\_PBASE\_0200103 T\_PBASE\_0200103 T\_PSAS\_0200103 C\_PSURF\_0200103



MATCHLINE  
SEE SHEET C1018

#### LEGEND

- PROPERTY LINE
- - - - - EXISTING MAJOR CONTOUR
- - - - - EXISTING MINOR CONTOUR
- — — — — PROPOSED MAJOR CONTOUR
- — — — — PROPOSED MINOR CONTOUR
- [Hatched Area] RAMP
- [L-Shape] CONCRETE CURB & GUTTER TYPE "CG-1"
- [L-Shape] CONCRETE CURB & GUTTER TYPE "CG-1 DRY"
- [L-Shape] CONCRETE CURB TYPE "C-1" MODIFIED
- (X) GRADING DETAIL DESIGNATION RE: SHEET C5.1 THRU C5.5



#### NOTES:

1. CONTRACTOR TO REMOVE AND REPLACE ALL SIDEWALK NECESSARY FOR CONNECTION TO EXISTING.
2. ALL ADA ACCESSIBLE SIDEWALK CROSS SLOPES SHALL HAVE A MAXIMUM CROSS SLOPE OF 2.00% AND MAXIMUM LONGITUDINAL SLOPE OF 5.00%.
3. ALL ADA ACCESSIBLE PARKING AREAS SHALL NOT EXCEED 2.00% IN ANY DIRECTION.


#### SPOT ELEVATION LEGEND

ALL SPOT ELEVATIONS ARE TOP OF PAVEMENT ELEVATION UNLESS NOTED OTHERWISE. RE: PLAN VIEW, LEGEND AND DETAILS FOR CURB TYPE AND TO CALCULATE TOP OF CURB ELEVATION.

- TC= TOP OF CURB
- FG= FINISHED GRADE WITHIN GREENSPACE
- TS= TOP OF STRUCTURE
- TP=TC= CURB DEPRESSED TO BE FLUSH WITH ADJACENT PAVEMENT
- HP= HIGH POINT
- LP= LOW POINT
- MATCH EX.= MATCH EXISTING
- FFE= FINISH FLOOR ELEVATION AT TOP OF SLAB



© DLR Group  
80320 DLR Group, Inc. a Missouri corporation,  
Missouri State Certificate of Authority #00939



www.olson.com

OLSSON, CIVIL ENGINEERING  
MISSOURI CERTIFICATE OF AUTHORITY #001982  
7301 West 133rd Street, Suite 200  
Overland Park, KS 66213-4750 TEL 913.381.1170

## LEE'S SUMMIT MIDDLE SCHOOL #4

LEE'S SUMMIT R-7 SCHOOL DISTRICT

1001 SE BAILEY ROAD  
LEE'S SUMMIT, MO 64081

PACKAGE 2-  
STRUCTURAL & SITE  
UTILITIES  
ISSUED FOR PERMIT  
08/28/20

PR002R 01.14.21


13-20102-00

GRADING DETAILS

C1020

DWG: F:\2020\0001-0500\020-0103\40-Design\AutoCAD\Final Plans\Sheets\GNCA\CONSTRUCTION DOCUMENTS\C\_GR020\_0200103.dwg USER: bklmimich  
DATE: Dec 01, 2021 7:05am XREFS: C\_XBASE\_0200103 C\_PBASE\_0200103 T\_PBASE\_0200103 T\_PSAS\_0200103 C\_PSURF\_0200103

MATCHLINE  
SEE SHEET C1019



#### LEGEND

- PROPERTY LINE
- - - - - EXISTING MAJOR CONTOUR
- - - - - EXISTING MINOR CONTOUR
- - - - - PROPOSED MAJOR CONTOUR
- - - - - PROPOSED MINOR CONTOUR
- ▨ RAMP
- CONCRETE CURB & GUTTER TYPE "CG-1"
- CONCRETE CURB & GUTTER TYPE "CG-1 DRY"
- CONCRETE CURB TYPE "C-1" MODIFIED
- (X) GRADING DETAIL DESIGNATION RE: SHEET C1022 THRU C1023


#### NOTES:



1. CONTRACTOR TO REMOVE AND REPLACE ALL SIDEWALK NECESSARY FOR CONNECTION TO EXISTING.
2. ALL ADA ACCESSIBLE SIDEWALK CROSS SLOPES SHALL HAVE A MAXIMUM CROSS SLOPE OF 2.00% AND MAXIMUM LONGITUDINAL SLOPE OF 5.00%.
3. ALL ADA ACCESSIBLE PARKING AREAS SHALL NOT EXCEED 2.00% IN ANY DIRECTION.

#### SPOT ELEVATION LEGEND






ALL SPOT ELEVATIONS ARE TOP OF PAVEMENT ELEVATION UNLESS NOTED OTHERWISE. RE: PLAN VIEW, LEGEND AND DETAILS FOR CURB TYPE AND TO CALCULATE TOP OF CURB ELEVATION.

- TC= TOP OF CURB
- FG= FINISHED GRADE WITHIN GREENSPACE
- TS= TOP OF STRUCTURE
- TP=TC= CURB DEPRESSED TO BE FLUSH WITH ADJACENT PAVEMENT
- HP= HIGH POINT
- LP= LOW POINT
- MATCH EX.= MATCH EXISTING
- FFE= FINISH FLOOR ELEVATION AT TOP OF SLAB









### LEGEND

	PROPERTY LINE
 995	EXISTING MAJOR CONTOUR
 995	EXISTING MINOR CONTOUR
 998	PROPOSED MAJOR CONTOUR
 998	PROPOSED MINOR CONTOUR

	RAMP
	CONCRETE CURB & GUTTER TYPE "CG-1"
	CONCRETE CURB & GUTTER TYPE "CG-1 DRY"
	CONCRETE CURB TYPE "C-1" MODIFIED


NOTES:

1. CONTRACTOR TO REMOVE AND REPLACE ALL SIDEWALK NECESSARY FOR CONNECTION TO EXISTING.
2. ALL ADA ACCESSIBLE SIDEWALK CROSS SLOPES SHALL HAVE A MAXIMUM CROSS SLOPE OF 2.00% AND MAXIMUM LONGITUDINAL SLOPE OF 5.00%.
3. ALL ADA ACCESSIBLE PARKING AREAS SHALL NOT EXCEED 2.00% IN ANY DIRECTION.


### SPOT ELEVATION LEGEND

ALL SPOT ELEVATIONS ARE TOP OF PAVEMENT ELEVATION  
UNLESS NOTED OTHERWISE. RE: PLAN VIEW, LEGEND AND  
DETAILS FOR CURB TYPE AND TO CALCULATE TOP OF  
CURB ELEVATION.

TC= TOP OF CURB  
FG= FINISHED GRADE WITH GREENSPACE  
TS= TOP OF STRUCTURE  
TP=TC= CURB DEPRESSED TO BE FLUSH WITH  
ADJACENT PAVEMENT  
HP= HIGH POINT  
LP= LOW POINT  
MATCH EX.= MATCH EXISTING  
FFE= FINISH FLOOR ELEVATION AT TOP OF SLAB



DWG: F:\2020\0001-0500\020-0103\40-Design\AutoCAD\Final Plans\Sheets\GNV\CONSTRUCTION DOCUMENTS\C\_GRD05\_0200103.dwg USER: bklmitch  
DATE: Dec 01, 2021 7:07am XREFS: C\_XBASE\_0200103 V\_XBOL\_00103 C\_PBASE\_0200103 C\_PTLBLK\_0200103 C\_PSURF\_0200103 T\_PBASE\_0200103 T\_PFSAS\_0200103



GRADING DETAIL C  
SCALE: 1"=5'




GRADING DETAIL CC  
SCALE: 1"=5'


- LEGEND**
- PROPERTY LINE
  - 995 EXISTING MAJOR CONTOUR
  - 995 EXISTING MINOR CONTOUR
  - 998 PROPOSED MAJOR CONTOUR
  - 998 PROPOSED MINOR CONTOUR
  - RAMP
  - CONCRETE CURB & GUTTER TYPE "CG-1"
  - CONCRETE CURB & GUTTER TYPE "CG-1 DRY"
  - CONCRETE CURB TYPE "C-1" MODIFIED

- NOTES:**
- CONTRACTOR TO REMOVE AND REPLACE ALL SIDEWALK NECESSARY FOR CONNECTION TO EXISTING.
  - ALL ADA ACCESSIBLE SIDEWALK CROSS SLOPES SHALL HAVE A MAXIMUM CROSS SLOPE OF 2.00% AND MAXIMUM LONGITUDINAL SLOPE OF 5.00%.
  - ALL ADA ACCESSIBLE PARKING AREAS SHALL NOT EXCEED 2.00% IN ANY DIRECTION.


- SPOT ELEVATION LEGEND**  
ALL SPOT ELEVATIONS ARE TOP OF PAVEMENT ELEVATION UNLESS NOTED OTHERWISE. RE: PLAN VIEW, LEGEND AND DETAILS FOR CURB TYPE AND TO CALCULATE TOP OF CURB ELEVATION.
- TC= TOP OF CURB
  - FG= FINISHED GRADE WITHIN GREENSPACE
  - TS= TOP OF STRUCTURE
  - TP=TC= CURB DEPRESSED TO BE FLUSH WITH ADJACENT PAVEMENT
  - HP= HIGH POINT
  - LP= LOW POINT
  - MATCH EX.= MATCH EXISTING
  - FFE= FINISH FLOOR ELEVATION AT TOP OF SLAB




DWG: F:\2020\0001-0500\020-0103\40-Design\AutoCAD\Final Plans\Sheets\GNV\CONSTRUCTION DOCUMENTS\C\_GRD05\_0200103.dwg USER: bklmmlch  
DATE: Dec 01, 2021 7:09am XREFS: C\_XBASE\_0200103 V\_XBOL\_00103 C\_PBASE\_0200103 C\_PTBK\_0200103 T\_PBASE\_0200103 T\_PFSAS\_0200103




GRADING DETAIL D  
SCALE: 1"=5'



GRADING DETAIL F  
SCALE: 1"=5'



GRADING DETAIL E  
SCALE: 1"=5'



GRADING DETAIL G  
SCALE: 1"=5'

GRADING DETAIL H  
SCALE: 1"=5'

LEGEND	
---	PROPERTY LINE
---	EXISTING MAJOR CONTOUR
---	EXISTING MINOR CONTOUR
---	PROPOSED MAJOR CONTOUR
---	PROPOSED MINOR CONTOUR
---	RAMP
---	CONCRETE CURB & GUTTER TYPE "CG-1"
---	CONCRETE CURB & GUTTER TYPE "CG-1 DRY"
---	CONCRETE CURB TYPE "C-1" MODIFIED


#### NOTES:

1. CONTRACTOR TO REMOVE AND REPLACE ALL SIDEWALK NECESSARY FOR CONNECTION TO EXISTING.
2. ALL ADA ACCESSIBLE SIDEWALK CROSS SLOPES SHALL HAVE A MAXIMUM CROSS SLOPE OF 2.00% AND MAXIMUM LONGITUDINAL SLOPE OF 5.00%.
3. ALL ADA ACCESSIBLE PARKING AREAS SHALL NOT EXCEED 2.00% IN ANY DIRECTION.

#### SPOT ELEVATION LEGEND

ALL SPOT ELEVATIONS ARE TOP OF PAVEMENT ELEVATION UNLESS NOTED OTHERWISE. RE: PLAN VIEW, LEGEND AND DETAILS FOR CURB TYPE AND TO CALCULATE TOP OF CURB ELEVATION.

TC=	TOP OF CURB
FG=	FINISHED GRADE WITHIN GREENSPACE
TS=	TOP OF STRUCTURE
TP=TC=	CURB DEPRESSED TO BE FLUSH WITH ADJACENT PAVEMENT
HP=	HIGH POINT
LP=	LOW POINT
MATCH EX.=	MATCH EXISTING
FFE=	FINISH FLOOR ELEVATION AT TOP OF SLAB



## LEE'S SUMMIT MIDDLE SCHOOL #4

LEE'S SUMMIT R-7 SCHOOL DISTRICT

1001 SE BAILEY ROAD  
LEE'S SUMMIT, MO 64861


PACKAGE 2-  
STRUCTURAL & SITE  
UTILITIES  
ISSUED FOR PERMIT  
08/28/20

PR002R 01.14.21  
PR-16 10.12.21

13-20102-00




GRADING DETAILS

C1023



**olsson**  
OLSSON, CIVIL ENGINEERING  
MO. CERTIFICATE OF AUTHORITY #001592  
7301 West 133rd Street, Suite 200  
Overland Park, KS 66213-4750  
TEL 913.381.1170  
www.olsson.com

**DLR Group**  
© DLR Group  
8030 DLR Group, Inc. a Missouri corporation,  
Missouri State Certificate of Authority #00099






- NOTES:**
1. CONTRACTOR TO REMOVE AND REPLACE ALL SIDEWALK NECESSARY FOR CONNECTION TO EXISTING.
  2. ALL ADA ACCESSIBLE SIDEWALK CROSS SLOPES SHALL HAVE A MAXIMUM CROSS SLOPE OF 2.00% AND MAXIMUM LONGITUDINAL SLOPE OF 5.00%.
  3. ALL ADA ACCESSIBLE PARKING AREAS SHALL NOT EXCEED 2.00% IN ANY DIRECTION.


## SPOT ELEVATION LEGEND

ALL SPOT ELEVATIONS ARE TOP OF PAVEMENT ELEVATION  
UNLESS NOTED OTHERWISE. RE: PLAN VIEW, LEGEND AND  
DETAILS FOR CURB TYPE AND TO CALCULATE TOP OF  
CURB ELEVATION.


TC= TOP OF CURB  
FG= FINISHED GRADE WITHIN GREENSPACE  
TS= TOP OF STRUCTURE  
TP=TC= CURB DEPRESSED TO BE FLUSH WITH  
ADJACENT PAVEMENT  
HP= HIGH POINT  
LP= LOW POINT  
MATCH EX.= MATCH EXISTING  
FFE= FINISH FLOOR ELEVATION AT TOP OF SLAB




DWG: F:\2020\0001-0500\020-0103\40-Design\AutoCAD\Final Plans\Sheets\GNV\CONSTRUCTION DOCUMENTS\C\_GRD05\_0200103.dwg USER: bkimnich DATE: Dec 01, 2021 7:12am XREFS: C\_XBASE\_0200103 C\_PBASE\_0200103 V\_XBOL\_00103 C\_PTEBK\_0200103 C\_PSURF\_0200103 T\_PBASE\_0200103 T\_PSAS\_0200103




GRADING DETAIL L  
SCALE: 1"=5'



GRADING DETAIL N  
SCALE: 1"=5'



GRADING DETAIL M  
SCALE: 1"=5'



GRADING DETAIL N  
SCALE: 1"=5'


LEGEND	
	PROPERTY LINE
	EXISTING MAJOR CONTOUR
	EXISTING MINOR CONTOUR
	PROPOSED MAJOR CONTOUR
	PROPOSED MINOR CONTOUR
	RAMP
	CONCRETE CURB & GUTTER TYPE "CG-1"
	CONCRETE CURB & GUTTER TYPE "CG-1 DRY"
	CONCRETE CURB TYPE "C-1" MODIFIED


- NOTES:**
1. CONTRACTOR TO REMOVE AND REPLACE ALL SIDEWALK NECESSARY FOR CONNECTION TO EXISTING.
  2. ALL ADA ACCESSIBLE SIDEWALK CROSS SLOPES SHALL HAVE A MAXIMUM CROSS SLOPE OF 2.00% AND MAXIMUM LONGITUDINAL SLOPE OF 5.00%.
  3. ALL ADA ACCESSIBLE PARKING AREAS SHALL NOT EXCEED 2.00% IN ANY DIRECTION.

**SPOT ELEVATION LEGEND**

ALL SPOT ELEVATIONS ARE TOP OF PAVEMENT ELEVATION UNLESS NOTED OTHERWISE. RE: PLAN VIEW, LEGEND AND DETAILS FOR CURB TYPE AND TO CALCULATE TOP OF CURB ELEVATION.

TC=	TOP OF CURB
FG=	FINISHED GRADE WITHIN GREENSPACE
TS=	TOP OF STRUCTURE
TP=TC=	CURB DEPRESSED TO BE FLUSH WITH ADJACENT PAVEMENT
HP=	HIGH POINT
LP=	LOW POINT
MATCH EX.=	MATCH EXISTING
FFE=	FINISH FLOOR ELEVATION AT TOP OF SLAB





GRADING DETAIL N


SCALE: 1"=5'

LEGEND

PROPERTY LINE	
995	EXISTING MAJOR CONTOUR
995	EXISTING MINOR CONTOUR
998	PROPOSED MAJOR CONTOUR
998	PROPOSED MINOR CONTOUR



RAMP



CONCRETE CURB &  
GUTTER TYPE "CG-1"

CONCRETE CURB &  
GUTTER TYPE "CG-1 DRY"

CONCRETE CURB  
TYPE "C-1" MODIFIED


NOTES:


1. CONTRACTOR TO REMOVE AND REPLACE ALL SIDEWALK NECESSARY FOR CONNECTION TO EXISTING.
2. ALL ADA ACCESSIBLE SIDEWALK CROSS SLOPES SHALL HAVE A MAXIMUM CROSS SLOPE OF 2.00% AND MAXIMUM LONGITUDINAL SLOPE OF 5.00%.
3. ALL ADA ACCESSIBLE PARKING AREAS SHALL NOT EXCEED 2.00% IN ANY DIRECTION.
4. REFERENCE SHEET C1026 FOR LANDSCAPE AND ROOF DRAIN KEYNOTE ELEVATIONS.

### SPOT ELEVATION LEGEND

ALL SPOT ELEVATIONS ARE TOP OF PAVEMENT ELEVATION  
UNLESS NOTED OTHERWISE. RE: PLAN VIEW, LEGEND AND  
DETAILS FOR CURB TYPE AND TO CALCULATE TOP OF  
CURB ELEVATION.

TC= TOP OF CURB  
FG= FINISHED GRADE WITHIN GREENSPACE  
TS= TOP OF STRUCTURE  
TP=TC= CURB DEPRESSED TO BE FLUSH WITH  
ADJACENT PAVEMENT  
HP= HIGH POINT  
LP= LOW POINT  
MATCH EX.= MATCH EXISTING  
FFE= FINISH FLOOR ELEVATION AT TOP OF SLAB





KEY NOTES (CONT):

COMMUNICATIONS:  
C1. INSTALL 352± LF OF 2-4" PVC CONDUIT W/PULL STRING. COORDINATE CONNECTION AND LOCATION WITH COMMUNICATIONS COMPANY.

BACKFLOW DRAIN:  
BD-1. INSTALL 42 LF OF 2" SDR26 PVC PIPE FROM BFP PIT TO DETENTION BASIN @ 1% MINIMUM SLOPE

SANITARY SERVICE:  
SS-15. INSTALL 51.3 LF OF 4" PVC (SDR-26) SANITARY SERVICE FROM SS-14 TO BUILDING (INV EL=1014.25) RE:MEP  
SS-16. INSTALL 47.0 LF OF 4" PVC (SDR-26) SANITARY SERVICE FROM SS-11 TO BUILDING (INV EL=1005.00) RE:MEP  
SS-17. INSTALL 47.0 LF OF 4" PVC (SDR-26) SANITARY SERVICE FROM SS-10 TO BUILDING (INV EL=1003.45) RE:MEP  
SS-18. INSTALL 60.8 LF OF 4" PVC (SDR-26) SANITARY SERVICE FROM SS-8 TO BUILDING (INV EL=1005.00) RE:MEP

KEY NOTES:

DOMESTIC WATER  
W1. WATERLINE TO CONCESSION BLDG AND IRRIGATION  
a. INSTALL 6x6x3 CUT-IN TEE ON PUBLIC MAIN COMING UNDER STREET  
b. INSTALL 15' LF OF 4" AWWA C900 PIPE FROM TEE TO METER  
c. INSTALL 3" 90° ELBOW  
d. INSTALL 2" METER AND PIT PER STANDARD CITY DETAIL  
e. INSTALL A MINIMUM 10 LF 3" AWWA C900 FROM METER TOWARDS BUILDING  
f. CONTINUE BUILDING SERVICE CONNECTION WITH 1018± LF OF 3" AWWA C900 PIPE RE: MEP FOR CONNECTION TO BLDG AND BACKFLOW PREVENTION.  
g. INSTALL 3x3x3 TEE AND 12 LF 3" AWWA C900 PIPE  
h. INSTALL 2" DUCTILE METER (FOR IRRIGATION) IN METER PIT PER CITY STANDARD DETAIL  
i. CONTINUE IRRIGATION SERVICE INCLUDING BACKFLOW PREVENTION AND BOOSTER PUMP PER LANDSCAPE PLANS

PUBLIC WATER (CONSTRUCT PER PUBLIC IMPROVEMENT PLANS)  
ALL WORK ON THE PUBLIC MAIN SHALL BE CONSTRUCTED AND INSTALLED PER CITY STANDARDS, INCLUDING WATER SHUT OFF, PUBLIC NOTIFICATION AND CONSTRUCTION AT NIGHT  
PW1. PROPOSED 16" BUTTERFLY VALVE ON PUBLIC WATER MAIN  
PW2. PUBLIC WATER MAIN WILL BE INSTALLED BY BORE UNDER BAILEY ROAD  
PW3. CUT 16x16x6 TEE ON PUBLIC MAIN  
PW4. INSTALL 6" GATE VALVE ON NORTH SIDE OF BAILEY ROAD

FIRE PROTECTION:  
ALL FIRE PROTECTION LINE SHALL BE 6" AWWA C900 U.N.O. ALL PUBLIC FITTINGS AND FIRE PROTECTION LINE FITTINGS MUST BE ZINC COATED DUCTILE IRON PIPE REFERENCE SHEETS C1028A AND C1028B FOR PROFILES AND KEYNOTE DESCRIPTIONS.

SANITARY SEWER:  
REF: SHEET C1028C FOR PROFILES AND KEYNOTE DESCRIPTIONS


ELECTRICAL:

INSTALL ELECTRICAL SERVICE PER EVERY DRAWING FILE NO. 977368-1. CONTRACTOR TO INSTALL TRANSFORMER AND SECTIONALIZER PADS AND CONDUIT PER UTILITY COMPANY STANDARDS AND SPECIFICATIONS. VERIFY CONDUIT SIZE AND ROUTING WITH EVERY PRIOR TO INSTALLATION. ELECTRICAL DESIGN IS BY EVERY. SEE MEP PLANS FOR LIGHTING AND LIGHTING CONDUIT.

- E1. TRANSFORMER LOCATION.
- E2. INSTALL 4" PVC CONDUIT (5300 LF TOTAL FOR SHEETS C1026 AND C1027)
- E3. SECTIONALIZER LOCATION.
- E4. RISER CONNECTION TO POLE BY EVERY.

LANDSCAPE AND ROOF DRAINS:

[LEN REFERS TO LENGTH OF THE DOWNSLOPE/PIPE FROM THE STRUCTURE (IN LINEAL FEET, ALL PIPE SHALL SLOPE)]																															
KEYNOTE		DS STRUC	TYPE	YS	IE	N	LEN	IE	NE	LEN	IE	E	SE	LEN	IE	S	SW	LEN	IE	W	LEN	IE	NW	SIZE	LEN	SLOPE					
L5-1	G8		CONNECTION TO G9	1016.26																											
L5-2	G9 (L5-3)	24"	NYLOPLAST BASIN W GRATED LID	1016.30									1009.84	15	24.4													1.07%			
L5-3	L5-2	24"	NYLOPLAST BASIN W GRATED LID	1016.70			1010.58	12					1010.58	15	25.5													1.01%			
L5-4	L5-3	24"	NYLOPLAST BASIN W GRATED LID	1016.69																								1.00%			
L5-5	L5-4	24"	NYLOPLAST BASIN W GRATED LID	1016.69									1011.18	12	60													1.05%			
L5-6	L5-5	24"	NYLOPLAST BASIN W GRATED LID	1016.53									1012.05	12	38.6													1.01%			
L5-7	L5-6	24"	NYLOPLAST BASIN W GRATED LID	1016.51									1012.35	12	35.8													0.84%			
L5-8	L5-7	24"	NYLOPLAST BASIN W GRATED LID	1015.85		1012.67	10						1012.67	12	40.6													0.79%			
L5-9	L5-8	24"	NYLOPLAST BASIN W GRATED LID	1016.00									1013.15	10														0.77%			
L5-10	L5-9	24"	NYLOPLAST BASIN W GRATED LID	1014.00									1012.95	8	15.3													0.98%			
L5-11	L5-3	24"	NYLOPLAST BASIN W GRATED LID	1016.70									1011.51	12	48.2													0.89%			
L5-12	L5-11	24"	NYLOPLAST BASIN W GRATED LID	1016.72									1011.85	12	38.6													0.80%			
L5-13	L5-12	24"	NYLOPLAST BASIN W GRATED LID	1016.81									1012.02	10	72.2													0.92%			
L5-14	L5-13	24"	NYLOPLAST BASIN W GRATED LID	1013.86									1012.52	8	78.3													0.64%			
L5-17	E6		CONNECTION TO E7	1022.25																											
L5-18	E7 (L5-17)	24"	NYLOPLAST BASIN W GRATED LID	1022.50									1020.46	8	61													1.79%			
L5-19	L5-18	24"	NYLOPLAST BASIN W GRATED LID	1013.36									1011.35	8	89.2													0.71%			
L5-20	L5-18	24"	NYLOPLAST BASIN W GRATED LID	1014.10																								0.86%			
L5-21	G9		CONNECTION TO G8	1016.69									1009.84															1.04%			
L5-22	G8 (L5-21)	24"	NYLOPLAST BASIN W GRATED LID	1010.40		1009.84	8						1009.84	10														0.92%			
L5-23	L5-22	24"	NYLOPLAST BASIN W GRATED LID	1010.67									1008.21	8	57.2													1.64%			
L5-24	L5-23	24"	NYLOPLAST BASIN W GRATED LID	1010.67									1009.92	6														1.00%			
L5-25	L5-24	24"	NYLOPLAST BASIN W GRATED LID	1010.83																								1.00%			
L5-26	G1		CONNECT TO H1	1008.46									1002.60	12																	
L5-27	H1 (L5-26)	24"	NYLOPLAST BASIN W GRATED LID	1010.55									1003.94	8														1.01%			
L5-28	L5-27	24"	NYLOPLAST BASIN W GRATED LID	1007.00									1003.94	8	60.4													0.99%			
L5-29	L5-28	24"	NYLOPLAST BASIN W GRATED LID	1007.00																								1.01%			
L5-30	K2		CONNECTION TO K3	1007.79																											
L5-31	K3		CONNECTION TO K4	1009.74																											
L5-32	K4		CONNECTION TO K5	1009.78																											
L5-33	F7		CONNECTION TO F8	1006.41									1003.65	12																	
L5-34	F8 (L5-33)	24"	NYLOPLAST BASIN W GRATED LID	1006.08																											
L5-35	L5-34	24"	NYLOPLAST BASIN W GRATED LID	1006.63									1003.96	12	22.1													0.90%			
L5-36	L5-35	24"	NYLOPLAST BASIN W GRATED LID	1009.76									1001.23	10														0.52%			
L5-37	L5-36	24"	NYLOPLAST BASIN W GRATED LID	1009.96									1005.60	10	36.1													2.48%			
L5-38	F5		CONNECTION TO F6	1006.52																											
L5-39	L5-38	24"	NYLOPLAST BASIN W GRATED LID	1004.95		1007.35	12	17.3					1002.35	8														0.52%			
L5-40	L5-39	24"	NYLOPLAST BASIN W GRATED LID	1004.76																											
L5-41	L5-40	24"	NYLOPLAST BASIN W GRATED LID	1004.76																											
L5-42	L5-41	24"	NYLOPLAST BASIN W GRATED LID	1003.68																											
L5-44	L5-39	24"	NYLOPLAST BASIN W GRATED LID	1003.48																											
L5-45	L5-44	24"	NYLOPLAST BASIN W GRATED LID	1004.92									1003.48	8	40.9																
L5-46	L5-45	24"	NYLOPLAST BASIN W GRATED LID	1004.92																											
L5-47	L5-46	24"	NYLOPLAST BASIN W GRATED LID	1004.61																											
L5-48	A4		CONNECTION TO A5	1013.00									1002.04	10																	
L5-49	A5 (L5-48)	24"	NYLOPLAST BASIN W SOLID LID	1013.96																											
L5-49A	L5-49		CONNECT TO RET WALL FOUND DRAIN	1022.86																											
L5-50	A2		CONNECTION TO A3	1014.37																											
L5-51	A3 (L5-50)	24"	NYLOPLAST BASIN W SOLID LID	1014.00									1011.30	12	85.7																
L5-54	G7		CONNECTION TO G8	1016.03									1010.50	6																	
L5-55	G8 (L5-54)	24"	NYLOPLAST BASIN W SOLID LID	1016.55			1013.20	6					1013.00	8	49.2																
L5-55A	G8 (L5-54)	24"	NYLOPLAST BASIN W SOLID LID	1016.55			1013.60	6					1013.02	6																	
L5-56	LINE A		INSERT-A-TEE W/ 8" FIELD DRAIN	1014.92																											
L5-57	LINE A		INSERT-A-TEE W/ 8" FIELD DRAIN	1014.20																											
L5-58	F2		CONNECTION TO F3	1003.68									998.88	12																	
L5-59	F3 (L5-58)	24"	NYLOPLAST BASIN W GRATED LID	1004.67									999.13	10																	
L5-60	L5-59		DN 10x10 TEE	1005.00									1000.27	10	11.9																
L5-61	L5-60	24"	NYLOPLAST BASIN W GRATED LID	1005.00									999.95	8																	
L5-62	L5-61	24"	NYLOPLAST BASIN W GRATED LID	1003.00									1000.76	8	81.1																
L5-63	L5-62	24"	NYLOPLAST BASIN W GRATED LID	1003.00									1001.60	6	74																
L5-64	L5-59	24"	NYLOPLAST BASIN W GRATED LID	1005.00									999.61	8	37.2																
L5-65	L5-64	24"	NYLOPLAST BASIN W GRATED LID	1003.00									1000.14	8																	
L5-66	L5-65	24"	NYLOPLAST BASIN W GRATED LID	1003.00									1000.82	8	82.8																
L5-67	L5-66	24"	NYLOPLAST BASIN W GRATED LID	1003.00									1001.50	6	85.2																
L5-68	L5-72	18"	NYLOPLAST BASIN W GRATED LID	1006.00									1005.03	8	36.2																
L5-69	L5-68	18"	NYLOPLAST BASIN W GRATED LID	1006.00																											
L5-70	L5-73	18"	NYLOPLAST BASIN W GRATED LID	1006.00									1001.13	8	25.4																
L5-71	L5-72	18"	NYLOPLAST BASIN W GRATED LID	1006.00									1001.13	8	25.4																
L5-72	L5-73		Bx6&TEE	NA								1006.95	8	16.2																	
L5-73	L5-35		Bx6&TEE	NA								1004.88	8	9.5																	
L5-74	L5-48		INSERT-A-TEE W/ 8" FIELD DRAIN	1014.40																											
L5-75	LINE A		INSERT-A-TEE W/ 8" FIELD DRAIN	1014.00																											
RD-1	L5-5		ROOF DRAIN CONNECTION	1013.40	6	5																						34.80%			
RD-2	L5-6		ROOF DRAIN CONNECTION	1013.40	6	5																						27.00%			
RD-3	L5-11		ROOF DRAIN CONNECTION										1013.40	6	8													31.67%			
RD-4	L5-12		ROOF DRAIN CONNECTION																												



**WATERLINE (DUGOUT)**

W-1 INSTALL LF OF 2" AWWA C901 PIPE CONNECT TO BLDG SUPPLY

W-2 INSTALL 2" CROSS TEE AND:  
NORTH - 66 LF OF 1" AWWA C901 PIPE WITH REDUCER AND BENDS  
EAST - 45 LF OF 2" AWWA C901 PIPE WITH BENDS  
SOUTH - 66 LF OF 1" AWWA C901 PIPE WITH REDUCER AND BENDS

W-3 STUB UP SUPPLY PIPE AND CONNECT TO SUPPLY LINE ON DUGOUT DRINKING FOUNTAIN (REF: LS DRAWINGS)

W-4 INSTALL 2" CROSS TEE AND:  
NORTH - 123 LF OF 1" AWWA C901 PIPE WITH REDUCER AND BENDS  
EAST - 37 LF OF 1" AWWA C901 PIPE WITH REDUCER  
SOUTH - 265 LF OF 2" AWWA C901 PIPE

W-5 INSTALL 2x2x2 TEE AND 177 LF OF 1" AWWA C901 PIPE WITH REDUCER AND BENDS

W-6 INSTALL 1x1x1 TEE AND 38 LF OF 1" AWWA C901 PIPE

W-7 INSTALL 2x2x2 TEE AND 22 LF OF 1" AWWA C901 PIPE WITH REDUCER AND BENDS

W-8 INSTALL BEND AND REDUCER AND 48 LF OF 1" AWWA C901 PIPE

**SANITARY SEWER SERVICE (DUGOUT)**

SS-56 INSTALL WYE ON SERVICE LINE AND 18 LF OF 3" PVC (SDR-26) AT 1.0% PERCENT MINIMUM SLOPE

SS-57 STUB UP PVC PIPE AND CONNECT TO DRAIN LINE ON DUGOUT DRINKING FOUNTAIN (REF: LS DRAWINGS)

SS-58 INSTALL WYE ON SERVICE LINE AND 74 LF OF 3" PVC (SDR-26) AT 1.0% PERCENT MINIMUM SLOPE

SS-59 INSTALL WYE ON SERVICE LINE AND 165 LF OF 3" PVC (SDR-26) WITH BENDS AT 1.0% PERCENT MINIMUM SLOPE

SS-60 INSTALL 2x2x2 TEE ON SERVICE LINE AND 69 LF OF 3" PVC (SDR-26) WITH BENDS AT 1.0% PERCENT MINIMUM SLOPE

SS-61 INSTALL WYE ON SERVICE LINE AND 199 LF OF 3" PVC (SDR-26) WITH BENDS AT 1.0% PERCENT MINIMUM SLOPE

SS-62 INSTALL 2x2x2 TEE ON SERVICE LINE AND 22 LF OF 3" PVC (SDR-26) AT 1.0% PERCENT MINIMUM SLOPE

SS-63 INSTALL 2x2x2 TEE ON SERVICE LINE AND 90 LF OF 3" PVC (SDR-26) WITH BENDS AT 1.0% PERCENT MINIMUM SLOPE


SS-64 INSTALL WYE ON SERVICE LINE AND 90 LF OF 3" PVC (SDR-26) WITH BENDS AT 1.0% PERCENT MINIMUM SLOPE

**EXISTING CONDITIONS LEGEND**


---	PROPERTY LINES
---	RIGHT-OF-WAY LINES
---	EASEMENT LINES
P-OH	OVERHEAD ELECTRIC
P-UG	UNDERGROUND ELECTRIC
TEL	UNDERGROUND TELEPHONE
FO	UNDERGROUND FIBER OPTIC
G	GAS LINE
W	WATER LINE
SS	STORM SEWER LINE
SS	SANITARY SEWER LINE

**PROPOSED CONDITIONS LEGEND**

E	PROPOSED UNDERGROUND ELECTRIC
FO	PROPOSED FIBER OPTIC
W	PROPOSED WATER LINE
FP	PROPOSED FIRE PROTECTION LINE
SD	PROPOSED STORM SEWER LINE
T	PROPOSED TURF DRAIN LINE
SS	PROPOSED SANITARY SEWER SERVICE
---	CONCRETE CURB & GUTTER
---	PROPOSED BUILDING







#### EXISTING CONDITIONS LEGEND

- PROPERTY LINES
- RIGHT-OF-WAY LINES
- EASEMENT LINES
- P-OH OVERHEAD ELECTRIC
- P-UG UNDERGROUND ELECTRIC
- TEL UNDERGROUND TELEPHONE
- FO UNDERGROUND FIBER OPTIC
- G GAS LINE
- W WATER LINE
- SS STORM SEWER LINE
- SS SANITARY SEWER LINE


#### PROPOSED CONDITIONS LEGEND

- E PROPOSED UNDERGROUND ELECTRIC
- FO PROPOSED FIBER OPTIC
- W PROPOSED WATER LINE
- FP PROPOSED FIRE PROTECTION LINE
- SD PROPOSED STORM SEWER LINE
- T PROPOSED TURF DRAIN LINE
- SS PROPOSED SANITARY SEWER SERVICE
- CONCRETE CURB & GUTTER
- PROPOSED BUILDING


#### LANDSCAPE AND ROOF DRAINS:

ELEV REFERS TO THE LENGTH OF THE DOWNSPILL/RAIN PIPE FROM THE STRUCTURE (IN LINEAL FEET, ALL PIPE SHALL SLOPE)																							
KEYNOTE	DS STRUC	TYPE	TS	IE	N SIZE	LEN	IE	NE SIZE	LEN	IE	E SIZE	LEN	IE	SE SIZE	LEN	IE	S SIZE	LEN	IE	SW SIZE	LEN	SLOPE	
LS-1	G8	CONNECTION TO G9	1016.20																				
LS-2	G9 (LS-3)	24" NYLOPLAST BASIN W GRATED LID	1016.30								1009.84	15	24.4							1009.58	15		1.07%
LS-3	LS-2	24" NYLOPLAST BASIN W GRATED LID	1016.70	1010.58	12						1010.58	15	73.5							1010.58	12		1.01%
LS-4	LS-3	24" NYLOPLAST BASIN W GRATED LID	1016.69												1011.18	12	60			1011.18	12		1.00%
LS-5	LS-4	24" NYLOPLAST BASIN W GRATED LID	1016.69								1011.66	12	45.9							1011.66	6		1.05%
LS-6	LS-5	24" NYLOPLAST BASIN W GRATED LID	1016.51								1012.05	12	38.6							1012.05	12		1.01%
LS-7	LS-6	24" NYLOPLAST BASIN W GRATED LID	1016.51								1012.95	12	35.8							1012.95	12		0.84%
LS-8	LS-7	24" NYLOPLAST BASIN W GRATED LID	1015.85	1012.67	10						1012.67	12	40.6							1012.80	10	16.9	0.77%
LS-9	LS-8	24" NYLOPLAST BASIN W SOLID LID	1016.00								1013.13	10								1012.80	8		0.77%
LS-10	LS-9	24" NYLOPLAST BASIN W GRATED LID	1016.00											1012.95	8	11.3						0.98%	
LS-11	LS-10	24" NYLOPLAST BASIN W GRATED LID	1016.70	1011.51	6						1011.51	12	68.2							1011.51	12		0.89%
LS-12	LS-11	24" NYLOPLAST BASIN W GRATED LID	1016.72	1011.85	6						1011.85	12	38.6							1011.85	10		0.88%
LS-13	LS-12	24" NYLOPLAST BASIN W GRATED LID	1016.81								1012.02	10	73.2							1012.02	8		0.92%
LS-14	LS-13	24" NYLOPLAST BASIN W GRATED LID	1016.86								1012.52	8	78.3										0.64%
LS-17	F6	CONNECTION TO F7	1016.35																				
LS-18	E7 (LS-17)	24" NYLOPLAST BASIN W GRATED LID	1014.50								1010.16	8								1010.16	8	64	1.78%
LS-19	LS-18	24" NYLOPLAST BASIN W GRATED LID	1013.36								1011.35	8	89.2										1.01%
LS-20	LS-19	24" NYLOPLAST BASIN W GRATED LID	1014.50																	1011.34	8	87.64	1.00%
LS-21	G3	CONNECTION TO G3	1016.41								1009.78	12											
LS-22	G61 (LS-21)	24" NYLOPLAST BASIN W GRATED LID	1010.40	1001.84	8									1009.84	10					1009.84	12	81.3	0.14%
LS-23	LS-22	24" NYLOPLAST BASIN W GRATED LID	1010.67								1009.21	8								1009.21	8	57.2	7.64%
LS-24	LS-23	24" NYLOPLAST BASIN W GRATED LID	1010.47	1001.32	10	48.1					1009.32	6								1009.32	8		1.00%
LS-25	LS-24	24" NYLOPLAST BASIN W GRATED LID	1010.83	1005.27	6	95.1														1005.27	6		1.00%
LS-26	G1	CONNECT TO H1	1008.46								1002.60	12											
LS-27	H1 (LS-26)	24" NYLOPLAST BASIN W GRATED LID	1008.55								1001.14	8								1002.08	10	39.8	1.01%
LS-28	LS-27	24" NYLOPLAST BASIN W GRATED LID	1007.00								1003.34	8								1003.34	8	60.4	0.99%
LS-29	LS-28	24" NYLOPLAST BASIN W GRATED LID	1007.00																	1003.88	8	53.5	1.01%
LS-30	K2	CONNECTION TO K3	1007.79																	1005.95	8		
LS-31	K3	CONNECTION TO K4	1009.74																	1005.95	8		
LS-32	K4	CONNECTION TO K5	1009.78																	1005.62	8		
LS-33	F7	CONNECTION TO F8	1006.41								1003.65	12											
LS-34	F8 (LS-33)	24" NYLOPLAST BASIN W GRATED LID	1006.08																	1003.76	12	24.6	0.37%
LS-35	LS-34	24" NYLOPLAST BASIN W GRATED LID	1006.03								1003.96	12	22.1							1003.96	8		0.90%
LS-36	LS-35	24" NYLOPLAST BASIN W GRATED LID	1009.76								1001.23	10								1001.23	12	34.9	0.50%
LS-37	LS-36	24" NYLOPLAST BASIN W GRATED LID	1009.76								1000.60	6								1000.60	10	36.1	2.48%
LS-38	F5	CONNECTION TO F6	1006.52																	1002.26	12		
LS-39	LS-38	24" NYLOPLAST BASIN W GRATED LID	1004.95	1002.55	12	17.5					1002.55	8								1002.55	8		0.52%
LS-40	LS-39	24" NYLOPLAST BASIN W SOLID LID	1004.95								1002.61	8								1002.61	8	53.8	0.60%
LS-41	LS-40	24" NYLOPLAST BASIN W GRATED LID	1004.76											H	1002.84	6			1002.84	8	66.6	0.50%	
LS-42	LS-41	24" NYLOPLAST BASIN W GRATED LID	1003.68								1002.55	8	40.3							1002.55	8		0.49%
LS-44	LS-39	24" NYLOPLAST BASIN W GRATED LID	1003.48																				
LS-45	LS-44	24" NYLOPLAST BASIN W GRATED LID	1004.92								1002.88	8	27.1							1002.88	8		0.50%
LS-46	LS-45	24" NYLOPLAST BASIN W GRATED LID	1003.92											1002.84	8	41.3			1002.84	8		0.48%	
LS-47	LS-46	24" NYLOPLAST BASIN W GRATED LID	1004.61								1002.91	8	14.5										
LS-48	A4	CONNECTION TO A5	1011.00								1010.04	10											
LS-49	A5 (LS-48)	24" NYLOPLAST BASIN W SOLID LID	1013.96								1012.80	10	92.5							1013.13	10		
LS-49A	LS-49	CONNECT TO RET WALL FOUND DRAIN	1012.86											1012.80	6	38.2							
LS-50	A2	CONNECTION TO A3	1016.37																	1010.45	12		
LS-51	A3 (LS-50)	24" NYLOPLAST BASIN W SOLID LID	1014.00								1011.80	12	85.7							1011.80	10		
LS-54	G7	CONNECTION TO G8	1016.03								1010.50	6								1010.50	6		
LS-55	G8 (LS-54)	24" NYLOPLAST BASIN W SOLID LID	1016.55	1013.20	6						1010.00	8	49.2							1010.20	10		
LS-55A	G8 (LS-54)	24" NYLOPLAST BASIN W SOLID LID	1016.53	1013.00	6									1014.02	6				1013.00	8	48.5	5.15%	
LS-56	LINE A	INSERT-A-TEE W/ 8" FIELD DRAIN	1014.52																				
LS-57	LINE A	INSERT-A-TEE W/ 8" FIELD DRAIN	1014.51																				
LS-58	F2	CONNECTION TO F3	1003.68											998.88	12								
LS-59	F3 (LS-58)	24" NYLOPLAST BASIN W GRATED LID	1004.67								999.43	10								999.43	8		
LS-60	LS-59	24" NYLOPLAST BASIN W GRATED LID	1005.00								1000.27	10	51.9										
LS-61	LS-60	24" NYLOPLAST BASIN W GRATED LID	1003.00								999.95	8								999.95	8	51.1	1.02%
LS-62	LS-61	24" NYLOPLAST BASIN W GRATED LID	1003.00								1000.76	6								1000.76	8	81.1	1.00%
LS-63	LS-62	24" NYLOPLAST BASIN W GRATED LID	1003.00											1001.50	6	74				1001.50	6		1.00%
LS-64	LS-63	24" NYLOPLAST BASIN W GRATED LID	1003.00								999.81	8	17.2							999.81	8		1.05%
LS-65	LS-64	24" NYLOPLAST BASIN W GRATED LID	1003.00								1000.14	8	86							1000.14	8		0.80%
LS-66	LS-65	24" NYLOPLAST BASIN W GRATED LID	1003.00								1000.82	8	82.8							1000.82	6		0.82%
LS-67	LS-66	24" NYLOPLAST BASIN W GRATED LID	1003.00								1001.50	6	85.2										
LS-68	LS-72	18" NYLOPLAST BASIN W GRATED LID	1006.90								1006.03	8	16.2										
LS-69	LS-68	18" NYLOPLAST BASIN W GRATED LID	1006.80																1009.23	8	25.4	0.39%	
LS-70	LS-73	18" NYLOPLAST BASIN W GRATED LID	1006.80																1009.13	8	25.4	0.39%	
LS-71	LS-72	18" NYLOPLAST BASIN W GRATED LID	1006.80																1009.13	8	25.4	0.39%	
LS-72	LS-73	18" NYLOPLAST BASIN W GRATED LID	1006.80																1009.13	8	25.4	0.39%	
LS-73	LS-35	Bx8/8 TEE	NA								1004.95	8								1004.95	8		
LS-74	LS-49	INSERT-A-TEE W/ 8" FIELD DRAIN	1014.60								1004.88	8	9.5										
LS-75	LINE A	INSERT-A-TEE W/ 8" FIELD DRAIN	1014.60																	1004.88	8		6.84%
RD-1	LS-5	ROOF DRAIN CONNECTION	1013.00	6	5																	14.80%	
RD-2	LS-6	ROOF DRAIN CONNECTION	1013.00	6	5																	27.00%	
RD-3	LS-11	ROOF DRAIN CONNECTION												1013.40	6	3						51.67%	
RD-4	LS-12	ROOF DRAIN CONNECTION												1013.40	6	3							
RD-5	LS-23	ROOF DRAIN CONNECTION																	1009.39	8	17.7	1.00%	
RD-6	LS-25																						


FIRE PROTECTION FP1 (9+75 - 21+00)



FIRE PROTECTION FP1 (20+00 - 24+50)




FIRE PROTECTION FP1 (23+50 - 36+00)




STRUCTURES	
ID	DESCRIPTION
FP1A	CONNECT TO PUBLIC MAIN BEGIN CONSTRUCTION FP1 10+00.0, 0.00' FIRE PROTECTION FP1 INV OUT = 999.06 (6" PVC) N: 991457.497; E: 2831717.706
	22.5' VERTICAL BEND WITH THRUST BLOCKS 33+90.93, 0.24' RT FIRE PROTECTION FP1 INV IN = 1009.30 (6" PVC) INV OUT = 1009.30 (6" PVC) N: 993447.120; E: 2832540.009
	INSTALL 6"x6"x4" TEE FOR DOMESTIC SERVICE 10+11.69, 0.00' FIRE PROTECTION FP1 INV IN = 999.15 (6" PVC) INV OUT = 999.15 (6" PVC) N: 991465.015; E: 2831726.659
FP1BB	22.5' VERTICAL BEND WITH THRUST BLOCKS 34+00.93, 0.27' RT FIRE PROTECTION FP1 INV IN = 1004.30 (6" PVC) INV OUT = 1004.30 (6" PVC) N: 993457.107; E: 2832540.530
	INSTALL GATE VALVE PER CITY STANDARDS BEGIN CONSTRUCTION FP1 10+25.84, 0.00' FIRE PROTECTION FP1 INV IN = 999.27 (6" PVC) INV OUT = 999.27 (6" PVC) N: 991474.115; E: 2831737.497
	FIRE HYDRANT 14+14.59, -1046.34' LT FIRE PROTECTION FP1 INV IN = 999.82 (6" PVC) INV OUT = 999.82 (6" PVC) N: 992011.512; E: 2831926.683
FP1D	INSTALL BACK FLOW PREVENTER AND VAULT PER CITY STANDARDS 10+31.77, 0.00' FIRE PROTECTION FP1 INV IN = 999.32 (6" PVC) INV OUT = 999.32 (6" PVC) N: 991477.926; E: 2831742.036
	45' VERTICAL BEND WITH THRUST BLOCKS 34+23.88, 0.14' RT FIRE PROTECTION FP1 INV IN = 1009.35 (6" PVC) INV OUT = 1009.35 (6" PVC) N: 993480.039; E: 2832541.526
	INSTALL BACK FLOW PREVENTER AND VAULT PER CITY STANDARDS END CONSTRUCTION FP1 34+40.30, 0.00' FIRE PROTECTION FP1 INV IN = 1009.51 (6" PVC) INV OUT = 1009.51 (6" PVC) N: 993496.448; E: 2832542.196
FP1F	22.5' BEND WITH THRUST BLOCKS 10+46.57, 0.00' FIRE PROTECTION FP1 INV IN = 999.44 (6" PVC) INV OUT = 999.44 (6" PVC) N: 991487.446; E: 2831753.373
	INSTALL GATE VALVE PER CITY STANDARDS 34+44.73, 0.00' FIRE PROTECTION FP1 INV IN = 1009.56 (6" PVC) INV OUT = 1009.56 (6" PVC) N: 993500.867; E: 2832542.377
	INSTALL FIRE HYDRANT AND GATE VALVE PER CITY STANDARDS 2+34.48, 0.00' FIRE PROTECTION FP1 INV IN = 999.91 (6" PVC) INV OUT = 999.91 (6" PVC) N: 991665.699; E: 2831812.816
FP1G	INSTALL GATE VALVE PER CITY STANDARDS 35+12.45, 0.00' LT FIRE PROTECTION FP1 INV IN = 1010.23 (6" PVC) INV OUT = 987.65 (6" PVC) N: 993568.535; E: 2832545.138
	INSTALL 6"x6"x6" TEE 15+98.57, 0.00' FIRE PROTECTION FP1 INV IN = 999.84 (6" PVC) INV OUT = 998.84 (6" PVC) N: 992009.297; E: 2831933.263
	CONSTRUCT PUBLIC TIE AT THE EXISTING 16" PUBLIC MAIN 35+17.12, 0.00' FIRE PROTECTION FP1 INV IN = 987.65 (6" PVC) N: 993573.202; E: 2832545.331
FP1I	45' BEND WITH THRUST BLOCKS W/ 11.25 VERTICAL BEND WITH THRUST BLOCKS 16+21.37, 0.00' FIRE PROTECTION FP1 INV IN = 1002.00 (6" PVC) INV OUT = 1002.00 (6" PVC) N: 992016.570; E: 2831911.856
	45' BEND WITH THRUST BLOCKS W/ 11.25 VERTICAL BEND WITH THRUST BLOCKS 16+64.92, 0.00' FIRE PROTECTION FP1 INV IN = 1004.40 (6" PVC) INV OUT = 1004.40 (6" PVC) N: 992055.735; E: 2831892.626
	11.25' BEND WITH THRUST BLOCK 19+53.76, 0.12' RT FIRE PROTECTION FP1 INV IN = 1005.77 (6" PVC) INV OUT = 1005.77 (6" PVC) N: 992329.554; E: 2831984.538
FP1L	FIRE HYDRANT 22+26.37, 0.00' FIRE PROTECTION FP1 INV IN = 1004.83 (6" PVC) INV OUT = 1004.83 (6" PVC) N: 992601.862; E: 2831996.927
	45' BEND WITH THRUST BLOCKS 22+53.51, 0.00' FIRE PROTECTION FP1 INV IN = 1004.73 (6" PVC) INV OUT = 1004.73 (6" PVC) N: 992628.993; E: 2831998.160

STRUCTURES	
ID	DESCRIPTION
FPIO	45' BEND WITH THRUST BLOCKS 22+73.51, 0.00' FIRE PROTECTION FP1 INV IN = 1004.66 (6" PVC) INV OUT = 1004.66 (6" PVC) N: 992642.478; E: 2832012.930
FPIP	11.25' VERTICAL BEND WITH THRUST BLOCKS 24+57.86, 0.00' FIRE PROTECTION FP1 INV IN = 1002.71 (6" PVC) INV OUT = 1002.71 (6" PVC) N: 992634.100; E: 2832197.090
FPIR	INSTALL 6"x6"x6" TEE END CONSTRUCTION FP3 24+81.06, 0.00' FIRE PROTECTION FP1 INV IN = 998.70 (6" PVC) INV IN = 999.78 (6" PVC) INV OUT = 998.70 (6" PVC) N: 992638.949; E: 2832218.127
FPIIS	FIRE HYDRANT 25+21.85, 0.00' FIRE PROTECTION FP1 INV IN = 998.39 (6" PVC) INV OUT = 998.39 (6" PVC) N: 992666.462; E: 2832248.234
FPIIT	11.25' BEND WITH THRUST BLOCK 26+00.10, 0.01' RT FIRE PROTECTION FP1 INV IN = 997.65 (6" PVC) INV OUT = 997.65 (6" PVC) N: 992719.249; E: 2832305.999
FPIU	22.5' BEND WITH THRUST BLOCK 26+71.61, 0.00' FIRE PROTECTION FP1 INV IN = 997.30 (6" PVC) INV IN = 997.30 (6" PVC) N: 992756.273; E: 2832367.181
FPIV	22.5' BEND WITH THRUST BLOCKS 27+43.11, 0.00' FIRE PROTECTION FP1 INV IN = 996.94 (6" PVC) INV OUT = 996.94 (6" PVC) N: 992813.870; E: 2832409.543
FPIW	INSTALL FIRE HYDRANT AND GATE VALVE PER CITY STANDARDS 29+56.36, 0.00' FIRE PROTECTION FP1 INV IN = 1000.34 (6" PVC) INV OUT = 1000.34 (6" PVC) N: 992924.270; E: 2832434.809
FPIY	FIRE HYDRANT 31+55.29, 0.00' FIRE PROTECTION FP1 INV IN = 1005.81 (6" PVC) INV OUT = 1005.81 (6" PVC) N: 993216.880; E: 2832495.862
FPIZ	22.5' BEND WITH THRUST BLOCKS 33+10.37, 0.00' FIRE PROTECTION FP1 INV IN = 1008.14 (6" PVC) INV OUT = 1008.14 (6" PVC) N: 993366.671; E: 2832535.815
FPIJ	INSTALL FIRE HYDRANT AND GATE VALVE PER CITY STANDARDS 19+16.78, 0.00' FIRE PROTECTION FP1 INV IN = 1005.46 (6" PVC) INV OUT = 1005.46 (6" PVC) N: 992294.441; E: 2831972.960
FPQ	45' BEND WITH THRUST BLOCK 24+72.86, 0.00' FIRE PROTECTION FP1 INV IN = 998.74 (6" PVC) INV OUT = 998.74 (6" PVC) N: 992633.418; E: 2832212.075
FPX	INSTALL 6"x6"x6" TEE BEGIN CONSTRUCTION FP2 29+25.11, 0.00' FIRE PROTECTION FP1 INV IN = 1002.40 (6" PVC) INV OUT = 1002.40 (6" PVC) N: 992991.285; E: 2832450.146

## LEGEND

 COMPACTED FILL MUST BE PLACED TO A MINIMUM OF 2'-0" ABOVE THE TOP OF THE PROPOSED FIRE LINE PIPE PRIOR TO INSTALLATION OF THE FIRE LINE PIPE.



**olson**

# LEE'S SUMMIT MIDDLE SCHOOL #4

## LEE'S SUMMIT R-7 SCHOOL DISTRICT

PACKAGE 2-  
STRUCTURAL & SITE  
UTILITIES  
ISSUED FOR PERMIT  
08/28/20

2 PR002R 01.14.21

5 ASI019 05.26.2


13-20102-00

## FIRE PROTECTION PROFILES

# C1028A


DWG: F:\2020\0001-0500\020-0103\40-Design\AutoCAD\Final Plans\Sheets\GNV\CONSTRUCTION DOCUMENTS\C\_UTL02\_0200103.dwg  
DATE: Dec 01, 2021 7:19am  
USER: bklmich  
V\_XALT\_00103  
C\_PBASE\_0200103  
T\_PSAFE\_0200103  
C\_PTLBK\_0200103  
C\_LSD01\_0200103  
C\_PBASE\_0200103  
TMP  
C\_PSAFE\_0200103  
C\_PBASE02\_0200103  
C\_PSAFE\_0200103

FIRE PROTECTION FP2 (9+75 - 18+25)



STRUCTURES	
ID	DESCRIPTION
FP2A	11' BEND WITH THRUST BLOCK 12+21.22, -0.01' LT FIRE PROTECTION FP2 INV IN = 1006.85 (6" PVC) INV OUT = 1006.85 (6" PVC) N: 993040.609; E: 2832234.502
FP2B	FIRE HYDRANT 12+69.84, -0.01' LT FIRE PROTECTION FP2 INV IN = 1008.79 (6" PVC) INV OUT = 1008.79 (6" PVC) N: 993043.355; E: 2832185.957
FP2C	45' ANGLE WITH THRUST BLOCK 14+14.59, 0.00' FIRE PROTECTION FP2 INV IN = 1006.35 (6" PVC) INV OUT = 1006.35 (6" PVC) N: 993051.538; E: 2832041.439
FP2D	FIRE HYDRANT 15+64.28, 0.00' FIRE PROTECTION FP2 INV IN = 1007.09 (6" PVC) INV OUT = 1007.09 (6" PVC) N: 993162.077; E: 2831940.502
FP2E	45' BEND WITH THRUST BLOCK 15+67.44, 0.00' FIRE PROTECTION FP2 INV IN = 1007.09 (6" PVC) INV OUT = 1007.09 (6" PVC) N: 993164.409; E: 2831938.373
FP2F	45' BEND WITH THRUST BLOCK 17+45.89, 0.00' FIRE PROTECTION FP2 INV IN = 1011.38 (6" PVC) INV OUT = 1011.38 (6" PVC) N: 993172.504; E: 2831760.106
FP2G	FIRE HYDRANT 17+87.85, 0.00' FIRE PROTECTION FP2 INV IN = 1012.29 (6" PVC) INV OUT = 1012.29 (6" PVC) N: 993200.200; E: 2831728.575
FPX	INSTALL 6"x6"x6" TEE BEGIN CONSTRUCTION FP2 29+25.11, 0.00' FIRE PROTECTION FP1 INV IN = 1002.40 (6" PVC) INV OUT = 1002.40 (6" PVC) N: 992991.285; E: 2832450.146

FIRE PROTECTION FP3 (9+75 - 20+25)




STRUCTURES	
ID	DESCRIPTION
FP1H	INSTALL 6"x6"x6" TEE 15+98.57, 0.00' FIRE PROTECTION FP1 INV IN = 998.84 (6" PVC) INV OUT = 998.84 (6" PVC) N: 992009.297; E: 2831933.263
FP1R	INSTALL 6"x6"x6" TEE END CONSTRUCTION FP3 24+81.06, 0.00' FIRE PROTECTION FP1 INV IN = 998.70 (6" PVC) INV OUT = 998.70 (6" PVC) N: 992638.949; E: 2832218.127
FP3A	45' BEND WITH THRUST BLOCK 11+31.89, 0.00' FIRE PROTECTION FP3 INV IN = 991906.783; E: 2832063.678
FP3B	FIRE HYDRANT 10+17.53, -1091.40' LT FIRE PROTECTION FP2 INV IN = 1000.44 (6" PVC) INV OUT = 1000.44 (6" PVC) N: 991931.305; E: 2832189.577
FP3C	11.25' BEND WITH THRUST BLOCK 10+07.60, -1000.75' LT FIRE PROTECTION FP2 INV IN = 1000.47 (6" PVC) INV OUT = 1000.47 (6" PVC) N: 992017.449; E: 2832219.473
FP3D	11.25' BEND WITH THRUST BLOCKS 15+68.98, 0.00' FIRE PROTECTION FP3 INV IN = 1002.13 (6" PVC) INV OUT = 1002.13 (6" PVC) N: 992216.809; E: 2832287.154
FP3F	11.25' BEND WITH THRUST BLOCK 17+76.84, 0.00' FIRE PROTECTION FP3 INV IN = 1000.83 (6" PVC) INV OUT = 1000.83 (6" PVC) N: 992424.458; E: 2832296.600
FP3G	11.25' BEND WITH THRUST BLOCK 18+98.44, 0.00' FIRE PROTECTION FP3 INV IN = 1002.24 (6" PVC) INV OUT = 1002.24 (6" PVC) N: 992543.631; E: 2832272.409
FP3H	45' VERTICAL BEND WITH THRUST BLOCK 19+53.28, 0.00' FIRE PROTECTION FP3 INV IN = 1002.84 (6" PVC) INV OUT = 1002.84 (6" PVC) N: 992593.943; E: 2832250.606
FP3I	45' VERTICAL BEND WITH THRUST BLOCK 19+58.28, 0.00' FIRE PROTECTION FP3 INV IN = 997.84 (6" PVC) INV OUT = 997.84 (6" PVC) N: 992598.531; E: 2832248.618

STRUCTURES	
ID	DESCRIPTION
FP3J	22.5' BEND WITH THRUST BLOCK 19+72.89, 0.00' FIRE PROTECTION FP3 INV IN = 998.39 (6" PVC) INV OUT = 998.39 (6" PVC) N: 992611.942; E: 2832242.807
FP3L	11.25' BEND WITH THRUST BLOCK 14+96.52, 0.00' FIRE PROTECTION FP3 INV IN = 1001.68 (6" PVC) INV OUT = 1001.68 (6" PVC) N: 992148.048; E: 2832264.304

STRUCTURES	
ID	DESCRIPTION
FP3A.1	45' BEND WITH THRUST BLOCK 12+54.06, 0.00' FIRE PROTECTION FP3 INV IN = 1000.37 (6" PVC) INV OUT = 1000.37 (6" PVC) N: 991918.837; E: 2832185.249

LEGEND

COMPACTED FILL MUST BE PLACED TO A MINIMUM OF 2'-0" ABOVE THE TOP OF THE PROPOSED FIRE LINE PIPE PRIOR TO INSTALLATION OF THE FIRE LINE PIPE.



LEE'S SUMMIT MIDDLE SCHOOL #4

LEE'S SUMMIT R-7 SCHOOL DISTRICT

100' SE BAILEY ROAD  
LEE'S SUMMIT, MO 64881

PACKAGE 2-  
STRUCTURAL & SITE  
UTILITIES  
ISSUED FOR PERMIT  
08/28/20

PR002R 01.14.21  
AS101R 05.26.21  
AS101R 10.26.21

FIRE PROTECTION  
PROFILES

C1028B

olsson


OLSSON, CIVIL ENGINEERING  
MO. CERTIFICATE OF AUTHORITY #001592  
7301 West 133rd Street, Suite 200  
Overland Park, KS 66214-7500  
TEL: 913.381.1170  
www.olson.com



DLR Group


© DLR Group  
80320, DLR Group, Inc., a Missouri corporation,  
Missouri State Certificate of Authority #00099

## SS1 THRU SS15 (9+75 - 25+00)



STRUCTURES	
ID	DESCRIPTION
SS1	48" MH 10+00, -0.26' LT SSI THRU SS15 INV IN = 981.57 (8" PVC) N: 99131.630; E: 283196.013
SS2	48" MH 10+85.68, 0.00" SSI THRU SS15 INV IN = 987.38 (6" PVC) INV OUT = 987.08 (8" PVC) N: 991370.234; E: 2831902.456
SS3	INSTALL STD. 4" DIA. MH 11+14.00, 0.00" SSI THRU SS15 INV IN = 989.30 (6" PVC) INV OUT = 988.93 (6" PVC) N: 991422.683; E: 2831755.635
SS4	INSTALL STD. 4" DIA. MH 14+13.04, 0.00" SSI THRU SS15 INV IN = 991.25 (6" PVC) INV OUT = 991.15 (6" PVC) N: 991593.052; E: 2831776.674
SS5	INSTALL STD. 4" DIA. MH 17+13.04, 0.00" SSI THRU SS15 INV IN = 994.55 (6" PVC) INV OUT = 994.25 (6" PVC) N: 991876.387; E: 2831875.328
SS6	INSTALL STD. 4" DIA. MH 18+69.33, 0.00" SSI THRU SS15 INV IN = 996.41 (6" PVC) INV OUT = 996.11 (6" PVC) N: 992023.960; E: 2831926.721
SS7	INSTALL STD. 4" DIA. MH 19+23.05, 0.00" SSI THRU SS15 INV IN = 997.25 (6" PVC) INV OUT = 996.95 (6" PVC) N: 992046.139; E: 2831877.791
SS8	INSTALL 6"x6"x4" WYE 21+92.29, 0.00" SSI THRU SS15 INV IN = 999.95 (6" PVC) INV OUT = 999.95 (6" PVC) N: 992301.371; E: 2831963.668
SS9	INSTALL STD. 4" DIA. MH 22+23.05, 0.00" SSI THRU SS15 INV IN = 1000.55 (6" PVC) INV OUT = 1000.26 (6" PVC) N: 992330.470; E: 2831973.479
SS10	INSTALL 6"x6"x4" WYE 23+00.56, 0.00" SSI THRU SS15 INV IN = 1001.63 (6" PVC) INV OUT = 1001.63 (6" PVC) N: 992407.809; E: 2831973.572
SS11	INSTALL 6"x6"x4" WYE 24+17.89, 0.00" SSI THRU SS15 INV IN = 1002.80 (6" PVC) INV OUT = 1002.80 (6" PVC) N: 992524.888; E: 2831986.282

## SS1 THRU SS15 (24+00 - 32+25)




STRUCTURES	
ID	DESCRIPTION
SS11	INSTALL 6"x6"x4" WYE 24±17.89, 0.00' SSI THRU SS15 INV IN = 1002.80 (6" PVC) INV OUT = 1002.80 (6" PVC) N: 995254.886; E: 2831986.282
SS12	INSTALL STD. 4" DIA. MH 28±23.03, 0.00' SSI THRU SS15 INV IN = 1007.15 (6" PVC) INV OUT = 1006.85 (6" PVC) N: 992929.567; E: 2832005.539
SS13	INSTALL ONE-WAY CLEANOUT 30±20.37, 0.00' SSI THRU SS15 INV IN = 1010.23 (6" PVC) INV OUT = 1009.93 (6" PVC) N: 993126.744; E: 2832013.612
SS14	INSTALL ONE-WAY CLEANOUT 31±14.14, 0.00' SSI THRU SS15 INV IN = 1011.16 (6" PVC) INV OUT = 1011.17 (6" PVC) N: 993194.231; E: 2831939.531
SS15	CONNECT SERVICE LINE TO BLDG. WITH CLEANOUT APPROX 10' FROM BLDG FIELD VERIFY ELEVATION REL MPP 31±65.41, 0.00' SSI THRU SS15 INV OUT = 1011.67 (6" PVC) N: 993186.328; E: 2831888.304


NOTES:

1. CONTRACTOR TO SUBMIT SHOP DRAWINGS TO ENGINEER FOR APPROVAL PRIOR TO FABRICATION OF STRUCTURES AND ORDERING OF PIPE PRODUCTS.

## LEGEND

 COMPACTED FILL MUST BE PLACED TO A MINIMUM OF 2'-0" ABOVE THE TOP OF THE PROPOSED SEWER PIPE PRIOR TO INSTALLATION OF THE SEWER PIPE.







STRUCTURES	
ID	DESCRIPTION
A4	INSTALL 4'X4' JUNCTION BOX 12+73.17, 0.00' LINE A (3) RIM= 1015.00 INV IN = 1010.54 (18" HDPE) INV OUT = 1010.04 (24" HDPE) N: 993487.779; E: 2832288.317
A5	INSTALL 4'X4' JUNCTION BOX 15+01.93, 0.00' LINE A (3) RIM= 1015.00 INV IN = 1011.98 (15" HDPE) INV OUT = 1011.68 (18" HDPE) N: 993480.510; E: 2832059.675
A6	INSTALL 2' DIA. NYLOPLAST BASIN WITH PEDESTRIAN GRATE LID 17+12.53, 0.00' LINE A (3) RIM= 1015.85 INV OUT = 1013.03 (15" HDPE) N: 993275.744; E: 2832010.413


- NOTES:**
- CONTRACTOR TO SUBMIT SHOP DRAWINGS TO ENGINEER FOR APPROVAL PRIOR TO FABRICATION OF STRUCTURES AND ORDERING OF PIPE PRODUCTS.
  - CONTRACTOR TO INSTALL CONCRETE COLLAR AROUND ALL ADS DRAIN BASINS (SEE DETAILS IN THESE PLANS.)

**LEGEND**

--- PROPERTY LINE  
--- 830 --- EXISTING CONTOUR  
--- 830 --- PROPOSED CONTOUR  
--- PROPOSED STORM SEWER  
[Hatched Box] COMPACTED FILL MUST BE PLACED TO A MINIMUM OF 2'-0" ABOVE THE TOP OF THE PROPOSED SEWER PIPE PRIOR TO INSTALLATION OF THE SEWER PIPE.

LINE A (3) (12+50 - 17+50)






STRUCTURES	
ID	DESCRIPTION
B1	INSTALL 24" END SECTION WITH CONCRETE TOEWALL 10+00, 0.00' LINE B RIM= 1005.11 INV IN = 1002.53 (24" HDPE) N: 993084.159; E: 2832531.362
B2	INSTALL STD. 4' DIA. MH 27+01.48, 896.81' RT LINE B RIM= 1007.00 INV IN = 1003.00 (24" HDPE) INV OUT = 1002.70 (24" HDPE) N: 993105.057; E: 2832507.447
B3	INSTALL CONTROL STRUCTURE PER C1057 12+37.67, 0.00' LINE B RIM= 1012.20 INV IN = 1004.40 (24" HDPE) INV OUT = 1004.05 (24" HDPE) N: 993297.366; E: 2832581.043
B4	INSTALL 24" END SECTION WITH CONCRETE TOEWALL 12+46.36, 0.00' LINE B RIM= 1007.02 INV OUT = 1004.44 (24" HDPE) N: 993305.603; E: 2832578.267

NOTES:



- CONTRACTOR TO SUBMIT SHOP DRAWINGS TO ENGINEER FOR APPROVAL PRIOR TO FABRICATION OF STRUCTURES AND ORDERING OF PIPE PRODUCTS.
- CONTRACTOR TO INSTALL CONCRETE COLLAR AROUND ALL ADS DRAIN BASINS (SEE DETAILS IN THESE PLANS.)


LEGEND




HEC-14 RIPRAP APRON SIZING FOR OUTFALL B-1									
	D50 (in)	Q ft <sup>3</sup> /s	D ft	TW ft	TW/D 0.4 Min 1.0 Max	APRON LENGTH Scale from Table 10.1	APRON DEPTH Scale x D (ft)	Scale from Table 10.1	Width at End of Apron (ft)
Required	2.2	9.9	2	0.91	0.455	4	8	3.3	19.8
Design	6						24	24	12

LINE B (9+50 - 12+75)





LINE C (9+75 - 13+25)




STRUCTURES	
ID	DESCRIPTION
C1	INSTALL 24" DIA. END SECTION WITH TOEWALL 10+00, 0.00' RT LINE C RIM= 1002.08 INV IN = 999.50 (24" HDPE) N: 992695.797; E: 2832336.866
C2	INSTALL 7'X4' NON-SETBACK CURB INLET 10+58.53, 0.00' LINE C RIM= 1005.57 INV IN = 1000.09 (24" HDPE) INV OUT = 999.79 (24" HDPE) N: 992754.318; E: 2832336.087
C3	INSTALL 6'X4' NON-SETBACK CURB INLET 11+45.03, 0.00' LINE C RIM= 1004.60 INV IN = 1000.82 (24" HDPE) INV OUT = 1000.52 (24" HDPE) N: 992825.971; E: 2832384.550
C4	INSTALL 6'X4' NON-SETBACK CURB INLET 12+73.74, 0.00' LINE C RIM= 1006.82 INV IN = 1002.86 (15" HDPE) INV OUT = 1002.11 (24" HDPE) N: 992947.233; E: 2832427.690


NOTES:

- CONTRACTOR TO SUBMIT SHOP DRAWINGS TO ENGINEER FOR APPROVAL PRIOR TO FABRICATION OF STRUCTURES AND ORDERING OF PIPE PRODUCTS.
- CONTRACTOR TO INSTALL CONCRETE COLLAR AROUND ALL ADS DRAIN BASINS (SEE DETAILS IN THESE PLANS.)

LEGEND

- PROPERTY LINE
- EXISTING CONTOUR
- PROPOSED CONTOUR
- PROPOSED STORM SEWER
- COMPACTED FILL MUST BE PLACED TO A MINIMUM OF 2'-0" ABOVE THE TOP OF THE PROPOSED SEWER PIPE PRIOR TO INSTALLATION OF THE SEWER PIPE.





STRUCTURES	
ID	DESCRIPTION
C4	INSTALL 6'X4' NON-SETBACK CURB INLET 12+73.74, 0.00' LINE C RIM= 1006.82 INV IN = 1002.86 (15" HDPE) INV IN = 1002.86 (15" HDPE) INV OUT = 1002.11 (24" HDPE) N: 992947.233; E: 2832427.690
C5	INSTALL 4'X4' JUNCTION BOX 13+34.19, 0.00' LINE C RIM= 1010.98 INV IN = 1004.52 (15" HDPE) INV OUT = 1004.22 (15" HDPE) N: 992993.091; E: 2832388.295
C6	INSTALL 2' DIA. NYLOPLAST BASIN WITH PEDESTRIAN GRATE LID 10+31.76, -301.30' LT LINE B RIM= 1015.44 INV IN = 1010.49 (15" HDPE) INV OUT = 1010.19 (15" HDPE) N: 993056.407; E: 2832210.098
C7	INSTALL 2' DIA. NYLOPLAST BASIN WITH PEDESTRIAN GRATE LID 16+42.22, 0.00' LINE C RIM= 1016.12 INV OUT = 1011.68 (15" HDPE) N: 993061.744; E: 2832091.305



NOTES:


- CONTRACTOR TO SUBMIT SHOP DRAWINGS TO ENGINEER FOR APPROVAL PRIOR TO FABRICATION OF STRUCTURES AND ORDERING OF PIPE PRODUCTS.
- CONTRACTOR TO INSTALL CONCRETE COLLAR AROUND ALL ADS DRAIN BASINS (SEE DETAILS IN THESE PLANS.)

LEGEND


- PROPERTY LINE
- EXISTING CONTOUR
- PROPOSED CONTOUR
- PROPOSED STORM SEWER
- COMPACTED FILL MUST BE PLACED TO A MINIMUM OF 2'-0" ABOVE THE TOP OF THE PROPOSED SEWER PIPE PRIOR TO INSTALLATION OF THE SEWER PIPE.

LINE C (12+50 - 16+75)





LINE CC (0+00 - 4+00)




STRUCTURES	
ID	DESCRIPTION
C4	INSTALL 6'X4' NON-SETBACK CURB INLET 12+73.74, 0.00' LINE C RIM= 1006.82 INV IN = 1002.86 (15" HDPE) INV OUT = 1002.86 (15" HDPE) N: 992947.233; E: 2832427.690
CC1	INSTALL 6'X4' NON-SETBACK CURB INLET 2+04.24, 0.00' LINE CC RIM= 1009.74 INV IN = 1005.85 (15" HDPE) INV OUT = 1005.55 (15" HDPE) N: 993121.028; E: 2832471.516
CC2	INSTALL 6'X4' NON-SETBACK CURB INLET 3+81.19, 0.00' LINE CC RIM= 1012.89 INV OUT = 1007.62 (15" HDPE) N: 993294.379; E: 2832507.027

NOTES:


- CONTRACTOR TO SUBMIT SHOP DRAWINGS TO ENGINEER FOR APPROVAL PRIOR TO FABRICATION OF STRUCTURES AND ORDERING OF PIPE PRODUCTS.
- CONTRACTOR TO INSTALL CONCRETE COLLAR AROUND ALL ADS DRAIN BASINS (SEE DETAILS IN THESE PLANS.)

LEGEND

- PROPERTY LINE
- EXISTING CONTOUR
- PROPOSED CONTOUR
- PROPOSED STORM SEWER
- COMPACTED FILL MUST BE PLACED TO A MINIMUM OF 2'-0" ABOVE THE TOP OF THE PROPOSED SEWER PIPE PRIOR TO INSTALLATION OF THE SEWER PIPE.



LINE D (9+50 - 11+50)




STRUCTURES	
ID	DESCRIPTION
D1	INSTALL 24" DIA. END SECTION WITH CONCRETE TOEWALL 10+00, 0.00' LINE D RIM= 997.28 INV IN = 994.71 (24" HDPE) N: 992436.343; E: 2832443.658
D2	INSTALL CONTROL STRUCTURE PER C1057 10+85, 0.00' LINE D RIM= 1003.30 INV IN = 995.63 (24" HDPE) INV OUT = 995.13 (24" HDPE) N: 992472.969; E: 2832366.953
D3	INSTALL 24" DIA. END SECTION WITH CONCRETE TOEWALL 10+93.69, 0.00' LINE D RIM= 997.83 INV OUT = 995.67 (24" HDPE) N: 992481.205; E: 2832364.177


NOTES:

1. CONTRACTOR TO SUBMIT SHOP DRAWINGS TO ENGINEER FOR APPROVAL PRIOR TO FABRICATION OF STRUCTURES AND ORDERING OF PIPE PRODUCTS.
2. CONTRACTOR TO INSTALL CONCRETE COLLAR AROUND ALL ADS DRAIN BASINS (SEE DETAILS IN THESE PLANS.)

LEGEND

- PROPERTY LINE
- EXISTING CONTOUR
- PROPOSED CONTOUR
- PROPOSED STORM SEWER
- COMPACTED FILL MUST BE PLACED TO A MINIMUM OF 2'-0" ABOVE THE TOP OF THE PROPOSED SEWER PIPE PRIOR TO INSTALLATION OF THE SEWER PIPE.






STRUCTURES	
ID	DESCRIPTION
E2	INSTALL 6"x6" CURB INLET 12+22.39, 0.00' LINE E RIM= 1003.86 INV IN = 998.54 (36" HDPE) INV OUT = 998.04 (36" HP) N: 991696.727; E: 2831544.472
E3	INSTALL 6"x6" CURB INLET 13+40.26, 0.00' LINE E RIM= 1006.25 INV IN = 999.43 (36" HDPE) INV OUT = 999.13 (36" HDPE) N: 991814.500; E: 2831549.282
E4	INSTALL 6"x6" CURB INLET 15+32.94, 0.00' LINE E RIM= 1010.16 INV IN = 1001.53 (30" HDPE) INV OUT = 1000.39 (36" HDPE) N: 992007.018; E: 2831557.144


- NOTES:**
- CONTRACTOR TO SUBMIT SHOP DRAWINGS TO ENGINEER FOR APPROVAL PRIOR TO FABRICATION OF STRUCTURES AND ORDERING OF PIPE PRODUCTS.
  - CONTRACTOR TO INSTALL CONCRETE COLLAR AROUND ALL ADS DRAIN BASINS (SEE DETAILS IN THESE PLANS.)

**LEGEND**

--- PROPERTY LINE  
--- 830 --- EXISTING CONTOUR  
--- 830 --- PROPOSED CONTOUR  
--- PROPOSED STORM SEWER  
[Hatched Box] COMPACTED FILL MUST BE PLACED TO A MINIMUM OF 2'-0" ABOVE THE TOP OF THE PROPOSED SEWER PIPE PRIOR TO INSTALLATION OF THE SEWER PIPE.

LINE E (9+75 - 16+00)





STRUCTURES	
ID	DESCRIPTION
E4	INSTALL 6'X6' CURB INLET 15+32.94, 0.00' LINE E RM= 1010.16 INV IN = 1001.53 (30" HDPE) INV OUT = 1000.39 (36" HDPE) N: 992007.018; E: 2831557.144
E5	INSTALL 6'X6' CURB INLET 18+24.27, 0.00' LINE E RM= 1015.54 INV IN = 1004.71 (30" HDPE) INV OUT = 1000.44 (30" HDPE) N: 992298.126; E: 2831568.526
E6	INSTALL 6'X6' CURB INLET 20+48.52, 0.00' LINE E RM= 1015.67 INV IN = 1006.58 (24" HDPE) INV OUT = 1006.28 (30" HDPE) N: 992522.182; E: 2831577.678



NOTES:

- CONTRACTOR TO SUBMIT SHOP DRAWINGS TO ENGINEER FOR APPROVAL PRIOR TO FABRICATION OF STRUCTURES AND ORDERING OF PIPE PRODUCTS.
- CONTRACTOR TO INSTALL CONCRETE COLLAR AROUND ALL ADS DRAIN BASINS (SEE DETAILS IN THESE PLANS.)

LEGEND

- PROPERTY LINE  
--- EXISTING CONTOUR  
--- PROPOSED CONTOUR  
--- PROPOSED STORM SEWER  
COMPACTED FILL MUST BE PLACED TO A MINIMUM OF 2'-0" ABOVE THE TOP OF THE PROPOSED SEWER PIPE PRIOR TO INSTALLATION OF THE SEWER PIPE.

LINE E (15+25 - 21+00)



LEE'S SUMMIT MIDDLE SCHOOL #4

LEE'S SUMMIT R-7 SCHOOL DISTRICT

1001 SE BAILEY ROAD  
LEE'S SUMMIT, MO 64081

PACKAGE 2-  
STRUCTURAL & SITE  
UTILITIES  
ISSUED FOR PERMIT  
08/28/20


PRO02R 01.14.21  
ASI-009 03.08.21

13-20102-00

STORM SEWER  
PLAN & PROFILE -  
LINE E

C1036

DWG: F:\2020\0001-0500\020-0103\40-Design\AutoCAD\Final Plans\Sheets\GNV\CONSTRUCTION DOCUMENTS\C\_STM01\_0200103.dwg  
DATE: Dec 01, 2021 7:27am  
USER: bkimmich  
T\_PBASE\_0200103  
C\_PSTRM\_0200103  
C\_PTLK\_0200103  
C\_PFSURF\_0200103  
C\_PBASE\_0200103  
XREFS: C\_XBASE\_0200103




STRUCTURES	
ID	DESCRIPTION
E6	INSTALL 6'X5' CURB INLET 20+48.52, 0.00' LINE E RIM= 1015.67 INV IN = 1006.58 (24" HDPE) INV OUT = 1006.28 (30" HDPE) N: 992522.182; E: 2831577.678
E7	INSTALL 6'X4' CURB INLET 24+39.50, 0.00' LINE E RIM= 1020.05 INV IN = 1009.62 (24" HDPE) INV IN = 1009.82 (10" HDPE) INV OUT = 1009.32 (24" HDPE) N: 992912.857; E: 2831593.136
E8	INSTALL STD. 4' DIA. MH 26+88.20, -1.01' LT LINE E RIM= 1019.97 INV IN = 1012.69 (24" HDPE) INV OUT = 1012.36 (24" HDPE) N: 993160.903; E: 2831611.266


- NOTES:
- CONTRACTOR TO SUBMIT SHOP DRAWINGS TO ENGINEER FOR APPROVAL PRIOR TO FABRICATION OF STRUCTURES AND ORDERING OF PIPE PRODUCTS.
  - CONTRACTOR TO INSTALL CONCRETE COLLAR AROUND ALL ADS DRAIN BASINS (SEE DETAILS IN THESE PLANS.)

LEGEND

- PROPERTY LINE
- EXISTING CONTOUR
- PROPOSED CONTOUR
- PROPOSED STORM SEWER
- COMPACTED FILL MUST BE PLACED TO A MINIMUM OF 2'-0" ABOVE THE TOP OF THE PROPOSED SEWER PIPE PRIOR TO INSTALLATION OF THE SEWER PIPE.

LINE E (20+25 - 27+50)





STRUCTURES	
ID	DESCRIPTION
E8	INSTALL STD. 4' DIA. MH 26+88.20, -1.01' LT LINE E RIM= 1019.97 INV IN = 1012.69 (24" HDPE) INV OUT = 1012.36 (24" HDPE) N: 993160.903; E: 2831611.266
E9	INSTALL 6'x5' CURB INLET 27+75.17, 0.00' LINE E RIM= 1023.75 INV IN = 1014.28 (15" HDPE) INV OUT = 1014.00 (24" HDPE) N: 993247.540; E: 2831618.964
E10	INSTALL 6'x4' CURB INLET 29+13.28, 0.00' LINE E RIM= 1025.18 INV OUT = 1016.35 (15" HDPE) N: 993356.535; E: 2831703.785

- NOTES:
- CONTRACTOR TO SUBMIT SHOP DRAWINGS TO ENGINEER FOR APPROVAL PRIOR TO FABRICATION OF STRUCTURES AND ORDERING OF PIPE PRODUCTS.
  - CONTRACTOR TO INSTALL CONCRETE COLLAR AROUND ALL ADS DRAIN BASINS (SEE DETAILS IN THESE PLANS.)

LEGEND

PROPERTY LINE



EXISTING CONTOUR


PROPOSED CONTOUR

PROPOSED STORM SEWER

COMPACTED FILL MUST BE PLACED TO A MINIMUM OF 2'-0" ABOVE THE TOP OF THE PROPOSED SEWER PIPE PRIOR TO INSTALLATION OF THE SEWER PIPE.

LINE E (26+75 - 29+50)







STRUCTURES	
ID	DESCRIPTION
F1	INSTALL 48" END SECTION WITH CONCRETE TOEWALL 10+00, 0.00' LINE F RIM= 999.49 INV IN = 994.87 (48" HDPE) N: 991398.070; E: 2831632.042
F2	INSTALL 7"x4" JUNCTION BOX 10+56.07, 211.14' RT LINE F RIM= 1004.88 INV IN = 995.94 (48" HDPE) INV OUT = 995.64 (48" HDPE) N: 991510.093; E: 2831737.899
F3	INSTALL 7"x4" DOUBLE GRATE INLET 14+26.65, 0.00' LINE F RIM= 1003.43 INV IN = 997.60 (48" HDPE) INV IN = 997.80 (12" HDPE) INV OUT = 997.30 (48" HDPE) N: 991768.065; E: 2831825.747


- NOTES:
- CONTRACTOR TO SUBMIT SHOP DRAWINGS TO ENGINEER FOR APPROVAL PRIOR TO FABRICATION OF STRUCTURES AND ORDERING OF PIPE PRODUCTS.
  - CONTRACTOR TO INSTALL CONCRETE COLLAR AROUND ALL ADS DRAIN BASINS (SEE DETAILS IN THESE PLANS.)

LEGEND

--- PROPERTY LINE  
--- 8.30 --- EXISTING CONTOUR  
--- 830 --- PROPOSED CONTOUR  
[Symbol] PROPOSED STORM SEWER  
[Symbol] COMPACTED FILL MUST BE PLACED TO A MINIMUM OF 2'-0" ABOVE THE TOP OF THE PROPOSED SEWER PIPE PRIOR TO INSTALLATION OF THE SEWER PIPE.

LINE F (9+75 - 14+75)







STRUCTURES	
ID	DESCRIPTION
F3	INSTALL 7'X4' DOUBLE GRATE INLET 14+26.65, 0.00' LINE F RIM= 1003.43 INV IN = 997.60 (48" HDPE) INV IN = 997.80 (12" HDPE) INV OUT = 997.30 (48" HDPE) N: 991768.065; E: 2831825.747
F4	INSTALL 9'X7' JUNCTION BOX 15+16.30, 339.76' RT LINE E RIM= 1006.44 INV IN = 1000.70 (48" HDPE) INV IN = 999.00 (42" HDPE) INV OUT = 998.70 (48" HDPE) N: 991976.526; E: 2831895.941
F5	INSTALL 9'X5' NON-SETBACK CURB INLET 16+08.20, 0.00' LINE F RIM= 1008.44 INV IN = 1001.25 (30" HDPE) INV OUT = 1000.95 (48" HDPE) N: 991999.575; E: 2831942.104
F6	INSTALL 6'X5' NON-SETBACK CURB INLET 18+01.51, 0.00' LINE F RIM= 1006.52 INV IN = 1002.06 (24" HDPE) INV IN = 1002.26 (12" HDPE) INV OUT = 1001.76 (30" HDPE) N: 991966.617; E: 2832040.014
F7	INSTALL STD. 4' DIA. MH WITH HEAVY DUTY RING AND COVER 19+46.09, 0.00' LINE F RIM= 1005.99 INV IN = 1003.08 (24" HDPE) INV OUT = 1002.78 (24" HDPE) N: 991937.029; E: 2832181.536
F8	INSTALL STD. 4' DIA. MH WITH HEAVY DUTY RING AND COVER 20+28.80, 0.00' LINE F RIM= 1006.41 INV IN = 1003.99 (12" HDPE) INV OUT = 1003.49 (24" HDPE) N: 992008.656; E: 2832222.880

- NOTES:**
- CONTRACTOR TO SUBMIT SHOP DRAWINGS TO ENGINEER FOR APPROVAL PRIOR TO FABRICATION OF STRUCTURES AND ORDERING OF PIPE PRODUCTS.
  - CONTRACTOR TO INSTALL CONCRETE COLLAR AROUND ALL ADS DRAIN BASINS (SEE DETAILS IN THESE PLANS.)

**LEGEND**


--- PROPERTY LINE  
--- 830 --- EXISTING CONTOUR  
--- 830 --- PROPOSED CONTOUR  
--- PROPOSED STORM SEWER  
[Hatched Box] COMPACTED FILL, MUST BE PLACED TO A MINIMUM OF 2'-0" ABOVE THE TOP OF THE PROPOSED SEWER PIPE PRIOR TO INSTALLATION OF THE SEWER PIPE.

LINE F (14+00 - 20+50.51)



DWG: F:\2020\0001-0500\020-0103\40-Design\AutoCAD\Final Plans\Sheets\GNV\CONSTRUCTION DOCUMENTS\C\_STM01\_0200103.dwg  
DATE: Dec 01, 2021 7:29am  
USER: bkimmich  
T\_PBASE\_0200103  
C\_PJDIR\_0200103  
C\_PTLK\_0200103  
C\_PBASE\_0200103  
XREFS: C\_XBASE\_0200103

STRUCTURES	
ID	DESCRIPTION
F4	INSTALL 9'X7' JUNCTION BOX 15+16.30, 339.76' RT LINE E RIM= 1006.44 INV IN = 1000.70 (48" HDPE) INV IN = 999.00 (42" HDPE) INV OUT = 998.70 (48" HDPE) N: 991976.526; E: 2831895.941
G1	INSTALL 8'X4' JUNCTION BOX 10+37.83, 0.00' RT LINE G RIM= 1008.46 INV IN = 1001.25 (15" HDPE) INV IN = 999.41 (42" HDPE) INV OUT = 999.20 (42" HDPE) N: 992013.639; E: 2831888.297
G2	INSTALL 7'X6' NON-SETBACK CURB INLET 11+33.58, 0.00' LINE G RIM= 1007.59 INV IN = 1000.19 (42" HDPE) INV IN = 1002.44 (15" HDPE) INV OUT = 999.89 (42" HDPE) N: 992050.220; E: 2831799.815
G3	INSTALL 6'X5' DOUBLE GRATE INLET 14+39.71, 0.00' LINE G RIM= 1007.65 INV IN = 1002.92 (30" HDPE) INV IN = 1002.44 (15" HDPE) INV OUT = 1001.92 (42" HDPE) N: 992353.638; E: 2831840.461



STRUCTURES	
ID	DESCRIPTION
G3	INSTALL 6'X5' DOUBLE GRATE INLET 14+39.71, 0.00' LINE G RIM= 1007.65 INV IN = 1002.92 (30" HDPE) INV IN = 1002.44 (15" HDPE) INV OUT = 1001.92 (42" HDPE) N: 992353.638; E: 2831840.461
GG1	5' X 5' - JUNCTION BOX 11+57.63, 0.00' LINE GG RIM= 1008.63 INV IN = 1003.73 (12" HDPE) INV OUT = 1003.23 (15" HDPE) N: 992465.374; E: 2831951.641

- NOTES:
- CONTRACTOR TO SUBMIT SHOP DRAWINGS TO ENGINEER FOR APPROVAL PRIOR TO FABRICATION OF STRUCTURES AND ORDERING OF PIPE PRODUCTS.
  - CONTRACTOR TO INSTALL CONCRETE COLLAR AROUND ALL ADS DRAIN BASINS (SEE DETAILS IN THESE PLANS.)




**LEGEND**


--- PROPERTY LINE  
--- EXISTING CONTOUR  
--- PROPOSED CONTOUR  
--- 830  
--- 830  
--- PROPOSED STORM SEWER

COMPACTED FILL MUST BE PLACED TO A MINIMUM OF 2'-0" ABOVE THE TOP OF THE PROPOSED SEWER PIPE PRIOR TO INSTALLATION OF THE SEWER PIPE.

LINE G (9+75 - 14+75)

LINE GG (9+75 - 11+75)





STRUCTURES	
ID	DESCRIPTION
G3	INSTALL 6'X5' DOUBLE GRATE INLET 14+39.71, 0.00' LINE G RIM= 1007.65 INV IN = 1002.92 (30" HDPE) INV IN = 1002.44 (15" HDPE) INV OUT = 1001.92 (42" HDPE) N: 992353.638; E: 2831840.461
G4	INSTALL 5'X5' DOUBLE GRATE INLET 15+72.47, 0.00' LINE G RIM= 1008.10 INV IN = 1003.88 (30" HDPE) INV OUT = 1003.58 (30" HDPE) N: 992486.265; E: 2831846.479
G5	INSTALL 5'X5' DOUBLE GRATE INLET 16+99.94, 0.00' LINE G RIM= 1010.43 INV IN = 1005.02 (24" HDPE) INV OUT = 1004.52 (30" HDPE) N: 992615.603; E: 2831852.256
G6	INSTALL 5'X4' JUNCTION BOX 18+52.50, 0.00' LINE G RIM= 1013.98 INV IN = 1006.08 (18" HDPE) INV OUT = 1005.94 (24" HDPE) N: 992765.725; E: 2831863.789



NOTES:


- CONTRACTOR TO SUBMIT SHOP DRAWINGS TO ENGINEER FOR APPROVAL PRIOR TO FABRICATION OF STRUCTURES AND ORDERING OF PIPE PRODUCTS.
- CONTRACTOR TO INSTALL CONCRETE COLLAR AROUND ALL ADS DRAIN BASINS (SEE DETAILS IN THESE PLANS.)

LEGEND

- PROPERTY LINE  
--- 830 --- EXISTING CONTOUR  
--- 830 --- PROPOSED CONTOUR  
--- PROPOSED STORM SEWER  
[Hatched Box] COMPACTED FILL MUST BE PLACED TO A MINIMUM OF 2'-0" ABOVE THE TOP OF THE PROPOSED SEWER PIPE PRIOR TO INSTALLATION OF THE SEWER PIPE.

LINE G (14+00 - 18+75)







STRUCTURES	
ID	DESCRIPTION
G6	INSTALL 5'x4' JUNCTION BOX 18+52.50, 0.00' LINE G RIM= 1013.98 INV IN = 1006.08 (18" HDPE) INV OUT = 1005.94 (24" HDPE) N: 992765.725; E: 2831863.789
G7	INSTALL 4'x4' JUNCTION BOX 19+79.80, 0.00' LINE G RIM= 1014.58 INV IN = 1007.27 (15" HDPE) INV OUT = 1006.84 (18" HDPE) N: 992857.289; E: 2831952.225
G8	INSTALL 2' DIA. NYLOPLAST BASIN WITH PEDESTRIAN GRATE LID 21+11.52, 0.00' LINE G RIM= 1016.03 INV IN = 1008.49 (15" HDPE) INV OUT = 1008.06 (15" HDPE) N: 992983.957; E: 2831988.380
G9	INSTALL 2' DIA. NYLOPLAST BASIN WITH PEDESTRIAN GRATE LID 22+87.96, 0.00' LINE G RIM= 1016.20 INV OUT = 1009.37 (15" HDPE) N: 993160.211; E: 2831996.383


- NOTES:
- CONTRACTOR TO SUBMIT SHOP DRAWINGS TO ENGINEER FOR APPROVAL PRIOR TO FABRICATION OF STRUCTURES AND ORDERING OF PIPE PRODUCTS.
  - CONTRACTOR TO INSTALL CONCRETE COLLAR AROUND ALL ADS DRAIN BASINS (SEE DETAILS IN THESE PLANS.)

LEGEND



--- PROPERTY LINE  
--- 830 --- EXISTING CONTOUR  
--- 830 --- PROPOSED CONTOUR  
--- PROPOSED STORM SEWER  
[Hatched Box] COMPACTED FILL MUST BE PLACED TO A MINIMUM OF 2'-0" ABOVE THE TOP OF THE PROPOSED SEWER PIPE PRIOR TO INSTALLATION OF THE SEWER PIPE.

LINE G (18+25 - 23+25)






LINE H (9+75 - 11+25)





NOTES:


- CONTRACTOR TO SUBMIT SHOP DRAWINGS TO ENGINEER FOR APPROVAL PRIOR TO FABRICATION OF STRUCTURES AND ORDERING OF PIPE PRODUCTS.
- CONTRACTOR TO INSTALL CONCRETE COLLAR AROUND ALL ADS DRAIN BASINS (SEE DETAILS IN THESE PLANS.)

LEGEND




LINE J (9+75 - 12+00)





STRUCTURES	
ID	DESCRIPTION
K1	INSTALL 24" DIA. END SECTION WITH CONCRETE TOEWALL 10+00, 0.00' LINE K RIM= 1002.08 INV IN = 999.50 (24" HP) N: 992644.388; E: 2832283.205
K2	INSTALL 6'X4' NON-SETBACK CURB INLET 10+36.25, 0.00' LINE K RIM= 1006.98 INV IN = 1000.36 (15" HDPE) INV IN = 1000.36 (18" HDPE) INV OUT = 999.86 (24" HP) N: 992641.229; E: 2832247.098
K3	INSTALL 5'X5' JUNCTION BOX 11+23.09, 0.00' LINE K RIM= 1007.79 INV IN = 1003.27 (15" HDPE) INV IN = 1003.47 (10" HDPE) INV OUT = 1002.97 (18" HDPE) N: 992554.618; E: 2832240.753
K4	INSTALL 5'X5' JUNCTION BOX 12+39.93, 0.00' LINE K RIM= 1009.74 INV IN = 1005.32 (15" HDPE) INV IN = 1005.52 (10" HDPE) INV OUT = 1005.02 (15" HDPE) N: 992437.898; E: 2832235.453
K5	INSTALL 2' DIA. NYLOPLAST BASIN WITH SOLID LID 13+55.90, 0.00' LINE K RIM= 1009.78 INV IN = 1006.98 (10" HDPE) INV OUT = 1006.48 (15" HDPE) N: 992322.041; E: 2832230.192




STRUCTURES	
ID	DESCRIPTION
K2	INSTALL 6'X4' NON-SETBACK CURB INLET 10+36.25, 0.00' LINE K RIM= 1006.98 INV IN = 1000.36 (15" HDPE) INV IN = 1000.36 (18" HDPE) INV OUT = 999.86 (24" HP) N: 992641.229; E: 2832247.098
L1	INSTALL 6'X4' NON-SETBACK CURB INLET 10+90.75, 0.00' LINE L RIM= 1008.11 INV IN = 1003.92 (15" HDPE) INV OUT = 1003.92 (15" HDPE) N: 992650.972; E: 2832156.877


NOTES:

- CONTRACTOR TO SUBMIT SHOP DRAWINGS TO ENGINEER FOR APPROVAL PRIOR TO FABRICATION OF STRUCTURES AND ORDERING OF PIPE PRODUCTS.
- CONTRACTOR TO INSTALL CONCRETE COLLAR AROUND ALL ADS DRAIN BASINS (SEE DETAILS IN THESE PLANS.)


LEGEND




LINE K (9+75 - 13+75)




LINE L (9+75 - 11+25)








STRUCTURES	
ID	DESCRIPTION
M1	INSTALL 24" DIA. END SECTION WITH CONCRETE TOEWALL AND 2.8 CY RIPRAP 10+00, 0.00' LINE M RIM= 1001.31 INV IN = 999.50 (15" HDPE) N: 992550.121; E: 2832314.726
M2	INSTALL 4'X3' NYLOPLAST CURB INLET 10+32.61, 0.00' LINE M RIM= 1006.57 INV IN = 999.80 (15" HDPE) INV OUT = 999.66 (15" HDPE) N: 992538.053; E: 2832284.431
M3	INSTALL 4'X3' NYLOPLAST CURB INLET 11+67.03, 0.00' LINE M RIM= 1006.54 INV IN = 1001.54 (15" HDPE) INV OUT = 1001.14 (15" HDPE) N: 992405.502; E: 2832306.749
M4	INSTALL 4'X3' NYLOPLAST CURB INLET 12+70.42, 0.00' LINE M RIM= 1006.67 INV OUT = 1002.57 (15" HDPE) N: 992302.216; E: 2832302.051





LINE M (9+75 - 13+00)



STRUCTURES	
ID	DESCRIPTION
G2	INSTALL 7'X6' NON-SETBACK CURB INLET 11+33.58, 0.00' LINE G RIM= 1007.59 INV IN = 1000.19 (42" HDPE) INV IN = 1002.44 (15" HDPE) INV OUT = 999.89 (42" HDPE) N: 992050.220; E: 2831799.815
N1	INSTALL 6'X4' NON-SETBACK CURB INLET 15+86.82, 110.22' RT LINE E RIM= 1008.86 INV OUT = 1003.75 (15" HDPE) N: 992056.549; E: 2831669.386



LINE N (9+75 - 11+50)



LEE'S SUMMIT MIDDLE SCHOOL #4

LEE'S SUMMIT R-7 SCHOOL DISTRICT

1001 SE BAILEY ROAD  
LEE'S SUMMIT, MO 64881

PACKAGE 2-  
STRUCTURAL & SITE  
UTILITIES  
ISSUED FOR PERMIT  
08/28/20  
PR002R 01.14.21

STORM SEWER  
PLAN & PROFILE -  
LINE M AND N

C1046

13-2010102-00


olsson

OLSSON, CIVIL ENGINEERING  
MO. CERTIFICATE OF AUTHORITY #001982  
7301 West 133rd Street, Suite 200  
Overland Park, KS 66213-4750  
TEL 913.381.1170  
www.olsson.com




DLR Group  
© DLR Group, Inc. a Missouri corporation,  
83020 DLR Group, Inc. a Missouri corporation,  
Missouri State Certificate of Authority #000939

DWG: F:\2020\0001-0500\020-0103\40-Design\AutoCAD\Final Plans\Sheets\GNV\CONSTRUCTION DOCUMENTS\C\_DRN01\_0200103.dwg  
DATE: Dec 01, 2021 7:34am XREFS: C\_XBASE\_0200103 C\_PBASE\_0200103 C\_PSURF\_0200103 C\_PTLK\_0200103 C\_PSAS\_0200103 C\_PSTRM\_0200103 V\_XALT\_00103  
USER: bkimmich T\_PBASE\_0200103




NOTE: UNLESS NOTED ON THE STORM SEWER PLAN AND PROFILE, RIPRAP SIZING FOR THE INLET AND OUTLET IN THE DETENTION BASINS SHALL MATCH THE RIPRAP TABLE PROVIDED ON C1050.


STORM SEWER PIPE AND STRUCTURE TABLE																																		
TITLE: LSMS #4 JOB #: 020-0103 DESIGN CONDITIONS: PRIVATE - 100 YEAR STORM EVENT																																		
STRUCTURES										RUNOFF CALCULATIONS										PIPE DESIGN														
FROM	TO	DIRECT AREA (ACRES)	TOTAL AREA (ACRES)	C	KC (K+1.25)	Tc (MIN)	FLOW TIME (MIN)	INTENSITY (IN/HR)	DESIGN Q (CFS)	DESCRIPTION	PIPE LENGTH (L.F.)	PIPE SLOPE (%)	PIPE DIA (IN)	Q FULL (CFS)	PIPE AREA (SQ.FT)	V FULL (F/FS)	DESIGN V (F/FS)	HW/D	MH TOP ELEVATION	UPSTREAM FLOWLINE	DOWNSTREAM FLOWLINE	DOWNSTREAM WATER ELEVATION	FRICTION HEAD (H F)	ENTRY LOSS COEFFICIENT (K)	ACTUAL ENTRY LOSS (K)	ENTRY LOSS (H M)	h f + h m (FT)	HW, INLET CONTROL	HW, OUTLET CONTROL	HYDRAULIC GRADIENT ELEV.	HYDRAULIC HEAD (MAX)	HG (Max) - HGL	Comments	
EDD 1	A6		0.35	0.90	1.00	5.0		10.32		Area Inlet									1016.21													1.19		
	A5		0.35	0.90	1.00	5.0	0.85	10.32	3.61	15 in. HDPE	210.61	0.50	15	4.58	1.23	3.73	4.13	0.95		1012.83	1011.78	1013.00	0.67	1.00	1.00	0.27	0.93	1014.02	1013.93	1014.02	1015.21			
	A4		0.15	0.46	0.56	5.0		10.32		Area Inlet									1015.02													1.22		
	A5	A4	0.50	0.85	0.98	5.8	0.85	10.32	4.99	15 in. HDPE	228.76	0.50	18	7.45	1.77	4.21	4.51	0.88		1011.48	1010.34	1011.67	0.52	0.30	0.30	0.09	0.82	1012.80	1012.28	1012.80	1014.00			
	A4		0.39	0.30	0.38	5.0		10.32		Area Inlet									1015.00													2.37		
	A3		0.89	0.74	0.93	6.7		9.66	7.95	24 in. HDPE	119.51	0.50	24	16.04	3.14	5.11	5.09	0.80		1010.04	1009.44	1010.94	0.15	0.20	0.20	0.08	0.23	1011.63	1011.17	1010.84	1016.13	5.29		
EDD 2	A3		0.27	0.30	0.38	5.0		10.32		Area Inlet									1017.13															
	A2		1.16	0.69	0.54	7.1	0.38	9.52	9.53	24 in. HDPE	120.29	0.50	24	16.04	3.14	5.11	5.31	0.85		1009.14	1008.54	1010.20	0.22	0.20	0.20	0.09	0.30	1010.84	1010.50	1010.93	1014.66	3.73		
	A2		0.05	0.55	0.69	5.0		10.32		Area Inlet									1015.66															
	A1		0.21	0.69	0.86	7.5	0.10	9.39	9.80	24 in. HDPE	33.37	0.50	24	16.04	3.14	5.11	5.35	0.86		1008.24	1008.07	1010.80	0.06	0.15	0.15	0.07	0.13	1009.96	1010.93					
	C7		0.15	0.85	1.00	5.0		10.32		Area Inlet									1016.91													3.33		
	C6		0.15	0.85	1.00	5.0	0.46	10.32	1.55	15 in. HDPE	118.91	1.00	15	6.48	1.23	5.28	4.33	0.72		1011.68	1010.49	1011.15	0.07	1.00	1.00	0.29	0.36	1012.58	1011.88	1011.20	1014.56	3.36		
EDD 3	C6		0.10	0.80	1.00	5.0		10.32		Area Inlet									1015.56															
	C5		0.25	0.83	1.00	5.5	0.43	10.14	2.53	15 in. HDPE	189.11	3.00	15	11.22	1.23	9.14	7.39	0.81		1010.19	1004.52	1005.24	0.29	0.20	0.20	0.17	0.46	1011.20	1010.19	1004.00	1005.89	1.89	ADD LINE CC	
	C5		0.24	0.45	0.56	5.0		10.32		Area Inlet									1010.82													2.70		
	C4		0.52	1.29	0.52	6.6	0.10	9.97	8.84	15 in. HDPE	60.46	3.00	15	11.22	1.23	9.14	10.11	2.32		1006.89														
	C4		0.52	0.52	0.65	5.0		10.32		Area Inlet									1010.82															
	C3		1.81	0.52	0.65	6.0	0.30	9.93	11.68	24 in. HDPE	128.71	1.00	24	22.68	3.14	7.22	7.26	0.95		1002.11	1000.82	1002.45	0.35	0.30	0.30	0.25	0.59	1004.00	1003.04	1002.29	1003.39	1.10		
EDD 4	C3		0.60	0.40	0.50	5.0		10.32		Area Inlet									1004.39															
	C2		2.41	0.46	0.58	6.3	0.25	9.82	13.60	30 in. RCP	86.50	0.50	24	29.08	4.91	5.92	5.82	0.79		1000.09	1000.29	1002.12	0.10	0.15	0.15	0.08	0.17	1002.07	1002.29	1001.88	1004.42	2.54		
	C2		0.56	0.40	0.50	5.0		10.32		Area Inlet									1005.42															
	C1		2.97	0.44	0.55	6.5	0.16	9.72	15.88	30 in. RCP	58.52	0.50	24	29.08	4.91	5.92	6.05	0.84		999.79	999.50	1001.10	0.09	0.30	0.30	0.17	0.26	1001.88	1001.36					
	CC2		0.50	0.45	0.56	5.0		10.32		Curb Inlet									1012.74													2.56		
	CC1	CC1	0.50	0.50	0.45	5.0	0.57	10.32	2.90	15 in. HDPE	176.95	1.00	15	6.48	1.23	5.28	5.13	0.85		1007.62	1005.85	1006.78	0.36	1.00	1.00	0.41	0.77	1008.68	1007.62	1008.68	1011.24			
EDD 5	CC1		0.30	0.55	0.69	5.0		10.32		Curb Inlet									1009.66													1.13		
	C4		0.80	0.49	0.61	5.8	0.44	10.09	4.94	15 in. HDPE	179.24	1.50	15	7.93	1.23	6.46	6.81	1.19		1005.55	1002.86	1004.03	1.06	0.30	0.30	0.22	1.28	1007.03	1005.55	1007.03	1008.16	1.13		
	M4		0.28	0.52	0.65	5.0		10.32		Area Inlet									1006.67													2.17		
	M3		0.28	0.52	0.65	5.0	0.38	10.32	1.88	15 in. HDPE	103.39	1.00	15	6.48	1.23	5.28	4.57	0.74		1002.57	1001.54	1002.27	0.09	1.00	1.00	0.32	0.41	1003.50	1002.69	1003.50	1005.67			
	M3		0.23	0.55	0.69	5.0		10.32		Area Inlet									1006.54													3.25		
	M2		0.51	0.53	0.66	5.4	0.42	10.17	3.44	15 in. HDPE	134.42	1.00	15	6.48	1.23	5.28	5.35	0.92		1001.14	999.80	1000.82	0.38	0.30	0.30	0.13	0.52	1002.29	1001.34	1002.29	1005.54			
EDD 6	M2		0.20	0.55	0.69	5.0		10.32		Area Inlet									1006.57													4.08		
	M1		0.71	0.54	0.68	5.8	0.09	10.00	4.79	15 in. HDPE	32.61	1.00	15	6.48	1.23	5.28	5.77	1.16		999.66	999.34	1001.10	0.18	0.40	0.40	0.21	0.39	1001.11	1001.49	1001.49	1005.57			
	K3		0.76	0.90	1.00	5.0		10.32		Area Inlet									1007.92													1.66		
	K2		0.18	2.09	0.57	0.71	5.0	0.12	10.32	15.37	24 in. HDPE	86.84	3.00	18	39.29	3.14	12.51	11.72	1.15		1002.97	1000.36	1001.94	0.40	1.00	1.00	2.13	2.54	1005.26	1004.47	1005.26	1006.92		
	K2		0.18	0.78	0.98	5.0		10.32		Area Inlet									1007.02													3.63		
	K1		2.27	0.59	0.74	5.1	0.08	10.27	17.20	24 in. HDPE	36.25	1.00	24	22.68	3.14	7.22	7.92	1.27		999.86	999.50	1001.10	0.21	0.40	0.40	0.39	0.60	1002.39	1001.70	1002.39	1006.02			
EDD 7	L1		1.33	0.38	0.48	5.0		10.32		Area Inlet									1007.92													1.45		
	K2		1.33	0.38	0.48	5.0	0.15	10.32	6.52	18 in. HDPE	90.75	3.92	18	20.85	1.77	11.80	10.42	1.03		1003.92	1000.36	1001.43	0.35	1.00	1.00	1.69	2.04	1005.47	1003.92	1005.47	1006.92			
	E11		0.13	0.45	0.56	5.0		10.32		Area Inlet									1027.14													5.45		
	E10		0.54	0.41	0.51	5.0		10.32	0.75	15 in. HDPE	212.64	1.50	15	7.93	1.23	6.46	4.08	0.68		1019.84	1016.65	1017.08	0.03	1.00	1.00	0.26	0.29	1020.69	1019.84	1020.69	1026.14			
	E9		0.70	0.67	0.42	0.50	0.37	10.32	3.49	15 in. HDPE	138.28	1.50	15	7.93	1.23	6.46	6.25	0.93		1016.35	1014.30	1015.26	0.41	0.30	0.30	0.18	0.59	1017.51	1016.35	1017.51	1024.31	6.80		
	E8		1.23	0.70	0.87	6.2	0.17	9.83	11.78	24 in. HDPE	87.11	1.50	24	27.78	3.14	8.84	8.47	0.95		1014.00	1012.69	1014.22	0.24	0.40	0.40	0.45	0.68	1015.90	1014.90	1015.90	1022.55	6.65		
EDD 8	E8		1.23	0.52	0.65	5.0		10.32		Area Inlet									1019.97													3.83		
	E7		2.60	0.60	0.74	6.4	0.49	9.77	18.89	24 in. HDPE	248.71	1.10	24	23.79	3.14	7.57	8.39	1.39		1012.36	1009.62	1011.75	1.75	0.20	0.20	0.22	1.97	1015.14	1013.72	1015.14	1018.97			
	E7		0.85	0.41	0.51	5.0		10.32		Area Inlet									1019.91													7.09		
	E6		3.45	0.54	0.68	6.9	0.87	9.59	22.40	30 in. RCP	390.96	0.70	30	34.41	4.91	7.01	7.45	1.00		1009.32	1006.58	1008.96	1.18	0.20	0.20	0.17	1.35	1011.82	1010.20	1011.82	1016.91			
	E6		0.82	0.40	0.50	5.0		10.32		Area Inlet									1016.91													6.89		
	E5		4.27	0.51	0.64	7.8	0.49	9.28	25.33	30 in. RCP	224.24	0.70	30	34.41	4.91	7.01	7.65	1.09		1006.28	1004.71	1007.16	0.86	0.20	0.20	0.18	1.04	1009.02	1008.21	1009.02	1015.91			
EDD 9	E5		0.47	0.43	0.54	5.0		10.32		Area Inlet									1015.36													7.03		
	E4		0.16	4.74	0.50	0.63	8.3																											



STORM SEWER PIPE AND STRUCTURE TABLE																																		
TITLE: LSMS #4 JOB # 020-0103 DESIGN CONDITIONS: PRIVATE - 10 YEAR STORM EVENT																																		
STRUCTURES										PIPE DESIGN																								
FROM	TO	DIRECT AREA (ACRES)	TOTAL AREA (ACRES)	C	KC (K=1.25)	Tc (MIN)	FLOW TIME (MIN)	INTENSITY (IN/HR)	DESIGN Q (CFS)	DESCRIPTION	PIPE LENGTH (L.F.)	P/PE SLOPE (%)	PIPE DIA (IN)	Q FULL (CFS)	PIPE AREA (SQ.FT.)	V FULL (F/S)	DESIGN V (F/S)	HWd	MH TOP ELEVATION	UPSTREAM FLOWLINE	DOWNSIDE FLOWLINE	DOWNSIDE WATER ELEVATION	FRICTION HEAD (H f)	ENTRY LOSS COEFFICIENT (k)	ACTUAL ENTRY LOSS (k)	ENTRY LOSS (h m)	h f + h m (FT)	HW INLET CONTROL	HW OUTLET CONTROL	PIPE CROWN	PIPE CROWN - HGL	HYDRAULIC GRADE ELEV.	HYDRAULIC GRADE (MAX)	Comments
E1D1	A6	0.35	0.90	0.90	5.0			7.35		Area Inlet									1016.21															
	A5	0.15	0.90	0.90	5.0		0.94	7.35	2.32	15 in. HDPE	210.61	0.50	15	4.58	1.23	3.73	3.74	0.78	1015.02	1012.83	1011.78	1012.71	0.27	1.00	1.00	0.22	0.49	1013.81	1013.20	1014.08	0.27	1013.81	1015.21	
	A5		0.45	0.45	5.0			7.35		Area Inlet									1015.02															
	A4	0.39	0.86	0.86	5.0			7.07	3.04	18 in. HDPE	228.76	0.50	18	7.45	1.77	4.21	4.00	0.75	1015.00	1011.48	1010.34	1011.34	0.19	0.30	0.30	0.07	0.27	1012.60	1011.60	1012.98	0.38	1012.60	1014.02	
	A4		0.30	0.30	5.0			7.35		Area Inlet									1015.00															
	A3	0.27	0.89	0.74	0.74	6.9	0.46	6.81	4.49	24 in. HDPE	119.51	0.50	24	16.04	3.14	5.11	4.37	0.71	1017.13	1010.04	1009.44	1010.53	0.05	0.20	0.20	0.06	0.11	1011.46	1010.64	1011.14	0.54	1010.59	1016.13	
E1D2	A3		0.30	0.30	5.0			7.35		Area Inlet									1017.13															
	A2	0.05	1.16	0.89	0.69	7.5	0.44	6.69	5.36	24 in. HDPE	120.29	0.50	24	16.04	3.14	5.11	4.59	0.73	1015.66	1008.14	1008.54	1009.74	0.07	0.20	0.20	0.07	0.13	1010.59	1009.88	1010.24	0.09	1010.15	1014.66	
	A2		0.55	0.55	5.0			7.35		Area Inlet									1015.66															
	A1	1.21	0.89	0.69	7.8	0.12	6.58	5.50	24 in. HDPE	33.37	0.50	24	16.04	3.14	5.11	4.62	0.73	1015.66	1008.24	1008.07	1010.30	0.02	0.15	0.20	0.07	0.09	1009.70	1010.15						
	C7	0.15	0.85	0.85	5.0			7.35		Area Inlet									1016.91															
	C6	0.10	0.80	0.80	5.0		0.53	7.35	0.94	15 in. HDPE	118.91	1.00	15	6.48	1.23	5.28	3.76	0.69	1015.56	1011.68	1010.49	1011.00	0.03	1.00	1.00	0.22	0.24	1012.54	1011.68	1012.93	0.39	1012.54	1015.91	
	C6		0.80	0.80	5.0			7.35		Area Inlet									1015.56															
	C5	0.24	0.25	0.83	0.83	5.5	0.50	7.19	1.49	15 in. HDPE	189.11	3.00	15	11.22	1.23	9.14	6.36	0.72	1010.82	1010.19	1004.52	1005.07	0.10	0.20	0.20	0.13	0.23	1011.09	1010.19	1011.44	0.35	1011.09	1014.56	
	C5		0.45	0.45	5.0			7.35		Area Inlet									1010.82															
	C4	0.52	1.29	0.55	0.55	6.0	0.11	7.05	5.00	15 in. HDPE	60.46	3.00	15	11.22	1.23	9.14	8.87	1.20	1006.89	1004.22	1002.41	1003.45	0.37	0.40	0.40	0.49	0.86	1005.72	1004.30	1005.85	0.13	1005.72	1009.82	ADD LINE CC
	C4		0.52	0.52	5.0			7.35		Area Inlet									1006.89															
	C3	0.60	1.81	0.52	0.52	6.1	0.34	7.02	6.61	24 in. HDPE	128.71	1.00	24	22.68	3.14	7.22	6.25	0.76	1004.39	1002.11	1000.82	1002.02	0.11	0.30	0.30	0.18	0.29	1003.63	1002.31	1002.09	0.15	1001.94	1003.39	
	C3		0.40	0.40	5.0			7.35		Area Inlet									1004.39															
	C2	0.56	2.41	0.45	0.46	5.0	0.29	6.92	7.67	24 in. HDPE	86.50	0.50	24	16.04	3.14	5.11	5.04	0.79	1005.42	1000.09	1000.29	1001.76	0.10	0.15	0.20	0.08	0.18	1001.67	1001.94	1001.79	0.34	1001.46	1004.42	
	C2		0.40	0.40	5.0			7.35		Area Inlet									1005.42															
	C1	2.97	0.44	0.44	6.8	0.19	6.85	8.95	24 in. HDPE	58.52	0.50	24	16.04	3.14	5.11	5.23	0.83	1012.74	999.79	999.50	1000.30	0.09	0.30	0.30	0.13	0.22	1001.46	1000.52	1008.87	0.34	1008.53	1011.24		
	CC2	0.50	0.45	0.45	5.0			7.35		Curb Inlet									1012.74															
	CC1	0.30	0.50	0.45	0.45	5.0	0.87	7.35	1.65	15 in. HDPE	176.95	1.00	15	6.48	1.23	5.28	4.42	0.73	1009.66	1007.62	1005.85	1006.54	0.12	1.00	1.00	0.30	0.42	1008.53	1007.62	1006.87	0.20	1006.60	1008.16	
	CC1		0.55	0.55	5.0			7.35		Curb Inlet									1009.66															
	C4	0.30	0.80	0.49	0.49	5.7	0.51	7.15	2.80	15 in. HDPE	179.24	1.50	15	7.93	1.23	6.46	5.91	0.84	1009.66	1005.55	1002.86	1003.83	0.34	0.30	0.30	0.16	0.50	1006.60	1005.55	1006.80	0.20	1006.60	1008.16	
M4	0.28	0.52	0.52	5.0			7.35		Area Inlet									1006.87																
M3	0.23	0.28	0.52	0.52	5.0	0.44	7.35	1.07	15 in. HDPE	103.39	1.00	15	6.48	1.23	5.28	3.91	0.69	1006.54	1002.57	1001.54	1002.09	0.03	1.00	1.00	0.24	0.27	1003.44	1002.57	1003.82	0.38	1003.44	1005.67		
M3		0.55	0.55	5.0			7.35		Area Inlet									1006.54																
M2	0.20	0.51	0.53	0.53	5.4	0.48	7.22	1.95	15 in. HDPE	134.42	1.00	15	6.48	1.23	5.28	4.62	0.75	1006.57	1001.14	999.80	1000.55	0.12	0.30	0.30	0.10	0.22	1002.08	1001.14	1002.39	0.31	1002.08	1005.54		
M2		0.55	0.55	5.0			7.35		Area Inlet									1006.57																
M1	0.71	0.54	0.54	5.9	0.11	7.08	2.71	15 in. HDPE	32.61	1.00	15	6.48	1.23	5.28	5.05	0.83	1006.57	999.66	999.34	1000.30	0.06	0.40	0.40	0.16	0.22	1000.69	1000.52	1000.91	0.22	1000.69	1005.57			
K3	0.76	0.90	0.90	5.0			7.35		Area Inlet									1007.92																
K2	0.18	2.09	0.57	0.57	5.0	0.14	7.35	8.76	18 in. HDPE	86.84	3.00	18	18.24	1.77	10.32	10.20	1.32	1007.02	1002.97	1000.36	1001.67	0.61	1.00	1.00	1.62	2.23	1004.32	1003.89	1004.47	0.15	1004.32	1006.92	ADD LINE L	
K2		0.78	0.78	5.0			7.35		Area Inlet									1007.02																
K1	2.27	0.59	0.59	5.1	0.09	7.31	9.79	24 in. HDPE	36.25	1.00	24	22.68	3.14	7.22	6.94	0.86	1007.02	999.86	999.50	1000.30	0.07	0.40	0.40	0.30	0.37	1001.59	1000.67	1001.86	0.27	1001.59	1006.02			
L1	1.33	0.38	0.38	5.0			7.35		Area Inlet									1007.92																
L1		1.33	0.38	5.0		0.17	7.35	3.72	18 in. HDPE	90.75	3.92	18	20.85	1.77	11.80	8.90	0.79	1007.92	1003.92	1000.36	1001.59	0.11	1.00	1.00	1.23	1.35	1005.10	1003.92	1005.42	0.32	1005.10			



LIGHT DUTY ASPHALT PAVEMENT SECTION  
NOT TO SCALE



HEAVY DUTY ASPHALT PAVEMENT SECTION  
NOT TO SCALE



GENERAL NOTES:

1. SUBGRADE MUST BE OF STABLE, COMPACTED EARTH AND SHALL BE OVERLAYED WITH 4" COMPACTED DENSE GRADED AGGREGATE BASE.
2. 1.5% CROSS SLOPE SHALL BE MAINTAINED THROUGH DRIVEWAYS.
3. KOWABE 4K CONCRETE MIX SHALL BE REQUIRED FOR ALL SIDEWALKS OR AS APPROVED BY THE CITY INSPECTOR.
4. ALL SIDEWALKS SHALL MEET CURRENT PUBLIC RIGHT OF WAY ACCESSIBILITY GUIDELINES (PROWAG) APPROVED BY THE CITY INSPECTOR.
5. JOINTS SHALL BE PLACED AT 150 FT. MAXIMUM. JOINTS SHALL BE PLACED THE SAME WIDTH OF SIDEWALK, BUT NO GREATER THAN 10 FT.
6. SIDEWALK FINISHING (NO PICTURE FRAMING) AS DIRECTED BY CITY INSPECTOR.
7. CURB FINISHING (NO PICTURE FRAMING) MUST BE APPLIED UNIFORMLY TO THE CONCRETE SURFACE IMMEDIATELY AFTER FINAL FINISHING.





## ACCESSIBLE PARKING SYMBOL



OUTLET WITHOUT DITCH PROTECTIVE APRON DIMENSIONS AND ESTIMATED QUANTITIES						
	CULVERT SIZE (Inches)	RIPRAP CLASS	LENGTH OF APRON (feet)	DEPTH OF APRON (feet)	ESTIMATED GEOTEXTILE QUANTITY (C.T.)	ESTIMATED GEOTEXTILE QUANTITY (S.Y)
WITH END SECTION	12	2	4	1.5	1	5
	18	2	6	1.5	2.2	9
	24	2	8	1.5	3.9	14
	30	3	12.5	2	10.9	26
	36	3	16	2	15.6	37
	42	4	21	2.5	24.1	63
	48	4	24	2.5	34.5	79
	12	6	2	1.5	1.7	8
WITHOUT END SECTION	18	2	8	1.5	3.2	12
	24	2	10	1.5	5.2	17
	30	3	14	1.5	7.2	23
	36	3	17	2	18.5	43
	42	4	23	2.5	38.7	79
	48	4	26	2.5	50.5	89

**NOTE:**

1. Use for aprons serving culverts with slopes of less than 10%.
2. Furnish geotextile conforming to Subsection 714.01(a).
3. Excavation for placement of riprap will not be measured for payment.



**PROTECTIVE APRON AT CULVERT OUTLET  
WITH DITCH**

OUTLET WITH DITCH						
PROTECTIVE APRON DIMENSIONS AND ESTIMATED QUANTITIES						
	CULVERT SIZE (inches)	RIPRAP CLASS	LENGTH (feet)	DEPTH APRON (feet)	ESTIMATED QUANTITY (CY)	ESTIMATED GEOTEKSTILE QUANTITY (S)
WITH END SECTION	18	2	4	1.5	0.9	5
	18	2	6	1.5	2	8
	24	2	8	1.5	3.6	13
	30	3	12.5	2	9.3	24
	36	3	15	2	13.4	32
	42	4	21	2.5	23.6	53
WITHOUT END SECTION	18	2	6	1.5	1.4	6
	18	2	8	1.5	2.7	10
	24	2	10	1.5	4.5	15
	30	3	14.5	2	10.8	27
	36	3	17	2	15.2	36
	42	4	23	2.5	29.9	57

NO SCALE

U.S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
CENTRAL FEDERAL LANDS HIGHWAY DIVISION

U.S. CUSTOMARY DETAIL

**PLACED RIPRAP  
AT CULVERT OUTLET**

DETAIL APPROVED FOR USE	DETAIL
REVISED: 06/2014	C251-5



NOTE:

ANCHOR RODS TO BE SLEEVED OF GREASED THRU CONCRETE CURBS TO PERMIT RELOCATION OF CURBS.



### WHEEL STOP DETAIL

NOT TO SCALE



## NOTES

1. SIGN TO BE PER LOCAL JURISDICTION REQUIREMENTS. VERIFY SIZE, SHAPE & VERBIAGE
2. PROVIDE SIGN AT EACH HANDICAPPED ACCESSIBLE PARKING STALL.




NOT TO SCALE



1. GRATE COVER DETAIL SHALL BE ADJUSTED AS NECESSARY TO FIT END SECTION PROVIDED.
2. MAXIMUM OPENING THRU END SECTION SHALL BE NO GREATER THAN 6". ADJUST DETAIL AS NECESSARY.
3. ALL METAL SURFACES SHALL BE HOT DIP ZINC COATED IN ACCORDANCE WITH ASTM A-123.
4. USE CITY APPROVED CONCRETE THROUGHOUT.
5. ALL CONCRETE AND MATERIALS USED IN THIS WORK SHALL MEET THE REQUIREMENTS OF THE GOVERNING BODY.
6. REINFORCING STEEL SHALL BE NEW BILLET, MINIMUM GRADE 40 AS PER ASTM A615, AND SHALL BE BENT COLD.
7. ALL DIMENSIONS RELATIVE TO REINFORCING STEEL ARE TO CENTERLINE OF BARS. 2" CLEARANCE SHALL BE PROVIDED THROUGHOUT UNLESS NOTED OTHERWISE. TOLERANCE OF  $\pm 1/8"$  SHALL BE PERMITTED.
8. ALL LAP SPLICES NOT SHOWN SHALL BE A MINIMUM OF 40 BAR DIAMETERS IN LENGTH.
9. ALL DOWELS SHALL BE ACCURATELY PLACED AND SECURELY TIED IN PLACE PRIOR TO PLACEMENT OF BOTTOM SLAB CONCRETE. STICKING OF DOWELS INTO FRESH OR PARTIALLY HARDENED CONCRETE WILL NOT BE ACCEPTABLE.
10. ALL REINFORCING STEEL SHALL BE SUPPORTED ON FABRICATED STEEL BAR SUPPORTS @ 3'-0" MAXIMUM SPACING.
11. DO NOT SCALE THESE DRAWINGS FOR DIMENSIONS OR CLEARANCES. ANY QUESTIONS REGARDING DIMENSIONS SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO CONSTRUCTION.

NOT TO SCALE



NOT TO SCALE



- NOTE:
1. EXPANSION JOINTS TO BE USED IN ALL AREAS THAT CONCRETE PAVEMENT ABUTS BUILDING
  2. 6X6X6 WELDED WIRE MESH IS TO BE USED IN ALL CONCRETE WALKS AROUND BUILDINGS.




## CONCRETE PAVING JOINT DETAILS

NOT TO SCALE







NOT TO SCALE



NOT TO SCALE





LEE'S SUMMIT MIDDLE SCHOOL #4  
LEE'S SUMMIT R-7 SCHOOL DISTRICT

PACKAGE 2-  
STRUCTURAL & SITE  
UTILITIES  
ISSUED FOR PERMIT  
08/28/20

STANDARD  
DETAILS

C1053



olsson  
OLSSON, CIVIL ENGINEERING  
MO CERTIFICATE OF AUTHORITY #001982  
7301 West 133rd Street, Suite 200  
Overland Park, KS 66211-4750  
TEL 913.381.1170  
www.olsson.com

DLR Group  
© DLR Group  
80320 DLR Group, Inc., a Missouri corporation,  
Missouri State Certificate of Authority #00039

LEE'S SUMMIT  
MISSOURI

STANDARD DETAILS  
CITY OF LEE'S SUMMIT, MO  
LEE'S SUMMIT, JACKSON COUNTY, MO  
PROJECT NAME: ADA RAMP RETROFIT DETAIL  
SHEET NAME: GEN-3A


GEN-3A

LEE'S SUMMIT  
MISSOURI

STANDARD DETAILS  
CITY OF LEE'S SUMMIT, MO  
LEE'S SUMMIT, JACKSON COUNTY, MO  
PROJECT NAME: DRIVEWAY DETAIL  
SHEET NAME: GEN-1

GEN-1

DWG: F:\2020\0001-0500\0200-0103\40-Design\AutoCAD\Final Plans\Sheets\GNV\CONSTRUCTION DOCUMENTS\CDT\01\_0200103.dwg USER: bkimnich  
DATE: Dec 01, 2021 7:39am XREFS: C\_4LS\_PBASE\_80330 C\_4LS\_PBASE\_61023 C\_4LS\_PBASE\_80330 C\_4LS\_PBASE\_61023 C\_PTBK\_0200103 C\_PBASE\_80330 C\_PBASE\_61023



3" LETTERS EQUALLY PLACED

1-1/2" LETTERS EQUALLY SPACED

STANDARD 24" MANHOLE COVER  
MINIMUM WEIGHT = 160 LB  
NOTE: PICK HOLES NOT SHOWN

\*COVER AND FRAME MODEL INFORMATION REFER TO THE STORMWATER APPROVED PRODUCT LIST.


LS

**LEE'S SUMMIT**  
MISSOURI  
PUBLIC WORKS ENGINEERING DIVISION | 220 SE GREEN STREET | LEE'S SUMMIT, MO 64063

STORM MANHOLE COVER DETAIL

Date: 04/17  
Drawn By: MIF  
Checked By: DL

STM-6



FINISHED GRADE

REGULAR BACKFILL

TRENCH AS REQUIRED BY OSHA

FLOWABLE FILL

12" MANH

NOT TO SCALE

NOTES:

1. FLOWABLE FILL SHALL MEET THE REQUIREMENTS OF THE CITY OF LEE'S SUMMIT DESIGN AND CONSTRUCTION MANUAL.
2. REGULAR BACKFILL ABOVE THE TRENCH CHECK SHALL BE FREE OF DEBRIS, ORGANIC MATTER, AND STONES > 6" IN ANY DIMENSION.
3. TOP OF FLOWABLE BACKFILL SHALL EXTEND 12" ABOVE THE TOP OF THE PIPE.
4. LENGTH OF TRENCH CHECK SHALL BE A MINIMUM OF 12".


LS

**LEE'S SUMMIT**  
MISSOURI  
PUBLIC WORKS ENGINEERING DIVISION | 220 SE GREEN STREET | LEE'S SUMMIT, MO 64063

TRENCH CHECK

Date: 02/13  
Drawn By: JN  
Checked By: DL  
FILE: WAT-6  
Rev: 1/14  
Rev:

GEN-7



2'-0 5/16"

1'-10 9/16"

1 1/2"

2'-0 5/16"

1'-10 9/16"

1 1/2"

8 5/8"

2'-9 1/2"

SLAB MANHOLE FRAME  
LEE'S SUMMIT PART NO.: LS103A  
MINIMUM WEIGHT = 145 LB

STANDARD 24" MANHOLE FRAME  
LEE'S SUMMIT PART NO.: LS101A  
MINIMUM WEIGHT = 250 LB

\*COVER AND FRAME MODEL INFORMATION REFER TO THE STORMWATER APPROVED PRODUCTS LIST.


LS

**LEE'S SUMMIT**  
MISSOURI  
PUBLIC WORKS ENGINEERING DIVISION | 220 SE GREEN STREET | LEE'S SUMMIT, MO 64063

STORM MANHOLE FRAME DETAIL

Date: 04/17  
Drawn By: MIF  
Checked By: DL

STM-7



TRENCH CHECK

1-1/8 (45°) BEND

PROPERTY LINE OR 10' FROM MAIN

TRACER BOX WITH GREEN CAP

WATERTIGHT CAP

COMPACTED BACKFILL

SERVICE WYE

MAGNESIUM ANODE (1lb MIN)

45° MAX

COMPACTED GRANULAR BEDDING

STANDARD INSTALLATION  
NOT TO SCALE

(2)-1/8 (45°) BENDS

TRACER WIRE

(1)-1/8 (45°) BEND

SERVICE WYE

MAGNESIUM ANODE (1lb MIN)

PROPERTY LINE OR 10' FROM MAIN

TRACER BOX WITH GREEN CAP

WATERTIGHT CAP

COMPACTED GRANULAR BEDDING

VERTICAL RISER  
NOT TO SCALE

SIDE VIEW

SEWAGE FLOW

NOTES:

1. ALL SEWER STUBS SHALL BE CONSTRUCTED TO PROPERTY LINE OR 10' MINIMUM FROM THE MAIN, WHERE SIDEWALKS ARE PRESENT, CONTRACTOR SHALL EXTEND SERVICE LINE UNDER EXISTING SIDEWALK TO TWO FEET BEYOND.
2. ALL NEW CONSTRUCTION OFF SEWER STUBS SHALL BE TEMPORARILY MARKED WITH A MARKING STAKE, 36" ABOVE GROUND AND PAINTED GREEN.
3. IMPERVIOUS TRENCH CHECKS SHALL BE PLACED ON BUILDING SEWER STUBS (AT LEAST 5' AWAY FROM THE SANITARY SEWER MAIN).
4. TRENCH CHECKS ON THE BUILDING SEWER STUBS SHALL EXTEND 6" BELOW THE BOTTOM OF THE PIPE. LENGTH SHALL BE A MINIMUM OF 12". THE HEIGHT OF THE TRENCH CHECK SHALL EXTEND 12" ABOVE THE TOP OF THE PIPE. THE WIDTH OF THE TRENCH CHECK SHALL BE THE WIDTH OF THE TRENCH.
5. SEE SPECIFICATION SECTION 2100 FOR SEWER MAIN BEDDING AND BACKFILL.
6. #12 GAUGE GREEN INSULATED COPPER TRACER WIRE SHALL BE INSTALLED. TRACER WIRE TERMINAL BOXES SHALL BE INSTALLED DIRECTLY ABOVE THE SEWER SERVICE OR AS DETERMINED BY THE ENGINEER.
7. FOR SERVICES, TRACER WIRE SHALL RUN FROM THE WYE AND TERMINATE IN A FLUSH MOUNTED TRACER BOX WITH A GREEN CAST IRON LOCKABLE TOP. WIRE SHALL BE TAPED OR TIED TO THE PIPE AT 5' INTERVALS.
8. TRACER WIRE BOX SHALL BE INSTALLED WITHIN 1.0' OF PROPERTY LINE.
9. THE TRACER WIRE SHALL REMAIN CONTINUOUS TO THE GREATEST EXTENT POSSIBLE. SPLICES IN THE TRACER WIRE SHOULD BE MADE WITH SPLIT BOLT CONNECTORS. WIRE NUTS SHALL NOT BE USED. A WATER-PROOF CONNECTION IS NECESSARY TO PREVENT CORROSION.


LS

**LEE'S SUMMIT**  
MISSOURI  
PUBLIC WORKS ENGINEERING DIVISION | 220 SE GREEN STREET | LEE'S SUMMIT, MO 64063

BUILDING SEWER STUB AND RISER

Date: 04/17  
Drawn By: Mif  
Checked By: DL

SAN-1



2" FROM BACK OF CURB

BACK OF CURB

GROUND SURFACE

MECHANICAL JOINT (TYP.)

THRUST BLOCK (SEE NOTE 1)

20" MIN. 42" MAX.

KEEP WEEPHOLE FREE OF CONCRETE AND FOREIGN MATERIAL

24"x24"x14" SOLID CONCRETE PAD

UNDISTURBED EARTH

PROVIDE MIN. 1/2 CU. YD. OF 3/4" GRANULAR FILL PER AWWA C600 SEC. 4.2.7.2.4

MJ RESTRAINT FITTINGS (SEE NOTES 1 & 2)

THRUST BLOCK

UNDISTURBED EARTH

VALVE LID & COVER

VARIES

VALVE BOX & BASE

6" GATE VALVE

NOTES:


1. WHEN RETAINER GLANDS ARE USED IN LIEU OF MECHANICAL JOINT (MJ) RESTRAINT FITTINGS, HORIZONTAL THRUST BLOCKS ARE REQUIRED.
2. GATE VALVE MAY BE BOLTED DIRECTLY TO MJ RESTRAINT TEE.
3. SEE APPROVED PRODUCTS LIST FOR WATER UTILITIES FOR FIRE HYDRANT, VALVES, VALVE BOX LID, AND COVER.
4. BOTTOM HYDRANT FLANGE SHALL BE 2" TO 6" ABOVE FINISHED GRADE.
5. FOR STREETS WITHOUT CURBS FIRE HYDRANTS SHALL BE PLACED WITHIN 1 FOOT OF THE 6" N LINE, BUT NOT MORE THAN 10" FROM EDGE OF PAVEMENT. FIRE HYDRANT SHALL NOT BE PLACED IN BOTTOM OF DITCH.
6. HYDRANT SHALL BE ROTATED AS DIRECTED BY INSPECTOR.

LS

**LEE'S SUMMIT**  
MISSOURI  
PUBLIC WORKS ENGINEERING DIVISION | 220 SE GREEN STREET | LEE'S SUMMIT, MO 64063

HYDRANT INSTALLATION - STRAIGHT SET

Date: 02/13  
Drawn By: JN  
Checked By: DL  
FILE: WAT-7  
Rev: 1/14  
Rev:



CORNER MAY BE MITERED AND ADJUSTED BACK TO ACCOMMODATE DRAINAGE

EXISTING CURB

FLOW LINES (TYP.)

45°

8'-0"

CONCRETE (KCCMB) VALLEY GUTTER

SECTION

Scale: 1" = 1'-0"

4'-0"

4'-0"

1" MIN.

6" CONC.

VALLEY GUTTER DETAIL  
Intersection of Two Public Streets


LS

**LEE'S SUMMIT**  
MISSOURI  
PUBLIC WORKS ENGINEERING DIVISION | 220 SE GREEN STREET | LEE'S SUMMIT, MO 64063

VALLEY GUTTER DETAIL

Date: 04/17  
Drawn By: MIF  
Checked By: DL

GEN-7



FLARED END SECTION

OUTSIDE WALL DIMENSION

WING WALL

PIPE - INSIDE DIAMETER

FLOOR

FLOOR THICKNESS

6"

6"

4"

8"

2' MIN. OR TO BEDROCK WHICHEVER IS SHALLOWER

PLAN VIEW  
NOT TO SCALE

END VIEW  
NOT TO SCALE

3,000 PSI OR GREATER CONCRETE MIX


LS

**LEE'S SUMMIT**  
MISSOURI  
PUBLIC WORKS ENGINEERING DIVISION | 220 SE GREEN STREET | LEE'S SUMMIT, MO 64063

FLARED END SECTION SUPPORT DETAIL

Date: 04/17  
Drawn By: MIF  
Checked By: DL

STM-5



#4 EPOXY COATED GR. 60 REBAR WITH 6" HOOK & 12" MIN. CONCRETE EMBEDMENT DEPTH

UNDISTURBED EARTH

REQUIRED CONCRETE VOLUME (CUBIC FEET - CF)					
NOM. DIA. (INCHES)	TEE, PLUG	90 BEND	45 BEND	22.5 BEND	11.25 BEND
6	50.5	71.4	38.6	19.7	9.9
8	89.9	126.9	68.7	35.0	17.6
10	140.2	198.3	107.3	54.7	27.5
12	202.0	292.0	154.6	78.9	39.6
14	REST. JT.	REST. JT.	210.4	107.3	53.9
16	REST. JT.	REST. JT.	REST. JT.	140.1	70.4
18	REST. JT.	REST. JT.	REST. JT.	177.3	89.1
20	REST. JT.	REST. JT.	REST. JT.	REST. JT.	110.0
24	REST. JT.	REST. JT.	REST. JT.	REST. JT.	158.4

NOTES:

1. ALL BENDS WITHOUT RESTRAINED JOINTS SHALL HAVE CONCRETE THRUST BLOCKS INSTALLED FOR RESTRAINT.
2. MEGA LUGS MAY BE USED ONLY IN CONJUNCTION WITH CONCRETE THRUST BLOCKING.
3. BEARING MUST BE AGAINST UNDISTURBED SOIL.
4. DO NOT COVER JOINTS OR BOLTS (WHERE APPLICABLE) WITH CONCRETE.

LS




**LEE'S SUMMIT**  
MISSOURI  
PUBLIC WORKS ENGINEERING DIVISION | 220 SE GREEN STREET | LEE'S SUMMIT, MO 64063

VERTICAL THRUST BLOCKS


Date: 02/13  
Drawn By: JN  
Checked By: DL  
FILE: WAT-2  
Rev: 1/14  
Rev:



DWG: F:\2020\0001-0500\020-0103\40-Design\AutoCAD\Final Plans\Sheets\GNCA\CONSTRUCTION DOCUMENTS\CDT\01\_0200103.dwg USER: bkimnich  
DATE: Dec 01, 2021 7:39am XREFS: C:\LS\_XBASE\_80330 C:\LS\_PBASE\_80330 C:\LS\_PSURF\_80330 C:\LS\_PBASE\_81023 C:\LS\_PBASE\_80330 C:\PTBLK\_0200103



**NON-SETBACK CURB INLET**  
NOT TO SCALE



**Section 2721**

**Engineered Surface Drainage Products**

**GENERAL**

PVC surface drainage inlets shall include the drain basin type as indicated on the contract drawing and referenced within the contract specifications. The ductile iron grates for each of these fittings are to be considered an integral part of the surface drainage inlet and shall be furnished by the same manufacturer. The surface drainage inlets shall be as manufactured by Nyloplast a division of Advanced Drainage Systems, Inc., or prior approved equal.


**MATERIALS**

The drain basins required for this contract shall be manufactured from PVC pipe stock, utilizing a thermoforming process to reform the pipe stock to the specified configuration. The drainage pipe connection stubs shall be manufactured from PVC pipe stock and formed to provide a watertight connection with the specified pipe system. This joint tightness shall conform to ASTM D3212 for joints for drain and sewer plastic pipe using flexible elastomeric seals. The flexible elastomeric seals shall conform to ASTM F477. The pipe bell spigot shall be joined to the main body of the drain basin or catch basin. The raw material used to manufacture the pipe stock that is used to manufacture the main body and pipe stubs of the surface drainage inlets shall conform to ASTM D1784 cell class 12454.

The grates and frames furnished for all surface drainage inlets shall be ductile iron for sizes 8", 10", 12", 15", 18", 24" and 30" and shall be made specifically for each basin so as to provide a round bottom flange that closely matches the diameter of the surface drainage inlet. Grates for drain basins shall be capable of supporting various wheel loads as specified by Nyloplast. 12" and 15" square grates will be hinged to the frame using pins. Ductile iron used in the manufacture of the castings shall conform to ASTM A536 grade 70-50-05. Grates and covers shall be provided painted black.

**INSTALLATION**

The specified PVC surface drainage inlet shall be installed using conventional flexible pipe backfill materials and procedures. The backfill material shall be crushed stone or other granular material meeting the requirements of class 1 or class 2 material as defined in ASTM D2321. Bedding and backfill for surface drainage inlets shall be well placed and compacted uniformly in accordance with ASTM D2321. The drain basin body will be cut at the time of the final grade. No brick, stone or concrete block will be required to set the grate to the final grade height. For load rated installations, a concrete slab shall be poured under and around the grate and frame. The concrete slab must be designed taking into consideration local soil conditions, traffic loading, and other applicable design factors. For other installation considerations such as migration of fines, ground water, and soft foundations refer to ASTM D2321 guidelines.



**LEE'S SUMMIT MIDDLE SCHOOL #4**  
LEE'S SUMMIT R-7 SCHOOL DISTRICT  
1001 SE BAILEY ROAD  
LEE'S SUMMIT, MO 64081

PACKAGE 2-  
STRUCTURAL & SITE  
UTILITIES  
ISSUED FOR PERMIT  
08/28/20

13-20102-00


STANDARD  
DETAILS

**C1056**


**DLR Group**  
© DLR Group  
80320 DLR Group, Inc. a Missouri corporation,  
Missouri State Certificate of Authority #00039



**olsson**  
OLSSON, CIVIL ENGINEERING  
MISSOURI CERTIFICATE OF AUTHORITY #001992  
7301 West 133rd Street, Suite 200  
Overland Park, KS 66211-4750  
TEL 913.381.1170  
www.olson.com



## PLANVIEW




SECTION A-A



## END SECTION NOTES

1. GRATE COVER DETAIL SHALL BE ADJUSTED AS NECESSARY TO FIT END SECTION PROVIDED.
2. MAXIMUM OPENING THRU END SECTION SHALL BE NO GREATER THAN 6". ADJUST DETAIL AS NECESSARY.
3. ALL METAL SURFACES SHALL BE HOT DIP ZINC COATED IN ACCORDANCE WITH ASTM A-123.
4. USE CITY APPROVED CONCRETE THROUGHOUT.
5. ALL CONCRETE AND MATERIALS USED IN THIS WORK SHALL MEET THE REQUIREMENTS OF THE GOVERNING BODY.
6. REINFORCING STEEL SHALL BE NEW BILLET, MINIMUM GRADE 40 AS PER ASTM A615, AND SHALL BE BENT COLD.
7. ALL DIMENSIONS RELATIVE TO REINFORCING STEEL ARE TO CENTERLINE OF BARS. 2" CLEARANCE SHALL BE PROVIDED THROUGHOUT UNLESS NOTED OTHERWISE. TOLERANCE OF  $\pm 1/8"$  SHALL BE PERMITTED.
8. ALL LAP SPLICES NOT SHOWN SHALL BE A MINIMUM OF 40 BAR DIAMETERS IN LENGTH.
9. ALL DOWELS SHALL BE ACCURATELY PLACED AND SECURELY TIED IN PLACE PRIOR TO PLACEMENT OF BOTTOM SLAB CONCRETE. STICKING OF DOWELS INTO FRESH OR PARTIALLY HARDENED CONCRETE WILL NOT BE ACCEPTABLE.
10. ALL REINFORCING STEEL SHALL BE SUPPORTED ON FABRICATED STEEL BAR SUPPORTS @ 3'-0" MAXIMUM SPACING.
11. DO NOT SCALE THESE DRAWINGS FOR DIMENSIONS OR CLEARANCES. ANY QUESTIONS REGARDING DIMENSIONS SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO CONSTRUCTION.


**END SECTION TOE WALL WITH GRATE**  
NOT TO SCALE



### PROFILE VIEW



PROFILE VIEW

SECTION A-A  
CONTROL STRUCTURE EDD-1  
(STRUCTURE B3)





CONTROL STRUCTURE EDD-2  
(STRUCTURE D2)







CONTROL STRUCTURE EDD-3 (STRUCTURE J2)








- LEGEND**
- PROPERTY LINE
  - - - - - EXISTING MAJOR CONTOUR
  - - - - - EXISTING MINOR CONTOUR
  - - - - - PROPOSED MAJOR CONTOUR
  - - - - - PROPOSED MINOR CONTOUR


**CONTRACTOR NOTE:**

ALL TEMPORARY SILTATION BASINS, SEDIMENT BASINS AND DETENTION BASINS MUST BE CONSTRUCTED PRIOR TO ANY OTHER IMPROVMENTS.

HEC-14 RIPRAP APRON SIZING FOR OUTFALL B-1									
	D50	Q	D	TW	TW/D	APRON LENGTH	APRON DEPTH	Width at	
	(in)	ft <sup>3</sup> /s	ft	ft	0.4 Min 3.0 Max	Scale from Table 10.3.1	Scale x D (ft)	Scale from Table 10.3.1	End of Apron (ft)
Required	2.2	9.9	2	0.91	0.455	4	8	3.3	19.8
Design	6						24		12


ADDED  
SHEET





CONTRACTOR NOTE:

ALL TEMPORARY SILTATION BASINS, SEDIMENT BASINS AND DETENTION BASINS MUST BE CONSTRUCTED PRIOR TO ANY OTHER IMPROVMENTS.




Q = 37.8 CFS  
DEPTH = 0.30 FT  
V = 2.2 FPS

EDD-2  
EMERGENCY SPILLWAY DETAIL

HEC-14 RIPRAP APRON SIZING FOR OUTFALL D-1									
	D50	Q	D	TW	TW/D	APRON LENGTH	APRON DEPTH	Width at	
	(in)	ft <sup>3</sup> /s	ft	ft	0.4 Min 1.0 Max	Scale from Table 10.1	Scale from Table 10.1	Scale from Table 10.1	End of Apron (ft)
Required	3.4	24.1	2	1.95	0.975	4	8	3.3	19.8
Design	6						19	24	11.4

ADDED  
SHEET



- LEGEND
- PROPERTY LINE
  - - - 995 EXISTING MAJOR CONTOUR
  - - - 995 EXISTING MINOR CONTOUR
  - 998 PROPOSED MAJOR CONTOUR
  - 998 PROPOSED MINOR CONTOUR

LEE'S SUMMIT MIDDLE SCHOOL #4  
LEE'S SUMMIT R-7 SCHOOL DISTRICT


PACKAGE 2-  
STRUCTURAL & SITE  
UTILITIES  
ISSUED FOR PERMIT  
08/28/20

PR002R 12.18.20


13-20102-00

DETENTION BASIN  
DETAIL

C1060




© DLR Group  
8020 DLR Group, Inc. a Missouri corporation,  
Missouri State Certificate of Authority #00939



OLSSON, CIVIL ENGINEERING  
MO. CERTIFICATE OF AUTHORITY #001592  
7301 West 133rd Street, Suite 200  
Overland Park, KS 66213-4750  
TEL 913.381.1170  
www.olsson.com

CONTRACTOR NOTE:


ALL TEMPORARY SILTATION BASINS, SEDIMENT BASINS  
AND DETENTION BASINS MUST BE CONSTRUCTED PRIOR  
TO ANY OTHER IMPROVMENTS.



EDD-3  
EMERGENCY SPILLWAY DETAIL

- LEGEND
- PROPERTY LINE
  - EXISTING MAJOR CONTOUR
  - EXISTING MINOR CONTOUR
  - PROPOSED MAJOR CONTOUR
  - PROPOSED MINOR CONTOUR

ADDED  
SHEET



HEC-14 RIPRAP APRON SIZING FOR OUTFALL J-1									
	D50	Q	D	TW	TW/D	APRON LENGTH	APRON DEPTH	Width at	
	(in)	ft <sup>3</sup> /s	ft	ft	0.4 Min 3.0 Max	Scale from Table 10.1	Scale x D	Scale from Table 10.1	End of Apron (ft)
Required	4.5	63	3.5	2.48	0.708571	4	14	3.3	29.7
Design	9					28		30	20

