GENERAL NOTES:

1 ~ ALL CONSTRUCTION SHALL CONFORM TO THE CITY OF LEE'S SUMMIT DESIGN AND CONSTRUCTION MANUAL AS ADOPTED BY ORDINANCE 5813. 2 ~ ALL REQUIRED EASEMENTS WITHIN THE BOUNDARY OF THIS PROJECT SHALL BE PROVIDED FOR ON THE FINAL PLAT.

3 ~ ANY REQUIRED EASEMENT LOCATED OUTSIDE OF THE BOUNDARY OF THIS PROJECT SHALL BE PROVIDED FOR BY SEPARATE

INSTRUMENT PRIOR TO ISSUANCE OF CONSTRUCTION PERMITS. 4 ~ THE CONTRACTOR SHALL CONTACT THE CITY'S DEVELOPMENT SERVICES ENGINEERING INSPECTION TO SCHEDULE A

PRE-CONSTRUCTION MEETING WITH A FIELD ENGINEERING INSPECTOR PRIOR TO ANY LAND DISTURBANCE WORK AT (816) 969-1200. 5 ~ THE CONTRACTOR SHALL NOTIFY ENGINEERING SOLUTIONS AT 816.623.9888 OF ANY CONFLICT WITH THE IMPROVEMENTS PROPOSED BY

THESE PLANS AND SITE CONDITIONS. 6 ~ THE CONTRACTOR SHALL NOTIFY THE CITY ENGINEER AND OBTAIN THE APPROPRIATE BLASTING PERMITS FOR A REQUIRED BLASTING. IF BLASTING IS ALLOWED, ALL BLASTING SHALL CONFORM TO STATE REGULATIONS AND LOCAL ORDINANCES.

UTILITY COMPANIES:

THE FOLLOWING LIST OF UTILITY COMPANIES IS PROVIDED FOR INFORMATION ONLY. WE DO NOT OFFER ANY GUARANTEE OR WARRANTY THAT THIS LIST IS COMPLETE OR ACCURATE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONTACTING ALL UTILITY COMPANIES THAT MAY BE AFFECTED BY THE PROPOSED CONSTRUCTION AND VERIFYING THE ACTUAL LOCATION OF EACH UTILITY LINE. THE CONTRACTOR SHALL NOTIFY ENGINEERING SOLUTIONS AT 816.623.9888 OF ANY CONFLICT WITH PROPOSED IMPROVEMENTS.

EVERGY ~ 298-1196

MISSOURI GAS ENERGY ~ 756-5261 SOUTHWESTERN BELL TELEPHONE ~ 761-5011

COMCAST CABLE ~ 795-1100

WILLIAMS PIPELINE ~ 422-6300

CITY OF LEE'S SUMMIT PUBLIC WORKS ~ 969-1800 CITY OF LEE'S SUMMIT DEVELOPMENT ENGINEERING INSPECTION AT 816,969,1200

CITY OF LEE'S SUMMIT WATER UTILITIES ~ 969-1900 MISSOURI ONE CALL (DIG RITE) ~ 1-800-344-7483

<u>DEVELOPER:</u> Sarah Borisky

RENOURISH LLC

102 SW 2ND ST LEES SUMMIT, MO 64063 PHONE: (816) 524-5432

PROPERTY DESCRIPTION

LOT 5, UNRECORDED PLAT OF LOTS 4-9, PALMER ADDITION

LEE'S SUMMIT, JACKSON COUNTY, MISSOURI

OIL - GAS WELLS ACCORDING TO EDWARD ALTON MAY JR'S ENVIRONMENTAL IMPACT STUDY

OF ABANDONED OIL AND GAS WELLS IN LEE'S SUMMIT, MISSOURI IN 1995, THERE ARE NOT OIL AND GAS WELLS WITHIN 185 FEET OF THE PROPERTY AS SURVEYED HEREON.

FLOOD INFORMATION:

THE SUBJECT PROPERTY SURVEYED LIES WITHIN A FLOOD ZONE DESIGNATED ZONE (X), AREAS LOCATED OUTSIDE THE 100 YEAR FLOOD PLAIN, PER F.E.M.A. MAP, COMMUNITY PANEL NO. 29095C0417G EFFECTIVE DATE: JANUARY 20, 2017

Current Zoning: TNZ - Transitional Neighborhood Zone

Proposed Zoning: TNZ - Transitional Neighborhood Zone

Sanitary Sewer Service ExistingSanitary Sewer service from south of property.

Water Service


Existing Service from south of property.

 $\frac{\text{Storm Sewer}}{N/A}$

orcel Address: SW MARKET S LEES SUMMIT MO 64063 Zoned: RP-2 Owner Information; CORN GORDON W & GLENNA M TR 1504 W 1ST ST LEES SUMMIT MO 64081 Porcel Address: 108 SW MARKET ST LEES SUMMIT MO 64063 Zoned: RP-2 Owner Information: CORN GORDON W & GLENNA M TRUSTEE 1504 W 1ST ST LEES SUMMIT MO 64081 arcel Address: SW MARKET ST LEES SUMMT MO 64063 Zoned: RP-2 Owner Information: DANELLA ANDY D & GLEND PO BOX 153 LEES SUMMIT NO 6406 EXISTING BUILDING Porcel Address: 110 SW 2ND ST UNIT LEES SUMMIT MO 64063 Zoned: TNZ Owner Information: BJS PROPERTY LLC 120 SW 2ND ST STE 105 LEES SUMMIT MO 64063 Owner Information: RAYSIK PATRICIA S 200 SW MARKET .EES SUMMIT MO 6406. /cel Address: SW MARKET 7 LEES SUMMT MO 64063 Zoned: CP-Owner Information: HOORFAR JAMSHID-TRUST 440 NE BROCKTON DR LEES SUMMIT MO 64064 MO 64063 Zoned: CP Owner Information: CITY OF LEES SUMMIT PO BOX 1600 LEES SUMMIT MO 64063

SITE LOCATION MAP SCALE" 1"=50'

RENOURISH FINAL DEVELOPMENT PLAN Section 6, Township 47 North, Range 31 West LEE'S SUMMIT, JACKSON COUNTY, MISSOURI



Vicinity Map LOCATION MAP SECTION 6-T47N-R31W Not to Scale

Summary of Quantities:

ITEM AND DESCRIPTION	UNIT	ESTIMATED QUANTITY
ASPHALT PAVING	S.Y.	70.00
CURBING	FT	141.00
MoDOT Type 5 Base	S.Y.	110.00
GEOGRID	S.Y.	110.00
CONCRETE PAVING	S.Y.	18.00
5' SIDEWALK	S.F.	215.00
RETAINING WALL	SFF	30.00
SILT FENCE	FT	350.00
SEEDING / MULCHING/ FERTILIZING	AC	0.14

ALL PAVING ON THE PARKING LOT WILL COMPLY WITH THE UNIFIED DEVELOPMENT ORDINANCE ARTICLE 8 IN TERMS OF PAVING THICKNESS AND BASE

Land	Use	<u>Schedule</u>	

- a. Total floor area
- b. Number of dwelling units c. Land area
- d. Number of required and
- proposed parking spaces Impervious coverage e
- Parking/Sidewalk Building

f. Floor Area Ratio (FAR)

765 sq. ft. 1,218 sq. ft. 1,983 sq. ft. (32% of Site) 19.7%

N/A

Office

1,218 sq. ft.

6,178 sq. ft. 0.14 acres

1 Standard / 1 Handicap

1 Standard / 1 Handicap

N/A

- Dwelling units per acre, with and without common area;
- h. The range of land uses to be permitted in each designated area of the development.
- **INDEX OF SHEETS:** C.001 ~ COVER SHEET C.050 ~ ESC PHASE 1 - Pre Clearing Plan C.051 ~ ESC PHASE 2 - Inactive Area Stabilization Plan C.052 ~ ESC PHASE 3 - Final Restoration Plan C.053 ~ ESC - Standard Details C.100 ~ SITE PLAN C.200 ~ GRADING PLAN

C.600 ~ STANDARD DETAILS

L.100 ~ LANDSCAPE PLAN

LEGEND:

- B/L BUILDING SET-BACK C/A – COMMON AREA D/E – DRAINAGE EASEMENT FND. – FOUND L/E – LANDSCAPE EASEMENT L.N.A. - LIMITS OF NO ACCESS R/W – RIGHT OF WAY
- SANITARY SEWER LINE SAN
- S/W SIDEWALK U/E – UTILITY EASEMENT
- W WATER LINE
- ST STORM SEWER LINE

ENGINEER'S CERTIFICATION:

I HEREBY CERTIFY THAT THIS PROJECT HAS BEEN DESIGNED AND THESE PLANS PREPARED IN ACCORDANCE WITH THE CURRENT DESIGN CRITERIA OF THE CITY OF LEE'S SUMMIT, MISSOURI AND THE STATE OF MISSOURI. I FURTHER CERTIFY THAT THESE PLANS WERE DESIGNED IN ACCORDANCE TO AASHTO STANDARDS.


:N F	MATTHENJ SCHUCHT NUMBER B SS / ONAL ENG MATTHENJ SS / ONAL ENG SS / ONAL ENG
IN	Matthew J. Schlicht MO PE 2006019708 KS PE 19071 OK PE 25226 <u>NE PE E-1433</u> 5
	REVISIONS
REVISED SHEET NUMBERS.	An REV. 3/21/2022 An REV. 4/13/2022 REV. 4/13/2022 An





RELEASED FOR CONSTRUCTION As Noted on Plans Review

nent Services Depart Lee's Summit, Missouri 04/21/2022

C.001







EROSION CONTROL DESCRIPTION1.)SILT FENCE SHALL BE PLACE AT THESHALL BE PLACEDSURROUNDING ALL 2.) INSTALL TEMPORARY CONSTRUCTION

EROSION CONTROL PROCEDURE 1.) SILT FENCE AND TEMPORARY CONST OPERATIONS. THE CONTRACTOR SHALL INST

MAINTENANCE: TO MAINTAIN THE EROSION AND SEDIMENT CO SEDIMENT CAPTURE DEVICES: SEDIM SEDIMENT REACHES ABOUT ONE-THIR STORM SEWER INLETS: ANY SEDIME TEMPORARY CONTROLS: ALL TEMPO

INSPECTION PROCEDURES:

INSPECTIONS WILL BE DONE BY THE RESPON AREAS THAT HAVE BEEN RESEEDED WILL BE HAVE NOT BEEN FINALLY STABILIZED SHALL STORM WATER LEAVES THE SITE SHALL BE I AND CORRECTED WITHIN SEVEN CALENDAR MAINTENANCE OF POLLUTION CONTROL DEV

IF THE EXISTING GROUND COVER IS NATURA PERMANENT SEEDING SHALL CONSIST OF 90. SQUARE FEET. BOTH TEMPORARY AND PERM GRASS. NEW GRASS SHALL BE WATERED AN

ALL EROSION CONTROL DEVICES SHALL BE I

THE DEVELOPER WILL DESIGNATE A QUALIFI STABILIZATION MEASURES: DISTUR

ONCE EVERY MONTH THROUGHOUT FOR STABILIZATION MEASURES. STRUCTURAL CONTROLS: FILTER F, PROPER POSITIONING, ANCHORING, A FROPER POSITIONING, ANCHORING, F FABRIC. CONTRACTOR CAN CONTAC DISCHARGE POINTS: DISCHARGE PO SIGNIFICANT AMOUNTS OF POLLUTAI CONSTRUCTION ENTRANCE: LOCAT

A LOG OF EACH INSPECTION SHALL BE KEPT. OBSERVATIONS RELATIVE TO THE EFFECTIVE LAND DISTURBANCE OPERATIONS HAVE PERM THE INSPECTION IF DULY AUTHORIZED TO DO

Image: Signed State of Construction Image: State of Construction <td>Professional Registration Brise Summit, Mo 64082 Professional Rest Professional Rest Profesional Rest Professional Rest</td>	Professional Registration Brise Summit, Mo 64082 Professional Rest Professional Rest Profesional Rest Professional Rest
EROSION AND SILTATION. NOTES: The Land Disturbance Plans indicates the Final placement of erosion control devices. The contractor(s) may proceed with construction prior to the final placement of these devices by providing additional devices to control erosion on their items of work.	Kansas Engineering E-1695 Surveying LS-218 Oklahoma Engineering 6254 Nebraska Engineering CA2821
These devices shall be maintained until the final devices are in place. RELEASED FOR CONSTRUCTION As Noted on Plans Review Development Services Department Lee's Summit, Missouri 04/21/2022	102 SW 2ND STREET Lee's Summit, Jackson County, Missouri
ON ENTRANCE AS SHOWN ON PLAN E: STRUCTION ENTRANCE SHALL BE INSTALLED AT THE PERIMETER OF THE GRADED AREAS PRIOR TO BEGINNING OF CLEARING OR DEMOLITION STALL SILT FENCE AS SHOWN ON PLANS AS GRADING PROGRESSES.	Project: 102 SW 2ND STREET, LSMO LSMO Issue Date: February 3, 2022
CONTROLS, THE FOLLOWING PROCEDURES WILL BE PERFORMED: DMENT WILL BE REMOVED FROM THE UPSTREAM OR UPSLOPE SIDE OF THE FILTER FABRIC FENCES, WHEN THE DEPTH OF ACCUMULATED THRD THE HEIGHT OF THE STRUCTURE. MENT IN THE STORM SEWER INLETS WILL BE REMOVED AND DISPOSED OF PROPERLY.	ESC PHASE 2 Inactive Area Stabilization Plan Construction Plans for: RENOURISH Lee's Summit, Jackson County, Missouri
MPORARY CONTROLS WILL BE REMOVED AFTER THE DISTURBED AREAS HAVE BEEN STABILIZED. DNSIBLE PERSON(S) AT LEAST ONCE EVERY WEEK AND WITHIN 24 HOURS EACH STORM EVENT PRODUCING ANY AMOUNT OF RAINFALL. DE INSPECTED REGULARLY AFTER SEED GERMINATION TO ENSURE COMPLETE COVERAGE OF EXPOSED AREAS. DISTURBED AREAS THAT L HAVE ALL POLLUTION CONTROL MEASURES INSPECTED FOR PROPER INSTALLATION, OPERATION AND MAINTENANCE. LOCATIONS WHERE INSPECTED FOR EVIDENCE OF EROSION OR SEDIMENT DEPOSITION. ANY DEFICIENCIES SHALL BE NOTED IN A REPORT OF THE INSPECTION R DAYS OF THE INSPECTION. THE PERMITTEE SHALL PROMPTLY NOTIFY THE SITE CONTRACTORS RESPONSIBLE FOR OPERATION AND EVICES OF DEFICIENCIES.	MATTHEWU SCHICHT NUMBER PECOOG019708 80 70NAL ENGINE
20% IN THREE EQUAL PARTS OF THIN BLADE, TURF-TYPE, TALL FESCUE AND 10% BLUEGRASS SEED AT A RATE OF 10 POUNDS PER 1000 RMANENT SEEDED AREAS SHALL BE MULCHED AND WATERED TO MAINTAIN THE PROPER MOISTURE LEVEL OF THE SOIL TO ESTABLISH ND MAINTAINED UNTIL IT REACHES A HEIGHT OF 3 INCHES. ANY BARE AREAS SHALL BE RESEEDED. FIED PERSON OR PERSONS TO PERFORM THE FOLLOWING INSPECTIONS: URBED AREAS AND AREAS USED FOR STORAGE OF MATERIALS THAT ARE EXPOSED TO PRECIPITATION WILL BE INSPECTED FOR EVIDENCE OF, NTS ENTERING THE DRAINAGE SYSTEM. AFTER A PORTION OF THE SITE IS FINALLY STABILIZED, INSPECTIONS WILL BE CONDUCTED AT LEAST IT THE LIFE OF THE PROJECT. CONTRACTOR CAN CONTACT ENGINEERING SOLUTIONS FOR COPIES OF THE INSPECTION FORM TO BE USED R FABRIC FENCES AND ALL OTHER EROSION AND SEDIMENT CONTROL MEASURES IDENTIFIED IN THE PLAN WILL BE INSPECTED REGULARLY FOR	Matthew J. Schlicht MO PE 2006019708 KS PE 19071 OK PE 25226 <u>NE PE E-14335</u> REVISIONS <u>A</u> REV. 3/21/2022 <u>A</u> REV. 4/13/2022
G, AND EFFECTIVENESS IN TRAPPING SEDIMENTS. SEDIMENT WILL BE REMOVED FROM THE UPSTREAM OR UPSLOPE SIDE OF THE FILTER ACT ENGINEERING SOLUTIONS FOR COPIES OF THE INSPECTION FORM TO BE USED FOR STABILIZATION MEASURES. POINTS OR LOCATIONS WILL BE INSPECTED TO DETERMINE WHETHER EROSION CONTROL MEASURES ARE EFFECTIVE IN PREVENTING TANTS FROM ENTERING RECEIVING WATERS. PATIONS WHERE VEHICLES ENTER OR EXIT THE SITE WILL BE INSPECTED FOR EVIDENCE OF OFF-SITE SEDIMENT TRACKING. PT. THE INSPECTION REPORT IS TO INCLUDE THE FOLLOWING MINIMUM INFORMATION: INSPECTOR'S NAME, DATE OF INSPECTION, VENESS OF THE POLLUTION CONTROL DEVICES, ACTIONS TAKEN OR NECESSARY TO CORRECT DEFICIENCIES, AND LISTING OF AREAS WHERE RMANENTLY OR TEMPORARILY STOPPED. THE INSPECTION REPORT SHALL BE SIGNED BY THE PERMITTEE OR BY THE PERSON PERFORMING DO SO.	 C.051



Mix I – Rye Grass / Blue Grass –––––

Lime

SEED AND MULCH NOTES: PHASE FINAL All areas disturbed by construction activities shall be seeded and mulched. Seeding shall be done before the proposed seedbed becomes eroded, crusted over, or SCALE: 1" = 10' dried out and shall not be done when the ground is frozen, or covered with snow. The seed shall comply with the requirements of the Missouri Seed Law and the Federal Seed Act. Also, it shall contain no seed of any plant on the Federal Noxious Weed List. Other weed seeds shall not exceed one percent by weight of mix SILT FENCE PROTECTION TO BE MAINTAINED BY CONTRACTOR Seed and Fertilizer Rate: 100 lbs. per Acre Mix II – Tall Fescue / Blue Grass ––––– 195 LEGEND lbs. per Acre Lime -----²⁰⁰⁰PHASE 1 SILT FENCE lbs per Acre (50 lbs. per 1000 sq. fl.) _____SF_1____SF_1____ Fertilizer PHASE 2 SILT FENCE -----800 to 1200 lbs per Acre (25 lbs per 1000 sq. ft.) INLET PROTECTION DURING ALL PHASES OF CONSTRUCTION, INACTIVE AREA STABILIZATION METHODS AS DESCRIBED IN APWA SECTION 5111.3 SHALL BE USED TO CONTROL EROSION AND SILTATION. Seed – 50% of the specified quantity Mulch – 100% of the specified quantity NOTES: The Land Disturbance Plans indicates the Final placement of erosion control devices. The contractor(s) may proceed with construction prior to the final

During the dates December 15th through May 31 ALL lime fertilizer, seed and mulch shall be applied to finished slopes of disturbed areas. During the months of June, July, October and November 1st through December 15th, lime fertilizer, seed and mulch shall be applied at the following rates: Lime - 100% of specified quantity Fertilizer – 75% of the specified quantity

Mulch shall be Vegetative type, cereal straw from stalks of oats, rye, or barley, or approved equal. The straw shall be free of prohibited weed seed and relatively free of all other noxious and undesirable seed. Mulch shall be applied at the rate of 2 tons per acre, (70 to 90 lbs per 1000 sq. ft.). Mulch shall be embedded by a mulch anchoring tool or disk type roller having flat serrated disks spaced not more than 10 inches apart and cleaning scrapers shall be provided

ONCE SITE IS 90% VEGETATED ALL ESC DEVICES SHALL BE REMOVED AND ANY DISTURBED AREAS SHALL BE RESTORED


placement of these devices by providing additional devices to control erosion on their items of work. These devices shall be maintained until the final devices are in place.


RELEASED FOR **CONSTRUCTION** As Noted on Plans Review lopment Services Departme Lee's Summit, Missouri 04/21/2022

C **IGINEER** (OITU) LEE (816) ٦ 10 Professional Registration Missouri Engineering 2005002186-D Surveying 2005008319-D Kansas Engineering E-1695 Surveying LS-218 Oklahoma Engineering 6254 Nebraska Engineering CA2821 STREET n County, 2ND SW t, Ja 102 Project: 102 SW LSMO Issue Da E 3 - Final Restoration Construction Plans for: RENOURISH ummit, Jackson County, Misso nty, PHASE Ñ ູທ Ð \bigcirc \mathcal{O} Motthew J. Schlicht MO PE 2006019708 KS PE 19071 OK PE 25226 <u>NE PE E-1433</u>5 REVISIONS A REV. 3/21/2022 A REV. 4/13/2022

C.052

.








ENGINEERING & SURVEYING ENGINEERING & SURVEYING ENGINEERING & SURVEYING 50 SE 30TH STREET LEE'S SUMMIT, MO 64082 P:(816) 623-9888 F:(816)623-9849	
Professional Registration Missouri Engineering 2005002186-D Surveying 2005008319-D Kansas Engineering E-1695 Surveying LS-218 Oklahoma Engineering 6254 Nebraska Engineering CA2821	
102 SW 2ND STREET Lee's Summit, Jackson County, Missouri	
Project: 102 SW 2ND STREET, LSMO Issue Date: February 3, 2022	
ESC - Standard Details Construction Plans for: RENOURISH Lee's Summit, Jackson County, Missouri	
Matthew J. Schlicht MO PE 2006019708 KS PE 19071 OK PE 25226 NE PE E-14335 REVISIONS REV. 3/21/2022 REV. 4/13/2022	
C.053	


RELEASED FOR CONSTRUCTION As Noted on Plans Review

Development Services Departm Lee's Summit, Missouri 04/21/2022










C.200

North




) JSE PATH) BASE	
EWALK) ARED–USE PATH) SE STABLE 1	
Date: 05/2021 Drawn By: MJF Checked By: DL GEN-2	
<u> </u>	


-1.5" ASPHALTIC CONCRETE SURFACE APWA TYPE 3-01 ASPHALT CONCRETE BASE

(MoDOT Type 5 aggregate or equivalent) Extend Geo-Grid and Base Rock to 1 foot

-1.5" ASPHALTIC CONCRETE SURFACE APWA TYPE 3-01

RELEASED FOR CONSTRUCTION As Noted on Plans Review nent Services Departm Lee's Summit, Missouri 04/21/2022





GENERAL LANDSCAPE NOTES:

PLANT MATERIAL

1. ALL PLANT MATERIAL SHALL BE FIRST CLASS REPRESENTATIVES OF SPECIFIED SPECIES, VARIETY OR CULTIVAR, IN HEALTHY CONDITION WITH NORMAL WELL DEVELOPED BRANCHES AND ROOT PATTERNS. PLANT MATERIAL MUST BE FREE OF OBJECTIONABLE FEATURES. PLANTS SHALL COMPLY IN ALL APPLICABLE RESPECTS WITH PROPER STANDARDS AS SET FORTH IN THE AMERICAN ASSOCIATION OF NURSERYMEN'S "AMERICAN STANDARD OF NURSERY STOCK", ANSI Z60.1-2004.

 SHRUBS SHALL BE CONTAINER GROWN AND WILL BE FREE OF DISEASE AND PESTS. NO BARE ROOT. ALL PLANT BEDS TO BE MULCHED TO A DEPTH OF 3" WITH DARK BROWN, HARDWOOD MULCH. PLANTING BEDS ARE TO BE FREE OF WEEDS AND GRASS. TREAT BEDS WITH A PRE-EMERGENT HERBICIDE PRIOR TO PLANTING AND MULCH PLACEMENT. APPLY IN ACCORDANCE WITH STANDARD TRADE PRACTICE.
 HOLE AREA FOR TREE TO BE TWICE (2x) THE DIAMETER OF THE ROOT BALL AND ROOT BALL SHALL BE SLIGHTLY MOUNDED FOR WATER RUN-OFF.

4. ALL PLANT MATERIALS SHALL BE PROTECTED FROM THE DRYING ACTION OF THE SUN AND WIND AFTER BEING DUG, WHILE BEING TRANSPORTED, AND WHILE AWAITING PLANTING. BALLS OF PLANTS WHICH CANNOT BE PLANTED IMMEDIATELY SHALL BE PROTECTED FROM DRYING ACTION BY COVERING THEM WITH MOIST MULCH. PERIODICALLY, APPLY WATER TO MULCH-COVERED BALLS TO KEEP MOIST. IF PLANTING SHOULD OCCUR DURING GROWING SEASON, APPLY ANTI-DESICCANT TO LEAVES BEFORE TRANSPORT TO REDUCE THE LIKELIHOOD OF WINDBURN. REAPPLY ANTI-DESICCANT AFTER PLANTING TO REDUCE TRANSPIRATION. REMOVE TWINE AND BURLAP FROM ROOT BALLS. SOIL ON TOP OF CONTAINERIZED OR BALLED PLANTS IS TO BE REMOVED UNTIL ALL PLANTS' ROOT FLARES ARE EXPOSED. THIS IS THE NATIVESOIL LINE AT WHICH PLANTING DEPTHS SHOULD BE MEASURED. 5. AFTER PLANTING IS COMPLETED, PRUNE MINIMALLY TO REMOVE DEAD OR INJURED TWIGS AND BRANCHES. PRUNE IN SUCH A MANNER AS NOT TO CHANGE THE NATURAL HABIT OR SHAPE OF THE PLANT. MAKE CUTS BACK TO BRANCH COLLAR, NOT FLUSH. DO NOT PAINT ANY CUTS WITH WITH TREE PAINT. CENTRAL LEADERS SHALL NOT BE REMOVED.

6. GUARANTEE TREES, SHRUBS, GROUND COVER PLANTS FOR ONE CALENDAR YEAR FOLLOWING PROVISIONAL ACCEPTANCE OF THE OVERALL PROJECT. DURING THE GUARANTEE PERIOD, PLANTS THAT DIE DUE TO NATURAL CAUSES OR THAT ARE UNHEALTHY OR UNSIGHTLY IN CONDITION, SHALL BE REPLACED BY THE CONTRACTOR.

LAWN AND TURF AREAS

7. ALL LAWN AREAS TO BE SODDED OR SEEDED AS SHOWN ON PLANS. SOD SHALL COMPLY WITH US DEPT. OF AGRICULTURE RULES AND REGULATIONS UNDER THE FEDERAL SEED ACT AND EQUAL IN QUALITY TO STANDARDS FOR CERTIFIED SEED. SOD SHALL BE HEALTHY, THICK TURF HAVING UNDERGONE A PROGRAM OF REGULAR FERTILIZING, MOWING AND WEED CONTROL. SEED AND SOD SHALL BE A TURF-TYPE TALL FESCUE (3 WAY) BLEND. SEED BLEND SHALL CONSIST OF THE FOLLOWING: TURF-TYPE TALL FESCUE

TURF-TYPE TALL FESCUE KENTUCKY BLUEGRASS

8. ALL SEEDED AREAS ARE TO BE MULCHED WITH STRAW OR HYDROMULCH AT TIME OF INSTALLATION UNTIL SEED HAS ESTABLISHED.

INSTALLATION

9. THE INSTALLATION OF ALL PLANT MATERIALS SHALL BE IN COMPLIANCE WITH THE REQUIREMENTS OF THE CITY OF LEE'S SUMMIT, MO. AND LANDSCAPE INDUSTRY STANDARDS.
10. ALL LANDSCAPE AREAS TO BE FREE OF ALL BUILDING DEBRIS AND TRASH, BACK FILLED WITH CLEAN FILL SOIL AND TOP DRESSED WITH 4" OF TOPSOIL. TOPSOIL SHALL HAVE A pH RANGE OF 5.5 TO 7 AND A 4%

- ORGANIC MATERIAL MINIMUM, ASTM D5268. 11. PLANT BEDS TO BE "MOUNDED". ALL PLANT MATERIAL, PLANT BEDS, MULCH AND DUG EDGE ARE TO BE INSTALLED PER LANDSCAPE PLANS, DETAILS, AND MANUFACTURER'S RECOMMENDATIONS. 12. REESTABLISH FINISH CRADES TO WITHIN ALLOWABLE TO FRANCES ALLOWING 3/4" FOR SOD AND 3" FOR
- REESTABLISH FINISH GRADES TO WITHIN ALLOWABLE TOLERANCES ALLOWING 3/4" FOR SOD AND 3" FOR MULCH IN PLANT BEDS. HAND RAKE ALL AREAS TO SMOOTH EVEN SURFACES FREE OF DEBRIS, CLODS, ROCKS, AND VEGETATIVE MATTER GREATER THAN 1".
 ALL PLANT BEDS, SHRUBS AND TREES SHALL BE MULCHED WITH 3" OF DARK BROWN, HARDWOOD MULCH,
- EXCEPT IF NOTED AS ROCK. DARK BROWN, HARDWOOD MULCH SHALL BE INSTALLED OVER DEWITT PRO 5 WEED CONTROL FABRIC IN PLANT BEDS ONLY. 14. CONTRACTOR IS RESPONSIBLE FOR INITIAL WATERING UPON INSTALLATION. 15. DUG EDGES ARE TO BE DUG WHERE MULCH BEDS ARE ADJACENT TO TURF AREAS. NO EDGING IS REQUIRED
- ADJACENT TO PAVEMENT OR CURB. 16. THE EXACT LOCATION OF ALL UTILITIES, STRUCTURES, AND UNDERGROUND UTILITIES SHALL BE DETERMINED AND VERIFIED ON SITE BY THE LANDSCAPE CONTRACTOR PRIOR TO INSTALLATION OF THE MATERIALS. DAMAGE TO EXISTING UTILITIES AND OR STRUCTURES SHALL BE REPLACED TO THEIR ORIGINAL CONDITION BY THE LANDSCAPE CONTRACTOR AT NO COST TO THE OWNER.
- LANDSCAPE CONTRACTOR IS RESPONSIBLE FOR OBTAINING NECESSARY PERMITS AND APPROVALS AND REQ'D INSPECTIONS BY LEGAL AUTHORITIES.
 PROVISIONS SHALL BE MADE FOR READILY ACCESSIBLE IRRIGATION WITHIN 100' MAX. OF ALL LANDSCAPED
- AREAS INCLUDING ALL PLANT BEDS, INDIVIDUAL TREES, AND TURF AREAS. ALL LAWN AREAS (AS SHOWN ON PLANS) WILL BE IRRIGATED BY AN AUTOMATIC SPRINKLER SYSTEM. THE LANDSCAPE CONTRACTOR IS RESPONSIBLE FOR THE DESIGN AND INSTALLATION OF ALL IRRIGATION COMPONENTS, SLEEVING, PIPE AND CONTROL. DESIGN DRAWINGS OF IRRIGATION SYSTEM SHALL BE SUBMITTED TO THE LANDSCAPE ARCHITECT AND OWNER FOR REVIEW AND APPROVAL PRIOR TO INSTALLATION. 19. ANY SUBSTITUTIONS OR DEVIATIONS SHALL BE REQUESTED IN WRITING BY THE CONTRACTOR FOR APPROVAL BY THE LANDSCAPE ARCHITECT PRIOR TO INSTALLATION OF PLANT MATERIALS. ALL PLANTS ARE TO
- APPROVAL BY THE LANDSCAPE ARCHITECT PRIOR TO INSTALLATION OF PLANT MATERIALS. ALL PLANTS ARE TO BE LOCATED AS SPECIFIED ON DRAWINGS. MAINTENANCE BY OWNER
- 20. ALL SHRUBS ARE TO BE MAINTAINED IN THEIR NATURAL SHAPE TO ALLOW EVENTUAL GROWTH INTO A HEDGE. 21. MAINTAIN NATURAL HABIT OF ALL SPECIFIED PLANT MATERIAL.
- 22. NEW SOD TO BE THOROUGHLY WATERED UNTIL ROOTS "TAKE HOLD" OF SOD BED. CONTINUE WATERING AS REQUIRED, UNTIL COMPLETELY ESTABISHED.

IRRIGATION PERFORMANCE SPECIFICATION:

- THE FOLLOWING CRITERIA SHALL BE CONSIDERED MINIMUM STANDARDS FOR DESIGN AND INSTALLATIONOF LANDSCAPE IRRIGATION SYSTEM:
- 1. GENERAL IRRIGATION SYSTEM TO INCLUDE DRIP IRTRIGATION OF SHRUB BEDS ADJACENT TO BUILDINGS, SPRAY HEADS IN THE PARKING ISLANDS, AND ROTORS AROUND THE PERIMETER OF THE PARKING LOTS. HEADS SHALL THROW AWAY FROM BUILDING AND ACOID SPRAYING OVER SIDEWALKS.
- 2. IRRIGATION SYSTEM SHALL CONFORM TO ALL INDUSTRY STANDARDS AND ALL FEDERAL, STATE AND LOCAL LAWS GOVERNING DESIGN AND INSTALLATION.
- 3. WATERLINE TYPW, SIZE LOCATION, PRESSURE AND FLOW SHALL BE FIELD VERIFIED PRIOR TO SYSTEM DESIGN AND INSTALLATION.
- 4. ALL MATERIALS SHALL BE FROM NEW STOCK FREE OF DEFECTS AND CARRY A MINIMUM ONE YEAR WARRANTY FROM THE DATE OF SUBSTANTIAL COMPLETION.
- 5. THE IRRIGATION SYSTEM SHALL BE DESIGNED AND INSTALLED IN SUCH A WAY THAT ALL SYSTEM COMPONENTS OPERATE WITHIN THE GUIDELINES ESTABLISHED BY THE MANUFACTURER.
- 6. LAWN AREA AND SHRUB BEDS SHALLBE ON SEPARATE CIRCUITS.
- 7. PROVIDE WATER TAP, METER SET, METER VAULT AND ALL OTHER OPERATIONS NECESSARY TO PROVIDE WATER FOR IRRIGATION SHALL CONFORM TO LOCAL WATER GOVERNING AUTHORITY CUIDELINES AND STANDARDS.
- BACKFLOW PREVENTION SHALL BE PROVIDED IN ACCORDANCE WITH STATE AND LOCAL REQULATIONS.
 IRRIGATION CONTROLLER TO BE LOCATED IN UTILITY ROOM INSIDE BUILDING. AS IDENTIFIED BY OWNER.
- IRRIGATION CONTROLLER TO BE LOCATED IN OTHER ROOM INSIDE BOILDING, AS IDENTIFIED BY OWNER.
 IRRIGATION CONTROLLER STATIONS SHALL BE LABELED TO CORRESPOND WITH THE CIRCUIT IT CONTROLS.
- 11. CONTRACTOR SHALL PROVIDE TO THE OWNER WRITTEN OPERATION INFORMATION FOR ALL SYSTEM COMPONENTS.
- 12. CONTRACTOR SHALL PROVIDE O THE OWNER ALL KEYS, ACCESS TOOLS, WRENCHES AND ADJUSTING TOOLS
- NECESSARY TO GAIN ACCESS, ADJUST AND CONTROL THE SYSTEM. 13. CONTRACTOR SHALL PROVIDE SHOP DRAWINGS TO THE OWNER FOR REVIEW AND APPROVAL PRIOR TO INSTALLATION.
- 14. AN AUTOMATIC RAIN SHUT-OFF OR MOISTURE DEVICE SHALL BE INSTALLED.
- 15. INSTALL SCHEDULE 40 PVC SLEEVES UNDER ALL CURBS, PAVING AND SIDEWALKS. SLEEVES TO BE TWICE THE SIZE OF THE LINE IT HOUSES.
- 16. INSTALL MANUAL DRAIN BALBES AT LOWEST POSSIBLE ELEVATION ON IRRIGATION MAIN TO ALLOW GRAVITY DRAINING OF MAIN DURING WINTER MONTHS. PROVIE QUICK COUPLERS AT MULTIPLE LOCATIONS TO ALLOW FOR EASY "BLOWING OUT" OF LATERAL AND MAIN LINES.
- 17. ZONES OR NOZZLES SHALL BE DESIGNED WITH MATCHED PRECIPITATION RATES.
- 18. MINIMUM LATERAL DEPTH IS 15" AND MAIN DEPTH IS 18".

19. SUBMIT DESGN DRAWING WITH BID TO ALLOW OWNER TO EVALUATE SYSTEM. INCLUDE CUT SHEETS OF ALL COMPONENTS AND ZONE TABLE ILLUSTRATING FLOWS AND ANTICIPATED PRESSURE AT FURTHEST HEAD.

20. AN "AS-BUILT" SCALED DRAWING SHALL BE PROVIDED TO THE OWNER BY THE CONTRACTOR AND SHALL INCLUDE UT NOT BE LIMITED TO THE FOLLOWING:

- a. AS CONSTRUCTED LOCATION OF ALL COMPONENTS
- b. COMPONENT NAME, MANUFACTURER, MODEL INFORMATION, SIZE AND QUANTITY
- c. PIPE SIZE AND QUANTITY
- d. INDICATION OF SPRINKLER HEAD SPRAY PATTERN
- e. CIRCUIT IDENTIFICATION SYSTEM f. DETAILED METHOD OF WINTERIZED SYSTEM

SUBMIT AS-BUILT DRAWING IN FULL SIZE DRAWING FORM AS WELL AS PDF ELECTRONIC FORMAT. (SCANNING FULL SIZE COPY OF PLAN IS ACCEPTABLE IF IT CAN BE PRINTED TO SCALE.

