

Luminaire Schedule							
Symbol	Qty	Label	Arrangement	LMF	Lum. Lumens	Lum. Watts	Part Number
	10	OSQ-4b	SINGLE	1.000	7075	130	OSQ-M-B-9L-40K7-4M-__-NM-__w/OSQ-ML-B-DA__ - OSQ-BLSMF
	8	OSQ-5Q	2 @ 180°	1.000	10250	60	OSQ-M-B-9L-40K7-5Q-__-NM-__w/OSQ-ML-B-DA__
	26	XP3	SINGLE	1.000	4270	31	XSPW-B-WM-3ME-4L-40K-__-__
	9	XP4	SINGLE	1.000	4270	31	XSPW-B-WM-4ME-4L-40K-__-__

Calculation Summary (Footcandles calculated using initial lumen values @ 25 °C)						
Label	Units	Avg	Max	Min	Avg/Min	Max/Min
CalcPts	Fc	0.61	9.3	0.0	N.A.	N.A.
Property Line	Fc	0.01	0.2	0.0	N.A.	N.A.
PAVED AREA	Fc	2.10	9.0	0.1	21.00	90.00

Pole Mount Fixture Height: 15' AFG (12' pole +3' base)

Pole Schedule
 (10) SSS-4-11-12-CW-BS-1D-C-__ (12' X 4" X 11ga STEEL SQUARE POLE)
 (8) SSS-4-11-12-CW-BS-2D18-C-__ (12' X 4" X 11ga STEEL SQUARE POLE)
 Proposed poles meet 140 MPH sustained winds.

Additional Equipment:
 (26) OSQ-ML-B-DA__ (Direct Arm Mount)

*** CUSTOMER TO VERIFY ORDERING INFORMATION AND CATALOGUE NUMBER PRIOR TO PLACING ORDER ***

