

CONSTRUCTION PLANS  
FOR  
ISPERING WOODS PO  
CITY OF LEE'S SUMMIT  
JACKSON COUNTY, MISSOURI


Sheet C1.0







\\p00004\2020\120.0484.1\CD\000SP - 120.0484 Pool Plan.dwg BARRY G. TURNER, SITE PLAN, 2/22/2020 1:17 PM, ANSI FULL BLEED 0 (34.00 X 22.00 INCHES)



- LEGEND:**  
**PROPOSED:**
- = STANDARD ASPHALT PAVEMENT (SEE DETAIL SHEET)
  - = CONCRETE POOL DECK
  - = CONCRETE SIDEWALK
  - = CURB AND GUTTER
  - = NUMBER OF PARKING STALLS

**SITE PLAN - CONSTRUCTION NOTES:**

- (A) PROPOSED ACCESSIBLE SIGNAGE AND STRIPING. SEE DETAIL SHEETS
- (B) PROPOSED PAVEMENT MARKINGS
- (C) PROPOSED CURB AND GUTTER
- (D) PROPOSED CURB RAMPS

**WHISPERING WOODS POOL**

**SITE PLAN**



Project No: 120.0484.11

Sheet C2.1

LEE'S SUMMIT, MO

**SNYDER & ASSOCIATES**  
ENGINEERS & PLANNERS, INC.

802 FRANCIS STREET  
ST. JOSEPH, MISSOURI 64501  
816-364-5222 | www.snyder-associates.com



SHAWN DUKE - ENGINEER  
MO PE#2013006489

Sheet C2.1

MARK	REVISION	DATE	BY
Engineer: SD	Checked By: SD	Scale: 1" = 10'	
Technician: JS	Date: 04-26-2022	T-R-S, 47N-32W-24	

Snyder & Associates Engineers & Planners, Inc.  
Missouri State Certificate of Authority #2006008544












V:\Projects\2020\120484\_120484\_Pool\_Plan\BARRY G. TURNER, EROSION CONTROL PLAN, 2/22/2020 1:10 PM, ANSI FULL BLEED, 0.00 X 22.00 INCHES



LEGEND:

- = SILT FENCE
- = VEHICLE TRACKING CONTROL.
- = CONCRETE WASH OUT

LEGEND:

- = EXISTING INDEX CONTOUR
- = NEW INDEX CONTOUR

- EROSION CONTROL PLAN - CONSTRUCTION NOTES
- CONTRACTOR TO INSTALL SILT FENCE PER APWA STANDARD DETAIL ESC 10-11. REMOVE AND RELOCATE AS NECESSARY FOR CONSTRUCTION.
  - APPROXIMATE LOCATION OF VEHICLE TRACKING CONTROL. CONTRACTOR TO INSTALL PER APWA STANDARD DETAIL ESC-01. LOCATION CAN BE ADJUSTED AS NEEDED FOR CONSTRUCTION.
  - PROPOSED CONCRETE WASHOUT LOCATION. CONTRACTOR TO INSTALL PER APWA STANDARD DETAIL ESC-01. LOCATION CAN BE ADJUSTED AS NEEDED FOR CONSTRUCTION.

- EROSION CONTROL - GENERAL NOTES
- IF SITE IS NOT STABILIZED PRIOR TO END OF FALL PLANTING SEASON CONTRACTOR TO INSTALL TEMPORARY WINTER STABILIZATION. WINTER STABILIZATION TO INCLUDE TEMPORARY EROSION CONTROL BLANKETS OR GEOTEXTILE FABRIC WITH BASE ROCK FOR ALL DISTURBED AREAS NOT CURRENTLY UNDER ACTIVE CONSTRUCTION.
- SEEDING FOR SPRING SHALL OCCUR BETWEEN FEBRUARY 1 AND APRIL 15. FALL SEEDING SHALL OCCUR BETWEEN AUGUST 15 AND OCTOBER 15. SEEDING SHALL OCCUR DURING FAVORABLE WEATHER CONDITIONS AND ONLY DURING NORMAL AND ACCEPTABLE PLANTING SEASONS WHEN SATISFACTORY GROWING CONDITIONS OCCUR.
  - THE PLANTING OPERATIONS SHALL NOT BE PERFORMED DURING TIMES OF EXTREME DROUGHT. WHEN GROUND IS FROZEN OR DURING TIMES OF OTHER UNFAVORABLE CLIMATIC CONDITIONS.

- GRADING PLAN - GENERAL NOTES
- UTILITY WARNING:  
THE UTILITIES SHOWN HAVE BEEN LOCATED FROM FIELD SURVEY INFORMATION AND/OR RECORDS OBTAINED. THE SURVEYOR MAKES NO GUARANTEE THAT THE UTILITIES SHOWN COMPRISE ALL SUCH UTILITIES IN THE AREA, EITHER IN SERVICE OR ABANDONED. THE SURVEY FURTHER DOES NOT WARRANT THAT THE UTILITIES SHOWN ARE IN THE EXACT LOCATION INDICATED.
  - NOTIFY UTILITY OWNERS PRIOR TO BEGINNING ANY CONSTRUCTION. CONTRACTOR IS RESPONSIBLE FOR DETERMINING EXISTENCE, EXACT LOCATION AND DEPTH OF ALL UTILITIES, AVOID DAMAGE TO UTILITIES AND SERVICES DURING CONSTRUCTION. ANY DAMAGE DUE TO THE CONTRACTOR'S CARELESSNESS SHALL BE CORRECTED AT THE CONTRACTOR'S EXPENSE. COORDINATE AND COOPERATE WITH UTILITY COMPANIES DURING CONSTRUCTION.

- ALL PROPOSED CONTOURS AND SPOT ELEVATIONS SHOWN ARE FINISHED GRADES AND/OR TOP OF PAVING SLAB (GUTTER), UNLESS OTHERWISE NOTED.
- ALL STORM SEWER PIPE LENGTHS ARE MEASURED FROM CENTER OF STRUCTURE TO CENTER OF STRUCTURE AND INCLUDE FLARED END SECTION.
- CONTRACTOR TO STRIP AND STOCKPILE TOPSOIL FROM ALL AREAS TO BE CUT OR FILLED. RE-SPREAD TO MINIMUM 8" DEPTH TO FINISH GRADES.
- THE CONTRACTOR IS RESPONSIBLE FOR CLEANING DIRT AND DEBRIS FROM STREETS, DRIVEWAYS, AND SIDEWALKS CAUSED BY CONSTRUCTION ACTIVITIES.
- CONTRACTOR TO VERIFY ALL UTILITY LOCATIONS AND DEPTH PRIOR TO WALL CONSTRUCTION TO DETERMINE ALL POSSIBLE CONFLICTS.

MARK		REVISION	DATE	BY
Engineer: SD	Checked By: SD		Scale: 1" = 10'	
Technician: JS	Date: 04-26-2022		T-R-S: 47N-32W-24	

Shawm Duke - Engineer  
MO PE#2013006489

Shawm Duke  
Professional Engineer  
Missouri State Certificate of Authority #2006008544

6/1/22

SHAWN DUKE - ENGINEER  
MO PE#2013006489

WHISPERING WOODS POOL

EROSION CONTROL PLAN

LEE'S SUMMIT, MO

**SNYDER & ASSOCIATES**  
ENGINEERS & PLANNERS, INC.

802 FRANCIS STREET  
ST. JOSEPH, MISSOURI 64501  
816-364-5222 | www.snyder-associates.com


**SNYDER & ASSOCIATES**

Project No: 120.0484.11

Sheet C3.2




V:\Projects\2020\120.0484\_11\CAD\DWG\_1200484\_Pool Utility.dwg BARRY.G. TURNER UTILITY PLAN 2022/06/01 1:07 PM, ANSI FULL BLEED D (34.00 X 22.00 INCHES)



MARK	REVISION	DATE	BY
Engineer: SD	Checked By: SD	Scale: 1" = 10'	
Technician: JS	Date: 04-26-2022	T-R-S, 47N-32W-24	

Sheet C3.3

Shnyder & Associates Engineers & Planners, Inc.  
Missouri State Certificate of Authority #2006008544

  
SHAWN DUKE - ENGINEER  
MO PE#2013006489

WHISPERING WOODS POOL

UTILITY PLAN


LEE'S SUMMIT, MO

**SNYDER & ASSOCIATES**  
ENGINEERS & PLANNERS, INC.


802 FRANCIS STREET  
ST. JOSEPH, MISSOURI 64501  
816-364-5222 | www.snyder-associates.com

Project No: 120.0484.11

Sheet C3.3


  
**SNYDER & ASSOCIATES**






FRONT EL.


SIDING STUCCO AND STONE ALL SIDES



LEFT EL.  
1/8" = 1'-0"




REAR EL.  
1/8" = 1'-0"



RIGHT EL.  
1/8" = 1'-0"

Review and Approval  
Structural Only

David Mezger Engineering LLC  
212 NE Circle Dr.  
Kansas City, MO 64116



BUILD IN ACCORDANCE WITH  
2018 INTERNATIONAL  
BUILDING CODE AND LOCAL  
CODES.

POOL HOUSE  
1901 SW RIVER RUN DR  
LEE SUMMIT MO


SCALE  
1/4" = 1'-0"

DATE  
5-27-22

PLAN NO.  
3781

SHEET NO.  
1 OF 5






FOUNDATION PLAN

Review and Approval  
Structural Only

David Mezger Engineering LLC  
212 NE Circle Dr.  
Kansas City, MO 64116



BUILD IN ACCORDANCE WITH  
2018 INTERNATIONAL  
BUILDING CODE AND LOCAL  
CODES.

POOL HOUSE  
1901 SW RIVER RUN DR  
LEE SUMMIT MO


SCALE  
1/4" = 1'-0

DATE  
5-27-22

PLAN NO.  
3781

SHEET NO.  
2 OF 5





MAIN FLOOR  
POOL HOUSE  
522 SF FINISHED

Review and Approval  
Structural Only

David Mezger Engineering LLC  
212 NE Circle Dr.  
Kansas City, MO 64116



BUILD IN ACCORDANCE WITH  
2018 INTERNATIONAL  
BUILDING CODE AND LOCAL  
CODES.

POOL HOUSE  
1901 SW RIVER RUN DR  
LEE SUMMIT MO

SCALE  
1/4" = 1'-0

DATE  
5-27-22

PLAN NO.  
3781

SHEET NO.  
3 OF 5



ENERGY CONSERVATION CODE  
THE FOLLOWING VALUES ARE NEEDED.

R-15 IN WALLS

R-49 IN ATTICS

R-38 IN VAULTS  
R-30 REDUCTION FOR VAULTS IS ONLY FOR 500 SF  
PF AREA

R-19 IN FLOORS OVER UNCONDITIONED SPACES


R-10 IN CRAWL SPACE WALLS

BASEMENT WALLS R-13 CAVITY OR R-10 CONTINUOUS


SLABS SHALL BE R-10 FOR A DEPTH OF 2 FOOT

A WINDOW U FACTOR OF .35 OR BETTER


DUCTWORK NEEDS TO HAVE AN R-8 VALUE




1. DWELLING / GARAGE OPENINGS BETWEEN GARAGE AND SLEEPING PURPOSES SHALL NOT BE PERMITTED. OTHER OPENINGS SHALL BE EQUIPPED WITH SOLID WOOD OR STEEL DOORS NOT LESS THAN 1-3/8" THICK OR 20 MINUTE RATED DOORS, WITH SELF CLOSING DEVICES REQUIRED FOR GARAGE / DWELLING SEPERATION DOORS R302.5.1
2. WHOLE HOUSE MECHANICAL VENTILATION SYSTEM IS REQUIRED FOR ANY DWELLING IN COMPLIANCE WITH IRC M 1505
3. CARBON MONOXIDE DETECTORS REQUIRED IRC R 315
4. STEEL COLUMNS SHALL BE MINIMUM SCHEDULE 40 R407.3
5. DECK SHALL BE BUILT PER TABLES 507.2 , 507.2.1, 507.3, 507.6, 507.5.1(1)&(2), 507.5, AND 507.6
6. STUDS SHALL BE CONTINUOUS BETWEEN FLOOR, CEILING AND OR ROOF DIAPHRAGMS R602.3
7. ADDED REQUIREMENTS FOR WINDOW FALL PROTECTION R312.2
8. NEW PROVISIONS FOR ATTACHMENT OF RAFTERS, TRUSSES AND ROOF BEAMS R802.3.1 R802.11
9. INSULATION REQUIRED FOR ALL BASEMENT WALLS ( INCLUDING UNFINISHED BASEMENTS) N1102.1
10. EXTERIOR WINDOWS/DOORS SHALL HAVE U-FACTOR 0.35 AND GLAZING SHALL HAVE SOLAR HEIGTH GAIN FACTOR OF 0.40 N1102.1
11. HOUSE LEAKAGE AND DUCT LEAKAGE PERFORMANCE STANDARDS EFFECTIVE JANUARY 1, 2014. A SAMPLE TESTING PROGRAM WILL BE IMPLEMENTED OCTOBER 1, 2012 KCBRC N1102.4.1.2 N1103.2.2
12. LIGHTING FIXTURES PENETRATING THE THERMAL ENVELOPE ( E.G. CAN LIGHTS IN ATTIC ) SHALL BE IC- RATED, LEAKAGE- RATED AND SEALED TO THE GYPSUM WALLBOARD N1102.4.4
- 13.PROGRAMMABLE THERMOSTAT REQUIRED N1103.1.1
14. AIR HANDLERS SHALL BE RATED FOR MAXIMUM 2 % AIR LEAKAGE RATE N1103.2.2.1
15. BUILDING CAVITIES USED AS RETURN AIR PLENUMS SHALL BE SEALED TO PREVENT LEAKAGE ACROSS THE THERMAL ENVELOPE KCBRC N1103.2.2
16. CERTAIN HOT WATER PIPES SHALL BE INSULATED N1103.4
17. ALL EXHAUST FANS SHALL TERMINATE TO THE BUILDING EXTERIOR M1507.2
18. MAKEUP AIR SYSTEM REQUIRED FOR KITHCHEN EXHAUST HOODS THAT EXCEED 400 CFM M1503.4
19. BUILDING CAVITIES IN A THERMAL ENVELOPE WALL ( INCLUDING THE WALL BETWEEN THE HOUSE AND GARAGE ) SHALL NOT BE USED AS RETURN AIR PLENUMS
20. AN AIR HANDLING SYSTEM SHALL NOT SERVE BOTH THE LIVING SPACE AND THE GARAGE M1601.6
21. A CONCRETE- ENCASED GROUNDING ELECTRODE ( 'UFER' GROUND ) CONNECTION SHALL BE PROVIDED TO THE ELECTRICAL SERVICE E3608.1
22. COMPLIANCE WITH THE REQUIRMENT AND SHOW CONNECTION AS NEEDED FOR ROOF BEAM, TRUS, RAFTER, AND GIRDER CONNECTION FOR UPLIFT PER IRC 802.11. ALL RAFTERS BE IN COMPLIANCE WITH IRC 502.11 AMENDED RAYMORE CODE



ROOF PLAN  
1/8 = 1-0  
ROOF PITCHES 8/12  
16" SOFFITS TYP.  
RAFTERS 2 X 6 DF NO 2 @ 16" O.C.  
HIPS AND RIDGES 2 X 8 DF NO 2



ALL CONCRETE EXPOSED TO  
WEATHER GARAGE SLABS  
FOOTINGS WALLS AND FLATWORK  
MUST HAVE 6% AIR ENTRAINMENT



#### PIER PADS

TYP. U.N.O. 3-0 X 3-0 X 12" PEIR PADS MIN.  
WITH # 4 REBAR, 6 EACH WAY

STUDS OVER 10-0 SHALL HAVE  
BLOCKING ALONG WALL MAX  
OF 6-0 O.C.

#### WINDOW SAFETY GLAZING PER 308


SAFETY GLAZING REQUIRED ALONG WALKING SURFACES AND STAIRS LOCATED WITHIN 36 INCHES HORIZONTALLY OF THE STEPS. SAFETY GLAZING REQUIRED IF EXPOSED SINGLE PANEL IS IN EXCESS OF 9 SQUARE FEET OR THE BOTTOM EDGE OF THE GLAZING IS LESS THAN 18 INCHES ABOVE THE FINISHED FLOOR.

SAFETY GLAZING REQUIRD WHERE THE NEAREST EXPOSED EDGE OF THE GLAZING IS WITHIN 24 INCHES OF EITHER VERTICAL EDGE OF THE DOOR IN A CLOSED POSITION AND WHERE THE BOTTOM EXPOSED EDGE OF THE GLAZING IS LESS THAN 60 INCHES ABOVE A WALKING SURFACE, SAFETY OR TEMPERED GLAZING IS REQUIRED.

WINDOWS ARE TO HAVE FALL  
PROTECTION PER IRC 312.2

#### WINDOW EGRESS REQUIREMENTS

BEDROOM WINDOW EGRESS MINIMUM FOR A DOUBLE HUNG WINDOW IS 34 INCH CLEAR WIDTH MIN. AND 24 INCH CLEAR HEIGHT MIN. WITH A CLEAR OPENABLE AREA OF 5.7 SQUARE FEET MIN. A CASEMENT OR SLIDER WINDOW MINIMUMS ARE 20 INCH CLEAR WIDTH MINIMUM AND 41 INCH CLEAR HEIGHT MINIMUM. WITH A MINIMUM 5.7 SQUARE FOOT OF OPENABLE AREA. OPENING OF EGRESS WINDOW NOT MORE THAN 42" FROM THE FLOOR



EGRESS WINDOW WELL AS NEEDED  
PER SECTION 308 MIN 3-0 X 3-0  
WITH LADDER

Review and Approval  
Structural Only

David Mezger Engineering LLC  
212 NE Circle Dr.  
Kansas City, MO 64116



BUILD IN ACCORDANCE WITH  
2018 INTERNATIONAL  
BUILDING CODE AND LOCAL  
CODES.

POOL HOUSE  
1901 SW RIVER RUN DR  
LEE SUMMIT MO

SCALE

1/4" = 1-0

DATE

5-27-22

PLAN NO.

3781

SHEET NO.

4 OF 5



EXPOSURE CATEGORY B • 38-FOOT MEAN ROOF HEIGHT • 10-FOOT WALL HEIGHT • 2 BRACED WALL LINES		MINIMUM TOTAL LENGTH (FEET) OF BRACED WALL PANELS REQUIRED ALONG EACH BRACED WALL LINE <sup>a</sup>					
Ultimate Design Wind Speed (mph)	Story Location	Braced Wall Line Spacing <sup>b</sup> (feet)	Method LIB <sup>c</sup>	Method GB	Methods DWB, WSP, SFB, PBS, FCP, HPS, BV-WSP, ABW, PFH, PCF, CS-SFB	Methods CS-WSP, CS-G, CS-PF	
≤ 115		10	3.5	3.5	2.0	2.0	
		20	6.5	6.5	3.5	3.5	
		30	9.5	9.5	5.5	4.5	
		40	12.5	12.5	7.0	6.0	
		50	15.0	15.0	9.0	7.5	
		60	18.0	18.0	10.5	9.0	
		10	7.0	7.0	4.0	3.5	
		20	12.5	12.5	7.5	6.5	
		30	18.0	18.0	10.5	9.0	
		40	23.5	23.5	13.5	11.5	
		50	29.0	29.0	16.5	14.0	
		60	34.5	34.5	20.0	17.0	
		10	NP	10.0	6.0	5.0	
		20	NP	18.5	11.0	9.0	
		30	NP	27.0	15.5	13.0	
		40	NP	35.0	20.0	17.0	
		50	NP	43.0	24.5	21.0	
		60	NP	51.0	29.0	25.0	





FIGURE R602.10.6.1  
METHOD ABW—ALTERNATE BRACED WALL PANEL



FRONT ELEVATION

SECTION

4 mm, 1 foot = 304.8 mm.

FIGURE R602.10.6.2  
METHOD PFH—PORTAL FRAME WITH HOLD-DOWNS

METHODS, MATERIAL	MINIMUM THICKNESS	FIGURE	CONNECTION CRITERIA <sup>a</sup>	
			Fasteners	Spacing
Intermittent Bracing Methods	LIB Let-in bracing		Wood: 2-8d common nails or 3-8d (2 1/2\"/>	Wood: per stud and top and bottom plates Metal: per manufacturer
	DWB Diagonal wood boards		2-8d (2 1/2\"/>	Per stud
	WSP Wood structural panel (See Section R604)		Exterior sheathing per Table R602.3(3) Interior sheathing per Table R602.3(1) or R602.3(2)	6\"/>
	BV-WSP <sup>b</sup> Wood structural panels with stone or masonry veneer (See Section R602.10.6.5)		8d common (2 1/2\"/>	4\"/>
	SFB Structural fiberboard sheathing		1 1/2\"/>	3\"/>
	GB Gypsum board		Nails or screws per Table R602.3.5 for exterior locations Nails or screws per Table R702.3.5 for interior locations	For all braced wall panel locations: 7\"/>
	PBS Particleboard sheathing (See Section R605)		For 3/4\"/>	3\"/>
	PCP Portland cement plaster		See Section R703.7 for maximum 16\"/>	6\"/>
	HPS Hardboard panel siding		1 1/2\"/>	4\"/>
	ABW Alternate braced wall		See Section R602.10.6.1	See Section R602.10.6.1

METHOD (See Table R602.10.4)	MINIMUM LENGTH <sup>a</sup> (inches)					CONTRIBUTING LENGTH (inches)
	8 feet	9 feet	10 feet	11 feet	12 feet	
DWB, WSP, SFB, PBS, FCP, HPS, BV-WSP	48	48	48	53	58	Actual <sup>b</sup>
GB	48	48	48	53	58	Double sided = Actual Single sided = 0.5 × Actual
LIB	55	62	69	NP	NP	Actual <sup>b</sup>
ABW	SDC A, B and C, ultimate design wind speed < 140 mph	28	32	34	38	42
	SDC D <sub>0</sub> , D <sub>1</sub> and D <sub>2</sub> , ultimate design wind speed < 140 mph	32	32	34	NP	NP
CS-G	Adjacent clear opening height (inches)	24	27	30	33	36
CS-WSP, CS-SFB	≤ 64	24	27	30	33	36
	68	26	27	30	33	36
	72	27	27	30	33	36
	76	30	29	30	33	36
	80	32	30	30	33	36
	84	35	32	32	33	36
	88	38	35	33	33	36
	92	43	37	35	35	36
	96	48	41	38	36	36
	100	—	44	40	38	38
	104	—	49	43	40	39
	108	—	54	46	43	41
	112	—	—	50	45	43
	116	—	—	55	48	45
	120	—	—	60	52	48
	124	—	—	—	56	51
	128	—	—	—	61	54
	132	—	—	—	66	58
	136	—	—	—	—	62
	140	—	—	—	—	66
	144	—	—	—	—	72
METHOD (See Table R602.10.4)	Portal header height					48
	Supporting roof only	16	16	16	Note c	Note c
PFH	Supporting one story and roof	24	24	24	Note c	Note c
PFG	Supporting roof only	24	27	30	Note d	Note d
	Supporting one story and roof	24	27	30	Note d	Note d
CS-PF	SDC A, B and C	16	18	20	Note e	Note e
	SDC D <sub>0</sub> , D <sub>1</sub> and D <sub>2</sub>	16	18	20	Note e	Note e

For SI: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1 mile per hour = 0.447 m/s.  
NP = Not Permitted.  
a. Linear interpolation shall be permitted.  
b. Use the actual length where it is greater than or equal to the minimum length.  
c. Maximum header height for PFH is 10 feet in accordance with Figure R602.10.6.2, but wall height shall be permitted to be increased to 12 feet with pony wall.  
d. Maximum header height for PFG is 10 feet in accordance with Figure R602.10.6.3, but wall height shall be permitted to be increased to 12 feet with pony wall.  
e. Maximum header height for CS-PF is 10 feet in accordance with Figure R602.10.6.4, but wall height shall be permitted to be increased to 12 feet with pony wall.

METHODS, MATERIAL	MINIMUM THICKNESS	FIGURE	CONNECTION CRITERIA <sup>a</sup>	
			Fasteners	Spacing
Intermittent Bracing Methods	PFH Portal frame with hold-downs		See Section R602.10.6.2	See Section R602.10.6.2
	PFG Portal frame at garage		See Section R602.10.6.3	See Section R602.10.6.3
	CS-WSP Continuously sheathed wood structural panel		Exterior sheathing per Table R602.3(3) Interior sheathing per Table R602.3(1) or R602.3(2)	6\"/>
Continuous Sheathing Methods	CS-G <sup>b</sup> Continuously sheathed wood structural panel adjacent to garage openings		See Method CS-WSP	See Method CS-WSP
	CS-PF Continuously sheathed portal frame		See Section R602.10.6.4	See Section R602.10.6.4
	CS-SFB <sup>c</sup> Continuously sheathed structural fiberboard		1 1/2\"/>	3\"/>

For SI: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1 degree = 0.0175 rad, 1 pound per square foot = 47.8 N/m<sup>2</sup>, 1 mile per hour = 0.447 m/s.  
a. Adhesive attachment of wall sheathing, including Method GB, shall not be permitted in Seismic Design Categories C, D<sub>0</sub>, D<sub>1</sub> and D<sub>2</sub>.  
b. Applies to panels next to garage door opening where supporting gable end wall or roof load only. Shall only be used on one wall of the garage. In Seismic Design Categories D<sub>0</sub>, D<sub>1</sub> and D<sub>2</sub>, roof covering dead load shall not exceed 3 psf.  
c. Garage openings adjacent to a Method CS-G panel shall be provided with a header in accordance with Table R602.7(1). A full-height clear opening shall not be permitted adjacent to a Method CS-G panel.  
d. Method CS-SFB does not apply in Seismic Design Categories D<sub>0</sub>, D<sub>1</sub> and D<sub>2</sub>.  
e. Method applies to detached one- and two-family dwellings in Seismic Design Categories D<sub>0</sub> through D<sub>2</sub> only.




FIGURE R602.10.6.4  
METHOD CS-PF—CONTINUOUSLY SHEATHED PORTAL FRAME PANEL CONSTRUCTION

For SI: 1 inch = 25.4 mm, 1 foot = 304.8 mm.

Review and Approval  
Structural Only

David Mezger Engineering LLC  
212 NE Circle Dr.  
Kansas City, MO 64116



BUILD IN ACCORDANCE WITH  
2018 INTERNATIONAL  
BUILDING CODE AND LOCAL  
CODES.

POOL HOUSE  
1901 SW RIVER RUN DR  
LEE SUMMIT MO

SCALE  
1/4" = 1-0

DATE  
5-27-22

PLAN NO.

3781

SHEET NO.

5 OF 5



7

6

5

4

3

2

1

EXHAUST FAN SCHEDULE												
MARK	AREA SERVED	MANUFACTURER	MODEL	TYPE	CFM	ESP (IN)	DRIVE	POWER	OPERATION	ELECTRICAL		WEIGHT
										VOLTS	PHASE	
EF-1	MEN R.R.	PANASONIC	FV-08-11VFL5	CEILING	110	0.25	DIRECT	26.5w	LIGHT SWITCH	120	1	12
EF-2	WOMEN R.R.	PANASONIC	FV-08-11VFL5	CEILING	110	0.25	DIRECT	26.5w	LIGHT SWITCH	120	1	12
EF-3	EQUIPMENT ROOM	FANTECH	FR-160	IN-LINE	225	0.5	DIRECT	125w	BREAKER	120	1	8

## MECHANICAL & PLUMBING SPECIFICATIONS


1. GENERAL PROVISIONS:
- PROVIDE ALL LABOR, MATERIALS, AND EQUIPMENT NECESSARY FOR THE COMPLETE INSTALLATION OF THE PLUMBING SYSTEMS OUTLINED.
  - OBTAIN ALL PERMITS, FEES, LICENSES, INSPECTIONS, AND CERTIFICATIONS OF COMPLIANCE OR APPROVAL AS REQUIRED BY AUTHORITIES.
  - ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH ALL APPLICABLE LAWS, CODES AND REGULATIONS OF THE GOVERNMENTAL BODIES HAVING JURISDICTION OVER THE SITE.
  - PROVIDE ALL NECESSARY CUTTING AND PATCHING OF WALLS, FLOORS, CEILINGS, AND ROOFS AS NECESSARY. PATCH AROUND ALL OPENINGS SHALL MATCH ADJACENT AREA. COORDINATE ALL ROOFING WORK WITH OWNER OR RESPONSIBLE PARTY, SO THAT THE EXISTING ROOFING WARRANTY WILL BE MAINTAINED.
  - CONTRACTOR SHALL GUARANTEE ALL WORK AND MATERIALS AGAINST DEFECT FOR A PERIOD OF ONE YEAR FROM FINAL ACCEPTANCE.
  - INSPECTION OF THE SITE: THIS CONTRACTOR SHALL THOROUGHLY ACQUAINT HIMSELF WITH THE MEP DRAWINGS, SPECIFICATIONS, DETAIL, AND THE SITE. THIS CONTRACTOR SHALL NOTIFY THE ARCHITECT OF ANY SPECIAL OR UNUSUAL PROBLEMS, CONFLICTS, OR OBSTRUCTIONS THAT AFFECT HIS BID.
  - FOR THE PURPOSE OF CLEARNESS AND LEGIBILITY, THE DRAWINGS ARE ESSENTIALLY DIAGRAMMATIC AND DO NOT SHOW ALL OFFSETS AND FITTINGS REQUIRED FOR INSTALLATION. DO NOT SCALE DRAWINGS. THE SIZE AND LOCATION OF EQUIPMENT IS SHOWN TO SCALE WHEREVER POSSIBLE. THE CONTRACTOR SHALL VERIFY ALL CONDITIONS AND DATA AS INDICATED ON THE DRAWINGS AND IN THE SPECIFICATION SECTIONS WHERE MECHANICAL WORK INTERFACES WITH OTHER TRADES.
  - INCLUDE ALL BASIC MATERIALS AND CONSTRUCTION METHODS INCLUDING PIPES, PIPE FITTINGS, AND SPECIALTIES AND SUPPORTING DEVICES, VALVES, PIPE AND VALVE IDENTIFICATION, PUMPS, VIBRATION ISOLATION, ETC.
2. PLUMBING
- PROVIDE AND APPROVED WATER HAMMER ARRESTOR FOR EACH PLUMBING FIXTURE SUPPLY AS REQUIRED BY FIXTURE MANUFACTURER.
  - ALL EXPOSED PIPE SHALL BE CHROME PLATED BRASS PIPE, NO FERROUS PIPE.
  - PROVIDE CLEANOUTS AT EACH CHANGE IN DIRECTION AND AT 100 FOOT INTERVALS IN STRAIGHT RUNS.
  - PROVIDE ACCESS PANELS FOR ALL CONCEALED VALVES AND TRAPS.
  - CLEANOUTS:
    - UNFINISHED FLOOR (FCO):JR SMITH #4020, OR EQUAL.
    - WALL (WCO):JR SMITH #4472, OR EQUAL, 24" ABOVE THE FLOOR.
    - GRADE (GCO):JR SMITH #4256, OR EQUAL, WITH HEAVY DUTY CAST IRON BODY AND COVER.
  - PROVIDE DIELECTRIC UNIONS WITH APPROPRIATE END CONNECTION TO MATCH THE PIPE SYSTEM IN WHICH INSTALLED (SCREWED, SOLDERED, OR FLANGED). PROVIDE DIELECTRIC UNIONS ON ALL PIPING CONNECTIONS TO HOT WATER HEATERS AND EXPANSION JOINTS.
  - ALL SEWER PIPING LOCATED INSIDE THE BUILDING SHALL BE INSTALLED WITH THE FOLLOWING SLOPES.
    - INSTALL 2-1/2" AND SMALLER PIPE AT 1/4" PER FOOT FALL.
    - INSTALL 3" AND LARGER PIPE AT 1/8" PER FOOT FALL.
  - ALL SEWER PIPING LOCATED EXTERIOR TO THE BUILDING SHALL BE INSTALLED WITH THE FOLLOWING SLOPES.
    - INSTALL 4" AND SMALLER PIPE AT A MINIMUM OF 2% SLOPE.
    - INSTALL 6" AND LARGER PIPE AT A MINIMUM OF 1% SLOPE.
3. PIPING
- DOMESTIC COLD, AND HOT.
    - TYPE L HARD DRAWN COPPER TUBING, ASTM B-88 WITH WROUGHT BRONZE SOLDERED FITTINGS.
    - BALL VALVE: CRANE #932 OR EQUAL.
  - SANITARY SEWER AND VENTS.
    - SCHEDULE 40 PVC SOLID PLASTIC PIPE WITH DWV FITTINGS.
4. INSULATION:
- ALL INSULATIONS AND ACCESSORIES SHALL HAVE A FIRE HAZARD CLASSIFICATION WITH A FLAME SPREAD RATING OF NOT OVER 25, A FUEL CONTRIBUTION RATING OF NOT OVER 50, AND A SMOKE DEVELOPMENT RATING OF NOT OVER 50, IN ACCORDANCE WITH NFPA.
  - PIPE INSULATION (ABOVE GRADE):
    - THE PIPE INSULATION USED SHALL HAVE A THERMAL CONDUCTIVITY OF 0.27 BTU PER IN./HR\*SQ-FT\*F OR LESS.
    - FLEXIBLE CLOSED CELL ELASTOMERIC THERMAL INSULATION, UNSUT OR PRESUT WITH PRESSURE SENSITIVE ADHESIVE SYSTEM FOR CLOSURE AND VAPOR SEALING, EQUAL TO ARMSTRONG AP ARMAFLEX OR ARMAFLEX 2000.
    - INSULATION SCHEDULE:
      - DOMESTIC HOT WATER: 1"
5. TESTING, BALANCING AND CLEANING:
- ALL PIPING SHALL BE TESTED FOR LEAKS BEFORE BEING CONCEALED IN WALL CONSTRUCTION OR COVERED WITH INSULATION.
  - SEWER AND VENT PIPING SHALL BE HYDROSTATICALLY TESTED WITH NO LESS THAN 10 FEET OF HEAD FOR A PERIOD OF NOT LESS THAN 15 MINUTES, PER THE LOCAL PLUMBING CODE, WITH NO LEAKS.
  - DOMESTIC WATER PIPING SHALL BE HYDROSTATICALLY TESTED AT A PRESSURE OF NOT LESS THAN 1-1/2 TIMES THE OPERATING PRESSURE, BUT NOT LESS THAN 60 PSI, FOR A PERIOD OF NOT LESS THAN 2 HOURS, WITH NO LEAKS.

## GENERAL NOTES

- DRAWINGS ARE DIAGRAMMATIC ONLY AND REPRESENT THE GENERAL SCOPE OF WORK. REVIEW THE GENERAL NOTES, SPECIFICATIONS AND PLANS FOR ADDITIONAL REQUIREMENTS THAT MAY NOT BE SPECIFICALLY CALLED OUT IN THIS PORTION OF THE CONSTRUCTION DOCUMENTS. NOTIFY ARCHITECT, ENGINEER AND/OR OWNER OF CONFLICTS OR DISCREPANCIES PRIOR TO SUBMISSION OF BID.
- COORDINATE INSTALLATION OF MECHANICAL SYSTEM WITH OTHER TRADES TO ENSURE A NEAT AND ORDERLY INSTALLATION AND AVOID CONFLICTS. INSTALL DUCTWORK AND PIPING AS TIGHT TO STRUCTURE AS POSSIBLE. COORDINATE INSTALLATION OF DUCTWORK AND PIPING TO AVOID CONFLICTS WITH ELECTRICAL PANELS, LIGHTING FIXTURES, ETC. VERIFY DUCT SPACE AVAILABLE ABOVE ALL CEILINGS PRIOR TO ANY FABRICATION OF INSTALLATION.
- ALL ROOF AND WALL PENETRATIONS SHALL BE COORDINATED WITH THE GENERAL CONTRACTOR. PROVIDE ALL REQUIRED SLEEVES, FLASHINGS, CURBS, REINFORCED ANGLES, SUPPORTING FRAMES, ETC. UNLESS THEY ARE SPECIFICALLY CALLED OUT TO BE FURNISHED BY OTHERS.
- THE ELECTRICAL SYSTEM DESIGN IS BASED IN PART ON THE SPECIFIED HVAC EQUIPMENT. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE THE ELECTRICAL REQUIREMENTS OF THE HVAC EQUIPMENT BEING FURNISHED. ANY CHANGES TO THE ELECTRICAL SYSTEM DUE TO HVAC EQUIPMENT OTHER THAN THE SPECIFIED EQUIPMENT BEING FURNISHED SHALL BE PROVIDED AT NO ADDITIONAL COST TO THE OWNER.

## # KEYED PLAN NOTES


- CEILING MOUNT EXHAUST FAN WITH 4"Ø DUCT UP THROUGH ROOF. DUCT SHALL TERMINATE 16" ABOVE ROOF WITH WEATHERPROOF RAIN CAP. SEAL ROOF PENETRATION WEATHER TIGHT.
- 6"Ø PVC EXHAUST DUCT UP THROUGH ROOF. DUCT SHALL TERMINATE 16" ABOVE ROOF WITH PVC WEATHER CAP.
- 6"Ø PVC EXHAUST DUCT DOWN. TERMINATE EXHAUST DUCT 12" A.F.F. COVER OPENING WITH 1/4"x1/4" WIRE MESH SCREEN. COORDINATE LOCATION WITH POOL CONSULTANT.
- LOUVERED DOOR BY GENERAL CONTRACTOR.



### CEILING MOUNTED EXHAUST FAN

SCALE : NO SCALE


3



### IN-LINE EXHAUST FAN

SCALE : NO SCALE


2



## MECHANICAL PLAN

SCALE: 1/4" = 1'-0"

1



MO CDA NO. 201000786 / KS CDA NO. E-2818  
1926 CENTRAL ST. SUITE #201  
KANSAS CITY, MO 64108  
phone: (816) 272-8289  
email: jsmothers@jscengineers.com



PROJECT  
**POOL HOUSE STRUCTURE**  
LEE'S SUMMIT, MO

REVISIONS:	DATE	DESCRIPTION
1		
2		
3		
4		
5		

Copyright 2021  
JSC Engineers

ISSUED:

PERMIT

SHEET TITLE:

**MECHANICAL PLAN  
AND  
SPECIFICATIONS**

DATE: 05.20.2022

JOB NO.: 22-133

SHEET:

**MP1.1**



7

6

5

4

3

2

1

E


D

C

B

A


PLUMBING FIXTURE SCHEDULE	
LAV	HANDICAP ACCESSIBLE WALL MOUNT LAVATORY WITH CARRIER, PROFLO MODEL PF5411WH, VITREOUS CHINA, WHITE, SELF-RIMMING COUNTER TOP, PROFLOW PFWS3006 ADA COMPLIANT FAUCET, SS FLEX SUPPLY RISERS WITH CHROME PLATED STOP VALVES, P-TRAP WITH CLEANOUT AND ESCUTCHEONS. INSULATE WITH "HANDI-LAV-GUARD" MODEL 102, OR EQUAL.
WC	FLOOR-MOUNTED ADA WATER CLOSET: PROFLO MODEL PF1503WH, HANDICAP ACCESSIBLE, VIREOUS CHINA, 1.28 GPF, ELONGATED BOWL, FLOOR MOUNTED, WHITE, VITREOUS CHINA TANK AND COVER CONTAINING FLUSHOMETER/TANK WITH BUILT-IN PRESSURE REGULATOR AND BACKFLOW PREVENTER, WHITE OPEN FRONT SEAT, CHROME STOPS, C.P. FLEXIBLE RISER TUBE, BOLT CAPS, AND ESCUTCHEON
FD	FLOOR DRAIN: SOUIX CHIEF 842-3PNR, FLOOR DRAIN, PVC BODY AND CLAMPING COLLAR, ADJUSTABLE 5-1/2" ROUND NICKEL BRONZE STRAINER. PROVIDE WITH PROSET SYSTEMS "TRAP GUARD" INSERT FOR ACTUAL FLOOR DRAIN MODEL AND SIZE PROVIDED.
FS	FLOOR SINK, JOSAM 49420-LF-NB SERIES SQUARE CAST IRON 12-1/4" DEEP SUPER FLO-SEPTOR® FLOOR SINK WITH ACID-RESISTING INTERIOR, BOTTOM OUTLET, ALUMINUM INTERNAL DOME STRAINER, NIKALOY SANITARY SLOPED RIM AND NIKALOY, LIGHT-DUTY, ANTI-TILTING, SUPER-FLO® GRATE. 16x16 SQUARE TOP, 4" OUTLET.
DF	DRINKING FOUNTAIN. ELKAY EZH2O. ELECTRIC WATER COOLER WITH BOTTLE FILLING STATION. ADA COMPLIANT. COLOR BY OWNER/ARCHITECT. MOUNT AT HEIGHT DETERMINED BY ARCHITECT. 115V/1PH, 4.2 FLA, 370 WATTS, 71 LBS.
RPZ1	REDUCED PRESSURE ZONE BACKFLOW PREVENTER: 1", WATTS # LF009QT, MEETING ASSE 1013, LEAD FREE CAST BRONZE BODY, QUARTER TURN TESTING COCKS, QUARTER TURN BALL VALVES, AND # 909AG AIR GAP FITTING.
RPZ2	REDUCED PRESSURE ZONE BACKFLOW PREVENTER: 3/4", WATTS # LF009QT, MEETING ASSE 1013, LEAD FREE CAST BRONZE BODY, QUARTER TURN TESTING COCKS, QUARTER TURN BALL VALVES, AND # 909AG AIR GAP FITTING.
FPWH	FREEZE-PROOF WALL HYDRANT: PRIER PRODUCTS HC-6341, 3/4" FPT INET, 3/4" THREADED HOSE CONNECTION, LOOSE KEY HANDLE HYDRANT LENGTH AS REQUIRED FOR INSTALLED WALL THICKNESS, ADJUSTABLE WALL CLAMP, BRASS BOX WITH SATIN NICKEL PLATED FINISH AND INTEGRAL ASSE 1052 DOUBLE CHECK VACUUM BREAKER.
UR1	URINAL: SLOAN WEUS1000.1001, WHITE, VITREOUS CHINA, WASHOUT WALL URINAL, 0.1 GALLONS PER FLUSH, 27"H X 17"W, FURNISH WITH FLUSHOMETER, VANDAL RESISTANT CHROME PLATED HOUSING, ADJUSTABLE TAILPIECE AND VANDAL RESISTANT OUTLET STRAINER. MOUNT NON-ADA AT 24" FROM FINISHED FLOOR, MOUNT ADA URINAL 17" FROM FINISHED FLOOR. TRIM: SUITABLE CARRIER WITH STANCHIONS TO FLOOR.
EW1	ELECTRIC WATER HEATER, EEMAX, MODEL SP2412, 2.4KW, 20 AMP, 110 VOLT, POINT OF USE WATER HEATER. SET HW SUPPLY TEMP SET TO 110F.
EW2	ELECTRIC WATER HEATER, EEMAX, MODEL SP2412, 2.4KW, 20 AMP, 110 VOLT, POINT OF USE WATER HEATER. SET HW SUPPLY TEMP SET TO 110F.



PLUMBING RISER DIAGRAM

SCALE : NO SCALE


3



WASTE & VENT PLAN

SCALE: 1/4" = 1'-0"


2



DOMESTIC WATER ENTRY

SCALE : NONE

4



WATER PLAN


SCALE: 1/4" = 1'-0"

1



# KEYED PLAN NOTES

- 4" SANITARY TO UTILITY SERVICE. CONTRACTOR SHALL WORK WITH LOCAL WASTE WATER AUTHORITY FOR INSTALLATION OF A NEW SEWER LINE CONNECTING INTO THE SEWER MAIN FOR A COMPLETE INSTALLATION. REFER TO CIVIL PLANS FOR CONTINUATION. COORDINATE INVERT ELEVATION WITH SITE CIVIL CONTRACTOR PRIOR TO START OF WORK.
- 1" DOMESTIC COLD WATER TO UTILITY SERVICE. CONTRACTOR SHALL WORK WITH THE WATER COMPANY FOR THE INSTALLATION OF A NEW WATER MAIN ENTRANCE, INCLUDING TAP, METER, METER PIT, PIPING, ETC. FOR A COMPLETE INSTALLATION. REFER TO CIVIL PLANS FOR CONTINUATION.
- 1"CW VALVED AND CAPPED FOR FUTURE USE BY POOL EQUIPMENT.
- 1/2"CW TO WATER CLOSET.
- 1/2" CW DOWN IN WALL. PROVIDE 1/2"CW TO LAV AND 1/2"CW TO INSTANTANEOUS WATER HEATER UNDER SINK. CONTINUE WITH 1/2"HW TO LAV. SET HW SUPPLY TEMPERATURE TO 110F.
- 1/2" CW TO DRINKING FOUNTAIN.
- COORDINATE PLACEMENT OF RPZ WITH POOL CONSULTANT PRIOR TO INSTALLATION. ALSO COORDINATE WITH ELECTRICAL CONTRACTOR. DO NOT ROUTE PIPING ABOVE OR WITHIN WORKING SPACE OF ELECTRICAL PANEL.
- 3/4CW DOWN TO URINAL.



MO COA NO. 2012000786 / KS COA NO. E-2818  
1925 CENTRAL ST. SUITE #201  
KANSAS CITY, MO 64108  
phone: (816) 272-8289  
email: jsmothers@jscengineers.com



PROJECT: POOL HOUSE STRUCTURE  
LEE'S SUMMIT, MO

REVISIONS:	DATE	DESCRIPTION
1		
2		
3		
4		
5		

Copyright 2021  
JSC Engineers

ISSUED:

PERMIT

SHEET TITLE:

PLUMBING PLANS

DATE: 05.20.2022

JOB NO.: 22-133

SHEET:

MP1.2



ELECTRICAL SPECIFICATIONS

PART I – GENERAL

A. CONDITIONS

- FURNISH AND INSTALL A COMPLETELY WIRED AND OPERATIONAL ELECTRICAL SYSTEM AS SHOWN ON THE DRAWINGS AND SPECIFIED HEREIN, INCLUDING BUT NOT LIMITED TO, THESE MAJOR ITEMS.  
A. LIGHTING FIXTURES AS INDICATED AND SPECIFIED ON THE PLANS.  
B. ELECTRICAL PANELS, SERVICE, CONDUIT, WIRING, ETC., FOR ALL OUTLETS AND EQUIPMENT.  
C. TELEPHONE, TELEVISION, AND FIRE ALARM. OUTLETS AND CONDUIT AS INDICATED.
- OBTAIN AND REVIEW ALL OTHER DRAWINGS INCLUDING REFLECTED CEILING PLAN, INTERIOR AND EXTERIOR ELEVATIONS, FURNITURE PLANS AND ALL MILL WORK DRAWINGS. COORDINATE INSTALLATION OF ALL ELECTRICAL DEVICES AND EQUIPMENT PRIOR TO ROUGH-IN.
- OBTAIN SUBMITTAL AND SHOP DRAWINGS FROM OTHER TRADES AND EQUIPMENT TO COORDINATE INSTALLATION ACCORDINGLY.
- INSTALLATION SHALL COMPLY WITH ALL CURRENT APPLICABLE CODES AND GOVERNING AGENCIES HAVING JURISDICTION.
- FIRE ALARM SYSTEM, IF REQUIRED PER IBC, SHALL BE DESIGN-BUILD BY OWNER'S/OC'S FIRE ALARM CONTRACTOR. DESIGN SHALL BE IN ACCORDANCE WITH NFPA 72. FIRE ALARM CONTRACTOR SHALL SUBMIT STAMPED DRAWINGS TO AHJ FOR REVIEW AND APPROVAL. FIRE ALARM CONTRACTOR IS RESPONSIBLE FOR TESTING AND VERIFYING THAT THE AUDIBILITY OF THE FIRE ALARM SYSTEM MEETS A MINIMUM OF 15 DBA ABOVE AMBIENT NOISE LEVELS. ADD HORNS WHERE REQUIRED TO MAINTAIN MINIMUM LEVELS.
- PROVIDE FIRE STOP ON ALL PIPING THAT PENETRATES RATED WALLS. METHOD OF FIRE STOP SHALL MEET WALL RATING. REFER TO ARCHITECTURAL DRAWINGS FOR LOCATION OF FIRE RATED WALLS. THIS CONTRACTOR SHALL PROVIDE FIRE RATED ENCLOSURES AROUND ALL ROUGH-IN BOXES, PANELS, ETC. THAT ARE LOCATED IN FIRE RATED WALLS AND SHALL FIRE CAULK ALL OPENINGS IN RATED ASSEMBLIES.

B. RELATED WORK BY OTHERS

- THE ELECTRICAL CONTRACTOR SHALL PROVIDE CONDUIT, TRENCH, AND BACKFILL FOR ELECTRICAL SERVICE ENTRANCE FROM THE MAIN SERVICE TO UTILITY POINT OF ELECTRICAL SERVICE. ELECTRICAL CONTRACTOR SHALL COORDINATE THE INSTALLATION OF THE ELECTRICAL SERVICE ENTRANCE WITH SERVING UTILITY COMPANY.
- THE ELECTRICAL CONTRACTOR SHALL PROVIDE CONDUIT, TRENCH, AND BACKFILL FOR PRIMARY PHONE AND CATV SERVICE FROM THE TELEPHONE TERMINAL BOARD OR CABINET TO THE PHONE COMPANY AND CATV COMPANY POINT OF SERVICE COORDINATE WITH LOCAL UTILITY COMPANIES.

C. CODES, REGULATIONS, AND STANDARDS

- THE INSTALLATION SHALL COMPLY WITH APPLICABLE LOCAL AND STATE CODES AND ORDINANCES, WITH THE REGULATIONS OF THE LATEST EDITION OF THE NATIONAL ELECTRIC CODE AND WITH THE REQUIREMENTS OF THE POWER, TELEPHONE, AND CATV COMPANIES FURNISHING SERVICES TO THIS INSTALLATION.
- THE LATEST EDITIONS OF THE FOLLOWING INDUSTRY STANDARDS, SPECIFICATIONS, AND CODES ARE MINIMUM REQUIREMENTS:  
A. THE NATIONAL ELECTRICAL MANUFACTURER'S ASSOCIATION STANDARDS.  
B. THE NATIONAL ELECTRICAL CODE, INCLUDING LOCAL AMENDMENTS.  
C. UNDERWRITER LABORATORIES INCORPORATED STANDARDS.  
D. AMERICAN NATIONAL STANDARDS INSTITUTE.  
E. INTERNATIONAL BUILDING CODE.

D. INSPECTION OF SITE

- PRIOR TO SUBMITTING A BID FOR ELECTRICAL WORK, THE CONTRACTOR SHALL VISIT THE SITE OF THE PROPOSED CONSTRUCTION AND SHALL THOROUGHLY ACQUAINT HIMSELF WITH EXISTING UTILITIES, AND WORKING CONDITIONS TO BE ENCOUNTERED, ETC. ALLOWANCE WILL NOT BE MADE FOR NONCOMPLIANCE WITH THIS CONDITION AFTER BIDDING.
- ELECTRICAL INSTALLATION SHALL MEET THE EXISTING CONDITIONS.

E. STORAGE AND HANDLING OF MATERIAL

- DELIVER MATERIALS AND EQUIPMENT TO THE PROJECT IN THE MANUFACTURER'S ORIGINAL, UNOPENED, LABELED CONTAINERS. PROTECT AGAINST MOISTURE, TAMPERING, OR DAMAGE FROM IMPROPER HANDLING OR STORAGE. CONTRACTOR SHALL PROTECT AND BE RESPONSIBLE FOR ANY DAMAGE TO WORK OR MATERIALS UNTIL FINAL ACCEPTANCE BY THE OWNER, AND SHALL MAKE GOOD WITHOUT COST TO THE OWNER, ANY DAMAGE OR LOSS THAT MAY OCCUR DURING THIS PERIOD.
- ARRANGE FOR TIMELY DELIVERY OF MATERIALS AND EQUIPMENT TO THE JOB SITE IN ORDER TO MINIMIZE THE LENGTH OF TIME BETWEEN DELIVERY AND INSTALLATION.
- COVER AND PROTECT ANY MATERIAL WHICH MAY BE AFFECTED BY THE WEATHER WHILE IN TRANSIT OR STORED AT THE PROJECT SITE. ANY MATERIAL FOUND DEFECTIVE OR NOT INSTALLED IN ACCORDANCE WITH THE CONTRACT DOCUMENTS MAY BE REJECTED BY THE ENGINEER.

F. CLEANUP

- KEEP THE PREMISES FREE FROM ACCUMULATION OF WASTE MATERIALS, OR RUBBISH CAUSED BY EMPLOYEES OR WORK UNDER THIS DIVISION OF THE SPECIFICATIONS. AT THE COMPLETION OF THE WORK REMOVE ALL SURPLUS MATERIALS, TOOLS, ETC., AND LEAVE THE PREMISES BROOM-CLEAN.

G. EXCAVATION, CUTTING, AND FITTING

- PERFORM ALL EXCAVATION AND BACK FILLING REQUIRED FOR WORK PERFORMED UNDER THIS DIVISION OF THE SPECIFICATIONS. USE EXCAVATED MATERIALS FOR BACKFILL UNLESS OFF SITE MATERIALS ARE DEEMED NECESSARY.
- PERFORM THE EXCAVATION, CUTTING, FITTING, REPAIRING, AND FINISHING OF THE WORK NECESSARY FOR THE INSTALLATION OF THE EQUIPMENT OF THIS SECTION. HOWEVER, NO CUTTING OF THE WORK OF OTHER TRADES OR OF ANY STRUCTURAL MEMBERS SHALL BE DONE WITHOUT THE CONSENT OF THE ARCHITECT.

H. DRAWINGS

- THE DRAWINGS INDICATE THE GENERAL ARRANGEMENT AND LOCATIONS OF THE ELECTRICAL WORK DATA PRESENTED ON THESE DRAWINGS ARE AS ACCURATE AS PLANNING CAN DETERMINE, BUT FIELD VERIFICATION OF ALL DIMENSIONS, LOCATIONS, LEVELS, ETC., TO SUIT FIELD CONDITIONS IS REQUIRED. REVIEW ALL ARCHITECTURAL, STRUCTURAL, AND MECHANICAL DRAWINGS AND ADJUST ALL WORK TO MEET THE REQUIREMENTS OF CONDITIONS SHOWN. THE ARCHITECTURAL DRAWINGS SHALL TAKE PRECEDENCE OVER ALL OTHER DRAWINGS. DISCREPANCIES BETWEEN DIFFERENT PLANS, OR BETWEEN DRAWINGS AND SPECIFICATIONS, OR REGULATIONS AND CODES GOVERNING THE INSTALLATION SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER IN WRITING BEFORE THE DATE OF BID OPENING. IF DISCREPANCIES ARE NOT REPORTED, THE CONTRACTOR SHALL BID THE GREATER QUANTITY OR BETTER QUALITY, AND APPROPRIATE ADJUSTMENTS WILL BE MADE AFTER CONTRACT AWARD. CONTRACTOR SHALL BE RESPONSIBLE TO FIELD MEASURE AND CONFIRM MOUNTING HEIGHTS AND LOCATION OF ELECTRICAL EQUIPMENT WITH RESPECT TO COUNTERS, RADIATION, ETC. DO NOT SCALE DISTANCES OFF THE ELECTRICAL DRAWINGS, USE ACTUAL BUILDING DIMENSIONS.

I. COOPERATION WITH OTHER CONTRACTORS

- COOPERATE WITH THE OTHER TRADES SO THAT THE INSTALLATION OF THE ELECTRICAL OUTLETS AND EQUIPMENT WILL BE PROPERLY COORDINATED. CONDUIT, LIGHTING FIXTURES, AND OTHER EQUIPMENT LOCATIONS SHALL BE VERIFIED WITH OTHER TRADES TO AVOID CONFLICT WITH THE PIPING, DUCTWORK, STEEL, BEAMS, OR OTHER OBSTRUCTIONS.
- CAREFULLY VERIFY THE LOCATIONS OF THE OUTLET BOXES AND DETERMINE THAT THEY HAVE NOT BEEN DISTURBED DURING THE INSTALLATION OF MATERIALS OF OTHER TRADES.
- COORDINATE THE LOCATION OF THE TRENCHES AND CONDUITS FOR ELECTRICAL AND TELEPHONE UTILITY SERVICES WITH THE GENERAL CONTRACTOR.
- COORDINATE HVAC AND PLUMBING EQUIPMENT CONNECTION REQUIREMENTS WITH HVAC AND PLUMBING CONTRACTORS.

J. RECORD DRAWINGS

- THE ELECTRICAL CONTRACTOR SHALL MAINTAIN A SET OF DRAWINGS AT THE JOB SITE FOR THE EXCLUSIVE PURPOSE OF MAINTAINING A RECORD OF ALL WORK INSTALLED AND TO SHOW ANY DEVIATIONS FROM THE WORK INDICATED ON THE DRAWINGS.
- AT THE COMPLETION OF THE PROJECT, ONE SET OF REPRODUCIBLE DRAWINGS, SHOWING ALL RECORD CONDITIONS, SHALL BE DELIVERED TO THE OWNER FOR ACCEPTANCE PRIOR TO FINAL PAYMENT.

PART II – PRODUCTS AND EXECUTION

A. MATERIALS

- ALL MATERIALS SHALL BE NEW AND OF QUALITY AS SPECIFIED ON THE PLANS OR SPECIFICATIONS AND MUST CARRY THE UNDERWRITER'S LABORATORIES APPROVAL COVERING THE PURPOSE FOR WHICH THEY ARE USED, IN ADDITION TO MEETING ALL REQUIREMENTS OF THE CURRENT APPLICABLE CODES AND REGULATIONS.

B. SHOP DRAWINGS AND APPROVALS

- THE ITEMS SPECIFIED HEREIN AND ON DRAWINGS ARE USED AS A STANDARD OF QUALITY. ANY MATERIALS OF EQUAL QUALITY AND AESTHETIC VALUE WILL BE GIVEN CONSIDERATION AS A SUBSTITUTE FOR THE MATERIALS SPECIFIED. NO APPROVAL WILL BE GIVEN TO A SPECIFIC CATALOG NUMBER, MODEL, OR TYPE OF EQUIPMENT, PRIOR TO BIDDING. AFTER BIDDING, THE DECISION OF THE ARCHITECT AND/OR ENGINEER DETERMINING EQUAL MATERIALS WILL BE FINAL.
- THE CONTRACTOR SHALL SUBMIT SEVEN (7) IDENTICAL BOUND SETS OF SHOP DRAWINGS ON THE FOLLOWING ITEMS:  
A. LIGHTING FIXTURE CUTS AND PERFORMANCE DATA.  
B. OUTLINE DRAWINGS AND DATA SHEETS OF EACH PANELBOARD, LOAD CENTERS, AND DISTRIBUTION PANELS.  
C. OUTLINE DRAWINGS OF ALL SWITCH GEAR COMPONENTS.  
D. WIRING DEVICES AND COVERPLATES.  
E. ALL CIRCUIT BREAKERS INSTALLED IN PANELBOARDS, LOAD CENTERS, AND DISTRIBUTION PANELS. SUBMIT ITEMS AT ONE TIME IN A NEAT AND ORDERLY MANNER WITHIN 15 DAYS OF AWARD OF CONTRACT. PARTIAL SUBMITTALS WILL NOT BE ACCEPTABLE.

C. SYSTEM GROUNDING

- GROUNDING SHALL COMPLY WITH REQUIREMENTS OF ARTICLE 250. ALL EXPOSED NONCURRENT CARRYING METALLIC PARTS OF ELECTRICAL EQUIPMENT, METALLIC RACEWAY SYSTEMS, METALLIC CABLE ARMOR, GROUNDING CONDUIT OF NONMETALLIC SHEATHED CABLES, GROUNDING CONDUCTOR IN NONMETALLIC RACEWAYS, AND GROUNDED CONDUCTORS OF THE WIRING SYSTEM SHALL BE GROUNDED.
- GROUNDING CONDUCTOR (NEUTRAL) OF THE WIRING SYSTEM SHALL BE CONNECTED TO THE SYSTEM GROUNDING CONDUCTOR AT A SINGLE PLACE IN EACH SYSTEM BY REMOVABLE BONDING JUMPERS, SIZED ACCORDING TO THE APPLICABLE PROVISIONS OF THE NATIONAL ELECTRICAL CODE. THE GROUNDED CONDUCTOR (NEUTRAL) TO THE GROUNDING CONDUCTOR CONNECTION SHALL BE LOCATED IN THE ENCLOSURE FOR THE SYSTEM'S OVERCURRENT PROTECTION OR WHERE OTHERWISE INDICATED ON THE PLANS OR SPECIFICATION.
- A GROUND BUS SEPARATE FROM THE NEUTRAL BUS SHALL BE PROVIDED IN ALL DISTRIBUTION PANELS AND PANELBOARDS. PROPER TORQUE ON GROUND BUS SHALL BE VERIFIED, PER MANUFACTURER'S RECOMMENDATIONS, PRIOR TO ENERGIZING EQUIPMENT.
- GROUND BUSES AND NEUTRAL BUSES IN ALL DISTRIBUTION PANELS, LOAD CENTERS, PANELBOARDS, AND THOSE PROVIDED IN ANY EQUIPMENT SHALL BE ISOLATED EXCEPT WHERE REQUIRED TO BE CONNECTED AS SPECIFIED ABOVE FOR THE SERVICE ENTRANCE.
- WHEN INDICATED ON THE DRAWINGS, EQUIPMENT GROUNDING CONDUCTORS SHALL BE EXTENDED FROM THE GROUND BUS IN THE DISTRIBUTION EQUIPMENT TO THE RECEPTACLE, FIXTURE OR DEVICE LUGS WHERE THEY ARE PROVIDED. WHERE LUGS ARE NOT PROVIDED, EQUIPMENT GROUNDING CONDUCTORS SHALL BE CONNECTED TO EQUIPMENT ENCLOSURES. THE CONNECTIONS SHALL BE ARRANGED SUCH THAT REMOVAL OF THE RECEPTACLE, EQUIPMENT GROUND CONDUCTORS, OR GROUND JUMPERS FROM GROUND BUSING SHALL NOT AFFECT THE GROUND SYSTEM.
- CONDUITS SHALL HAVE SEPARATE CODE SIZED GREEN GROUND WIRE INSTALLED IN THE CONDUIT TO INSURE A CONTINUOUS GROUNDING PATH.
- IN INACCESSIBLE LOCATIONS, MAKE CONNECTIONS BY EXOTHERMIC WELD PROCESS.
- IN ACCESSIBLE LOCATIONS, CONNECTIONS SHALL BE MADE WITH BOLTED THROUGH, APPROVED SOLDERLESS BRONZE GROUNDING DEVICES.

D. WIRE

- CONDUCTOR SIZES SHOWN ON THE DRAWINGS ARE BASED ON COPPER WIRE. UNLESS OTHERWISE SPECIFIED, ALL WIRE SHALL BE TYPE XHHW OR SE FOR FEEDERS OR BRANCH CIRCUITS LARGER THAN 4 AWG, TYPE THHN/THWN INSULATION FOR FEEDERS AND BRANCH CIRCUITS 4 AWG AND SMALLER. ALL BRANCH CIRCUIT WIRING SHALL BE COPPER.
- ALUMINUM CONDUCTORS MAY BE UTILIZED FOR SERVICE ENTRANCE AND PANEL FEEDERS. CONDUCTORS SHALL BE ALUMINUM ALLOW AA-8000 SERIES.
- THE WIRES SHALL BE MARKED WITH COLOR TO SIMPLIFY CIRCUIT IDENTIFICATION. UNLESS OTHERWISE REQUIRED BY LOCAL ORDINANCES GROUND WIRES SHALL BE GREEN, NEUTRAL WIRES SHALL BE 120V-WHITE, AND LIVE WIRES 208Y/120V AND 120/240V SHALL BE BLACK (PHASE A), RED (PHASE B), AND BLUE (PHASE C). CIRCUIT SHALL BE LABELED IN EACH J-BOX.
- ALL CONDUCTORS SHALL BE RATED 600 VOLT.
- SPLICERS IN EXTERIOR PULL BOXES AND MANHOLES SHALL BE WEATHERPROOF USING "SCOTCHCAST" SPLICER KIT OR APPROVED EQUAL. SEAL ENDS OF CONDUITS AND DUCTS WITH "DUCTSEAL" OR APPROVED EQUAL.
- PROVIDE SOLID CONDUCTOR FOR 12 AWG AND SMALLER.
- ALL WIRING WITHIN RESIDENTIAL UNITS ONLY MAY BE TYPE NM CABLE.
- NO WIRE SHALL BE INSTALLED IN THE CONDUIT SYSTEM UNTIL THE CONDUIT SYSTEM IS COMPLETE. USE MINERALAC NO. 100 OR EQUIVALENT AS A LUBRICANT TO FACILITATE THE INSTALLATION OF THE CONDUCTORS IN THE CONDUIT SYSTEM.
- MC CABLE WITH COPPER CONDUCTORS AND GROUND WIRE MAY BE USED WHERE PERMITTED.

E. CONDUIT

- ALL WIRING SHALL BE INSTALLED IN LISTED METALLIC CONDUIT EXCEPT AS PERMITTED IN OTHER SECTIONS. RGS, WITH A 20 MIL PVC COATING WILL BE USED WHEN IN CONTACT WITH EARTH. IMC MAY BE USED IN INDOOR LOCATIONS NOT IN CONTACT WITH THE EARTH. EMT MAY BE USED IN INDOOR LOCATIONS NOT IN CONTACT WITH EARTH, NOT IN CONCRETE SLABS OR WALLS AND NOT SUBJECT TO DAMAGE. PVC MAY BE USED IN OR BELOW CONCRETE AND DIRECT BURIED IN EARTH. FLEXIBLE STEEL CONDUIT SHALL BE USED FOR INDOOR FINAL CONNECTIONS TO EQUIPMENT IN LENGTHS NOT TO EXCEED 72". LIQUID-TIGHT FLEXIBLE STEEL CONDUIT SHALL BE FOR OUTDOOR FINAL CONNECTIONS TO EQUIPMENT NOT TO EXCEED 48".
- WHERE CONDUIT ENTERS OUTLET BOXES, FIXTURES OR CABINETS, FIRMLY FASTEN WITH STEEL SET SCREW, COMPRESSION CONNECTORS, OR DOUBLE LOCKNUTS FOR GRC. ALL CONNECTIONS SHALL HAVE BUSHINGS OR INSULATED THROAT CONNECTORS. FIRMLY FASTEN CONDUIT TO THE BUILDING CONSTRUCTION. RUN EXPOSED CONDUIT PARALLEL TO THE BUILDING LINES, SUPPORTED BY APPROPRIATE HANGERS (UNISTRUT, T & B OR APPLETON, OR EQUAL).
- COVER METALLIC CONDUIT IN CONTACT WITH EARTH WITH POLYETHYLENE TAPED SPIRAL WRAPPED, 1/2 LAPPED TO PROVIDE 20 MIL THICKNESS. TAPE SHALL BE SCOTCH NO. 50 TAPE. CONDUIT AND DUCTS NOT UNDER BUILDINGS AND FEEDER DUCTS SHALL BE INSTALLED PER N.E.C. 300-5. MAKE JOINTS WITH COMPOUND TO BE WATERTIGHT.
- SCHEDULE 40 PVC CONDUIT SHALL BE PERMITTED UNDERGROUND WITH PROPER FITTINGS, ALL UL APPROVED AND CEMENTED JOINTS. PENETRATIONS THROUGH FLOOR SLABS AND BENDS GREATER THAN 22" SHALL BE WRAPPED RIGID GALVANIZED STEEL ELBOWS.
- FITTINGS AND CONDUIT BODIES SHALL BE STEEL. DIECAST FITTINGS ARE NOT ACCEPTABLE. CONDUIT SIZES SHALL BE AS REQUIRED BY CODE AND AS INDICATED OR SPECIFIED.
- ALL EMPTY CONDUIT SYSTEMS SHALL HAVE A 200 LB. TEST NYLON PULL STRING TO FACILITATE INSTALLATION OF FUTURE WIRE.
- WIRING, CONDUITS, AND OUTLETS SHALL BE CONCEALED WITH THE BUILDING STRUCTURE, EXCEPT THAT CERTAIN MOTOR AND LIGHTING FEEDER CONDUITS MAY BE RUN EXPOSED IN CERTAIN AREAS AS INDICATED ON THE DRAWINGS.
- CONDUIT PENETRATION THROUGH ROOF SHALL HAVE ROOF FLASHING WITH CAULK TYPE COUNTER FLASHING SLEEVE. INSTALLATION SHALL BE WATERTIGHT.
- CONDUITS SHALL BE ROUTED PARALLEL AND PERPENDICULAR TO THE STRUCTURE.

F. OUTLET, PULL, AND JUNCTION BOXES

- EACH SWITCH, LIGHT, RECEPTACLE OR OTHER OUTLET, INSTALLED IN RESIDENTIAL UNITS, SHALL BE PROVIDED WITH A CODE SIZED, PLASTIC OUTLET BOX. JUNCTION AND PULL BOXES SHALL BE CODE SIZED, PLASTIC OR METAL OUTLET BOX. ALL OTHER OUTLET BOXES SHALL BE STEEL.
- BOXES INSTALLED IN POURED CEMENT FLOORS SHALL BE FLUSH TYPE CAST IRON OR STEEL WITH WATERTIGHT GASKETED COVERS. WHERE BOXES ARE INSTALLED IN FLOORS WITH TILE OR CARPET FLOOR COVERING, COVERS SHALL BE OF THE RECESSED TYPE TO ACCOMMODATE THE FLOOR COVERING. BOXES INSTALLED FOR THE ALARM, COMPUTER, AND SECURITY SYSTEM SHALL BE PROVIDED WITH APPROPRIATE COVER PLATES.
- BOXES FOR TELEPHONE, COMPUTER, T.V., FIRE ALARM, SECURITY, AND SIMILAR SYSTEMS SHALL BE MINIMUM 2-1/8" DEEP.

G. WIRING DEVICES

- WALL SWITCHES SHALL BE SPECIFICATION GRADE AC SILENT TYPE SWITCHES, 20A 120/277 VOLT. RECEPTACLES SHALL BE SPECIFICATION GRADE, DUPLEX TYPE. NEMAS-20R, 20 AMPERE, 120VOLT GROUNDED TYPE. SPECIAL APPLICATION RECEPTACLES SHALL BE INDICATED ON PLANS. MOUNT WITH THE GROUND DOWN.
- DEVICE PLATES SHALL BE EQUAL TO SIERRA SMOOTH-LINE PLASTIC WALL PLATES. COLOR SHALL BE WHITE, UNLESS OTHERWISE NOTED.
- RECEPTACLES IN OUTDOOR AND WET LOCATIONS SHALL BE INSTALLED WITH A HINGED OUTLET COVER/ENCLOSURE CLEARLY MARKED AND U.L. LISTED SUITABLE FOR WET LOCATIONS WHILE IN USE, EQUAL TO TAYMAC SPECIFICATION GRADE.

H. SERVICE ENTRANCE SECTION

- THE SERVICE ENTRANCE EQUIPMENT SHALL BE AS INDICATED ON THE DRAWINGS. EQUIPMENT SHALL CARRY THE U.L. LABEL AND SHALL CONFORM TO THE POWER COMPANY REGULATIONS.
- SERVICE ENTRANCE EQUIPMENT SHALL BE PROVIDED WITH A FULLY RATED COPPER OR ALUMINUM BUS. HORIZONTALLY TAPERED BUSSING SHALL NOT BE ALLOWED.

I. DISTRIBUTION PANELS

- DISTRIBUTION PANELS SHALL BE PROVIDED WITH FULLY RATED COPPER OR ALUMINUM BUS. HORIZONTAL TAPERED BUSSING SHALL NOT BE ALLOWED.
- ACCEPTABLE MANUFACTURERS – CUTLER HAMMER, SIEMENS, SQUARE D OR GENERAL ELECTRIC
- FACTORY ASSEMBLED DEAD FRONT, METAL ENCLOSED, AND SELF-SUPPORTING SWITCH BOARD ASSEMBLY CONFORMING T NEMA PB 2 AND UL 891, AND COMPLETE FROM INCOMING LINE TERMINALS TO LOAD SIDE TERMINATIONS.
- LINE AND LOAD TERMINATIONS: ACCESSIBLE FROM FRONT ONLY OF THE SWITCH BOARD. SUITABLE FOR CONDUCTOR MATERIALS AND NUMBER OF CONDUCTORS USED.
- BUS CONNECTIONS: BOLTED, ACCESSIBLE FROM FRONT FOR MAINTENANCE. PROVIDE BELLEVILLE WASHERS FOR PROPERLY TORQUE ALL CONNECTIONS
- PROVIDE FULLY-RATED NEUTRAL BUS AND FULLY RATED GROUND BUS MATCHING MATERIAL USED FOR MAIN BUS.
- FUTURE PROVISIONS: FULLY EQUIP SPACES FOR FUTURE DEVICES WITH BUSSING AND BUS CONNECTIONS SUITABLY INSULATED AND BRACED FOR SHORT CIRCUIT CURRENTS. CONTINUOUS CURRENT RATING AS INDICATED ON DRAWINGS.
- ALL CIRCUIT BREAKERS SHALL BE BOLT-ON TYPE.

J. PANEL BOARDS

- CIRCUIT BREAKER TYPE AS INDICATED ON DRAWINGS, UNLESS INDICATED OTHERWISE, ALL PANELS SHALL HAVE PANEL HAVE PANEL BOARD TYPE CONSTRUCTION WITH BOLT-ON CIRCUIT BREAKERS FOR 3ø PANELS
- MANUFACTURERS SHALL BE GENERAL ELECTRIC, SQUARE D, SIEMENS, CUTLER-HAMMER WITH VOLTAGE, SIZES, AND RATINGS AS INDICATED ON DRAWINGS.
- THE CIRCUIT BREAKERS SHALL BE OPERABLE IN ANY POSITION AND BE REMOVABLE FROM THE FRONT OF THE PANEL BOARD WITHOUT DISTURBING THE ADJACENT UNITS. BRANCH BREAKERS SHALL BE OF SUCH DESIGN THAT COMBINATION OF SINGLE-POLE, DOUBLE-POLE, AND THREE-POLE BREAKERS CAN BE ASSEMBLED ON THE SAME PANEL. EACH BRANCH CIRCUIT SHALL BE CLEARLY NUMBERED. BRANCH AND MAIN TERMINALS SHALL BE OF THE SOLDERLESS TYPE. HANDLE TIES TO FORM MULTI-POLE BREAKERS NOT ACCEPTABLE. A. CIRCUIT BREAKERS SHALL BE PLUG-IN TYPE

K. LOAD CENTER

- CIRCUIT BREAKER TYPE AS INDICATED ON DRAWINGS. MANUFACTURERS SHALL BE GENERAL ELECTRIC, SQUARE D, SIEMENS, CUTLER-HAMMER/EATON WITH VOLTAGE, SIZES, AND RATINGS AS INDICATED ON DRAWINGS.
- THE CIRCUIT BREAKERS SHALL BE OPERABLE IN ANY POSITION AND BE REMOVABLE FROM THE FRONT OF THE PANEL BOARD WITHOUT DISTURBING THE ADJACENT UNITS. BRANCH BREAKERS SHALL BE OF SUCH DESIGN THAT COMBINATION OF SINGLE-POLE AND DOUBLE-POLE BREAKERS CAN BE ASSEMBLED ON THE SAME PANEL. EACH BRANCH CIRCUIT SHALL BE CLEARLY NUMBERED. BRANCH AND MAIN TERMINALS SHALL BE OF THE SOLDERLESS TYPE. HANDLE TIES TO FORM MULTI-POLE BREAKERS NOT ACCEPTABLE. A. CIRCUIT BREAKERS SHALL BE PLUG-IN TYPE
- WIRE TERMINATION FOR PANEL BOARDS AND CIRCUIT BREAKERS SHALL BE LISTED AS SUITABLE FOR 75 DEGREES C.
- PROVIDE A TYPEWRITTEN CIRCUIT INDEX BEHIND CLEAR PLASTIC COVER ON INSIDE OF DOOR. INFORMATION SHALL INCLUDE ROOM AND TYPE LOAD SERVED. ALL CIRCUIT BREAKERS SHALL BE IDENTIFIED, INCLUDING SPARES. INDEX CARD FRAME SHALL BE METAL, SECURED TO DOOR.
- PANEL BOARDS/LOAD CENTERS TO BE PROVIDED WITH COPPER BUSSING ONLY.

L. LIGHTING FIXTURES

- PROVIDE ALL LIGHTING FIXTURES, WIRED AND CONNECTED. THE DRAWINGS INDICATE THE FIXTURES FOR EACH LOCATION. PROVIDE LAMPS FOR ALL FIXTURES. THE LAMPS SHALL BE BY THE SAME MANUFACTURER. VERIFY CEILING CONSTRUCTION BEFORE ORDERING RECESSED UNITS. PROVIDE PLASTER FRAMES AND HANGERS AS REQUIRED. CEILING CONSTRUCTION, ARCHITECTURAL ACCESSORIES, VOLTAGE, AND BALLASTS TO MEET THE EXISTING CEILING CONDITION.

M. LIGHTING CONTROL

- FURNISH AND INSTALL TIME SWITCHES, PHOTOCELLS, CONTRACTORS AND FULL LIGHTING CONTROL SYSTEMS AS REQUIRED FOR LIGHTING CONTROLS INDICATED ON THE DRAWINGS.
- TIME SWITCHES SHALL BE EQUAL TO PARAGON, GENERAL ELECTRIC, TORK, OR INTERMATIC AND SHALL HAVE SIZE AND NUMBER OF POLES AS REQUIRED.
- PHOTOCELLS SHALL BE EQUAL TO TORK OR INTERMATIC WITH VOLTAGE AS INDICATED.

N. TELEPHONE AND CABLE TELEVISION SYSTEMS

- TELEPHONE WALL OUTLETS SHALL CONSIST OF STANDARD BOXES MOUNTED 18" ABOVE THE FLOOR UNLESS OTHERWISE INDICATED. PROVIDE A TERMINAL MOUNTING BOARD FOR THE INCOMING SERVICE CABLE.
- CABLE TELEVISION OUTLETS SHALL CONSIST OF STANDARD BOXES MOUNTED 18" ABOVE THE FLOOR UNLESS OTHERWISE INDICATED. PROVIDE A TERMINAL MOUNTING BOARD FOR THE INCOMING SERVICE CABLE.

O. GUARANTEE

- GUARANTEE ALL MATERIAL FURNISHED AND ALL WORKMANSHIP PERFORMED FOR A PERIOD OF ONE YEAR FROM DATE OF FINAL ACCEPTANCE OF WORK. ANY DEFECTS DEVELOPING WITHIN THIS PERIOD, TRACEABLE TO MATERIAL FURNISHED AS A PART OF THIS SECTION OR WORKMANSHIP PERFORMED HEREUNDER, SHALL BE MADE GOOD AT NO EXPENSE TO THE OWNER.

SYMBOLS LEGEND

NOTE: THIS IS A MASTER LEGEND AND NOT ALL SYMBOLS, ETC, ARE NECESSARILY USED ON THE DRAWINGS.

LIGHTING FIXTURES – SYMBOL/LETTER INDICATES LIGHT FIXTURE AS INDICATED ON FIXTURE SCHEDULE

- LED FIXTURE (SEE LIGHTING FIXTURE SCHEDULE)
- FIXTURE WITH EMERGENCY BATTERY DRIVER UNIT
- TRACK LIGHT
- DOWNLIGHT FIXTURE WITH EMERGENCY BATTERY DRIVER UNIT
- WALL MOUNTED FIXTURE WITH EMERGENCY BATTERY DRIVER UNIT
- PENDANT MOUNTED FIXTURE WITH EMERGENCY BATTERY DRIVER UNIT
- DOWNLIGHT FIXTURE
- WALL MOUNTED FIXTURE
- PENDANT MOUNTED FIXTURE
- WALL WASHER
- SINGLE FACE EXIT SIGN – UNIVERSAL MOUNTED
- SINGLE FACE EXIT SIGN W/ DIRECTIONAL ARROWS – UNIVERSAL MTD
- DOUBLE FACE EXIT SIGN W/ DIRECTIONAL ARROWS – UNIVERSAL MTD
- DUAL HEADED EMERGENCY UNIT
- COMBO DUAL HEADED EMERGENCY AND EXIT SIGN UNIT

LIGHTING CONTROLS

- S SINGLE POLE SWITCH @ +48" UNLESS NOTED
- Sabc SWITCH BANK @ +48" UNLESS NOTED. LOWER CASE LETTER INDICATES FIXTURE CONTROLLED.
- S3 3-WAY SWITCH @ +48" UNLESS NOTED
- S4 4-WAY SWITCH @ +48" UNLESS NOTED
- SD DIMMER SWITCH – SIZE AS REQUIRED @ +48" UNLESS NOTED
- Sm MANUAL MOTOR STARTER
- Sos WALL SWITCH WITH OCCUPANCY SENSOR. DIGITAL LOW VOLTAGE WALL SWITCH. SWITCH @ +48" UNLESS NOTED.
- SLV TWO BUTTON DIGITAL LOW VOLTAGE WALL SWITCH. PROVIDES ON/OFF/0-10V DIMMING. SWITCH @ +48" UNLESS NOTED. PROVIDE EXTRA CONTROL CABLES NEEDED TO FIXTURE CONTROLLED.
- CS LIGHTING CONTROLS CEILING MOUNT OCCUPANCY SENSOR
- PC LIGHTING CONTROLS POWER PACK
- PH PHOTOCELL
- TC TIMECLOCK

POWER DISTRIBUTION

- SWITCHBOARD, MOTOR CONTROL CENTER OR DISTRIBUTION BOARD
- 277/480V, 3 PHASE, 4 WIRE PANELBOARD, UNO
- 120/208V, 3 PHASE, 4 WIRE PANELBOARD, UNO
- 120/240V, 1 PHASE, 3 WIRE PANELBOARD, UNO
- TRANSFORMER

POWER DEVICES

- SPECIAL HEAVY DUTY RECEPTACLE – SIZE AS NOTED. @ +18" UNLESS NOTED
- 1/2 SWITCHED RECEPTACLE @ +18" UNLESS NOTED
- FIRE RATED POKE THRU WITH TYPE INDICATED
- FLUSH FLOOR BOX WITH TYPE INDICATED
- SINGLE RECEPTACLE @ +18" UNLESS NOTED
- DUPLEX RECEPTACLE @ +18" UNLESS NOTED
- DOUBLE DUPLEX RECEPTACLE @ +18" UNLESS NOTED
- DUPLEX RECEPTACLE INSTALLED ABOVE COUNTERTOP
- GFCI-RATED DUPLEX RECEPTACLE
- ARC FAULT RATED DUPLEX RECEPTACLE
- TAMPER RESISTANT RATED DUPLEX RECEPTACLE
- DUPLEX RECEPTACLE WITH WEATHERPROOF COVERPLATE @ 18" UNLESS NOTED
- JUNCTION BOX
- DISCONNECT SWITCH – SIZE AND TYPE NOTED
- COMBINATION FUSED STARTER DISCONNECT SWITCH FUSE SIZE AS INDICATED, STARTER SIZE '1'

AUXILIARY SYSTEMS

- MECHANICAL EQUIP. CONNECTION, SEE SCHED. ON MECH. PLAN
- TELEPHONE OUTLET @ +18" UNLESS NOTED
- DATA OUTLET @ +18" UNLESS NOTED
- COMBINATION TELEPHONE/DATA OUTLET @ +18" UNLESS NOTED
- TELEVISION OUTLET @ +60" UNLESS NOTED
- SMOKE DETECTOR
- HEAT DETECTOR
- DUCT SMOKE DETECTOR
- REMOTE TEST STATION WITH INDICATING LIGHT. MOUNT AT 48" AFF UNO.
- AUXILIARY SYSTEM TERMINAL CABINET


GENERAL

- CONDUIT RUN CONCEALED IN WALL OR ABOVE CEILING
- CONDUIT RUN BELOW FLOOR OR GRADE

P1-3,5,7 HOMERUN TO PANELBOARD, INFORMATION AT ARROWS ARE CIRCUIT NUMBERS AND PANELBOARD FOR TERMINATION. REFER TO ASSOCIATED NOTE FOR BRANCH CIRCUIT CONDUCTOR SIZES.

INDICATES 1/2" CONDUIT CONCEALED IN CEILING OR WALL WITH (3) CONDUCTORS. (1) PHASE, (1) NEUTRAL AND (1) GROUND WIRE. ALL ARE #12 AWG UNLESS NOTED OTHERWISE.

(E) OR ETR: DENOTES EXISTING ITEM/EQUIPMENT TO REMAIN



MO COA NO. 20160007861 / JS COA NO. E-2818  
1925 CENTRAL ST. SUITE #201  
KANSAS CITY, MO 64108  
phone: (816) 272-8289  
email: jsc@jscengineers.com



POOL HOUSE STRUCTURE  
LEE'S SUMMIT, MO

PROJECT:

REVISIONS:	DATE	DESCRIPTION
1		
2		
3		
4		
5		

Copyright 2021  
JSC Engineers

ISSUED:

PERMIT

SHEET TITLE:

ELECTRICAL  
SPECIFICATIONS

DATE: 05.20.2022


JOB NO.: 22-133

SHEET:

E0.1




ELECTRICAL LIGHTING SCHEDULE							
FIXTURE TYPE	MANUFACTURER		VOLT AMPS	MOUNTING	LAMP TYPE	REMARKS	VOLT
	NAME	CATALOG NUMBER					
A	LITHONIA	VAP-600LM-FST-MD-MVOLT-40K-80CRI-VAP5MB-WLF-DL-STSL-MSI02L3VWL	50	SURFACE CEILING	INCLUDED LED 4000K	VANDAL RESISTANT LED 4' DAMP LOCATION STRIP LUMINAIRE	120
B	LITHONIA	LDN6-30/15-L06-LSS-MVOLT-30K	17.5	RECESSED CEILING	INCLUDED LED 3000K	6' LED RECESSED DOWNLIGHT - WET LOCATION LISTED	120
W	EXTERIOR SCONCE	OWNER SELECTED	60	WALL SURFACE	INCLUDED LED 3000K	WET LOCATION RATED SCONCE - MAX 60W/FIXTURE	120
	LITHONIA	WLTU LED	5	SURFACE CEILING	INCLUDED	LED COMBO EXIT SIGN EMERGENCY LUMINAIRE WITH 90 MIN BATT. PACK WET LOCATION	120
	LITHONIA	ELA LED TWP M12	3	WALL	INCLUDED	OUTDOOR DOUBLE REMOTE HEAD EMERGENCY EGRESS LUMINAIRE	120



## SINGLE LINE DIAGRAM

SCALE: NO SCALE




## ELECTRICAL LIGHTING PLAN

SCALE: 1/4" = 1'-0"

PANEL: P				VOLTAGE: 240/120V				1PH, 3W				CIRCUIT CODES: 1=(CONTINUOUS LOAD)											
LOCATION: EQUIPMENT ROOM				BUS: 200 AMPS				MAIN: M.L.O				2=(NON-CONTINUOUS LOAD)											
SHEET/1 LINE: E1.1				MOUNTING: SURFACE								3=(RECEPTACLES)											
AIC RATING: 42,000												4=(KITCHEN EQUIPMENT)											
CKT	CB	LOAD DESIGNATION				LOAD				PHASES				LOAD				LOAD DESIGNATION				CB	CKT
NO.	TRIP	POLE	DESCRIPTION				MISC	REC	LITE	VA	A	B	VA	LITE	MISC	DESCRIPTION				POLE	TRIP	NO.	
1	2	30	1	EWH-1				X			2400	2914	514	X		INDOOR LIGHTING&EXHAUST FANS				1	20	1	
2	3	30	1	EWH-2				X			2400	2800	400	X		OUTDOOR LIGHTING				1	20	1	
3	20	1	RESTROOM&BREEZEWAY OUTLETS				X			360	730	370	370	X		"GF" RCPT - DRINKING FOUNTAIN				1	20	1	
5	3	20	1	EF-3				X			72	612	540	X		EQUIPMENT ROOMS OUTLETS				1	20	3	
7	1	15	1											X		RCPT - PERGOLA STRING LIGHTS				1	20	8	
9			SPACE								500	500	500	X		PWR - SITE FIXTURE				1	20	2	
11			SPACE								500	500	500	X		SPACE				1	20	2	
13			SPACE								0	0	0			SPACE				1	20	2	
15			SPACE								0	0	0			SPACE				1	20	2	
17			SPACE								0	0	0			SPACE				2	18	2	
19			SPACE								0	0	0			SPACE				2	18	2	
21			SPACE								0	0	0			SPACE				2	22	2	
23			SPACE								0	0	0			SPACE				2	24	2	
25			SPACE								0	0	0			SPACE				2	26	2	
27			SPACE								0	0	0			SPACE				2	28	2	
29			SPACE								0	0	0			SPACE				2	30	2	
31			SPACE								0	0	0			SPACE				2	32	2	
33			SPACE								0	0	0			SPACE				2	34	2	
35			SPACE								0	0	0			SPACE				2	36	2	
37			SPACE								0	0	0			SPACE				2	38	2	
39			SPACE								0	0	0			FUTURE POOL PANEL				100	2	40	
41			SPACE								0	0	0			/(SHUNT TRIP TYPE BREAKER)				2	2	42	
TOTAL											4144	3912											
NOTES:																							
"GF" = GFCI TYPE BREAKER																							
											CONNECTED KVA 8.1												
											CONN.KVA (CODE 1) 1.4												
											CONN.KVA (CODE 2) 5.8												
											CONN.KVA (CODE 3) 0.9												
											CONN.KVA (CODE 4) 0.0												
JOB NAME: LSMO POOLHOUSE											FEEDER DEMAND KVA 8.4												
ISSUE DATE: 05.18.22											FEEDER DEMAND AMPS 35.0												

## PANELBOARD SCHEDULES

SCALE: NO SCALE



## ELECTRICAL POWER PLAN


SCALE: 1/4" = 1'-0"

## GENERAL NOTES


- REFER TO LIGHTING FIXTURE SCHEDULE FOR LIGHT FIXTURE TYPES AND REQUIREMENTS.
- CONNECT ALL EXIT SIGNS AND EMERGENCY LIGHTING UNITS TO THE INDICATED CIRCUIT WITH A SEPARATE AND UN-SWITCHED CONDUCTOR BYPASSING ALL CONTROLS AND CONTACTORS. REFER TO MANUFACTURER'S WRITTEN INSTRUCTIONS FOR PROPER INSTALLATION AND TESTING.
- CONTRACTOR SHALL BE RESPONSIBLE FOR ENSURING THAT COORDINATION AND CONFLICT ISSUES BE RESOLVED PRIOR TO INSTALLATION OF LIGHT FIXTURES.
- ROUTE ALL EXPOSED, RIGID CONDUIT TIGHT TO STRUCTURE, PARALLEL TO BUILDING LINES AND IN UNISTRUT CABLE/PIPE TRAY WHERE POSSIBLE. COORDINATE CONDUIT ROUTING AND INSTALLATION WITH OTHER TRADES PRIOR TO ROUGH-IN. SUPPORT CONDUIT FROM STRUCTURE NOT ROOF DECK. MAINTAIN 2" MIN SPACING FROM BOTTOM OF ROOF DECK TO PREVENT ROOFING SCREWS FROM PENETRATING CONDUITS.
- THROUGH WIRING OF RECESSED LIGHT FIXTURES, IN SUSPENDED CEILINGS, IS NOT PERMITTED. CONNECT EACH LIGHT FIXTURE BY A WHIP TO A JUNCTION BOX. PROVIDE CABLE WHIPS OF SUFFICIENT LENGTH TO ALLOW FOR RELOCATING EACH LIGHT FIXTURE WITHIN A 5-FOOT RADIUS OF ITS INSTALLED LOCATION, BUT NOT EXCEEDING 6 FEET IN UNSUPPORTED LENGTH.
- ALL INTERNALLY ILLUMINATED SIGNS SHALL BE PROVIDED WITH AN ACCESSIBLE DISCONNECTION MEANS. VERIFY EACH SIGN IS FURNISHED WITH AN INTEGRAL DISCONNECT SWITCH. PROVIDE WEATHERPROOF DISCONNECT SWITCHES WITHIN SIGHT OF ALL SIGNS AS REQUIRED. MAKE FINAL CONNECTION AS REQUIRED.

## KEYED PLAN NOTES

- PROVIDE NEW CONDUCTORS TO UTILITY SOURCE. VERIFY EXACT LOCATION AND REQUIREMENTS WITH UTILITY PRIOR TO ROUGH-IN.
- PROVIDE NEW UTILITY METER PER UTILITY REQUIREMENTS.
- NEW DISCONNECT PER UTILITY REQUIREMENTS.
- PROVIDE NEW GROUND PER NEC 250.52(A)(1).
- PROVIDE NEW GROUND PER NEC 250.52(A)(2).
- PROVIDE NEW GROUND PER NEC 250.52(A)(3).
- PROVIDE MOTOR RATED SWITCH DESIGNED TO OPERATE CONTINUOUSLY.
- PROVIDE MOTOR RATED SWITCH DESIGNED TO OPERATE CONTINUOUSLY. CONNECT TO LIGHTING CIRCUIT FOR SIMULTANEOUS OPERATION.
- CONNECT TO INSTA-HOT PER MECHANICAL PLANS AND MANUFACTURER REQUIREMENTS.
- (1) 1/2" W/ 2 #10 & 1 #12 GND.
- MOUNT RECEPTACLE TO PERGOLA STRUCTURE AND ROUTE CONDUIT IN DISCRETE MANNER FOR AVAILABILITY FOR PLUG-IN PERGOLA LIGHTING. COORDINATE EXACT MOUNTING LOCATION WITH ARCHITECT.
- PROVIDE PHOTOCELL MOUNTED TO ROOF STRUCTURE AND POINTED NORTH. COORDINATE EXACT LOCATION WITH ARCHITECT. ROUTE CIRCUIT THROUGH PHOTOCELL EN ROUTE TO BREAKER TERMINATION.
- NORMALLY-CLOSED OVERRIDE SWITCHES FOR EXTERIOR CANOPY LIGHTING (CKT P-4) AND PLUG-IN CANOPY LIGHTING (CKT P-10). ROUTE CIRCUITS THROUGH RESPECTIVE OVERRIDE SWITCHES EN ROUTE TO BREAKER TERMINATION.
- PROVIDE CONDUIT UNDERGROUND TO JUNCTION BOX FOR FUTURE SITE POLE BY OTHERS. COORDINATE EXACT LOCATION WITH OWNER PRIOR TO CONSTRUCTION.



MO COA NO. 201200356 / KS COA NO. E-2818  
1925 CENTRAL ST. SUITE #201  
KANSAS CITY, MO 64108  
phone: (816) 272-8289  
email: jsmothers@jscengineers.com



PROJECT: POOL HOUSE STRUCTURE  
LEE'S SUMMIT, MO

REVISIONS:	DATE / DESCRIPTION
1	
2	
3	
4	
5	

Copyright 2021  
JSC Engineers

ISSUED:

PERMIT

SHEET TITLE:

ELECTRICAL PLANS

DATE: 05.20.2022  
JOB NO.: 22-133  
SHEET:

E1.1