

# FINAL STORMWATER REPORT

## Automotive Sales & Detail Center 2100 NE Independence Avenue Lee's Summit, Missouri 64064

Prepared For:


Lee's Summit Town Center, LLC  
Bob Balderston  
3200 NW South Outer Road  
Blue Springs, MO 64015

Prepared by:

### DAVIDSON ARCHITECTURE & ENGINEERING, LLC

Paul A. Miller, P.E.  
4301 Indian Creek Parkway  
Overland Park, Kansas 66207  
913.451.9390 (phone)  
913.451.9391 (fax)  
[www.davidsonae.com](http://www.davidsonae.com)

Prepared: 02.20.2020  
Revised: 03.23.2020  
Revised: 06.19.2020  
Revised: 11.05.2020  
Revised: 01.22.2021  
Revised: 06.09.2022



Project No. 19076

## Table of Contents

General Information.....	1
Methodology.....	1
Existing Condition Analysis.....	2
Proposed Condition Analysis.....	3
Summary.....	3

## Appendices

### Appendix A – Supporting Data

- Hydrological Soil Group
- FEMA FIRM
- Sheet C3.1 – Existing Drain Area Map
- Sheet C3.2 – Proposed Drain Area Map
- Sheet C3.3 – Storm Plan & Profile

### Appendix B – Existing Conditions Hydraflow Hydrographs Output Data

### Appendix C – Proposed Conditions Hydraflow Hydrographs Output Data

## GENERAL INFORMATION

The proposed commercial development for Lee's Summit Town Center, LLC is located northwest of the intersection of Town Center Drive and Independence Avenue. The total area for the development is this property is approximately 5.57 acres.

The current site soil condition for this property is classified as "Greenton-Urban, 5 to 9 percent Slopes", with a Map Unit Symbol of '10024'. The hydrological soil group for this site is Class D. The site lies entirely within 'Zone X', areas determined to be outside the 0.2% annual chance floodplain as depicted on the FEMA Flood Insurance Rate Map (FIRM) no. 29095C0430G, Revision Date: January 20, 2017.



Figure 1 – Location Map (no scale)

## METHODOLOGY

KCAPWA IDF curves were used to determine the rainfall intensity for 2, 10, and 100-year storm events. Hydraflow Hydrographs Extension for AutoCAD 2020 was used to determine runoff flow amounts for existing and proposed site conditions. Hydraflow computes the rational method runoff hydrographs by convoluting a rainfall hyetograph through a unit hydrograph. Convolution is known as linear superpositioning where each ordinate of the rainfall hyetograph is multiplied by each ordinate of the unit hydrograph, thus creating a series of hydrographs. These hydrographs are then summed to form the final runoff hydrograph.

## EXISTING CONDITIONS

The existing project site location is 5.57 acres, with the entirety of the property being pervious area. Runoff from this site flows from the northwest of the property to east. For analysis, the majority of the undeveloped area, encompassed by NE Town Center Boulevard was taken into consideration for runoff volume contribution. The resulting area is approximately 29.35 acres of pervious area. The area for the two existing ponds was added to the overall impervious area contributing to runoff. The total runoff volume, including the areas for the existing ponds, will be considered for the detention ponds design.

An existing storm inlet at the east end of the property along NE Independence Avenue allows runoff to be conveyed east toward an existing dedicated drainage area. Refer to Sheet C3.1 “Existing Drainage Map” in Appendix A for the existing drainage patterns for the property.

**Table 1** below shows the peak discharges for the 2, 10, and 100-year rainfall events. Refer to Appendix B for Complete Hydraflows Report and results for the existing site conditions.

<b>Table 1 – Existing Site Runoff Hydraflow Results</b>	
<b>Storm Event</b>	<b>Pre-developed Peak Flow (cfs)</b>
2-Yr	34.18
10-Yr	47.72
100-Yr	71.89

## PROPOSED CONDITIONS

The existing property will undergo development for a proposed commercial area for Lee's Summit Town Center LLC. The proposed development will increase the impervious area from 0.60 acres to 2.90 acres, with the remaining 29.35 acres as open grass area. Refer to sheet C3.2 "Proposed Drainage Map" in Appendix A for the proposed drainage patterns for the property. The runoff will be collected and conveyed to a detention pond by way of natural topography and proposed storm sewer network where the existing storm inlet, at the eastern edge of the property, will further convey the runoff towards the existing dedicated drainage area.

**Table 2** shows the increase in peak discharge rates for the 2, 10, and 100-year storms rainfall events, due to the increase in impervious area.

Storm Event	Pre-developed Peak Flow (cfs)
2-Yr	39.21
10-Yr	53.77
100-Yr	89.21

In order to mitigate the increase in discharge rates from the site due to the increase in impervious area created by the proposed development, two separate storm networks are proposed to direct runoff to the existing drainage area via the existing storm inlet at the east edge of the property.

**Table 3** shows the resulting discharge rates for the 2, 10, and 100-year rainfall events with the proposed storm networks and detention pond.

Storm Event	Post-developed Peak Flow (cfs)
2-Yr	1.04
10-Yr	1.37
100-Yr	5.83

Hydraflow Hydrographs Extension for AutoCAD civil 3D was used to model the post developed site with the proposed storm system. A complete hydrograph can be found in Appendix C.

The above mentioned methodology was used to design the proposed detention pond to effectively capture and discharge the total runoff from the contributing drainage area, per the requirements set by APWA Section 5601.5.A.4.a. The discharge rates are controlled by a proposed storm structure to maintain release rates less than the rates, while also achieving water quality requirements indicated within APWA Section 5608.4.C.1, where post-development peak discharge rates shall not exceed those indicated below:

- 50% storm peak rate less than or equal to 0.5 cfs per acre
  - Site specific allowable release rate: 14.68
- 10% storm peak rate less than or equal to 2.0 cfs per acre
  - Site specific allowable release rate: 58.7
- 1% storm peak rate less than or equal to 3.0 cfs per acre
  - Site specific allowable release rate: 88.05

The above site specific release rates are considerably high due to the large area that is under consideration for detention design. Using a larger time of concentration for the undeveloped areas provides skewed release rates as the developed area is conveyed through the system before the additional impact of the undeveloped areas, yielding in a reduction in release rates for post-development conditions. Adjusting time of concentration to allow for contribution from the undeveloped grass land before developed area is released allows a more intuitive understanding of overall volume of runoff to be detained and released.

The design of the detention basin and outlet elevations were determined by using varying rainfall events to both effectively discharge the collected runoff and meeting water quality requirements.

For water quality design consideration, a perforated riser is proposed to reach the water quality rainfall event elevation. Perforations within the riser allow for a controlled discharge from the detention pond through the proposed storm network, meeting the minimum forty-hour extended detention requirement for comprehensive control.

Any overflow from the existing pond to the west will be collected and routed via a proposed earthen drainage swale to the north of the proposed development, and then to the detention pond. Outlet pipes convey storm water to existing infrastructure leading to an existing detention area to the east.

A spillway for the proposed detention pond was designed using the 100-yr water surface elevation of 983.93'. Manipulating the design within the Hydraflows program to simulate clogged conditions and zero available storage the spillway crest elevation was set 0.5' above the 100-yr water surface elevation at 986.41'. One foot of freeboard is available above the 100-yr water surface elevation to the top of the berm at 987'. The emergency spillway will allow the overflow to drain towards NE Independence Ave, and into the existing storm infrastructure.

## SUMMARY

The proposed commercial development for Lee's Summit Town Center, LLC is located northwest of the intersection of Town Center Drive and Independence Avenue increases the amount of impervious area within the property. To account for the increase in runoff, storm networks and a detention basin have been designed to maintain the discharge rates below existing conditions flow rates.

Off-site contributions to runoff have been considered for the detention pond design. Outlet pipes and structures control peak discharge rates to less than that of existing conditions, while also meeting water quality requirements for the water quality rainfall event.

Table 4 below provides the discharge rates for the existing and post developed conditions for the 2, 10, and 100-year rainfall events for this site.

<b>Table 4 – Total Runoff Volume Comparison</b>			
Storm Event (yr)	Pre-development Discharge (cfs)	Post-development Discharge (cfs)	Difference (cfs)
2	34.18	1.04	33.14
10	47.72	1.37	46.35
100	71.89	5.83	66.06


**Appendix A**  
**Supporting Data**



Soil Map—Jackson County, Missouri



Map Scale: 1:961 if printed on A portrait (8.5" x 11") sheet.



## MAP LEGEND

### Area of Interest (AOI)

 Area of Interest (AOI)

### Soils

 Soil Map Unit Polygons

 Soil Map Unit Lines

 Soil Map Unit Points

### Special Point Features



Blowout



Borrow Pit



Clay Spot



Closed Depression



Gravel Pit



Gravelly Spot



Landfill



Lava Flow



Marsh or swamp



Mine or Quarry



Miscellaneous Water



Perennial Water



Rock Outcrop



Saline Spot



Sandy Spot



Severely Eroded Spot



Sinkhole



Slide or Slip



Sodic Spot



Spoil Area



Stony Spot



Very Stony Spot



Wet Spot



Other



Special Line Features

### Water Features



Streams and Canals

### Transportation



Rails



Interstate Highways



US Routes



Major Roads



Local Roads

### Background



Aerial Photography

## MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service

Web Soil Survey URL:

Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Jackson County, Missouri

Survey Area Data: Version 20, Sep 16, 2019

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Sep 6, 2019—Nov 16, 2019

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

## Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
10024	Greenton-Urban land complex, 5 to 9 percent slopes	4.0	98.8%
10128	Sharpsburg-Urban land complex, 2 to 5 percent slopes	0.0	1.2%
<b>Totals for Area of Interest</b>		<b>4.0</b>	<b>100.0%</b>

**NOTES TO USERS**

This map is for use in administering the National Flood Insurance Program. It does not necessarily identify all areas subject to flooding, particularly from local drainage sources of small size. The community map repository should be consulted for possible updated or additional flood hazard information.

To obtain more detailed information in areas where **Base Flood Elevations (BFEs)** and/or **floodways** have been determined, users are encouraged to consult the Flood Profiles and Floodway Data and/or Summary of Stillwater Elevations tables contained within the Flood Insurance Study (FIS) Report that accompanies this FIRM. Users should be aware that BFEs shown on the FIRM represent rounded whole-foot elevations. These BFEs are intended for flood insurance rating purposes only and should not be used as the sole source of flood elevation information. Accordingly, flood elevation data presented in the FIS Report should be utilized in conjunction with the FIRM for purposes of construction and/or floodplain management.

Boundaries of the **floodways** were computed at cross sections and interpolated between cross sections. The floodways were based on hydraulic considerations with regard to requirements of the National Flood Insurance Program. Floodway widths and other pertinent floodway data are provided in the Flood Insurance Study Report for this jurisdiction.

Certain areas not in Special Flood Hazard Areas may be protected by **flood control structures**. Refer to Section 2.4 "Flood Protection Measures" of the Flood Insurance Study Report for information on flood control structures for this jurisdiction.

The **projection** used in the preparation of this map was Missouri State Plane West Zone (FIPS zone 2403). The **horizontal datum** was NAD 83, GRS 1980 spheroid. Differences in datum, spheroid, projection or UTM zones used in the production of FIRMs for adjacent jurisdictions may result in slight positional differences in map features across jurisdiction boundaries. These differences do not affect the accuracy of this FIRM.

Flood elevations on this map are referenced to the North American Vertical Datum of 1988. These flood elevations must be compared to structure and ground elevations referenced to the same **vertical datum**. For information regarding conversion between the National Geodetic Vertical Datum of 1929 and the North American Vertical Datum of 1988, visit the National Geodetic Survey website at <http://www.ngs.noaa.gov> or contact the National Geodetic Survey at the following address:

NGS Information Services  
NOAA, NNGS12  
National Geodetic Survey  
SSM-C-3 #2022  
1315 East-West Highway  
Silver Spring, Maryland 20910-3282  
(301) 713-3242

To obtain current elevation, description, and/or location information for **bench marks** shown on this map, please contact the Information Services Branch of the National Geodetic Survey at (301) 713-3242, or visit its website at <http://www.ngs.noaa.gov>.

**Base map** information shown on this FIRM was derived from the U.S.D.A Farm Service National Agriculture Imagery Program (NAIP) dated 2014. Produced at scale of 1:24,000.


The **profile baselines** depicted on this map represent the hydraulic modeling baselines that match the flood profiles in the FIS report. As a result of improved topographic data, the **profile baseline**, in some cases, may deviate significantly from the channel centerline or appear outside the SFHA.

Based on updated topographic information, this map reflects more detailed and up-to-date **stream channel configurations and floodplain delineations** than those shown on the previous FIRM for this jurisdiction. As a result, the Flood Profiles and Floodway Data tables for multiple streams in the Flood Insurance Study Report (which contains authoritative hydraulic data) may reflect stream channel distances that differ from what is shown on the map. Also, the road to floodplain relationships for unrevised streams may differ from what is shown on previous maps.

**Corporate limits** shown on this map are based on the best data available at the time of publication. Because changes due to annexations or de-annexations may have occurred after this map was published, map users should contact appropriate community officials to verify current corporate limit locations.


Please refer to the separately printed **Map Index** for an overview map of the county showing the layout of map panels, community map repository addresses, and a Listing of Communities table containing National Flood Insurance Program dates for each community as well as a listing of the panels on which each community is located.

For information on available products associated with this FIRM visit the **Map Service Center (MSC)** website at <http://msc.fema.gov>. Available products may include previously issued Letters of Map Change, a Flood Insurance Study Report, and/or digital versions of this map. Many of these products can be ordered or obtained directly from the MSC website.



**LEGEND**

- SPECIAL FLOOD HAZARD AREAS (SFHAs) SUBJECT TO INUNDATION BY THE 1% ANNUAL CHANCE FLOOD. The 1% annual chance flood (100-year flood), also known as the base flood, is the flood that has a 1% chance of being equaled or exceeded in any given year. The Special Flood Hazard Area is the area subject to flooding by the 1% annual chance flood. Areas of Special Flood Hazard include Zones A, AE, AH, AO, AR, A99, V, and VE. The Base Flood Elevation is the water-surface elevation of the 1% annual chance flood.
  - ZONE A** No Base Flood Elevations determined.
  - ZONE AE** Base Flood Elevations determined.
  - ZONE AH** Flood depths of 1 to 3 feet (usually areas of ponding); Base Flood Elevations determined.
  - ZONE AO** Flood depths of 1 to 3 feet (usually sheet flow on sloping terrain); average depths determined. For areas of alluvial fan flooding, velocities also determined.
  - ZONE AR** Special Flood Hazard Areas formerly protected from the 1% annual chance flood by a flood control system that was subsequently decreed. Zone AR indicates that the former flood control system is being restored to provide protection from the 1% annual chance or greater flood.
  - ZONE A99** Area to be protected from 1% annual chance flood by a Federal flood protection system under construction; no Base Flood Elevations determined.
  - ZONE V** Coastal flood zone with velocity hazard (wave action); no Base Flood Elevations determined.
  - ZONE VE** Coastal flood zone with velocity hazard (wave action); Base Flood Elevations determined.
  - FLOODWAY AREAS IN ZONE AE
  - The floodway is the channel of a stream plus any adjacent floodplain areas that must be kept free of encroachment so that the 1% annual chance flood can be carried without substantial increases in flood heights.
  - OTHER FLOOD AREAS
  - ZONE X** Areas of 0.2% annual chance flood; areas of 1% annual chance flood with average depths of less than 1 foot or with drainage areas less than 1 square mile; and areas protected by levees from 1% annual chance flood.
  - OTHER AREAS**
  - ZONE D** Areas determined to be outside the 0.2% annual chance floodplain.
  - ZONE D** Areas in which flood hazards are undetermined, but possible.
  - COASTAL BARRIER RESOURCES SYSTEM (CBRS) AREAS
  - OTHERWISE PROTECTED AREAS (OPAs)
  - CBRS areas and OPAs are normally located within or adjacent to Special Flood Hazard Areas.
  - 1% Annual Chance Floodplain Boundary
  - 0.2% Annual Chance Floodplain Boundary
  - Floodway boundary
  - Zone D boundary
  - CBRS and OPA boundary
  - Boundary dividing Special Flood Hazard Area Zones and boundary dividing Special Flood Hazard Areas of different Base Flood Elevations, flood depths, or flood velocities.
  - Base Flood Elevation line and value; elevation in feet\*
  - Base Flood Elevation value where uniform within zone; elevation in feet\*
- \*Referenced to the North American Vertical Datum of 1988
- Cross section line
  - Transect line
  - Culvert
  - Bridge
  - Geographic coordinates referenced to the North American Datum of 1983 (NAD 83) Western Hemisphere
  - 5000-foot ticks: Missouri State Plane West Zone (FIPS Zone 2403), Transverse Mercator projection
  - Bench mark (see explanation in Notes to Users section of this FIRM panel)
  - River Mile
- MAP REPOSITORIES  
Refer to Map Repositories list on Map Index
- EFFECTIVE DATE OF COUNTYWIDE FLOOD INSURANCE RATE MAP  
September 29, 2006
- EFFECTIVE DATE(S) OF REVISION(S) TO THIS PANEL  
January 20, 2017 - to change Special Flood Hazard Areas.



**NATIONAL FLOOD INSURANCE PROGRAM**

**PANEL 0430G**

**FIRM**  
FLOOD INSURANCE RATE MAP  
JACKSON COUNTY,  
MISSOURI  
AND INCORPORATED AREAS

**PANEL 430 OF 625**  
(SEE MAP INDEX FOR FIRM PANEL LAYOUT)

CONTAINS:

COMMUNITY	NUMBER	PANEL	SUFFIX
JACKSON COUNTY	290462	0430	G
LEE'S SUMMIT	290174	0430	G
CITY OF			

Notice to User: The **Map** shown below should be used when placing map orders; the **Community Number** shown above should be used on insurance applications for the subject community.

**MAP NUMBER 29095C0430G**  
**MAP REVISED JANUARY 20, 2017**  
Federal Emergency Management Agency

**Local Benchmarks:** BM-#

**BM-1:** Storm Structure, Manhole Cover  
Elevation: 982.05'  
N: 1013823.1378  
E: 2827361.8656

**BM-2:** Storm Structure, Manhole Cover  
Elevation: 1001.21'  
N: 1013384.7454  
E: 2827199.0101

**Symbol Legend**

- |  |                          |  |                                 |
|--|--------------------------|--|---------------------------------|
|  | sanitary manhole         |  | service transformer (pad mount) |
|  | service cleanout         |  | primary switch gear             |
|  | force main release valve |  | light pole                      |
|  | rectangular structure    |  | cable/phone/data junction box   |
|  | circular structure       |  | street light                    |
|  | fire hydrant             |  | pedestrian street light         |
|  | water valve              |  | electric pole                   |
|  | water meter              |  | guy wire                        |
|  | backflow preventer       |  | end section                     |
|  | natural gas meter        |  |                                 |

**Floodplain Note:**

The site lies entirely within 'Zone X', areas determined to be outside the 0.2% annual chance floodplain as depicted on the FEMA Flood Insurance Rate Map (FIRM) no. 29095C0430G, Revision Date: January 20, 2017.

**Drainage Legend**

- drainage area
- existing flow direction

**Property Legend**

- right of way
- property lines
- easements
- setbacks

**Grading Legend**

- existing minor contour
- existing major contour
- proposed minor contour
- proposed major contour

**Utility Legend**


- existing
- proposed

**Linetypes**

- |  |      |                                      |
|--|------|--------------------------------------|
|  | sanm | sanitary main                        |
|  | sans | sanitary service                     |
|  | ssm  | storm sewer (existing)               |
|  | ssm  | storm sewer (solid wall, proposed)   |
|  | ssm  | storm sewer (solid wall, proposed)   |
|  | ssm  | storm sewer (perforated, proposed)   |
|  | wrm  | water main                           |
|  | wrf  | water service (fire)                 |
|  | wrd  | water service (domestic)             |
|  | wri  | water service (irrigation)           |
|  | gasm | natural gas main                     |
|  | gass | natural gas service schematic        |
|  | elpu | underground primary electric         |
|  | elsu | underground secondary electric       |
|  | elpo | overhead electric                    |
|  | datu | underground cable/phone/data         |
|  | datu | underground cable/phone/data service |
|  |      | fence-chainlink                      |
|  |      | fence-wood                           |
|  |      | fence-barbed wire                    |
|  |      | treeline                             |



**2 Vicinity Map**  
No Scale



**1 Existing Drainage Area Map**  
1"=80'

**Pre-Construction Impervious Area Calculations**

	Square Feet	Acres
Area of Site	1,252,503	28.75
Impervious Area	25,983	0.60
Pervious Area	1,278,486	29.35

Q: 2 year 34.18 cfs  
10 year 47.72 cfs  
100 year 71.89 cfs



A New Facility for  
**Automotive Sales & Detail Center**  
2100 NE Independence Ave  
Lee's Summit, Missouri 64064

date  
drawn by SLM  
checked by PAM  
revisions  
02.16.2021 FDP  
05.04.2021 2  
06.09.2022 3

sheet number  
**C3.1**  
drawing type fdp  
project number 19076

**Local Benchmarks:** BM-#


**BM-1:** Storm Structure, Manhole Cover  
Elevation: 982.05'  
N: 1013823.1378  
E: 2827361.8656

**BM-2:** Storm Structure, Manhole Cover  
Elevation: 1001.21'  
N: 1013384.7454  
E: 2827199.0101


**Floodplain Note:**

The site lies entirely within 'Zone X', areas determined to be outside the 0.2% annual chance floodplain as depicted on the FEMA Flood Insurance Rate Map (FIRM) no. 29095C04306, Revision Date: January 20, 2017.


**Drainage Legend**




**Property Legend**




**Grading Legend**




**Utility Legend**





**Symbol Legend**




**Linetypes**



**2 Proposed Drainage Area Map Detail**



**1 Proposed Drainage Area Map**



**Post-Construction Impervious Area Calculations**

	Square Feet	Acres
Area of Site	1,278,486	29.35
Impervious Area	125,453	2.88
Pervious Area	1,153,033	26.47

Q:	2 year	10 year	100 year
	1.04 cfs	1.40 cfs	5.83 cfs

A New Facility for  
**Automotive Sales & Detail Center**  
2100 NE Independence Ave  
Lee's Summit, Missouri 64064

date  
drawn by SLM  
checked by PAM  
revisions  
02.16.2021 FDP  
05.04.2021 2  
06.09.2022 3

sheet number  
**C3.2**  
drawing type fdp  
project number 19076



**Local Benchmarks:** BM-#

**BM-1:** Storm Structure, Manhole Cover  
Elevation: 982.05'  
N: 1013823.1378  
E: 2827361.8656

**BM-2:** Storm Structure, Manhole Cover  
Elevation: 1001.21'  
N: 1013384.7454  
E: 2827199.0101

**Property Legend**

- right of way
- - - property lines
- - - easements
- - - setbacks

**Grading Legend**

- - - existing minor contour
- - - existing major contour
- - - proposed minor contour
- - - proposed major contour

**Utility Legend**


- - - existing
- - - proposed

**Linetypes**



- sanm sanitary main
- sans sanitary service
- ssm storm sewer (existing)
- ssm storm sewer (solid wall, proposed)
- ssm storm sewer (solid wall, proposed)
- ssm storm sewer (perforated, proposed)
- wtrm water main
- wtrf water service (fire)
- wtrd water service (domestic)
- wtrir water service (irrigation)
- gasm natural gas main
- gass natural gas service schematic
- elpu underground primary electric
- elss underground secondary electric
- elpo overhead electric
- datu underground cable/phone/data
- datss underground cable/phone/data service
- fence-chainlink
- fence-wood
- fence-barbed wire
- treeline

**Symbols**

- ⊙ sanitary manhole
- ⊙ service cleanout
- ⊙ force main release valve
- ⊙ rectangular structure
- ⊙ circular structure
- ⊙ fire hydrant
- ⊙ water valve
- ⊙ water meter
- ⊙ backflow preventer
- ⊙ natural gas meter
- ⊙ service transformer
- ⊙ primary switch gear
- ⊙ light pole
- ⊙ data junction box
- ⊙ street light
- ⊙ pedestrian street light
- ⊙ electric pole
- ⊙ guy wire
- ⊙ end section




**Note:**  
Compacted fill shall be placed to a minimum 18" above the top of the pipe prior to installation.



**Storm Line 1**

**Storm Line 2**



**Storm Plan and Profile**  
V: 1"=10' H: 1"=50'




A New Facility for  
**Automotive Sales & Detail Center**  
2100 NE Independence Ave  
Lee's Summit, Missouri 64064

date 02.02.2020  
drawn by SLM  
checked by PAM  
revisions:  
02.16.2021 FDP  
05.04.2021 2  
06.09.2022 3

sheet number  
**C3.3**  
drawing type fdp  
project number 19076



PROPOSED STAGE STORAGE TABLE				
ELEV	AREA (sq. ft.)	DEPT H (ft)	AVG END INC. VOL. (cu. ft.)	AVG END TOTAL VOL. (cu. ft.)
977.00	823.44	N/A	N/A	0
978.00	1,673.12	1.000	1248.28	1248.28
979.00	2,819.25	1.000	2246.19	3494.47
980.00	4,265.72	1.000	3542.49	7036.95
981.00	6,033.57	1.000	5149.65	12186.60
982.00	8,150.06	1.000	7091.82	19278.41
983.00	10,653.06	1.000	9401.56	28679.97
984.00	13,588.79	1.000	12120.93	40800.90
985.00	17,026.99	1.000	15307.89	56108.79
986.00	21,037.18	1.000	19032.09	75140.87



AS-BUILT STAGE STORAGE TABLE				
ELEV	AREA (sq. ft.)	DEPT H (ft)	AVG END INC. VOL. (cu. ft.)	AVG END TOTAL VOL. (cu. ft.)
977.00	0	N/A	0	0
978.00	232	N/A	77	77
979.00	2,260	1.000	1,072	1,149
980.00	7,193	1.000	4,495	5,644
981.00	9,031	1.000	8,094	13,738
982.00	11,046	1.000	10,021	23,758
983.00	13,273	1.000	12,141	35,899
984.00	15,742	1.000	14,489	50,388
985.00	18,505	1.000	17,103	67,491
986.00	21,785	1.000	20,121	87,612

**1** Originally Proposed Basin  
1"=40'  
north

**2** As-Built Basin  
1"=40'  
north

**Linetypes**

- sanitary main
- sanitary service
- storm sewer (existing)
- storm sewer (solid wall, proposed)
- storm sewer (solid wall, proposed)
- storm sewer (perforated, proposed)
- water main
- water service (fire)
- water service (domestic)
- water service (irrigation)
- natural gas main
- natural gas service schematic
- underground primary electric
- underground secondary electric
- overhead electric
- underground cable/phone/data
- underground cable/phone/data service
- fence-chainlink
- fence-wood
- fence-barbed wire
- treeline

**Local Benchmarks:** BM-#

**BM-1:** Storm Structure, Manhole Cover  
Elevation: 983.62'  
N: 1013823.1758  
E: 2827361.8695

**BM-2:** Storm Structure, Manhole Cover  
Elevation: 1001.21'  
N: 1013384.7454  
E: 2827199.0101

**Grading Legend**

- existing minor contour
- existing major contour
- proposed minor contour
- proposed major contour

**Utility Legend**


- existing
- proposed

**Property Legend**

- right of way
- property lines
- easements
- setbacks

**Symbols**

- sanitary manhole
- service cleanout
- force main release valve
- rectangular structure
- circular structure
- fire hydrant
- water valve
- water meter
- backflow preventer
- natural gas meter
- service transformer (pad mount)
- primary switch gear
- light pole
- cable/phone/data junction box
- street light
- pedestrian street light
- electric pole
- guy wire
- end section



AS-BUILT STAGE STORAGE TABLE				
ELEV	AREA (sq. ft.)	DEPT H (ft)	AVG END INC. VOL. (cu. ft.)	AVG END TOTAL VOL. (cu. ft.)
977.00	0	N/A	0	0
978.00	232	N/A	77	77
979.00	2,260	1.000	1,072	1,149
980.00	7,193	1.000	4,495	5,644
981.00	9,031	1.000	8,094	13,738
982.00	11,046	1.000	10,021	23,758
983.00	13,273	1.000	12,141	35,899
984.00	15,742	1.000	14,489	50,388
985.00	18,505	1.000	17,103	67,491
986.00	21,785	1.000	20,121	87,612

**3** Proposed Basin  
1"=40'  
north

A New Facility for

**Automotive Sales & Detail Center**

2100 NE Independence Ave  
Lee's Summit, Missouri 64064

date 06.09.2022  
drawn by OPH  
checked by PAM  
revisions

sheet number

**Ex. 1**

drawing type

project number 19076




## **Appendix B**

### **Existing Conditions Hydraflow Hydrograph Output Data**

<b>Watershed Model Schematic.....</b>	<b>1</b>
<b>Hydrograph Return Period Recap.....</b>	<b>2</b>
<b>2 - Year</b>	
<b>Summary Report.....</b>	<b>3</b>
<b>Hydrograph Reports.....</b>	<b>4</b>
Hydrograph No. 1, Rational, Area 1-1.....	4
Hydrograph No. 2, Rational, Area 1-2.....	5
Hydrograph No. 3, Rational, Area 1-3.....	6
Hydrograph No. 4, Combine, Total Existing.....	7
<b>10 - Year</b>	
<b>Summary Report.....</b>	<b>8</b>
<b>Hydrograph Reports.....</b>	<b>9</b>
Hydrograph No. 1, Rational, Area 1-1.....	9
Hydrograph No. 2, Rational, Area 1-2.....	10
Hydrograph No. 3, Rational, Area 1-3.....	11
Hydrograph No. 4, Combine, Total Existing.....	12
<b>100 - Year</b>	
<b>Summary Report.....</b>	<b>13</b>
<b>Hydrograph Reports.....</b>	<b>14</b>
Hydrograph No. 1, Rational, Area 1-1.....	14
Hydrograph No. 2, Rational, Area 1-2.....	15
Hydrograph No. 3, Rational, Area 1-3.....	16
Hydrograph No. 4, Combine, Total Existing.....	17
<b>IDF Report.....</b>	<b>18</b>

# Watershed Model Schematic

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020



## Legend

Hyd. Origin	Description
1 Rational	Area 1-1
2 Rational	Area 1-2
3 Rational	Area 1-3
4 Combine	Total Existing

# Hydrograph Return Period Recap

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Hyd. No.	Hydrograph type (origin)	Inflow hyd(s)	Peak Outflow (cfs)								Hydrograph Description
			1-yr	2-yr	3-yr	5-yr	10-yr	25-yr	50-yr	100-yr	
1	Rational	-----	8.491	10.79	-----	-----	15.07	-----	19.47	22.70	Area 1-1
2	Rational	-----	3.933	5.000	-----	-----	6.981	-----	9.020	10.52	Area 1-2
3	Rational	-----	14.46	18.39	-----	-----	25.67	-----	33.17	38.67	Area 1-3
4	Combine	1, 2, 3	26.89	34.18	-----	-----	47.72	-----	61.66	71.89	Total Existing

# Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020


Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	Rational	10.79	1	15	9,714	----	----	----	Area 1-1
2	Rational	5.000	1	15	4,500	----	----	----	Area 1-2
3	Rational	18.39	1	15	16,548	----	----	----	Area 1-3
4	Combine	34.18	1	15	30,762	1, 2, 3	----	----	Total Existing
19076.ExistingConditions.01.22.2021.gpw					Return Period: 2 Year			Friday, 01 / 22 / 2021	

# Hydrograph Report

## Hyd. No. 1

Area 1-1

Hydrograph type	= Rational	Peak discharge	= 10.79 cfs
Storm frequency	= 2 yrs	Time to peak	= 15 min
Time interval	= 1 min	Hyd. volume	= 9,714 cuft
Drainage area	= 9.380 ac	Runoff coeff.	= 0.31
Intensity	= 3.712 in/hr	Tc by User	= 15.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Friday, 01 / 22 / 2021

## Hyd. No. 2

Area 1-2

Hydrograph type	= Rational	Peak discharge	= 5.000 cfs
Storm frequency	= 2 yrs	Time to peak	= 15 min
Time interval	= 1 min	Hyd. volume	= 4,500 cuft
Drainage area	= 4.490 ac	Runoff coeff.	= 0.3
Intensity	= 3.712 in/hr	Tc by User	= 15.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Friday, 01 / 22 / 2021

## Hyd. No. 3

Area 1-3

Hydrograph type	= Rational	Peak discharge	= 18.39 cfs
Storm frequency	= 2 yrs	Time to peak	= 15 min
Time interval	= 1 min	Hyd. volume	= 16,548 cuft
Drainage area	= 15.480 ac	Runoff coeff.	= 0.32
Intensity	= 3.712 in/hr	Tc by User	= 15.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1





# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Friday, 01 / 22 / 2021

## Hyd. No. 4

Total Existing

Hydrograph type	= Combine	Peak discharge	= 34.18 cfs
Storm frequency	= 2 yrs	Time to peak	= 15 min
Time interval	= 1 min	Hyd. volume	= 30,762 cuft
Inflow hyds.	= 1, 2, 3	Contrib. drain. area	= 29.350 ac



# Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	Rational	15.07	1	15	13,563	----	----	----	Area 1-1
2	Rational	6.981	1	15	6,283	----	----	----	Area 1-2
3	Rational	25.67	1	15	23,105	----	----	----	Area 1-3
4	Combine	47.72	1	15	42,951	1, 2, 3	----	----	Total Existing
19076.ExistingConditions.01.22.2021.gpw					Return Period: 10 Year			Friday, 01 / 22 / 2021	

# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Friday, 01 / 22 / 2021

## Hyd. No. 1

Area 1-1

Hydrograph type	= Rational	Peak discharge	= 15.07 cfs
Storm frequency	= 10 yrs	Time to peak	= 15 min
Time interval	= 1 min	Hyd. volume	= 13,563 cuft
Drainage area	= 9.380 ac	Runoff coeff.	= 0.31
Intensity	= 5.183 in/hr	Tc by User	= 15.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Friday, 01 / 22 / 2021

## Hyd. No. 2

Area 1-2

Hydrograph type	= Rational	Peak discharge	= 6.981 cfs
Storm frequency	= 10 yrs	Time to peak	= 15 min
Time interval	= 1 min	Hyd. volume	= 6,283 cuft
Drainage area	= 4.490 ac	Runoff coeff.	= 0.3
Intensity	= 5.183 in/hr	Tc by User	= 15.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Friday, 01 / 22 / 2021

## Hyd. No. 3

Area 1-3

Hydrograph type	= Rational	Peak discharge	= 25.67 cfs
Storm frequency	= 10 yrs	Time to peak	= 15 min
Time interval	= 1 min	Hyd. volume	= 23,105 cuft
Drainage area	= 15.480 ac	Runoff coeff.	= 0.32
Intensity	= 5.183 in/hr	Tc by User	= 15.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020


Friday, 01 / 22 / 2021

## Hyd. No. 4

Total Existing

Hydrograph type = Combine  
 Storm frequency = 10 yrs  
 Time interval = 1 min  
 Inflow hyds. = 1, 2, 3

Peak discharge = 47.72 cfs  
 Time to peak = 15 min  
 Hyd. volume = 42,951 cuft  
 Contrib. drain. area = 29.350 ac



# Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	Rational	22.70	1	15	20,431	----	----	----	Area 1-1
2	Rational	10.52	1	15	9,464	----	----	----	Area 1-2
3	Rational	38.67	1	15	34,806	----	----	----	Area 1-3
4	Combine	71.89	1	15	64,701	1, 2, 3	----	----	Total Existing
19076.ExistingConditions.01.22.2021.gpw					Return Period: 100 Year			Friday, 01 / 22 / 2021	

# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Friday, 01 / 22 / 2021

## Hyd. No. 1

Area 1-1

Hydrograph type	= Rational	Peak discharge	= 22.70 cfs
Storm frequency	= 100 yrs	Time to peak	= 15 min
Time interval	= 1 min	Hyd. volume	= 20,431 cuft
Drainage area	= 9.380 ac	Runoff coeff.	= 0.31
Intensity	= 7.807 in/hr	Tc by User	= 15.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1





# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Friday, 01 / 22 / 2021

## Hyd. No. 2

Area 1-2

Hydrograph type	= Rational	Peak discharge	= 10.52 cfs
Storm frequency	= 100 yrs	Time to peak	= 15 min
Time interval	= 1 min	Hyd. volume	= 9,464 cuft
Drainage area	= 4.490 ac	Runoff coeff.	= 0.3
Intensity	= 7.807 in/hr	Tc by User	= 15.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Friday, 01 / 22 / 2021

## Hyd. No. 3

Area 1-3

Hydrograph type	= Rational	Peak discharge	= 38.67 cfs
Storm frequency	= 100 yrs	Time to peak	= 15 min
Time interval	= 1 min	Hyd. volume	= 34,806 cuft
Drainage area	= 15.480 ac	Runoff coeff.	= 0.32
Intensity	= 7.807 in/hr	Tc by User	= 15.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020


Friday, 01 / 22 / 2021

## Hyd. No. 4

Total Existing

Hydrograph type = Combine  
 Storm frequency = 100 yrs  
 Time interval = 1 min  
 Inflow hyds. = 1, 2, 3

Peak discharge = 71.89 cfs  
 Time to peak = 15 min  
 Hyd. volume = 64,701 cuft  
 Contrib. drain. area = 29.350 ac



# Hydraflow Rainfall Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2020

Friday, 01 / 22 / 2021

Return Period (Yrs)	Intensity-Duration-Frequency Equation Coefficients (FHA)			
	B	D	E	(N/A)
1	2.9200	0.1000	0.0000	-----
2	110.7137	16.5000	0.9842	-----
3	0.0000	0.0000	0.0000	-----
5	168.3971	19.5000	1.0189	-----
10	183.3473	19.2000	1.0096	-----
25	103.5313	15.9000	0.8218	-----
50	235.4014	19.9000	1.0020	-----
100	83.7894	6.1000	0.7783	-----

File name: KCAPWA.IDF

$$\text{Intensity} = B / (T_c + D)^E$$

Return Period (Yrs)	Intensity Values (in/hr)											
	5 min	10	15	20	25	30	35	40	45	50	55	60
1	2.92	2.92	2.92	2.92	2.92	2.92	2.92	2.92	2.92	2.92	2.92	2.92
2	5.41	4.40	3.71	3.21	2.83	2.53	2.29	2.09	1.92	1.78	1.66	1.55
3	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
5	6.47	5.35	4.56	3.98	3.52	3.16	2.86	2.62	2.41	2.24	2.08	1.95
10	7.35	6.08	5.18	4.52	4.00	3.59	3.26	2.98	2.74	2.54	2.37	2.22
25	8.51	7.14	6.17	5.46	4.90	4.46	4.10	3.79	3.54	3.31	3.12	2.95
50	9.39	7.82	6.70	5.86	5.20	4.68	4.25	3.90	3.60	3.34	3.12	2.92
100	12.87	9.64	7.81	6.62	5.77	5.14	4.65	4.25	3.92	3.65	3.41	3.21

T<sub>c</sub> = time in minutes. Values may exceed 60.

Precip. file name: P:\DAE Civil\Hydraflow Storm Sewer\SCS Custom Water Quality.pcp

Storm Distribution	Rainfall Precipitation Table (in)							
	1-yr	2-yr	3-yr	5-yr	10-yr	25-yr	50-yr	100-yr
SCS 24-hour	1.37	3.50	0.00	4.50	5.30	6.10	6.90	7.50
SCS 6-Hr	0.00	1.80	0.00	0.00	2.60	2.90	0.00	4.00
Huff-1st	0.00	1.55	0.00	2.75	4.00	5.38	6.50	8.00
Huff-2nd	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Huff-3rd	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Huff-4th	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Huff-Indy	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Custom	0.00	1.75	0.00	2.80	3.90	5.25	6.00	7.10

## **Appendix C**

### **Proposed Conditions Hydraflow Output Data**

<b>Watershed Model Schematic.....</b>	<b>1</b>
<b>Hydrograph Return Period Recap.....</b>	<b>2</b>
<b>1 - Year</b>	
<b>Summary Report.....</b>	<b>3</b>
<b>Hydrograph Reports.....</b>	<b>4</b>
Hydrograph No. 1, Rational, Area 2-1.....	4
Hydrograph No. 2, Rational, Area 2-2.....	5
Hydrograph No. 3, Rational, Area 2-3.....	6
Hydrograph No. 4, Rational, Area 2-4.....	7
Hydrograph No. 5, Rational, Area 2-5.....	8
Hydrograph No. 6, Rational, Area 2-6.....	9
Hydrograph No. 7, Rational, Area 2-7.....	10
Hydrograph No. 8, Rational, Area 2-8.....	11
Hydrograph No. 9, Rational, Area 2-9.....	12
Hydrograph No. 10, Rational, Area 2-10.....	13
Hydrograph No. 11, Rational, Area 2-11.....	14
Hydrograph No. 12, Combine, Combined 1.....	15
Hydrograph No. 13, Combine, Combined 2.....	16
Hydrograph No. 14, Combine, Combined 3.....	17
Hydrograph No. 15, Combine, TOTAL TO DETENTION.....	18
Hydrograph No. 16, Reservoir, TOTAL DETENTION.....	19
Pond Report - Detention.....	20
Hydrograph No. 17, Combine, TOTAL RUNOFF.....	22
<b>2 - Year</b>	
<b>Summary Report.....</b>	<b>23</b>
<b>Hydrograph Reports.....</b>	<b>24</b>
Hydrograph No. 1, Rational, Area 2-1.....	24
Hydrograph No. 2, Rational, Area 2-2.....	25
Hydrograph No. 3, Rational, Area 2-3.....	26
Hydrograph No. 4, Rational, Area 2-4.....	27
Hydrograph No. 5, Rational, Area 2-5.....	28
Hydrograph No. 6, Rational, Area 2-6.....	29
Hydrograph No. 7, Rational, Area 2-7.....	30
Hydrograph No. 8, Rational, Area 2-8.....	31
Hydrograph No. 9, Rational, Area 2-9.....	32
Hydrograph No. 10, Rational, Area 2-10.....	33
Hydrograph No. 11, Rational, Area 2-11.....	34
Hydrograph No. 12, Combine, Combined 1.....	35
Hydrograph No. 13, Combine, Combined 2.....	36
Hydrograph No. 14, Combine, Combined 3.....	37
Hydrograph No. 15, Combine, TOTAL TO DETENTION.....	38
Hydrograph No. 16, Reservoir, TOTAL DETENTION.....	39
Hydrograph No. 17, Combine, TOTAL RUNOFF.....	40

## 5 - Year

<b>Summary Report.....</b>	<b>41</b>
<b>Hydrograph Reports.....</b>	<b>42</b>
Hydrograph No. 1, Rational, Area 2-1.....	42
Hydrograph No. 2, Rational, Area 2-2.....	43
Hydrograph No. 3, Rational, Area 2-3.....	44
Hydrograph No. 4, Rational, Area 2-4.....	45
Hydrograph No. 5, Rational, Area 2-5.....	46
Hydrograph No. 6, Rational, Area 2-6.....	47
Hydrograph No. 7, Rational, Area 2-7.....	48
Hydrograph No. 8, Rational, Area 2-8.....	49
Hydrograph No. 9, Rational, Area 2-9.....	50
Hydrograph No. 10, Rational, Area 2-10.....	51
Hydrograph No. 11, Rational, Area 2-11.....	52
Hydrograph No. 12, Combine, Combined 1.....	53
Hydrograph No. 13, Combine, Combined 2.....	54
Hydrograph No. 14, Combine, Combined 3.....	55
Hydrograph No. 15, Combine, TOTAL TO DETENTION.....	56
Hydrograph No. 16, Reservoir, TOTAL DETENTION.....	57
Hydrograph No. 17, Combine, TOTAL RUNOFF.....	58

**10 - Year**

<b>Summary Report.....</b>	<b>59</b>
<b>Hydrograph Reports.....</b>	<b>60</b>
Hydrograph No. 1, Rational, Area 2-1.....	60
Hydrograph No. 2, Rational, Area 2-2.....	61
Hydrograph No. 3, Rational, Area 2-3.....	62
Hydrograph No. 4, Rational, Area 2-4.....	63
Hydrograph No. 5, Rational, Area 2-5.....	64
Hydrograph No. 6, Rational, Area 2-6.....	65
Hydrograph No. 7, Rational, Area 2-7.....	66
Hydrograph No. 8, Rational, Area 2-8.....	67
Hydrograph No. 9, Rational, Area 2-9.....	68
Hydrograph No. 10, Rational, Area 2-10.....	69
Hydrograph No. 11, Rational, Area 2-11.....	70
Hydrograph No. 12, Combine, Combined 1.....	71
Hydrograph No. 13, Combine, Combined 2.....	72
Hydrograph No. 14, Combine, Combined 3.....	73
Hydrograph No. 15, Combine, TOTAL TO DETENTION.....	74
Hydrograph No. 16, Reservoir, TOTAL DETENTION.....	75
Hydrograph No. 17, Combine, TOTAL RUNOFF.....	76

**25 - Year**

<b>Summary Report.....</b>	<b>77</b>
<b>Hydrograph Reports.....</b>	<b>78</b>
Hydrograph No. 1, Rational, Area 2-1.....	78
Hydrograph No. 2, Rational, Area 2-2.....	79
Hydrograph No. 3, Rational, Area 2-3.....	80
Hydrograph No. 4, Rational, Area 2-4.....	81
Hydrograph No. 5, Rational, Area 2-5.....	82
Hydrograph No. 6, Rational, Area 2-6.....	83

Hydrograph No. 7, Rational, Area 2-7.....	84
Hydrograph No. 8, Rational, Area 2-8.....	85
Hydrograph No. 9, Rational, Area 2-9.....	86
Hydrograph No. 10, Rational, Area 2-10.....	87
Hydrograph No. 11, Rational, Area 2-11.....	88
Hydrograph No. 12, Combine, Combined 1.....	89
Hydrograph No. 13, Combine, Combined 2.....	90
Hydrograph No. 14, Combine, Combined 3.....	91
Hydrograph No. 15, Combine, TOTAL TO DETENTION.....	92
Hydrograph No. 16, Reservoir, TOTAL DETENTION.....	93
Hydrograph No. 17, Combine, TOTAL RUNOFF.....	94

**100 - Year**

<b>Summary Report.....</b>	<b>95</b>
----------------------------	-----------

<b>Hydrograph Reports.....</b>	<b>96</b>
--------------------------------	-----------


Hydrograph No. 1, Rational, Area 2-1.....	96
Hydrograph No. 2, Rational, Area 2-2.....	97
Hydrograph No. 3, Rational, Area 2-3.....	98
Hydrograph No. 4, Rational, Area 2-4.....	99
Hydrograph No. 5, Rational, Area 2-5.....	100
Hydrograph No. 6, Rational, Area 2-6.....	101
Hydrograph No. 7, Rational, Area 2-7.....	102
Hydrograph No. 8, Rational, Area 2-8.....	103
Hydrograph No. 9, Rational, Area 2-9.....	104
Hydrograph No. 10, Rational, Area 2-10.....	105
Hydrograph No. 11, Rational, Area 2-11.....	106
Hydrograph No. 12, Combine, Combined 1.....	107
Hydrograph No. 13, Combine, Combined 2.....	108
Hydrograph No. 14, Combine, Combined 3.....	109
Hydrograph No. 15, Combine, TOTAL TO DETENTION.....	110
Hydrograph No. 16, Reservoir, TOTAL DETENTION.....	111
Hydrograph No. 17, Combine, TOTAL RUNOFF.....	112

<b>IDF Report.....</b>	<b>113</b>
------------------------	------------



# Watershed Model Schematic

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021



**Legend**

Hyd. Origin	Description
1 Rational	Area 2-1
2 Rational	Area 2-2
3 Rational	Area 2-3
4 Rational	Area 2-4
5 Rational	Area 2-5
6 Rational	Area 2-6
7 Rational	Area 2-7
8 Rational	Area 2-8
9 Rational	Area 2-9
10 Rational	Area 2-10
11 Rational	Area 2-11
12 Combine	Combined 1
13 Combine	Combined 2
14 Combine	Combined 3
15 Combine	TOTAL TO DETENTION
16 Reservoir	TOTAL DETENTION
17 Combine	TOTAL RUNOFF

# Hydrograph Return Period Recap

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Hyd. No.	Hydrograph type (origin)	Inflow hyd(s)	Peak Outflow (cfs)								Hydrograph Description
			1-yr	2-yr	3-yr	5-yr	10-yr	25-yr	50-yr	100-yr	
1	Rational	-----	8.491	12.79	-----	15.57	17.68	21.26	-----	28.02	Area 2-1
2	Rational	-----	3.933	5.927	-----	7.213	8.189	9.849	-----	12.98	Area 2-2
3	Rational	-----	10.07	17.09	-----	20.61	23.40	27.61	-----	39.03	Area 2-3
4	Rational	-----	1.993	3.689	-----	4.416	5.015	5.815	-----	8.784	Area 2-4
5	Rational	-----	0.368	0.681	-----	0.815	0.926	1.074	-----	1.622	Area 2-5
6	Rational	-----	2.197	4.067	-----	4.868	5.529	6.410	-----	9.684	Area 2-6
7	Rational	-----	1.285	2.378	-----	2.847	3.233	3.749	-----	5.663	Area 2-7
8	Rational	-----	0.728	1.348	-----	1.614	1.833	2.125	-----	3.210	Area 2-8
9	Rational	-----	0.631	1.168	-----	1.398	1.587	1.840	-----	2.780	Area 2-9
10	Rational	-----	0.918	1.700	-----	2.035	2.311	2.680	-----	4.048	Area 2-10
11	Rational	-----	0.450	0.832	-----	0.996	1.132	1.312	-----	1.982	Area 2-11
12	Combine	1, 2, 3,	18.77	30.19	-----	36.55	41.51	49.38	-----	67.73	Combined 1
13	Combine	4, 5, 7,	3.646	6.749	-----	8.078	9.175	10.64	-----	16.07	Combined 2
14	Combine	6, 8, 9, 10,	4.474	8.283	-----	9.914	11.26	13.06	-----	19.72	Combined 3
15	Combine	12, 13, 14	23.64	39.21	-----	47.35	53.77	63.60	-----	89.21	TOTAL TO DETENTION
16	Reservoir	15	0.327	0.439	-----	0.496	0.540	0.695	-----	5.833	TOTAL DETENTION
17	Combine	11, 16	0.607	1.040	-----	1.220	1.368	1.566	-----	5.833	TOTAL RUNOFF

# Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021


Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	Rational	8.491	1	10	5,094	-----	-----	-----	Area 2-1
2	Rational	3.933	1	10	2,360	-----	-----	-----	Area 2-2
3	Rational	10.07	1	7	4,231	-----	-----	-----	Area 2-3
4	Rational	1.993	1	5	598	-----	-----	-----	Area 2-4
5	Rational	0.368	1	5	110	-----	-----	-----	Area 2-5
6	Rational	2.197	1	5	659	-----	-----	-----	Area 2-6
7	Rational	1.285	1	5	385	-----	-----	-----	Area 2-7
8	Rational	0.728	1	5	218	-----	-----	-----	Area 2-8
9	Rational	0.631	1	5	189	-----	-----	-----	Area 2-9
10	Rational	0.918	1	5	276	-----	-----	-----	Area 2-10
11	Rational	0.450	1	5	135	-----	-----	-----	Area 2-11
12	Combine	18.77	1	7	11,685	1, 2, 3,	-----	-----	Combined 1
13	Combine	3.646	1	5	1,094	4, 5, 7,	-----	-----	Combined 2
14	Combine	4.474	1	5	1,342	6, 8, 9, 10,	-----	-----	Combined 3
15	Combine	23.64	1	7	14,121	12, 13, 14	-----	-----	TOTAL TO DETENTION
16	Reservoir	0.327	1	20	14,115	15	981.01	13,844	TOTAL DETENTION
17	Combine	0.607	1	5	14,250	11, 16	-----	-----	TOTAL RUNOFF
19076.As-BuiltConditions.04.11.2022.gpw					Return Period: 1 Year			Thursday, 06 / 9 / 2022	

# Hydrograph Report

## Hyd. No. 1

Area 2-1

Hydrograph type	= Rational	Peak discharge	= 8.491 cfs
Storm frequency	= 1 yrs	Time to peak	= 10 min
Time interval	= 1 min	Hyd. volume	= 5,094 cuft
Drainage area	= 9.380 ac	Runoff coeff.	= 0.31
Intensity	= 2.920 in/hr	Tc by User	= 10.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1




# Hydrograph Report

## Hyd. No. 2

Area 2-2

Hydrograph type	= Rational	Peak discharge	= 3.933 cfs
Storm frequency	= 1 yrs	Time to peak	= 10 min
Time interval	= 1 min	Hyd. volume	= 2,360 cuft
Drainage area	= 4.490 ac	Runoff coeff.	= 0.3
Intensity	= 2.920 in/hr	Tc by User	= 10.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 3

Area 2-3

Hydrograph type	= Rational	Peak discharge	= 10.07 cfs
Storm frequency	= 1 yrs	Time to peak	= 7 min
Time interval	= 1 min	Hyd. volume	= 4,231 cuft
Drainage area	= 11.500 ac	Runoff coeff.	= 0.3
Intensity	= 2.920 in/hr	Tc by User	= 7.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 4

Area 2-4

Hydrograph type	= Rational	Peak discharge	= 1.993 cfs
Storm frequency	= 1 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 598 cuft
Drainage area	= 1.050 ac	Runoff coeff.	= 0.65
Intensity	= 2.920 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1




# Hydrograph Report

## Hyd. No. 5

Area 2-5

Hydrograph type	= Rational	Peak discharge	= 0.368 cfs
Storm frequency	= 1 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 110 cuft
Drainage area	= 0.200 ac	Runoff coeff.	= 0.63
Intensity	= 2.920 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1





# Hydrograph Report

## Hyd. No. 6

Area 2-6

Hydrograph type	= Rational	Peak discharge	= 2.197 cfs
Storm frequency	= 1 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 659 cuft
Drainage area	= 0.990 ac	Runoff coeff.	= 0.76
Intensity	= 2.920 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 7

Area 2-7

Hydrograph type	= Rational	Peak discharge	= 1.285 cfs
Storm frequency	= 1 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 385 cuft
Drainage area	= 0.500 ac	Runoff coeff.	= 0.88
Intensity	= 2.920 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 8

Area 2-8

Hydrograph type	= Rational	Peak discharge	= 0.728 cfs
Storm frequency	= 1 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 218 cuft
Drainage area	= 0.290 ac	Runoff coeff.	= 0.86
Intensity	= 2.920 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 9

Area 2-9

Hydrograph type	= Rational	Peak discharge	= 0.631 cfs
Storm frequency	= 1 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 189 cuft
Drainage area	= 0.240 ac	Runoff coeff.	= 0.9
Intensity	= 2.920 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 10

Area 2-10

Hydrograph type	= Rational	Peak discharge	= 0.918 cfs
Storm frequency	= 1 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 276 cuft
Drainage area	= 0.370 ac	Runoff coeff.	= 0.85
Intensity	= 2.920 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 11

Area 2-11

Hydrograph type	= Rational	Peak discharge	= 0.450 cfs
Storm frequency	= 1 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 135 cuft
Drainage area	= 0.350 ac	Runoff coeff.	= 0.44
Intensity	= 2.920 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021


Thursday, 06 / 9 / 2022

## Hyd. No. 12

Combined 1

Hydrograph type = Combine  
Storm frequency = 1 yrs  
Time interval = 1 min  
Inflow hyds. = 1, 2, 3

Peak discharge = 18.77 cfs  
Time to peak = 7 min  
Hyd. volume = 11,685 cuft  
Contrib. drain. area = 25.370 ac



# Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021


Thursday, 06 / 9 / 2022

## Hyd. No. 13

Combined 2

Hydrograph type = Combine  
Storm frequency = 1 yrs  
Time interval = 1 min  
Inflow hyds. = 4, 5, 7

Peak discharge = 3.646 cfs  
Time to peak = 5 min  
Hyd. volume = 1,094 cuft  
Contrib. drain. area = 1.750 ac





# Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021


Thursday, 06 / 9 / 2022

## Hyd. No. 14

Combined 3

Hydrograph type = Combine  
Storm frequency = 1 yrs  
Time interval = 1 min  
Inflow hyds. = 6, 8, 9, 10

Peak discharge = 4.474 cfs  
Time to peak = 5 min  
Hyd. volume = 1,342 cuft  
Contrib. drain. area = 1.890 ac



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 15

### TOTAL TO DETENTION

Hydrograph type	= Combine	Peak discharge	= 23.64 cfs
Storm frequency	= 1 yrs	Time to peak	= 7 min
Time interval	= 1 min	Hyd. volume	= 14,121 cuft
Inflow hyds.	= 12, 13, 14	Contrib. drain. area	= 0.000 ac



# Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021


Thursday, 06 / 9 / 2022

## Hyd. No. 16

### TOTAL DETENTION

Hydrograph type	= Reservoir	Peak discharge	= 0.327 cfs
Storm frequency	= 1 yrs	Time to peak	= 20 min
Time interval	= 1 min	Hyd. volume	= 14,115 cuft
Inflow hyd. No.	= 15 - TOTAL TO DETENTION	Max. Elevation	= 981.01 ft
Reservoir name	= Detention	Max. Storage	= 13,844 cuft

Storage Indication method used.



# Pond Report

## Pond No. 1 - Detention

### Pond Data

Contours -User-defined contour areas. Conic method used for volume calculation. Begining Elevation = 977.14 ft

### Stage / Storage Table

Stage (ft)	Elevation (ft)	Contour area (sqft)	Incr. Storage (cuft)	Total storage (cuft)
0.00	977.00	00	0	0
1.00	978.00	232	77	77
2.00	979.00	2,260	1,072	1,149
3.00	980.00	7,193	4,495	5,644
4.00	981.00	9,031	8,094	13,738
5.00	982.00	11,046	10,021	23,758
6.00	983.00	13,273	12,141	35,899
7.00	984.00	15,742	14,489	50,388
8.00	985.00	18,505	17,103	67,491
9.00	986.00	21,785	20,121	87,612
10.00	987.00	32,375	26,903	114,515

### Culvert / Orifice Structures

	[A]	[B]	[C]	[PrfRsr]
Rise (in)	= 42.00	36.00	15.00	1.50
Span (in)	= 42.00	36.00	15.00	1.50
No. Barrels	= 1	1	1	6
Invert El. (ft)	= 976.75	983.47	982.94	976.70
Length (ft)	= 15.00	10.00	20.00	5.80
Slope (%)	= 2.00	1.00	2.00	n/a
N-Value	= .013	.013	.013	n/a
Orifice Coeff.	= 0.60	0.60	0.60	0.60
Multi-Stage	= n/a	Yes	Yes	Yes

### Weir Structures

	[A]	[B]	[C]	[D]
Crest Len (ft)	= 12.00	0.00	10.00	0.00
Crest El. (ft)	= 985.87	0.00	986.41	0.00
Weir Coeff.	= 2.60	2.60	2.60	3.33
Weir Type	= Broad	Broad	Broad	---
Multi-Stage	= Yes	Yes	Yes	No
Exfil.(in/hr)	= 0.000 (by Wet area)			
TW Elev. (ft)	= 0.00			

Note: Culvert/Orifice outflows are analyzed under inlet (ic) and outlet (oc) control. Weir risers checked for orifice conditions (ic) and submergence (s).

### Stage / Storage / Discharge Table

Stage ft	Storage cuft	Elevation ft	Clv A cfs	Clv B cfs	Clv C cfs	PrfRsr cfs	Wr A cfs	Wr B cfs	Wr C cfs	Wr D cfs	Exfil cfs	User cfs	Total cfs
0.00	0	977.00	0.00	0.00	0.00	0.00	0.00	---	0.00	---	---	---	0.000
0.10	8	977.10	0.54 ic	0.00	0.00	0.00	0.00	---	0.00	---	---	---	0.001
0.20	15	977.20	0.54 ic	0.00	0.00	0.00	0.00	---	0.00	---	---	---	0.004
0.30	23	977.30	0.54 ic	0.00	0.00	0.01	0.00	---	0.00	---	---	---	0.007
0.40	31	977.40	0.54 ic	0.00	0.00	0.01	0.00	---	0.00	---	---	---	0.010
0.50	39	977.50	0.54 ic	0.00	0.00	0.01	0.00	---	0.00	---	---	---	0.014
0.60	46	977.60	0.54 ic	0.00	0.00	0.02	0.00	---	0.00	---	---	---	0.019
0.70	54	977.70	0.54 ic	0.00	0.00	0.02	0.00	---	0.00	---	---	---	0.024
0.80	62	977.80	0.54 ic	0.00	0.00	0.03	0.00	---	0.00	---	---	---	0.029
0.90	70	977.90	0.54 ic	0.00	0.00	0.03	0.00	---	0.00	---	---	---	0.035
1.00	77	978.00	0.54 ic	0.00	0.00	0.04	0.00	---	0.00	---	---	---	0.041
1.10	185	978.10	0.54 ic	0.00	0.00	0.05	0.00	---	0.00	---	---	---	0.047
1.20	292	978.20	0.54 ic	0.00	0.00	0.05	0.00	---	0.00	---	---	---	0.054
1.30	399	978.30	0.54 ic	0.00	0.00	0.06	0.00	---	0.00	---	---	---	0.060
1.40	506	978.40	0.54 ic	0.00	0.00	0.07	0.00	---	0.00	---	---	---	0.067
1.50	613	978.50	0.54 ic	0.00	0.00	0.07	0.00	---	0.00	---	---	---	0.075
1.60	720	978.60	0.54 ic	0.00	0.00	0.08	0.00	---	0.00	---	---	---	0.082
1.70	828	978.70	0.54 ic	0.00	0.00	0.09	0.00	---	0.00	---	---	---	0.090
1.80	935	978.80	0.54 ic	0.00	0.00	0.10	0.00	---	0.00	---	---	---	0.098
1.90	1,042	978.90	0.54 ic	0.00	0.00	0.11	0.00	---	0.00	---	---	---	0.107
2.00	1,149	979.00	0.54 ic	0.00	0.00	0.12	0.00	---	0.00	---	---	---	0.115
2.10	1,599	979.10	0.54 ic	0.00	0.00	0.12	0.00	---	0.00	---	---	---	0.124
2.20	2,048	979.20	0.54 ic	0.00	0.00	0.13	0.00	---	0.00	---	---	---	0.133
2.30	2,498	979.30	0.54 ic	0.00	0.00	0.14	0.00	---	0.00	---	---	---	0.142
2.40	2,947	979.40	0.54 ic	0.00	0.00	0.15	0.00	---	0.00	---	---	---	0.151
2.50	3,397	979.50	0.54 ic	0.00	0.00	0.16	0.00	---	0.00	---	---	---	0.161
2.60	3,846	979.60	0.54 ic	0.00	0.00	0.17	0.00	---	0.00	---	---	---	0.171
2.70	4,295	979.70	0.54 ic	0.00	0.00	0.18	0.00	---	0.00	---	---	---	0.181
2.80	4,745	979.80	0.54 ic	0.00	0.00	0.19	0.00	---	0.00	---	---	---	0.191
2.90	5,194	979.90	0.54 ic	0.00	0.00	0.20	0.00	---	0.00	---	---	---	0.201
3.00	5,644	980.00	0.54 ic	0.00	0.00	0.21	0.00	---	0.00	---	---	---	0.212
3.10	6,453	980.10	0.54 ic	0.00	0.00	0.22	0.00	---	0.00	---	---	---	0.222

Continues on next page...

Detention

**Stage / Storage / Discharge Table**

Stage ft	Storage cuft	Elevation ft	Civ A cfs	Civ B cfs	Civ C cfs	PrfRsr cfs	Wr A cfs	Wr B cfs	Wr C cfs	Wr D cfs	Exfil cfs	User cfs	Total cfs
3.20	7,263	980.20	0.54 ic	0.00	0.00	0.23	0.00	---	0.00	---	---	---	0.233
3.30	8,072	980.30	0.54 ic	0.00	0.00	0.24	0.00	---	0.00	---	---	---	0.244
3.40	8,881	980.40	0.54 ic	0.00	0.00	0.26	0.00	---	0.00	---	---	---	0.255
3.50	9,691	980.50	0.54 ic	0.00	0.00	0.27	0.00	---	0.00	---	---	---	0.267
3.60	10,500	980.60	0.54 ic	0.00	0.00	0.28	0.00	---	0.00	---	---	---	0.278
3.70	11,309	980.70	0.54 ic	0.00	0.00	0.29	0.00	---	0.00	---	---	---	0.290
3.80	12,119	980.80	0.54 ic	0.00	0.00	0.30	0.00	---	0.00	---	---	---	0.302
3.90	12,928	980.90	0.54 ic	0.00	0.00	0.31	0.00	---	0.00	---	---	---	0.314
4.00	13,738	981.00	0.54 ic	0.00	0.00	0.33	0.00	---	0.00	---	---	---	0.326
4.10	14,740	981.10	0.54 ic	0.00	0.00	0.34	0.00	---	0.00	---	---	---	0.338
4.20	15,742	981.20	0.54 ic	0.00	0.00	0.35	0.00	---	0.00	---	---	---	0.351
4.30	16,744	981.30	0.54 ic	0.00	0.00	0.36	0.00	---	0.00	---	---	---	0.363
4.40	17,746	981.40	0.54 ic	0.00	0.00	0.38	0.00	---	0.00	---	---	---	0.376
4.50	18,748	981.50	0.54 ic	0.00	0.00	0.39	0.00	---	0.00	---	---	---	0.389
4.60	19,750	981.60	0.54 ic	0.00	0.00	0.40	0.00	---	0.00	---	---	---	0.402
4.70	20,752	981.70	0.54 ic	0.00	0.00	0.42	0.00	---	0.00	---	---	---	0.415
4.80	21,754	981.80	0.54 ic	0.00	0.00	0.43	0.00	---	0.00	---	---	---	0.428
4.90	22,756	981.90	0.54 ic	0.00	0.00	0.44	0.00	---	0.00	---	---	---	0.442
5.00	23,758	982.00	0.54 ic	0.00	0.00	0.46	0.00	---	0.00	---	---	---	0.456
5.10	24,972	982.10	0.54 ic	0.00	0.00	0.47	0.00	---	0.00	---	---	---	0.469
5.20	26,186	982.20	0.54 ic	0.00	0.00	0.48	0.00	---	0.00	---	---	---	0.483
5.30	27,401	982.30	0.54 ic	0.00	0.00	0.50	0.00	---	0.00	---	---	---	0.497
5.40	28,615	982.40	0.54 ic	0.00	0.00	0.51	0.00	---	0.00	---	---	---	0.511
5.50	29,829	982.50	0.54 ic	0.00	0.00	0.53	0.00	---	0.00	---	---	---	0.526
5.60	31,043	982.60	0.54 ic	0.00	0.00	0.54	0.00	---	0.00	---	---	---	0.540
5.70	32,257	982.70	0.60 ic	0.00	0.00	0.55	0.00	---	0.00	---	---	---	0.553
5.80	33,471	982.80	0.60 ic	0.00	0.00	0.57	0.00	---	0.00	---	---	---	0.568
5.90	34,685	982.90	0.60 ic	0.00	0.00	0.58	0.00	---	0.00	---	---	---	0.583
6.00	35,899	983.00	0.62 ic	0.00	0.02 ic	0.60	0.00	---	0.00	---	---	---	0.615
6.10	37,348	983.10	0.74 ic	0.00	0.13 ic	0.61	0.00	---	0.00	---	---	---	0.736
6.20	38,797	983.20	0.99 ic	0.00	0.33 ic	0.62	0.00	---	0.00	---	---	---	0.947
6.30	40,246	983.30	1.29 ic	0.00	0.62 ic	0.62	0.00	---	0.00	---	---	---	1.239
6.40	41,695	983.40	1.66 ic	0.00	0.95 ic	0.63	0.00	---	0.00	---	---	---	1.577
6.50	43,144	983.50	2.09 ic	0.01 ic	1.38 ic	0.64	0.00	---	0.00	---	---	---	2.021
6.60	44,593	983.60	2.61 ic	0.14 ic	1.83 ic	0.64	0.00	---	0.00	---	---	---	2.611
6.70	46,041	983.70	3.38 ic	0.42 ic	2.32 ic	0.65	0.00	---	0.00	---	---	---	3.385
6.80	47,490	983.80	4.38 ic	0.88 ic	2.86 ic	0.65	0.00	---	0.00	---	---	---	4.383
6.90	48,939	983.90	5.45 ic	1.43 ic	3.37 ic	0.65	0.00	---	0.00	---	---	---	5.454
7.00	50,388	984.00	6.73 ic	2.17 ic	3.91 ic	0.65	0.00	---	0.00	---	---	---	6.726
7.10	52,098	984.10	8.07 ic	2.97 ic	4.36 ic	0.65	0.00	---	0.00	---	---	---	7.980
7.20	53,809	984.20	9.55 oc	3.92 ic	4.71 ic	0.65	0.00	---	0.00	---	---	---	9.273
7.30	55,519	984.30	10.79 oc	5.03 ic	5.06 ic	0.65	0.00	---	0.00	---	---	---	10.74
7.40	57,229	984.40	12.40 oc	6.29 ic	5.40 ic	0.64	0.00	---	0.00	---	---	---	12.33
7.50	58,940	984.50	14.06 oc	7.48 ic	5.71 ic	0.64	0.00	---	0.00	---	---	---	13.83
7.60	60,650	984.60	15.76 oc	9.02 ic	6.01 ic	0.63	0.00	---	0.00	---	---	---	15.66
7.70	62,360	984.70	17.46 oc	10.44 ic	6.29 ic	0.62	0.00	---	0.00	---	---	---	17.36
7.80	64,070	984.80	19.16 oc	11.94 ic	6.57 ic	0.62	0.00	---	0.00	---	---	---	19.13
7.90	65,781	984.90	21.49 oc	13.81 ic	6.83 ic	0.61	0.00	---	0.00	---	---	---	21.24
8.00	67,491	985.00	23.39 oc	15.48 ic	7.08 ic	0.60	0.00	---	0.00	---	---	---	23.15
8.10	69,503	985.10	25.18 oc	17.20 ic	7.32 ic	0.59	0.00	---	0.00	---	---	---	25.11
8.20	71,515	985.20	27.33 oc	18.97 ic	7.55 ic	0.57	0.00	---	0.00	---	---	---	27.10
8.30	73,527	985.30	29.60 oc	21.07 ic	7.78 ic	0.56	0.00	---	0.00	---	---	---	29.41
8.40	75,539	985.40	31.48 oc	22.88 ic	8.00 ic	0.54	0.00	---	0.00	---	---	---	31.43
8.50	77,551	985.50	33.43 oc	24.70 ic	8.22 ic	0.50	0.00	---	0.00	---	---	---	33.42
8.60	79,564	985.60	35.71 oc	26.79 ic	8.43 ic	0.50	0.00	---	0.00	---	---	---	35.71
8.70	81,576	985.70	37.96 oc	28.82 ic	8.63 ic	0.51	0.00	---	0.00	---	---	---	37.96
8.80	83,588	985.80	40.13 oc	30.78 ic	8.83 ic	0.51	0.00	---	0.00	---	---	---	40.13
8.90	85,600	985.90	42.36 oc	32.65 ic	9.03 ic	0.52	0.16	---	0.00	---	---	---	42.36
9.00	87,612	986.00	45.82 oc	34.61 ic	9.22 ic	0.52	1.46	---	0.00	---	---	---	45.81
9.10	90,302	986.10	49.76 oc	36.38 ic	9.41 ic	0.52	3.44	---	0.00	---	---	---	49.75
9.20	92,992	986.20	54.12 oc	38.09 ic	9.59 ic	0.52	5.92	---	0.00	---	---	---	54.12
9.30	95,683	986.30	58.71 oc	39.63 ic	9.77 ic	0.52	8.80	---	0.00	---	---	---	58.71
9.40	98,373	986.40	63.46 oc	40.97 ic	9.95 ic	0.51	12.04	---	0.00	---	---	---	63.46
9.50	101,063	986.50	69.01 oc	42.09 ic	10.12 ic	0.49	15.60	---	0.70	---	---	---	69.01
9.60	103,754	986.60	75.82 oc	43.45 ic	10.29 ic	0.47	19.46	---	2.15	---	---	---	75.82
9.70	106,444	986.70	83.30 oc	44.76 ic	10.46 ic	0.44	23.59	---	4.06	---	---	---	83.30
9.80	109,134	986.80	91.34 ic	46.03 ic	10.63 ic	0.38	27.97	---	6.33	---	---	---	91.34
9.90	111,825	986.90	99.88 ic	47.27 ic	10.79 ic	0.30	32.60	---	8.91	---	---	---	99.88
10.00	114,515	987.00	108.26 ic	48.49 ic	10.30 ic	0.22	37.48	---	11.78	---	---	---	108.26

...End

# Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021


Thursday, 06 / 9 / 2022

## Hyd. No. 17

### TOTAL RUNOFF

Hydrograph type = Combine  
Storm frequency = 1 yrs  
Time interval = 1 min  
Inflow hyds. = 11, 16

Peak discharge = 0.607 cfs  
Time to peak = 5 min  
Hyd. volume = 14,250 cuft  
Contrib. drain. area = 0.350 ac



# Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	Rational	12.79	1	10	7,677	-----	-----	-----	Area 2-1
2	Rational	5.927	1	10	3,556	-----	-----	-----	Area 2-2
3	Rational	17.09	1	7	7,176	-----	-----	-----	Area 2-3
4	Rational	3.689	1	5	1,107	-----	-----	-----	Area 2-4
5	Rational	0.681	1	5	204	-----	-----	-----	Area 2-5
6	Rational	4.067	1	5	1,220	-----	-----	-----	Area 2-6
7	Rational	2.378	1	5	714	-----	-----	-----	Area 2-7
8	Rational	1.348	1	5	404	-----	-----	-----	Area 2-8
9	Rational	1.168	1	5	350	-----	-----	-----	Area 2-9
10	Rational	1.700	1	5	510	-----	-----	-----	Area 2-10
11	Rational	0.832	1	5	250	-----	-----	-----	Area 2-11
12	Combine	30.19	1	7	18,409	1, 2, 3,	-----	-----	Combined 1
13	Combine	6.749	1	5	2,025	4, 5, 7,	-----	-----	Combined 2
14	Combine	8.283	1	5	2,485	6, 8, 9, 10,	-----	-----	Combined 3
15	Combine	39.21	1	7	22,919	12, 13, 14	-----	-----	TOTAL TO DETENTION
16	Reservoir	0.439	1	20	22,913	15	981.88	22,552	TOTAL DETENTION
17	Combine	1.040	1	5	23,162	11, 16	-----	-----	TOTAL RUNOFF
19076.As-BuiltConditions.04.11.2022.gpw					Return Period: 2 Year			Thursday, 06 / 9 / 2022	

# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 1

Area 2-1

Hydrograph type	= Rational	Peak discharge	= 12.79 cfs
Storm frequency	= 2 yrs	Time to peak	= 10 min
Time interval	= 1 min	Hyd. volume	= 7,677 cuft
Drainage area	= 9.380 ac	Runoff coeff.	= 0.31
Intensity	= 4.400 in/hr	Tc by User	= 10.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1





# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 2

Area 2-2

Hydrograph type	= Rational	Peak discharge	= 5.927 cfs
Storm frequency	= 2 yrs	Time to peak	= 10 min
Time interval	= 1 min	Hyd. volume	= 3,556 cuft
Drainage area	= 4.490 ac	Runoff coeff.	= 0.3
Intensity	= 4.400 in/hr	Tc by User	= 10.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 3

Area 2-3

Hydrograph type	= Rational	Peak discharge	= 17.09 cfs
Storm frequency	= 2 yrs	Time to peak	= 7 min
Time interval	= 1 min	Hyd. volume	= 7,176 cuft
Drainage area	= 11.500 ac	Runoff coeff.	= 0.3
Intensity	= 4.952 in/hr	Tc by User	= 7.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 4

Area 2-4

Hydrograph type	= Rational	Peak discharge	= 3.689 cfs
Storm frequency	= 2 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 1,107 cuft
Drainage area	= 1.050 ac	Runoff coeff.	= 0.65
Intensity	= 5.406 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 5

Area 2-5

Hydrograph type	= Rational	Peak discharge	= 0.681 cfs
Storm frequency	= 2 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 204 cuft
Drainage area	= 0.200 ac	Runoff coeff.	= 0.63
Intensity	= 5.406 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 6

Area 2-6

Hydrograph type	= Rational	Peak discharge	= 4.067 cfs
Storm frequency	= 2 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 1,220 cuft
Drainage area	= 0.990 ac	Runoff coeff.	= 0.76
Intensity	= 5.406 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1




# Hydrograph Report

## Hyd. No. 7

Area 2-7

Hydrograph type	= Rational	Peak discharge	= 2.378 cfs
Storm frequency	= 2 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 714 cuft
Drainage area	= 0.500 ac	Runoff coeff.	= 0.88
Intensity	= 5.406 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 8

Area 2-8

Hydrograph type	= Rational	Peak discharge	= 1.348 cfs
Storm frequency	= 2 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 404 cuft
Drainage area	= 0.290 ac	Runoff coeff.	= 0.86
Intensity	= 5.406 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 9

Area 2-9

Hydrograph type	= Rational	Peak discharge	= 1.168 cfs
Storm frequency	= 2 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 350 cuft
Drainage area	= 0.240 ac	Runoff coeff.	= 0.9
Intensity	= 5.406 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1





# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 10

Area 2-10

Hydrograph type	= Rational	Peak discharge	= 1.700 cfs
Storm frequency	= 2 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 510 cuft
Drainage area	= 0.370 ac	Runoff coeff.	= 0.85
Intensity	= 5.406 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 11

Area 2-11

Hydrograph type	= Rational	Peak discharge	= 0.832 cfs
Storm frequency	= 2 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 250 cuft
Drainage area	= 0.350 ac	Runoff coeff.	= 0.44
Intensity	= 5.406 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021


Thursday, 06 / 9 / 2022

## Hyd. No. 12

Combined 1

Hydrograph type = Combine  
 Storm frequency = 2 yrs  
 Time interval = 1 min  
 Inflow hyds. = 1, 2, 3

Peak discharge = 30.19 cfs  
 Time to peak = 7 min  
 Hyd. volume = 18,409 cuft  
 Contrib. drain. area = 25.370 ac



# Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021


Thursday, 06 / 9 / 2022

## Hyd. No. 13

Combined 2

Hydrograph type = Combine  
Storm frequency = 2 yrs  
Time interval = 1 min  
Inflow hyds. = 4, 5, 7

Peak discharge = 6.749 cfs  
Time to peak = 5 min  
Hyd. volume = 2,025 cuft  
Contrib. drain. area = 1.750 ac



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 14

Combined 3

Hydrograph type	= Combine	Peak discharge	= 8.283 cfs
Storm frequency	= 2 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 2,485 cuft
Inflow hyds.	= 6, 8, 9, 10	Contrib. drain. area	= 1.890 ac



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 15

### TOTAL TO DETENTION

Hydrograph type	= Combine	Peak discharge	= 39.21 cfs
Storm frequency	= 2 yrs	Time to peak	= 7 min
Time interval	= 1 min	Hyd. volume	= 22,919 cuft
Inflow hyds.	= 12, 13, 14	Contrib. drain. area	= 0.000 ac



# Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021


Thursday, 06 / 9 / 2022

## Hyd. No. 16

### TOTAL DETENTION

Hydrograph type	= Reservoir	Peak discharge	= 0.439 cfs
Storm frequency	= 2 yrs	Time to peak	= 20 min
Time interval	= 1 min	Hyd. volume	= 22,913 cuft
Inflow hyd. No.	= 15 - TOTAL TO DETENTION	Max. Elevation	= 981.88 ft
Reservoir name	= Detention	Max. Storage	= 22,552 cuft

Storage Indication method used.



# Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021


Thursday, 06 / 9 / 2022

## Hyd. No. 17

### TOTAL RUNOFF

Hydrograph type = Combine  
Storm frequency = 2 yrs  
Time interval = 1 min  
Inflow hyds. = 11, 16

Peak discharge = 1.040 cfs  
Time to peak = 5 min  
Hyd. volume = 23,162 cuft  
Contrib. drain. area = 0.350 ac





# Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	Rational	15.57	1	10	9,342	-----	-----	-----	Area 2-1
2	Rational	7.213	1	10	4,328	-----	-----	-----	Area 2-2
3	Rational	20.61	1	7	8,655	-----	-----	-----	Area 2-3
4	Rational	4.416	1	5	1,325	-----	-----	-----	Area 2-4
5	Rational	0.815	1	5	245	-----	-----	-----	Area 2-5
6	Rational	4.868	1	5	1,460	-----	-----	-----	Area 2-6
7	Rational	2.847	1	5	854	-----	-----	-----	Area 2-7
8	Rational	1.614	1	5	484	-----	-----	-----	Area 2-8
9	Rational	1.398	1	5	419	-----	-----	-----	Area 2-9
10	Rational	2.035	1	5	610	-----	-----	-----	Area 2-10
11	Rational	0.996	1	5	299	-----	-----	-----	Area 2-11
12	Combine	36.55	1	7	22,324	1, 2, 3,	-----	-----	Combined 1
13	Combine	8.078	1	5	2,423	4, 5, 7,	-----	-----	Combined 2
14	Combine	9.914	1	5	2,974	6, 8, 9, 10,	-----	-----	Combined 3
15	Combine	47.35	1	7	27,722	12, 13, 14	-----	-----	TOTAL TO DETENTION
16	Reservoir	0.496	1	20	27,716	15	982.29	27,311	TOTAL DETENTION
17	Combine	1.220	1	5	28,014	11, 16	-----	-----	TOTAL RUNOFF
19076.As-BuiltConditions.04.11.2022.gpw					Return Period: 5 Year			Thursday, 06 / 9 / 2022	

# Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 1

Area 2-1

Hydrograph type	= Rational	Peak discharge	= 15.57 cfs
Storm frequency	= 5 yrs	Time to peak	= 10 min
Time interval	= 1 min	Hyd. volume	= 9,342 cuft
Drainage area	= 9.380 ac	Runoff coeff.	= 0.31
Intensity	= 5.355 in/hr	Tc by User	= 10.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 2

Area 2-2

Hydrograph type	= Rational	Peak discharge	= 7.213 cfs
Storm frequency	= 5 yrs	Time to peak	= 10 min
Time interval	= 1 min	Hyd. volume	= 4,328 cuft
Drainage area	= 4.490 ac	Runoff coeff.	= 0.3
Intensity	= 5.355 in/hr	Tc by User	= 10.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 3

Area 2-3

Hydrograph type	= Rational	Peak discharge	= 20.61 cfs
Storm frequency	= 5 yrs	Time to peak	= 7 min
Time interval	= 1 min	Hyd. volume	= 8,655 cuft
Drainage area	= 11.500 ac	Runoff coeff.	= 0.3
Intensity	= 5.973 in/hr	Tc by User	= 7.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 4

Area 2-4

Hydrograph type	= Rational	Peak discharge	= 4.416 cfs
Storm frequency	= 5 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 1,325 cuft
Drainage area	= 1.050 ac	Runoff coeff.	= 0.65
Intensity	= 6.470 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 5

Area 2-5

Hydrograph type	= Rational	Peak discharge	= 0.815 cfs
Storm frequency	= 5 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 245 cuft
Drainage area	= 0.200 ac	Runoff coeff.	= 0.63
Intensity	= 6.470 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 6

Area 2-6

Hydrograph type	= Rational	Peak discharge	= 4.868 cfs
Storm frequency	= 5 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 1,460 cuft
Drainage area	= 0.990 ac	Runoff coeff.	= 0.76
Intensity	= 6.470 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 7

Area 2-7

Hydrograph type	= Rational	Peak discharge	= 2.847 cfs
Storm frequency	= 5 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 854 cuft
Drainage area	= 0.500 ac	Runoff coeff.	= 0.88
Intensity	= 6.470 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1






# Hydrograph Report

## Hyd. No. 8

Area 2-8

Hydrograph type	= Rational	Peak discharge	= 1.614 cfs
Storm frequency	= 5 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 484 cuft
Drainage area	= 0.290 ac	Runoff coeff.	= 0.86
Intensity	= 6.470 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 9

Area 2-9

Hydrograph type	= Rational	Peak discharge	= 1.398 cfs
Storm frequency	= 5 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 419 cuft
Drainage area	= 0.240 ac	Runoff coeff.	= 0.9
Intensity	= 6.470 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 10

Area 2-10

Hydrograph type	= Rational	Peak discharge	= 2.035 cfs
Storm frequency	= 5 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 610 cuft
Drainage area	= 0.370 ac	Runoff coeff.	= 0.85
Intensity	= 6.470 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 11

Area 2-11

Hydrograph type	= Rational	Peak discharge	= 0.996 cfs
Storm frequency	= 5 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 299 cuft
Drainage area	= 0.350 ac	Runoff coeff.	= 0.44
Intensity	= 6.470 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021


Thursday, 06 / 9 / 2022

## Hyd. No. 12

Combined 1

Hydrograph type = Combine  
Storm frequency = 5 yrs  
Time interval = 1 min  
Inflow hyds. = 1, 2, 3

Peak discharge = 36.55 cfs  
Time to peak = 7 min  
Hyd. volume = 22,324 cuft  
Contrib. drain. area = 25.370 ac



# Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021


Thursday, 06 / 9 / 2022

## Hyd. No. 13

Combined 2

Hydrograph type = Combine  
Storm frequency = 5 yrs  
Time interval = 1 min  
Inflow hyds. = 4, 5, 7

Peak discharge = 8.078 cfs  
Time to peak = 5 min  
Hyd. volume = 2,423 cuft  
Contrib. drain. area = 1.750 ac



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 14

Combined 3

Hydrograph type	= Combine	Peak discharge	= 9.914 cfs
Storm frequency	= 5 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 2,974 cuft
Inflow hyds.	= 6, 8, 9, 10	Contrib. drain. area	= 1.890 ac



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 15

### TOTAL TO DETENTION

Hydrograph type	= Combine	Peak discharge	= 47.35 cfs
Storm frequency	= 5 yrs	Time to peak	= 7 min
Time interval	= 1 min	Hyd. volume	= 27,722 cuft
Inflow hyds.	= 12, 13, 14	Contrib. drain. area	= 0.000 ac





# Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021


Thursday, 06 / 9 / 2022

## Hyd. No. 16

### TOTAL DETENTION

Hydrograph type	= Reservoir	Peak discharge	= 0.496 cfs
Storm frequency	= 5 yrs	Time to peak	= 20 min
Time interval	= 1 min	Hyd. volume	= 27,716 cuft
Inflow hyd. No.	= 15 - TOTAL TO DETENTION	Max. Elevation	= 982.29 ft
Reservoir name	= Detention	Max. Storage	= 27,311 cuft

Storage Indication method used.



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 17

### TOTAL RUNOFF

Hydrograph type	= Combine	Peak discharge	= 1.220 cfs
Storm frequency	= 5 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 28,014 cuft
Inflow hyds.	= 11, 16	Contrib. drain. area	= 0.350 ac



# Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	Rational	17.68	1	10	10,606	----	----	----	Area 2-1
2	Rational	8.189	1	10	4,913	----	----	----	Area 2-2
3	Rational	23.40	1	7	9,828	----	----	----	Area 2-3
4	Rational	5.015	1	5	1,505	----	----	----	Area 2-4
5	Rational	0.926	1	5	278	----	----	----	Area 2-5
6	Rational	5.529	1	5	1,659	----	----	----	Area 2-6
7	Rational	3.233	1	5	970	----	----	----	Area 2-7
8	Rational	1.833	1	5	550	----	----	----	Area 2-8
9	Rational	1.587	1	5	476	----	----	----	Area 2-9
10	Rational	2.311	1	5	693	----	----	----	Area 2-10
11	Rational	1.132	1	5	339	----	----	----	Area 2-11
12	Combine	41.51	1	7	25,347	1, 2, 3,	----	----	Combined 1
13	Combine	9.175	1	5	2,752	4, 5, 7,	----	----	Combined 2
14	Combine	11.26	1	5	3,378	6, 8, 9, 10,	----	----	Combined 3
15	Combine	53.77	1	7	31,478	12, 13, 14	----	----	TOTAL TO DETENTION
16	Reservoir	0.540	1	20	31,472	15	982.60	31,033	TOTAL DETENTION
17	Combine	1.368	1	5	31,811	11, 16	----	----	TOTAL RUNOFF
19076.As-BuiltConditions.04.11.2022.gpw					Return Period: 10 Year			Thursday, 06 / 9 / 2022	

# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 1

Area 2-1

Hydrograph type	= Rational	Peak discharge	= 17.68 cfs
Storm frequency	= 10 yrs	Time to peak	= 10 min
Time interval	= 1 min	Hyd. volume	= 10,606 cuft
Drainage area	= 9.380 ac	Runoff coeff.	= 0.31
Intensity	= 6.079 in/hr	Tc by User	= 10.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 2

Area 2-2

Hydrograph type	= Rational	Peak discharge	= 8.189 cfs
Storm frequency	= 10 yrs	Time to peak	= 10 min
Time interval	= 1 min	Hyd. volume	= 4,913 cuft
Drainage area	= 4.490 ac	Runoff coeff.	= 0.3
Intensity	= 6.079 in/hr	Tc by User	= 10.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 3

Area 2-3

Hydrograph type	= Rational	Peak discharge	= 23.40 cfs
Storm frequency	= 10 yrs	Time to peak	= 7 min
Time interval	= 1 min	Hyd. volume	= 9,828 cuft
Drainage area	= 11.500 ac	Runoff coeff.	= 0.3
Intensity	= 6.782 in/hr	Tc by User	= 7.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 4

Area 2-4

Hydrograph type	= Rational	Peak discharge	= 5.015 cfs
Storm frequency	= 10 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 1,505 cuft
Drainage area	= 1.050 ac	Runoff coeff.	= 0.65
Intensity	= 7.348 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 5

Area 2-5

Hydrograph type	= Rational	Peak discharge	= 0.926 cfs
Storm frequency	= 10 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 278 cuft
Drainage area	= 0.200 ac	Runoff coeff.	= 0.63
Intensity	= 7.348 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1





# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 6

Area 2-6

Hydrograph type	= Rational	Peak discharge	= 5.529 cfs
Storm frequency	= 10 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 1,659 cuft
Drainage area	= 0.990 ac	Runoff coeff.	= 0.76
Intensity	= 7.348 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 7

Area 2-7

Hydrograph type	= Rational	Peak discharge	= 3.233 cfs
Storm frequency	= 10 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 970 cuft
Drainage area	= 0.500 ac	Runoff coeff.	= 0.88
Intensity	= 7.348 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 8

Area 2-8

Hydrograph type	= Rational	Peak discharge	= 1.833 cfs
Storm frequency	= 10 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 550 cuft
Drainage area	= 0.290 ac	Runoff coeff.	= 0.86
Intensity	= 7.348 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 9

Area 2-9

Hydrograph type	= Rational	Peak discharge	= 1.587 cfs
Storm frequency	= 10 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 476 cuft
Drainage area	= 0.240 ac	Runoff coeff.	= 0.9
Intensity	= 7.348 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 10

Area 2-10

Hydrograph type	= Rational	Peak discharge	= 2.311 cfs
Storm frequency	= 10 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 693 cuft
Drainage area	= 0.370 ac	Runoff coeff.	= 0.85
Intensity	= 7.348 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 11

Area 2-11

Hydrograph type	= Rational	Peak discharge	= 1.132 cfs
Storm frequency	= 10 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 339 cuft
Drainage area	= 0.350 ac	Runoff coeff.	= 0.44
Intensity	= 7.348 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021


Thursday, 06 / 9 / 2022

## Hyd. No. 12

Combined 1

Hydrograph type = Combine  
Storm frequency = 10 yrs  
Time interval = 1 min  
Inflow hyds. = 1, 2, 3

Peak discharge = 41.51 cfs  
Time to peak = 7 min  
Hyd. volume = 25,347 cuft  
Contrib. drain. area = 25.370 ac



# Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021


Thursday, 06 / 9 / 2022

## Hyd. No. 13

Combined 2

Hydrograph type = Combine  
Storm frequency = 10 yrs  
Time interval = 1 min  
Inflow hyds. = 4, 5, 7

Peak discharge = 9.175 cfs  
Time to peak = 5 min  
Hyd. volume = 2,752 cuft  
Contrib. drain. area = 1.750 ac





# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 14

Combined 3

Hydrograph type	= Combine	Peak discharge	= 11.26 cfs
Storm frequency	= 10 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 3,378 cuft
Inflow hyds.	= 6, 8, 9, 10	Contrib. drain. area	= 1.890 ac



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 15

### TOTAL TO DETENTION

Hydrograph type	= Combine	Peak discharge	= 53.77 cfs
Storm frequency	= 10 yrs	Time to peak	= 7 min
Time interval	= 1 min	Hyd. volume	= 31,478 cuft
Inflow hyds.	= 12, 13, 14	Contrib. drain. area	= 0.000 ac



# Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021


Thursday, 06 / 9 / 2022

## Hyd. No. 16

### TOTAL DETENTION

Hydrograph type	= Reservoir	Peak discharge	= 0.540 cfs
Storm frequency	= 10 yrs	Time to peak	= 20 min
Time interval	= 1 min	Hyd. volume	= 31,472 cuft
Inflow hyd. No.	= 15 - TOTAL TO DETENTION	Max. Elevation	= 982.60 ft
Reservoir name	= Detention	Max. Storage	= 31,033 cuft

Storage Indication method used.



# Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021


Thursday, 06 / 9 / 2022

## Hyd. No. 17

### TOTAL RUNOFF

Hydrograph type = Combine  
Storm frequency = 10 yrs  
Time interval = 1 min  
Inflow hyds. = 11, 16

Peak discharge = 1.368 cfs  
Time to peak = 5 min  
Hyd. volume = 31,811 cuft  
Contrib. drain. area = 0.350 ac



# Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	Rational	21.26	1	10	12,756	-----	-----	-----	Area 2-1
2	Rational	9.849	1	10	5,909	-----	-----	-----	Area 2-2
3	Rational	27.61	1	7	11,595	-----	-----	-----	Area 2-3
4	Rational	5.815	1	5	1,744	-----	-----	-----	Area 2-4
5	Rational	1.074	1	5	322	-----	-----	-----	Area 2-5
6	Rational	6.410	1	5	1,923	-----	-----	-----	Area 2-6
7	Rational	3.749	1	5	1,125	-----	-----	-----	Area 2-7
8	Rational	2.125	1	5	637	-----	-----	-----	Area 2-8
9	Rational	1.840	1	5	552	-----	-----	-----	Area 2-9
10	Rational	2.680	1	5	804	-----	-----	-----	Area 2-10
11	Rational	1.312	1	5	394	-----	-----	-----	Area 2-11
12	Combine	49.38	1	7	30,260	1, 2, 3,	-----	-----	Combined 1
13	Combine	10.64	1	5	3,191	4, 5, 7,	-----	-----	Combined 2
14	Combine	13.06	1	5	3,917	6, 8, 9, 10,	-----	-----	Combined 3
15	Combine	63.60	1	7	37,368	12, 13, 14	-----	-----	TOTAL TO DETENTION
16	Reservoir	0.695	1	20	37,362	15	983.07	36,858	TOTAL DETENTION
17	Combine	1.566	1	5	37,756	11, 16	-----	-----	TOTAL RUNOFF
19076.As-BuiltConditions.04.11.2022.gpw					Return Period: 25 Year			Thursday, 06 / 9 / 2022	

# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 1

Area 2-1

Hydrograph type	= Rational	Peak discharge	= 21.26 cfs
Storm frequency	= 25 yrs	Time to peak	= 10 min
Time interval	= 1 min	Hyd. volume	= 12,756 cuft
Drainage area	= 9.380 ac	Runoff coeff.	= 0.31
Intensity	= 7.312 in/hr	Tc by User	= 10.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1




# Hydrograph Report

## Hyd. No. 2

Area 2-2

Hydrograph type	= Rational	Peak discharge	= 9.849 cfs
Storm frequency	= 25 yrs	Time to peak	= 10 min
Time interval	= 1 min	Hyd. volume	= 5,909 cuft
Drainage area	= 4.490 ac	Runoff coeff.	= 0.3
Intensity	= 7.312 in/hr	Tc by User	= 10.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 3

Area 2-3

Hydrograph type	= Rational	Peak discharge	= 27.61 cfs
Storm frequency	= 25 yrs	Time to peak	= 7 min
Time interval	= 1 min	Hyd. volume	= 11,595 cuft
Drainage area	= 11.500 ac	Runoff coeff.	= 0.3
Intensity	= 8.002 in/hr	Tc by User	= 7.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1





# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 4

Area 2-4

Hydrograph type	= Rational	Peak discharge	= 5.815 cfs
Storm frequency	= 25 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 1,744 cuft
Drainage area	= 1.050 ac	Runoff coeff.	= 0.65
Intensity	= 8.520 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 5

Area 2-5

Hydrograph type	= Rational	Peak discharge	= 1.074 cfs
Storm frequency	= 25 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 322 cuft
Drainage area	= 0.200 ac	Runoff coeff.	= 0.63
Intensity	= 8.520 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 6

Area 2-6

Hydrograph type	= Rational	Peak discharge	= 6.410 cfs
Storm frequency	= 25 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 1,923 cuft
Drainage area	= 0.990 ac	Runoff coeff.	= 0.76
Intensity	= 8.520 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 7

Area 2-7

Hydrograph type	= Rational	Peak discharge	= 3.749 cfs
Storm frequency	= 25 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 1,125 cuft
Drainage area	= 0.500 ac	Runoff coeff.	= 0.88
Intensity	= 8.520 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 8

Area 2-8

Hydrograph type	= Rational	Peak discharge	= 2.125 cfs
Storm frequency	= 25 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 637 cuft
Drainage area	= 0.290 ac	Runoff coeff.	= 0.86
Intensity	= 8.520 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 9

Area 2-9

Hydrograph type	= Rational	Peak discharge	= 1.840 cfs
Storm frequency	= 25 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 552 cuft
Drainage area	= 0.240 ac	Runoff coeff.	= 0.9
Intensity	= 8.520 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 10

Area 2-10

Hydrograph type	= Rational	Peak discharge	= 2.680 cfs
Storm frequency	= 25 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 804 cuft
Drainage area	= 0.370 ac	Runoff coeff.	= 0.85
Intensity	= 8.520 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 11

Area 2-11

Hydrograph type	= Rational	Peak discharge	= 1.312 cfs
Storm frequency	= 25 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 394 cuft
Drainage area	= 0.350 ac	Runoff coeff.	= 0.44
Intensity	= 8.520 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1





# Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021


Thursday, 06 / 9 / 2022

## Hyd. No. 12

Combined 1

Hydrograph type = Combine  
Storm frequency = 25 yrs  
Time interval = 1 min  
Inflow hyds. = 1, 2, 3

Peak discharge = 49.38 cfs  
Time to peak = 7 min  
Hyd. volume = 30,260 cuft  
Contrib. drain. area = 25.370 ac



# Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021


Thursday, 06 / 9 / 2022

## Hyd. No. 13

Combined 2

Hydrograph type = Combine  
Storm frequency = 25 yrs  
Time interval = 1 min  
Inflow hyds. = 4, 5, 7

Peak discharge = 10.64 cfs  
Time to peak = 5 min  
Hyd. volume = 3,191 cuft  
Contrib. drain. area = 1.750 ac



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 14

Combined 3

Hydrograph type	= Combine	Peak discharge	= 13.06 cfs
Storm frequency	= 25 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 3,917 cuft
Inflow hyds.	= 6, 8, 9, 10	Contrib. drain. area	= 1.890 ac



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 15

### TOTAL TO DETENTION

Hydrograph type	= Combine	Peak discharge	= 63.60 cfs
Storm frequency	= 25 yrs	Time to peak	= 7 min
Time interval	= 1 min	Hyd. volume	= 37,368 cuft
Inflow hyds.	= 12, 13, 14	Contrib. drain. area	= 0.000 ac



# Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021


Thursday, 06 / 9 / 2022

## Hyd. No. 16

### TOTAL DETENTION

Hydrograph type	= Reservoir	Peak discharge	= 0.695 cfs
Storm frequency	= 25 yrs	Time to peak	= 20 min
Time interval	= 1 min	Hyd. volume	= 37,362 cuft
Inflow hyd. No.	= 15 - TOTAL TO DETENTION	Max. Elevation	= 983.07 ft
Reservoir name	= Detention	Max. Storage	= 36,858 cuft

Storage Indication method used.



# Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021


Thursday, 06 / 9 / 2022

## Hyd. No. 17

### TOTAL RUNOFF

Hydrograph type = Combine  
Storm frequency = 25 yrs  
Time interval = 1 min  
Inflow hyds. = 11, 16

Peak discharge = 1.566 cfs  
Time to peak = 5 min  
Hyd. volume = 37,756 cuft  
Contrib. drain. area = 0.350 ac



# Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	Rational	28.02	1	10	16,812	----	----	----	Area 2-1
2	Rational	12.98	1	10	7,788	----	----	----	Area 2-2
3	Rational	39.03	1	7	16,394	----	----	----	Area 2-3
4	Rational	8.784	1	5	2,635	----	----	----	Area 2-4
5	Rational	1.622	1	5	487	----	----	----	Area 2-5
6	Rational	9.684	1	5	2,905	----	----	----	Area 2-6
7	Rational	5.663	1	5	1,699	----	----	----	Area 2-7
8	Rational	3.210	1	5	963	----	----	----	Area 2-8
9	Rational	2.780	1	5	834	----	----	----	Area 2-9
10	Rational	4.048	1	5	1,214	----	----	----	Area 2-10
11	Rational	1.982	1	5	595	----	----	----	Area 2-11
12	Combine	67.73	1	7	40,993	1, 2, 3,	----	----	Combined 1
13	Combine	16.07	1	5	4,821	4, 5, 7,	----	----	Combined 2
14	Combine	19.72	1	5	5,917	6, 8, 9, 10,	----	----	Combined 3
15	Combine	89.21	1	7	51,731	12, 13, 14	----	----	TOTAL TO DETENTION
16	Reservoir	5.833	1	19	51,725	15	983.93	49,371	TOTAL DETENTION
17	Combine	5.833	1	19	52,319	11, 16	----	----	TOTAL RUNOFF
19076.As-BuiltConditions.04.11.2022.gpw					Return Period: 100 Year			Thursday, 06 / 9 / 2022	

# Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021


Thursday, 06 / 9 / 2022

## Hyd. No. 1

Area 2-1

Hydrograph type = Rational  
Storm frequency = 100 yrs  
Time interval = 1 min  
Drainage area = 9.380 ac  
Intensity = 9.636 in/hr  
IDF Curve = KCAPWA.IDF

Peak discharge = 28.02 cfs  
Time to peak = 10 min  
Hyd. volume = 16,812 cuft  
Runoff coeff. = 0.31  
Tc by User = 10.00 min  
Asc/Rec limb fact = 1/1






# Hydrograph Report

## Hyd. No. 2

Area 2-2

Hydrograph type	= Rational	Peak discharge	= 12.98 cfs
Storm frequency	= 100 yrs	Time to peak	= 10 min
Time interval	= 1 min	Hyd. volume	= 7,788 cuft
Drainage area	= 4.490 ac	Runoff coeff.	= 0.3
Intensity	= 9.636 in/hr	Tc by User	= 10.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021


Thursday, 06 / 9 / 2022

## Hyd. No. 3

Area 2-3

Hydrograph type = Rational  
Storm frequency = 100 yrs  
Time interval = 1 min  
Drainage area = 11.500 ac  
Intensity = 11.314 in/hr  
IDF Curve = KCAPWA.IDF

Peak discharge = 39.03 cfs  
Time to peak = 7 min  
Hyd. volume = 16,394 cuft  
Runoff coeff. = 0.3  
Tc by User = 7.00 min  
Asc/Rec limb fact = 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 4

Area 2-4

Hydrograph type	= Rational	Peak discharge	= 8.784 cfs
Storm frequency	= 100 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 2,635 cuft
Drainage area	= 1.050 ac	Runoff coeff.	= 0.65
Intensity	= 12.871 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 5

Area 2-5

Hydrograph type	= Rational	Peak discharge	= 1.622 cfs
Storm frequency	= 100 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 487 cuft
Drainage area	= 0.200 ac	Runoff coeff.	= 0.63
Intensity	= 12.871 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 6

Area 2-6

Hydrograph type	= Rational	Peak discharge	= 9.684 cfs
Storm frequency	= 100 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 2,905 cuft
Drainage area	= 0.990 ac	Runoff coeff.	= 0.76
Intensity	= 12.871 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 7

Area 2-7

Hydrograph type	= Rational	Peak discharge	= 5.663 cfs
Storm frequency	= 100 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 1,699 cuft
Drainage area	= 0.500 ac	Runoff coeff.	= 0.88
Intensity	= 12.871 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 8

Area 2-8

Hydrograph type	= Rational	Peak discharge	= 3.210 cfs
Storm frequency	= 100 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 963 cuft
Drainage area	= 0.290 ac	Runoff coeff.	= 0.86
Intensity	= 12.871 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 9

Area 2-9

Hydrograph type	= Rational	Peak discharge	= 2.780 cfs
Storm frequency	= 100 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 834 cuft
Drainage area	= 0.240 ac	Runoff coeff.	= 0.9
Intensity	= 12.871 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1





# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 10

Area 2-10

Hydrograph type	= Rational	Peak discharge	= 4.048 cfs
Storm frequency	= 100 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 1,214 cuft
Drainage area	= 0.370 ac	Runoff coeff.	= 0.85
Intensity	= 12.871 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 11

Area 2-11

Hydrograph type	= Rational	Peak discharge	= 1.982 cfs
Storm frequency	= 100 yrs	Time to peak	= 5 min
Time interval	= 1 min	Hyd. volume	= 595 cuft
Drainage area	= 0.350 ac	Runoff coeff.	= 0.44
Intensity	= 12.871 in/hr	Tc by User	= 5.00 min
IDF Curve	= KCAPWA.IDF	Asc/Rec limb fact	= 1/1



# Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021


Thursday, 06 / 9 / 2022

## Hyd. No. 12

Combined 1

Hydrograph type = Combine  
 Storm frequency = 100 yrs  
 Time interval = 1 min  
 Inflow hyds. = 1, 2, 3

Peak discharge = 67.73 cfs  
 Time to peak = 7 min  
 Hyd. volume = 40,993 cuft  
 Contrib. drain. area = 25.370 ac



# Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021


Thursday, 06 / 9 / 2022

## Hyd. No. 13

Combined 2

Hydrograph type = Combine  
 Storm frequency = 100 yrs  
 Time interval = 1 min  
 Inflow hyds. = 4, 5, 7

Peak discharge = 16.07 cfs  
 Time to peak = 5 min  
 Hyd. volume = 4,821 cuft  
 Contrib. drain. area = 1.750 ac



# Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021


Thursday, 06 / 9 / 2022

## Hyd. No. 14

Combined 3

Hydrograph type = Combine  
 Storm frequency = 100 yrs  
 Time interval = 1 min  
 Inflow hyds. = 6, 8, 9, 10

Peak discharge = 19.72 cfs  
 Time to peak = 5 min  
 Hyd. volume = 5,917 cuft  
 Contrib. drain. area = 1.890 ac



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 15

### TOTAL TO DETENTION

Hydrograph type	= Combine	Peak discharge	= 89.21 cfs
Storm frequency	= 100 yrs	Time to peak	= 7 min
Time interval	= 1 min	Hyd. volume	= 51,731 cuft
Inflow hyds.	= 12, 13, 14	Contrib. drain. area	= 0.000 ac



# Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021


Thursday, 06 / 9 / 2022

## Hyd. No. 16

### TOTAL DETENTION

Hydrograph type	= Reservoir	Peak discharge	= 5.833 cfs
Storm frequency	= 100 yrs	Time to peak	= 19 min
Time interval	= 1 min	Hyd. volume	= 51,725 cuft
Inflow hyd. No.	= 15 - TOTAL TO DETENTION	Max. Elevation	= 983.93 ft
Reservoir name	= Detention	Max. Storage	= 49,371 cuft

Storage Indication method used.



# Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

## Hyd. No. 17

### TOTAL RUNOFF

Hydrograph type	= Combine	Peak discharge	= 5.833 cfs
Storm frequency	= 100 yrs	Time to peak	= 19 min
Time interval	= 1 min	Hyd. volume	= 52,319 cuft
Inflow hyds.	= 11, 16	Contrib. drain. area	= 0.350 ac





# Hydraflow Rainfall Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2021

Thursday, 06 / 9 / 2022

Return Period (Yrs)	Intensity-Duration-Frequency Equation Coefficients (FHA)			
	B	D	E	(N/A)
1	2.9200	0.1000	0.0000	-----
2	110.7137	16.5000	0.9842	-----
3	0.0000	0.0000	0.0000	-----
5	168.3971	19.5000	1.0189	-----
10	183.3473	19.2000	1.0096	-----
25	12318.8496	51.4998	1.8037	-----
50	235.4014	19.9000	1.0020	-----
100	83.7894	6.1000	0.7783	-----

File name: KCAPWA.IDF

$$\text{Intensity} = B / (T_c + D)^E$$

Return Period (Yrs)	Intensity Values (in/hr)											
	5 min	10	15	20	25	30	35	40	45	50	55	60
1	2.92	2.92	2.92	2.92	2.92	2.92	2.92	2.92	2.92	2.92	2.92	2.92
2	5.41	4.40	3.71	3.21	2.83	2.53	2.29	2.09	1.92	1.78	1.66	1.55
3	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
5	6.47	5.35	4.56	3.98	3.52	3.16	2.86	2.62	2.41	2.24	2.08	1.95
10	7.35	6.08	5.18	4.52	4.00	3.59	3.26	2.98	2.74	2.54	2.37	2.22
25	8.52	7.31	6.35	5.57	4.93	4.40	3.95	3.57	3.24	2.96	2.72	2.50
50	9.39	7.82	6.70	5.86	5.20	4.68	4.25	3.90	3.60	3.34	3.12	2.92
100	12.87	9.64	7.81	6.62	5.77	5.14	4.65	4.25	3.92	3.65	3.41	3.21

T<sub>c</sub> = time in minutes. Values may exceed 60.

Precip. file name: bluesprings.pcp

Storm Distribution	Rainfall Precipitation Table (in)							
	1-yr	2-yr	3-yr	5-yr	10-yr	25-yr	50-yr	100-yr
SCS 24-hour	2.90	3.50	0.00	4.50	5.30	6.10	6.80	7.70
SCS 6-Hr	0.00	2.65	0.00	3.30	3.45	4.50	5.10	5.70
Huff-1st	0.00	1.55	0.00	2.75	4.00	5.38	6.50	8.00
Huff-2nd	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Huff-3rd	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Huff-4th	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Huff-Indy	0.00	1.55	0.00	2.75	4.00	5.38	6.50	8.00
Custom	0.00	1.75	0.00	2.80	3.90	5.25	6.00	7.10