

Luminaire Schedule							
Symbol	Qty	Label	Arrangement	LMF	Lum. Lumens	Lum. Watts	Part Number
	16	OSQ-4b	SINGLE	1.000	7075	130	OSQ-M-B-9L-40K7-4M-__-NM-__ w/OSQ-ML-B-DA__ - OSQ-BLSMF
	11	OSQ-5Q	2 @ 180°	1.000	10250	60	OSQ-M-B-9L-40K7-5Q-__-NM-__ w/OSQ-ML-B-DA__
	41	XP3	SINGLE	1.000	4270	31	XSPW-B-WM-3ME-4L-40K-__-__
	23	XP4	SINGLE	1.000	4270	31	XSPW-B-WM-4ME-4L-40K-__-__

Calculation Summary (Footcandles calculated using initial lumen values @ 25°C)						
Label	Units	Avg	Max	Min	Avg/Min	Max/Min
CalcPts	Fc	1.09	9.7	0.0	N.A.	N.A.
Property Line	Fc	0.06	0.4	0.0	N.A.	N.A.
PAVED AREA	Fc	2.03	9.7	0.0	N.A.	N.A.

Pole Mount Fixture Height: 15' AFG (12' pole +3' base)

Pole Schedule
(16) SSS-4-11-12-CW-BS-1D-C-__ (12' X 4" X 11ga STEEL SQUARE POLE)
(11) SSS-4-11-12-CW-BS-2D18-C-__ (12' X 4" X 11ga STEEL SQUARE POLE)
Proposed poles meet 140 MPH sustained winds.

Additional Equipment:
(38) OSQ-ML-B-DA__ (Direct Arm Mount)

*** CUSTOMER TO VERIFY ORDERING INFORMATION AND CATALOGUE NUMBER PRIOR TO PLACING ORDER ***

