Final Stormwater Management Plan

prepared for

Residences at Blackwell Traditions at Blackwell Blackwell Reserve

Lee's Summit, MO 64081

November 18, 2022

prepared by



14920 W 107th ST Lenexa, Kansas (913) 492-5158 Schlagel & Associates Project 20-205

for

Griffin Riley Property Group 21 SE 29th Terrace Lee's Summit, Missouri 64082

Executive Summary

November 18, 2022

Gene Williams, P.E. 220 SE Green Street Lee's Summit, MO 64063

RE: Residences at Blackwell

Blue Parkway & Blackwell Road

Lee's Summit, MO 64081

Dear Gene Williams,

We are submitting the enclosed final stormwater management study in support of the site development plan for The Residences at Blackwell, a proposed 252 unit Multi-family development. Also included in this study is the preliminary stormwater analysis for The Traditions at Blackwell and Blackwell Reserve, the townhome and single-family phases of this multi-phase project. Final design for these phases will be submitted with the respective final plats of each phase This report has been prepared to address permitting requirements and provides final design calculations for the required storm water detention and BMP facilities. We have modeled the existing site conditions as they existed at the time this report was prepared.

The proposed site is a 62.40-acre mixed use parcel located in Lee's Summit, MO at the intersection of Blue Parkway and Blackwell Road. The proposed development has been analyzed and designed to meet the APWA Comprehensive Control Strategy, which entails limiting post-development peak discharge rates from the site for the 2-Year, 10-Year, and 100-Year design storm events. One Extended Dry Detention Basin (EDDB) and three Extended Wet Detention Basins (EWDB) have been designed to detain the mentioned events as well as provided 40-hour detention of runoff from the local 90% mean annual event. All elements of the enclosed drainage system will be designed and constructed in accordance with all City of Lee's Summit, Missouri, requirements.

Sincerely,

Schlagel & Associates, P.A.

Michael Moore, E.I.T. Design Engineer



Mark Breuer, P.E. Project Engineer

TABLE OF CONTENTS

			<u>Page No.</u>
TABI	LE OF	CONTENTS	
LIST	OF TA	ABLES	IV
LIST	OF FI	GURES	V
1.0	GEN	ERAL INFORMATION	1-1
	1.1	Objective	
	1.2	Methodology	1-1
2.0		TING CONDITIONS ANALYSIS	
	2.1 2.2	Tributary Areas	
	2.2	Curve Number and Time of Concentration Existing Flow Rates	
	2.4	Downstream Drainage Issues	
	2.5	Agency Review	
		2.5.1 Corps of Engineers Review	
		2.5.2 FEMA Requirements	
		2.5.3 Missouri Department of Natural Resources	
3.0		POSED CONDITIONS ANALYSIS	
	3.1 3.2	Tributary Areas Curve Number and Time of Concentration	
	3.3	Proposed Flow Rates	
	3.4	Detention Analysis	
4.0	SUM	MARY AND RECOMMENDATIONS	4-1
APPI	ENDIX	A	A
-EXIS	STING	SITE AERIAL PHOTOGRAPH	A.1
-EXIS	STING	DRAINAGE MAP	A.2
-PRC	POSE	D DRAINAGE MAP	A.3
		TER QUALITY DESIGN	
		METTE	
-NAT	IONAL	_ WETLANDS INVENTORY	A.6
		EL OF SERVICE	
APPI	ENDIX	В	В
-NRC	S SOI	L RESOURCE REPORT	B.1
-HYD	ROCA	ND MODEL OUTPUT REPORT	B 2
		DELINEATION AND JURISDICTIONAL ASSESSMENT	

LIST OF TABLES

<u>Table No.</u>	<u>Page No.</u>
Table 2-1 - Existing Flow Rates	2-3
Table 3-1 – HydroCAD Runoff Conditions	3-3
Table 3-2.B – Allowable Release Rate Calculations	3-5
Table 3-3.B - Required & Proposed Runoff Comparison	3-6

LIST OF FIGURES

<u>Figure No.</u>	<u>Page No.</u>
Figure A.1 – Existing Site Aerial Photograph	
Figure A.3 – Proposed Drainage Map Figure A.4 – FEMA FIRMette	Appendix A
Figure A.5 – National Wetlands Inventory	• •
NRCS Soil Survey Report	

1.0 GENERAL INFORMATION

Griffin Riley Property Group is proposing to develop the 62.40 acres of land located in Section 11, Township 47 North, Range 31 West, Jackson County, Missouri. The property is located at the intersection of Blue Parkway and Blackwell Road. The proposed development consists of single-family lots, townhomes, apartments, and commercial use along with associated infrastructure.

1.1 OBJECTIVE

The intent of this report is to provide information pertaining to the existing and proposed watersheds, identifying and addressing any downstream drainage issues, determine and address any detention requirements, provide 40-hour extended detention of runoff from the local 90% mean annual event, and address permitting requirements. This study provides the preliminary design calculations for the development of the facility and associated infrastructure. Detailed designs will be required and provided with permit documents.

1.2 METHODOLOGY

The following were utilized in the assessment, preparation and analysis of watersheds in this design concept plan: Section 5600, 2011, Storm Drainage Systems & Facilities of the Standard Specifications & Design Criteria of the Kansas City Metropolitan Chapter of the American Public Works Association; City of Lee's Summit, Missouri Design Criteria (2011 Revision), Storm Drainage Systems & Facilities, prepared by the City of Lee's Summit, Missouri, Public Works Department.

Watersheds for the site were defined according to soil cover and type, tributary area, and runoff times of concentration. Soil cover was determined from inspection of the site and aerial photography. A soil survey for the project area was obtained from the United States Department of Agriculture, Natural Resources Conservation Service (NRCS), website and was utilized in determining soil type. The entire NRCS Soil Resource

Report can be found in Appendix B. Watershed size was determined from both aerial topography and topographical survey, and by the proposed grading plan.

Times of concentration were compiled according to *NRCS TR-55 Urban Hydrology for Small Watersheds (1986)* methodology for sheet flow, shallow concentrated flow, and channel flow. For this report, sheet flow travel lengths were modeled at a total distance of 100'. Travel times for channel flows were determined using the length and velocity of the open channel. *HydroCAD-10* was utilized to model the runoff. All storm events were modeled using *SCS 24-hour Type II* distributions and were modeled for 2-Year, 10-Year, and 100-Year storm events.

2.0 EXISTING CONDITIONS ANALYSIS

The site lies within the East Fork Little Blue River Watershed. The existing site contains 4 watersheds which have release points located in the southwest, northwest, northern boundary, and eastern boundary of the site. Offsite stormwater comes into the site from south and drains to the release point located along the eastern boundary.

2.1 TRIBUTARY AREAS

The existing drainage tributary map is provided in Appendix A, Figure A.1. The site release points have been identified as Release Point 1(RP-1), Release Point 2 (RP-2), Release Point 3 (RP-3), and Release Point 4 (RP-4). The area has been delineated according to the existing topography and an annotation callout of EX DA-1, EX DA-2, EX DA-3, EX DA-4, and EX OFF DA-4, on Figure A.2, have been provided for the watersheds that drain to the release points RP-1 – RP-4 respectively.

2.2 CURVE NUMBER AND TIME OF CONCENTRATION

The existing curve numbers and time of concentrations for each area have been established based on the procedures outlined in *NRCS TR-55 Urban Hydrology for Small Watersheds (1986)*. Existing curve numbers were based upon aerial photography, site inspection, and the soil types present on site.

The NRCS Soil Resource Report indicated that a Hydrologic Soil Group (HSG) of C and D were present on site. A current aerial photograph can be found in Appendix A; it depicts the existing cover conditions. Table 2-1 found in section 2.3 Existing Flow Rates summarizes the curve numbers for each of the watershed areas.

Cover types for existing conditions were considered to be "pasture/grassland" in fair condition for the on-site area, and "Woods/grass combo" in fair condition for the off-site area. Procedures outlined in *NRCS TR-55 Urban Hydrology for Small Watersheds* recommends utilizing curve numbers 79 and 84 for HSG C and D for pasture/grassland, and 76 and 82 for the Woods/Grass combination.

Time of concentration flow paths were based upon sheet flow and shallow concentrated flow for the existing conditions. Sheet flow lengths were limited to where a grade break occurred. Flow was then considered shallow concentrated flow until a channel was visible either from the USGS topographic map or the aerial photograph, and then from that point was considered channel flow determined by the length of the channel and the velocity of flow.

2.3 EXISTING FLOW RATES

Existing flow rates were determined for the 2-Year, 10-Year, and 100-Year design storms. Offsite runoff is included in the calculations for Table 2-1 below for existing site conditions. Appropriate runoff coefficient curve numbers were based upon aerial photography, site inspection, and the soil types present on site. Detailed calculations with composite curve numbers and time of concentration can be found in the HydroCAD Model Output in Appendix B.

Table 2-1 - Existing Flow Rates

Drainage Sub-	Area	CN	Storm	Runoff	
Basin	(Acres)		Event	(CFS)	
			2-YR	14.34	
EX DA-1	9.52	79	10-YR	28.81	
			100-YR	48.20	
			2-YR	7.26	
EX DA-2	4.28	80	10-YR	14.09	
			100-YR	23.62	
			2-YR	36.97	
EX DA-3	29.35	80	80	10-YR	72.33
			100-YR	121.81	
			2-YR	31.44	
EX DA-4	19.25	82	10-YR	64.09	
			100-YR	110.52	
			2-YR	11.43	
EX OFF DA-4	A-4 4.58	92	10-YR	18.56	
			100-YR	27.98	

2.4 DOWNSTREAM DRAINAGE ISSUES

The existing downstream drainage system has been reviewed with this development plan. FEMA flood maps have been checked and currently no immediate downstream issues appear to be present. A FEMA FIRMette is included in Appendix A. The project lies outside of the identified FEMA floodplain per map numbers 29095C0437G, 29095C0439G, 29095C0441G, and 29095C0445G.

2.5 AGENCY REVIEW

Permitting requirements of the following agencies were reviewed as part of the existing conditions analysis.

2.5.1 Corps of Engineers Review

The National Wetlands Inventory (NWI) map was reviewed for the site and there are no identified wetlands located within the project site. The NWI map can be found in Appendix A. A jurisdictional determination is being prepared by others, and any required wetland permitting or mitigation will be completed prior to land disturbance of the wetlands.

2.5.2 FEMA Requirements

No FEMA identified floodplain is located on the proposed property per Flood Insurance Rate Map Panel Nos. 29095C0437G, 29095C0439G, 29095C0441G, and 29095C0445G. There is currently no work proposed in the regulated floodplain. Please see the attached FEMA FIRMette in Appendix A.

2.5.3 Missouri Department of Natural Resources

All land disturbance activities will be permitted in accordance with the City of Lee's Summit, MO specifications as well as the Missouri Department of Water Pollution Control general permit under the National Pollution Discharge Elimination System (NPDES) and an authorized Notice of Intent (NOI) application form. The disturbance of the site is greater than one acre; therefore, NPDES and NOI applications are required with the future permitting of the site in compliance with local, state and federal guidelines.

3.0 PROPOSED CONDITIONS ANALYSIS

With the proposed development, the site watershed will be divided into four sub-basins for analysis. These sub-basins correspond to: Release Points 1-4. Stormwater runoff will be conveyed through the site via open sheet flow, shallow concentrated flow, enclosed storm sewer, one extended dry detention basin, and three extended wet detention basins. All detention facilities have been designed to detain the 2-Year, 10-Year, and 100-Year storm events.

All components of the overland and enclosed storm sewer systems will meet or exceed the specifications provided in *Section 5600 – Storm Drainage Systems & Facilities* of the *Standard Specifications and Design Criteria* compiled by the Kansas City Metropolitan Chapter of the American Public Works Association.

3.1 TRIBUTARY AREAS

RP-1 will be divided into two sub-catchments, Onsite 1 and Onsite 2. Onsite 1 will bypass the proposed extended dry detention basin, while Onsite 2 will be collected by the extended dry detention basin and then released to two existing 24" pipes located under Blue Parkway. RP-2 sub-catchment existing flows are proposed to be routed to the detention facility located in the northeast corner of the site. RP-3 will also be divided into two sub-catchments, Onsite 3 and Onsite 4. Onsite 3 will be collected by a proposed extended wet detention basin. It will then be routed downstream to a second proposed extended wet detention basin that will collect Onsite 4 and then be released via storm sewer to an existing area inlet located directly north of our proposed site. Final design of this basin will be designed to ensure the downstream storm sewer system does not exceed the 100-year storm event. RP-4 sub-catchment, Onsite 5, will be collected by an extended wet detention basin. The proposed extended wet detention basin will also collect the off-site area, EX OFF, from the south. Stormwater runoff will be released into the existing swale and continue to flow to the northeast.

3.2 CURVE NUMBER AND TIME OF CONCENTRATION

Curve numbers for the proposed development were developed in a similar manner as the existing conditions. Hydrologic Soil Group (HSG) of D was utilized for post-development conditions. Cover types for the proposed conditions were considered to be 1/8 acre lots, Multi-Family, Single Family lots, and urban commercial in good condition.

Time of concentration was established in a similar manner as the existing conditions. Shallow concentrated flow lengths were shortened and considered paved. Detailed calculations with composite curve numbers and time of concentration can be found in the HydroCAD Model Output in Appendix B. Appendix A, Figure A.2 depicts the proposed drainage conditions.

3.3 PROPOSED FLOW RATES

Proposed flow rates were determined for the 2-Year, 10-Year, and 100-Year design storms. Detailed calculations can be found in the HydroCAD Model Output Report in Appendix B.

Table 3-1 – HydroCAD Runoff Conditions

Drainage	Drainage Area	Storm	Peak
Sub-Basin	(Acres)	Event	Discharge
			(CFS)
		2-YR	2.43
*OnSite 1	0.54	10-YR	3.79
		100-YR	5.58
		2-YR	22.39
*OnSite 2	4.97	10-YR	34.88
		100-YR	51.36
		2-YR	44.14
*OnSite 3	10.76	10-YR	71.05
		100-YR	106.44
		2-YR	88.82
*OnSite 4	25.50	10-YR	143.48
		100-YR	215.38
		2-YR	69.12
OnSite 5	17.37	10-YR	116.83
		100-YR	179.92
		2-YR	27.58
EX OFF	6.93	10-YR	46.61
		100-YR	71.78

^{*}Preliminary Calculations

3.4 DETENTION ANALYSIS

The runoff hydrographs utilized to determine the peak flow volumes for each tributary area were determined using *TR-55* methodology and *HydroCAD-10*. For the 2-Year, 10-Year, and 100-Year storm events, the complete hydrograph routing and model output can be found in the HydroCAD Model Output Report in Appendix B.

The site will need to provide detention that meets the requirement under the Comprehensive Control release rates under Section 5608.4C1a and 5608.4C1b of the APWA. This entails limiting post-development peak discharge rates from the site for the 2-Year, 10-Year, and 100-Year design storm events, as well as providing 40-Hour extended detention of runoff from the local 90% mean annual event. The post-development peak discharge rates from the site shall not exceed the following:

- 50% storm peak rate less than or equal to 0.5 cfs per site acre
- 10% storm peak rate less than or equal to 2.0 cfs per site acre
- 1% storm peak rate less than or equal to 3.0 cfs per site acre

For Release Points 1, 3, and 4, HydroCAD output represents the design release rate. For Release Point 2, we propose to route all existing flows to the proposed detention facility located in the northeast corner of the site.

Table 3-1 – HydroCAD Runoff Conditions are shown in Table 3-3.B - Required & Proposed Runoff Comparison. The proposed post-development design release rates are shown next to the allowable release rates for comparison.

Table 3-2.B - Allowable Release Rate Calculations

	Allowable Release Rate (CFS) Calculations							
Release	Area	Storm	Allowable	Allowable	Allowable			
Point	(Acres)	Event	On-Site	Off-Site	Release			
			Release	Release	Rate (CFS)			
			Rate (CFS)	Rate (CFS)	(A+B)			
			(A)	(B)				
		2-YR	2.76	0.00	2.76			
*RP-1	5.51	10-YR	11.02	0.00	11.02			
		100-YR	16.53	0.00	16.53			
		2-YR	18.16	0.00	18.16			
*RP-3	36.31	10-YR	72.62	0.00	72.62			
		100-YR	108.93	0.00	108.93			
		2-YR	8.69	27.58	36.27			
RP-4	24.30	10-YR	34.74	46.61	81.35			
		100-YR	52.11	71.78	123.89			

^{*}Preliminary Calculations

Table 3-3.B - Required & Proposed Runoff Comparison

Si	Site Release Information (cubic feet per second) (w/ EDDB)							
Area	Drainage Area	Storm Event	Allowable	Design				
			Release Rate	Release Rate				
			(CFS)	(CFS)				
*RP-1	5.51	2-YR	2.76	2.67				
		10-YR	11.02	4.05				
		100-YR	16.53	15.22				
*RP-3	36.31	2-YR	18.16	13.80				
		10-YR	72.62	35.30				
		100-YR	108.93	87.30				
RP-4	24.30	2-YR	36.27	15.00				
		10-YR	81.35	29.51				
		100-YR	123.89	39.74				

^{*}Preliminary Calculations

Please note: Site release rates are not a direct addition of sub-basin runoff due to differences in the time peak as well as storage effects within the basins.

Proposed stormwater drainage structures will be located throughout the site to capture and convey proposed stormwater runoff to both dry detention basins. The Water Quality volume for all proposed basins will be released over 40 hours. Water quality outlet structures have been provided for each basin and have been designed to meet the allowable release rates provided in Table 3-2 for the 2, 10, and 100 year storm events. The water quality storm event will be controlled by a 15" riser pipe with 1" diameter orifices evenly spaced across the pipe for the extended dry detention basin, and V-notch weirs will be utilized for all proposed extended wet detention basins.

Emergency spillways will be provided for each basin per Section 5600 of the Design and Construction Manual. Each emergency spillway will be set 0.5 feet above the 100-

year water surface elevation and designed to carry the 100-year storm event assuming a 100% clogged condition. An additional 1 foot of freeboard will be provided from the water surface elevation in the spillway and the top of dam. Final emergency spillway details will be provided with the subsequent Final Stormwater Management Report and construction documents for EDDB-1, EWDB-2, EWDB-3. For EWDB-1 the primary discharge device was removed from the HydroCAD model to simulate a clogged condition. The water surface elevation was set equal to the peak 1% storm water surface elevation, then with no method of primary discharge a second 1% (Back to back) storm was simulated lacking the method of primary discharge and the storage available to the first storm the emergency spillway was utilized. Table 3-4 summarizes the results of this analysis.

Table 3-4 – Emergency Spillway Analysis

	Storm Event	Inflow to Basin	Emergency	Emergency	Clogged
		(CFS)	Spillway	Spillway	Surface
			Elevation	Length	Elevation
			(FT)	(FT)	
EWDB-1	24.30	251.70	999.70	14.00	1001.37

Note: Spillways for the remaining basins will be analyzed with those phases.

Additionally, erosion control procedures will be designed and implemented at the outlets to reduce impact on the site downstream.

4.0 SUMMARY AND RECOMMENDATIONS

The proposed drainage site is a 62.40-acre mixed use parcel of land located in Lee's Summit, MO at the intersection of Blue Parkway and Blackwell Road. The proposed development has been analyzed and designed to meet the APWA Comprehensive Control Strategy, which entails limiting post-development peak discharge rates from the site for the 2-Year, 10-Year, and 100-Year design storm events. One extended dry detention basin and three extended wet detention basins have been designed to detain the mentioned events as well as provided 40-hour detention of runoff from the local 90% mean annual event. All elements of the enclosed drainage system will be designed and constructed in accordance with all City of Lee's Summit, Missouri, requirements.

* * * *


APPENDIX A

-Existing Site Aerial Photograph
-Existing Drainage Map
-Proposed Drainage Map
-EDDB Water Quality Design
-EWDB Water Quality Design
-FEMA FIRMette

-National Wetlands Inventory

7/30/2021 Google Earth








SCALE: 1" = 100'

PROPOSED CONTOUR

PROPOSED WATERSHED



DRAWN BY:

MWM

CHECKED BY:

MAB

DATE PREPARED:

11/18/22

PROJ. NUMBER:

SCALE: 1" = 100'

LEGEND:

_ __ _ 1000 ___ __

EXISTING CONTOUR

PROPOSED CONTOUR

PROPOSED WATERSHED

PROPOSED DRAINAGE MAP

PREPARED BY:

SCHLAGEL & ASSOCIATES, P.A.

BLACKWELL HYDRO MAPS

A.2

Water Quality Volume Calculation - EDDB#1

WQV = P * Weighted RV

WQV - Water Quality Volume (watershed-inches) P - Rainfall Event (1.37 inches in Kansas City)

RV - Volumetric Runoff Coefficient

RV = 0.05 + 0.009(I)

I - Percent Site Imperviousness (%)

I. Determine Weighted RV & Weighted Rational C Coefficient

Total	85	4.97	4.22			4.03	4.05
Commercial	85	4.97	4.22	0.81	0.82	4.03	4.05
Cover Type	Impervious	(Ac.)	Area (Ac.)	Coefficient	RV	C * Area	RV * Area
	%	Area	Total Impervious	Rational Runoff			

Rv = Sum(Rv*A)/Total Area = 4.051 / 4.97 =0.815

C = Sum(C*A)/Total Area = 4.026 / 4.97 =0.810

II. Determine Water Quality Volume

WQV = P * Rv = 1.37 * 0.815 = 1.117 in

III. Determine Total Water Quality Volume

Total Watershed Area (AT) = 4.97 acres WQV = 1.117 in

WQV = (4.97 * 1.116)/12 = 20143.79 c.f. 0.46 ac-ft

IV. Peak rate of runoff for WQv

 $Q = K^*C^*i^*A$

K = 1 for WQvC = 0.3+0.6*I =0.81 C = 0.3 + 0.6 IK = 1.00 I = Percent impervious 1.90 i = Q(cfs) =7.65

i = Rainfall Intensity from Table 9 in BMP manual

Design Procedure Form: Extended Dry Detention Basin (EDDB) Main Worksheet						
Designer: NCA Checked by: MAB Company: SCHLAGEL & ASSOCIATES, P.A. Date: 11/18/2022 Project: 20-205 Location: 11/18/2022	EDDB#1					
I. Basin Water Quality Storage Volume:						
Step 1) Tributary Area to EDDB, A_T (ac.)	A _T (ac.) =	4.97				
Step 2) Calculate WQv using method in Section 6.1	WQv (ac-ft) =	0.46				
Step 3) Add 20 percent to account for silt and sand sediment deposition in the basin	V_{design} (ac-ft) =	0.55				
Ila. Water Quality Outlet Type Step 1) Set Water Quality Outlet Type Type 1 = Single Orifice Type 2 = Perforated riser or plate Type 3 = v-notch weir Step 2) Proceed to step 2b, 2c, or 2d based on water quality outlet type	Outlet Type =	1.00				
Ilb. Water Quality Outlet, Single Orifice						
Step 1) Depth of water quality volume at outlet, Z_{WQ} (ft.)	Z_{WQ} (ft.) =	3.70				
Step 2) Average head of Water Quality volume over invert of orifice, H_{WQ} (ft) $H_{WQ} = 0.5 * Z_{WQ}$	H_{WQ} (ft.) =	1.85				
Step 3) Average water quality outflow rate, Q_{WQ} (cfs) $Q_{WQ} = (WQv * 43,560)/(40 * 3600)$	Q _{WQ} (cfs) =	0.17				
Step 4) Set value of orifice discharge coefficient, C_O $C_O = 0.66 \text{ when thickness of riser/weir plate is = or < orifice diameter}$ $C_O = 0.80 \text{ when thickness of riser/weir plate is > orifice diameter}$	C _O =	0.66				
Step 5) Water quality outlet orifice diameter (4.0-in, min.), D_O (in) D_O (in) = $D_O = 12 * 2 * (Q_{WO}/C_O * \pi * (2 * g * H)^{0.5}))^{0.5}$						

Ilc. Water Quality Outlet, Perforated Riser		
Step 1) Depth at outlet above lowest perforation, Z_{WQ} (ft.)	Z_{WQ} (ft.) =	5.00
Step 2) Recommended maximum outlet area per row, A_O (in ²) $A_O = (WQv)/(0.013 * Z_{WQ}^2 + 0.22 * Z_{WQ} - 0.10)$	A_{O} (in ²) =	0.35
Step 3) Circular perforation diameter per row assuming a single column, D ₁ (in)	D_1 (in) =	0.67
Step 4) Number of Columns, n _c	n _c =	1.00
Step 5) Design circular perforation diameter (should be between 1 and 2 inches), Dper (in)	D _{perf} (in) =	1.00
Step 6) Horizontal perforation column spacing when n_c > 1, center to center, S_c If D_{perf} >/= 1.0 in, S_c =4	S _c (in)=	4.00
Step 7) Number of rows (4" vertical spacing between perforations, center to center), n _r	$n_r =$	46.00
Ilb. Water Quality Outlet, V-notch Weir		
Step 1) Depth of water quality volume above permanent pool, Z_{WQ} (ft.)	Z_{WQ} (ft.) =	2.50
Step 2) Average head of Water Quality volume over invert of V-notch, H_{WQ} (ft) $H_{WQ} = 0.5 * Z_{WQ}$	H_{WQ} (ft.) =	1.25
Step 3) Average water quality outflow rate, Q_{WQ} (cfs) $Q_{WQ} = (WQv * 43,560)/(40 * 3600)$	Q _{WQ} (cfs) =	0.17
Step 4) V-notch weir coefficient, C _V	C _V =	2.50
Step 5) V-notch weir angle, θ (deg) θ = 2 * arctan(Q_{WQ}/C_V * H_{WQ} ^{5/2})) V-notch angle should be at least 20 degrees. Set to 20 degrees if calculated angle is smaller.	θ (deg) =	20.00 Use 20
Step 6) Top width of V-notch weir $W_V = 2 * Z_{WQ} * TAN(\theta/2)$	W _V (ft.) =	0.88
Step 7) To calculate v-notch angle for EDDB with and irregular stage-volume relationship,	use the V-notch Wei	r Worksheet

Project: 22-102 Residences at Blackwell 11/18/2022 11:43

Water Quality Volume Calculation

WQV = P * Weighted RV

WQV - Water Quality Volume (watershed-inches)
P - Rainfall Event (1.37 inches in Kansas City)
RV - Volumetric Runoff Coefficient

RV = 0.05 + 0.009(I)

I - Percent Site Imperviousness (%)

I. Determine Weighted RV & Weighted Rational C Coefficient

			Total	Rational			
	%	Area	Impervious	Runoff			
Cover Type	Impervious	(Ac.)	Area (Ac.)	Coefficient	RV	C * Area	RV * Area
Multifamily (Apartments)	60	24.30	14.58	0.66	0.59	16.038	14.337
			0.00		0.05	0	0
Total	·	24.3	14.58			16.038	14.337

Rv = Sum(Rv*A)/Total Area = 14.33 / 24.3 = 0.590

 $C = Sum(C^*A)/Total Area = 16.03 / 24.3 = 0.660$

II. Determine Water Quality Volume

WQV = P * Rv = 1.37 * 0.59 = **0.808 in**

III. Determine Total Water Quality Volume

Total Watershed Area (AT) = 24.3 acres WQV = 0.808 in

WQV = (24.3 * 0.808)/12 = 1.64 ac-ft

Design Worksheet

Project: 22-102 Residences at BlackwellFINAL STORMWATER MANAGEMENT PLAN 11/18/2022

I. Basin Water Quality Volume		
Tributary Area to EWDB, A _T	$A_T =$	24.30 acres
Water Qualtity Volume, WQ_V - See Attached Calculations	$WQ_V =$	1.637 ac-ft
IIa. Permanent Pool Volume - Method 1		
Average 14 Day Wet Season Rainfal, R ₁₄	R ₁₄ =	2.2 in
Rational Runoff Coefficient, C	C =	0.660
Permanent Pool Volume by Method 1, V_{P1} $V_{P1} = (C^*A_T^*R_{14})/12$	V _{P1} =	2.940 ac-ft
Ilb. Permanent Pool Volume - Method 2		
Ratio of Basin Volume to Runoff Volume, $V_{B/R}$ (From Figure 12; $V_{B/R}$ should be >= 4.0)	$V_{B/R} =$	4
Mean Storm Depth, Sd	Sd =	0.6 in
Impervious Tributary Area, Ai	Ai =	14.58 acres
Permanent Pool Volume by Method 2, V_{P2} $V_{P2} = (V_{B/R} * Sd * Ai)/12$	V _{P2} =	2.916 ac-ft
Ilc. Permanent Pool Design Volume		
Design Permanent Pool Volume, V_P (Larger of V_{P1} and V_{P2} plus 20%)	V _P =	3.528 ac-ft
Average Permanent Pool Depth, Z _P	$Z_P =$	6 ft
Permanent Pool Surface Area, A _P	$A_P =$	0.588 ac
IIId. Water Quality Outlet - V-Notch Weir		
Depth of Water Quality Volume Above Permanent Pool, Z_{WQ}	$Z_{WQ} =$	1.65 ft
Average Head of Water Quality Pool Volume Over Invert of V-Notch, H_{WQ} H _{WQ} = 0.50 * Z_{WQ}	H _{WQ} =	0.8 ft
Average Water Quality Pool Outflow Rate, Q_{WQ} $Q_{WQ} = (WQ_V * 43560)/(40*3600)$	Q _{WQ} =	0.50 cfs
V-Notch Weir Coefficient, Cv	Cv	2.62
V-Notch Weir Angle $\Theta = 2*(180/\Pi)*\arctan(Q_{WQ}/(Cv*H_{QW}^5/2)) - Not < 20 \text{ degrees}$	Θ =	0.6 deg
V-Notch Weir Top Width, WV $Wv = 2*Z_{WQ}*tan(\Theta/2)$	Wv =	0.02 ft

Project: 20-096 CANYON CREEK FOREST 11/18/2022 14:09

Water Quality Volume Calculation

WQV = P * Weighted RV

WQV - Water Quality Volume (watershed-inches)
P - Rainfall Event (1.37 inches in Kansas City)
RV - Volumetric Runoff Coefficient

RV = 0.05 + 0.009(I)

I - Percent Site Imperviousness (%)

I. Determine Weighted RV & Weighted Rational C Coefficient

			Total	Rational			
	%	Area	Impervious	Runoff			
Cover Type	Impervious	(Ac.)	Area (Ac.)	Coefficient	RV	C * Area	RV * Area
Townhomes	65	10.76	6.99	0.66	0.635	7.1016	6.8326
			0.00		0.05	0	0
Total		10.76	6.99			7.102	6.8326

Rv = Sum(Rv*A)/Total Area = 6.83 / 10.76 = 0.635

C = Sum(C*A)/Total Area = 7.1 / 10.76 = 0.660

II. Determine Water Quality Volume

WQV = P * Rv = 1.37 * 0.635 = **0.870 in**

III. Determine Total Water Quality Volume

Total Watershed Area (AT) = 10.76 acres WQV = 0.870 in

WQV = (10.76 * 0.869)/12 = 0.78 ac-ft

Design Worksheet

Traditions at BlackwellPRELIMINARY STORMWATER MANAGEMENT PLAN 11/18/2022

I. Basin Water Quality Volume		
Tributary Area to EWDB, A _T	$A_T =$	10.76 acres
Water Qualtity Volume, WQ _V - See Attached Calculations	$WQ_V =$	0.780 ac-ft
IIa. Permanent Pool Volume - Method 1		
Average 14 Day Wet Season Rainfal, R ₁₄	R ₁₄ =	2.2 in
Rational Runoff Coefficient, C	C =	0.660
Permanent Pool Volume by Method 1, V_{P1} $V_{P1} = (C^*A_T^*R_{14})/12$	V _{P1} =	1.302 ac-ft
Ilb. Permanent Pool Volume - Method 2		
Ratio of Basin Volume to Runoff Volume, $V_{B/R}$ (From Figure 12; $V_{B/R}$ should be >= 4.0)	$V_{B/R} =$	4
Mean Storm Depth, Sd	Sd =	0.6 in
Impervious Tributary Area, Ai	Ai =	6.99 acres
Permanent Pool Volume by Method 2, V_{P2} $V_{P2} = (V_{B/R} * Sd * Ai)/12$	V _{P2} =	1.399 ac-ft
Ilc. Permanent Pool Design Volume		
Design Permanent Pool Volume, V_P (Larger of V_{P1} and V_{P2} plus 20%)	V _P =	1.679 ac-ft
Average Permanent Pool Depth, Z _P	$Z_P =$	6 ft
Permanent Pool Surface Area, A _P	A _P =	0.280 ac
IIId. Water Quality Outlet - V-Notch Weir		
Depth of Water Quality Volume Above Permanent Pool, Z_{WQ}	$Z_{WQ} =$	1.5 ft
Average Head of Water Quality Pool Volume Over Invert of V-Notch, H_{WQ} = 0.50 * Z_{WQ}	H _{WQ} =	0.8 ft
Average Water Quality Pool Outflow Rate, Q_{WQ} $Q_{WQ} = (WQ_V * 43560)/(40*3600)$	Q _{WQ} =	0.24 cfs
V-Notch Weir Coefficient, Cv	Cv	2.62
V-Notch Weir Angle $\Theta = 2*(180/\Pi)*\arctan(Q_{WQ}/(Cv*H_{QW}^5/2)) - Not < 20 \text{ degrees}$	Θ =	0.4 deg
V-Notch Weir Top Width, WV $Wv = 2*Z_{WQ}*tan(\Theta/2)$	Wv =	0.01 ft

Project: 22-093 Blackwell Reserve 11/18/2022 14:29

Water Quality Volume Calculation

WQV = P * Weighted RV

WQV - Water Quality Volume (watershed-inches)
P - Rainfall Event (1.37 inches in Kansas City)
RV - Volumetric Runoff Coefficient

RV = 0.05 + 0.009(I)

I - Percent Site Imperviousness (%)

I. Determine Weighted RV & Weighted Rational C Coefficient

Total		23.37	13.88		0.00	15.424	13.66383
			0.00		0.05	0	0
Townhomes	65	12.48	8.11	0.66	0.635	8.2368	7.9248
Single-Family Lots	53	10.89	5.77		0.527	7.1874	5.73903
Cover Type	Impervious	\ ' ' /	` ,	Coefficient		C * Area	RV * Area
	%	Area	Impervious				

Rv = Sum(Rv*A)/Total Area = 13.66 / 23.37 = 0.585

C = Sum(C*A)/Total Area = 15.42 / 23.37 = 0.660

II. Determine Water Quality Volume

WQV = P * Rv = 1.37 * 0.584673 **0.801 in**

III. Determine Total Water Quality Volume

Total Watershed Area (AT) = 23.37 acres WQV = 0.801 in

WQV = (23.37 * 0.801)/12 = **1.56 ac-ft**

Design Worksheet

Blackwell Reserve

PRELIMINARY STORMWATER MANAGEMENT PLAN 11/18/2022

I. Basin Water Quality Volume		
Tributary Area to EWDB, A _T	$A_T =$	23.37 acres
Water Qualtity Volume, WQ _V - See Attached Calculations	$WQ_V =$	1.560 ac-ft
IIa. Permanent Pool Volume - Method 1		
Average 14 Day Wet Season Rainfal, R ₁₄	R ₁₄ =	2.2 in
Rational Runoff Coefficient, C	C =	0.660
Permanent Pool Volume by Method 1, V_{P1} $V_{P1} = (C^*A_T^*R_{14})/12$	V _{P1} =	2.828 ac-ft
Ilb. Permanent Pool Volume - Method 2		
Ratio of Basin Volume to Runoff Volume, $V_{B/R}$ (From Figure 12; $V_{B/R}$ should be >= 4.0)	$V_{B/R} =$	4
Mean Storm Depth, Sd	Sd =	0.6 in
Impervious Tributary Area, Ai	Ai =	13.88 acres
Permanent Pool Volume by Method 2, V_{P2} $V_{P2} = (V_{B/R} * Sd * Ai)/12$	V _{P2} =	2.777 ac-ft
Ilc. Permanent Pool Design Volume		
Design Permanent Pool Volume, V_P (Larger of V_{P1} and V_{P2} plus 20%)	V _P =	3.393 ac-ft
Average Permanent Pool Depth, Z _P	$Z_P =$	6 ft
Permanent Pool Surface Area, A _P	A _P =	0.566 ac
IIId. Water Quality Outlet - V-Notch Weir		
Depth of Water Quality Volume Above Permanent Pool, Z_{WQ}	$Z_{WQ} =$	2.0 ft
Average Head of Water Quality Pool Volume Over Invert of V-Notch, H_{WQ} H _{WQ} = 0.50 * Z_{WQ}	H _{WQ} =	1.0 ft
Average Water Quality Pool Outflow Rate, Q_{WQ} $Q_{WQ} = (WQ_V * 43560)/(40*3600)$	Q _{WQ} =	0.47 cfs
V-Notch Weir Coefficient, Cv	Cv	2.62
V-Notch Weir Angle $\Theta = 2*(180/\Pi)*arctan(Q_{WQ}/(Cv*H_{QW}^5/2)) - Not < 20 \text{ degrees}$	Θ =	0.4 deg
V-Notch Weir Top Width, WV Wv = 2*Z _{WQ} *tan(Θ/2)	Wv =	0.01 ft

Basin Volume - EWDB #1

Project #: Residences at Blackwell 22-102

Time: 11/18/2022 14:54

Work By: NCA

Volume computed using Conic Method For Reservoir Volumes

Volume = (1/3) * (EL2-EL1)* $(Area1 + Area2 + (Area1*Area2)^{0.5})$

Elevation (ft)	Area (ft²)	Area (AC)	Δ Volume (ft ³)	Total Volume (ft ³)	Total Volume (ac-ft)
984	23839	0.547	0	0	0.000
985	27090	0.622	25445	25445	0.584
986	30397	0.698	28725	54169	1.244
987	33763	0.775	32062	86231	1.980
988	37182	0.854	35455	121687	2.794
989	40663	0.933	38906	160592	3.687
990	44196	1.015	42413	203005	4.660
991	47790	1.097	45977	248982	5.716
992	51437	1.181	49597	298579	6.854
993	57646	1.323	54507	353086	8.106
994	64008	1.469	60793	413879	9.501
995	67904	1.559	65940	479819	11.015
996	71853	1.650	69862	549681	12.619
997	75863	1.742	73842	623523	14.314
998	79925	1.835	77877	701400	16.102
999	84048	1.929	81970	783370	17.984
1000	88224	2.025	86119	869489	19.961

National Flood Hazard Layer FIRMette




Basemap: USGS National Map: Orthoimagery: Data refreshed October, 2020



Legend

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR FIRM PANEL LAYOUT



NO SCREEN Area of Minimal Flood Hazard Zone X Effective LOMRs OTHER AREAS Area of Undetermined Flood Hazard Zone D

- - - Channel, Culvert, or Storm Sewer **GENERAL** STRUCTURES | LILLI Levee, Dike, or Floodwall

20.2 Cross Sections with 1% Annual Chance 17.5 Water Surface Elevation **Coastal Transect** ₩₩ 513 WW Base Flood Elevation Line (BFE) Limit of Study Jurisdiction Boundary **Coastal Transect Baseline** OTHER **Profile Baseline FEATURES** Hydrographic Feature

Digital Data Available No Digital Data Available MAP PANELS Unmapped

The pin displayed on the map is an approximate point selected by the user and does not represent

an authoritative property location.

This map complies with FEMA's standards for the use of digital flood maps if it is not void as described below. The basemap shown complies with FEMA's basemap

accuracy standards


The flood hazard information is derived directly from the authoritative NFHL web services provided by FEMA. This map was exported on 7/30/2021 at 10:56 AM and does not reflect changes or amendments subsequent to this date and time. The NFHL and effective information may change or become superseded by new data over time.

This map image is void if the one or more of the following map elements do not appear: basemap imagery, flood zone labels, legend, scale bar, map creation date, community identifiers, FIRM panel number, and FIRM effective date. Map images for unmapped and unmodernized areas cannot be used for regulatory purposes.

U.S. Fish and Wildlife Service

National Wetlands Inventory

Wetland Inventory Map



July 30, 2021

Wetlands

Estuarine and Marine Deepwater

Estuarine and Marine Wetland

Freshwater Emergent Wetland

Freshwater Forested/Shrub Wetland

Freshwater Pond

Lake

Riverine

Other

This map is for general reference only. The US Fish and Wildlife Service is not responsible for the accuracy or currentness of the base data shown on this map. All wetlands related data should be used in accordance with the layer metadata found on the Wetlands Mapper web site.

APPENDIX B


-NRCS Soil Resource Report
-HydroCAD Model Output Report
- Wetland Delineation and Jurisdictional Assessment



NRCS

Natural Resources Conservation Service A product of the National Cooperative Soil Survey, a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local participants

Custom Soil Resource Report for Jackson County, Missouri



Preface

Soil surveys contain information that affects land use planning in survey areas. They highlight soil limitations that affect various land uses and provide information about the properties of the soils in the survey areas. Soil surveys are designed for many different users, including farmers, ranchers, foresters, agronomists, urban planners, community officials, engineers, developers, builders, and home buyers. Also, conservationists, teachers, students, and specialists in recreation, waste disposal, and pollution control can use the surveys to help them understand, protect, or enhance the environment.

Various land use regulations of Federal, State, and local governments may impose special restrictions on land use or land treatment. Soil surveys identify soil properties that are used in making various land use or land treatment decisions. The information is intended to help the land users identify and reduce the effects of soil limitations on various land uses. The landowner or user is responsible for identifying and complying with existing laws and regulations.

Although soil survey information can be used for general farm, local, and wider area planning, onsite investigation is needed to supplement this information in some cases. Examples include soil quality assessments (http://www.nrcs.usda.gov/wps/portal/nrcs/main/soils/health/) and certain conservation and engineering applications. For more detailed information, contact your local USDA Service Center (https://offices.sc.egov.usda.gov/locator/app?agency=nrcs) or your NRCS State Soil Scientist (http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2 053951).

Great differences in soil properties can occur within short distances. Some soils are seasonally wet or subject to flooding. Some are too unstable to be used as a foundation for buildings or roads. Clayey or wet soils are poorly suited to use as septic tank absorption fields. A high water table makes a soil poorly suited to basements or underground installations.

The National Cooperative Soil Survey is a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local agencies. The Natural Resources Conservation Service (NRCS) has leadership for the Federal part of the National Cooperative Soil Survey.

Information about soils is updated periodically. Updated information is available through the NRCS Web Soil Survey, the site for official soil survey information.

The U.S. Department of Agriculture (USDA) prohibits discrimination in all its programs and activities on the basis of race, color, national origin, age, disability, and where applicable, sex, marital status, familial status, parental status, religion, sexual orientation, genetic information, political beliefs, reprisal, or because all or a part of an individual's income is derived from any public assistance program. (Not all prohibited bases apply to all programs.) Persons with disabilities who require

alternative means for communication of program information (Braille, large print, audiotape, etc.) should contact USDA's TARGET Center at (202) 720-2600 (voice and TDD). To file a complaint of discrimination, write to USDA, Director, Office of Civil Rights, 1400 Independence Avenue, S.W., Washington, D.C. 20250-9410 or call (800) 795-3272 (voice) or (202) 720-6382 (TDD). USDA is an equal opportunity provider and employer.

Contents

Preface	2
How Soil Surveys Are Made	
Soil Map	
Soil Map	
Legend	
Map Unit Legend	
Map Unit Descriptions	
Jackson County, Missouri	
10000—Arisburg silt loam, 1 to 5 percent slopes	13
10082—Arisburg-Urban land complex, 1 to 5 percent slopes	14
10117—Sampsel silty clay loam, 5 to 9 percent slopes	16
10128—Sharpsburg-Urban land complex, 2 to 5 percent slopes	17
10180—Udarents-Urban land-Sampsel complex, 2 to 5 percent slopes	. 18
10181—Udarents-Urban land-Sampsel complex, 5 to 9 percent slopes	. 20
10183—Udarents-Urban land-Polo complex, 5 to 9 percent slopes	22
Soil Information for All Uses	
Soil Properties and Qualities	25
Soil Qualities and Features	25
Hydrologic Soil Group	. 25
References	30

How Soil Surveys Are Made

Soil surveys are made to provide information about the soils and miscellaneous areas in a specific area. They include a description of the soils and miscellaneous areas and their location on the landscape and tables that show soil properties and limitations affecting various uses. Soil scientists observed the steepness, length, and shape of the slopes; the general pattern of drainage; the kinds of crops and native plants; and the kinds of bedrock. They observed and described many soil profiles. A soil profile is the sequence of natural layers, or horizons, in a soil. The profile extends from the surface down into the unconsolidated material in which the soil formed or from the surface down to bedrock. The unconsolidated material is devoid of roots and other living organisms and has not been changed by other biological activity.

Currently, soils are mapped according to the boundaries of major land resource areas (MLRAs). MLRAs are geographically associated land resource units that share common characteristics related to physiography, geology, climate, water resources, soils, biological resources, and land uses (USDA, 2006). Soil survey areas typically consist of parts of one or more MLRA.

The soils and miscellaneous areas in a survey area occur in an orderly pattern that is related to the geology, landforms, relief, climate, and natural vegetation of the area. Each kind of soil and miscellaneous area is associated with a particular kind of landform or with a segment of the landform. By observing the soils and miscellaneous areas in the survey area and relating their position to specific segments of the landform, a soil scientist develops a concept, or model, of how they were formed. Thus, during mapping, this model enables the soil scientist to predict with a considerable degree of accuracy the kind of soil or miscellaneous area at a specific location on the landscape.

Commonly, individual soils on the landscape merge into one another as their characteristics gradually change. To construct an accurate soil map, however, soil scientists must determine the boundaries between the soils. They can observe only a limited number of soil profiles. Nevertheless, these observations, supplemented by an understanding of the soil-vegetation-landscape relationship, are sufficient to verify predictions of the kinds of soil in an area and to determine the boundaries.

Soil scientists recorded the characteristics of the soil profiles that they studied. They noted soil color, texture, size and shape of soil aggregates, kind and amount of rock fragments, distribution of plant roots, reaction, and other features that enable them to identify soils. After describing the soils in the survey area and determining their properties, the soil scientists assigned the soils to taxonomic classes (units). Taxonomic classes are concepts. Each taxonomic class has a set of soil characteristics with precisely defined limits. The classes are used as a basis for comparison to classify soils systematically. Soil taxonomy, the system of taxonomic classification used in the United States, is based mainly on the kind and character of soil properties and the arrangement of horizons within the profile. After the soil

scientists classified and named the soils in the survey area, they compared the individual soils with similar soils in the same taxonomic class in other areas so that they could confirm data and assemble additional data based on experience and research.

The objective of soil mapping is not to delineate pure map unit components; the objective is to separate the landscape into landforms or landform segments that have similar use and management requirements. Each map unit is defined by a unique combination of soil components and/or miscellaneous areas in predictable proportions. Some components may be highly contrasting to the other components of the map unit. The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The delineation of such landforms and landform segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, onsite investigation is needed to define and locate the soils and miscellaneous areas.

Soil scientists make many field observations in the process of producing a soil map. The frequency of observation is dependent upon several factors, including scale of mapping, intensity of mapping, design of map units, complexity of the landscape, and experience of the soil scientist. Observations are made to test and refine the soil-landscape model and predictions and to verify the classification of the soils at specific locations. Once the soil-landscape model is refined, a significantly smaller number of measurements of individual soil properties are made and recorded. These measurements may include field measurements, such as those for color, depth to bedrock, and texture, and laboratory measurements, such as those for content of sand, silt, clay, salt, and other components. Properties of each soil typically vary from one point to another across the landscape.

Observations for map unit components are aggregated to develop ranges of characteristics for the components. The aggregated values are presented. Direct measurements do not exist for every property presented for every map unit component. Values for some properties are estimated from combinations of other properties.

While a soil survey is in progress, samples of some of the soils in the area generally are collected for laboratory analyses and for engineering tests. Soil scientists interpret the data from these analyses and tests as well as the field-observed characteristics and the soil properties to determine the expected behavior of the soils under different uses. Interpretations for all of the soils are field tested through observation of the soils in different uses and under different levels of management. Some interpretations are modified to fit local conditions, and some new interpretations are developed to meet local needs. Data are assembled from other sources, such as research information, production records, and field experience of specialists. For example, data on crop yields under defined levels of management are assembled from farm records and from field or plot experiments on the same kinds of soil.

Predictions about soil behavior are based not only on soil properties but also on such variables as climate and biological activity. Soil conditions are predictable over long periods of time, but they are not predictable from year to year. For example, soil scientists can predict with a fairly high degree of accuracy that a given soil will have a high water table within certain depths in most years, but they cannot predict that a high water table will always be at a specific level in the soil on a specific date.

After soil scientists located and identified the significant natural bodies of soil in the survey area, they drew the boundaries of these bodies on aerial photographs and

identified each as a specific map unit. Aerial photographs show trees, buildings, fields, roads, and rivers, all of which help in locating boundaries accurately.

Soil Map

The soil map section includes the soil map for the defined area of interest, a list of soil map units on the map and extent of each map unit, and cartographic symbols displayed on the map. Also presented are various metadata about data used to produce the map, and a description of each soil map unit.



MAP LEGEND

Area of Interest (AOI)

Area of Interest (AOI)

Soils

Soil Map Unit Polygons



Soil Map Unit Lines



Soil Map Unit Points

Special Point Features

(0)

Blowout



Borrow Pit



Clay Spot



Closed Depression



Gravel Pit



Gravelly Spot



Landfill



Lava Flow

Marsh or swamp



Mine or Quarry



Miscellaneous Water



Perennial Water
Rock Outcrop



Saline Spot



Sandy Spot

• • •

Severely Eroded Spot



Sinkhole



Sodic Spot

Slide or Slip

8

Spoil Area



Stony Spot



Very Stony Spot



Wet Spot Other



Special Line Features

Water Features

_

Streams and Canals

Transportation

Fransp

Rails



Interstate Highways



US Routes



Major Roads



Local Roads

Background

Marie Contract

Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24.000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service Web Soil Survey URL:

Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Jackson County, Missouri Survey Area Data: Version 22, May 29, 2020

Soil map units are labeled (as space allows) for map scales 1:50.000 or larger.

Date(s) aerial images were photographed: Sep 6, 2019—Nov 16, 2019

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
10000	Arisburg silt loam, 1 to 5 percent slopes	50.5	46.1%
10082	Arisburg-Urban land complex, 1 to 5 percent slopes	9.1	8.3%
10117	Sampsel silty clay loam, 5 to 9 percent slopes	27.1	24.8%
10128	Sharpsburg-Urban land complex, 2 to 5 percent slopes	5.9	5.4%
10180	Udarents-Urban land-Sampsel complex, 2 to 5 percent slopes	5.8	5.3%
10181	Udarents-Urban land-Sampsel complex, 5 to 9 percent slopes	9.2	8.4%
10183 Udarents-Urban land-Polo complex, 5 to 9 percent slopes		1.9	1.8%
Totals for Area of Interest		109.5	100.0%

Map Unit Descriptions

The map units delineated on the detailed soil maps in a soil survey represent the soils or miscellaneous areas in the survey area. The map unit descriptions, along with the maps, can be used to determine the composition and properties of a unit.

A map unit delineation on a soil map represents an area dominated by one or more major kinds of soil or miscellaneous areas. A map unit is identified and named according to the taxonomic classification of the dominant soils. Within a taxonomic class there are precisely defined limits for the properties of the soils. On the landscape, however, the soils are natural phenomena, and they have the characteristic variability of all natural phenomena. Thus, the range of some observed properties may extend beyond the limits defined for a taxonomic class. Areas of soils of a single taxonomic class rarely, if ever, can be mapped without including areas of other taxonomic classes. Consequently, every map unit is made up of the soils or miscellaneous areas for which it is named and some minor components that belong to taxonomic classes other than those of the major soils.

Most minor soils have properties similar to those of the dominant soil or soils in the map unit, and thus they do not affect use and management. These are called noncontrasting, or similar, components. They may or may not be mentioned in a particular map unit description. Other minor components, however, have properties and behavioral characteristics divergent enough to affect use or to require different management. These are called contrasting, or dissimilar, components. They generally are in small areas and could not be mapped separately because of the

scale used. Some small areas of strongly contrasting soils or miscellaneous areas are identified by a special symbol on the maps. If included in the database for a given area, the contrasting minor components are identified in the map unit descriptions along with some characteristics of each. A few areas of minor components may not have been observed, and consequently they are not mentioned in the descriptions, especially where the pattern was so complex that it was impractical to make enough observations to identify all the soils and miscellaneous areas on the landscape.

The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The objective of mapping is not to delineate pure taxonomic classes but rather to separate the landscape into landforms or landform segments that have similar use and management requirements. The delineation of such segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, however, onsite investigation is needed to define and locate the soils and miscellaneous areas.

An identifying symbol precedes the map unit name in the map unit descriptions. Each description includes general facts about the unit and gives important soil properties and qualities.

Soils that have profiles that are almost alike make up a *soil series*. Except for differences in texture of the surface layer, all the soils of a series have major horizons that are similar in composition, thickness, and arrangement.

Soils of one series can differ in texture of the surface layer, slope, stoniness, salinity, degree of erosion, and other characteristics that affect their use. On the basis of such differences, a soil series is divided into *soil phases*. Most of the areas shown on the detailed soil maps are phases of soil series. The name of a soil phase commonly indicates a feature that affects use or management. For example, Alpha silt loam, 0 to 2 percent slopes, is a phase of the Alpha series.

Some map units are made up of two or more major soils or miscellaneous areas. These map units are complexes, associations, or undifferentiated groups.

A *complex* consists of two or more soils or miscellaneous areas in such an intricate pattern or in such small areas that they cannot be shown separately on the maps. The pattern and proportion of the soils or miscellaneous areas are somewhat similar in all areas. Alpha-Beta complex, 0 to 6 percent slopes, is an example.

An *association* is made up of two or more geographically associated soils or miscellaneous areas that are shown as one unit on the maps. Because of present or anticipated uses of the map units in the survey area, it was not considered practical or necessary to map the soils or miscellaneous areas separately. The pattern and relative proportion of the soils or miscellaneous areas are somewhat similar. Alpha-Beta association, 0 to 2 percent slopes, is an example.

An *undifferentiated group* is made up of two or more soils or miscellaneous areas that could be mapped individually but are mapped as one unit because similar interpretations can be made for use and management. The pattern and proportion of the soils or miscellaneous areas in a mapped area are not uniform. An area can be made up of only one of the major soils or miscellaneous areas, or it can be made up of all of them. Alpha and Beta soils, 0 to 2 percent slopes, is an example.

Some surveys include *miscellaneous areas*. Such areas have little or no soil material and support little or no vegetation. Rock outcrop is an example.

Jackson County, Missouri

10000—Arisburg silt loam, 1 to 5 percent slopes

Map Unit Setting

National map unit symbol: 2w22b Elevation: 610 to 1,130 feet

Mean annual precipitation: 39 to 43 inches Mean annual air temperature: 50 to 55 degrees F

Frost-free period: 177 to 220 days

Farmland classification: All areas are prime farmland

Map Unit Composition

Arisburg and similar soils: 87 percent Minor components: 13 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Arisburg

Setting

Landform: Interfluves

Landform position (two-dimensional): Summit Landform position (three-dimensional): Interfluve

Down-slope shape: Convex Across-slope shape: Convex Parent material: Loess

Typical profile

Ap - 0 to 6 inches: silt loam A - 6 to 13 inches: silt loam

Bt - 13 to 19 inches: silty clay loam Btg - 19 to 56 inches: silty clay loam BCg - 56 to 79 inches: silty clay loam

Properties and qualities

Slope: 1 to 5 percent

Depth to restrictive feature: More than 80 inches Drainage class: Somewhat poorly drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately high (0.20

to 0.60 in/hr)

Depth to water table: About 18 to 30 inches

Frequency of flooding: None Frequency of ponding: None

Maximum salinity: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)

Available water capacity: High (about 11.5 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 2e

Hydrologic Soil Group: C

Ecological site: R107BY007MO - Loess Upland Prairie Amorpha canescens/ Andropogon gerardii-Zizia aurea Leadplant/Big Bluestem-Golden Zizia

Hydric soil rating: No

Minor Components

Greenton

Percent of map unit: 5 percent

Landform: Hillslopes

Landform position (two-dimensional): Shoulder Landform position (three-dimensional): Side slope

Down-slope shape: Convex Across-slope shape: Convex

Ecological site: R109XY002MO - Loess Upland Prairie

Hydric soil rating: No

Sharpsburg

Percent of map unit: 5 percent

Landform: Ridges

Landform position (two-dimensional): Summit Landform position (three-dimensional): Interfluve

Down-slope shape: Linear Across-slope shape: Linear

Ecological site: R109XY002MO - Loess Upland Prairie

Hydric soil rating: No

Haig

Percent of map unit: 3 percent

Landform: Flats

Landform position (two-dimensional): Summit Landform position (three-dimensional): Talf

Down-slope shape: Linear Across-slope shape: Convex

Ecological site: R109XY001MO - Claypan Summit Prairie

Hydric soil rating: Yes

10082—Arisburg-Urban land complex, 1 to 5 percent slopes

Map Unit Setting

National map unit symbol: 2w7ld Elevation: 750 to 1,130 feet

Mean annual precipitation: 39 to 45 inches
Mean annual air temperature: 50 to 55 degrees F

Frost-free period: 177 to 220 days

Farmland classification: All areas are prime farmland

Map Unit Composition

Arisburg and similar soils: 61 percent

Urban land: 30 percent Minor components: 9 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Arisburg

Setting

Landform: Interfluves

Landform position (two-dimensional): Summit Landform position (three-dimensional): Interfluve

Down-slope shape: Convex Across-slope shape: Convex Parent material: Loess

Typical profile

Ap - 0 to 6 inches: silt loam A - 6 to 13 inches: silt loam

Bt - 13 to 19 inches: silty clay loam
Btg - 19 to 56 inches: silty clay loam
BCg - 56 to 79 inches: silty clay loam

Properties and qualities

Slope: 1 to 5 percent

Depth to restrictive feature: More than 80 inches Drainage class: Somewhat poorly drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately high (0.20

to 0.60 in/hr)

Depth to water table: About 18 to 30 inches

Frequency of flooding: None Frequency of ponding: None

Maximum salinity: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)

Available water capacity: High (about 11.5 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 2e

Hydrologic Soil Group: C

Ecological site: R107BY007MO - Loess Upland Prairie Amorpha canescens/ Andropogon gerardii-Zizia aurea Leadplant/Big Bluestem-Golden Zizia

Hydric soil rating: No

Description of Urban Land

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 8

Hydric soil rating: No

Minor Components

Sampsel

Percent of map unit: 3 percent

Landform: Hills

Landform position (two-dimensional): Backslope Landform position (three-dimensional): Side slope

Down-slope shape: Convex Across-slope shape: Concave

Ecological site: R109XY010MO - Interbedded Sedimentary Upland Savanna

Hydric soil rating: Yes

Greenton

Percent of map unit: 3 percent

Landform: Hillslopes

Landform position (two-dimensional): Shoulder Landform position (three-dimensional): Side slope

Down-slope shape: Convex Across-slope shape: Convex

Ecological site: R109XY002MO - Loess Upland Prairie

Hydric soil rating: No

Sharpsburg

Percent of map unit: 3 percent

Landform: Ridges

Landform position (two-dimensional): Summit Landform position (three-dimensional): Interfluve

Down-slope shape: Linear Across-slope shape: Linear

Ecological site: R109XY002MO - Loess Upland Prairie

Hydric soil rating: No

10117—Sampsel silty clay loam, 5 to 9 percent slopes

Map Unit Setting

National map unit symbol: 2qkzz

Elevation: 600 to 900 feet

Mean annual precipitation: 33 to 41 inches
Mean annual air temperature: 50 to 55 degrees F

Frost-free period: 177 to 220 days

Farmland classification: Prime farmland if drained

Map Unit Composition

Sampsel and similar soils: 85 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Sampsel

Setting

Landform: Hillslopes

Landform position (two-dimensional): Shoulder Landform position (three-dimensional): Side slope

Down-slope shape: Concave

Across-slope shape: Convex, concave

Parent material: Residuum weathered from shale

Typical profile

Ap - 0 to 13 inches: silty clay loam Bt - 13 to 80 inches: silty clay

Properties and qualities

Slope: 5 to 9 percent

Depth to restrictive feature: More than 80 inches Drainage class: Somewhat poorly drained

Runoff class: Very high

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to

moderately high (0.06 to 0.20 in/hr)

Depth to water table: About 0 to 18 inches

Frequency of flooding: None Frequency of ponding: None

Maximum salinity: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)

Available water capacity: Moderate (about 8.6 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 3e

Hydrologic Soil Group: C/D

Ecological site: R109XY010MO - Interbedded Sedimentary Upland Savanna

Other vegetative classification: Grass/Prairie (Herbaceous Vegetation)

Hydric soil rating: No

10128—Sharpsburg-Urban land complex, 2 to 5 percent slopes

Map Unit Setting

National map unit symbol: 2ql09 Elevation: 1,000 to 1,300 feet

Mean annual precipitation: 33 to 41 inches
Mean annual air temperature: 50 to 55 degrees F

Frost-free period: 177 to 220 days

Farmland classification: All areas are prime farmland

Map Unit Composition

Sharpsburg and similar soils: 60 percent

Urban land: 35 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Sharpsburg

Setting

Landform: Interfluves

Landform position (two-dimensional): Summit Landform position (three-dimensional): Interfluve

Down-slope shape: Convex Across-slope shape: Convex Parent material: Loess

Typical profile

A - 0 to 17 inches: silt loam

Bt - 17 to 55 inches: silty clay loam

C - 55 to 60 inches: silty clay loam

Properties and qualities

Slope: 2 to 5 percent

Depth to restrictive feature: More than 80 inches

Drainage class: Moderately well drained

Runoff class: High

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to

moderately high (0.06 to 0.20 in/hr)

Depth to water table: About 24 to 35 inches

Frequency of flooding: None Frequency of ponding: None

Maximum salinity: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)

Available water capacity: Very high (about 12.0 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 2e

Hydrologic Soil Group: D

Ecological site: R109XY002MO - Loess Upland Prairie

Other vegetative classification: Grass/Prairie (Herbaceous Vegetation)

Hydric soil rating: No

Description of Urban Land

Setting

Landform: Interfluves

Landform position (two-dimensional): Summit Landform position (three-dimensional): Interfluve

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 8

Hydric soil rating: No

10180—Udarents-Urban land-Sampsel complex, 2 to 5 percent slopes

Map Unit Setting

National map unit symbol: 1n85h

Elevation: 600 to 900 feet

Mean annual precipitation: 33 to 43 inches
Mean annual air temperature: 50 to 57 degrees F

Frost-free period: 175 to 220 days

Farmland classification: All areas are prime farmland

Map Unit Composition

Udarents and similar soils: 41 percent

Urban land: 39 percent

Sampsel and similar soils: 15 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Udarents

Setting

Landform position (two-dimensional): Summit Landform position (three-dimensional): Crest

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Mine spoil or earthy fill

Typical profile

C1 - 0 to 5 inches: silt loam C2 - 5 to 80 inches: silty clay loam

Properties and qualities

Slope: 2 to 5 percent

Depth to restrictive feature: More than 80 inches Drainage class: Somewhat poorly drained

Runoff class: Very high

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to

moderately high (0.14 to 0.57 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Maximum salinity: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)

Available water capacity: Moderate (about 9.0 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 6e

Hydrologic Soil Group: C

Ecological site: R107BY002MO - Deep Loess Upland Prairie Amorpha

canescens/Schizachyrium scoparium-Sporobolus heterolepis Leadplant/Little

Bluestem-Prairie Dropseed

Other vegetative classification: Mixed/Transitional (Mixed Native Vegetation)

Hydric soil rating: No

Description of Urban Land

Setting

Landform: Interfluves

Landform position (two-dimensional): Summit Landform position (three-dimensional): Interfluve

Across-slope shape: Convex

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 8

Hydric soil rating: No

Description of Sampsel

Setting

Landform: Hillslopes

Landform position (two-dimensional): Footslope Landform position (three-dimensional): Base slope

Down-slope shape: Concave Across-slope shape: Convex

Parent material: Residuum weathered from shale

Typical profile

Ap - 0 to 13 inches: silty clay loam Bt - 13 to 80 inches: silty clay

Properties and qualities

Slope: 2 to 5 percent

Depth to restrictive feature: More than 80 inches Drainage class: Somewhat poorly drained

Runoff class: Very high

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to

moderately high (0.06 to 0.20 in/hr)

Depth to water table: About 0 to 18 inches

Frequency of flooding: None Frequency of ponding: None

Maximum salinity: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)

Available water capacity: Moderate (about 8.6 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 2e

Hydrologic Soil Group: C/D

Ecological site: R109XY010MO - Interbedded Sedimentary Upland Savanna *Other vegetative classification:* Grass/Prairie (Herbaceous Vegetation)

Hydric soil rating: No

10181—Udarents-Urban land-Sampsel complex, 5 to 9 percent slopes

Map Unit Setting

National map unit symbol: 1n85g

Elevation: 600 to 900 feet

Mean annual precipitation: 33 to 43 inches Mean annual air temperature: 50 to 57 degrees F

Frost-free period: 175 to 220 days

Farmland classification: Farmland of statewide importance

Map Unit Composition

Udarents and similar soils: 41 percent

Urban land: 39 percent

Sampsel and similar soils: 15 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Udarents

Setting

Landform position (two-dimensional): Shoulder Landform position (three-dimensional): Side slope

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Mine spoil or earthy fill

Typical profile

C1 - 0 to 5 inches: silt loam
C2 - 5 to 80 inches: silty clay loam

Properties and qualities

Slope: 5 to 9 percent

Depth to restrictive feature: More than 80 inches Drainage class: Somewhat poorly drained

Runoff class: Very high

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to

moderately high (0.14 to 0.57 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Maximum salinity: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)

Available water capacity: Moderate (about 9.0 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 6e

Hydrologic Soil Group: C

Ecological site: R107BY002MO - Deep Loess Upland Prairie Amorpha

canescens/Schizachyrium scoparium-Sporobolus heterolepis Leadplant/Little

Bluestem-Prairie Dropseed

Other vegetative classification: Mixed/Transitional (Mixed Native Vegetation)

Hydric soil rating: No

Description of Urban Land

Setting

Landform: Hillslopes

Landform position (two-dimensional): Shoulder Landform position (three-dimensional): Side slope

Across-slope shape: Convex

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 8

Hydric soil rating: No

Description of Sampsel

Setting

Landform: Hillslopes

Landform position (two-dimensional): Footslope Landform position (three-dimensional): Base slope

Down-slope shape: Concave Across-slope shape: Convex

Parent material: Residuum weathered from shale

Typical profile

Ap - 0 to 13 inches: silty clay loam Bt - 13 to 80 inches: silty clay

Properties and qualities

Slope: 5 to 9 percent

Depth to restrictive feature: More than 80 inches Drainage class: Somewhat poorly drained

Runoff class: Very high

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to

moderately high (0.06 to 0.20 in/hr)

Depth to water table: About 0 to 18 inches

Frequency of flooding: None Frequency of ponding: None

Maximum salinity: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)

Available water capacity: Moderate (about 8.6 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 3e

Hydrologic Soil Group: C/D

Ecological site: R109XY010MO - Interbedded Sedimentary Upland Savanna *Other vegetative classification:* Grass/Prairie (Herbaceous Vegetation)

Hydric soil rating: No

10183—Udarents-Urban land-Polo complex, 5 to 9 percent slopes

Map Unit Setting

National map unit symbol: 1n85d Elevation: 600 to 1,000 feet

Mean annual precipitation: 33 to 41 inches Mean annual air temperature: 50 to 57 degrees F

Frost-free period: 175 to 220 days

Farmland classification: Farmland of statewide importance

Map Unit Composition

Udarents and similar soils: 41 percent

Urban land: 39 percent

Polo and similar soils: 15 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Udarents

Settina

Landform position (two-dimensional): Shoulder Landform position (three-dimensional): Side slope

Down-slope shape: Convex Across-slope shape: Convex

Parent material: Mine spoil or earthy fill

Typical profile

C1 - 0 to 5 inches: silt loam C2 - 5 to 80 inches: silty clay loam

Properties and qualities

Slope: 5 to 9 percent

Depth to restrictive feature: More than 80 inches Drainage class: Somewhat poorly drained

Runoff class: Very high

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to

moderately high (0.14 to 0.57 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Maximum salinity: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)

Available water capacity: Moderate (about 9.0 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 6e

Hydrologic Soil Group: C

Ecological site: R107BY002MO - Deep Loess Upland Prairie Amorpha

canescens/Schizachyrium scoparium-Sporobolus heterolepis Leadplant/Little

Bluestem-Prairie Dropseed

Other vegetative classification: Mixed/Transitional (Mixed Native Vegetation)

Hydric soil rating: No

Description of Urban Land

Setting

Landform: Hillslopes

Landform position (two-dimensional): Shoulder Landform position (three-dimensional): Side slope

Across-slope shape: Convex

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 8

Hydric soil rating: No

Description of Polo

Setting

Landform: Hillslopes

Landform position (two-dimensional): Shoulder Landform position (three-dimensional): Side slope

Down-slope shape: Concave

Across-slope shape: Concave, convex Parent material: Loess over residuum

Typical profile

A - 0 to 12 inches: silt loam

BA - 12 to 29 inches: silty clay loam Bt1 - 29 to 35 inches: silty clay loam 2Bt2 - 35 to 80 inches: silty clay

Properties and qualities

Slope: 5 to 9 percent

Depth to restrictive feature: More than 80 inches

Drainage class: Well drained

Runoff class: High

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to

moderately high (0.06 to 0.20 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None Frequency of ponding: None

Maximum salinity: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)

Available water capacity: High (about 9.9 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 3e

Hydrologic Soil Group: C

Ecological site: R107BY007MO - Loess Upland Prairie Amorpha canescens/ Andropogon gerardii-Zizia aurea Leadplant/Big Bluestem-Golden Zizia Other vegetative classification: Grass/Prairie (Herbaceous Vegetation)

Hydric soil rating: No

Soil Information for All Uses

Soil Properties and Qualities

The Soil Properties and Qualities section includes various soil properties and qualities displayed as thematic maps with a summary table for the soil map units in the selected area of interest. A single value or rating for each map unit is generated by aggregating the interpretive ratings of individual map unit components. This aggregation process is defined for each property or quality.

Soil Qualities and Features

Soil qualities are behavior and performance attributes that are not directly measured, but are inferred from observations of dynamic conditions and from soil properties. Example soil qualities include natural drainage, and frost action. Soil features are attributes that are not directly part of the soil. Example soil features include slope and depth to restrictive layer. These features can greatly impact the use and management of the soil.

Hydrologic Soil Group

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.



MAP LEGEND MAP INFORMATION Area of Interest (AOI) The soil surveys that comprise your AOI were mapped at С 1:24.000. Area of Interest (AOI) C/D Soils D Warning: Soil Map may not be valid at this scale. Soil Rating Polygons Not rated or not available Α Enlargement of maps beyond the scale of mapping can cause **Water Features** A/D misunderstanding of the detail of mapping and accuracy of soil Streams and Canals line placement. The maps do not show the small areas of В contrasting soils that could have been shown at a more detailed Transportation scale. B/D Rails ---Interstate Highways Please rely on the bar scale on each map sheet for map C/D **US Routes** measurements. Major Roads Source of Map: Natural Resources Conservation Service Not rated or not available Local Roads Web Soil Survey URL: -Coordinate System: Web Mercator (EPSG:3857) Soil Rating Lines Background Aerial Photography Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required. This product is generated from the USDA-NRCS certified data as of the version date(s) listed below. Soil Survey Area: Jackson County, Missouri Not rated or not available Survey Area Data: Version 22, May 29, 2020 **Soil Rating Points** Soil map units are labeled (as space allows) for map scales Α 1:50.000 or larger. A/D Date(s) aerial images were photographed: Sep 6, 2019—Nov 16. 2019 B/D The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Table—Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI		
10000	Arisburg silt loam, 1 to 5 percent slopes	С	50.5	46.1%		
10082	Arisburg-Urban land complex, 1 to 5 percent slopes	С	9.1	8.3%		
10117	Sampsel silty clay loam, 5 to 9 percent slopes	C/D	27.1	24.8%		
10128	Sharpsburg-Urban land complex, 2 to 5 percent slopes	D	5.9	5.4%		
10180	Udarents-Urban land- Sampsel complex, 2 to 5 percent slopes	С	5.8	5.3%		
10181	Udarents-Urban land- Sampsel complex, 5 to 9 percent slopes	С	9.2	8.4%		
10183	Udarents-Urban land- Polo complex, 5 to 9 percent slopes	С	1.9	1.8%		
Totals for Area of Intere	est	1	109.5	100.0%		

Rating Options—Hydrologic Soil Group

Aggregation Method: Dominant Condition
Component Percent Cutoff: None Specified

Tie-break Rule: Higher

References

American Association of State Highway and Transportation Officials (AASHTO). 2004. Standard specifications for transportation materials and methods of sampling and testing. 24th edition.

American Society for Testing and Materials (ASTM). 2005. Standard classification of soils for engineering purposes. ASTM Standard D2487-00.

Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of wetlands and deep-water habitats of the United States. U.S. Fish and Wildlife Service FWS/OBS-79/31.

Federal Register. July 13, 1994. Changes in hydric soils of the United States.

Federal Register. September 18, 2002. Hydric soils of the United States.

Hurt, G.W., and L.M. Vasilas, editors. Version 6.0, 2006. Field indicators of hydric soils in the United States.

National Research Council. 1995. Wetlands: Characteristics and boundaries.

Soil Survey Division Staff. 1993. Soil survey manual. Soil Conservation Service. U.S. Department of Agriculture Handbook 18. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_054262

Soil Survey Staff. 1999. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. 2nd edition. Natural Resources Conservation Service, U.S. Department of Agriculture Handbook 436. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2 053577

Soil Survey Staff. 2010. Keys to soil taxonomy. 11th edition. U.S. Department of Agriculture, Natural Resources Conservation Service. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2 053580

Tiner, R.W., Jr. 1985. Wetlands of Delaware. U.S. Fish and Wildlife Service and Delaware Department of Natural Resources and Environmental Control, Wetlands Section.

United States Army Corps of Engineers, Environmental Laboratory. 1987. Corps of Engineers wetlands delineation manual. Waterways Experiment Station Technical Report Y-87-1.

United States Department of Agriculture, Natural Resources Conservation Service. National forestry manual. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2 053374


United States Department of Agriculture, Natural Resources Conservation Service. National range and pasture handbook. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/landuse/rangepasture/?cid=stelprdb1043084


United States Department of Agriculture, Natural Resources Conservation Service. National soil survey handbook, title 430-VI. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2_054242


United States Department of Agriculture, Natural Resources Conservation Service. 2006. Land resource regions and major land resource areas of the United States, the Caribbean, and the Pacific Basin. U.S. Department of Agriculture Handbook 296. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053624


United States Department of Agriculture, Soil Conservation Service. 1961. Land capability classification. U.S. Department of Agriculture Handbook 210. http://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/nrcs142p2_052290.pdf

Existing Conditions

















Routing Diagram for 22-102-HYDRO-EX
Prepared by Schlagel, Printed 11/18/2022
HydroCAD® 10.00-13 s/n 08303 © 2014 HydroCAD Software Solutions LLC

HydroCAD® 10.00-13 s/n 08303 © 2014 HydroCAD Software Solutions LLC

Page 2


Summary for Subcatchment 11S: EX DA-4

Runoff = 38.59 cfs @ 12.12 hrs, Volume= 2.622 af, Depth> 1.63"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 2-Year Rainfall=3.50"

_	Area	(ac) C	N Desc	cription			
8.950 79 Pasture/grassland/range, Fair, HSG C							
_	10.300 84 Pasture/grassland/range, Fair, HSG D						
	19.250 82 Weighted Average						
	19.	250	100.	00% Pervi	ous Area		
	Тс	Length	Slope	Velocity	Capacity	Description	
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)		
	8.3	100	0.0260	0.20		Sheet Flow,	
						Grass: Short n= 0.150 P2= 3.60"	
	11.1	750	0.0260	1.13		Shallow Concentrated Flow,	
_						Short Grass Pasture Kv= 7.0 fps	
	19.4	850	Total				

Subcatchment 11S: EX DA-4




Summary for Subcatchment 12S: EX OFF DA -4

Runoff = 11.43 cfs @ 12.18 hrs, Volume= 0.939 af, Depth> 2.46"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 2-Year Rainfall=3.50"

_	Area	(ac) C	N Des	cription					
4.580 92 Paved roads w/open ditches, 50% imp, HSG C									
	2.290 50.00% Pervious Area								
2.290 50.00% Impervious Area									
				·					
	Тс	Length	Slope	Velocity	Capacity	Description			
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)				
	1.1	100	0.0200	1.46		Sheet Flow,			
						Smooth surfaces n= 0.011 P2= 3.60"			
	24.1	1,430	0.0200	0.99		Shallow Concentrated Flow,			
						Short Grass Pasture Kv= 7.0 fps			
-	25.2	1.530	Total			·			

Subcatchment 12S: EX OFF DA -4



HydroCAD® 10.00-13 s/n 08303 © 2014 HydroCAD Software Solutions LLC

Page 4


Summary for Subcatchment 13S: EX DA- 3

Runoff = 36.97 cfs @ 12.31 hrs, Volume= 3.631 af, Depth> 1.48"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 2-Year Rainfall=3.50"

	Area	(ac) (CN E)esc	cription		
2.920 76 Woods/grass comb., Fair, HSG C						comb., Fair	, HSG C
14.020 79 Pasture/grassland/range, Fair, HSG C							Fair, HSG C
7.890 82 Woods/grass comb., Fair, HSG D							, HSG D
	4.	520	84 F	ast	ure/grassl	and/range,	Fair, HSG D
	29.	350	80 V	Veiç	ghted Aver	age	
	29.	350	1	00.	00% Pervi	ous Area	
	Tc	Length	. Slo	ре	Velocity	Capacity	Description
	(min)	(feet)	(ft	/ft)	(ft/sec)	(cfs)	
	9.1	100	0.02	05	0.18		Sheet Flow,
							Grass: Short n= 0.150 P2= 3.60"
	26.0	1,565	0.02	05	1.00		Shallow Concentrated Flow,
							Short Grass Pasture Kv= 7.0 fps
-	35.1	1,665	Tota				

Subcatchment 13S: EX DA- 3



HydroCAD® 10.00-13 s/n 08303 © 2014 HydroCAD Software Solutions LLC

Page 5


Summary for Subcatchment 14S: EX DA-2

Runoff = 7.26 cfs @ 12.16 hrs, Volume= 0.532 af, Depth> 1.49"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 2-Year Rainfall=3.50"

	Area	(ac) C	N Desc	cription				
3.220 79 Pasture/grassland/range, Fair, HSG C								
1.060 84 Pasture/grassland/range, Fair, HSG D								
	4.280 80 Weighted Average							
	4.	280	100.	00% Pervi	ous Area			
	Тс	Length	Slope	Velocity	Capacity	Description		
	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)			
	9.2	100	0.0200	0.18		Sheet Flow,		
						Grass: Short n= 0.150 P2= 3.60"		
	13.0	770	0.0200	0.99		Shallow Concentrated Flow,		
						Short Grass Pasture Kv= 7.0 fps		
	22.2	870	Total		•			

Subcatchment 14S: EX DA-2



Page 6


Summary for Subcatchment 15S: EX DA-1

Runoff = 14.34 cfs @ 12.19 hrs, Volume= 1.129 af, Depth> 1.42"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 2-Year Rainfall=3.50"

	Area	(ac) C	N Des	cription			
-	0.	590 7	76 Woo	ds/grass o	omb., Fair,	, HSG C	
	8.	930 7	79 Past	ure/grassl	and/range,	Fair, HSG C	
	9.	520 7	79 Weig	ghted Aver	age		
	9.	520	100.	00% Pervi	ous Area		
	Tc	Length	Slope	Velocity	Capacity	Description	
	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)		
	10.3	100	0.0152	0.16		Sheet Flow,	
						Grass: Short n= 0.150 P2= 3.60"	
	14.5	750	0.0152	0.86		Shallow Concentrated Flow,	
						Short Grass Pasture Kv= 7.0 fps	_
	24.8	850	Total				

Subcatchment 15S: EX DA-1



Page 7

Summary for Link 7L: RP-1


Inflow Area = 9.520 ac, 0.00% Impervious, Inflow Depth > 1.42" for 2-Year event

Inflow = 14.34 cfs @ 12.19 hrs, Volume= 1.129 af

Primary = 14.34 cfs @ 12.19 hrs, Volume= 1.129 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 7L: RP-1



Page 8

Summary for Link 8L: RP-2


Inflow Area = 4.280 ac, 0.00% Impervious, Inflow Depth > 1.49" for 2-Year event

Inflow = 7.26 cfs @ 12.16 hrs, Volume= 0.532 af

Primary = 7.26 cfs @ 12.16 hrs, Volume= 0.532 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 8L: RP-2



Page 9

Summary for Link 9L: RP-3


Inflow Area = 29.350 ac, 0.00% Impervious, Inflow Depth > 1.48" for 2-Year event

Inflow = 36.97 cfs @ 12.31 hrs, Volume= 3.631 af

Primary = 36.97 cfs @ 12.31 hrs, Volume= 3.631 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 9L: RP-3



Page 10

Summary for Link 10L: RP-4


Inflow Area = 23.830 ac, 9.61% Impervious, Inflow Depth > 1.79" for 2-Year event

Inflow = 49.48 cfs @ 12.13 hrs, Volume= 3.560 af

Primary = 49.48 cfs @ 12.13 hrs, Volume= 3.560 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 10L: RP-4




Summary for Subcatchment 11S: EX DA-4

Runoff = 72.33 cfs @ 12.12 hrs, Volume= 4.977 af, Depth> 3.10"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 10-Year Rainfall=5.30"

	Area	(ac) C	N Desc	cription					
	8.	950 7	79 Past	Pasture/grassland/range, Fair, HSG C					
_	10.	300 8	34 Past	Pasture/grassland/range, Fair, HSG D					
	19.	250 8	32 Weig	Weighted Average					
	19.	250	100.	00% Pervi	ous Area				
	Тс	Length	Slope	Velocity	Capacity	Description			
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)				
	8.3	100	0.0260	0.20		Sheet Flow,			
						Grass: Short n= 0.150 P2= 3.60"			
	11.1	750	0.0260	1.13		Shallow Concentrated Flow,			
_						Short Grass Pasture Kv= 7.0 fps			
	19.4	850	Total						

Subcatchment 11S: EX DA-4




Summary for Subcatchment 12S: EX OFF DA -4

Runoff = 18.56 cfs @ 12.18 hrs, Volume= 1.562 af, Depth> 4.09"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 10-Year Rainfall=5.30"

_	Area	(ac) C	N Desc	cription			
	4.	580 9	2 Pave	ed roads w	nes, 50% imp, HSG C		
-	2.	290	50.0	0% Pervio			
	2.	290	50.0	0% Imperv	∕ious Area		
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description	
	1.1	100	0.0200	1.46		Sheet Flow,	
	24.1	1,430	0.0200	0.99		Smooth surfaces n= 0.011 P2= 3.60" Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps	
	25.2	1.530	Total				

Subcatchment 12S: EX OFF DA -4



Page 13


Summary for Subcatchment 13S: EX DA-3

Runoff = 72.33 cfs @ 12.31 hrs, Volume= 7.092 af, Depth> 2.90"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 10-Year Rainfall=5.30"

	Area	(ac)	C١	l Desc	cription		
2.920 76 Woods/grass comb., Fair, HSG							, HSG C
	14.	020	79	Past	ure/grassla	and/range,	Fair, HSG C
	7.	890	82	2 Woo	ds/grass d	omb., Fair,	, HSG D
	4.	520	84	1 Past	ure/grassl	and/range,	Fair, HSG D
	29.	350	80) Weig	ghted Aver	age	
29.350 100.00% Pervious Area							
	Тс	Lengt	th	Slope	Velocity	Capacity	Description
	(min)	(fee	et)	(ft/ft)	(ft/sec)	(cfs)	
	9.1	10	00	0.0205	0.18		Sheet Flow,
							Grass: Short n= 0.150 P2= 3.60"
	26.0	1,56	35	0.0205	1.00		Shallow Concentrated Flow,
		•					Short Grass Pasture Kv= 7.0 fps
	35.1	1,66	35	Total			<u> </u>

Subcatchment 13S: EX DA- 3



Page 14


Summary for Subcatchment 14S: EX DA-2

Runoff = 14.09 cfs @ 12.15 hrs, Volume= 1.039 af, Depth> 2.91"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 10-Year Rainfall=5.30"

_	Area	(ac) C	N Desc	cription					
	3.	220 7	'9 Past	Pasture/grassland/range, Fair, HSG C					
	1.	060 8	4 Past	ure/grassl	and/range,	Fair, HSG D			
	4.	280 8	0 Weig						
	4.	280	100.	100.00% Pervious Area					
	Тс	Length	Slope	Velocity	Capacity	Description			
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)				
	9.2	100	0.0200	0.18		Sheet Flow,			
						Grass: Short n= 0.150 P2= 3.60"			
	13.0	770	0.0200	0.99		Shallow Concentrated Flow,			
_						Short Grass Pasture Kv= 7.0 fps			
	22.2	870	Total						

Subcatchment 14S: EX DA-2




Summary for Subcatchment 15S: EX DA-1

Runoff = 28.41 cfs @ 12.18 hrs, Volume= 2.236 af, Depth> 2.82"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 10-Year Rainfall=5.30"

_	Area	(ac) C	N Desc	cription			_		
	0.	590 7	'6 Woo	Woods/grass comb., Fair, HSG C					
_	8.	930 7	'9 Past	ure/grassl	and/range,	Fair, HSG C	_		
	9.	520 7	'9 Weig	Weighted Average					
	9.	520	100.	00.00% Pervious Area					
	Тс	Length	Slope	Velocity	Capacity	Description			
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)		_		
	10.3	100	0.0152	0.16		Sheet Flow,			
						Grass: Short n= 0.150 P2= 3.60"			
	14.5	750	0.0152	0.86		Shallow Concentrated Flow,			
_						Short Grass Pasture Kv= 7.0 fps	_		
	24.8	850	Total						

Subcatchment 15S: EX DA-1



Page 16

Summary for Link 7L: RP-1


Inflow Area = 9.520 ac, 0.00% Impervious, Inflow Depth > 2.82" for 10-Year event

Inflow = 28.41 cfs @ 12.18 hrs, Volume= 2.236 af

Primary = 28.41 cfs @ 12.18 hrs, Volume= 2.236 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 7L: RP-1



Page 17

Summary for Link 8L: RP-2


Inflow Area = 4.280 ac, 0.00% Impervious, Inflow Depth > 2.91" for 10-Year event

Inflow = 14.09 cfs @ 12.15 hrs, Volume= 1.039 af

Primary = 14.09 cfs @ 12.15 hrs, Volume= 1.039 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 8L: RP-2



Page 18

Summary for Link 9L: RP-3


Inflow Area = 29.350 ac, 0.00% Impervious, Inflow Depth > 2.90" for 10-Year event

Inflow = 72.33 cfs @ 12.31 hrs, Volume= 7.092 af

Primary = 72.33 cfs @ 12.31 hrs, Volume= 7.092 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 9L: RP-3



Page 19

Summary for Link 10L: RP-4


Inflow Area = 23.830 ac, 9.61% Impervious, Inflow Depth > 3.29" for 10-Year event

Inflow = 89.87 cfs @ 12.13 hrs, Volume= 6.539 af

Primary = 89.87 cfs @ 12.13 hrs, Volume= 6.539 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 10L: RP-4




Summary for Subcatchment 11S: EX DA-4

Runoff = 118.61 cfs @ 12.11 hrs, Volume= 8.341 af, Depth> 5.20"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 100-Year Rainfall=7.70"

_	Area	(ac) C	N Desc	cription					
	8.	950	79 Past	Pasture/grassland/range, Fair, HSG C					
	10.300 84		34 Past	ure/grassl	and/range,	Fair, HSG D			
	19.	250 8	32 Weig	Weighted Average					
	19.	250	100.	00% Pervi	ous Area				
	Tc	Length	Slope	Velocity	Capacity	Description			
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)				
	8.3	100	0.0260	0.20		Sheet Flow,			
						Grass: Short n= 0.150 P2= 3.60"			
	11.1	750	0.0260	1.13		Shallow Concentrated Flow,			
_						Short Grass Pasture Kv= 7.0 fps			
	19 4	850	Total						

Subcatchment 11S: EX DA-4



Page 21


Summary for Subcatchment 12S: EX OFF DA -4

Runoff = 27.98 cfs @ 12.17 hrs, Volume= 2.398 af, Depth> 6.28"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 100-Year Rainfall=7.70"

_	Area	(ac) C	N Des	cription				
	4.	580 9	2 Pave	ed roads w	/open ditch	nes, 50% imp, HSG C		
2.290 50.00% Pervious Area								
	2.	290	50.0	0% Imperv	ious Area			
	_				_			
	Tc	Length	Slope	Velocity	Capacity	Description		
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)			
	1.1	100	0.0200	1.46		Sheet Flow,		
						Smooth surfaces n= 0.011 P2= 3.60"		
	24.1	1,430	0.0200	0.99		Shallow Concentrated Flow,		
						Short Grass Pasture Kv= 7.0 fps		
-	25.2	1.530	Total			·		

Subcatchment 12S: EX OFF DA -4




Summary for Subcatchment 13S: EX DA-3

Runoff = 121.81 cfs @ 12.30 hrs, Volume= 12.105 af, Depth> 4.95"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 100-Year Rainfall=7.70"

	Area	(ac)	CN	Desc	ription		
2.920 76 Woods/grass comb., Fair, HS							, HSG C
	14.	020	79	Past	ure/grassla	and/range,	Fair, HSG C
	7.	890	82	Woo	ds/grass d	omb., Fair,	, HSG D
_	4.	520	84	Past	ure/grassla	and/range,	Fair, HSG D
	29.	350	80	Weig	hted Aver	age	
	29.	350		100.0	00% Pervi	ous Area	
	Tc	Lengt	h	Slope	Velocity	Capacity	Description
_	(min)	(feet	:)	(ft/ft)	(ft/sec)	(cfs)	
	9.1	10	0 0	.0205	0.18		Sheet Flow,
							Grass: Short n= 0.150 P2= 3.60"
	26.0	1,56	5 0	.0205	1.00		Shallow Concentrated Flow,
							Short Grass Pasture Kv= 7.0 fps
	35.1	1,66	5 T	otal			

Subcatchment 13S: EX DA- 3



Page 23


Summary for Subcatchment 14S: EX DA-2

Runoff = 23.62 cfs @ 12.15 hrs, Volume= 1.772 af, Depth> 4.97"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 100-Year Rainfall=7.70"

_	Area	(ac) C	N Des	cription					
_	3.	220 7	'9 Past	ure/grassl	and/range,	Fair, HSG C			
	1.	060 8	34 Past	Pasture/grassland/range, Fair, HSG D					
_	4.	280 8	30 Weig	Weighted Average					
	4.	280	100.	00% Pervi	ous Area				
	Tc	Length	Slope	Velocity	Capacity	Description			
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)				
	9.2	100	0.0200	0.18		Sheet Flow,			
						Grass: Short n= 0.150 P2= 3.60"			
	13.0	770	0.0200	0.99		Shallow Concentrated Flow,			
_						Short Grass Pasture Kv= 7.0 fps			
	22.2	870	Total						

Subcatchment 14S: EX DA-2



Page 24


Summary for Subcatchment 15S: EX DA-1

Runoff = 48.20 cfs @ 12.18 hrs, Volume= 3.850 af, Depth> 4.85"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs Type II 24-hr 100-Year Rainfall=7.70"

	Area	(ac) C	N Des	cription			_
	0.	590 7	76 Woo	ds/grass d	omb., Fair,	, HSG C	
_	8.	930 7	79 Past	ure/grassl	and/range,	Fair, HSG C	_
	9.	520 7	79 Weig	ghted Aver	age		
	9.	520	100.	00% Pervi	ous Area		
	Тс	Length	Slope	Velocity	Capacity	Description	
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)		_
	10.3	100	0.0152	0.16		Sheet Flow,	
						Grass: Short n= 0.150 P2= 3.60"	
	14.5	750	0.0152	0.86		Shallow Concentrated Flow,	
_						Short Grass Pasture Kv= 7.0 fps	_
	24.8	850	Total				

Subcatchment 15S: EX DA-1



Page 25

Summary for Link 7L: RP-1


Inflow Area = 9.520 ac, 0.00% Impervious, Inflow Depth > 4.85" for 100-Year event

Inflow = 48.20 cfs @ 12.18 hrs, Volume= 3.850 af

Primary = 48.20 cfs @ 12.18 hrs, Volume= 3.850 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 7L: RP-1



Page 26

Summary for Link 8L: RP-2


Inflow Area = 4.280 ac, 0.00% Impervious, Inflow Depth > 4.97" for 100-Year event

Inflow = 23.62 cfs @ 12.15 hrs, Volume= 1.772 af

Primary = 23.62 cfs @ 12.15 hrs, Volume= 1.772 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 8L: RP-2



Page 27

Summary for Link 9L: RP-3


Inflow Area = 29.350 ac, 0.00% Impervious, Inflow Depth > 4.95" for 100-Year event

Inflow = 121.81 cfs @ 12.30 hrs, Volume= 12.105 af

Primary = 121.81 cfs @ 12.30 hrs, Volume= 12.105 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 9L: RP-3



Page 28

Summary for Link 10L: RP-4


Inflow Area = 23.830 ac, 9.61% Impervious, Inflow Depth > 5.41" for 100-Year event


Inflow = 145.17 cfs @ 12.12 hrs, Volume= 10.739 af

Primary = 145.17 cfs @ 12.12 hrs, Volume= 10.739 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link 10L: RP-4





Summary for Subcatchment 11S: Onsite 5


[49] Hint: Tc<2dt may require smaller dt

Runoff = 69.12 cfs @ 11.95 hrs, Volume= 3.281 af, Depth> 2.27"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Type II 24-hr 2-Year Rainfall=3.50"

	Area	(ac) C	N Des	cription		
*	17.	370 8	38 Apai	tments, 65	5% imp, HS	SG C
	6.	079	35.0	0% Pervio	us Area	
	11.	290	65.0	0% Imper	∕ious Area	
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
	1.1	100	0.0200	1.46		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.60"
	3.9					Direct Entry, Pipe flow
	5.0	100	Total			

Subcatchment 11S: Onsite 5



Summary for Subcatchment 12S: EX OFF


[49] Hint: Tc<2dt may require smaller dt

Runoff = 27.58 cfs @ 11.95 hrs, Volume= 1.309 af, Depth> 2.27"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Type II 24-hr 2-Year Rainfall=3.50"

	Area	(ac) C	N Des	cription			
*	6.930 88 Future Multi-Family, 65% imp, HSG C						
	2.	425	35.0	0% Pervio	us Area		_
4.504 65.00% Impervious Area							
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description	
	1.0	100	0.0300	1.72		Sheet Flow, Sheet flow	
	4.0	700		0.00		Smooth surfaces n= 0.011 P2= 3.60"	
_	4.0	700		2.92		Direct Entry, Pipe flow	_
	5.0	800	Total				

Subcatchment 12S: EX OFF



Page 4


Summary for Subcatchment 13S: Onsite 4

Runoff = 88.82 cfs @ 12.04 hrs, Volume= 5.600 af, Depth> 2.63"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Type II 24-hr 2-Year Rainfall=3.50"

_	Area	(ac) C	N Des	cription		
*	13.	070	92 SING	GLE FAMI	LY LOTS	
12.480 92 1/8 acre lots, 65% imp, HS						SG D
25.550 92 Weighted Average						
17.438 68.25% Pervious Area						
	8.112 31.75% Impervious Area				∕ious Area	
	_		01			
	Tc	Length	Slope	Velocity	Capacity	Description
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
	1.1	100	0.0205	1.47		Sheet Flow,
						Smooth surfaces n= 0.011 P2= 3.60"
	12.0	1,830	0.0250	2.55		Shallow Concentrated Flow,
_						Unpaved Kv= 16.1 fps
	13.1	1,930	Total			

Subcatchment 13S: Onsite 4




Summary for Subcatchment 15S: Onsite 2

Runoff = 22.39 cfs @ 11.98 hrs, Volume= 1.216 af, Depth> 2.94"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Type II 24-hr 2-Year Rainfall=3.50"

_	Area	(ac) C	N Desc	cription			
4.970 95 Urban commercial, 85% imp, HSG D							
-	0.	746					
4.224 85.00% Impervious Area					ious Area		
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description	
-	1.1	100	0.0200	1.46		Sheet Flow,	
_	5.9	805	0.0200	2.28		Smooth surfaces n= 0.011 P2= 3.60" Shallow Concentrated Flow, Unpaved Kv= 16.1 fps	
	7.0	905	Total				

Subcatchment 15S: Onsite 2




Summary for Subcatchment 16S: Onsite 3

Runoff = 44.14 cfs @ 11.99 hrs, Volume= 2.361 af, Depth> 2.63"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Type II 24-hr 2-Year Rainfall=3.50"

	Area	(ac) C	N Desc	cription			
10.760 92 1/8 acre lots, 65% imp, HSG D							
3.766 35.00% Pervious Area							
6.994 65.00% Impervious Area					ious Area		
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description	
	1.1	100	0.0200	1.46		Sheet Flow,	
	6.8	1,045	0.0250	2.55		Smooth surfaces n= 0.011 P2= 3.60" Shallow Concentrated Flow, Unpaved Kv= 16.1 fps	
	7.9	1.145	Total				

Subcatchment 16S: Onsite 3



Page 7


Summary for Subcatchment 17S: Onsite 1

Runoff = 2.43 cfs @ 11.98 hrs, Volume= 0.132 af, Depth> 2.94"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Type II 24-hr 2-Year Rainfall=3.50"

_	Area	(ac) C	N Desc	cription			
0.540 95 Urban commercial, 85% imp, HSG D							
-	0.	081	15.0				
0.459 85.00% Impervious Area					ious Area		
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description	
-	1.1	100	0.0200	1.46		Sheet Flow,	
_	5.9	805	0.0200	2.28		Smooth surfaces n= 0.011 P2= 3.60" Shallow Concentrated Flow, Unpaved Kv= 16.1 fps	
	7.0	905	Total				

Subcatchment 17S: Onsite 1



Page 8

Summary for Pond 12P: EWDB #1

Inflow Area = 24.300 ac, 65.00% Impervious, Inflow Depth > 2.27" for 2-Year event

Inflow 96.70 cfs @ 11.95 hrs, Volume= 4.590 af

15.00 cfs @ 12.16 hrs, Volume= Outflow 3.598 af, Atten= 84%, Lag= 12.6 min

Primary 15.00 cfs @ 12.16 hrs, Volume= 3.598 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Peak Elev= 996.42' @ 12.16 hrs Surf.Area= 73,555 sf Storage= 100,744 cf

Plug-Flow detention time= 185.1 min calculated for 3.598 af (78% of inflow)

Center-of-Mass det. time= 100.3 min (907.2 - 806.9)

Volume	Inver	t Avail.Sto	rage Storag	e Description			
#1	995.00)' 389,75	53 cf Custo	m Stage Data (P	rismatic)Listed below (Recalc)		
	_						
Elevation	on S	Surf.Area	Inc.Store	Cum.Store			
(fee	t)	(sq-ft)	(cubic-feet)	(cubic-feet)			
995.0	00	67,904	0	0			
996.0	00	71,853	69,879	69,879			
997.0	00	75,863	73,858	143,737			
998.0	00	79,925	77,894	221,631			
999.0	00	84,048	81,987	303,617			
1,000.0	00	88,224	86,136	389,753			
Device	Routing	Invert	Outlet Device	ces			
#1	Primary	994.50'	30.0" Rour	nd Culvert			
	•		L= 80.0' R	CP, sq.cut end pro	ojecting, Ke= 0.500		
			Inlet / Outlet	t Invert= 994.50' /	993.90' S= 0.0075 '/' Cc= 0.900		
			n= 0.012 C	oncrete pipe, finis	hed, Flow Area= 4.91 sf		
#2	Device 1	994.80'	···				
			Cv= 2.69 (C= 3.36)				
#3	Device 1	995.50'	5.0' long x 3.00' rise Sharp-Crested Rectangular Weir				
			2 End Contraction(s) 3.0' Crest Height				
#4	Device 1	998.50'	60.0" x 60.0" Horiz. Orifice/Grate C= 0.600				

Limited to weir flow at low heads

Primary OutFlow Max=14.97 cfs @ 12.16 hrs HW=996.42' (Free Discharge)

-1=Culvert (Passes 14.97 cfs of 17.04 cfs potential flow)


²⁼Sharp-Crested Vee/Trap Weir (Orifice Controls 0.47 cfs @ 5.41 fps)

⁻³⁼Sharp-Crested Rectangular Weir (Weir Controls 14.50 cfs @ 3.26 fps)


⁻⁴⁼Orifice/Grate (Controls 0.00 cfs)

Page 9

Pond 12P: EWDB #1




Pond 12P: EWDB #1



Page 10

Pond 12P: EWDB #1

Stage-Area-Storage



Prepared by Schlagel

HydroCAD® 10.00-13 s/n 08303 © 2014 HydroCAD Software Solutions LLC

Printed 11/18/2022 Page 11

Summary for Pond 13P: EWDB #2

Inflow Area = 10.760 ac, 65.00% Impervious, Inflow Depth > 2.63" for 2-Year event

Inflow 44.14 cfs @ 11.99 hrs, Volume= 2.361 af

4.27 cfs @ 12.47 hrs, Volume= Outflow 1.767 af, Atten= 90%, Lag= 29.0 min

Primary 4.27 cfs @ 12.47 hrs, Volume= 1.767 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Peak Elev= 994.41' @ 12.47 hrs Surf.Area= 27,552 sf Storage= 58,861 cf

Plug-Flow detention time= 253.6 min calculated for 1.767 af (75% of inflow)

Center-of-Mass det. time= 164.8 min (957.0 - 792.3)

Volume	Inve	rt Avail.Sto	rage Stora	ge Description	
#1	992.00	0' 175,79	99 cf Cust	om Stage Data (P	rismatic)Listed below (Recalc)
Elevation (fee	et)	Surf.Area (sq-ft) 21,391	Inc.Store (cubic-feet)	•	
994.0 996.0	-	26,438 31,892	47,829 58,330	•	
998.0	-	37,748	69,640	,	
Device	Routing	Invert	Outlet Dev	ices	
#1	Primary	992.00'	L= 50.0' F	et Invert= 992.00' /	ojecting, Ke= 0.500 991.00' S= 0.0200 '/' Cc= 0.900 shed, Flow Area= 1.77 sf
#2	Device 1	992.00'		4.00' rise Sharp-	Crested Vee/Trap Weir
#3	Device 1	996.00'	72.0" x 72	.0" Horiz. Orifice/ weir flow at low hea	

Primary OutFlow Max=4.27 cfs @ 12.47 hrs HW=994.41' (Free Discharge)


-1=Culvert (Passes 4.27 cfs of 10.96 cfs potential flow)

-2=Sharp-Crested Vee/Trap Weir (Weir Controls 4.27 cfs @ 4.17 fps)


-3=Orifice/Grate (Controls 0.00 cfs)

Page 12

Pond 13P: EWDB #2




Pond 13P: EWDB #2



Page 13

Pond 13P: EWDB #2

Stage-Area-Storage



Printed 11/18/2022 Page 14

Summary for Pond 14P: EWDB #3

Inflow Area = 36.310 ac, 41.60% Impervious, Inflow Depth > 2.43" for 2-Year event

Inflow = 91.67 cfs @ 12.05 hrs, Volume= 7.367 af

Outflow = 13.81 cfs @ 12.60 hrs, Volume= 5.931 af, Atten= 85%, Lag= 33.0 min

Primary = 13.81 cfs @ 12.60 hrs, Volume= 5.931 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Peak Elev= 987.85' @ 12.60 hrs Surf.Area= 43,325 sf Storage= 142,136 cf

Plug-Flow detention time= 212.5 min calculated for 5.919 af (80% of inflow)

Center-of-Mass det. time= 129.0 min (963.8 - 834.9)

Volume	Inve	rt Avail.Sto	rage Storag	e Description	
#1	984.0	0' 355,62	25 cf Custo	m Stage Data (P	rismatic)Listed below (Recalc)
Elevatio (fee		Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	
984.0	00	30,844	0	0	
986.0	0	36,957	67,801	67,801	
988.0	00	43,835	80,792	148,593	
990.0	00	51,620	95,455	244,048	
992.0	00	59,957	111,577	355,625	
Device	Routing	Invert	Outlet Device	ces	
#1	Primary	983.00'	36.0" Rour	nd Culvert	
	·				ojecting, Ke= 0.500 982.00' S= 0.0200 '/' Cc= 0.900
#2	Device 1	984.00'	n= 0.012 C	oncrete pipe, finis	soz.00 S= 0.0200 / CC= 0.900 hed, Flow Area= 7.07 sf Crested Vee/Trap Weir
			Cv= 2.69 (C	•	·

990.00' **72.0" x 72.0" Horiz. Orifice/Grate** C= 0.600

Limited to weir flow at low heads

Primary OutFlow Max=13.81 cfs @ 12.60 hrs HW=987.85' (Free Discharge)

-1=Culvert (Passes 13.81 cfs of 62.31 cfs potential flow)

—2=Sharp-Crested Vee/Trap Weir (Weir Controls 13.81 cfs @ 5.28 fps)


-3=Orifice/Grate (Controls 0.00 cfs)

#3


Device 1

Page 15

Pond 14P: EWDB #3




Pond 14P: EWDB #3



Page 16

Pond 14P: EWDB #3

Stage-Area-Storage



HydroCAD® 10.00-13 s/n 08303 © 2014 HydroCAD Software Solutions LLC

Page 17

Summary for Pond 15P: EDDB #1

Inflow Area = 4.970 ac, 85.00% Impervious, Inflow Depth > 2.94" for 2-Year event

Inflow 22.39 cfs @ 11.98 hrs, Volume= 1.216 af

4.75 cfs @ 12.17 hrs, Volume= Outflow 0.730 af, Atten= 79%, Lag= 11.4 min

Primary 4.75 cfs @ 12.17 hrs, Volume= 0.730 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Peak Elev= 1,007.87' @ 12.17 hrs Surf.Area= 14,115 sf Storage= 26,583 cf

Plug-Flow detention time= 186.7 min calculated for 0.730 af (60% of inflow)

Center-of-Mass det. time= 82.1 min (857.1 - 775.0)

Volume	Inver	t Avail.Sto	rage Storage	Description		
#1	1,004.00)' 68,10	00 cf Custom	Stage Data (Pi	rismatic)Listed below (Rec	alc)
	_		. 0	0 01		
Elevatio		Surf.Area	Inc.Store	Cum.Store		
(fee	i)	(sq-ft)	(cubic-feet)	(cubic-feet)		
1,004.0	0	50	0	0		
1,006.0	0	6,872	6,922	6,922		
1,008.0	0	14,603	21,475	28,397		
1,010.0	0	25,100	39,703	68,100		
Device	Routing	Invert	Outlet Device	S		
#1	Primary	1,002.00'	24.0" Round	Culvert		
	,	•	L= 50.0' RCF	, sq.cut end pro	ojecting, Ke= 0.500	
					'/ 1,001.50' S= 0.0100 '/'	Cc = 0.900
					hed, Flow Area= 3.14 sf	
#2	Device 1	1,002.25'		" ORIFICE C=		
#3	Device 1	1,007.50'		/Orifice, Cv= 2.	.62 (C= 3.28)	
		,		,007.50 1,009.		
			Width (feet) 6			
#4	Device 2	1,002.50'	6.0" Round (
,, .		.,002.00			neadwall, Ke= 0.500	
					'/ 1,002.25' S= 0.0083 '/'	Cc = 0.900
				•		0.000
#5	Device 2	1 005 00'				
,, 0	_ J L	.,000.00				
#6	Device 1	1 010 00'				
,, 0	231100 1	1,010.00				
#5 #6	Device 2 Device 1	1,005.00' 1,010.00'	1.0" Vert. 15" X 9 rows with 72.0" x 72.0"	' RISER X 7.00 4.0" cc spacing	C= 0.600 Grate C= 0.600	

Primary OutFlow Max=4.67 cfs @ 12.17 hrs HW=1,007.87' (Free Discharge)

-1=Culvert (Passes 4.67 cfs of 33.38 cfs potential flow)

-2=2.0" ORIFICE (Orifice Controls 0.25 cfs @ 11.33 fps)


-4=6" PVC (Passes < 2.09 cfs potential flow)

5=15" RISER (Passes < 1.91 cfs potential flow)


-3=Custom Weir/Orifice (Weir Controls 4.42 cfs @ 1.99 fps)

-6=Orifice/Grate (Controls 0.00 cfs)

Pond 15P: EDDB #1




Pond 15P: EDDB #1



Page 19

Pond 15P: EDDB #1

Stage-Area-Storage



Page 20

Summary for Link 7L: RP-1


Inflow Area = 5.510 ac, 85.00% Impervious, Inflow Depth > 1.88" for 2-Year event

Inflow = 5.25 cfs @ 12.14 hrs, Volume= 0.862 af

Primary = 5.25 cfs @ 12.14 hrs, Volume= 0.862 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Link 7L: RP-1



Page 21

Summary for Link 9L: RP-3


Inflow Area = 36.310 ac, 41.60% Impervious, Inflow Depth > 1.96" for 2-Year event

Inflow = 13.81 cfs @ 12.60 hrs, Volume= 5.931 af

Primary = 13.81 cfs @ 12.60 hrs, Volume= 5.931 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Link 9L: RP-3



Page 22

Summary for Link 10L: RP-4


Inflow Area = 24.300 ac, 65.00% Impervious, Inflow Depth > 1.78" for 2-Year event

Inflow = 15.00 cfs @ 12.16 hrs, Volume= 3.598 af

Primary = 15.00 cfs @ 12.16 hrs, Volume= 3.598 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Link 10L: RP-4



Summary for Subcatchment 11S: Onsite 5


[49] Hint: Tc<2dt may require smaller dt

Runoff = 116.83 cfs @ 11.95 hrs, Volume= 5.720 af, Depth> 3.95"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Type II 24-hr 10-Year Rainfall=5.30"

	Area	(ac) C	N Des	cription						
*	17.	370 8	70 88 Apartments, 65% imp, HSG C							
	6.	079	35.0	0% Pervio	us Area					
	11.	290	65.0	0% Imperv	∕ious Area					
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description				
-	1.1	100	0.0200	1.46	(013)	Sheet Flow, Smooth surfaces n= 0.011 P2= 3.60"				
_	3.9					Direct Entry, Pipe flow				
	5.0	100	Total							

Subcatchment 11S: Onsite 5



Page 24

Summary for Subcatchment 12S: EX OFF


[49] Hint: Tc<2dt may require smaller dt

Runoff = 46.61 cfs @ 11.95 hrs, Volume= 2.282 af, Depth> 3.95"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Type II 24-hr 10-Year Rainfall=5.30"

Area (ac) CN Description							
*	6.	930 8	38 Futu	re Multi-Fa	amily, 65%	imp, HSG C	
	2.	425	35.0	0% Pervio	us Area		
	4.	504	65.0	0% Imper	∕ious Area		
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description	
	1.0	100	0.0300	1.72		Sheet Flow, Sheet flow	
	4.0	700		0.00		Smooth surfaces n= 0.011 P2= 3.60"	
_	4.0	700		2.92		Direct Entry, Pipe flow	_
	5.0	800	Total				

Subcatchment 12S: EX OFF




Summary for Subcatchment 13S: Onsite 4

Runoff = 143.48 cfs @ 12.04 hrs, Volume= 9.310 af, Depth> 4.37"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Type II 24-hr 10-Year Rainfall=5.30"

	Area	(ac) C	N Des	cription		
	* 13.	.070 9	2 SINO	GLE FAMI	LY LOTS	
	12.	480 9	92 1/8 a	acre lots, 6	55% imp, H	SG D
25.550 92 Weighted Average						
	17.	438	68.2	5% Pervio	us Area	
	8.	112	31.7	5% Imperv	vious Area	
	Тс	Length	Slope	Velocity	Capacity	Description
	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)	
	1.1	100	0.0205	1.47		Sheet Flow,
						Smooth surfaces n= 0.011 P2= 3.60"
	12.0	1,830	0.0250	2.55		Shallow Concentrated Flow,
						Unpaved Kv= 16.1 fps
	13.1	1.930	Total			

Subcatchment 13S: Onsite 4




Summary for Subcatchment 15S: Onsite 2

Runoff = 34.88 cfs @ 11.98 hrs, Volume= 1.952 af, Depth> 4.71"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Type II 24-hr 10-Year Rainfall=5.30"

_	Area	(ac) C	N Des	cription					
4.970 95 Urban commercial, 85% imp, HSG D									
_	0.	746	15.0	0% Pervio	us Area				
4.224 85.00% Impervious Area									
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description			
	1.1	100	0.0200	1.46		Sheet Flow,			
	5.9	805	0.0200	2.28		Smooth surfaces n= 0.011 P2= 3.60" Shallow Concentrated Flow, Unpaved Kv= 16.1 fps			
	7.0	905	Total	·	·				

Subcatchment 15S: Onsite 2



Page 27


Summary for Subcatchment 16S: Onsite 3

Runoff = 71.05 cfs @ 11.99 hrs, Volume= 3.925 af, Depth> 4.38"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Type II 24-hr 10-Year Rainfall=5.30"

	Area	(ac) C	N Desc	cription			
	10.	760 9)2 1/8 a	acre lots, 6	5% imp, H	SG D	
-	3.	766	35.0	0% Pervio	us Area		
	6.	994	65.0	0% Imper	ious Area		
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description	
	1.1	100	0.0200	1.46		Sheet Flow,	
	6.8	1,045	0.0250	2.55		Smooth surfaces n= 0.011 P2= 3.60" Shallow Concentrated Flow, Unpaved Kv= 16.1 fps	
	7.9	1.145	Total				

Subcatchment 16S: Onsite 3



Page 28


Summary for Subcatchment 17S: Onsite 1

Runoff = 3.79 cfs @ 11.98 hrs, Volume= 0.212 af, Depth> 4.71"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Type II 24-hr 10-Year Rainfall=5.30"

	Area	(ac) C	N Desc	cription					
0.540 95 Urban commercial, 85% imp, HSG D									
•	0.	081	15.0	0% Pervio	us Area				
0.459 85.00% Impervious Area									
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description			
	1.1	100	0.0200	1.46		Sheet Flow,			
	5.9	805	0.0200	2.28		Smooth surfaces n= 0.011 P2= 3.60" Shallow Concentrated Flow, Unpaved Kv= 16.1 fps			
	7.0	905	Total						

Subcatchment 17S: Onsite 1



HydroCAD® 10.00-13 s/n 08303 © 2014 HydroCAD Software Solutions LLC

Page 29

Summary for Pond 12P: EWDB #1

Inflow Area = 24.300 ac, 65.00% Impervious, Inflow Depth > 3.95" for 10-Year event

Inflow 163.44 cfs @ 11.95 hrs, Volume= 8.002 af

29.51 cfs @ 12.13 hrs, Volume= Outflow 6.923 af, Atten= 82%, Lag= 10.7 min

Primary 29.51 cfs @ 12.13 hrs, Volume= 6.923 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Peak Elev= 997.38' @ 12.13 hrs Surf.Area= 77,425 sf Storage= 173,208 cf

Plug-Flow detention time= 149.9 min calculated for 6.908 af (86% of inflow)

Center-of-Mass det. time= 87.6 min (878.9 - 791.2)

Volume	Inver	t Avail.Sto	rage Stora	ge Description	
#1	995.00)' 389,75	53 cf Custo	om Stage Data (Prismatic)Listed below (Recalc)	
- 1	6	N	l Ot	0 01	
Elevation		Surf.Area	Inc.Store		
(fee	et)	(sq-ft)	(cubic-feet)	(cubic-feet)	
995.0	00	67,904	0	0	
996.0	00	71,853	69,879	69,879	
997.0	00	75,863	73,858	143,737	
998.0	00	79,925	77,894	221,631	
999.0	00	84,048	81,987	303,617	
1,000.0	00	88,224	86,136	· · · · · · · · · · · · · · · · · · ·	
,		,	,	,	
Device	Routing	Invert	Outlet Devi	ices	
#1	Primary	994.50'	30.0" Rou	ind Culvert	
	,		L= 80.0' R	RCP, sq.cut end projecting, Ke= 0.500	
				et Invert= 994.50' / 993.90' S= 0.0075 '/' Cc= 0.900	
			n= 0.012 C	Concrete pipe, finished, Flow Area= 4.91 sf	
#2	Device 1	994.80'		0.70' rise Sharp-Crested Vee/Trap Weir	
			Cv= 2.69 (0		
#3	Device 1	995.50'	`	3.00' rise Sharp-Crested Rectangular Weir	
				traction(s) 3.0' Crest Height	
#4	Device 1	998.50'		.0" Horiz. Orifice/Grate Č= 0.600	
			Limited to v	weir flow at low heads	

Primary OutFlow Max=29.49 cfs @ 12.13 hrs HW=997.38' (Free Discharge)

-1=Culvert (Barrel Controls 29.49 cfs @ 6.54 fps)


²⁼Sharp-Crested Vee/Trap Weir (Passes < 0.63 cfs potential flow)

⁻³⁼Sharp-Crested Rectangular Weir (Passes < 42.05 cfs potential flow)


⁻⁴⁼Orifice/Grate (Controls 0.00 cfs)

Page 30

Pond 12P: EWDB #1




Pond 12P: EWDB #1



Page 31

Pond 12P: EWDB #1

Stage-Area-Storage



Page 32

Summary for Pond 13P: EWDB #2

Inflow Area = 10.760 ac, 65.00% Impervious, Inflow Depth > 4.38" for 10-Year event

Inflow 71.05 cfs @ 11.99 hrs, Volume= 3.925 af

11.44 cfs @ 12.24 hrs, Volume= Outflow 3.242 af, Atten= 84%, Lag= 15.3 min

Primary 11.44 cfs @ 12.24 hrs, Volume= 3.242 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Peak Elev= 995.57' @ 12.24 hrs Surf.Area= 30,724 sf Storage= 92,751 cf

Plug-Flow detention time= 208.4 min calculated for 3.235 af (82% of inflow)

Center-of-Mass det. time= 135.9 min (914.4 - 778.4)

Volume	Inve	rt Avail.Sto	rage Storage	Description	
#1	992.00	0' 175,79	99 cf Custom	Stage Data (P	rismatic)Listed below (Recalc)
Elevatio (fee 992.0 994.0 996.0 998.0	et) 00 00 00	Surf.Area (sq-ft) 21,391 26,438 31,892 37,748	Inc.Store (cubic-feet) 0 47,829 58,330 69,640	Cum.Store (cubic-feet) 0 47,829 106,159 175,799	
Device	Routing	Invert	Outlet Device	S	
#1	Primary	992.00'	18.0" Round		
			Inlet / Outlet I	nvert= 992.00' /	ojecting, Ke= 0.500 991.00' S= 0.0200 '/' Cc= 0.900 hed, Flow Area= 1.77 sf
#2	Device 1	992.00'	20.0 deg x 4.	00' rise Sharp-	Crested Vee/Trap Weir
#3	Device 1	996.00'	Cv= 2.69 (C= 72.0" x 72.0"	,	Grate C= 0.600

Limited to weir flow at low heads


Primary OutFlow Max=11.43 cfs @ 12.24 hrs HW=995.57' (Free Discharge)

-1=Culvert (Passes 11.43 cfs of 14.29 cfs potential flow)


2=Sharp-Crested Vee/Trap Weir (Weir Controls 11.43 cfs @ 5.08 fps)

-3=Orifice/Grate (Controls 0.00 cfs)

Pond 13P: EWDB #2




Pond 13P: EWDB #2



Page 34

Pond 13P: EWDB #2

Stage-Area-Storage



Page 35

Summary for Pond 14P: EWDB #3

Inflow Area = 36.310 ac, 41.60% Impervious, Inflow Depth > 4.15" for 10-Year event

Inflow = 152.29 cfs @ 12.05 hrs, Volume= 12.552 af

Outflow = 35.59 cfs @ 12.41 hrs, Volume= 10.895 af, Atten= 77%, Lag= 21.6 min

Primary = 35.59 cfs @ 12.41 hrs, Volume= 10.895 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Peak Elev= 989.62' @ 12.41 hrs Surf.Area= 50,159 sf Storage= 224,953 cf

Plug-Flow detention time= 167.8 min calculated for 10.895 af (87% of inflow)

Center-of-Mass det. time= 105.4 min (922.0 - 816.6)

Volume	Inve	rt Avail.Sto	rage Storag	e Description	
#1	984.0	0' 355,62	25 cf Custo	m Stage Data (P	rismatic)Listed below (Recalc)
Elevation	on .	Surf.Area	Inc.Store	Cum.Store	
(fee	et)	(sq-ft)	(cubic-feet)	(cubic-feet)	
984.0	00	30,844	0	0	
986.0	00	36,957	67,801	67,801	
988.0	00	43,835	80,792	148,593	
990.0	00	51,620	95,455	244,048	
992.0	00	59,957	111,577	355,625	
Device	Routing	Invert	Outlet Device	es	
#1	Primary	983.00'	36.0" Rour	nd Culvert	
	-		L= 50.0' R	CP, sq.cut end pro	ojecting, Ke= 0.500
			Inlet / Outlet	t Invert= 983.00' /	982.00' S= 0.0200 '/' Cc= 0.900
			n= 0.012 C	oncrete pipe, finis	hed, Flow Area= 7.07 sf
#2	Device 1	984.00'	20.0 deg x	6.00' rise Sharp-	Crested Vee/Trap Weir
			Cv= 2.69 (C	= 3.36)	•
#3	Device 1	990.00'	72.0" x 72.0)" Horiz. Orifice/	Grate C= 0.600
			Limited to w	eir flow at low hea	ads

Primary OutFlow Max=35.58 cfs @ 12.41 hrs HW=989.62' (Free Discharge)


-1=Culvert (Passes 35.58 cfs of 77.04 cfs potential flow)

—2=Sharp-Crested Vee/Trap Weir (Weir Controls 35.58 cfs @ 6.38 fps)


-3=Orifice/Grate (Controls 0.00 cfs)

Page 36

Pond 14P: EWDB #3




Pond 14P: EWDB #3



Page 37

Pond 14P: EWDB #3

Stage-Area-Storage



HydroCAD® 10.00-13 s/n 08303 © 2014 HydroCAD Software Solutions LLC

Page 38

Summary for Pond 15P: EDDB #1

Inflow Area = 4.970 ac, 85.00% Impervious, Inflow Depth > 4.71" for 10-Year event

Inflow 34.88 cfs @ 11.98 hrs, Volume= 1.952 af

19.45 cfs @ 12.07 hrs, Volume= Outflow 1.451 af, Atten= 44%, Lag= 5.7 min

Primary 19.45 cfs @ 12.07 hrs, Volume= 1.451 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Peak Elev= 1,008.48' @ 12.07 hrs Surf.Area= 17,146 sf Storage= 36,089 cf

Plug-Flow detention time= 145.9 min calculated for 1.451 af (74% of inflow)

Center-of-Mass det. time= 56.7 min (820.0 - 763.3)

Volume	Inver	t Avail.Sto	rage Storage	Description		
#1	1,004.00)' 68,10	00 cf Custom	Stage Data (Pi	rismatic)Listed below (Rec	alc)
	_		. 0	0 01		
Elevatio		Surf.Area	Inc.Store	Cum.Store		
(fee	i)	(sq-ft)	(cubic-feet)	(cubic-feet)		
1,004.0	0	50	0	0		
1,006.0	0	6,872	6,922	6,922		
1,008.0	0	14,603	21,475	28,397		
1,010.0	0	25,100	39,703	68,100		
Device	Routing	Invert	Outlet Device	S		
#1	Primary	1,002.00'	24.0" Round	Culvert		
	,	•	L= 50.0' RCF	, sq.cut end pro	ojecting, Ke= 0.500	
					'/ 1,001.50' S= 0.0100 '/'	Cc = 0.900
					hed, Flow Area= 3.14 sf	
#2	Device 1	1,002.25'		" ORIFICE C=		
#3	Device 1	1,007.50'		/Orifice, Cv= 2.	.62 (C= 3.28)	
		,		,007.50 1,009.		
			Width (feet) 6			
#4	Device 2	1,002.50'	6.0" Round (
,, .		.,002.00			neadwall, Ke= 0.500	
					'/ 1,002.25' S= 0.0083 '/'	Cc = 0.900
				•		0.000
#5	Device 2	1 005 00'				
,, 0	_ J L	.,000.00				
#6	Device 1	1 010 00'				
,, 0	231100 1	1,010.00				
#5 #6	Device 2 Device 1	1,005.00' 1,010.00'	1.0" Vert. 15" X 9 rows with 72.0" x 72.0"	' RISER X 7.00 4.0" cc spacing	C= 0.600 Grate C= 0.600	

Primary OutFlow Max=18.99 cfs @ 12.07 hrs HW=1,008.47' (Free Discharge)

-1=Culvert (Passes 18.99 cfs of 35.37 cfs potential flow)

-2=2.0" ORIFICE (Orifice Controls 0.26 cfs @ 11.93 fps)

-4=6" PVC (Passes < 2.21 cfs potential flow)


5=15" RISER (Passes < 2.34 cfs potential flow)

-3=Custom Weir/Orifice (Weir Controls 18.73 cfs @ 3.22 fps)


-6=Orifice/Grate (Controls 0.00 cfs)

Page 39

Pond 15P: EDDB #1




Pond 15P: EDDB #1



Page 40

Pond 15P: EDDB #1

Stage-Area-Storage



Page 41

Summary for Link 7L: RP-1


Inflow Area = 5.510 ac, 85.00% Impervious, Inflow Depth > 3.62" for 10-Year event

Inflow = 21.70 cfs @ 12.06 hrs, Volume= 1.663 af

Primary = 21.70 cfs @ 12.06 hrs, Volume= 1.663 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Link 7L: RP-1



Page 42

Summary for Link 9L: RP-3


Inflow Area = 36.310 ac, 41.60% Impervious, Inflow Depth > 3.60" for 10-Year event

Inflow = 35.59 cfs @ 12.41 hrs, Volume= 10.895 af

Primary = 35.59 cfs @ 12.41 hrs, Volume= 10.895 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Link 9L: RP-3



Page 43

Summary for Link 10L: RP-4


Inflow Area = 24.300 ac, 65.00% Impervious, Inflow Depth > 3.42" for 10-Year event

Inflow = 29.51 cfs @ 12.13 hrs, Volume= 6.923 af

Primary = 29.51 cfs @ 12.13 hrs, Volume= 6.923 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Link 10L: RP-4



Page 44

Summary for Subcatchment 11S: Onsite 5


[49] Hint: Tc<2dt may require smaller dt

Runoff = 179.92 cfs @ 11.95 hrs, Volume= 9.077 af, Depth> 6.27"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Type II 24-hr 100-Year Rainfall=7.70"

	Area	(ac) C	N Des	cription		
*	17.	370 8	38 Apai	rtments, 6	5% imp, HS	SG C
	6.	079	35.0	0% Pervio	us Area	
	11.290 65.00% Impervious Area					
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
-	1.1	100	0.0200	1.46	(013)	Sheet Flow, Smooth surfaces n= 0.011 P2= 3.60"
_	3.9					Direct Entry, Pipe flow
	5.0	100	Total			

Subcatchment 11S: Onsite 5



Summary for Subcatchment 12S: EX OFF


[49] Hint: Tc<2dt may require smaller dt

Runoff = 71.78 cfs @ 11.95 hrs, Volume= 3.621 af, Depth> 6.27"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Type II 24-hr 100-Year Rainfall=7.70"

	Area	(ac) C	N Des	cription			
*	6.	930 8	38 Futu	re Multi-Fa	amily, 65%	imp, HSG C	
	2.	425	35.0	0% Pervio	us Area		_
	4.504 65.00% Impervious Area						
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description	
	1.0	100	0.0300	1.72		Sheet Flow, Sheet flow	
	4.0	700		0.00		Smooth surfaces n= 0.011 P2= 3.60"	
_	4.0	700		2.92		Direct Entry, Pipe flow	_
	5.0	800	Total				

Subcatchment 12S: EX OFF




Summary for Subcatchment 13S: Onsite 4

Runoff = 215.38 cfs @ 12.04 hrs, Volume= 14.333 af, Depth> 6.73"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Type II 24-hr 100-Year Rainfall=7.70"

_	Area	(ac) C	N Des	cription				
*	13.	.070	92 SINO	SINGLE FAMILY LOTS				
	12.	480 9	92 1/8 a	acre lots, 6	5% imp, H	SG D		
	25.	.550 9	92 Weig	ghted Aver	age			
	17.	438	68.2	5% Pervio	us Area			
	8.	112	31.7	5% Imperv	ious Area			
	Tc	Length	Slope	Velocity	Capacity	Description		
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)			
	1.1	100	0.0205	1.47		Sheet Flow,		
						Smooth surfaces n= 0.011 P2= 3.60"		
	12.0	1,830	0.0250	2.55		Shallow Concentrated Flow,		
_						Unpaved Kv= 16.1 fps		
	13.1	1.930	Total					

Subcatchment 13S: Onsite 4



Page 47


Summary for Subcatchment 15S: Onsite 2

Runoff = 51.36 cfs @ 11.98 hrs, Volume= 2.939 af, Depth> 7.10"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Type II 24-hr 100-Year Rainfall=7.70"

Area (ac) CN Description								
4.970 95 Urban commercial, 85% imp, HSG D								
-	0.	746	15.0	0% Pervio	us Area			
4.224 85.00% Impervious Area					ious Area			
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description		
-	1.1	100	0.0200	1.46		Sheet Flow,		
_	5.9	805	0.0200	2.28		Smooth surfaces n= 0.011 P2= 3.60" Shallow Concentrated Flow, Unpaved Kv= 16.1 fps		
	7.0	905	Total					

Subcatchment 15S: Onsite 2




Summary for Subcatchment 16S: Onsite 3

Runoff = 106.44 cfs @ 11.99 hrs, Volume= 6.042 af, Depth> 6.74"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Type II 24-hr 100-Year Rainfall=7.70"

Area	(ac) C	N Desc	cription				
10.	760 9	92 1/8 acre lots, 65% imp, HSG D					
3.	766	35.00% Pervious Area					
6.994 65.00% Impervious Area							
Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description		
1.1	100	0.0200	1.46		Sheet Flow,		
6.8	1,045	0.0250	2.55		Smooth surfaces n= 0.011 P2= 3.60" Shallow Concentrated Flow, Unpaved Kv= 16.1 fps		
7 0	1 1/15	Total					

Subcatchment 16S: Onsite 3




Summary for Subcatchment 17S: Onsite 1

Runoff = 5.58 cfs @ 11.98 hrs, Volume= 0.319 af, Depth> 7.10"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Type II 24-hr 100-Year Rainfall=7.70"

	Area						
	0.	540 9	5 Urba	ın commer	cial, 85% ii	mp, HSG D	_
	0.	0.081		0% Pervio	us Area		
0.459 85.00% Impervious Area					ious Area		
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description	
-	1.1	100	0.0200	1.46		Sheet Flow,	
	5.9	805	0.0200	2.28		Smooth surfaces n= 0.011 P2= 3.60" Shallow Concentrated Flow, Unpaved Kv= 16.1 fps	
	7.0	905	Total				

Subcatchment 17S: Onsite 1



Printed 11/18/2022 Page 50

Summary for Pond 12P: EWDB #1

Inflow Area = 24.300 ac, 65.00% Impervious, Inflow Depth > 6.27" for 100-Year event

Inflow 251.70 cfs @ 11.95 hrs, Volume= 12.698 af

39.74 cfs @ 12.15 hrs, Volume= Outflow 11.521 af, Atten= 84%, Lag= 12.1 min

Primary 39.74 cfs @ 12.15 hrs, Volume= 11.521 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Peak Elev= 998.58' @ 12.15 hrs Surf.Area= 82,303 sf Storage= 268,404 cf

Plug-Flow detention time= 138.2 min calculated for 11.521 af (91% of inflow)

Center-of-Mass det. time= 90.1 min (868.6 - 778.6)

Volume	Inve	rt Avail.Sto	rage S	Storage	Description		
#1	995.00	0' 389,7	53 cf C	Custom	n Stage Data (P	rismatic)Listed below (Recalc)	
Elevation	on S	Surf.Area	Inc.Store		Cum.Store		
(fee	et)	(sq-ft)	(cubic-1	feet)	(cubic-feet)		
995.0	00	67,904		0	0		
996.0	00	71,853	69	,879	69,879		
997.0	00	75,863	73	,858	143,737		
998.0	00	79,925	77	,894	221,631		
999.0	00	84,048	81	,987	303,617		
1,000.0	00	88,224	86	,136	389,753		
Device	Routing	Invert	Outlet	Device	es		
#1	Primary	994.50'	30.0"	Round	d Culvert		
			L= 80.	0' RC	P, sq.cut end pre	ojecting, Ke= 0.500	
			Inlet /	Outlet I	nvert= 994.50' /	993.90' S= 0.0075 '/' Cc= 0.900	
			n= 0.0	12 Co	ncrete pipe, finis	shed, Flow Area= 4.91 sf	
#2	Device 1	994.80'				Crested Vee/Trap Weir	
			Cv= 2.69 (C= 3.36)				
#3	Device 1	995.50'	5.0' long x 3.00' rise Sharp-Crested Rectangular Weir				
					ction(s) 3.0' Cr		
#4	Device 1	998.50'	8.50' 60.0" x 60.0" Horiz. Orifice/Grate C= 0.600			Grate C= 0.600	
			Limite	d to we	ir flow at low hea	ads	

Primary OutFlow Max=39.73 cfs @ 12.15 hrs HW=998.58' (Free Discharge)


-1=Culvert (Inlet Controls 39.73 cfs @ 8.09 fps)

²⁼Sharp-Crested Vee/Trap Weir (Passes < 0.79 cfs potential flow)


⁻³⁼Sharp-Crested Rectangular Weir(Passes < 87.02 cfs potential flow)

⁻⁴⁼Orifice/Grate (Passes < 1.37 cfs potential flow)

Pond 12P: EWDB #1




Pond 12P: EWDB #1



Page 52

Pond 12P: EWDB #1



Prepared by Schlagel

HydroCAD® 10.00-13 s/n 08303 © 2014 HydroCAD Software Solutions LLC

Printed 11/18/2022 Page 53

Summary for Pond 13P: EWDB #2

Inflow Area = 10.760 ac, 65.00% Impervious, Inflow Depth > 6.74" for 100-Year event

Inflow 106.44 cfs @ 11.99 hrs, Volume= 6.042 af

17.40 cfs @ 12.24 hrs, Volume= Outflow 5.266 af, Atten= 84%, Lag= 14.9 min

Primary 17.40 cfs @ 12.24 hrs, Volume= 5.266 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Peak Elev= 996.93' @ 12.24 hrs Surf.Area= 34,620 sf Storage= 137,147 cf

Plug-Flow detention time= 181.3 min calculated for 5.255 af (87% of inflow)

Center-of-Mass det. time= 121.1 min (888.5 - 767.5)

Volume	Inve	rt Avail.Sto	rage Storage	Description		
#1	992.0	0' 175,79	99 cf Custom	Stage Data (P	rismatic)Listed below (Recalc)	
Elevation	n (Surf.Area	Inc.Store	Cum.Store		
(fee		(sq-ft)	(cubic-feet)	(cubic-feet)		
992.0	00	21,391	0	0		
994.0	00	26,438	47,829	47,829		
996.0	00	31,892	58,330	106,159		
998.0	00	37,748	69,640	175,799		
Device	Routing	Invert	Outlet Device	es		
#1	Primary	992.00'	18.0" Round	d Culvert		
	•		L= 50.0' RC	P, sq.cut end pro	ojecting, Ke= 0.500	
			Inlet / Outlet I	nvert= 992.00' /	991.00' S= 0.0200 '/' Cc= 0.900	
			n= 0.012 Co	ncrete pipe, finis	hed, Flow Area= 1.77 sf	
#2	Device 1	992.00'	•	•	Crested Vee/Trap Weir	
			Cv= 2.69 (C= 3.36)			
#3	Device 1	996.00'			Grate C= 0.600	
			Limited to we	ir flow at low hea	ads	


Primary OutFlow Max=17.40 cfs @ 12.24 hrs HW=996.93' (Free Discharge)

-1=Culvert (Inlet Controls 17.40 cfs @ 9.84 fps)


-2=Sharp-Crested Vee/Trap Weir(Passes < 20.95 cfs potential flow)

-3=Orifice/Grate (Passes < 70.40 cfs potential flow)

Pond 13P: EWDB #2




Pond 13P: EWDB #2



Page 55

Pond 13P: EWDB #2



Volume

HydroCAD® 10.00-13 s/n 08303 © 2014 HydroCAD Software Solutions LLC

Printed 11/18/2022 Page 56

Summary for Pond 14P: EWDB #3

[79] Warning: Submerged Pond 13P Primary device # 1 OUTLET by 0.11'

36.310 ac, 41.60% Impervious, Inflow Depth > 6.48" for 100-Year event Inflow Area =

231.78 cfs @ 12.04 hrs, Volume= Inflow 19.599 af

Outflow 87.51 cfs @ 12.26 hrs, Volume= 17.711 af, Atten= 62%, Lag= 12.9 min

Primary 87.51 cfs @ 12.26 hrs, Volume= 17.711 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Peak Elev= 991.11' @ 12.26 hrs Surf.Area= 56,253 sf Storage= 303,996 cf

Plug-Flow detention time= 134.5 min calculated for 17.674 af (90% of inflow)

Avail Storage Description

Center-of-Mass det. time= 86.0 min (889.0 - 803.0)

Invert

VOIUITIE	IIIVE	it Avaii.Sto	rage Storage	Description			
#1	984.00	0' 355,62	25 cf Custom	Stage Data (Pr	rismatic)Listed below (Recalc)		
Elevation (feet)		Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)			
984.0	00	30,844	0	0			
986.0	00	36,957	67,801	67,801			
988.0	00	43,835	80,792	148,593			
990.0	00	51,620	95,455	244,048			
992.0	00	59,957	111,577	355,625			
Device	Routing	Invert	Outlet Devices	S			
#1	Primary	983.00'	36.0" Round	Culvert			
	•		L= 50.0' RCP, sq.cut end projecting, Ke= 0.500				
			Inlet / Outlet Ir	nvert= 983.00' /	982.00' S= 0.0200 '/' Cc= 0.900		
				1 1 1	hed, Flow Area= 7.07 sf		
#2	Device 1	984.00'	00' 20.0 deg x 6.00' rise Sharp-Crested Vee/Trap Weir		Crested Vee/Trap Weir		
			Cv= 2.69 (C= 3.36)				
#3 Device 1 990.00'		72.0" x 72.0" Horiz. Orifice/Grate C= 0.600					
			Limited to wei	r flow at low hea	ads		

Primary OutFlow Max=87.48 cfs @ 12.26 hrs HW=991.11' (Free Discharge)


-1=Culvert (Inlet Controls 87.48 cfs @ 12.38 fps)

2=Sharp-Crested Vee/Trap Weir (Passes < 54.97 cfs potential flow)


-3=Orifice/Grate (Passes < 91.36 cfs potential flow)

Page 57

Pond 14P: EWDB #3




Pond 14P: EWDB #3



Page 58

Pond 14P: EWDB #3



Printed 11/18/2022

HydroCAD® 10.00-13 s/n 08303 © 2014 HydroCAD Software Solutions LLC

Page 59

Summary for Pond 15P: EDDB #1

Inflow Area = 4.970 ac, 85.00% Impervious, Inflow Depth > 7.10" for 100-Year event

Inflow 51.36 cfs @ 11.98 hrs, Volume= 2.939 af

34.89 cfs @ 12.05 hrs, Volume= Outflow 2.430 af, Atten= 32%, Lag= 4.6 min

Primary 34.89 cfs @ 12.05 hrs, Volume= 2.430 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Peak Elev= 1,008.96' @ 12.05 hrs Surf.Area= 19,635 sf Storage= 44,809 cf

Plug-Flow detention time= 125.3 min calculated for 2.425 af (83% of inflow)

Center-of-Mass det. time= 52.2 min (806.5 - 754.3)

Volume	Inver	t Avail.Sto	rage Storage	Description				
#1	1,004.00)' 68,10	00 cf Custom	Stage Data (Pi	rismatic)Listed below (Rec	alc)		
	_			0 01				
Elevatio		Surf.Area	Inc.Store	Cum.Store				
(fee	i)	(sq-ft)	(cubic-feet)	(cubic-feet)				
1,004.0	0	50	0	0				
1,006.0	0	6,872	6,922	6,922				
1,008.0	0	14,603	21,475	28,397				
1,010.0	0	25,100	39,703	68,100				
Device	Routing	Invert	Outlet Device	S				
#1	Primary	1,002.00'	24.0" Round	Culvert				
	,	•	L= 50.0' RCF	, sq.cut end pro	ojecting, Ke= 0.500			
					'/ 1,001.50' S= 0.0100 '/'	Cc = 0.900		
			n= 0.012 Concrete pipe, finished, Flow Area= 3.14 sf					
#2	Device 1	1,002.25'		" ORIFICE C=				
#3	Device 1	1,007.50'		/Orifice, Cv= 2.	.62 (C= 3.28)			
		,		,007.50 1,009.				
			Width (feet) 6					
#4	Device 2	1,002.50'	6.0" Round (
,, .		.,002.00			neadwall, Ke= 0.500			
						Cc = 0.900		
			Inlet / Outlet Invert= 1,002.50' / 1,002.25' S= 0.0083 '/' Cc= 0.900					
#5	Device 2	1 005 00'						
,, 0	_ J L	.,000.00						
· · · · · · · · · · · · · · · · · · ·								
,, 0	231100 1	1,010.00						
#5 #6	Device 2 Device 1	1,005.00' 1,010.00'	n= 0.010 PVC, smooth interior, Flow Area= 0.20 sf 1.0" Vert. 15" RISER X 7.00 columns X 9 rows with 4.0" cc spacing C= 0.600 72.0" x 72.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads					

Primary OutFlow Max=34.72 cfs @ 12.05 hrs HW=1,008.95' (Free Discharge)

-1=Culvert (Passes 34.72 cfs of 36.91 cfs potential flow)

-2=2.0" ORIFICE (Orifice Controls 0.27 cfs @ 12.39 fps)

-4=6" PVC (Passes < 2.30 cfs potential flow)

5=15" RISER (Passes < 2.62 cfs potential flow)


-3=Custom Weir/Orifice (Weir Controls 34.45 cfs @ 3.95 fps)

-6=Orifice/Grate (Controls 0.00 cfs)


Page 60

HydroCAD® 10.00-13 s/n 08303 © 2014 HydroCAD Software Solutions LLC

Pond 15P: EDDB #1




Pond 15P: EDDB #1



Page 61

Pond 15P: EDDB #1



Page 62

Summary for Link 7L: RP-1


Inflow Area = 5.510 ac, 85.00% Impervious, Inflow Depth > 5.99" for 100-Year event

Inflow = 38.85 cfs @ 12.04 hrs, Volume= 2.750 af

Primary = 38.85 cfs @ 12.04 hrs, Volume= 2.750 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Link 7L: RP-1



Page 63

Summary for Link 9L: RP-3


Inflow Area = 36.310 ac, 41.60% Impervious, Inflow Depth > 5.85" for 100-Year event

Inflow = 87.51 cfs @ 12.26 hrs, Volume= 17.711 af

Primary = 87.51 cfs @ 12.26 hrs, Volume= 17.711 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Link 9L: RP-3



Page 64

Summary for Link 10L: RP-4


Inflow Area = 24.300 ac, 65.00% Impervious, Inflow Depth > 5.69" for 100-Year event

Inflow = 39.74 cfs @ 12.15 hrs, Volume= 11.521 af

Primary = 39.74 cfs @ 12.15 hrs, Volume= 11.521 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Link 10L: RP-4



Page 65

Summary for Subcatchment 11S: Onsite 5


[49] Hint: Tc<2dt may require smaller dt

Runoff = 15.22 cfs @ 11.96 hrs, Volume= 0.707 af, Depth> 0.49"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Type II 24-hr WQv Rainfall=1.37"

	Area	(ac) C	N Des	cription							
*	17.	370 8	38 Apai	spartments, 65% imp, HSG C							
	6.	079	35.0	0% Pervio	us Area						
	11.	290	65.0	0% Imperv	∕ious Area						
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description					
-	1.1	100	0.0200	1.46	(013)	Sheet Flow, Smooth surfaces n= 0.011 P2= 3.60"					
_	3.9					Direct Entry, Pipe flow					
	5.0	100	Total								

Subcatchment 11S: Onsite 5



Page 66

Summary for Subcatchment 12S: EX OFF


[49] Hint: Tc<2dt may require smaller dt

Runoff = 6.07 cfs @ 11.96 hrs, Volume= 0.282 af, Depth> 0.49"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Type II 24-hr WQv Rainfall=1.37"

	Area	(ac) C	N Des	Description						
*	6.	930 8	38 Futu	re Multi-Fa	amily, 65%	imp, HSG C				
	2.	425	35.0	0% Pervio	us Area					
	4.	504	65.0	0% Imper	∕ious Area					
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description				
	1.0	100	0.0300	1.72		Sheet Flow, Sheet flow				
	4.0	700		0.00		Smooth surfaces n= 0.011 P2= 3.60"				
_	4.0	700		2.92		Direct Entry, Pipe flow	_			
	5.0	800	Total							

Subcatchment 12S: EX OFF




Summary for Subcatchment 13S: Onsite 4

Runoff = 24.24 cfs @ 12.05 hrs, Volume= 1.470 af, Depth> 0.69"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Type II 24-hr WQv Rainfall=1.37"

_	Area	(ac) C	N Des	cription			
*	13.	.070	92 SINO	GLE FAMI	LY LOTS		
	12.	480	92 1/8 a	acre lots, 6	55% imp, H	SG D	
	25.	.550	92 Weig	ghted Aver	age		
	17.	438	68.2	5% Pervio	us Area		
8.112 31.75% Impervious Area							
	Tc	Length	Slope	Velocity	Capacity	Description	
_	(min)	(feet)	(ft/ft)	(ft/sec)	(cfs)		_
	1.1	100	0.0205	1.47		Sheet Flow,	
						Smooth surfaces n= 0.011 P2= 3.60"	
	12.0	1,830	0.0250	2.55		Shallow Concentrated Flow,	
_						Unpaved Kv= 16.1 fps	
	13.1	1.930	Total				

Subcatchment 13S: Onsite 4




Summary for Subcatchment 15S: Onsite 2

Runoff = 7.31 cfs @ 11.98 hrs, Volume= 0.369 af, Depth> 0.89"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Type II 24-hr WQv Rainfall=1.37"

Area	(ac) C	N Desc	cription					
4.970 95 Urban commercial, 85% imp, HSG D								
0.	746	15.0	0% Pervio	us Area				
4.	224	85.0	0% Imperv	ious Area				
Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description			
1.1	100	0.0200	1.46		Sheet Flow,			
5.9	805	0.0200	2.28		Smooth surfaces n= 0.011 P2= 3.60" Shallow Concentrated Flow, Unpaved Kv= 16.1 fps			
7.0	905	Total						

Subcatchment 15S: Onsite 2



Page 69


Summary for Subcatchment 16S: Onsite 3

Runoff = 12.23 cfs @ 11.99 hrs, Volume= 0.620 af, Depth> 0.69"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Type II 24-hr WQv Rainfall=1.37"

	Area	(ac) C	N Desc	cription			
_	10.	760 9)2 1/8 a	acre lots, 6	5% imp, H	SG D	
	3.	766	35.0	0% Pervio	us Area		
	6.	994	65.0	0% Imperv	ious Area		
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description	
	1.1	100	0.0200	1.46		Sheet Flow,	
	6.8	1,045	0.0250	2.55		Smooth surfaces n= 0.011 P2= 3.60" Shallow Concentrated Flow, Unpaved Kv= 16.1 fps	
	7.9	1 145	Total				

Subcatchment 16S: Onsite 3



Page 70


Summary for Subcatchment 17S: Onsite 1

Runoff = 0.79 cfs @ 11.98 hrs, Volume= 0.040 af, Depth> 0.89"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Type II 24-hr WQv Rainfall=1.37"

	Area	(ac) C	N Desc	cription			
-	0.	540 9	5 Urba	ın commer	cial, 85% ii	mp, HSG D	
•	0.	081	15.0	0% Pervio	us Area		
	0.	459	85.0	0% Imper	∕ious Area		
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description	
	1.1	100	0.0200	1.46		Sheet Flow,	
	5.9	805	0.0200	2.28		Smooth surfaces n= 0.011 P2= 3.60" Shallow Concentrated Flow, Unpaved Kv= 16.1 fps	
	7.0	905	Total				

Subcatchment 17S: Onsite 1



Page 71

Summary for Pond 12P: EWDB #1

Inflow Area = 24.300 ac, 65.00% Impervious, Inflow Depth > 0.49" for WQv event

Inflow 21.30 cfs @ 11.96 hrs, Volume= 0.990 af

0.24 cfs @ 24.00 hrs, Volume= Outflow 0.180 af, Atten= 99%, Lag= 722.2 min

Primary 0.24 cfs @ 24.00 hrs, Volume= 0.180 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Peak Elev= 995.51' @ 24.00 hrs Surf.Area= 69,925 sf Storage= 35,261 cf

Plug-Flow detention time= 423.3 min calculated for 0.180 af (18% of inflow)

Center-of-Mass det. time= 278.2 min (1,129.3 - 851.1)

Volume	Inve	rt Avail.Sto	rage S	torage	Description	
#1	995.00)' 389,75	3 cf C	ustom	Stage Data (P	rismatic)Listed below (Recalc)
Elevatio	n (Surf.Area	Inc.St	toro	Cum.Store	
(fee	τ)	(sq-ft)	(cubic-fe	eet)	(cubic-feet)	
995.0	0	67,904		0	0	
996.0	0	71,853	69,	879	69,879	
997.0	0	75,863	73,	858	143,737	
998.0	0	79,925	77,	894	221,631	
999.0	0	84,048	81,	987	303,617	
1,000.0	0	88,224	86,	136	389,753	
Device	Routing	Invert	Outlet	Device	S	
#1	Primary	994.50'	30.0"	Round	Culvert	
		001.00				ojecting, Ke= 0.500
						993.90' S= 0.0075 '/' Cc= 0.900
110	D	004.001				hed, Flow Area= 4.91 sf
#2	Device 1	994.80'				Crested Vee/Trap Weir
			Cv= 2.0	`	,	
#3	Device 1	995.50'				Crested Rectangular Weir
			2 End (Contrac	ction(s) 3.0' Cr	est Height

60.0" x 60.0" Horiz. Orifice/Grate C= 0.600

Limited to weir flow at low heads

Primary OutFlow Max=0.22 cfs @ 24.00 hrs HW=995.51' (Free Discharge)

-1=Culvert (Passes 0.22 cfs of 5.86 cfs potential flow)

998.50'

#4


Device 1

²⁼Sharp-Crested Vee/Trap Weir (Orifice Controls 0.20 cfs @ 2.33 fps)


⁻³⁼Sharp-Crested Rectangular Weir (Weir Controls 0.02 cfs @ 0.35 fps)

⁻⁴⁼Orifice/Grate (Controls 0.00 cfs)

Pond 12P: EWDB #1




Pond 12P: EWDB #1



Page 73

Pond 12P: EWDB #1



HydroCAD® 10.00-13 s/n 08303 © 2014 HydroCAD Software Solutions LLC

Page 74

Summary for Pond 13P: EWDB #2

Inflow Area = 10.760 ac, 65.00% Impervious, Inflow Depth > 0.69" for WQv event

Inflow 12.23 cfs @ 11.99 hrs, Volume= 0.620 af

0.28 cfs @ 15.95 hrs, Volume= Outflow 0.248 af, Atten= 98%, Lag= 237.5 min

Primary 0.28 cfs @ 15.95 hrs, Volume= 0.248 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Peak Elev= 992.81' @ 15.95 hrs Surf.Area= 23,444 sf Storage= 18,239 cf

Plug-Flow detention time= 373.5 min calculated for 0.248 af (40% of inflow)

Center-of-Mass det. time= 249.2 min (1,079.3 - 830.1)

Volume	Inve	rt Avail.Sto	rage Storag	e Description			
#1	992.00	0' 175,79	99 cf Custo	m Stage Data (P	rismatic)Listed below (Recalc)		
Elevation (fee	et)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)			
992.0	-	21,391	0	0			
994.0	-	26,438	47,829	47,829			
996.0	00	31,892	58,330	106,159			
998.0	00	37,748	69,640	175,799			
Device	Routing	Invert	Outlet Device	es			
#1	Primary	992.00'	18.0" Roun	nd Culvert			
,, .	, initially	002.00	L= 50.0' RCP, sq.cut end projecting, Ke= 0.500 Inlet / Outlet Invert= 992.00' / 991.00' S= 0.0200 '/' Cc= 0.90 n= 0.012 Concrete pipe, finished, Flow Area= 1.77 sf				
#2	Device 1	992.00'	20.0 deg x 4.00' rise Sharp-Crested Vee/Trap Weir Cv= 2.69 (C= 3.36)				
#3 Device 1 996.00'		72.0" x 72.0	72.0" x 72.0" Horiz. Orifice/Grate C= 0.600				

Limited to weir flow at low heads

Primary OutFlow Max=0.28 cfs @ 15.95 hrs HW=992.81' (Free Discharge)


-1=Culvert (Passes 0.28 cfs of 3.01 cfs potential flow)

-2=Sharp-Crested Vee/Trap Weir (Weir Controls 0.28 cfs @ 2.43 fps)


-3=Orifice/Grate (Controls 0.00 cfs)

Page 75

Pond 13P: EWDB #2




Pond 13P: EWDB #2



Page 76

Pond 13P: EWDB #2



Page 77

Summary for Pond 14P: EWDB #3

Inflow Area = 36.310 ac, 41.60% Impervious, Inflow Depth > 0.57" for WQv event

Inflow = 24.32 cfs @ 12.05 hrs, Volume= 1.718 af

Outflow = 0.95 cfs @ 16.05 hrs, Volume= 0.831 af, Atten= 96%, Lag= 239.9 min

Primary = 0.95 cfs @ 16.05 hrs, Volume= 0.831 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Peak Elev= 985.32' @ 16.05 hrs Surf.Area= 34,885 sf Storage= 43,446 cf

Plug-Flow detention time= 363.9 min calculated for 0.829 af (48% of inflow)

Center-of-Mass det. time= 213.1 min (1,082.5 - 869.4)

Volume	Inve	rt Avail.Sto	rage Storage	Description				
#1	984.0	0' 355,62	25 cf Custon	n Stage Data (Pris	smatic)Listed below (Recalc)			
Elevatio (fee 984.0 986.0 988.0 990.0 992.0	et) 00 00 00 00	Surf.Area (sq-ft) 30,844 36,957 43,835 51,620 59,957	Inc.Store (cubic-feet) 0 67,801 80,792 95,455 111,577	Cum.Store (cubic-feet) 0 67,801 148,593 244,048 355,625				
Device	Routing	Invert	Outlet Device	es				
#1	Primary	983.00'	36.0" Round Culvert L= 50.0' RCP, sq.cut end projecting, Ke= 0.500 Inlet / Outlet Invert= 983.00' / 982.00' S= 0.0200 '/' Cc= 0.900 n= 0.012 Concrete pipe, finished, Flow Area= 7.07 sf					
#2								
#3 Device 1 990.00'			72.0" x 72.0" Horiz. Orifice/Grate C= 0.600					

Limited to weir flow at low heads

Primary OutFlow Max=0.95 cfs @ 16.05 hrs HW=985.32' (Free Discharge)


-1=Culvert (Passes 0.95 cfs of 30.46 cfs potential flow)

—2=Sharp-Crested Vee/Trap Weir (Weir Controls 0.95 cfs @ 3.09 fps)


-3=Orifice/Grate (Controls 0.00 cfs)

Page 78

Pond 14P: EWDB #3




Pond 14P: EWDB #3



Page 79

Pond 14P: EWDB #3



Printed 11/18/2022 Page 80

Summary for Pond 15P: EDDB #1

Inflow Area = 4.970 ac, 85.00% Impervious, Inflow Depth > 0.89" for WQv event

Inflow = 7.31 cfs @ 11.98 hrs, Volume= 0.369 af

Outflow = 0.21 cfs @ 14.50 hrs, Volume= 0.238 af, Atten= 97%, Lag= 150.8 min

Primary = 0.21 cfs @ 14.50 hrs, Volume= 0.238 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Peak Elev= 1,006.28' @ 14.50 hrs Surf.Area= 7,964 sf Storage= 9,017 cf

Plug-Flow detention time= 306.0 min calculated for 0.238 af (65% of inflow)

Center-of-Mass det. time= 202.1 min (1,010.0 - 807.9)

Volume	Inve	rt Avail.Sto	rage	Storage	Description		
#1	1,004.0	0' 68,10	00 cf	Custom	Stage Data (Pr	rismatic)Listed below (Red	alc)
	,			0.1	0 0		
Elevatio		Surf.Area		:Store	Cum.Store		
(fee	t)	(sq-ft)	(cubi	c-feet)	(cubic-feet)		
1,004.0	0	50		0	0		
1,006.0	0	6,872		6,922	6,922		
1,008.0	0	14,603	2	21,475	28,397		
1,010.0		25,100		39,703	68,100		
,		.,		,	, , , , , ,		
Device	Routing	Invert	Outl	et Devices	S		
#1	Primary	1,002.00'	24.0	" Round	Culvert		
	,	,	L= 5	0.0' RCF	P. sa.cut end pro	ojecting, Ke= 0.500	
						'/ 1,001.50' S= 0.0100 '/'	Cc = 0.900
					•	hed, Flow Area= 3.14 sf	
#2	Device 1	1 002 25'			"ORIFICE C=		
#3	· · · · · · · · · · · · · · · · · · ·						
"0	BOVICE I	1,007.00			,007.50 1,009.5	•	
				th (feet) 6	,	00	
#4	Device 2	1,002.50'		Round 6			
#4	Device 2	1,002.50				neadwall, Ke= 0.500	
							Co= 0.000
						'/ 1,002.25' S= 0.0083 '/'	CC- 0.900
		4 005 001	n= 0	.010 PVC	, sinooth interio	or, Flow Area= 0.20 sf	

1,005.00' **1.0" Vert. 15" RISER X 7.00 columns**

Limited to weir flow at low heads

X 9 rows with 4.0" cc spacing C= 0.600

72.0" x 72.0" Horiz. Orifice/Grate C= 0.600

Primary OutFlow Max=0.21 cfs @ 14.50 hrs HW=1,006.28' (Free Discharge)

1=Culvert (Passes 0.21 cfs of 27.41 cfs potential flow)

-2=2.0" ORIFICE (Orifice Controls 0.21 cfs @ 9.57 fps)

-4=6" PVC (Passes < 1.74 cfs potential flow)

-5=15" RISER (Passes < 0.61 cfs potential flow)

-3=Custom Weir/Orifice (Controls 0.00 cfs)

1,010.00'

-6=Orifice/Grate (Controls 0.00 cfs)

Device 2


Device 1

#5


#6

Page 81

Pond 15P: EDDB #1




Pond 15P: EDDB #1



Page 82

Pond 15P: EDDB #1



Page 83

Summary for Link 7L: RP-1


Inflow Area = 5.510 ac, 85.00% Impervious, Inflow Depth > 0.61" for WQv event

Inflow = 0.99 cfs @ 11.98 hrs, Volume= 0.279 af

Primary = 0.99 cfs @ 11.98 hrs, Volume= 0.279 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Link 7L: RP-1



Page 84

Summary for Link 9L: RP-3


Inflow Area = 36.310 ac, 41.60% Impervious, Inflow Depth > 0.27" for WQv event

Inflow = 0.95 cfs @ 16.05 hrs, Volume= 0.831 af

Primary = 0.95 cfs @ 16.05 hrs, Volume= 0.831 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Link 9L: RP-3



Page 85

Summary for Link 10L: RP-4


Inflow Area = 24.300 ac, 65.00% Impervious, Inflow Depth > 0.09" for WQv event


Inflow = 0.24 cfs @ 24.00 hrs, Volume= 0.180 af

Primary = 0.24 cfs @ 24.00 hrs, Volume= 0.180 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Link 10L: RP-4





Printed 11/18/2022 Page 2

Summary for Subcatchment 11S: Onsite 5


[49] Hint: Tc<2dt may require smaller dt

Runoff = 179.92 cfs @ 11.95 hrs, Volume= 9.077 af, Depth> 6.27"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Type II 24-hr 100-Year Rainfall=7.70"

	Area	(ac) C	N Des	cription						
*	17.	.370 8	8 Apartments, 65% imp, HSG C							
6.079 35.00% Pervious Area										
	11.	290	65.0	0% Imperv	∕ious Area					
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description				
	1.1	100	0.0200	1.46		Sheet Flow,				
						Smooth surfaces n= 0.011 P2= 3.60"				
_	3.9					Direct Entry, Pipe flow				
	5.0	100	Total							

Subcatchment 11S: Onsite 5



Printed 11/18/2022 Page 3

Summary for Subcatchment 12S: EX OFF


[49] Hint: Tc<2dt may require smaller dt

Runoff = 71.78 cfs @ 11.95 hrs, Volume= 3.621 af, Depth> 6.27"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs Type II 24-hr 100-Year Rainfall=7.70"

	Area	(ac) C	N Des	cription						
*	6.	930 8	8 Future Multi-Family, 65% imp, HSG C							
	2.	425	35.0	0% Pervio	us Area					
	4.	504	65.0	0% Imper	∕ious Area					
	Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description				
	1.0	100	0.0300	1.72		Sheet Flow, Sheet flow				
	4.0	700		0.00		Smooth surfaces n= 0.011 P2= 3.60"				
_	4.0	700		2.92		Direct Entry, Pipe flow	_			
	5.0	800	Total							

Subcatchment 12S: EX OFF



22-102-HYDRO-PRO CLOGGED

Prepared by Schlagel

HydroCAD® 10.00-13 s/n 08303 © 2014 HydroCAD Software Solutions LLC

Printed 11/18/2022 Page 4

Summary for Pond 12P: EWDB #1

Inflow Area = 24.300 ac, 65.00% Impervious, Inflow Depth > 6.27" for 100-Year event

Inflow = 251.70 cfs @ 11.95 hrs, Volume= 12.698 af

Outflow = 126.66 cfs @ 12.05 hrs, Volume= 10.269 af, Atten= 50%, Lag= 6.0 min

Primary = 126.66 cfs @ 12.05 hrs, Volume= 10.269 af

Routing by Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Peak Elev= 1,001.37' @ 12.05 hrs Surf.Area= 94,118 sf Storage= 245,493 cf

Plug-Flow detention time= 145.8 min calculated for 10.269 af (81% of inflow)

Center-of-Mass det. time= 68.5 min (847.1 - 778.6)

Volume	Inv	ert Avail.	Storage	Storage	Description			
#1	998.	58' 40	5,643 cf	Custom	Stage Data (Pi	rismatic)Listed below (Recalc)		
Elevatio		Surf.Area (sq-ft)		c.Store c-feet)	Cum.Store (cubic-feet)			
998.5	58	82,316		0	0			
999.0	00	84,048		34,936	34,936			
1,000.0	00	88,224	8	36,136	121,072			
1,001.0	00	92,459	(90,342	211,414			
1,002.0	00	97,000		94,730	306,143			
1,003.0	00	102,000		99,500	405,643			
Device	Routing	Inv	ert Outl	et Device	s			
#1	Primary	999.	70' Cus	O' Custom Weir/Orifice, Cv= 2.62 (C= 3.28)				
Elev. (feet) 999.70 1,002.70								
			Wid	Width (feet) 14.00 32.00				


Primary OutFlow Max=126.50 cfs @ 12.05 hrs HW=1,001.36' (Free Discharge) 1=Custom Weir/Orifice (Weir Controls 126.50 cfs @ 4.00 fps)

Printed 11/18/2022


Page 5

HydroCAD® 10.00-13 s/n 08303 © 2014 HydroCAD Software Solutions LLC

Pond 12P: EWDB #1



Pond 12P: EWDB #1




Printed 11/18/2022

Page 6

HydroCAD® 10.00-13 s/n 08303 © 2014 HydroCAD Software Solutions LLC

Pond 12P: EWDB #1



22-102-HYDRO-PRO CLOGGED

Prepared by Schlagel

HydroCAD® 10.00-13 s/n 08303 © 2014 HydroCAD Software Solutions LLC

Page 7

Summary for Link 10L: RP-4

Inflow Area = 24.300 ac, 65.00% Impervious, Inflow Depth > 5.07" for 100-Year event

Inflow = 126.66 cfs @ 12.05 hrs, Volume= 10.269 af

Primary = 126.66 cfs @ 12.05 hrs, Volume= 10.269 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-24.00 hrs, dt= 0.05 hrs

Link 10L: RP-4

