

DWG: F:\2021\04001-04500\021-04157-B\40-Design\AutoCAD\Final Plans\Sheets\GNVCAC_TTL01_B2104157.dwg
DATE: Dec 06, 2022 9:30am
USER: moore
C:\BTLK_B2104157
XREFS: C:\AERIAL_02104157

GENERAL NOTES:

- THE EXISTING UTILITY LOCATIONS SHOWN ON THE PLANS ARE APPROXIMATE AND MAY NOT INCLUDE ALL LINES PRESENT. THE CONTRACTOR SHALL BE RESPONSIBLE TO CALL "1-800-DIG-RITE", 1(800)344-7483, OR 811 AND COORDINATE FIELD LOCATION OF EXISTING UNDERGROUND UTILITIES PRIOR TO BEGINNING GRADING ACTIVITIES. !!STOP!! CALL BEFORE YOU DIG!
- THE CONTRACTOR SHALL NOT CHANGE OR DEViate FROM THE PLANS WITHOUT FIRST OBTAINING WRITTEN APPROVAL FROM THE OWNER AND ENGINEER.
- ALL WORK AND MATERIALS SHALL BE SUBJECT TO INSPECTION AND APPROVAL BY THE OWNER OR THE OWNER'S REPRESENTATIVE.
- ALL ESTIMATES OF QUANTITIES ARE FOR INFORMATION PURPOSES ONLY. CONTRACTOR AND SUBCONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING ALL QUANTITIES AND FOR BRINGING THE PROJECT TO THE LINES AND GRADES SHOWN HEREIN. CONTRACTOR SHALL PROVIDE ALL WORK AND MATERIALS REQUIRED TO COMPLETE THE WORK SHOWN IN THESE PLANS. IT IS THE CONTRACTOR'S SOLE RESPONSIBILITY TO DETERMINE EARTHWORK QUANTITIES AND TO ACCOUNT FOR HAUL IN OR HAUL OFF OF MATERIAL AS NECESSARY TO MEET THE LINES AND GRADES OF THE PLANS EVEN IF QUANTITY ESTIMATES ARE SHOWN WITHIN THESE DOCUMENTS. NO ADDITIONAL PAYMENTS WILL BE MADE FOR IMPORT OR EXPORT OF MATERIAL OR FOR ADJUSTMENTS TO QUANTITY ESTIMATES.
- ALL CONSTRUCTION SHALL CONFORM TO THE LATEST STANDARDS AND SPECIFICATIONS OF THE CITY OF LEE'S SUMMIT, EXCEPT WHERE SHOWN OTHERWISE. NOTIFY ENGINEER OF DISCREPANCIES.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL REQUIRED PERMITS, PAYING ALL FEES AND FOR OTHERWISE COMPLYING WITH ALL APPLICABLE REGULATIONS GOVERNING THE WORK.
- THE CONTRACTOR SHALL ADHERE TO THE PROVISIONS OF MISSOURI STATE LAW WHICH REQUIRES THAT ANY PERSON OR FIRM DOING EXCAVATION ON PUBLIC RIGHT-OF-WAY DO SO ONLY AFTER GIVING NOTICE TO, AND OBTAINING INFORMATION FROM UTILITY COMPANIES.
- PRIOR TO COMMENCEMENT OF WORK, THE CONTRACTOR SHALL NOTIFY ALL THOSE COMPANIES WHICH HAVE FACILITIES IN THE NEAR VICINITY OF THE CONSTRUCTION TO BE PERFORMED.
- THE CONTRACTOR SHALL PROTECT ALL MAJOR TREES SHOWN TO REMAIN FROM DAMAGE. NO TREE SHALL BE REMOVED WITHOUT PERMISSION OF THE OWNER, UNLESS SHOWN FOR REMOVAL ON THESE PLANS.
- CLEARING AND GRUBBING OPERATIONS AND DISPOSAL OF ALL DEBRIS THEREFROM SHALL BE PERFORMED BY THE CONTRACTOR IN STRICT ACCORDANCE WITH ALL LOCAL CODES AND ORDINANCES.
- ALL WASTE MATERIAL RESULTING FROM THE PROJECT SHALL BE DISPOSED OF OFF-SITE BY THE CONTRACTOR.
- ALL UTILITY EXTENSIONS AND CONSTRUCTION SHALL CONFORM TO THE STANDARDS AND SPECIFICATIONS OF THE APPLICABLE UTILITY COMPANIES.
- ALL MANHOLES, CATCH BASINS, UTILITY VALVES AND METER PITS ARE TO BE ADJUSTED OR REBUILT TO GRADE AS REQUIRED.
- ALL DISTURBED AREAS SHALL BE LANDSCAPED, SEEDED OR SODDED, AS SHOWN ON THE LANDSCAPE PLAN.
- HANDICAP PARKING STALLS SHALL BE SIGNED WITH CITY/ADA APPROVED SIGN AND CONSTRUCTED IN STRICT ACCORDANCE WITH CITY/ADA STANDARDS AND SHALL NOT EXCEED 2.00 PERCENT IN ANY DIRECTION. ACCESSIBLE SIDEWALKS HAVE A MAXIMUM GROSS SLOPE OF 2 PERCENT AND A MAXIMUM LONGITUDINAL SLOPE OF 5 PERCENT.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONTROL OF SURFACE EROSION DURING CONSTRUCTION AND UNTIL THE OWNER ACCEPTS THE WORK AS COMPLETE. EROSION CONTROL MEASURES INCLUDING, BUT NOT LIMITED TO, THE SILT FENCES AND GRAVEL FILTER BAGS SHOWN ON THE EROSION CONTROL PLAN SHALL BE IN PLACE FOR THE DURATION OF THE SITE IMPROVEMENTS.
- ALL HDPE PIPE SHALL BE ADS (N-12) OR APPROVED EQUAL, AND CONFORM TO AASHTO M294 SPECIFICATIONS. ALL PIPE LENGTHS ARE MEASURED FROM CENTER OF STRUCTURE TO CENTER OF STRUCTURE.
- IF PRECAST CONCRETE STORM SEWER STRUCTURES ARE TO BE USED ON THIS PROJECT, THE CONTRACTOR SHALL SUBMIT SHOP DRAWINGS AND HAVE THEM APPROVED BY THE ENGINEER PRIOR TO FABRICATION OF THE STRUCTURES. FAILURE TO DO SO SHALL BE CAUSE FOR REJECTION.
- EXISTING TOPSOIL SHALL BE STRIPPED TO A POINT WHERE ALL VEGETATION IS REMOVED.
- THE CONTRACTOR SHALL, BY HIS OWN INVESTIGATION, AND PRIOR TO COMMENCING WORK, SATISFY HIMSELF AS TO THE SURFACE AND SUBSURFACE CONDITIONS TO BE ENCOUNTERED.
- ALL WATER SERVICE LINES SHALL BE INSTALLED PER LEE'S SUMMIT WATER UTILITIES STANDARDS. ALL WATER LINES SHALL BE A MINIMUM OF 48 INCHES BELOW THE FINISHED GRADE ELEVATIONS SHOWN HEREIN.
- THE CONTRACTOR IS RESPONSIBLE FOR THE PROTECTION OF ALL BOUNDARY CORNERS AND SECTION CORNERS. ANY BOUNDARY CORNER AND/OR SECTION CORNER DISTURBED OR DAMAGED BY CONSTRUCTION ACTIVITIES SHALL BE RESET BY A LAND SURVEYOR LICENSED IN THE STATE OF MISSOURI, AT THE CONTRACTOR'S EXPENSE.
- NO FEDERALLY OWNED MAILBOX MAY BE DISTURBED. THE CONTRACTOR SHALL GIVE AT LEAST TWENTY-FOUR (24) HOURS ADVANCE NOTICE TO THE MANAGER OF DELIVERY AND COLLECTIONS. TAMPERING WITH FEDERAL MAIL FACILITIES MAY SUBJECT THE CONTRACTOR TO PROSECUTION BY THE FEDERAL GOVERNMENT.
- THE CONTOUR LINES, SPOT ELEVATIONS AND BUILDING FLOOR ELEVATIONS SHOWN ARE TO FINISH GRADE FOR SURFACE OF PAVEMENT, TOP OF SIDEWALKS AND CURBS, TOP OF FLOOR SLABS, ETC. REFER TO TYPICAL SECTIONS FOR PAVING, SLAB AND AGGREGATE BASE THICKNESS TO DEDUCT FOR GRADING LINE ELEVATIONS.
- THE CONTRACTOR SHALL FINISH GRADE SLOPES AS SHOWN NO STEEPER THAN 1 FOOT VERTICAL IN 3 FEET HORIZONTAL.
- THE CONTRACTOR SHALL GRADE LANDSCAPED AREAS TO PROVIDE POSITIVE DRAINAGE AWAY FROM BUILDING AND SIDEWALKS WHEN FINISH LANDSCAPE MATERIALS ARE IN PLACE.
- ALL EXTERIOR CONCRETE SHALL HAVE A MINIMUM 28-DAY COMPRESSIVE STRENGTH OF 4000 PSI AND BE AIR ENTRAINED. FLYASH IS NOT A SUITABLE REPLACEMENT FOR PORTLAND CEMENT.
- ALL ON-SITE WIRING AND CABLES SHALL BE PLACED UNDERGROUND.
- THE CONTRACTOR SHALL MAKE HIS OWN ASSUMPTIONS ON THE LOCATION AND CONSISTENCY OF ANY EXISTING ROCK LAYERS UNDERLYING THE PROJECT SITE. ALL ROCK EXCAVATION AND REMOVAL SHALL BE INCLUDED IN THE CONTRACTORS' BID.
- CONCRETE PAVEMENT JOINTS SHALL AT A MINIMUM BE CONSTRUCTED AS FOLLOWS (REFER TO HARDCAPE PLANS FOR SPECIFIC TREATMENT OF THESE AREAS):
 - LONGITUDINAL CONSTRUCTION JOINTS SPACED AT INTERVALS NOT GREATER THAN 12 FEET, TOOLED TO 1/3 THE SLAB THICKNESS AND OF THE BAR TYPE.
 - CONSTRUCTION JOINTS AT THE END OF EACH POUR AND WHEN PAVING OPERATIONS ARE SUSPENDED FOR 30 MINUTES OR MORE AND DOWELED WITH SMOOTH DOWELS.
 - TRANSVERSE JOINTS SPACED AT INTERVALS NOT GREATER THAN 15 FEET AND TOOLED TO 1/3 OF THE SLAB THICKNESS.
 - ISOLATION JOINTS PLACED WHERE THE PAVEMENT ABUTS THE BUILDING, DRAINAGE STRUCTURES AND OTHER FIXED STRUCTURES, CONSTRUCTED WITH A 3/4" NONEXTRUDING FILLER, CLOSED-CELL FOAM RUBBER OR A BITUMEN-TREATED FIBER-BOARD, AND WITH A THICKENED EDGE, INCREASED BY 20 PERCENT, TAPERED TO THE REGULAR THICKNESS IN 5 FEET.
 - ALL EXPANSION JOINTS SHALL BE FILLED AND SEALED WITH A PLASTIC JOINT SEALANT MATERIAL.
- CONTRACTOR TO FIELD VERIFY ELEVATIONS AND LOCATIONS OF EXISTING UTILITIES AND INFRASTRUCTURE PRIOR TO CONSTRUCTION. NOTIFY ENGINEER OF ANY DISCREPANCIES BETWEEN PLANS AND FIELD CONDITIONS.
- TELEPHONE AND COMMUNICATION SERVICE ROUTING AND CONDUITS NOT SHOWN ON PLANS. CONTRACTOR SHALL INSTALL NECESSARY CONDUIT PRIOR TO PAVEMENT INSTALLATION. CONTRACTOR SHALL COORDINATE ROUTING AND INSTALLATION SCOPE WITH SERVICE PROVIDER.
- BY ACCEPTING AND UTILIZING ANY ELECTRONIC FILE OF ANY DRAWING, REPORT OR DATA TRANSMITTED BY OLSSON, THE RECIPIENT AGREES FOR ITSELF, ITS SUCCESSORS, ASSIGNS, INSURERS AND ALL THOSE CLAIMING UNDER OR THROUGH IT, THAT BY USING ANY OF THE INFORMATION CONTAINED IN THE ELECTRONIC FILE, ALL USERS AGREE TO BE BOUND BY THE FOLLOWING TERMS. ALL OF THE INFORMATION CONTAINED IN THIS ELECTRONIC FILE IS THE WORK PRODUCT AND INSTRUMENT OF SERVICE OF OLSSON, WHO SHALL BE DEEMED THE AUTHOR, AND SHALL RETAIN ALL COMMON LAW, STATUTORY LAW AND OTHER RIGHTS, INCLUDING COPYRIGHTS, UNLESS THE SAME HAVE PREVIOUSLY BEEN TRANSFERRED IN WRITING TO THE RECIPIENT. THE INFORMATION CONTAINED IN THE ELECTRONIC FILE IS PROVIDED FOR THE CONVENIENCE OF THE RECIPIENT AND IS PROVIDED IN "AS IS" CONDITION. THE RECIPIENT IS AWARE THAT DIFFERENCES MAY EXIST BETWEEN THE ELECTRONIC FILES AND THE PRINTED HARD-COPY ORIGINAL SIGNED AND SEALED DRAWINGS OR REPORTS. IN THE EVENT OF A CONFLICT BETWEEN THE SIGNED AND SEALED ORIGINAL DOCUMENTS PREPARED BY OLSSON AND THE ELECTRONIC FILES TRANSFERRED HERewith, THE SIGNED AND SEALED ORIGINAL DOCUMENTS SHALL GOVERN. OLSSON SPECIFICALLY DISCLAIMS ALL WARRANTIES, EXPRESSED OR IMPLIED, INCLUDING WITHOUT LIMITATION, ANY WARRANTY OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE WITH RESPECT TO ELECTRONIC FILES. IT SHALL BE THE RECIPIENT'S RESPONSIBILITY TO CONFIRM THE ACCURACY OF THE INFORMATION CONTAINED IN THE ELECTRONIC FILE AND THAT IF ACCURATELY REFLECTS THE INFORMATION NEEDED BY THE RECIPIENT. THE RECIPIENT SHALL NOT RETRANSMIT THE ELECTRONIC FILE, OR ANY PORTION THEREOF, WITHOUT INCLUDING THIS DISCLAIMER AS PART OF ANY SUCH TRANSMISSION. IN ADDITION, THE RECIPIENT AGREES, TO THE FULLEST EXTENT PERMITTED BY LAW, TO INDEMNIFY AND HOLD HARMLESS OLSSON, ITS OFFICERS, DIRECTORS, EMPLOYEES AND SUBCONSULTANTS AGAINST ANY AND ALL DAMAGES, LIABILITIES, CLAIMS OR COSTS, INCLUDING REASONABLE ATTORNEY'S AND EXPERT WITNESS FEES AND DEFENSE COSTS, ARISING FROM ANY CHANGES MADE BY ANYONE OTHER THAN OLSSON OR FROM ANY REUSE OF THE ELECTRONIC FILES WITHOUT THE PRIOR WRITTEN CONSENT OF OLSSON.
- DESIGN PROFESSIONAL SHALL REVIEW SHOP DRAWINGS OR SAMPLES FOR GENERAL CONFORMANCE WITH THE DESIGN CONCEPTS ON THE PROJECT AND FOR COMPLIANCE WITH THE INFORMATION GIVEN IN THE CONTRACT DOCUMENTS, AND SHALL NOT EXTEND TO MEANS OR METHODS OF CONSTRUCTION. THE DESIGN PROFESSIONAL'S REVIEW SHALL NOT RELIEVE CONTRACTOR FROM RESPONSIBILITY FOR ANY VARIATION FROM THE REQUIREMENTS OF THE CONTRACT DOCUMENTS UNLESS CONTRACTOR HAS IN WRITING CALLED DESIGN PROFESSIONAL'S ATTENTION TO EACH SUCH VARIATION AT THE TIME OF SUBMISSION, AND DESIGN PROFESSIONAL HAS GIVEN WRITTEN APPROVAL OF EACH SUCH VARIATION BY SPECIFIC WRITTEN NOTATION THEREOF INCORPORATED INTO OR ACCOMPANYING THE SHOP DRAWING OR SAMPLE; NOR WILL ANY APPROVAL BY THE DESIGN PROFESSIONAL RELIEVE CONTRACTOR FROM RESPONSIBILITY FOR ERRORS OR OMISSIONS IN SHOP DRAWINGS WITH CONFORMANCE TO CONTRACT DOCUMENTS.

- BEFORE SUBMITTING EACH SHOP DRAWING OR SAMPLE, CONTRACTOR SHALL HAVE DETERMINED AND VERIFIED:
- ALL FIELD MEASUREMENTS, QUANTITIES, DIMENSIONS, SPECIFIED PERFORMANCE CRITERIA, INSTALLATION REQUIREMENTS, MATERIALS, CATALOG NUMBERS AND SIMILAR INFORMATION WITH RESPECT THERETO;
 - ALL MATERIALS WITH RESPECT TO INTENDED USE, FABRICATION, SHIPPING, HANDLING, STORAGE, ASSEMBLY AND INSTALLATION PERTAINING TO THE PERFORMANCE OF THE WORK;
 - ALL INFORMATION RELATIVE TO MEANS, METHODS, TECHNIQUES, SEQUENCES AND PROCEDURES OF CONSTRUCTION AND SAFETY PRECAUTIONS AND PROGRAMS INCIDENT THERETO;
 - CONTRACTOR SHALL ALSO HAVE REVIEWED AND COORDINATED EACH SHOP DRAWING OR SAMPLE WITH OTHER SHOP DRAWINGS AND SAMPLES, AND WITH THE REQUIREMENTS OF THE WORK AND THE CONTRACT DOCUMENTS.

ALL SUBMITTED SHOP DRAWINGS SHALL BEAR A STAMP OR SPECIFIC WRITTEN INDICATION AND SIGNATURE THAT CONTRACTOR HAS FULLY REVIEWED THE SUBMISSION AND CHECKED ALL DATA AND DETAILS. BY CONTRACTOR SIGNATURE, CONTRACTOR CERTIFIES SHOP DRAWING CONFORMANCE AND ACCURACY TO THE CONTRACT DOCUMENTS.

- ANY CONTRACTOR BIDDING ANY PORTION OF THIS WORK SHALL HAVE IN HIS OR HER POSSESSION A COMPLETE SET OF CONSTRUCTION DOCUMENTS AND BE FAMILIAR WITH ALL SCOPES OF WORK AND TRADES TO UNDERSTAND THEIR INTERACTIONS.
- CONTRACTOR TO PROVIDE A STRUCTURAL DESIGN FOR ALL STORM STRUCTURES WITH A ("L"+"H") AND ("W" + "H") GREATER THAN 20 FEET. "L" IS THE LENGTH OF THE BOX, "W" IS THE WIDTH OF THE BOX, AND "H" IS THE HEIGHT OF THE BOX. STRUCTURAL DESIGN SHOULD INCLUDE DETAILS AND CALCULATIONS SEALED BY A LICENSED ENGINEER. DESIGN SHALL BE SUBMITTED FOR REVIEW PRIOR TO ANY FABRICATION AND ORDERING OF PIPE PRODUCTS. IN THE EVEN THIS NOTE IS LESS STRINGENT THAN THE LOCAL JURISDICTION, THE MORE STRINGENT REQUIREMENTS SHOULD APPLY.

DEMOLITION NOTES

- CONTRACTOR TO PRESERVE ALL SURVEY CONTROL.
- CONTRACTOR TO COMPLETE DEMOLITION PER THE INTENT OF THESE PLANS.
- THE UNDERGROUND UTILITIES SHOWN HAVE BEEN LOCATED FROM FIELD SURVEY INFORMATION AND EXISTING DRAWINGS. THE ENGINEER MAKES NO GUARANTEES THAT THE UTILITIES SHOWN COMPRISE ALL SUCH UTILITIES IN THE AREA, EITHER IN SERVICE OR ABANDONED. THE ENGINEER HAS NOT PHYSICALLY LOCATED THE UNDERGROUND UTILITIES. THIS INCLUDES PRIVATE AND PUBLIC UTILITIES. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT MISSOURI ONE CALL AT 1-800-344-7483 IN ADVANCE OF ANY EXCAVATION TO COORDINATE UTILITY LOCATIONS.
- CONTRACTOR IS REQUIRED TO TAKE PRECAUTIONARY MEASURES TO PROTECT THE UTILITY LINES SHOWN AND ANY OTHER EXISTING LINES NOT OF RECORD OR SHOWN ON THESE PLANS.
- REMOVAL AND DISPOSAL OF BUSHES AND TREES SMALLER THAN 12" IN DIAMETER SHALL BE CONSIDERED SUBSIDIARY TO THE PRICE BID FOR CLEARING AND GRUBBING.
- ALL ITEMS REMOVED SHALL BE LEGALLY DISPOSED OFF SITE BY THE CONTRACTOR.
- DO NOT DISRUPT UTILITY SERVICE TO ADJACENT BUSINESSES OR RESIDENCES WITHOUT PRIOR WRITTEN APPROVAL BY THE ENGINEER.
- DO NOT DISRUPT TRAFFIC ON ADJACENT PUBLIC STREETS WITHOUT PRIOR WRITTEN APPROVAL BY THE CITY.
- ALL SIDEWALK AND PAVEMENT TO REMAIN SHALL BE PROTECTED IN PLACE INCLUDING PROTECTION FROM DAMAGE CAUSED BY REMOVAL OF ABUTTING PAVEMENT. CONTRACTOR SHALL SAW CUT WHERE NECESSARY.
- CONTRACTOR SHALL GIVE NOTICE TO ALL UTILITY COMPANIES REGARDING DISCONNECTION, DEMOLITION, AND REMOVAL OF SERVICE LINES. CAP ALL LINES BEFORE PROCEEDING WITH WORK ON THIS CONTRACT.
- CONTRACTOR SHALL COORDINATE WITH UTILITY COMPANY CONCERNING PORTIONS OF WORK WHICH MAY BE PERFORMED BY THE UTILITY COMPANIES WORK FORCE AND ANY FEES WHICH ARE TO BE PAID TO THE UTILITY COMPANY FOR THEIR SERVICES.
- CONTRACTOR SHALL PROTECT THE PUBLIC AT ALL TIME WITH FENCING, BARRICADES, ENCLOSURES, ETC. TO THE BEST PRACTICES AND AS APPROVED BY THE ENGINEER AND THE CITY.
- DAMAGE TO ALL EXISTING CONDITIONS TO REMAIN SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.
- DEMOLITION OF BUILDINGS SHALL INCLUDE THE BUILDING STRUCTURE, PAD, FOOTINGS, FOUNDATIONS, BASEMENT WALLS, BASEMENT FLOORS, TRUCK DOCKS, STEPS, DECKS, ALL ITEMS REMAINING IN BUILDING, ALL BUILDING UTILITY SERVICES, SIDEWALKS, AND BACKFILLING AND RESTORING REMAINING EXCAVATIONS, BASEMENTS AND TRENCHES PER SPECIFICATIONS.
- ALL LIGHT POLE DEMOLITION SHALL INCLUDE FIXTURES, BASES AND WIRING.
- ALL UTILITY DEMOLITION SHALL INCLUDE METERS, MANHOLES AND OTHER STRUCTURES ASSOCIATED WITH THE UTILITY SERVICE LINE.

PAVEMENT MARKING NOTES:

- PAVEMENT MARKING PAINT: LATEX, WATER-BASE EMULSION, READY-MIXED, COMPLYING WITH FS TT-P-1952 WITH DRYING TIME OF LESS THAN 45 MINUTES.
- DO NOT APPLY PAVEMENT MARKING PAINT UNTIL LAYOUT, COLORS AND PLACEMENT HAVE BEEN VERIFIED WITH THE ARCHITECT.
- ALLOW PAVING TO AGE FOR 24 HOURS BEFORE MARKING.
- SWEEP AND CLEAN SURFACE.
- APPLY PAINT WITH MECHANICAL EQUIPMENT TO PRODUCE MARKINGS WITH UNIFORM STRAIGHT EDGES. PROVIDE A MINIMUM WET FILM THICKNESS OF 15 MILS.
- THIS WORK SHALL CONSIST OF FURNISHING AND APPLYING PAINT ON PAVEMENT SURFACES, IN TRAFFIC LANES, PARKING BAYS, AREAS RESTRICTED TO HANDICAPPED PERSONS, CROSSWALKS, AND OTHER DETAIL PAVEMENT MARKINGS, IN ACCORDANCE WITH THE DETAILS SHOWN ON THE DRAWINGS.
- DETAILS NOT SHOWN SHALL BE IN CONFORMITY WITH THE STATE STANDARDS FOR TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS, AND SIMILAR REQUIREMENTS ESTABLISHED BY THE U.S. DEPARTMENT OF TRANSPORTATION, FEDERAL HIGHWAY ADMINISTRATION.
- ALL PARKING LOT STRIPING SHALL BE SINGLE LINE 4" WIDE AS PER THE SITE PLANS.
- PAINT FOR MARKING PAVEMENT SHALL CONFORM TO FEDERAL HIGHWAY MARKING STANDARDS. USE SHERWIN WILLIAMS PROMAR TRAFFIC MARKING PAINT, COLORS TO MATCH THE EXISTING ADJACENT INSTALLATIONS. USE FLAT BLACK, WHITE OR YELLOW, WHERE APPROPRIATE. UNLESS OTHERWISE DIRECTED, USE THE FOLLOWING:
 - BLACKTOP OR BITUMINOUS ASPHALT PAVING: USE WHITE COLOR.
 - PORTLAND CEMENT CONCRETE PAVING: USE YELLOW COLOR.
 - HANDICAPPED ACCESSIBLE PARKING AND ENTRYWAYS: USE WHITE COLOR WITH WHITE STRIPES.
 - PROVIDE PAINTED CURBS AT FIRE LANE DESIGNATIONS PER FIRE MARSHAL REQUIREMENTS.
- APPLY ALL MARKINGS USING APPROVED MECHANICAL EQUIPMENT (WITH PROVISIONS FOR CONSTANT AGITATION OF PAINT), CAPABLE OF APPLYING THE MARKING WIDTHS AS SHOWN. USE PNEUMATIC SPRAY GUNS FOR HAND APPLICATION OF PAINT. ALL PAINTING EQUIPMENT AND OPERATIONS SHALL BE UNDER THE CONTROL OF EXPERIENCED TECHNICIANS THOROUGHLY FAMILIAR WITH EQUIPMENT AND MATERIALS AND MARKING LAYOUTS.
- DETAIL PAVEMENT MARKINGS SHALL BE THAT MARKING, EXCLUSIVE OF ACTUAL TRAFFIC LANE MARKING, AT EXIT AND ENTRANCE ISLANDS AND TURNOUTS, ON CURBS, AT CROSSWALKS, AT PARKING BAYS AND AT SUCH OTHER LOCATIONS AS SHOWN. HANDICAPPED PARKING SPACES SHALL BE MARKED BY THE INTERNATIONAL HANDICAPPED SYMBOL AT INDICATED PARKING SPACES. USE A SUITABLE TEMPLATE THAT WILL PROVIDE A PAVEMENT MARKING WITH TRUE, SHARP EDGES AND ENDS.

EROSION & SEDIMENT CONTROL NOTES

- PRIOR TO LAND DISTURBANCE ACTIVITIES, THE FOLLOWING SHALL OCCUR:
 - DELINEATE THE OUTER LIMITS OF ANY NATURAL STREAM CORRIDOR DESIGNATED IN ACCORDANCE WITH THE CITY'S DESIGN AND CONSTRUCTION MANUAL SHALL BE APPLICABLE TO DEVELOPMENT IN THE ADP.
 - CONSTRUCT A STABILIZED ENTRANCE/PARKING/DELIVERY AREA.
 - INSTALL PERIMETER CONTROLS AND REQUEST THE INSPECTION OF THE PRECONSTRUCTION EROSION AND SEDIMENT CONTROL MEASURES DESIGNATED ON THE APPROVED EROSION AND SEDIMENT CONTROL PLAN. LAND DISTURBANCE WORK SHALL NOT PROCEED UNTIL THERE IS A SATISFACTORY INSPECTION.
 - IDENTIFY THE LIMITS OF CONSTRUCTION ON THE GROUND WITH EASILY RECOGNIZABLE INDICATIONS SUCH AS CONSTRUCTION STAKING, CONSTRUCTION FENCING, AND PLACEMENT OF PHYSICAL BARRIERS OR OTHER MEANS ACCEPTABLE TO THE CITY INSPECTOR AND IN CONFORMANCE WITH THE EROSION AND SEDIMENT CONTROL PLAN.
- THE SITE SHALL COMPLY WITH ALL REQUIREMENTS OF THE MISSOURI WATER POLLUTION CONTROL AND NPDES STORMWATER RUNOFF FROM CONSTRUCTION SITES GENERAL PERMIT, AND LEE'S SUMMIT STANDARDS AND SPECIFICATIONS LIMITED TO:
 - STABILIZATION OF ANY DISTURBED AREA WHERE THE LAND DISTURBANCE ACTIVITY HAS CEASED FOR MORE THAN 14 DAYS.
 - INSPECTIONS OF EROSION AND SEDIMENT CONTROL MEASURES SHALL BE PERFORMED TO MEET OR EXCEED THE MINIMUM INSPECTION FREQUENCY IN THE MISSOURI GENERAL PERMIT. AT A MINIMUM, INSPECTIONS SHALL BE PERFORMED DURING ALL PHASES OF CONSTRUCTION AT THE FOLLOWING INTERVALS:
 - AT LEAST ONCE EVERY 14 DAYS
 - BY THE END OF THE NEXT DAY, EXCLUDING WEEKENDS AND FEDERAL HOLIDAYS, AFTER A RAIN EVENT OF ½ INCH OR MORE.
 - AN INSPECTION LOG SHALL BE MAINTAINED AND SHALL BE AVAILABLE FOR REVIEW BY THE REGULATORY AUTHORITY.
 - THE EROSION AND SEDIMENT CONTROL PLAN SHALL BE ROUTINELY UPDATED PER THE SWPPP AND NOI TO SHOW ALL CHANGES AND AMENDMENTS TO THE PLAN. A COPY OF THE EROSION AND SEDIMENT CONTROL PLAN SHALL BE KEPT ON SITE AND MADE AVAILABLE FOR REVIEW BY THE REGULATORY AUTHORITY.
- UNLESS OTHERWISE NOTED IN THE PLANS, ALL SEEDING MUST CONFORM TO THE CITY OF LEE'S SUMMIT STANDARDS AND SPECIFICATIONS.
- EROSION AND SEDIMENT CONTROL SHALL BE PROVIDED FOR THE DURATION OF A PROJECT. ALL INSTALLED EROSION AND SEDIMENT CONTROL DEVICES SHALL BE MAINTAINED IN A MANNER THAT PRESERVES THEIR EFFECTIVENESS. IF THE CITY DETERMINES THAT THE BMPS IN PLACE DO NOT PROVIDE ADEQUATE EROSION AND SEDIMENT CONTROL AT ANY TIME DURING THE PROJECT, ADDITIONAL OR ALTERNATE MEASURES THAT PROVIDE EFFECTIVE CONTROL SHALL BE REQUIRED. FAILURE TO DO SO IS A VIOLATION.
- SILT FENCES AND SEDIMENT CONTROL BMPS WHICH ARE SHOWN ALONG THE BACK OF CURB MUST BE INSTALLED WITHIN TWO WEEKS OF CURB BACKFILL AND PRIOR TO PLACEMENT OF BASE ASPHALT. EXACT LOCATIONS OF THESE EROSION CONTROL METHODS MAY BE FIELD ADJUSTED TO MINIMIZE CONFLICTS WITH UTILITY CONSTRUCTION; HOWEVER, ANTICIPATED DISTURBANCE BY UTILITY CONSTRUCTION SHALL NOT DELAY INSTALLATION.
- THE ABOVE REQUIREMENTS ARE THE RESPONSIBILITY OF THE PERMITTEE FOR THE SITE. RESPONSIBILITY MAY BE TRANSFERRED TO ANOTHER PARTY BY THE PERMITTEE ACCORDING TO THE SWPPP, BUT THE PERMITTEE SHALL REMAIN LIABLE BY THE CITY OF LEE'S SUMMIT IF ANY OF THE ABOVE CONDITIONS ARE NOT MET.
- APWA EROSION AND SEDIMENT CONTROL/BMPS USED ON THE PROJECT SHALL BE CONSTRUCTED, INSPECTED, AND MAINTAINED AT A MINIMUM TO APWA STANDARDS AND SPECIFICATIONS.
- THE SITE SHALL COMPLY WITH ALL REQUIREMENTS OF THE MISSOURI WATER POLLUTION CONTROL AND NPDES STORMWATER RUNOFF FROM CONSTRUCTION SITES GENERAL PERMIT, OTHER PERMIT REQUIREMENTS, AND CITY OF LEE'S SUMMIT.
- CONTRACTOR SHALL, BY HIS OWN INVESTIGATION, AND PRIOR TO BIDDING, SATISFY HIMSELF AS TO THE CONDITION OF EXISTING BMPS INCLUDING SEDIMENT TRAPS AND BASINS UNDER CURRENT OPERATION/NOI FROM THE DEMOLITION PLANS CONSTRUCTION DOCUMENTS. AT NOTICE TO PROCEED, BMPS, EXISTING PERMITS, SWPPP OPERATIONS, AND MAINTENANCE BECOMES THE CONTRACTOR'S RESPONSIBILITY.

SANITARY SEWER NOTES:

- ALL SANITARY SEWER SERVICE PIPE SHALL BE PVC SDR-26. SEWER SERVICE LINE W/PUSH ON JOINTS.
- INSTALL 6" ONE-WAY CLEANOUT 10' FROM BUILDING OR AS NOTED ON PLANS.
- NO FOUNDATION DRAINS ARE PLANNED FOR THIS PROJECT. DOWNSPOUTS SHALL NOT BE CONNECTED TO SANITARY SEWER. DOWNSPOUTS WILL DISCHARGE AT GRADE USING SPLASHBLOCK OR TO PROPOSED STORM SEWER.
- TEN FEET OF HORIZONTAL SEPARATION AND TWO FEET OF VERTICAL SEPARATION SHALL BE PROVIDED BETWEEN WATER LINES AND THE SANITARY SEWER SERVICE LINE.
- IN THE EVENT OF WORK IN OR ON THE SANITARY MAIN, ANY TREES OR PLANTINGS PLACED WITHIN THE SEWER EASEMENT MAY BE REMOVED WITHOUT REPLACEMENT OR COMPENSATION THERE-OF.
- 90-DEGREE TURNS TO BE ACCOMPLISHED WITH TWO 45-DEGREE BENDS WITH A MINIMUM OF ONE FOOT OF PIPE BETWEEN THE 45-DEGREE BENDS.
- FOR VERTICAL RISERS AND ENCASEMENTS, SEE SANITARY SEWER CONNECTION SHEETS.
- SANITARY SERVICE LINES SHALL BE INSTALLED BY BUILDING PLUMBER AND IN ACCORDANCE WITH THE CURRENT SERVICE LINE DESIGN AND CONSTRUCTION STANDARDS.
- ROOF DRAINS SHALL NOT BE CONNECTED TO THE SANITARY SEWER.
- REPLACE/ADD BARREL SECTIONS AS REQUIRED TO MEET THE GRADE REQUIREMENTS.
- MANHOLE STATIONS AND PIPE LENGTHS SHOWN ON PLANS ARE TO THE CENTER OF MANHOLES. DO NOT SCALE DRAWINGS.
- CONTRACTOR IS RESPONSIBLE FOR REPLACING ANY PAVEMENT OR SIDEWALKS DAMAGED DURING THE CONSTRUCTION OF THE SANITARY SEWER SERVICE LINE.

AMERICAN WITH DISABILITIES ACT. (ADA)

- ADA PARKING SPACES, MARKINGS AND ACCESS TO THE BUILDING(S) SHALL COMPLY WITH ADA.
- ALL CONSTRUCTION TRAFFIC, TEMPORARY TRAFFIC CONTROL DEVICES, AND PAVEMENT MARKINGS SHALL CONFORM TO THE REQUIREMENTS OF THE LATEST MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES.

olsson

7301 West 133rd Street, Suite 200
Overland Park, KS 66213-4750
TEL 913.381.1170
www.olsson.com

SCANNELL

PROPERTIES

STATE OF MISSOURI
JAMES M. MOSELEY
GOVERNOR
MICHIELL ALAN
MILK
COMMISSIONER
NUMBER
PE-0000010104
2-2-22

REVISIONS

REV.	NO.	DATE	DESCRIPTION
1	1	06-25-2022	CITY COMMENTS
2	2	06-13-2022	CITY COMMENTS
3	3	10-04-2022	CITY COMMENTS
4	4	10-13-2022	CITY COMMENTS
5	5	11-11-2022	DESIGNER

GENERAL NOTES

FINAL DEVELOPMENT PLAN - BUILDING 2

SCANNELL DEVELOPMENT LEE'S SUMMIT LOGISTICS
NORTHWEST CORNER OF TUDOR ROAD AND MAIN STREET

LEE'S SUMMIT, MISSOURI

drawn by: SL

checked by: LM

approved by: SR

QA/QC by: MK

project no.: B21-04157


drawing no.: TT01_B2104157.dwg

date: 03.11.2022

SHEET

C1.01

DWG: F:\2021\04001-04500\021-04157-B\40-Design\AutoCAD\Final Plans\Sheets\GNVC\CLP01_B2104157.dwg
DATE: Dec 06, 2022 9:31am USER: Imoore
XREFS: C:\BLK_B2104157 C:\PBASE_B2104157 C:\XBASE_B2104157



UNIVERSITY OF CENTRAL
MISSOURI - LEE'S SUMMIT

BUILDING & SITE DATA							
ZONING							
NO. OF STORIES	BLDG HEIGHT	USE	BUILDING SQ. FT.	PARKING REQUIRED	PARKING PROVIDED	FLOOR AREA RATIO	LOT AREA
1	48 FT	BUILDING 2 WAREHOUSE	113,615 S.F.	1 STALL PER 1000 SF (114 STALLS)	115 STALLS	0.36	13.21 ACRES
LOT 2 PROPOSED OPEN SPACE= 315,719 S.F. (7.2479 ACRES) 54.85%							
REQUIRED OPEN SPACE= REFERENCE LANDSCAPE PLAN							
LOT 2 PROPOSED IMPERVIOUS AREA= 259,930 S.F. (5.9671 ACRES)							

PROPERTY DESCRIPTION

ALL THAT PART OF AN UNPLATTED TRACT OF LAND, TOGETHER WITH ALL THAT PART OF NORTH MAIN STREET RIGHT OF WAY, ALL LYING IN THE WEST HALF OF SECTION 31, TOWNSHIP 48 NORTH, RANGE 31 WEST, LYING IN THE CITY OF LEE'S SUMMIT, JACKSON COUNTY, MISSOURI, DESCRIBED BY PATRICK ETHAN WARD, MO PLS-20050071, OF OLSSON MOLC-366, ON OCTOBER 14, 2021, AS FOLLOWS:

BEGINNING AT THE NORTHEAST CORNER OF THE SOUTHWEST QUARTER OF SECTION 31, TOWNSHIP 48 NORTH, RANGE 31 WEST; THENCE SOUTH 01 DEGREE 59 MINUTES 47 SECONDS WEST, ON THE EAST LINE OF SAID SOUTHWEST QUARTER, A DISTANCE OF 65.98 FEET TO A POINT ON THE WEST LINE OF NW SLOAN STREET RIGHT OF WAY, AS ESTABLISHED IN DOCUMENT 2013E0075031, SAID POINT ALSO LYING ON A NON-TANGENT CURVE; THENCE IN A SOUTHERLY DIRECTION, DEPARTING SAID EAST LINE, ON SAID WEST LINE AND ON A CURVE TO THE RIGHT WHOSE INITIAL TANGENT BEARS SOUTH 02 DEGREES 47 MINUTES 37 SECONDS WEST, HAVING A RADIUS OF 970.00 FEET, THROUGH A CENTRAL ANGLE OF 6 DEGREES 27 MINUTES 07 SECONDS, AN ARC DISTANCE OF 109.23 FEET TO A POINT OF TANGENCY; THENCE SOUTH 09 DEGREES 14 MINUTES 44 SECONDS WEST, CONTINUING ON SAID WEST LINE, A DISTANCE OF 111.80 FEET TO A POINT OF CURVATURE, THENCE IN A SOUTHERLY DIRECTION, CONTINUING ON SAID WEST LINE AND ON A CURVE TO THE LEFT, HAVING A RADIUS OF 1030.00 FEET, THROUGH A CENTRAL ANGLE OF 7 DEGREES 14 MINUTES 57 SECONDS, AN ARC DISTANCE OF 130.32 FEET TO A POINT OF TANGENCY; THENCE SOUTH 01 DEGREE 59 MINUTES 47 SECONDS WEST, CONTINUING ON SAID WEST LINE, A DISTANCE OF 69.49 FEET TO A POINT ON THE NORTH LINE OF NE TUDOR ROAD RIGHT OF WAY, AS ESTABLISHED IN SAID DOCUMENT 2013E0075031; THENCE SOUTH 46 DEGREES 15 MINUTES 48 SECONDS WEST, DEPARTING SAID WEST LINE, ON SAID NORTH LINE, A DISTANCE OF 46.09 FEET TO A POINT; THENCE NORTH 89 DEGREES 24 MINUTES 16 SECONDS WEST, CONTINUING ON SAID NORTH LINE, AND ON THE NORTH LINE OF NW TUDOR ROAD RIGHT OF WAY, AS ESTABLISHED IN DOCUMENT 2013E0075030, A DISTANCE OF 1249.23 FEET TO A POINT ON THE EAST LINE OF UNION PACIFIC RAILROAD RIGHT OF WAY, AS NOW ESTABLISHED, SAID POINT ALSO LYING ON A NON-TANGENT CURVE; THENCE IN A NORTHERLY AND NORTHWESTERLY DIRECTION, DEPARTING SAID NORTH LINE, ON SAID EAST LINE AND ON A CURVE TO THE LEFT WHOSE INITIAL TANGENT BEARS NORTH 15 DEGREES 46 MINUTES 27 SECONDS WEST, HAVING A RADIUS OF 3203.90 FEET, THROUGH A CENTRAL ANGLE OF 22 DEGREES 48 MINUTES 11 SECONDS, AN ARC DISTANCE OF 1275.12 FEET TO A POINT OF TANGENCY; THENCE NORTH 38 DEGREES 34 MINUTES 39 SECONDS WEST, CONTINUING ON SAID EAST LINE, A DISTANCE OF 738.40 FEET TO A POINT OF CURVATURE; THENCE IN A NORTHWESTERLY DIRECTION, CONTINUING ON SAID EAST LINE AND ON A CURVE TO THE RIGHT, HAVING A RADIUS OF 5981.13 FEET, THROUGH A CENTRAL ANGLE OF 2 DEGREES 39 MINUTES 22 SECONDS, AN ARC DISTANCE OF 277.27 FEET TO A POINT ON THE NORTH LINE OF THE SOUTH HALF OF THE NORTHWEST QUARTER OF SAID SECTION 31, SAID POINT ALSO LYING ON A NON-TANGENT CURVE; THENCE SOUTH 87 DEGREES 40 MINUTES 30 SECONDS EAST, DEPARTING SAID EAST LINE, ON SAID NORTH LINE, A DISTANCE OF 884.17 FEET TO A POINT ON A NON-TANGENT CURVE; THENCE IN A SOUTHEASTERLY DIRECTION, DEPARTING SAID NORTH LINE, ON A CURVE TO THE RIGHT WHOSE INITIAL TANGENT BEARS SOUTH 45 DEGREES 29 MINUTES 38 SECONDS EAST, HAVING A RADIUS OF 544.00 FEET, THROUGH A CENTRAL ANGLE OF 16 DEGREES 50 MINUTES 44 SECONDS, AN ARC DISTANCE OF 159.94 FEET TO A POINT OF TANGENCY; THENCE SOUTH 28 DEGREES 38 MINUTES 55 SECONDS EAST A DISTANCE OF 437.58 FEET TO A POINT OF CURVATURE; THENCE IN A SOUTHEASTERLY AND EASTERLY DIRECTION, ON A CURVE TO THE LEFT, HAVING A RADIUS OF 476.00 FEET, THROUGH A CENTRAL ANGLE OF 63 DEGREES 19 MINUTES 59 SECONDS, AN ARC DISTANCE OF 526.16 FEET TO A POINT OF TANGENCY; THENCE NORTH 88 DEGREES 01 MINUTE 06 SECONDS EAST A DISTANCE OF 416.85 FEET TO A POINT OF CURVATURE; THENCE IN AN EASTERLY AND SOUTHEASTERLY DIRECTION, ON A CURVE TO THE RIGHT, HAVING A RADIUS OF 544.00 FEET, THROUGH A CENTRAL ANGLE OF 65 DEGREES 51 MINUTES 08 SECONDS, AN ARC DISTANCE OF 625.24 FEET TO A POINT ON A NON-TANGENT LINE, SAID POINT ALSO LYING ON THE EAST LINE OF SAID NORTHWEST QUARTER; THENCE SOUTH 01 DEGREE 53 MINUTES 30 SECONDS WEST, ON SAID EAST LINE, A DISTANCE OF 338.00 FEET TO THE POINT OF BEGINNING, CONTAINING 2,375,437 SQUARE FEET OR 54.5325 ACRES, MORE OR LESS.

PROPERTY OWNER/ DEVELOPER

SCANNELL PROPERTIES #603, LLC
8801 RIVER CROSSING BLVD, SUITE 300
INDIANAPOLIS, IN 46240
PH: 317-218-1648

ENGINEER/ LANDSCAPE ARCHITECT

OLSSON
7301 W. 133RD STREET, SUITE 200
OVERLAND PARK, KS 66213
PH: 913-381-1170
F: 913-381-1174

PROPOSED SITE USE



INDUSTRIAL

EXISTING & PROPOSED ZONING

EXISTING: PLANNED INDUSTRIAL
PROPOSED: PLANNED INDUSTRIAL

SITE AREA

NET SITE AREA= 3,439,837 SQ. FT., (78.9678 AC±)



LEGEND	
	PROPERTY LINE
	SECTION LINE
	FEMA FLOOD PLAIN LIMITS
	LOT LINE
	ADA PATH - SIDEWALKS NOT DELINEATED AS ADA PATHS WILL NOT BE ADA COMPLIANT.
	EXISTING SANITARY SEWER
	EXISTING STORM
	EXISTING WATER PIPE
	EXISTING OVERHEAD POWER LINE
	EXISTING UNDERGROUND POWER LINE
	UNDERGROUND POWER CONDUIT
	NATURAL GAS PIPE
	CABLE TELEVISION CONDUIT
	WATER PIPE
	SANITARY SEWER SERVICE LINE
	PROPOSED STORM SEWER
	INSTALL STANDARD "WET" CURB & GUTTER (PER LEE'S SUMMIT STANDARD DETAIL)
	INSTALL STANDARD "DRY" CURB & GUTTER (PER LEE'S SUMMIT STANDARD DETAIL)
	INSTALL "ADA RAMP" CURB & GUTTER (PER LEE'S SUMMIT STANDARD DETAIL)
	INSTALL MEDIUM DUTY ASPHALT SEE PAVEMENT SECTION ON C3.00
	INSTALL HEAVY DUTY ASPHALT SEE PAVEMENT SECTION ON C3.00
	INSTALL HEAVY DUTY CONCRETE SEE PAVEMENT SECTION ON C3.00
	INSTALL CONCRETE SIDEWALK SEE PAVEMENT SECTION ON C3.00

GENERAL LAYOUT PLAN
FINAL DEVELOPMENT PLAN - BUILDING 2

SCANNELL DEVELOPMENT LEE'S SUMMIT LOGISTICS
NORTHWEST CORNER OF TUDOR ROAD AND MAIN STREET

REV.	NO.	DATE	REVISIONS DESCRIPTION
1	06-28-2022	CITY COMMENTS	
2	06-28-2022	CITY COMMENTS	
3	06-13-2022	CITY COMMENTS	
4	10-04-2022	CITY COMMENTS	
5	10-18-2022	CITY COMMENTS	
6	11-15-2022	CITY COMMENTS	

BY	DATE	REVISIONS




olsson

7301 West 133rd Street, Suite 200
Overland Park, KS 66213-1170
TEL 913.381.1170 www.olsson.com


drawn by: SR
checked by: LM
approved by: SR
GNCC by: MK
project no.: B21-04157
drawing @ CLP01_B2104157.dwg
date: 03.11.2022

SHEET
C2.00




MEDIUM DUTY ASPHALT PAVEMENT SECTION

NOT TO SCALE
PER GEOTECHNICAL REPORT




HEAVY DUTY ASPHALT PAVEMENT SECTION

NOT TO SCALE
PER GEOTECHNICAL REPORT



MEDIUM DUTY CONCRETE PAVEMENT SECTION

NOT TO SCALE
PER GEOTECHNICAL REPORT




HEAVY DUTY CONCRETE PAVEMENT SECTION

NOT TO SCALE
PER GEOTECHNICAL REPORT


NOTE

1. ALL CONSTRUCTION, SITE PREPARATION, GRADING, AND EXCAVATION PROCEDURES SHALL CONFORM TO RECOMMENDATIONS AS OUTLINED IN THE GEOTECHNICAL REPORT INCLUDING ADDENDUMS. CONTRACTOR SHALL CONTACT ENGINEER WITH ANY DISCREPANCIES OR CONCERNS BASED ON ACTUAL SITE CONDITIONS.
2. GEOTECHNICAL REPORT GOVERNS ONLY IF IT MEETS OR EXCEEDS CITY REQUIREMENTS.
3. SUBGRADE STABILIZED WITH 15 PERCENT CLASS "C" FLY ASH, 5 PERCENT LIME OR CEMENT.



DIMENSION PLAN LEGEND

- PROPERTY LINE
- LOT LINE
- UTILITY EASEMENT
- BUILDING SET/BACK/LANDSCAPE BUFFER
- SAWCUT PAVEMENT FULL DEPTH
- ADA PATH - SIDEWALKS NOT DELINEATED AS ADA PATHS WILL NOT BE ADA COMPLIANT.
- PROPOSED STORM SEWER
- INSTALL STANDARD "WET" CURB & GUTTER (PER LEE'S SUMMIT STANDARD DETAIL)
- INSTALL STANDARD "DRY" CURB & GUTTER (PER LEE'S SUMMIT STANDARD DETAIL)
- INSTALL "ADA RAMP" CURB & GUTTER (PER LEE'S SUMMIT STANDARD DETAIL)
- INSTALL MEDIUM DUTY ASPHALT SEE PAVEMENT SECTION ON C3.00
- INSTALL HEAVY DUTY ASPHALT SEE PAVEMENT SECTION ON C3.00
- INSTALL HEAVY DUTY CONCRETE SEE PAVEMENT SECTION ON C3.00
- INSTALL CONCRETE SIDEWALK SEE PAVEMENT SECTION ON C3.00



DWG: F:\2021\04001-04500\021-04157-B\40-Design\AutoCAD\Final Plans\Sheets\GNVC\B2104157.dwg
DATE: Dec 06, 2022 9:31am XREFS: C:\BASE_B2104157 C:\PSURF_B2104157 C:\LSC01_B2104157 E:\PBASE_B2104157
USER: moore C:\TBLK_B2104157

drawn by: SL
checked by: LM
approved by: SR
GNVC by: MM
project no.: B21-04157
drawing: 02.DIM01_B2104157.dwg
date: 03.11.2022

OVERALL DIMENSION PLAN
FINAL DEVELOPMENT PLAN - BUILDING 2
SCANNELL DEVELOPMENT LEE'S SUMMIT LOGISTICS
NORTHWEST CORNER OF TUDOR ROAD AND MAIN STREET
LEE'S SUMMIT, MISSOURI

REV. NO.	DATE	REVISIONS DESCRIPTION
1	06-28-2022	CITY COMMENTS
2	06-28-2022	CITY COMMENTS
3	06-15-2022	CITY COMMENTS
4	10-04-2022	CITY COMMENTS
5	10-18-2022	CITY COMMENTS
6	11-14-2022	CITY COMMENTS
7	11-14-2022	ADDITIONAL

BY:

REVISIONS

2022

SHEET
C4.00



olsson

7301 West 133rd Street, Suite 200
Overland Park, KS 66203-4755
TEL 913.381.1170 www.olsson.com

SCANNELL
PROPERTIES

STATE OF MISSOURI
PEAK
NUMBER
PE-2008016164
1-2-2-22
PROFESSIONAL ENGINEER

DWG: F:\2021\04001-04500\021-04157-B\40-Design\AutoCAD\Final Plans\Sheets\GNVC\B2104157.dwg
DATE: Dec 06, 2022 9:31am
USER: moore
C:\BLK_B2104157
C:\LSC01_B2104157
E:\PBASE_B2104157
C:\PSURF_B2104157
XREFS: C:\XBASE_B2104157



KEY MAP
NOT TO SCALE

DIMENSION PLAN LEGEND


- PROPERTY LINE
- LOT LINE
- UTILITY EASEMENT
- BUILDING SET/BACK/LANDSCAPE BUFFER
- SAWCUT PAVEMENT FULL DEPTH
- ADA PATH - SIDEWALKS NOT DELINEATED AS ADA PATHS WILL NOT BE ADA COMPLIANT.
- PROPOSED STORM SEWER
- INSTALL STANDARD CURB & GUTTER (PER LEE'S SUMMIT STANDARD DETAIL)
- INSTALL STANDARD "DRY" CURB & GUTTER (PER LEE'S SUMMIT STANDARD DETAIL)
- INSTALL "ADA RAMP" CURB & GUTTER (PER LEE'S SUMMIT STANDARD DETAIL)

- INSTALL MEDIUM DUTY ASPHALT SEE PAVEMENT SECTION ON C3.00
- INSTALL HEAVY DUTY ASPHALT SEE PAVEMENT SECTION ON C3.00
- INSTALL HEAVY DUTY CONCRETE SEE PAVEMENT SECTION ON C3.00
- INSTALL CONCRETE SIDEWALK SEE PAVEMENT SECTION ON C3.00

- PROPOSED LIGHT POLE
- PROPOSED PARKING STALL COUNT

KEYNOTES

- 1 CONSTRUCT ADA ACCESSIBLE RAMP. (SEE DETAIL SHEET)
- 2 PROPOSED ADA ACCESSIBLE PARKING SIGN. (SEE DETAIL SHEET). SIGNS PROVIDED BY TENANT.
- 3 ADA PARKING STALL LAYOUT. (SEE DETAIL SHEET)
- 4 PROPOSED PAVEMENT STRIPING. (SEE PAVEMENT STRIPING PLAN)
- 5 PROPOSED CONCRETE SIDEWALK. (SEE DETAIL SHEET)
- 6 PROPOSED TRANSFORMER. (SEE MEP PLANS)
- 7 PROPOSED CONCRETE APRON
- 8 PARKING AND STREET LIGHTING. (SEE SEPARATE PLAN SET)
- 9 PROPOSED ROOF DRAIN/DOWN SPOUT LOCATION. (SEE STORM SHEETS)
- 10 INSTALL YIELD/STOP SIGNS. (SEE ARCH PLANS)
- 11 PROPOSED TRAILER SPACING NUMBERING
- 12 PROPOSED DRY DETENTION BASIN
- 13 CONCRETE STAIRS (SEE DETAIL SHEET)
- 14 PROPOSED EV CHARGING STATION(SEE MEP/ARCH PLANS)
- 15 PROPOSED FIRE HYDRANT
- 16 PROPOSED RETAINING WALL WITH TRAFFIC RATED RAILING/FENCE.
- 17 PROPOSED FDC
- 18 PROPOSED FIRE SERVICE BACK FLOW AND METER VAULT
- 19 PROPOSED DOMESTIC WATER METER AND VAULT
- 20 PROPOSED 6" BOLLARDS
- 21 PROPOSED WHEEL STOP - ADA PARKING STALLS



olsson

7001 West 133rd Street, Suite 200
Overland Park, KS 66204-7756
TEL 913.381.1170
www.olson.com

SCANNELL

PROPERTIES

STATE OF MISSOURI

MITCHELL ALAN
PEAK
NUMBER
PE-2008010164
2-2-22
PROFESSIONAL ENGINEER

BY

REVISIONS DESCRIPTION

DATE

REV

NO.

1

06-25-2022

CITY COMMENTS

2

06-25-2022

CITY COMMENTS

3

06-15-2022

CITY COMMENTS

4

10-04-2022

CITY COMMENTS

5

10-10-2022

CITY COMMENTS

6

11-14-2022

CITY COMMENTS

7

11-14-2022

CITY COMMENTS

DIMENSION PLAN - BUILDING 2

FINAL DEVELOPMENT PLAN - BUILDING 2

SCANNELL DEVELOPMENT LEE'S SUMMIT LOGISTICS

NORTHWEST CORNER OF TUDOR ROAD AND MAIN STREET

LEE'S SUMMIT, MISSOURI

2022

drawn by: SL

checked by: LM

approved by: SR

QA/QC by: MM



project no.: B21-04157

drawing no.: 02104157.dwg

date: 03.11.2022

SHEET

C4.01




KEY MAP
NOT TO SCALE

DIMENSION PLAN LEGEND

- PROPERTY LINE
- LOT LINE
- UTILITY EASEMENT
- BUILDING SET/BACK/LANDSCAPE BUFFER
- SAWCUT PAVEMENT FULL DEPTH
- ADA PATH - SIDEWALKS NOT DELINEATED AS ADA PATHS WILL NOT BE ADA COMPLIANT.
- PROPOSED STORM SEWER
- INSTALL STANDARD CURB & GUTTER (PER LEE'S SUMMIT STANDARD DETAIL)
- INSTALL STANDARD "DRY" CURB & GUTTER (PER LEE'S SUMMIT STANDARD DETAIL)
- INSTALL "ADA RAMP" CURB & GUTTER (PER LEE'S SUMMIT STANDARD DETAIL)
- INSTALL MEDIUM DUTY ASPHALT SEE PAVEMENT SECTION ON C3.00
- INSTALL HEAVY DUTY ASPHALT SEE PAVEMENT SECTION ON C3.00
- INSTALL HEAVY DUTY CONCRETE SEE PAVEMENT SECTION ON C3.00
- INSTALL CONCRETE SIDEWALK SEE PAVEMENT SECTION ON C3.00
- PROPOSED LIGHT POLE
- PROPOSED PARKING STALL COUNT

KEYNOTES #

- CONSTRUCT ADA ACCESSIBLE RAMP. (SEE DETAIL SHEET)
- PROPOSED ADA ACCESSIBLE PARKING SIGN. (SEE DETAIL SHEET). SIGNS PROVIDED BY TENANT.
- ADA PARKING STALL LAYOUT. (SEE DETAIL SHEET)
- PROPOSED PAVEMENT STRIPING. (SEE PAVEMENT STRIPING PLAN)
- PROPOSED CONCRETE SIDEWALK. (SEE DETAIL SHEET)
- PROPOSED TRANSFORMER. (SEE MEP PLANS)
- PROPOSED CONCRETE APRON
- PARKING AND STREET LIGHTING. (SEE SEPARATE PLAN SET)
- PROPOSED ROOF DRAIN/DOWN SPOUT LOCATION. (SEE STORM SHEETS)
- INSTALL YIELD/STOP SIGNS. (SEE ARCH PLANS)
- PROPOSED TRAILER SPACING NUMBERING
- PROPOSED DRY DETENTION BASIN
- CONCRETE STAIRS (SEE DETAIL SHEET)
- PROPOSED EV CHARGING STATION(SEE MEP/ARCH PLANS)
- PROPOSED FIRE HYDRANT
- PROPOSED RETAINING WALL WITH TRAFFIC RATED RAILING/FENCE.
- PROPOSED FDC
- PROPOSED FIRE SERVICE BACK FLOW AND METER VAULT
- PROPOSED DOMESTIC WATER METER AND VAULT
- PROPOSED 6" BOLLARDS
- PROPOSED WHEEL STOP - ADA PARKING STALLS



BY	DATE	REVISIONS DESCRIPTION
1	06-28-2022	CITY COMMENTS
2	06-28-2022	CITY COMMENTS
3	06-15-2022	CITY COMMENTS
4	10-04-2022	CITY COMMENTS
5	10-18-2022	CITY COMMENTS
6	11-14-2022	CITY COMMENTS

DIMENSION PLAN
FINAL DEVELOPMENT PLAN - BUILDING 2

SCANNELL DEVELOPMENT LEE'S SUMMIT LOGISTICS
NORTHWEST CORNER OF TUDOR ROAD AND MAIN STREET

LEE'S SUMMIT, MISSOURI

drawn by: SL

checked by: LM

approved by: SR

QA/QC by: MK

project no.: B21-04157



drawing no.: DIM01_B2104157.dwg

date: 03.11.2022

SHEET
C4.03

2022

REVISIONS



KEY MAP
NOT TO SCALE

DIMENSION PLAN LEGEND


- PROPERTY LINE
- LOT LINE
- UTILITY EASEMENT
- BUILDING SET/BACK/LANDSCAPE BUFFER
- SAWCUT PAVEMENT FULL DEPTH
- ADA PATH - SIDEWALKS NOT DELINEATED AS ADA PATHS WILL NOT BE ADA COMPLIANT.
- PROPOSED STORM SEWER
- INSTALL STANDARD CURB & GUTTER (PER LEE'S SUMMIT STANDARD DETAIL)
- INSTALL STANDARD "DRY" CURB & GUTTER (PER LEE'S SUMMIT STANDARD DETAIL)
- INSTALL "ADA RAMP" CURB & GUTTER (PER LEE'S SUMMIT STANDARD DETAIL)

- INSTALL MEDIUM DUTY ASPHALT SEE PAVEMENT SECTION ON C3.00
- INSTALL HEAVY DUTY ASPHALT SEE PAVEMENT SECTION ON C3.00
- INSTALL HEAVY DUTY CONCRETE SEE PAVEMENT SECTION ON C3.00
- INSTALL CONCRETE SIDEWALK SEE PAVEMENT SECTION ON C3.00

- PROPOSED LIGHT POLE
- PROPOSED PARKING STALL COUNT

KEYNOTES

- 1 CONSTRUCT ADA ACCESSIBLE RAMP. (SEE DETAIL SHEET)
- 2 PROPOSED ADA ACCESSIBLE PARKING SIGN. (SEE DETAIL SHEET). SIGNS PROVIDED BY TENANT.
- 3 ADA PARKING STALL LAYOUT. (SEE DETAIL SHEET)
- 4 PROPOSED PAVEMENT STRIPING. (SEE PAVEMENT STRIPING PLAN)
- 5 PROPOSED CONCRETE SIDEWALK. (SEE DETAIL SHEET)
- 6 PROPOSED TRANSFORMER. (SEE MEP PLANS)
- 7 PROPOSED CONCRETE APRON
- 8 PARKING AND STREET LIGHTING. (SEE SEPARATE PLAN SET)
- 9 PROPOSED ROOF DRAIN/DOWN SPOUT LOCATION. (SEE STORM SHEETS)
- 10 INSTALL YIELD/STOP SIGNS. (SEE ARCH PLANS)
- 11 PROPOSED TRAILER SPACING NUMBERING
- 12 PROPOSED DRY DETENTION BASIN
- 13 CONCRETE STAIRS (SEE DETAIL SHEET)
- 14 PROPOSED EV CHARGING STATION(SEE MEP/ARCH PLANS)
- 15 PROPOSED FIRE HYDRANT
- 16 PROPOSED RETAINING WALL WITH TRAFFIC RATED RAILING/FENCE.
- 17 PROPOSED FDC
- 18 PROPOSED FIRE SERVICE BACK FLOW AND METER VAULT
- 19 PROPOSED DOMESTIC WATER METER AND VAULT
- 20 PROPOSED 6" BOLLARDS
- 21 PROPOSED WHEEL STOP - ADA PARKING STALLS



DWG: F:\2021\04001-04500\021-04157-B\40-Design\AutoCAD\Final Plans\Sheets\GNV\AC_DIM01_B2104157.dwg
DATE: Dec 06, 2022 9:32am
XREFS: C:\BASE_B2104157 C:\PSURF_B2104157 C:\LSC01_B2104157 E:\PBASE_B2104157
USER: moore
C:\BLK_B2104157

7301 West 133rd Street, Suite 200
Overland Park, KS 66213-4755
TEL 913.381.1170 www.olsson.com

STATE OF MISSOURI
MITCHELL ALAN
PE 2008010164
2-2-22
PROFESSIONAL ENGINEER

REV	NO.	DATE	REVISIONS DESCRIPTION
1	1	06-29-2022	CITY COMMENTS
2	2	06-29-2022	CITY COMMENTS
3	3	06-15-2022	CITY COMMENTS
4	4	10-04-2022	CITY COMMENTS
5	5	10-10-2022	CITY COMMENTS
6	6	11-14-2022	CITY COMMENTS


REV	NO.	DATE	REVISIONS DESCRIPTION
1	1	06-29-2022	CITY COMMENTS
2	2	06-29-2022	CITY COMMENTS
3	3	06-15-2022	CITY COMMENTS
4	4	10-04-2022	CITY COMMENTS
5	5	10-10-2022	CITY COMMENTS
6	6	11-14-2022	CITY COMMENTS

2022

DIMENSION PLAN - BUILDING 2
FINAL DEVELOPMENT PLAN - BUILDING 2
SCANNELL DEVELOPMENT LEE'S SUMMIT LOGISTICS
NORTHWEST CORNER OF TUDOR ROAD AND MAIN STREET
LEE'S SUMMIT, MISSOURI


drawn by: SL
checked by: LM
approved by: SR
GNV by: MN
project no.: B21-04157
drawing no.: DIM01_B2104157.dwg
date: 03.11.2022

SHEET
C4.04



LEGEND


- PROPERTY LINE
SURROUNDING PROPERTY LINES
EXISTING UTILITY EASEMENT
PROPOSED CONTOUR
EXISTING CONTOUR
CONSTRUCT CONCRETE CURB & GUTTER
PROPOSED SANITARY SERVICE LINE
PROPOSED WATER SERVICE LINE
PROPOSED UNDERGROUND POWER SERVICE LINE
PROPOSED FIRE PROTECTION LINE
PROPOSED COMMUNICATIONS SERVICE LINE



GRADING DETAILS
(SEE SHEETS C5.05-C5.08)

NOTES:

- CONTRACTOR TO NOTIFY ENGINEER IF EXISTING GRADES VARY SIGNIFICANTLY FROM THOSE SHOWN IN THESE PLANS.
- ALL ADA ACCESSIBLE SIDEWALK CROSS SLOPES SHALL HAVE A MAXIMUM CROSS SLOPE OF 2.00% AND MAXIMUM LONGITUDINAL SLOPE OF 5.00%.
- ALL ADA ACCESSIBLE PARKING AREAS SHALL NOT EXCEED 2.00% IN ANY DIRECTION. SEE SLOPE ARROWS IN PLAN VIEW ON THIS SHEET.
- FINISHED GRADE ADJACENT TO BUILDINGS (GREEN SPACE) SHOULD BE MINIMUM 6" BELOW FFE.
- DO NOT DISTURB GRADES IN EXISTING UTILITY EASEMENT



olsson

7301 West 133rd Street, Suite 200
Overland Park, KS 66213-4756
TEL 913.381.1170
www.olsson.com

SCANNELL

PROPERTIES

STATE OF MISSOURI

MITCHELL ALAN

PE 0000010164

2-2-22

PROFESSIONAL ENGINEER

REV. NO.	DATE	REVISIONS DESCRIPTION	BY
1	06-28-2022	CITY COMMENTS	
2	06-28-2022	CITY COMMENTS	
3	06-15-2022	CITY COMMENTS	
4	10-04-2022	CITY COMMENTS	
5	10-18-2022	CITY COMMENTS	
6	11-15-2022	CITY COMMENTS	
7	11-15-2022	CITY COMMENTS	

REVISIONS
2022

drawn by: SL

checked by: LM

approved by: SR

GNV by: MN

project no: B21-04157

drawing: GRD01_B2104157.dwg

date: 03.11.2022

OVERALL GRADING PLAN

FINAL DEVELOPMENT PLAN - BUILDING 2

SCANNELL DEVELOPMENT LEE'S SUMMIT LOGISTICS



NORTHWEST CORNER OF TUDOR ROAD AND MAIN STREET

LEE'S SUMMIT, MISSOURI

SHEET

C5.00

DWG: F:\2021\04001-04500\021-04157-B\40-Design\AutoCAD\Final Plans\Sheets\GNVC\GRD02_B2104157.dwg
DATE: Dec 06, 2022 9:33am XREFS: C:\BASE_B2104157 C:\PSURF_B2104157 C:\LSC01_B2104157 C:\PBASE_02104157 with driveways
USER: Imoore C:\BLK_B2104157



KEY MAP
NOT TO SCALE

LEGEND

- PROPERTY LINE
- SURROUNDING PROPERTY LINES
- EXISTING UTILITY EASEMENT
- PROPOSED CONTOUR
- EXISTING CONTOUR
- CONSTRUCT CONCRETE CURB & GUTTER
- PROPOSED SANITARY SERVICE LINE
- PROPOSED WATER SERVICE LINE
- PROPOSED UNDERGROUND POWER SERVICE LINE
- PROPOSED FIRE PROTECTION LINE
- PROPOSED COMMUNICATIONS SERVICE LINE
- GRADE BREAK LINE
- RIDGE LINE
- VALLEY LINE


SPOT ELEVATION LEGEND:

ALL SPOT ELEVATIONS ARE TOP OF PAVEMENT ELEVATION UNLESS NOTED OTHERWISE. RE: PLAN VIEW, LEGEND AND DETAILS FOR CURB TYPE AND TO CALCULATE TOP OF CURB ELEVATION.

- TC TOP OF CURB
- FG FINISHED GRADE WITHIN GREENSPACE
- TS TOP OF STRUCTURE
- FC CURB DERESSED TO BE FLUSH WITH ADJACENT PAVEMENT
- HP HIGH POINT
- LP LOW POINT
- ME± MATCH EXISTING
- FFE FINISH FLOOR ELEVATION AT TOP OF SLAB
- HFG HIGH FINISHED GRADE
- LFG LOW FINISHED GRADE

NOTES:

- CONTRACTOR TO REMOVE AND REPLACE ALL SIDEWALK NECESSARY FOR CONNECTION TO EXISTING.
- ALL ADA ACCESSIBLE SIDEWALK CROSS SLOPES SHALL HAVE A MAXIMUM CROSS SLOPE OF 2.00% AND MAXIMUM LONGITUDINAL SLOPE OF 5.00%.
- ALL ADA ACCESSIBLE PARKING AREAS SHALL NOT EXCEED 2.00% IN ANY DIRECTION.
- CONTRACTOR TO PROVIDE FLAT A/C UNIT PADS FOR ALL A/C UNITS.
- NO GRADES SHALL EXCEED 5:1 UNLESS OTHERWISE NOTES.
- GRADING AND STORM SEWER IMPROVEMENTS SHALL BE STAKED, INCLUDING ALL HIGH POINTS AND KEY GRADE BREAKS.



olsson

7301 West 133rd Street, Suite 200
Overland Park, KS 66213-7755
TEL 913.381.1170
www.olsson.com

SCANNELL PROPERTIES

STATE OF MISSOURI
JULIE A. ALAN
PE 0000016164
2-2-22
PROFESSIONAL ENGINEER

GRADING PLAN
FINAL DEVELOPMENT PLAN - BUILDING 2

SCANNELL DEVELOPMENT LEE'S SUMMIT LOGISTICS
NORTHWEST CORNER OF TUDOR ROAD AND MAIN STREET

LEE'S SUMMIT, MISSOURI

drawn by: SL
checked by: LM
approved by: SR
QA/QC by: MM
project no.: B21-04157
drawing: GRD02_B2104157.dwg
date: 03.11.2022

2022

SHEET
C5.01

REV. NO.


DATE

REVISIONS DESCRIPTION

BY

1	06-25-2022	CITY COMMENTS	
2	06-25-2022	CITY COMMENTS	
3	06-15-2022	CITY COMMENTS	
4	10-04-2022	CITY COMMENTS	
5	10-10-2022	CITY COMMENTS	
6	11-15-2022	CITY COMMENTS	
7	11-15-2022	CITY COMMENTS	

REVISIONS



KEY MAP
NOT TO SCALE

LEGEND

	PROPERTY LINE
	SURROUNDING PROPERTY LINES
	EXISTING UTILITY EASEMENT
	PROPOSED CONTOUR
	EXISTING CONTOUR
	CONSTRUCT CONCRETE CURB & GUTTER
	PROPOSED SANITARY SERVICE LINE
	PROPOSED WATER SERVICE LINE
	PROPOSED UNDERGROUND POWER SERVICE LINE
	PROPOSED FIRE PROTECTION LINE
	PROPOSED COMMUNICATIONS SERVICE LINE
	GRADE BREAK LINE
	RIDGE LINE
	VALLEY LINE


SPOT ELEVATION LEGEND:

ALL SPOT ELEVATIONS ARE TOP OF PAVEMENT ELEVATION UNLESS NOTED OTHERWISE. RE: PLAN VIEW, LEGEND AND DETAILS FOR CURB TYPE AND TO CALCULATE TOP OF CURB ELEVATION.

TC	TOP OF CURB
FG	FINISHED GRADE WITHIN GREENSPACE
TS	TOP OF STRUCTURE
FC	CURB DEPRESSED TO BE FLUSH WITH ADJACENT PAVEMENT
HP	HIGH POINT
LP	LOW POINT
ME±	MATCH EXISTING
FFE	FINISH FLOOR ELEVATION AT TOP OF SLAB
HFG	HIGH FINISHED GRADE
LFG	LOW FINISHED GRADE

NOTES:

1. CONTRACTOR TO REMOVE AND REPLACE ALL SIDEWALK NECESSARY FOR CONNECTION TO EXISTING.
2. ALL ADA ACCESSIBLE SIDEWALK CROSS SLOPES SHALL HAVE A MAXIMUM CROSS SLOPE OF 2.00% AND MAXIMUM LONGITUDINAL SLOPE OF 5.00%.
3. ALL ADA ACCESSIBLE PARKING AREAS SHALL NOT EXCEED 2.00% IN ANY DIRECTION.
4. CONTRACTOR TO PROVIDE FLAT A/C UNIT PADS FOR ALL A/C UNITS.
5. NO GRADES SHALL EXCEED 5:1 UNLESS OTHERWISE NOTED.
6. GRADING AND STORM SEWER IMPROVEMENTS SHALL BE STAKED, INCLUDING ALL HIGH POINTS AND KEY GRADE BREAKS.



MATCHLINE
SEE SHEET C5.04

DWG: F:\2021\04001-04500\021-0157-B\40-Design\AutoCAD\Final Plans\Sheets\GNC\X_C_GRD02_B2104157.dwg
DATE: Dec 06, 2022 9:33am XREFS: C:\XBASE_B2104157 C:\PBASE_B2104157 C:\SURF_B2104157
USER: moore C:\TBLK_B2104157

C_LSC01_B2104157 T_PBASE_02104157 with driveways

MATCHLINE ———
SEE SHEET C5.01

GRADING PLAN
FINAL DEVELOPMENT PLAN - BUILDING 2


SCANNELL DEVELOPMENT LEE'S SUMMIT LOGISTICS
NORTHWEST CORNER OF TUDOR ROAD AND MAIN STREET

LEE'S SUMMIT, MISSOURI

SHEET
C5.02

drawn by: SL
checked by: LM
approved by: SR
QA/QC by: MK
project no.: B21-04157
drawing @cGRD02_B2104157.dwg
date: 03.11.2022

REV. NO.	DATE	REVISIONS DESCRIPTION
1	06-29-2022	CITY COMMENTS
2	07-28-2022	CITY COMMENTS
3	09-13-2022	CITY COMMENTS
4	10-04-2022	CITY COMMENTS
5	10-19-2022	CITY COMMENTS
6	11-21-2022	ADDENDUM 1



SCANNELL
PROPERTIES

olsson

7301 West 133rd Street, Suite 200
Overland Park, KS 66213-4750
TEL 913.381.1170 www.olsson.com

DWG: F:\2021\04001-04500\021-04157-B\40-Design\AutoCAD\Final Plans\Sheets\GNV\C_GRD02_B2104157.dwg
DATE: Dec 06, 2022 9:34am XREFS: C:\BASE_B2104157 C:\PSURF_B2104157 C:\LSC01_B2104157 T:\PBASE_02104157 with driveways
USER: Imoore C:\TBLK_B2104157

MATCHLINE
SEE SHEET C5.01

MATCHLINE
SEE SHEET C5.04

STREAM CORRIDOR ENCROACHMENT

PROPOSED
RETAINING WALL C,
SEE SHEET C5.08
FOR DETAILS

KEY MAP
NOT TO SCALE

LEGEND

- PROPERTY LINE
SURROUNDING PROPERTY LINES
EXISTING UTILITY EASEMENT
PROPOSED CONTOUR
EXISTING CONTOUR
CONSTRUCT CONCRETE CURB & GUTTER
PROPOSED SANITARY SERVICE LINE
PROPOSED WATER SERVICE LINE
PROPOSED UNDERGROUND POWER SERVICE LINE
PROPOSED FIRE PROTECTION LINE
PROPOSED COMMUNICATIONS SERVICE LINE
GRADE BREAK LINE
RIDGE LINE
VALLEY LINE


SPOT ELEVATION LEGEND:

ALL SPOT ELEVATIONS ARE TOP OF PAVEMENT ELEVATION UNLESS NOTED OTHERWISE. RE: PLAN VIEW, LEGEND AND DETAILS FOR CURB TYPE AND TO CALCULATE TOP OF CURB ELEVATION.

- TC TOP OF CURB
FG FINISHED GRADE WITHIN GREENSPACE
TS TOP OF STRUCTURE
FC CURB DEPRESSED TO BE FLUSH WITH ADJACENT PAVEMENT
HP HIGH POINT
LP LOW POINT
ME± MATCH EXISTING
FFE FINISH FLOOR ELEVATION AT TOP OF SLAB
HFG HIGH FINISHED GRADE
LFG LOW FINISHED GRADE

NOTES:

- CONTRACTOR TO REMOVE AND REPLACE ALL SIDEWALK NECESSARY FOR CONNECTION TO EXISTING.
- ALL ADA ACCESSIBLE SIDEWALK CROSS SLOPES SHALL HAVE A MAXIMUM CROSS SLOPE OF 2.00% AND MAXIMUM LONGITUDINAL SLOPE OF 5.00%.
- ALL ADA ACCESSIBLE PARKING AREAS SHALL NOT EXCEED 2.00% IN ANY DIRECTION.
- CONTRACTOR TO PROVIDE FLAT A/C UNIT PADS FOR ALL A/C UNITS.
- NO GRADES SHALL EXCEED 5:1 UNLESS OTHERWISE NOTES.
- GRADING AND STORM SEWER IMPROVEMENTS SHALL BE STAKED, INCLUDING ALL HIGH POINTS AND KEY GRADE BREAKS.



GRADING PLAN
FINAL DEVELOPMENT PLAN - BUILDING 2

SCANNELL DEVELOPMENT LEE'S SUMMIT LOGISTICS
NORTHWEST CORNER OF TUDOR ROAD AND MAIN STREET

LEE'S SUMMIT, MISSOURI

drawn by: SL
checked by: LM
approved by: SR
QA/QC by: MK
project no.: B21-04157
drawing: GDR02_B2104157.dwg
date: 03.11.2022

SHEET
C5.03



REV. NO.	DATE	REVISIONS DESCRIPTION	BY
1	06-28-2022	CITY COMMENTS	
2	06-28-2022	CITY COMMENTS	
3	06-15-2022	CITY COMMENTS	
4	10-04-2022	CITY COMMENTS	
5	10-10-2022	CITY COMMENTS	
6	11-14-2022	CITY COMMENTS	
7	11-14-2022	CITY COMMENTS	


REVISIONS

2022


olsson

7301 West 133rd Street, Suite 200
Overland Park, KS 66213-7755

TEL 913.381.1170
www.olson.com



3 GRADING DETAIL



KEY MAP
NOT TO SCALE

LEGEND

- PROPERTY LINE
SURROUNDING PROPERTY LINES
EXISTING UTILITY EASEMENT
PROPOSED CONTOUR
EXISTING CONTOUR
CONSTRUCT CONCRETE CURB & GUTTER
PROPOSED SANITARY SERVICE LINE
PROPOSED WATER SERVICE LINE
PROPOSED UNDERGROUND POWER SERVICE LINE
PROPOSED FIRE PROTECTION LINE
PROPOSED COMMUNICATIONS SERVICE LINE
GRADE BREAK LINE
RIDGE LINE
VALLEY LINE


SPOT ELEVATION LEGEND:

ALL SPOT ELEVATIONS ARE TOP OF PAVEMENT ELEVATION UNLESS NOTED OTHERWISE. RE: PLAN VIEW, LEGEND AND DETAILS FOR CURB TYPE AND TO CALCULATE TOP OF CURB ELEVATION.


- TC TOP OF CURB
FG FINISHED GRADE WITHIN GREENSPACE
TS TOP OF STRUCTURE
FC CURB DEPRESSED TO BE FLUSH WITH ADJACENT PAVEMENT
HP HIGH POINT
LP LOW POINT
ME± MATCH EXISTING
FFE FINISH FLOOR ELEVATION AT TOP OF SLAB
HFG HIGH FINISHED GRADE
LFG LOW FINISHED GRADE

NOTES:

- CONTRACTOR TO REMOVE AND REPLACE ALL SIDEWALK NECESSARY FOR CONNECTION TO EXISTING.
- ALL ADA ACCESSIBLE SIDEWALK CROSS SLOPES SHALL HAVE A MAXIMUM CROSS SLOPE OF 2.00% AND MAXIMUM LONGITUDINAL SLOPE OF 5.00%.
- ALL ADA ACCESSIBLE PARKING AREAS SHALL NOT EXCEED 2.00% IN ANY DIRECTION.




DWG: F:\2021\04001-04500\021-04157-B\40-Design\AutoCAD\Final Plans\Sheets\GNVC\AC_GRD03_B2104157.dwg
DATE: Dec 06, 2022 9:35am
USER: Imoore
C:\BLK_B2104157
C:\BASE_B2104157
C:\PSURF_B2104157
XREFS: C:\BASE_B2104157
C:\PSURF_B2104157



Retaining Wall A									
NO.		STATION	NORTHING	EASTING	LENGTH	LINE/CHORD BEARING	DELTA	TANGENT	RADIUS
C9	PC=	0+00.00	53846.9303	54116.0500					
	PI=	1+58.73	53930.3253	54251.1054	263.00'	S81°17'22"E	80°48'38"	158.73'	186.47'
	PT=	2+63.00	53810.3212	54354.9982					
L10		2+63.00	53810.3212	54354.9982	54.68'	S39°32'39"E			
		3+17.68	53768.1562	54389.8110					

A RETAINING WALL DETAIL



KEY MAP
NOT TO SCALE

LEGEND

- PROPERTY LINE
- SURROUNDING PROPERTY LINES
- EXISTING UTILITY EASEMENT
- PROPOSED CONTOUR
- EXISTING CONTOUR
- CONSTRUCT CONCRETE CURB & GUTTER
- PROPOSED SANITARY SERVICE LINE
- PROPOSED WATER SERVICE LINE
- PROPOSED UNDERGROUND POWER SERVICE LINE
- PROPOSED FIRE PROTECTION LINE
- PROPOSED COMMUNICATIONS SERVICE LINE
- GRADE BREAK LINE
- RIDGE LINE
- VALLEY LINE

SPOT ELEVATION LEGEND:

ALL SPOT ELEVATIONS ARE TOP OF PAVEMENT ELEVATION UNLESS NOTED OTHERWISE. RE: PLAN VIEW, LEGEND AND DETAILS FOR CURB TYPE AND TO CALCULATE TOP OF CURB ELEVATION.

- TOP OF CURB
- FINISHED GRADE WITHIN GREENSPACE
- TOP OF STRUCTURE
- CURB DEPRESSED TO BE FLUSH WITH ADJACENT PAVEMENT
- HIGH POINT
- LOW POINT
- MATCH EXISTING
- FINISH FLOOR ELEVATION AT TOP OF SLAB
- HIGH FINISHED GRADE
- LOW FINISHED GRADE

NOTES:

- WALL TYPE, COLOR, AND MATERIAL SPECIFICATIONS TO BE DETERMINED BY OWNER AND DEVELOPER. CONTRACTOR TO COORDINATE ALL MATERIALS WITH OWNER AND DEVELOPER PRIOR TO CONSTRUCTION.
- WALL STATION VALUES AND GEOMETRY IS BOTTOM/FACE OF WALL. WALL ELEVATION INFORMATION SHOWN HERE IS FOR FINISH GRADE REFERENCE PURPOSES. VERIFY ANY REQUIRED STRUCTURAL DETAILS WITH STRUCTURAL ENGINEER.

olsson

7301 West 133rd Street, Suite 200
Overland Park, KS 66213-7755
TEL 913.381.1170
www.olson.com

SCANNELL
PROPERTIES



REVISIONS			
REV. NO.	DATE	REVISIONS DESCRIPTION	BY
1	06-28-2022	CITY COMMENTS	
2	06-28-2022	CITY COMMENTS	
3	06-15-2022	CITY COMMENTS	
4	10-04-2022	CITY COMMENTS	
5	10-18-2022	CITY COMMENTS	
6	11-11-2022	CITY COMMENTS	
7	11-11-2022	CITY COMMENTS	
2022			

RETAINING WALL DETAILS
FINAL DEVELOPMENT PLAN - BUILDING 2


SCANNELL DEVELOPMENT LEE'S SUMMIT LOGISTICS
NORTHWEST CORNER OF TUDOR ROAD AND MAIN STREET

LEE'S SUMMIT, MISSOURI

drawn by: SL
checked by: LM
approved by: SR
GNVC by: MK
project no.: B21-04157
drawing: GRD03_B2104157.dwg
date: 03.11.2022

SHEET
C5.07


DWG: F:\2021\04001-04500\021-04157-B\40-Design\AutoCAD\Final Plans\Sheets\GNVC\GRD03_B2104157.dwg
DATE: Dec 06, 2022 9:36am
USER: Imoore
C:\BLK_B2104157
C:\BASE_B2104157
C:\PSURF_B2104157
C:\LSC01_B2104157



RETAINING WALL B									
NO.		STATION	NORTHING	EASTING	LENGTH	LINE/CHORD BEARING	DELTA	TANGENT	RADIUS
L26		0+00.00 0+67.33	53757.1291 53711.2799	54322.3254 54371.6322	67.33'	S47°04'52"E			
C22	PC=PI=PT=	0+67.33 0+80.57 0+92.27	53711.2799 53702.2654 53703.3422	54371.6322 54381.3265 54394.5205	24.94'	S70°52'24"E	47°35'06"	13.24'	30.03'
C23	PC=PI=PT=	0+92.27 1+05.03 1+16.43	53703.3422 53703.9967 53695.3596	54394.5205 54407.2631 54416.6547	24.16'	S70°10'06"E	45°32'36"	12.76'	30.40'
L27		1+16.43 2+45.15	53695.3596 53607.7047	54416.6547 54510.9198	128.72'	S47°04'52"E			
C24	PC=PI=PT=	2+45.15 2+61.56 2+77.97	53607.7047 53596.5277 53584.7371	54510.9198 54522.9397 54534.3585	32.82'	S45°34'54"E	2°59'56"	16.41'	627.06'


C24	PC= 2+45.15 PI= 2+61.56 PT= 2+77.97	53607.7047 53596.5277 53584.7371	54510.9198 54522.9397 54534.3585	32.82'	S45°34'54"E	2°59'56"	16.41'	627.06'
C25	PC= 2+77.97 PI= 2+94.38 PT= 3+10.79	53584.7371 53572.7785 53560.1934	54534.3585 54545.6028 54556.1412	32.82'	S41°35'21"E	3°17'41"	16.41'	570.76'
C26	PC= 3+10.79 PI= 3+15.82 PT= 3+18.67	53560.1934 53556.2895 53553.1411	54556.1412 54559.3134 54555.3904	7.88'	S6°04'38"W	90°20'49"	5.03'	5.00'
L28	3+18.67 3+23.23	53553.1411 53550.2905	54555.3904 54551.8389	4.55'	S51°14'53"W			
C27	PC= 3+23.23 PI= 3+33.17 PT= 3+38.88	53550.2905 53544.0674 53536.2779	54551.8389 54544.0855 54550.2635	15.65'	S6°24'53"W	89°40'00"	9.94'	10.00'

B RETAINING WALL DETAIL



Retaining Wall C								
NO.	STATION	NORTHING	EASTING	LENGTH	LINE/CHORD BEARING	DELTA	TANGENT	RADIUS
L9	0+00.00 3+78.08	53402.9468 53145.4873	54086.1676 54363.0426	378.08'	S47°04'52"E			

C RETAINING WALL DETAIL



KEY MAP
NOT TO SCALE

LEGEND

- PROPERTY LINE
- SURROUNDING PROPERTY LINES
- EXISTING UTILITY EASEMENT
- PROPOSED CONTOUR
- EXISTING CONTOUR
- CONSTRUCT CONCRETE CURB & GUTTER
- PROPOSED SANITARY SERVICE LINE
- PROPOSED WATER SERVICE LINE
- PROPOSED UNDERGROUND POWER SERVICE LINE
- PROPOSED FIRE PROTECTION LINE
- PROPOSED COMMUNICATIONS SERVICE LINE
- GRADE BREAK LINE
- RIDGE
- RIDGE LINE
- VALLEY
- VALLEY LINE


SPOT ELEVATION LEGEND:

ALL SPOT ELEVATIONS ARE TOP OF PAVEMENT ELEVATION UNLESS NOTED OTHERWISE. RE: PLAN VIEW, LEGEND AND DETAILS FOR CURB TYPE AND TO CALCULATE TOP OF CURB ELEVATION.

- TC TOP OF CURB
- FG FINISHED GRADE WITHIN GREENSPACE
- TS TOP OF STRUCTURE
- FC CURB DERESSED TO BE FLUSH WITH ADJACENT PAVEMENT
- HP HIGH POINT
- LP LOW POINT
- ME± MATCH EXISTING
- FFE FINISH FLOOR ELEVATION AT TOP OF SLAB
- HFG HIGH FINISHED GRADE
- LFG LOW FINISHED GRADE

NOTES:

- WALL TYPE, COLOR, AND MATERIAL SPECIFICATIONS TO BE DETERMINED BY OWNER AND DEVELOPER. CONTRACTOR TO COORDINATE ALL MATERIALS WITH OWNER AND DEVELOPER PRIOR TO CONSTRUCTION.
- WALL STATION VALUES AND GEOMETRY IS BOTTOM/FACE OF WALL. WALL ELEVATION INFORMATION SHOWN HERE IS FOR FINISH GRADE REFERENCE PURPOSES. VERIFY ANY REQUIRED STRUCTURAL DETAILS WITH STRUCTURAL ENGINEER.



olsson

7301 West 133rd Street, Suite 200
Overland Park, KS 66213-7755
TEL 913.381.1170
www.olson.com

SCANNELL

PROPERTIES

STATE OF MISSOURI

Mitchell Alan
Professional Engineer
NUMBER
PE-2008010164
2-2-22

RETAINING WALL DETAILS

FINAL DEVELOPMENT PLAN - BUILDING 2

SCANNELL DEVELOPMENT LEE'S SUMMIT LOGISTICS

NORTHWEST CORNER OF TUDOR ROAD AND MAIN STREET

LEE'S SUMMIT, MISSOURI

drawn by: SL

checked by: LM

approved by: SR

QA/QC by: MK


project no.: B21-04157

drawing no.: GRD03_B2104157.dwg

date: 03.11.2022

2022

SHEET
C5.08



- UTILITY PLAN LEGEND
- PROPERTY LINE
 - EXISTING SANITARY SEWER
 - EXISTING STORM
 - EXISTING WATER PIPE
 - EXISTING OVERHEAD POWER LINE
 - EXISTING UNDERGROUND POWER LINE
 - STORM SEWER
 - STORM HEADER PIPE AND ROOF DRAINS
 - UNDERGROUND POWER CONDUIT
 - NATURAL GAS PIPE
 - CABLE TELEVISION CONDUIT
 - WATER PIPE
 - SANITARY SEWER SERVICE LINE
 - SANITARY SEWER MAIN (PER SHEETS C6.05-C6.09)

NOTE:
1. NO GAS WELLS ARE PRESENT ON THE PROPERTY BASED ON THE "ENVIRONMENTAL IMPACT STUDY OF ABANDONED OIL AND GAS WELLS IN LEE'S SUMMIT, MISSOURI", BY EDWARD ALTON MAY, JR. DATED 1995.

OVERALL UTILITY PLAN			BY		
FINAL DEVELOPMENT PLAN - BUILDING 2					
SCANNELL DEVELOPMENT LEE'S SUMMIT LOGISTICS					
NORTHWEST CORNER OF TUDOR ROAD AND MAIN STREET					
LEE'S SUMMIT, MISSOURI					
			2022		
			REVISIONS		
REV. NO.	DATE	REVISIONS DESCRIPTION			
1	06-28-2022	CITY COMMENTS			
2	06-28-2022	CITY COMMENTS			
3	06-15-2022	CITY COMMENTS			
4	10-04-2022	CITY COMMENTS			
5	10-18-2022	CITY COMMENTS			
6	11-15-2022	CITY COMMENTS			
7	11-15-2022	CITY COMMENTS			

drawn by: SL
checked by: LM
approved by: SR
GNVC by: MM
project no.: B21-04157
drawing: 01_B2104157.dwg
date: 03.11.2022

SHEET
C6.00




olsson

7301 West 133rd Street, Suite 200
Overland Park, KS 66213-7755
TEL 913.381.1170
www.olson.com

DWG: F:\2021\04001-04500\021-04157-B\40-Design\AutoCAD\Final Plans\Sheets\GNVC\AC_U\T\01_B2104157.dwg
DATE: Dec 06, 2022 9:36am
XREFS: C:\BASE_B2104157 C:\BASE_B2104157 C:\PSURF_B2104157 C:\LSC01_B2104157
USER: Imoore C:\TBLK_B2104157

MATCHLINE
SEE SHEET C6.03

MATCHLINE
SEE SHEET C6.02




KEY MAP
NOT TO SCALE

UTILITY PLAN LEGEND

- PROPERTY LINE
- SS EXISTING SANITARY SEWER
- EXISTING STORM
- W EXISTING WATER PIPE
- P-OH EXISTING OVERHEAD POWER LINE
- P-UG EXISTING UNDERGROUND POWER LINE
- STORM SEWER
- SD STORM HEADER PIPE AND ROOF DRAINS
- P-UG UNDERGROUND POWER CONDUIT
- G NATURAL GAS PIPE
- CATV CABLE TELEVISION CONDUIT
- W WATER PIPE
- SS SANITARY SEWER SERVICE LINE
- SS SANITARY SEWER MAIN (PER SHEETS C6.05-C6.09)

KEYNOTES

- WATER**
- W1 APPROXIMATE LOCATION OF EXISTING 12" PUBLIC WATERMAIN. CONTRACTOR SHALL COORDINATE WITH CITY ON FINAL LOCATION.
 - W2 APPROXIMATE LOCATION OF PROPOSED 10" PRIVATE PRESSURIZED FIRE PROTECTION LOOP. INSTALL 1,770 LF ± 10" C900 DR 14. CONTRACTOR SHALL COORDINATE WITH CITY ON FINAL LOCATION.
 - W3 DOMESTIC WATER SERVICE. CONNECT TO MAIN 12"x 2" TAP. AND INSTALL 15± LF OF 2" SOFT TYPE "K" COPPER PIPE TO THE PROPOSED DISPLACEMENT WATER METER PROVIDED BY THE CITY. CONTRACTOR SHALL COORDINATE WITH CITY ON CONNECTION.
 - W4 INSTALL 2" COMPOUND WATER METER IN A METER WELL PROVIDED BY THE CITY. 10± LF OF 2" SOFT TYPE "K" COPPER PIPE AFTER THE METER AND THEN 100± LF OF 4" IPS HDPE DR11 TO THE BUILDING CONNECTION POINT PER CITY WATER STANDARDS AND SPECIFICATIONS.
 - W5 CONNECT TO MAIN 12"x 12" TEE. AND INSTALL 125± LF OF 12" C900 DR 14 FOR FIRE PROTECTION WATER SERVICE. CONTRACTOR SHALL COORDINATE WITH CITY ON CONNECTION.
 - W6 INSTALL DOUBLE CHECK VALVE ASSEMBLY IN VAULT TO MEET CITY WATER STANDARDS AND SPECIFICATIONS. TAMPER SWITCHES AND THEIR ASSOCIATED WIRING WILL BE PROVIDED FOR THE SHUT-OFF VALUES IN THE VAULT. COORDINATE INSTALL AND BACKFLOW PREVENTION WITH CITY WATER AND MEP PLANS.
 - W7 APPROXIMATE LOCATION OF PROPOSED YARD FIRE HYDRANT BY CONTRACTOR. YARD HYDRANTS SHALL MATCH CITY STANDARD AND DETAILS. SHALL BE PAINTED RED.
 - W8 APPROXIMATE LOCATION OF PROPOSED PRIVATE FIRE HYDRANT BY CONTRACTOR. PRIVATE HYDRANTS SHALL MATCH CITY STANDARD AND DETAILS. SHALL BE PAINTED YELLOW WITH A SILVER TOP.
 - W9 PUBLIC FIRE HYDRANTS. SEE SEPARATE PLANS.
 - W10 CONNECT TO MAIN 12"x 2" TAP AND INSTALL 15± LF OF 2" SOFT TYPE "K" COPPER PIPE AND CONNECT TO THE DISPLACEMENT IRRIGATION METER.
 - W11 INSTALL DOUBLE CHECK BACKFLOW PREVENTER, BELOW GRADE, IN APPROVED CONCRETE VAULT PER CITY REQUIREMENTS.
- GAS**
- G1 APPROXIMATE LOCATION OF PROPOSED GAS MAIN. CONTRACTOR SHALL COORDINATE WITH ENGINEER ON FINAL LOCATION OF GAS MAIN AND CONTACT ENGINEER WITH ANY CHANGES.
 - G1 INSTALL ±100 LF OF NEW GAS SERVICE TO PROPOSED GAS MAIN. COORDINATE WITH UTILITY COMPANY FOR EXACT LOCATION, ROUTING, AND CONNECTION.
- ELECTRIC**
- E1 INSTALL APPROXIMATELY 100± LF OF PRIMARY ELECTRICAL SERVICE PER EVERY/LEE'S SUMMIT DESIGN STANDARDS AND SPECIFICATIONS. VERIFY CONDUIT SIZE AND ROUTING WITH CITY AND EVERY. THE ALIGNMENT IS APPROXIMATE. CONTRACTOR SHALL COORDINATE ELECTRICAL SERVICE ROUTE DIRECTLY WITH CITY AND EVERY.
 - E2 PROPOSED SITE LIGHTING. REFERENCE SITE LIGHTING PLANS FOR DETAILS.
 - E3 INSTALL APPROXIMATELY 1000± LF OF SECONDARY ELECTRICAL SERVICE PER EVERY/LEE'S SUMMIT DESIGN STANDARDS AND SPECIFICATIONS. VERIFY CONDUIT SIZE AND ROUTING WITH CITY AND EVERY. THE ALIGNMENT IS APPROXIMATE. CONTRACTOR SHALL COORDINATE ELECTRICAL SERVICE ROUTE DIRECTLY WITH CITY AND EVERY.
- STORM ROOF DRAINS**
- RD1 INSTALL 12" HDPE FROM THE ROOF DRAIN TO STORM HEADER PIPE WITH A 1.0% MINIMUM SLOPE. MINIMUM COVER OF PIPE IS 2.5' AND SHALL COORDINATE WITH ALL OTHER IMPROVEMENTS. INCLUDE BENDS, FITTINGS, AND OTHER PARTS FOR INSTALLATION. SEE MEP PLANS FOR ROOF DRAIN LOCATIONS AND DETAILS.
 - RD2 INSTALL BACK OF CURB PERFORATED PIPE WITH SOCK AND TIE INTO CLOSEST PRIVATE STORM SEWER.
- SANITARY SEWER SERVICE**
- SS1 SANITARY SEWER SERVICE LINES. REFERENCE SHEETS C6.08 -C6.09 FOR INFORMATION ON SANITARY SEWER SERVICE LINES.
 - SS2 PRIVATE SANITARY SEWER MAIN EXTENSION. REFERENCE SHEETS C6.05 -C6.07 PRIVATE SANITARY SEWER SHEETS FOR MORE INFORMATION.
- EXISTING UTILITIES**
- X1 EXISTING SANITARY SEWER MAIN
 - X2 EXISTING STORM SEWER
 - X3 EXISTING WATER MAIN
- NOTE:**
- FDC SHALL BE LOCATED WITH 100' OF FIRE HYDRANT.
 - ALL ISSUES PERTAINING TO LIFE SAFETY AND PROPERTY PROTECTION FROM THE HAZARDS OF FIRE, EXPLOSION OR DANGEROUS CONDITIONS IN NEW AND EXISTING BUILDINGS, STRUCTURES, AND PREMISES, AND TO THE SAFETY TO FIRE FIGHTERS AND EMERGENCY RESPONDERS DURING EMERGENCY OPERATIONS, SHALL BE ACCORDANCE WITH THE 2018 INTERNATIONAL FIRE CODE.



UTILITY PLAN
FINAL DEVELOPMENT PLAN - BUILDING 2

SCANNELL DEVELOPMENT LEE'S SUMMIT LOGISTICS
NORTHWEST CORNER OF TUDOR ROAD AND MAIN STREET
LEE'S SUMMIT, MISSOURI

REV.	NO.	DATE	REVISIONS DESCRIPTION
1	06-25-2022	CITY COMMENTS	
2	06-25-2022	CITY COMMENTS	
3	06-15-2022	CITY COMMENTS	
4	10-04-2022	CITY COMMENTS	
5	10-10-2022	CITY COMMENTS	
6	11-15-2022	CITY COMMENTS	
7	11-15-2022	DESIGNER	





SCANNELL
PROPERTIES

olsson

7301 West 133rd Street, Suite 200
Overland Park, KS 66213-4756
TEL 913.381.1170 www.olson.com

drawn by: SL
checked by: LM
approved by: SR
GNOC by: MW
project no.: B21-04157
drawing: 02101_01_B2104157.dwg
date: 03.11.2022

SHEET
C6.01



KEY MAP
NOT TO SCALE

UTILITY PLAN LEGEND

- PROPERTY LINE
- SS EXISTING SANITARY SEWER
- SS EXISTING STORM
- W EXISTING WATER PIPE
- P-OH EXISTING OVERHEAD POWER LINE
- P-UG EXISTING UNDERGROUND POWER LINE
- SD STORM SEWER
- SD STORM HEADER PIPE AND ROOF DRAINS
- P-UG UNDERGROUND POWER CONDUIT
- G NATURAL GAS PIPE
- CATV CABLE TELEVISION CONDUIT
- W WATER PIPE
- SS SANITARY SEWER SERVICE LINE
- SS SANITARY SEWER MAIN (PER SHEETS C6.05-C6.09)

KEYNOTES

- WATER**
- W1 APPROXIMATE LOCATION OF EXISTING 12" PUBLIC WATERMAIN. CONTRACTOR SHALL COORDINATE WITH CITY ON FINAL LOCATION.
 - W2 APPROXIMATE LOCATION OF PROPOSED 10" PRIVATE PRESSURIZED FIRE PROTECTION LOOP. INSTALL 1,770 LF \pm 10" C900 DR 14. CONTRACTOR SHALL COORDINATE WITH CITY ON FINAL LOCATION.
 - W3 DOMESTIC WATER SERVICE. CONNECT TO MAIN 12"x 2" TAP. AND INSTALL 15 \pm LF OF 2" SOFT TYPE "K" COPPER PIPE TO THE PROPOSED DISPLACEMENT WATER METER PROVIDED BY THE CITY. CONTRACTOR SHALL COORDINATE WITH CITY ON CONNECTION.
 - W4 INSTALL 2" COMPOUND WATER METER IN A METER WELL PROVIDED BY THE CITY. 10 \pm LF OF 2" SOFT TYPE "K" COPPER PIPE AFTER THE METER AND THEN 100 \pm LF OF 4" IPS HDPE DR11 TO THE BUILDING CONNECTION POINT PER CITY WATER STANDARDS AND SPECIFICATIONS.
 - W5 CONNECT TO MAIN 12"x 12" TEE. AND INSTALL 125 \pm LF OF 12" C900 DR 14 FOR FIRE PROTECTION WATER SERVICE. CONTRACTOR SHALL COORDINATE WITH CITY ON CONNECTION.
 - W6 INSTALL DOUBLE CHECK VALVE ASSEMBLY IN VAULT TO MEET CITY WATER STANDARDS AND SPECIFICATIONS. TAMPER SWITCHES AND THEIR ASSOCIATED WIRING WILL BE PROVIDED FOR THE SHUT-OFF VALVES IN THE VAULT. COORDINATE INSTALL AND BACKFLOW PREVENTION WITH CITY WATER AND MEP PLANS.
 - W7 APPROXIMATE LOCATION OF PROPOSED YARD FIRE HYDRANT BY CONTRACTOR. YARD HYDRANTS SHALL MATCH CITY STANDARD AND DETAILS. SHALL BE PAINTED RED.
 - W8 APPROXIMATE LOCATION OF PROPOSED PRIVATE FIRE HYDRANT BY CONTRACTOR. PRIVATE HYDRANTS SHALL MATCH CITY STANDARD AND DETAILS. SHALL BE PAINTED YELLOW WITH A SILVER TOP.
 - W9 PUBLIC FIRE HYDRANTS. SEE SEPARATE PLANS.
 - W10 CONNECT TO MAIN 12"x 2" TAP AND INSTALL 15 \pm LF OF 2" SOFT TYPE "K" COPPER PIPE AND CONNECT TO THE DISPLACEMENT IRRIGATION METER.
 - W11 INSTALL DOUBLE CHECK BACKFLOW PREVENTER, BELOW GRADE, IN APPROVED CONCRETE VAULT PER CITY REQUIREMENTS.
- GAS**
- G1 APPROXIMATE LOCATION OF PROPOSED GAS MAIN. CONTRACTOR SHALL COORDINATE WITH ENGINEER ON FINAL LOCATION OF GAS MAIN AND CONTACT ENGINEER WITH ANY CHANGES.
 - G2 INSTALL \pm 100 LF OF NEW GAS SERVICE TO PROPOSED GAS MAIN. COORDINATE WITH UTILITY COMPANY FOR EXACT LOCATION, ROUTING, AND CONNECTION.
- ELECTRIC**
- E1 INSTALL APPROXIMATELY 100 \pm LF OF PRIMARY ELECTRICAL SERVICE PER EVERGY/LEE'S SUMMIT DESIGN STANDARDS AND SPECIFICATIONS. VERIFY CONDUIT SIZE AND ROUTING WITH CITY AND EVERGY. THE ALIGNMENT IS APPROXIMATE. CONTRACTOR SHALL COORDINATE ELECTRICAL SERVICE ROUTE DIRECTLY WITH CITY AND EVERGY.
 - E2 PROPOSED SITE LIGHTING. REFERENCE SITE LIGHTING PLANS FOR DETAILS.
 - E3 INSTALL APPROXIMATELY 1000 \pm LF OF SECONDARY ELECTRICAL SERVICE PER EVERGY/LEE'S SUMMIT DESIGN STANDARDS AND SPECIFICATIONS. VERIFY CONDUIT SIZE AND ROUTING WITH CITY AND EVERGY. THE ALIGNMENT IS APPROXIMATE. CONTRACTOR SHALL COORDINATE ELECTRICAL SERVICE ROUTE DIRECTLY WITH CITY AND EVERGY.
- STORM ROOF DRAINS**
- RD1 INSTALL 12" HDPE FROM THE ROOF DRAIN TO STORM HEADER PIPE WITH A 1.0% MINIMUM SLOPE. MINIMUM COVER OF PIPE IS 2.5' AND SHALL COORDINATE WITH ALL OTHER IMPROVEMENTS. INCLUDE BENDS, FITTINGS, AND OTHER PARTS FOR INSTALLATION. SEE MEP PLANS FOR ROOF DRAIN LOCATIONS AND DETAILS.
 - RD2 INSTALL BACK OF CURB PERFORATED PIPE WITH SOCK AND TIE INTO CLOSEST PRIVATE STORM SEWER.
- SANITARY SEWER SERVICE**
- SS1 SANITARY SEWER SERVICE LINES. REFERENCE SHEETS C6.08 -C6.09 FOR INFORMATION ON SANITARY SEWER SERVICE LINES.
 - SS2 PRIVATE SANITARY SEWER MAIN EXTENSION. REFERENCE SHEETS C6.05 -C6.07 PRIVATE SANITARY SEWER SHEETS FOR MORE INFORMATION.
- EXISTING UTILITIES**
- X1 EXISTING SANITARY SEWER MAIN
 - X2 EXISTING STORM SEWER
 - X3 EXISTING WATER MAIN
- NOTE:**
- FDC SHALL BE LOCATED WITH 100' OF FIRE HYDRANT.
 - ALL ISSUES PERTAINING TO LIFE SAFETY AND PROPERTY PROTECTION FROM THE HAZARDS OF FIRE, EXPLOSION OR DANGEROUS CONDITIONS IN NEW AND EXISTING BUILDINGS, STRUCTURES, AND PREMISES, AND TO THE SAFETY TO FIRE FIGHTERS AND EMERGENCY RESPONDERS DURING EMERGENCY OPERATIONS, SHALL BE ACCORDANCE WITH THE 2018 INTERNATIONAL FIRE CODE.

7301 West 133rd Street, Suite 200
Overland Park, KS 66213-7755
TEL 913.381.1170 www.olsson.com

SCANNELL PROPERTIES

STATE OF MISSOURI
MITCHELL ALAN MINK
No. PE-2008010164
Exp. 12-2-22
PROFESSIONAL ENGINEER

REV	NO.	DATE	DESCRIPTION
1	06-25-2022	CITY COMMENTS	
2	06-25-2022	CITY COMMENTS	
3	06-13-2022	CITY COMMENTS	
4	10-04-2022	CITY COMMENTS	
5	10-18-2022	CITY COMMENTS	
6	11-11-2022	DESIGNER	


UTILITY PLAN
FINAL DEVELOPMENT PLAN - BUILDING 2
SCANNELL DEVELOPMENT LEE'S SUMMIT LOGISTICS
NORTHWEST CORNER OF TUDOR ROAD AND MAIN STREET
LEE'S SUMMIT, MISSOURI

drawn by: SM
checked by: LM
approved by: SR
check by: MM
project no.: B21-04157
drawing: 02TTL01_B2104157.dwg
date: 03.11.2022

SHEET
C6.02


SEE SHEET C6.01

MATCHLINE
SEE SHEET 06.04



KEY MAP
NOT TO SCALE

UTILITY PLAN LEGEND



—	—	PROPERTY LINE
SS	SS	EXISTING SANITARY SEWER
—	—	EXISTING STORM
—	W	EXISTING WATER PIPE
—	P-OH	EXISTING OVERHEAD POWER LINE
—	P-UG	EXISTING UNDERGROUND POWER LINE
—	—	STORM SEWER
SD	SD	STORM HEADER PIPE AND ROOF DRAINS
—	P-UG	UNDERGROUND POWER CONDUIT
G	G	NATURAL GAS PIPE
—	DTV	CABLE TELEVISION CONDUIT
W	W	WATER PIPE
SS	SS	SANITARY SEWER SERVICE LINE
●	SS	SANITARY SEWER MAIN (PER SHEETS C6.05—C6.09)

KEYNOTES

WATER

- | | |
|-----|---|
| W1 | APPROXIMATE LOCATION OF EXISTING 12" PUBLIC WATERMAIN. CONTRACTOR SHALL COORDINATE WITH CITY ON FINAL LOCATION. |
| W2 | APPROXIMATE LOCATION OF PROPOSED 10" PRIVATE PRESSURIZED FIRE PROTECTION LOOP. INSTALL 1,770 LF ± 10" C900 DR 14. CONTRACTOR SHALL COORDINATE WITH CITY ON FINAL LOCATION. |
| W3 | DOMESTIC WATER SERVICE. CONNECT TO MAIN 12" x 2" TAP, AND INSTALL 15± LF OF 2" SOFT TYPE "K" COPPER PIPE TO THE PROPOSED DISPLACEMENT WATER METER PROVIDED BY THE CITY. CONTRACTOR SHALL COORDINATE WITH CITY ON CONNECTION. |
| W4 | INSTALL 2" COMPOUND WATER METER IN A METER WELL PROVIDED BY THE CITY, 10± LF OF 2" SOFT TYPE "K" COPPER PIPE AFTER THE METER AND THEN 100± LF OF 4" IPS HDPE DR11 TO THE BUILDING CONNECTION POINT PER CITY WATER STANDARDS AND SPECIFICATIONS. |
| W5 | CONNECT TO MAIN 12" x 12" TEE, AND INSTALL 125± LF OF 12" C900 DR 14 FOR FIRE PROTECTION WATER SERVICE. CONTRACTOR SHALL COORDINATE WITH CITY ON CONNECTION. |
| W6 | INSTALL DOUBLE CHECK VALVE ASSEMBLY IN VAULT TO MEET CITY WATER STANDARDS AND SPECIFICATIONS. TAMPER SWITCHES AND THEIR ASSOCIATE WIRING WILL BE PROVIDED FOR THE SHUT-OFF VALVES IN THE VAULT. COORDINATE INSTALL AND BACKFLOW PREVENTION WITH CITY WATER AND MDP PLANS. |
| W7 | APPROXIMATE LOCATION OF PROPOSED YARD FIRE HYDRANT BY CONTRACTOR. YARD HYDRANTS SHALL MATCH CITY STANDARD AND DETAILS SHALL BE PAINTED RED. |
| W8 | APPROXIMATE LOCATION OF PROPOSED PRIVATE FIRE HYDRANT BY CONTRACTOR. PRIVATE HYDRANTS SHALL MATCH CITY STANDARD AND DETAILS. SHALL BE PAINTED YELLOW WITH A SILVER TOP. |
| W9 | PUBLIC FIRE HYDRANTS. SEE SEPARATE PLANS. |
| W10 | CONNECT TO MAIN 12" x 2" TAP AND INSTALL 15± LF OF 2"SOFT TYPE "K" COPPER PIPE AND connect to the DISPLACEMENT IRRIGATION METER. |
| W11 | INSTALL DOUBLE CHECK BACKFLOW PREVENTER, BELOW GRADE, IN APPROVE CONCRETE VAULT PER CITY REQUIREMENTS. |

GAS

- G1 APPROXIMATE LOCATION OF PROPOSED GAS MAIN. CONTRACTOR SHALL COORDINATE WITH ENGINEER ON FINAL LOCATION OF GAS MAIN AND CONTACT ENGINEER WITH ANY CHANGES.
- G1 INSTALL ±100 LF OF NEW GAS SERVICE TO PROPOSED GAS MAIN. COORDINATE WITH UTILITY COMPANY FOR EXACT LOCATION, ROUTING, AND CONNECTION.

ELECTRIC

- | | |
|----|---|
| E1 | INSTALL APPROXIMATELY 100± LF OF PRIMARY ELECTRICAL SERVICE PER EVERY/LC'S SUMMIT DESIGN STANDARDS AND SPECIFICATIONS. VERIFY CONDUIT SIZE AND ROUTING WITH CITY AND EVERY. THE ALIGNMENT IS APPROXIMATE. CONTRACTOR SHALL COORDINATE ELECTRICAL SERVICE ROUTE DIRECTLY WITH CITY AND EVERY. |
| E2 | PROPOSED SITE LIGHTING. REFERENCE SITE LIGHTING PLANS FOR DETAILS. |
| E3 | INSTALL APPROXIMATELY 1000± LF OF SECONDARY ELECTRICAL SERVICE PER EVERY/LC'S SUMMIT DESIGN STANDARDS AND SPECIFICATIONS. VERIFY CONDUIT SIZE AND ROUTING WITH CITY AND EVERY. THE ALIGNMENT IS APPROXIMATE. CONTRACTOR SHALL COORDINATE ELECTRICAL SERVICE ROUTE DIRECTLY WITH CITY AND EVERY. |

STORM ROOF DRAINS

- RD1 INSTALL 12" HDPE FROM THE ROOF DRAIN TO STORM HEADER PIPE WITH A 1.0% MINIMUM SLOPE. MINIMUM COVER OF PIPE IS 2.5' AND SHALL COORDINATE WITH ALL OTHER IMPROVEMENTS. INCLUDE BENDS, FITTINGS, AND OTHER PARTS FOR INSTALLATION. SEE MEP PLANS FOR ROOF DRAIN LOCATIONS AND DETAILS.
- RD2 INSTALL BACK OF CURB PERFORATED PIPE WITH SOCK AND TIE INTO CLOSEST PRIVATE STORM SEWER.

SANITARY SEWER SERVICE

- SS1 SANITARY SEWER SERVICE LINES. REFERENCE SHEETS C6.08 -C6.09 FOR INFORMATION ON SANITARY SEWER SERVICE LINES.
- SS2 PRIVATE SANITARY SEWER MAIN EXTENSION. REFERENCE SHEETS C6.05 -C6.07 PRIVATE SANITARY SEWER SHEETS FOR MORE INFORMATION.

EXISTING UTILITIES

- X1 EXISTING SANITARY SEWER MAIN
X2 EXISTING STORM SEWER
X3 EXISTING WATER MAIN


NOTE:

1. FDC SHALL BE LOCATED WITH 100' OF FIRE HYDRANT.
2. ALL ISSUES PERTAINING TO LIFE SAFETY AND PROPERTY PROTECTION FROM THE HAZARDS OF FIRE, EXPLOSION OR DANGEROUS CONDITIONS IN NEW AND EXISTING BUILDINGS, STRUCTURES, AND PREMISES, AND TO THE SAFETY TO FIRE FIGHTERS AND EMERGENCY RESPONDERS DURING EMERGENCY OPERATIONS, SHALL BE ACCORDANCE WITH THE 2018 INTERNATIONAL FIRE CODE.



0' 10' 20' 40'

SCALE IN FEET



SCANNELL
PROPERTIES





REV. NO.	DATE	REVISIONS DESCRIPTION	BY
1	08-25-2022	CITY COMMENTS	
2	07-26-2022	CITY COMMENTS	
3	09-13-2022	CITY COMMENTS	
4	10-04-2022	CITY COMMENTS	
5	10-15-2022	CITY COMMENTS	
6	11-21-2022	ADDENDUM 1	
REVISIONS			

UTILITY PLAN FINAL DEVELOPMENT PLAN - BUILDING 2	2022
SCANNELL DEVELOPMENT LEE'S SUMMIT LOGISTICS NORTHWEST CORNER OF TUDOR ROAD AND MAIN STREET	LEE'S SUMMIT MISSOURI

drawn by: _____ SL
checked by: _____ LM
approved by: _____ SR
QA/QC by: _____ MK
project no.: _____ B21-04157
drawing @_UTIL_01 B2104157.dwg
date: _____ 03.11.2022

SHEET
C6.03

DWG: F:\2021\04001-04500\021-04157-B\40-Design\AutoCAD\Final Plans\Sheets\GNVC\U_T\01_B2104157.dwg
DATE: Dec 06, 2022 9:37am
USER: Imoore
C:\BLK_B2104157
C:\BASE_B2104157
C:\PSURF_B2104157
XREFS: C:\BASE_B2104157
C:\PSURF_B2104157
C:\LSC01_B2104157



- KEY MAP**
NOT TO SCALE
- UTILITY PLAN LEGEND**
- PROPERTY LINE
 - SS --- EXISTING SANITARY SEWER
 - EXISTING STORM
 - W --- EXISTING WATER PIPE
 - P-OH --- EXISTING OVERHEAD POWER LINE
 - P-UG --- EXISTING UNDERGROUND POWER LINE
 - STORM SEWER
 - SD --- STORM HEADER PIPE AND ROOF DRAINS
 - P-UG --- UNDERGROUND POWER CONDUIT
 - G --- NATURAL GAS PIPE
 - CATV --- CABLE TELEVISION CONDUIT
 - W --- WATER PIPE
 - SS --- SANITARY SEWER SERVICE LINE
 - SS --- SANITARY SEWER MAIN (PER SHEETS C6.05-C6.09)

- KEYNOTES**
- WATER**
- (W1) APPROXIMATE LOCATION OF EXISTING 12" PUBLIC WATERMAIN. CONTRACTOR SHALL COORDINATE WITH CITY ON FINAL LOCATION.
 - (W2) APPROXIMATE LOCATION OF PROPOSED 10" PRIVATE PRESSURIZED FIRE PROTECTION LOOP. INSTALL 1,770 LF ± 10" C900 DR 14. CONTRACTOR SHALL COORDINATE WITH CITY ON FINAL LOCATION.
 - (W3) DOMESTIC WATER SERVICE. CONNECT TO MAIN 12"x 2" TAP, AND INSTALL 15± LF OF 2" SOFT TYPE "K" COPPER PIPE TO THE PROPOSED DISPLACEMENT WATER METER PROVIDED BY THE CITY. CONTRACTOR SHALL COORDINATE WITH CITY ON CONNECTION.
 - (W4) INSTALL 2" COMPOUND WATER METER IN A METER WELL PROVIDED BY THE CITY, 10± LF OF 2" SOFT TYPE "K" COPPER PIPE AFTER THE METER AND THEN 100± LF OF 4" IPS HDPE DR11 TO THE BUILDING CONNECTION POINT PER CITY WATER STANDARDS AND SPECIFICATIONS.
 - (W5) CONNECT TO MAIN 12"x 2" TEE, AND INSTALL 125± LF OF 12" C900 DR 14 FOR FIRE PROTECTION WATER SERVICE. CONTRACTOR SHALL COORDINATE WITH CITY ON CONNECTION.
 - (W6) INSTALL DOUBLE CHECK VALVE ASSEMBLY IN VAULT TO MEET CITY WATER STANDARDS AND SPECIFICATIONS. TAMPER SWITCHES AND THEIR ASSOCIATED WIRING WILL BE PROVIDED FOR THE SHUT-OFF VALUES IN THE VAULT. COORDINATE INSTALL AND BACKFLOW PREVENTION WITH CITY WATER AND MEP PLANS.
 - (W7) APPROXIMATE LOCATION OF PROPOSED YARD FIRE HYDRANT BY CONTRACTOR. YARD HYDRANTS SHALL MATCH CITY STANDARD AND DETAILS. SHALL BE PAINTED RED.
 - (W8) APPROXIMATE LOCATION OF PROPOSED PRIVATE FIRE HYDRANT BY CONTRACTOR. PRIVATE HYDRANTS SHALL MATCH CITY STANDARD AND DETAILS. SHALL BE PAINTED YELLOW WITH A SILVER TOP.
 - (W9) PUBLIC FIRE HYDRANTS. SEE SEPARATE PLANS.
 - (W10) CONNECT TO MAIN 12"x 2" TAP AND INSTALL 15± LF OF 2" SOFT TYPE "K" COPPER PIPE AND CONNECT TO THE DISPLACEMENT IRRIGATION METER.
 - (W11) INSTALL DOUBLE CHECK BACKFLOW PREVENTER, BELOW GRADE, IN APPROVED CONCRETE VAULT PER CITY REQUIREMENTS.
- GAS**
- (G1) APPROXIMATE LOCATION OF PROPOSED GAS MAIN. CONTRACTOR SHALL COORDINATE WITH ENGINEER ON FINAL LOCATION OF GAS MAIN AND CONTACT ENGINEER WITH ANY CHANGES.
 - (G1) INSTALL ±100 LF OF NEW GAS SERVICE TO PROPOSED GAS MAIN. COORDINATE WITH UTILITY COMPANY FOR EXACT LOCATION, ROUTING, AND CONNECTION.
- ELECTRIC**
- (E1) INSTALL APPROXIMATELY 100± LF OF PRIMARY ELECTRICAL SERVICE PER EVERGY/LEE'S SUMMIT DESIGN STANDARDS AND SPECIFICATIONS. VERIFY CONDUIT SIZE AND ROUTING WITH CITY AND EVERGY. THE ALIGNMENT IS APPROXIMATE. CONTRACTOR SHALL COORDINATE ELECTRICAL SERVICE ROUTE DIRECTLY WITH CITY AND EVERGY.
 - (E2) PROPOSED SITE LIGHTING. REFERENCE SITE LIGHTING PLANS FOR DETAILS.
 - (E3) INSTALL APPROXIMATELY 1000± LF OF SECONDARY ELECTRICAL SERVICE PER EVERGY/LEE'S SUMMIT DESIGN STANDARDS AND SPECIFICATIONS. VERIFY CONDUIT SIZE AND ROUTING WITH CITY AND EVERGY. THE ALIGNMENT IS APPROXIMATE. CONTRACTOR SHALL COORDINATE ELECTRICAL SERVICE ROUTE DIRECTLY WITH CITY AND EVERGY.
- STORM ROOF DRAINS**
- (RD1) INSTALL 12" HDPE FROM THE ROOF DRAIN TO STORM HEADER PIPE WITH A 1.0% MINIMUM SLOPE. MINIMUM COVER OF PIPE IS 2.5' AND SHALL COORDINATE WITH ALL OTHER IMPROVEMENTS. INCLUDE BENDS, FITTINGS, AND OTHER PARTS FOR INSTALLATION. SEE MEP PLANS FOR ROOF DRAIN LOCATIONS AND DETAILS.
 - (RD2) INSTALL BACK OF CURB PERFORATED PIPE WITH SOCK AND TIE INTO CLOSEST PRIVATE STORM SEWER.
- SANITARY SEWER SERVICE**
- (SS1) SANITARY SEWER SERVICE LINES. REFERENCE SHEETS C6.08 -C6.09 FOR INFORMATION ON SANITARY SEWER SERVICE LINES.
 - (SS2) PRIVATE SANITARY SEWER MAIN EXTENSION. REFERENCE SHEETS C6.05 -C6.07 PRIVATE SANITARY SEWER SHEETS FOR MORE INFORMATION.
- EXISTING UTILITIES**
- (X1) EXISTING SANITARY SEWER MAIN
 - (X2) EXISTING STORM SEWER
 - (X3) EXISTING WATER MAIN
- NOTE:**
1. FDC SHALL BE LOCATED WITH 100' OF FIRE HYDRANT.
 2. ALL ISSUES PERTAINING TO LIFE SAFETY AND PROPERTY PROTECTION FROM THE HAZARDS OF FIRE, EXPLOSION OR DANGEROUS CONDITIONS IN NEW AND EXISTING BUILDINGS, STRUCTURES, AND PREMISES, AND TO THE SAFETY TO FIRE FIGHTERS AND EMERGENCY RESPONDERS DURING EMERGENCY OPERATIONS, SHALL BE ACCORDANCE WITH THE 2018 INTERNATIONAL FIRE CODE.

7301 West 133rd Street, Suite 200
Overland Park, KS 66204-7756
TEL 913.381.1170
www.olsson.com

SCANNELL PROPERTIES

STATE OF MISSOURI
MITCHELL ALAN MINK
No. PE-0000016164
Exp. 12-1-22
PROFESSIONAL ENGINEER

REV.	NO.	DATE	DESCRIPTION
1	06-25-2022	CITY COMMENTS	
2	06-25-2022	CITY COMMENTS	
3	06-13-2022	CITY COMMENTS	
4	10-04-2022	CITY COMMENTS	
5	10-10-2022	CITY COMMENTS	
6	11-15-2022	CITY COMMENTS	
7	11-15-2022	DESIGNER	


REV.	NO.	DATE	DESCRIPTION
1	06-25-2022	CITY COMMENTS	
2	06-25-2022	CITY COMMENTS	
3	06-13-2022	CITY COMMENTS	
4	10-04-2022	CITY COMMENTS	
5	10-10-2022	CITY COMMENTS	
6	11-15-2022	CITY COMMENTS	
7	11-15-2022	DESIGNER	

UTILITY PLAN
FINAL DEVELOPMENT PLAN - BUILDING 2
SCANNELL DEVELOPMENT LEE'S SUMMIT LOGISTICS
NORTHWEST CORNER OF TUDOR ROAD AND MAIN STREET
LEE'S SUMMIT, MISSOURI

drawn by: SL
checked by: LM
approved by: SR
GNCC by: MW
project no.: B21-04157
drawing no.: UTL01_B2104157.dwg
date: 03.11.2022


SHEET
C6.04

DWG: F:\2021\04001-04500\021-04157-B\40-Design\AutoCAD\Final Plans\Sheets\GNVC\GNVC_SAN01_B2104157.dwg
DATE: Dec 06, 2022 9:38am
XREFS: C:\BLK_B2104157 C:\BASE_B2104157 C:\BASE_B2104157 C:\PSURF_B2104157 C:\ERC_LEGEND_B2104157
USER: Imoore
C:\ERC_LEGEND_B2104157



- NOTES:**
1. CONNECTION TO THE EXISTING SANITARY SEWER MANHOLE SHALL BE CORE-DRILLED.
 2. ALL SANITARY SEWER SERVICE PIPE SHALL BE PVC SDR-26. SEWER SERVICE LINE W/PUSH ON JOINTS.
 3. INSTALL 6" ONE-WAY CLEANOUT 10' FROM BUILDING OR AS NOTED ON PLANS.
 4. TEN FEET OF HORIZONTAL SEPARATION AND TWO FEET OF VERTICAL SEPARATION SHALL BE PROVIDED BETWEEN WATER LINES AND THE SANITARY SEWER SERVICE LINE.
 5. IN THE EVENT OF WORK IN OR ON THE SANITARY MAIN, ANY TREES OR PLANTINGS PLACED WITHIN THE SEWER EASEMENT MAY BE REMOVED WITHOUT REPLACEMENT OR COMPENSATION THERE-OF.
 6. 90-DEGREE TURNS TO BE ACCOMPLISHED WITH TWO 45-DEGREE BENDS WITH A MINIMUM OF ONE FOOT OF PIPE BETWEEN THE 45-DEGREE BENDS.
 7. FOR VERTICAL RISERS AND ENCASEMENTS, SEE SANITARY SEWER CONNECTION SHEETS.
 8. SANITARY SERVICE LINES SHALL BE INSTALLED BY BUILDING PLUMBER AND IN ACCORDANCE WITH THE CURRENT LEE'S SUMMIT SERVICE LINE DESIGN AND CONSTRUCTION STANDARDS.
 9. ROOF DRAINS SHALL NOT BE CONNECTED TO THE SANITARY SEWER.
 10. REPLACE/ADD BARREL SECTIONS AS REQUIRED TO MEET THE GRADE REQUIREMENTS.
 11. MANHOLE STATIONS AND PIPE LENGTHS SHOWN ON PLANS ARE TO THE CENTER OF MANHOLES. DO NOT SCALE DRAWINGS.
 12. CONTRACTOR IS RESPONSIBLE FOR REPLACING ANY PAVEMENT OR SIDEWALKS DAMAGED DURING THE CONSTRUCTION OF THE SANITARY SEWER SERVICE LINE.

SANITARY SEWER PLAN LEGEND




EASEMENT/SETBACK LEGEND


D/E STORM DRAINAGE EASEMENT
S/B PROPERTY SETBACK
S/E SANITARY SEWER EASEMENT
U/E UTILITY EASEMENT
E/E ELECTRIC EASEMENT

NOTE


FUTURE IMPROVEMENTS ARE SHOWN FOR REFERENCE ONLY.



HEAVY DUTY ONE-WAY CLEANOUT (IN PAVEMENT) DETAIL
NOT TO SCALE




ONE-WAY WYE CLEANOUT (NOT IN PAVEMENT) DETAIL
NOT TO SCALE



TEE ORIENTATION AND RISER DETAIL
NOT TO SCALE





SCANNELL
P R O P E R T I E S



BY		REVISIONS	
REV.	NO.	DATE	DESCRIPTION
1	06-25-2022	06-25-2022	CITY COMMENTS
2	06-25-2022	06-25-2022	CITY COMMENTS
3	06-25-2022	06-25-2022	CITY COMMENTS
4	10-04-2022	10-04-2022	CITY COMMENTS
5	10-12-2022	10-12-2022	CITY COMMENTS
6	11-15-2022	11-15-2022	CITY COMMENTS

OVERALL SANITARY SEWER PLAN
FINAL DEVELOPMENT PLAN - BUILDING 2
SCANNELL DEVELOPMENT LEE'S SUMMIT LOGISTICS
NORTHWEST CORNER OF TUDOR ROAD AND MAIN STREET
LEE'S SUMMIT, MISSOURI
2022
drawn by: SR
checked by: LM
approved by: SR
GNVC by: MM
project no.: B21-04157
drawing no.: GNVC_SAN01_B2104157.dwg
date: 03.11.2022
SHEET
C6.05

SHEET
C6.06




LEGEND	
	PROPERTY LINE
	EXISTING CONTOUR
	PROPOSED CONTOUR

- EASEMENT/SETBACK LEGEND**
- D/E STORM DRAINAGE EASEMENT
S/B PROPERTY SETBACK
S/E SANITARY SEWER EASEMENT
U/E UTILITY EASEMENT
E/E ELECTRIC EASEMENT
- SANITARY SEWER NOTES:**
- ALL SANITARY SEWER SERVICE PIPE SHALL BE PVC SDR-26. SEWER SERVICE LINE W/PUSH ON JOINTS.
 - TEN FEET OF HORIZONTAL SEPARATION AND TWO FEET OF VERTICAL SEPARATION SHALL BE PROVIDED BETWEEN WATER LINES AND THE SANITARY SEWER SERVICE LINE.
 - IN THE EVENT OF WORK IN OR ON THE SANITARY MAIN, ANY TREES OR PLANTINGS PLACED WITHIN THE SEWER EASEMENT MAY BE REMOVED WITHOUT REPLACEMENT OR COMPENSATION THERE-OF.
 - FOR VERTICAL RISERS AND ENCASEMENTS, SEE SANITARY SEWER CONNECTION SHEETS.
 - ROOF DRAINS SHALL NOT BE CONNECTED TO THE SANITARY SEWER.
 - REPLACE/ADD BARREL SECTIONS AS REQUIRED TO MEET THE GRADE REQUIREMENTS.
 - MANHOLE STATIONS AND PIPE LENGTHS SHOWN ON PLANS ARE TO THE CENTER OF MANHOLES. DO NOT SCALE DRAWINGS.
 - CONTRACTOR IS RESPONSIBLE FOR REPLACING ANY PAVEMENT OR SIDEWALKS DAMAGED DURING THE CONSTRUCTION OF THE SANITARY SEWER MAIN.
- RIM ADJUSTMENT NOTES:**
- REPLACE/ADD BARREL SECTIONS AS REQUIRED TO MEET THE GRADE REQUIREMENTS.


STRUCTURES	
ID	DESCRIPTION
MH 2-1	4" ID STD MANHOLE
1+64.38	PROPOSED SANITARY SEWER - LINE 2 RIM= 949.52 INV IN = 938.96 (6" PVC) INV OUT = 938.66 (8" PVC) N: 53590.121; E: 54052.436



- NOTES:
1. A MINIMUM OF 36 INCHES OF COVER SHALL BE OVER THE TOP OF THE PIPE. THIS AMOUNT OF COVER SHALL BE FROM THE TOP OF THE PIPE TO THE FINISH GRADE.
 2. BEDDING AGGREGATE MATERIAL SHALL BE PER SECTION 6900 AND 2102 OF THE CITY DESIGN AND CONSTRUCTION MANUAL. BEDDING AGGREGATE SHALL BE PLACED FROM A LEVEL 6 INCHES BELOW THE BOTTOM OF THE PIPE TO A LEVEL 12 INCHES ABOVE THE TOP OF THE PIPE.
 3. BACKFILL MATERIAL AND PLACEMENT SHALL BE PER SECTION 6900 AND 2102 OF THE CITY DESIGN AND CONSTRUCTION MANUAL.
 4. TRENCHING SHALL BE IN ACCORDANCE WITH CURRENT OSHA REGULATIONS. SLOPES MUST BE NOTED AND EXTENDED BELOW THE TOP OF THE PIPE.
 5. MINIMUM AND MAXIMUM TRENCH WIDTHS SHALL BE IN ACCORDANCE WITH PIPE MANUFACTURERS RECOMMENDATION AS APPROVED ON ENGINEERING PLANS.



DWG: F:\2021\04001-04500\021-04157-B\40-Design\AutoCAD\Final Plans\Sheets\GNVAC_STM01_B2104157.dwg
DATE: Dec 06, 2022 9:40am XREFS: C:\BASE_B2104157 C:\PSURF_B2104157 C:\PSTRM_B2104157
USER: Imoore C:\TBLK_B2104157



- LEGEND**
- PROPERTY LINE
 - EXISTING CONTOUR
 - PROPOSED CONTOUR
 - PROPOSED DRAINAGE BOUNDARY
 - PROPOSED LANDSCAPE WALL
 - STORM SEWER

olsson

7301 West 133rd Street, Suite 200
Overland Park, KS 66213-7755
TEL 913.381.1170 www.olsson.com

SCANNELL

PROPERTIES

STATE OF MISSOURI

PE 2008016164

2-2-22

PROFESSIONAL ENGINEER

REV.	NO.	DATE	DESCRIPTION	BY
1	06-28-2022	CITY COMMENTS		
2	06-28-2022	CITY COMMENTS		
3	06-15-2022	CITY COMMENTS		
4	10-04-2022	CITY COMMENTS		
5	10-18-2022	CITY COMMENTS		
6	11-15-2022	CITY COMMENTS		
7	11-15-2022	CITY COMMENTS		

OVERALL STORM SEWER PLAN
FINAL DEVELOPMENT PLAN - BUILDING 2

SCANNELL DEVELOPMENT LEE'S SUMMIT LOGISTICS
NORTHWEST CORNER OF TUDOR ROAD AND MAIN STREET

LEE'S SUMMIT, MISSOURI

drawn by: SL

checked by: LM

approved by: SR

GNVAC by: MN



project no: B21-04157

drawing no: 02817001_B2104157.dwg

date: 03.11.2022

2022

SHEET
C7.00



- NOTES:**
- CONTRACTOR TO SUBMIT SHOP DRAWINGS TO ENGINEER FOR APPROVAL PRIOR TO FABRICATION OF STRUCTURES AND ORDERING OF PIPE PRODUCTS.
 - SEE ARCHITECTURAL PLANS FOR ROOF DRAIN CONNECTION DETAIL.
 - CURB & GUTTER SIZE (STANDARD, 10", 12") SHOWN ON DIMENSION PLANS
 - COMPACTED FILL SHALL BE PLACED TO A MINIMUM 18" ABOVE THE TOP OF THE PIPE PRIOR TO INSTALLATION.
 - ROOF DRAINS ARE TO BE INSTALLED AT A 1.0% MINIMUM SLOPE WITH A MINIMUM COVER OF 2". SEE MEP PLANS FOR ROOF DRAIN LOCATIONS AND DETAILS.

STRUCTURES	
ID	DESCRIPTION
A4-1	5'X4' NONSETBACK CURB INLET 0+35.99, -0.05' LT STORM A4 RIM= 955.87 INV OUT = 950.13 (15" HDPE) N: 53815.919; E: 54292.691

STRUCTURES	
ID	DESCRIPTION
A1	30" CONCRETE FLARED END SECTION WITH TOE WALL 0+20, 0.11' RT STORM LINE A RIM= 946.03 INV IN = 943.36 (30" HDPE) N: 53758.773; E: 53917.764
A2	7'X6" NONSETBACK CURB INLET 2+04.22, 0.00' STORM LINE A RIM= 953.10 INV IN = 944.48 (30" HDPE) INV OUT = 944.28 (30" HDPE) N: 53828.174; E: 54096.556
A3	84" I.D. MANHOLE 3+09.57, 0.00' STORM LINE A RIM= 953.79 INV IN = 945.50 (24" HDPE) INV OUT = 945.00 (30" HDPE) N: 53818.314; E: 54201.446
A4	5'X5' NONSETBACK CURB INLET 3+84.30, 0.00' STORM LINE A RIM= 953.45 INV IN = 946.37 (18" HDPE) INV OUT = 945.87 (24" HDPE) N: 53798.992; E: 54273.635
A5	5'X4' NONSETBACK CURB INLET 5+45.81, 0.00' STORM LINE A RIM= 952.23 INV IN = 947.43 (15" HDPE) INV OUT = 947.18 (18" HDPE) N: 53688.650; E: 54391.563
A6	5'X4' NONSETBACK CURB INLET 6+57.43, 0.00' STORM LINE A RIM= 952.69 INV OUT = 947.99 (15" HDPE) N: 53627.658; E: 54485.057

DWG: F:\2021\04001-04500\021-04157-B\40-Design\AutoCAD\Final Plans\Sheets\GNVC\AC_STM01_B2104157.dwg
DATE: Dec 06, 2022 9:41am
XREFS: C:\BASE_B2104157 C:\BASE_B2104157 C:\PSURF_B2104157 C:\PSTRM_B2104157
USER: Imoore
C:\TBLK_B2104157




- LEGEND**
- PROPERTY LINE
 - CONSTRUCT CONCRETE CURB & GUTTER
 - CONSTRUCT STORM SEWER
 - INSTALL SANITARY SEWER SERVICE
 - INSTALL ELECTRICAL LINE
 - INSTALL FIRE PROTECTION LINE
 - INSTALL DOMESTIC WATER SERVICE
 - INSTALL GAS SERVICE
 - INSTALL TELEPHONE SERVICE
 - PROPOSED STORM STRUCTURE

- NOTES:**
- CONTRACTOR TO SUBMIT SHOP DRAWINGS TO ENGINEER FOR APPROVAL PRIOR TO FABRICATION OF STRUCTURES AND ORDERING OF PIPE PRODUCTS.
 - SEE ARCHITECTURAL PLANS FOR ROOF DRAIN CONNECTION DETAIL.
 - CURB & GUTTER SIZE (STANDARD, 10", 12") SHOWN ON DIMENSION PLANS
 - COMPACTED FILL SHALL BE PLACED TO A MINIMUM 18" ABOVE THE TOP OF THE PIPE PRIOR TO INSTALLATION.
 - ROOF DRAINS ARE TO BE INSTALLED AT A 1.0% MINIMUM SLOPE WITH A MINIMUM COVER OF 2". SEE MEP PLANS FOR ROOF DRAIN LOCATIONS AND DETAILS.

STRUCTURES	
ID	DESCRIPTION
B1	30" CONCRETE FLARED END SECTION WITH TOE WALL 0+10.05, 0.00' LT STORM LINE B RIM= 944.03 INV IN = 941.37 (30" HDPE) N: 53792.802; E: 53886.216
B2	5'X6' NONSETBACK CURB INLET 1+65.73, 0.00' STORM LINE B RIM= 952.27 INV IN = 942.33 (30" HDPE) INV IN = 943.33 (18" HDPE) INV OUT = 941.83 (30" HDPE) N: 53643.505; E: 53999.962
B3	5'X4' NONSETBACK CURB INLET 2+85.52, 0.00' STORM LINE B RIM= 949.26 INV IN = 943.19 (24" HDPE) INV OUT = 942.69 (30" HDPE) N: 53527.546; E: 53969.942
B4	5'X4' NONSETBACK CURB INLET 3+93.62, 0.00' LT STORM LINE B RIM= 947.76 INV IN = 944.01 (18" HDPE) INV OUT = 943.51 (24" HDPE) N: 53453.931; E: 54049.109
B5	5'X4' NONSETBACK CURB INLET 6+25.64, 0.00' LT STORM LINE B RIM= 947.87 INV OUT = 944.71 (18" HDPE) N: 53295.934; E: 54219.021

STORM LINE B (0+00 - 6+45.64)



olsson

7301 West 133rd Street, Suite 200
Overland Park, KS 66213-7755
TEL 913.381.1170
www.olson.com

SCANNELL
P R O P E R T I E S

MITCHELL ALAN
PE 2008010164
2-2-22
PROFESSIONAL ENGINEER

REV	NO.	DATE	REVISIONS DESCRIPTION
1	06-25-2022	CITY COMMENTS	
2	06-25-2022	CITY COMMENTS	
3	06-15-2022	CITY COMMENTS	
4	10-04-2022	CITY COMMENTS	
5	10-12-2022	CITY COMMENTS	
6	11-15-2022	CITY COMMENTS	

BY: _____


REVISIONS

2022


STORM SEWER PLAN & PROFILE LINE B
FINAL DEVELOPMENT PLAN - BUILDING 2
SCANNELL DEVELOPMENT LEE'S SUMMIT LOGISTICS
NORTHWEST CORNER OF TUDOR ROAD AND MAIN STREET
LEE'S SUMMIT, MISSOURI

drawn by: _____
checked by: _____
approved by: _____
GNCC by: _____
project no.: B21-04157
drawing no.: B21-04157.dwg
date: 03.11.2022

SHEET
C7.02




STORM LINE C (0+00 - 3+84.84)




- LEGEND**
- PROPERTY LINE
 - CONSTRUCT CONCRETE CURB & GUTTER
 - CONSTRUCT STORM SEWER
 - INSTALL SANITARY SEWER SERVICE
 - INSTALL ELECTRICAL LINE
 - INSTALL FIRE PROTECTION LINE
 - INSTALL DOMESTIC WATER SERVICE
 - INSTALL GAS SERVICE
 - INSTALL TELEPHONE SERVICE
 - PROPOSED STORM STRUCTURE

NOTES:



- CONTRACTOR TO SUBMIT SHOP DRAWINGS TO ENGINEER FOR APPROVAL PRIOR TO FABRICATION OF STRUCTURES AND ORDERING OF PIPE PRODUCTS.
- SEE ARCHITECTURAL PLANS FOR ROOF DRAIN CONNECTION DETAIL.
- CURB & GUTTER SIZE (STANDARD, 10", 12") SHOWN ON DIMENSION PLANS
- COMPACTED FILL SHALL BE PLACED TO A MINIMUM 18" ABOVE THE TOP OF THE PIPE PRIOR TO INSTALLATION.
- ROOF DRAINS ARE TO BE INSTALLED AT A 1.0% MINIMUM SLOPE WITH A MINIMUM COVER OF 2". SEE MEP PLANS FOR ROOF DRAIN LOCATIONS AND DETAILS.



STRUCTURES	
ID	DESCRIPTION
C1	24" CONCRETE FLARED END SECTION WITH TOE WALL 0+20, 0.00' STORM LINE C RIM= 944.44 INV IN = 942.29 (24" HDPE) N: 53229.312; E: 54475.078
C2	5'X4' NONSETBACK CURB INLET 0+76.87, 0.00' STORM LINE C RIM= 949.21 INV IN = 943.07 (18" HDPE) INV IN = 943.07 (18" HDPE) INV OUT = 942.57 (24" HDPE) N: 53272.213; E: 54437.742
C3	4' X 4' AREA INLET (OPEN ON ALL SIDES) 2+44.08, 0.00' STORM LINE C RIM= 952.59 INV IN = 945.12 (18" HDPE) INV OUT = 944.92 (18" HDPE) N: 53384.594; E: 54561.551
C4	48" I.D. MANHOLE 2+80.19, 0.00' STORM LINE C RIM= 956.88 INV IN = 946.07 (18" HDPE) INV OUT = 945.57 (18" HDPE) N: 53400.219; E: 54594.105
C5	5'X4' NONSETBACK CURB INLET 3+64.83, 0.08' RT STORM LINE C RIM= 953.65 INV OUT = 947.13 (18" HDPE) N: 53473.999; E: 54552.617




BASIN A-1 OUTFLOW (0+00 - 4+38.45)




SECTION THROUGH OUTLET STRUCTURE
N.T.S.

- NOTES:
1. BOTTOM TO BE POURED IN PLACE.
 2. PIPE TO BE ON GRADE BEFORE BOTTOM IS CONSTRUCTED.
 3. RAM-NEK ALL JOINTS (OR EQUAL).
 4. #4 BARS @ 10" C.C. VERT. & HOR. IN WALLS & BOTTOM.
 5. REINFORCING BARS SHALL BE CUT OR BENT AT PIPE OPENINGS.
 6. ALL PIPES SHALL FIT FLUSH WITH INSIDE FACE OF BOX.
 7. BOTTOM OF BOX TO BE FILLED WITH CONCRETE TO 6" ABOVE INVERT OF PIPE FORMING CHANNELS TOWARD OUTLET PIPE FROM ALL INLET PIPES.
 8. ALL CONCRETE SHALL HAVE 28 DAY COMPRESSIVE STRENGTH OF 4,000 PSI.
 9. ALL REINFORCING BARS TO BE DEFORMED BARS AND MEET REQUIREMENTS OF 1965 ASTM STANDARDS NO. A-615-65 MIN. GRADE 40.
 10. MUST MAINTAIN 6" CLEARANCE BETWEEN THE PIPE AND WALLS FOR PRECAST BOXES.



PERFORATED RISER PIPE DETAIL
N.T.S.



STRUCTURE TOP OPENING. INSTALL FLAT ROOF
RECTANGULAR TRASH RACK ON TOP OF STRUCTURE.



N2 OUTLET STRUCTURE DETAIL
N.T.S.


POND VOLUMES		
INFLOW VOLUME WATER QUALITY (ACRE-FT)	INFLOW VOLUME 100 YEAR STORM (ACRE-FT)	TOTAL STORAGE VOLUME TO TOP OF POND (ACRE-FT)
0.4	3.9	8.5

STRUCTURES	
ID	DESCRIPTION
N1	15" CONCRETE FLARED END SECTION WITH TOE WALL 0+20.02, 0.05' RT BASIN A-1 OUTFLOW RIM= 939.65 INV IN = 938.26 (15" HDPE) N: 53415.184; E: 53992.694
N2	4'x4' JUNCTION BOX REFERENCE DETAIL ON SHEET 3+76.25, 0.00' BASIN A-1 OUTFLOW RIM= 951.00 INV IN = 940.23 (8" PVC) INV OUT = 940.03 (15" HDPE) N: 53739.657; E: 53845.658



- LEGEND**
- PROPERTY LINE
 - LOT LINES
 - RIGHT-OF-WAY LINE
 - SS SANITARY SEWER SERVICE
 - E FUTURE ELECTRICAL LINE
 - W FUTURE DOMESTIC WATER SERVICE
 - GAS FUTURE GAS SERVICE
 - COMM FUTURE TELEPHONE SERVICE
 - EXISTING GRADE CONTOUR
 - FINISHED GRADE CONTOUR
 - STORM SEWER
 - 10-YEAR HGL
 - 100-YEAR HGL
- KEYNOTE LEGEND**
- XX PROPOSED STORM STRUCTURE
 - CONTRACTOR SHALL PROVIDE 95% COMPACTED FILL TO AN ELEVATION OF 2'-0" (MIN.) OVER THE TOP OF PROPOSED PIPE ELEVATION AND TEMPORARY FILL
- STORM STRUCTURE NOTES**
1. CONTRACTOR TO PROVIDE STRUCTURAL DETAILS AND CALCULATIONS SEALED BY A LICENSED ENGINEER FOR STRUCTURES GREATER THAN 15' IN DEPTH.
 2. NORTHING & EASTINGS SHOWN REPRESENT CENTER OF INLET STRUCTURES AND ENDS OF FLARED END SECTIONS.
 3. SEE DETAILS IN THESE PLANS FOR INFORMATION ON STORM STRUCTURES.
 4. ALL STORM SEWER PIPE TO BE HDPE, RCP CLASS III, OR PRE-APPROVED EQUIVALENT.
 5. ALL AREA INLETS SHOULD BE CONSTRUCTED WITH 6" THROAT.

DWG: F:\2021\04001-04500\021-04157-B\40-Design\AutoCAD\Final Plans\Sheets\GNCV\C_STM01_B2104157.dwg
DATE: Dec 06, 2022 9:42am XREFS: C_XBASE_B2104157 C_PBASE_B2104157 C_PSURF_B2104157



POND VOLUMES		
INFLOW VOLUME WATER QUALITY (ACRE-FT)	INFLOW VOLUME 100 YEAR STORM (ACRE-FT)	TOTAL STORAGE VOLUME TO TOP OF POND (ACRE-FT)
0.1	1.5	0.4*

1. CONTRACTOR TO PROVIDE STRUCTURAL DETAILS AND CALCULATIONS SEALED BY A LICENSED ENGINEER FOR STRUCTURES GREATER THAN 15' IN DEPTH.
2. NORTHING & EASTINGS SHOWN REPRESENT CENTER OF INLET STRUCTURES AND ENDS OF FLARED END SECTIONS.
3. SEE DETAILS IN THESE PLANS FOR INFORMATION ON STORM STRUCTURES.
4. ALL STORM SEWER PIPE TO BE HDPE, RCP CLASS III, OR PRE-APPROVED EQUIVALENT.
5. ALL AREA INLETS SHOULD BE CONSTRUCTED WITH 6" THROAT.

drawn by: _____ SL
checked by: _____ LM
approved by: _____ SR
QA/QC by: _____ MK
project no.: B21-04157
drawing no: STM01 B2104157.dwg
date: 03.11.2022


SHEET
C7.05

2

DWG: F:\2021\04001-04500\021-04157-B\40-Design\AutoCAD\Final Plans\Sheets\GNVC\C_STM02_B2104157.dwg
DATE: Dec 06, 2022 9:42am
USER: Imoore
C:\SC01_B2104157
C:\BLK_B2104157
C:\BASE_B2104157
C:\SURF_B2104157
XREFS: C:\BASE_B2104157


STORM SEWER PIPE AND STRUCTURE TABLE - 10 YEAR																																	
TITLE: Lee's Summit Logistics Building B																																	
JOB #: B021-04157																																	
DESIGN CONDITIONS: PRIVATE - 10 YEAR STORM EVENT																																	
STRUCTURES		RUNOFF CALCULATIONS							PIPE DESIGN																				Comments				
FROM	TO	DIRECT AREA (ACRES)	TOTAL AREA (ACRES)	C	KC (K=1)	Tc (MIN)	FLOW TIME (MIN)	INTENSITY (IN/HR)	DESIGN Q (CFS)	DESCRIPTION	PIPE LENGTH (L.F.)	PIPE SLOPE (%)	PIPE DIA (IN)	Q FULL (CFS)	PIPE AREA (SQ.FT.)	V FULL (F/S)	DESIGN V (F/S)	Hw/D	MH TOP ELEVATION	UPSTREAM FLOWLINE	DOWNSTREAM FLOWLINE	DOWNSTREAM WATER ELEVATION	FRICTION HEAD (h f)	ENTRY LOSS COEFFICIENT (k)	ACTUAL ENTRY LOSS (k)	ENTRY LOSS (h m)	h f + h m (FT)	HW, INLET CONTROL		HW, OUTLET CONTROL	HYDRAULIC GRADE ELEV.	HYDRAULIC GRADE (MAX)	
A6		0.58		0.90	0.90	5.0		7.35	3.85											952.69										949.38	951.19		
	A5		0.58	0.90	0.90	5.0	0.45	7.35	3.85		111.63	0.50	15	4.58	1.23	3.73	4.18	0.98		952.23	947.74	947.43	948.71	0.40	0.40	1.00	0.27	0.67	948.97	949.38	948.68	950.73	
A5	A4	0.37	0.96	0.90	0.90	5.0	0.57	7.35	2.48		161.50	0.50	18	7.45	1.77	4.21	4.71	1.00		953.45	947.18	946.37	947.90	0.57	0.40	0.40	0.14	0.71	948.68	948.61	947.61	951.95	
A4	A3	0.24		0.90	0.90	5.0		7.35	1.56											953.45													
		1.56		0.90	0.90	6.0	0.23	7.05	9.90	Storm Line A + Storm Line A4	74.73	0.50	24	16.04	3.14	5.11	5.36	0.87		945.87	945.50	947.20	0.14	0.40	0.40	0.18	0.32	947.61	947.52	947.61	951.95		
A3		0.00		0.90	0.90	5.0		7.35	0.00											953.79													
	A2	1.56	0.90	0.90	6.2	0.33	6.99	9.81			104.90	0.50	30	29.08	4.91	5.92	5.34	0.73		945.00	944.48	946.12	0.06	0.40	0.40	0.18	0.24	946.83	946.35	946.83	952.29		
A2		0.63		0.90	0.90	5.0		7.35	4.15											953.08													
	A1	2.19	0.90	0.90	6.6	0.53	6.90	13.58			184.32	0.50	30	29.08	4.91	5.92	5.81	0.79		944.28	943.36	945.20	0.20	0.40	0.40	0.21	0.41	946.26	945.61	946.26	951.58		
A4-1		0.37		0.90	0.90	5.0		7.35	2.43											955.87													
	A4	0.37	0.37	0.90	0.90	5.0	0.04	7.35	2.43		24.00	6.00	15	15.87	1.23	12.93	9.36	0.80		950.13	948.75	949.72	0.03	0.40	1.00	1.36	1.40	951.12	951.11	951.12	954.37		
B5		0.83		0.90	0.90	5.0		7.35	5.52											947.87													
	B4	0.67	0.83	0.90	0.90	5.0	1.05	7.35	5.52		233.30	0.30	18	5.77	1.77	3.26	3.71	0.93		947.76	944.71	944.01	945.64	0.65	0.40	1.00	0.21	0.87	946.10	946.50	946.50	946.37	
B4		0.67		0.90	0.90	5.0		7.35	4.45											947.76													
	B3	1.51	0.90	0.90	5.0	0.41	7.35	9.97			108.11	0.30	24	12.42	3.14	3.95	4.39	0.87		943.51	943.19	945.11	0.21	0.40	0.40	0.12	0.33	945.25	945.44	945.44	946.26		
B3		0.23		0.90	0.90	5.0		7.35	1.51											949.26													
	B2	1.73	0.90	0.90	5.4	0.44	7.23	11.28			120.02	0.30	30	22.53	4.91	4.59	4.58	0.75		942.69	942.33	944.15	0.09	0.40	0.40	0.13	0.22	944.58	944.37	944.60	950.76		
B2		0.38		0.90	0.90	5.0		7.35	2.49											952.26													
	B1	3.41	0.90	0.90	5.8	0.50	7.10	24.90		Storm Line B + SE Roof Drains	155.18	0.30	30	22.53	4.91	4.59	5.22	0.98		941.83	941.37	943.99	0.44	0.40	0.40	0.17	0.61	944.29	944.60	948.32	952.15		
C5		0.58		0.90	0.90	5.0		7.35	3.85											953.65													
	C4	0.00	0.58	0.90	0.90	5.0	0.22	7.35	3.85		79.72	1.25	18	11.78	1.77	6.66	5.96	0.80		947.13	946.07	947.04	0.11	0.40	1.00	0.55	0.66	948.32	947.70	948.32	952.15		
C4		0.00		0.90	0.90	5.0		7.35	0.00											956.88													
	C3	0.16	0.58	0.90	0.90	5.2	0.09	7.28	3.82		32.41	1.25	18	11.78	1.77	6.66	5.94	0.79		945.57	945.12	946.08	0.04	0.40	0.40	0.22	0.26	946.76	946.34	946.76	955.38		
C3		0.16		0.90	0.90	5.0		7.35	1.06											952.59													
	C2	0.74	0.90	0.90	5.3	0.51	7.26	4.85			179.98	1.00	18	10.53	1.77	5.96	5.83	0.87		944.92	943.07	944.21	0.39	0.40	0.40	0.21	0.60	946.23	944.92	946.23	951.09		
C2		0.38		0.90	0.90	5.0		7.35	2.51											949.56													
	C1	2.42	0.90	0.90	5.8	0.16	7.11	15.49		Storm Line C + SE Roof Drains	56.79	0.50	24	16.04	3.14	5.11	5.80	1.15		942.57	942.28	944.57	0.27	0.40	0.40	0.21	0.48	944.88	945.05	945.05	948.06		

STORM SEWER PIPE AND STRUCTURE TABLE - 100 YEAR																																	
TITLE: Lee's Summit Logistics Building B																																	
JOB # B021-04157																																	
DESIGN CONDITIONS: PRIVATE - 100 YEAR STORM EVENT																																	
STRUCTURES			RUNOFF CALCULATIONS						PIPE DESIGN																								
FROM	TO	DIRECT AREA (ACRES)	TOTAL AREA (ACRES)	C	KC (K=1)	Tc (MIN)	FLOW TIME (MIN)	INTENSITY (IN/HR)	DESIGN Q (CFS)	DESCRIPTION	PIPE LENGTH (L.F.)	PIPE SLOPE (%)	PIPE DIA (IN)	Q FULL (CFS)	PIPE AREA (SQ.FT.)	V FULL (F/S)	DESIGN V (F/S)	HW/D	MH TOP ELEVATION	UPSTREAM FLOWLINE	DOWNSTREAM FLOWLINE	DOWNSTREAM WATER ELEVATION	FRICTION HEAD (h f)	ENTRY LOSS COEFFICIENT (k)	ACTUAL ENTRY LOSS (k)	ENTRY LOSS (h m)	h f + h m (FT)	HW, INLET CONTROL	HW, OUTLET CONTROL	HYDRAULIC GRADE ELEV.	HYDRAULIC GRADE (MAX)	Comments	
A6		0.58		0.90	1.00	5.0		10.32	6.01											952.69										950.52	951.19		
	A5		0.58	0.90	1.00	5.0	0.38	10.32	6.01		111.63	0.50	15	4.58	1.23	3.73	4.90	1.43		952.23	947.74	947.43	949.18	0.98	0.40	1.00	0.37	1.35	949.53	950.52	950.06	950.73	
A5		0.37		0.90	1.00	5.0		10.32	3.87																								
	A4		0.96	0.90	1.00	5.4	0.49	10.17	9.73		161.50	0.50	18	7.45	1.77	4.21	5.50	1.47		947.18	946.37	948.47	1.40	0.40	0.40	0.19	1.59	949.39	950.06	948.37	951.95		
A4		0.24		0.90	1.00	5.0		10.32	2.44											953.45													
	A3		1.56	0.90	1.00	5.9	0.21	9.97	15.56	Storm Line A + Storm Line A4	74.73	0.50	24	16.04	3.14	5.11	5.81	1.16		945.87	945.50	947.80	0.36	0.40	0.40	0.21	0.57	948.19	948.37	947.07	952.29		
A3		0.00		0.90	1.00	5.0		10.32	0.00											953.79													
	A2		1.56	0.90	1.00	6.1	0.29	9.89	15.43		104.90	0.50	30	29.08	4.91	5.92	6.00	0.83		945.00	944.48	946.44	0.15	0.40	0.40	0.22	0.37	947.07	946.81	947.07	952.29		
A2		0.63		0.90	1.00	5.0		10.32	6.47											953.08													
	A1		2.19	0.90	1.00	6.4	0.48	9.78	21.39		184.32	0.50	30	29.08	4.91	5.92	6.46	0.97		944.28	943.36	945.74	0.51	0.40	0.40	0.26	0.76	946.71	946.51	946.71	951.58		
A4-1		0.37		0.90	1.00	5.0		10.32	3.87											955.87													
	A4		0.37	0.90	1.00	5.0	0.04	10.32	3.80		24.00	6.00	15	15.87	1.23	12.93	10.60	0.97		950.13	948.75	949.56	0.08	0.40	1.00		1.74	1.83	951.35	951.39	951.39	954.37	
B5		0.83		0.90	1.00	5.0		10.32	8.61											947.87													
	B4		0.83	0.90	1.00	5.0	0.80	10.32	8.61		233.30	0.30	18	5.77	1.77	3.26	4.87	1.30		944.71	944.01	946.08	1.58	0.40	1.00	0.37	1.95	946.66	948.03	948.03	946.37		
B4		0.67		0.90	1.00	5.0		10.32	6.93											947.76													
	B3		1.51	0.90	1.00	5.0	0.36	10.32	15.54		108.11	0.30	24	12.42	3.14	3.95	4.95	1.16		943.51	943.19	945.90	0.52	0.40	0.40	0.15	0.67	945.83	946.57	946.57	946.26		
B3		0.23		0.90	1.00	5.0		10.32	2.36											949.26													
	B2		1.73	0.90	1.00	5.4	0.39	10.17	17.65		120.02	0.30	30	22.53	4.91	4.59	5.07	0.88		942.69	942.33	944.71	0.22	0.40	0.40	0.16	0.38	944.88	945.09	945.09	947.76		
B2		0.38		0.90	1.00	5.0		10.32	3.89											952.26													
	B1		3.41	0.90	1.00	5.8	0.37	10.02	24.17	Storm Line B + RW Roof Drains	155.18	0.30	30	22.53	4.91	4.59	6.96	1.44		941.83	941.37	944.86	1.08	0.40	0.40	0.30	1.39	945.44	946.25	946.25	950.76		
C5		0.58		0.90	1.00	5.0		10.32	6.01											953.65													
	C4		0.58	0.90	1.00	5.0	0.20	10.32	6.01		79.72	1.25	18	11.78	1.77	6.66	6.69	0.98		947.13	946.07	947.30	0.26	0.40	1.00	0.69	0.96	948.60	948.26	948.60	952.15		
C4		0.00		0.90	1.00	5.0		10.32	0.00											956.88													
	C3		0.58	0.90	1.00	5.2	0.08	10.24	5.96		32.41	1.25	18	11.78	1.77	6.66	6.68	0.97		945.57	945.12	946.35	0.11	0.40	0.40	0.28	0.38	947.03	946.73	947.03	955.38		
C3		0.16		0.90	1.00	5.0		10.32	1.86											952.59													
	C2		0.74	0.90	1.00	5.3	0.46	10.21	7.58		179.98	1.00	18	10.53	1.77	5.96	6.48	1.16		944.92	943.07	944.55	0.95	0.40	0.40	0.26	1.21	946.66	945.75	946.66	951.09		
C2		0.38		0.90	1.00	5.0		10.32	3.92											949.56													
	C1		2.42	0.90	1.00	5.7	0.12	10.02	24.28	Storm Line C + SE Roof Drains	56.79	0.50	24	16.04	3.14	5.11	7.73	1.86		942.57	942.28	945.15	0.66	0.40	0.40	0.37	1.03	946.29	946.18	946.29	948.06		




STRAIGHT BACK CURB & GUTTER

NOT TO SCALE



STRAIGHT BACK DRY CURB & GUTTER

NOT TO SCALE




CURB CUT DETAIL


NOT TO SCALE

GENERAL NOTES:

- 3/4" ISOLATION JOINTS WITH 5/8" DIA. X 2' SMOOTH DOWELS SHALL BE PLACED AT RADIUS POINTS AND AT 150' INTERVALS. THESE DOWEL BARS SHALL BE GREASED AND WRAPPED ON ONE END WITH EXPANSION TUBES.
- 1" DEEP CONTRACTION JOINTS SHALL BE INSTALLED AT APPROXIMATELY 10' INTERVALS. THESE JOINTS SHALL PASS ACROSS THE ENTIRE CURB SECTION.
- FIX DOWEL BARS WITH BAR SUPPORTS.
- DEPTH OF CURB SHALL BE A MINIMUM OF 8" THROUGH HANDICAP ACCESSIBLE RAMP.




FRONT ELEVATION




STANDARD CONCRETE WALK DETAIL

NOT TO SCALE




SIDEWALK TO STORM BOX CONNECTION DETAIL

NOT TO SCALE




CONCRETE STAIR DETAIL


NOTE: THE NUMBER OF 6" RISERS VARIES (SEE PLAN).




CONTRACTION JOINT (TYPE C)




EXPANSION JOINT (TYPE D)




EXPANSION JOINT (TYPE E)




TIED EXPANSION JOINT (TYPE EE)




DRILLED CONSTRUCTION JOINT (TYPE DD)



ACC TO PCC (TYPE F)




TIED CONSTRUCTION JOINT (TYPE KD)



LONGITUDINAL JOINT (TYPE LD)

PAVEMENT JOINT DETAILS

NOT TO SCALE





1. GRATE COVER DETAIL SHALL BE ADJUSTED AS NECESSARY TO FIT END SECTION PROVIDED.
2. MAXIMUM OPENING THRU END SECTION SHALL BE NO GREATER THAN 6".
ADJUST DETAIL AS NECESSARY.
3. ALL METAL SURFACES SHALL BE HOT DIP ZINC COATED IN ACCORDANCE WITH ASTM A-123.
4. USE CITY APPROVED CONCRETE THROUGHOUT.
5. ALL CONCRETE AND MATERIALS USED IN THIS WORK SHALL MEET THE REQUIREMENTS OF THE GOVERNING BODY.
6. REINFORCING STEEL SHALL BE BUILT WELLY, MINIMUM GRADE 40 AS PER ASTM A615, AND SHALL BE BENT COLD.
7. ALL DIMENSIONS RELATIVE TO REINFORCING STEEL ARE TO CENTERLINE.
8. ALL DIMENSIONS TO CLEARANCE SHALL BE PROVIDED THROUGHOUT UNLESS NOTED OTHERWISE. TOLERANCE OF $\pm 1/8"$ SHALL BE PERMITTED.
9. ALL LAP SPACES NOT SHOWN SHALL BE A MINIMUM OF 40 BAR DIAMETERS IN LENGTH.
10. ALL DOWELS SHALL BE ACCURATELY PLACED AND SECURELY TIED INTO EXISTING CONCRETE TO PREVENT BOTTOM SLAB CONCRETE SPLITTING OR STICKING OF DOWELS INTO FRESH OR PARTIALLY HARDENED CONCRETE.
WILL NOT BE ACCEPTABLE.
11. ALL REINFORCING STEEL SHALL BE SUPPORTED ON FABRICATED STEEL BAR SUPPORTS @ 3'-0" MAXIMUM SPACING.
12. DO NOT SCALE THESE DRAWINGS FOR DIMENSIONS OR CLEARANCES. ANY QUESTIONS REGARDING DIMENSIONS SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO CONSTRUCTION.



NOT TO SCALE



NON-SETBACK CURB INLET

NOT TO SCALE



NOT TO SCALE

1. USE CITY APPROVED CONCRETE THROUGHOUT.
2. THE FIRST DIMENSION LISTED IN THE CONSTRUCTION NOTES IS THE "L" DIMENSION. THE SECOND DIMENSION IS THE "W" DIMENSION.
3. FLOOR OF INLET SHALL BE SHAPED TO PROVIDE SMOOTH FLOW.
4. EXPANSION JOINTS SHALL BE EITHER HOT OR COLD POURED JOINT SEALING COMPOUND, OR PREMOULDED EXPANSION JOINT FILLER.
5. STEEL INLET FRAME SPACERS SHALL BE PLACED AT EQUAL SPACINGS NOT TO EXCEED 4'-0".
6. CAST IRON STEPS SHALL BE TO CLAY & BAILEY 2102 OR APPROVED EQUAL. STEEL COATED PLASTIC COATED STEPS MAY BE USED (M.A. IND. INC. NO. PSI-PF, PS2-PF, OR APPROVED EQUAL). CAST IRON STEPS SHALL BE SPACED AT 1'-4" O.C. VERTICALLY.
7. BEVEL ALL EXPOSED EDGES WITH TRIANGULAR MOLDING.
8. ON-GRADE INLETS SHALL CONFORM TO THE STREET GRADE AND SUMP INLETS SHALL BE LEVEL.
9. ALL STORM SEWER STRUCTURES SHALL BE PRECAST. PRECAST SHOP DRAWINGS SHALL BE APPROVED BY THE DESIGN ENGINEER.
10. REINFORCING STEEL SHALL BE NEW BILLET, MINIMUM GRADE 40 AS PER ASTM A615, AND SHALL BE BENT COLD.
11. ALL DIMENSIONS RELATIVE TO REINFORCING STEEL ARE TO CENTERLINE OF BARS. 2" CLEARANCE SHALL BE PROVIDED THROUGHOUT UNLESS NOTED OTHERWISE. TOLERANCE OF $\pm 1/8"$ SHALL BE PERMITTED.
12. ALL LAP SPACES NOT SHOWN SHALL BE A MINIMUM OF 40 BAR DIAMETERS IN LENGTH.
13. ALL DOWELS SHALL BE ACCURATELY PLACED AND SECURELY TIED IN PLACE PRIOR TO PLACEMENT OF BOTTOM SLAB CONCRETE. STICKING OF DOWELS INTO FRESH OR PARTIALLY HARDENED CONCRETE WILL NOT BE ACCEPTABLE.
14. ALL REINFORCING STEEL SHALL BE SUPPORTED ON FABRICATED STEEL BAR SUPPORTS @ 3'-0" MAXIMUM SPACING.
15. DO NOT SCALE THESE DRAWINGS FOR DIMENSIONS OR CLEARANCES. ANY QUESTIONS REGARDING DIMENSIONS SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO CONSTRUCTION.
16. THE BOTTOM SLAB SHALL BE AT LEAST 24 HOURS OLD BEFORE PLACING SIDEWALK CONCRETE. ALL SIDEWALK FORMS SHALL REMAIN IN PLACE A MINIMUM OF 24 HOURS AFTER SIDEWALKS ARE POURED BEFORE REMOVAL AND AFTER REMOVAL SHALL BE IMMEDIATELY TREATED WITH MEMBRANE CURING COMPOUND.
17. ALL CURB INLET TOPS ARE TO BE CONSTRUCTED AFTER FINAL CURB STRING LINE HAS BEEN APPROVED BY THE ENGINEER AND PRIOR TO CURB CONSTRUCTION, OR AS DIRECTED BY THE CITY ENGINEER.
18. RCP CONNECTIONS TO PRECAST STRUCTURE SHALL MEET ALL CITY STANDARDS.
19. BACKFILL AROUND STRUCTURES SHALL BE COMPACTED AND SHALL BE OF THE MATERIAL SPECIFIED PER CITY STANDARDS.
20. NON-SETBACK CURB INLET TO BE USED ONLY WITH THE APPROVAL OF THE CITY ENGINEER.

1. RETAINING WALL SHALL BE "VERSALOG MOSAIC RETAINING WALL (NONWEATHERED) AND THE COLOR SHALL BE PALOMINO GRAY". THE DETAILS PROVIDED HERE ARE FOR GENERAL GUIDANCE ONLY. THE WALL SHALL BE "DESIGN-BUILT" PROVIDED COMPLETE IN-PLACE BY THE CONTRACTOR.
2. THE MODULAR WALL UNITS SHALL HAVE A STRAIGHT FACE WITH SPLIT FINISH TEXTURE. COLOR SHALL BE "PALOMINO GRAY".
3. THE WALL SHALL BE DESIGNED BY THE INSTALLER ACCORDING TO THE WALL UNIT MANUFACTURER'S DESIGN CRITERIA. THE DESIGN SHALL BE SUBMITTED TO THE ARCHITECT/ENGINEER AS A SHOP DRAWING FOR REVIEW. ALL DESIGN CALCULATIONS AND DESIGN CRITERIA, (ANGLE OF FRICTION, SOIL WEIGHT, ETC.), SHALL BE SUBMITTED WITH THE SHOP DRAWING. ALL DESIGN MUST BE SEALED BY A QUALIFIED PROFESSIONAL ENGINEER REGISTERED IN THE STATE OF MISSOURI.
4. FACTORS OF SAFETY SHALL BE AS FOLLOWS:
 - 1.5 AGAINST REINFORCEMENT GRID PULLOUT OR RUPTURE
 - 1.5 AGAINST EXTERNAL SLIDING FAILURE
 - 2.0 AGAINST OVERTURNING
5. THE DESIGN, DIMENSIONS, AND MATERIAL SHOWN IN THIS DETAIL ARE GENERAL IN NATURE. THE AGGREGATE MATERIALS, GEODRID SYSTEM, AND INSTALLATION SHALL BE AS WALL UNIT MANUFACTURER'S REQUIREMENTS.
6. SEE SPECIFICATIONS FOR MATERIAL SELECTION AND OTHER REQUIREMENTS.
7. WALL DESIGN SHALL INCLUDE GLOBAL STABILITY.
8. RETAINING WALL SHALL PROVIDE POSITIVE INTERLOCKING BETWEEN BLOCKS AND GRID.



1. ALL RAILING SHALL BE 2" SQUARE STEEL PIPE.
2. ALL EXPOSED STEEL SHALL BE PRIMED WITH ZINC OXIDE PAINT AND PAINTED WITH TWO COAT OF HIGH GLOSS EXTERIOR DARK BROWN PAINT. SUBMIT SAMPLE TO ARCHITECT PRIOR TO PAINTING FOR APPROVAL.
3. SPACING AND LOCATION AS SHOWN ON DETAILS.
4. SPACING OF VERTICAL POSTS SHALL BE EQUAL THROUGHOUT EACH SECTION OF THE HANDRAIL.

METAL PIPE HANDRAIL DETAIL

NOT TO SCALE


REINFORCEMENT SCHEDULE, BASE	
SECTION	
"A"	#4's @ 6" E.W.

REINFORCEMENT SCHEDULE, WALLS			
SECTION	WIDTH ("W")	HOR.	VERT.
"A"	4'	#4's @ 9"	#4's @ 10"
	BETWEEN 4' & 7'	#6's @ 9"	#4's @ 10"
	GREATER THAN 7'	#5's @ 4 1/2"	#4's @ 10"


TABLE OF "T" & "N" DIMENSIONS			
SECTION	WIDTH ("W")	"T"	"N" "D"
"A"	BETWEEN 4' & 7'	6" + PIPE THICKNESS	8" 8"
	GREATER THAN 7'	6" + PIPE THICKNESS	8" 8"

REINFORCEMENT SCHEDULE, TOP		
DIMENSIONS	STEEL	SPECIAL PATTERN
L = 7' OR LESS	#4's @ 8" E.W.	DIAGONAL @ COVER
W = 7' OR LESS	#4's @ 8" E.W.	DIAGONAL @ COVER
L = 7' OR LESS	#4's @ 8" E.W.	DIAGONAL @ COVER
W = 7' OR GREATER	#4's @ 6" E.W.	DIAGONAL @ COVER
L = 7' OR GREATER	#4's @ 6" E.W.	DIAGONAL @ COVER
W = 7' OR GREATER	#4's @ 6" E.W.	DIAGONAL @ COVER


TABLE OF "W" DIMENSIONS					
PIPE SIZE	SKEW OF CROSS DRAIN			PIPE SIZE	SKEW OF CROSS DRAIN
SINGLE	STRAIGHT	30'	45'	SINGLE	STRAIGHT 30' 45'
24"	4'-0"	4'-0"	4'-10"	DOUBLE FOR "A" SECTION ONLY	
30"	4'-0"	4'-7"	5'-8"		
36"	4'-0"	5'-3"	6'-5"		
42"	5'-3"	5'-11"	7'-3"		
48"	5'-10"	6'-7"	8'-0"		
60"	7'-0"	7'-10"	9'-8"		
				DOUBLE	FOR "A" SECTION ONLY
24"	7'-0"	7'-10"	9'-5"	24"	7'-0" 7'-10" 9'-5"
30"	8'-2"	9'-2"	11'-0"	30"	8'-2" 9'-2" 11'-0"
36"	9'-4"	10'-6"	12'-6"	36"	9'-4" 10'-6" 12'-6"
42"	10'-6"	11'-10"	14'-2"	42"	10'-6" 11'-10" 14'-2"
48"	11'-8"	13'-2"	15'-10"	48"	11'-8" 13'-2" 15'-10"



PLAN OF GRATE INLET TYPE 2



TOP VIEW



GENERAL NOTES:

- ALL EXPOSED CORNERS TO HAVE 3/4" CHAMFER.
- ALL #4 & #5 REINFORCING BARS TO HAVE 1 1/2" COVER, LARGER SIZES TO HAVE 2" COVER.
- SEE GRADING AND DRAINAGE PLAN FOR PIPE SIZES, LOCATIONS, AND FLOW LINES.
- PIPES SHALL CONNECT TO THE ENDS OR SIDES OF THE INLET. CONNECTION SHALL NOT BE MADE AT CORNERS OF BOX.
- ALL REINFORCING BARS TO BE GRADE 40.
- A 2' MINIMUM INTERIOR WALL WIDTH IS REQUIRED FOR SIDES WITHOUT PIPES AND A 4' MINIMUM IS REQUIRED FOR SIDES WITH PIPES.
- CONCRETE USED IN THIS WORK SHALL BE APPROVED BY THE CITY.
- THE FIRST DIMENSION LISTED IN THE CONSTRUCTION NOTES IS THE "L" DIMENSION. THE SECOND DIMENSION IS THE "W" DIMENSION.
- EXPANSION JOINTS SHALL BE EITHER HOT OR COLD POURED JOINT SEALING COMPOUND, OR PREMOLDED EXPANSION JOINT FILLER.
- INSTALL ANGLE IRON FACE ON ALL INLETS.
- STEEL INLET FRAME SPACERS SHALL BE PLACED AT EQUAL SPACINGS NOT TO EXCEED 4'-0".
- CAST IRON STEPS TO BE CLAY & BAILEY 2102 OR APPROVED EQUAL. STEEL CORE, PLASTIC COATED STEPS MAY BE USED (M.A. IND./INC. NO. PS1-PF, PS2-PF, OR APPROVED EQUAL). CAST IRON STEPS SHALL BE SPACED AT 1'-4" O.C. VERTICALLY. THE DISTANCE FROM THE LAST STEP TO THE TOP OF CONCRETE INVERT SHOULD BE A MAXIMUM OF 24".
- BEVEL ALL EXPOSED EDGES WITH 3/4" TRIANGULAR MOLDING.
- ON-GRADE INLETS SHALL CONFORM TO THE STREET GRADE AND SUMP INLETS SHALL BE LEVEL.
- ALL STORM SEWER STRUCTURES SHALL BE PRECAST. PRECAST SHOP DRAWINGS SHALL BE APPROVED BY THE DESIGN ENGINEER.
- REINFORCING STEEL SHALL BE NEW BILLET, MINIMUM GRADE 40 AS PER ASTM A615, AND SHALL BE BENT COLD.
- ALL DIMENSIONS RELATIVE TO REINFORCING STEEL ARE TO CENTERLINE OF BARS. 2" CLEARANCE SHALL BE PROVIDED THROUGHOUT UNLESS NOTED OTHERWISE. ALL LAP SPLICES NOT SHOWN SHALL BE A MINIMUM OF 40 BAR DIAMETERS IN LENGTH.
- ALL DOWELS SHALL BE ACCURATELY PLACED AND SECURELY TIED IN PLACE PRIOR TO PLACEMENT OF BOTTOM SLAB CONCRETE. STICKING OF DOWELS INTO FRESH OR PARTIALLY HARDENED CONCRETE WILL NOT BE ACCEPTABLE. ALL REINFORCING STEEL SHALL BE SUPPORTED ON FABRICATED STEEL.
- BAR SUPPORTS @ 3'-0" MAXIMUM SPACING. DO NOT SCALE THESE DRAWINGS FOR DIMENSIONS OR CLEARANCES.
- ANY QUESTIONS REGARDING DIMENSIONS SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO CONSTRUCTION. THE BOTTOM SLAB SHALL BE AT LEAST 24 HOURS OLD BEFORE PLACING SIDEWALL CONCRETE.
- ALL SIDEWALL FORMS SHALL REMAIN IN PLACE A MINIMUM OF 24 HOURS AFTER SIDEWALLS ARE POURED BEFORE REMOVAL, AND AFTER REMOVAL SHALL BE IMMEDIATELY TREATED WITH MEMBRANE CURING COMPOUND.

CURB/GRATE INLET NOTES:


- CONCRETE USED IN THIS WORK SHALL BE APPROVED BY THE CITY.
- THE FIRST DIMENSION LISTED IN THE CONSTRUCTION NOTES IS THE "L" DIMENSION. THE SECOND DIMENSION IS THE "W" DIMENSION.
- EXPANSION JOINTS SHALL BE EITHER HOT OR COLD POURED JOINT SEALING COMPOUND, OR PREMOLDED EXPANSION JOINT FILLER.
- INSTALL ANGLE IRON FACE ON ALL INLETS.
- STEEL INLET FRAME SPACERS SHALL BE PLACED AT EQUAL SPACINGS NOT TO EXCEED 4'-0".
- CAST IRON STEPS TO BE CLAY & BAILEY 2102 OR APPROVED EQUAL. STEEL CORE, PLASTIC COATED STEPS MAY BE USED (M.A. IND./INC. NO. PS1-PF, PS2-PF, OR APPROVED EQUAL). CAST IRON STEPS SHALL BE SPACED AT 1'-4" O.C. VERTICALLY. THE DISTANCE FROM THE LAST STEP TO THE TOP OF CONCRETE INVERT SHOULD BE A MAXIMUM OF 24".
- BEVEL ALL EXPOSED EDGES WITH 3/4" TRIANGULAR MOLDING.
- ON-GRADE INLETS SHALL CONFORM TO THE STREET GRADE AND SUMP INLETS SHALL BE LEVEL.
- ALL STORM SEWER STRUCTURES SHALL BE PRECAST. PRECAST SHOP DRAWINGS SHALL BE APPROVED BY THE DESIGN ENGINEER.
- REINFORCING STEEL SHALL BE NEW BILLET, MINIMUM GRADE 40 AS PER ASTM A615, AND SHALL BE BENT COLD.
- ALL DIMENSIONS RELATIVE TO REINFORCING STEEL ARE TO CENTERLINE OF BARS. 2" CLEARANCE SHALL BE PROVIDED THROUGHOUT UNLESS NOTED OTHERWISE. ALL LAP SPLICES NOT SHOWN SHALL BE A MINIMUM OF 40 BAR DIAMETERS IN LENGTH.
- ALL DOWELS SHALL BE ACCURATELY PLACED AND SECURELY TIED IN PLACE PRIOR TO PLACEMENT OF BOTTOM SLAB CONCRETE. STICKING OF DOWELS INTO FRESH OR PARTIALLY HARDENED CONCRETE WILL NOT BE ACCEPTABLE. ALL REINFORCING STEEL SHALL BE SUPPORTED ON FABRICATED STEEL.
- BAR SUPPORTS @ 3'-0" MAXIMUM SPACING. DO NOT SCALE THESE DRAWINGS FOR DIMENSIONS OR CLEARANCES.
- ANY QUESTIONS REGARDING DIMENSIONS SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO CONSTRUCTION. THE BOTTOM SLAB SHALL BE AT LEAST 24 HOURS OLD BEFORE PLACING SIDEWALL CONCRETE.
- ALL SIDEWALL FORMS SHALL REMAIN IN PLACE A MINIMUM OF 24 HOURS AFTER SIDEWALLS ARE POURED BEFORE REMOVAL, AND AFTER REMOVAL SHALL BE IMMEDIATELY TREATED WITH MEMBRANE CURING COMPOUND.

TABLE OF FILL DEPTHS BELOW PIPE		
D	"A" MIN. IN SOIL	"A" MIN. IN ROCK
27" & SMALLER	6"	6"
30" TO 66"	6"	9"
66" & LARGER	6"	12"

TABLE OF TRENCH WIDTHS		
PIPE SIZE (INCHES)	MINIMUM TRENCH WIDTH (INCHES)	MINIMUM SIDE WALL CLEARANCE (INCHES)
18	35	6
21	39	6 1/2
24	44	7
27	49	8
30	54	8 1/2
33	58	9
36	64	10
42	73	11
48	83	12 1/2
54	92	13 1/2
60	102	15
66	109	15

LEGEND

- BC = OUTSIDE DIAMETER OF PIPE
H = BACKFILL COVER ABOVE TOP OF PIPE
D = NOMINAL PIPE DIAMETER
A = FILL BELOW PIPE (SEE TABLE)
MC = MINIMUM SIDEWALL CLEARANCE (SEE TABLE)



CLASS B

FIRST CLASS BEDDING

CLASS C


ORDINARY BEDDING

BEDDING NOTES

- GRANULAR FILL TO BE CRUSHED STONE OR PEA GRAVEL WITH NOT LESS THAN 95% PASSING 1/2" SIEVE AND NOT LESS THAN 95% TO BE RETAINED ON A #4 SIEVE, TO BE PLACED IN NOT MORE THEN 6" LAYERS AND COMPACTED BY SLICING WITH A SHOVEL.
- TAMPED BACKFILL SHALL BE FINELY DIVIDED JOB EXCAVATED MATERIAL FREE FROM DEBRIS, ORGANIC MATERIAL AND STONES, COMPACTED TO 95% MAXIMUM DENSITY AS DETERMINED BY AASHTO STANDARD METHOD T-99. GRANULAR FILL MAY BE SUBSTITUTED FOR ALL OR PART OF TAMPED BACKFILL.
- HAND PLACED BACKFILL SHALL BE FINELY DIVIDED MATERIAL FREE FROM DEBRIS AND STONES.

STORM SEWER TRENCH DETAIL

NOT TO SCALE



CONDUIT DETAIL


NOT TO SCALE

CONDUIT TRENCH DETAIL

NOT TO SCALE

olsson


SCANNELL
PROPERTIES



REV. NO.	DATE	REVISIONS DESCRIPTION
1	06-25-2022	CITY COMMENTS
2	06-25-2022	CITY COMMENTS
3	06-15-2022	CITY COMMENTS
4	10-04-2022	CITY COMMENTS
5	10-12-2022	CITY COMMENTS
6	11-12-2022	QUESTIONS

STANDARD DETAILS	FINAL DEVELOPMENT PLAN - BUILDING 2
SCANNELL DEVELOPMENT LEE'S SUMMIT LOGISTICS NORTHWEST CORNER OF TUDOR ROAD AND MAIN STREET	
LEE'S SUMMIT, MISSOURI	























drawn by:	SL
checked by:	LM
approved by:	SR
QA/QC by:	MM
project no.:	B21-04157
drawing no.:	DTL01_B2104157.dwg
date:	03.11.2022




LANDSCAPE CALCULATIONS - LOT 2


OPEN YARD AREAS
1 TREE AND 2 SHRUBS PER 5,000 SF OF TOTAL LOT AREA
EXCLUDING BUILDING FOOTPRINT AREA AND TRACTS.
315,719 SF /5,000 SF
63.15 TREES REQUIRED
63 TREES PROVIDED
*SEE PLAN FOR EXISTING TREE MASSES TO REMAIN
126.31 SHRUBS REQUIRED
126 SHRUBS PROVIDED

STREET FRONTAGE REQUIREMENT
MAIN STREET (SOUTH SIDE)
708 LF
1 TREE / 30' OF STREET FRONTAGE
23.6 TREES REQUIRED
23 TREES PROVIDED
1 SHRUB PER 20' OF STREET FRONTAGE
35.4 SHRUBS REQUIRED
41 SHRUBS PROVIDED

PLANT SCHEDULE					
DECIDUOUS TREES	BOTANICAL / COMMON NAME	SIZE	CALIPER		QTY
	EUCOMMIA ULMOIDES HARDY RUBBER TREE	B & B	3"		7
	GLEDITSIA TRIACANTHOS INERMIS 'SHADEMASTER' SHADEMASTER LOCUST	B & B	3"		6
	PLATANUS X ACERIFOLIA 'EXCLAMATION' TM EXCLAMATION LONDON PLANE TREE	B & B	3"		16
	QUERCUS BICOLOR SWAMP WHITE OAK	B & B	3"		8
	QUERCUS MACROCARPA BURR OAK	B & B	3"		4
	TILIA AMERICANA 'BOULEVARD' BOULEVARD LINDEN	B & B	3"		9
	ULMUS PROPINQUA 'EMERALD SUNSHINE' EMERALD SUNSHINE ELM	B & B	3"		5
	ZELKOVA SERRATA 'MUSASHINO' SAWLEAF ZELKOVA	B & B	3"		7
EVERGREEN TREES	BOTANICAL / COMMON NAME	SIZE	CALIPER		QTY
	PICEA ABIES NORWAY SPRUCE	B&B, 8' HT.			20
ORNAMENTAL TREES	BOTANICAL / COMMON NAME	SIZE	CALIPER		QTY
	CEROIS CANADENSIS EASTERN REDBUD	B & B	3"		3
	MALUS X 'PRAIRIFIRE' PRAIRIFIRE CRABAPPLE	B & B	3"		5
SHRUBS	BOTANICAL / COMMON NAME	SIZE			
	BUXUS X 'GREEN VELVET' BOXWOOD	5 GAL			10
	CHASMANTHIUM LATIFOLIUM NORTHERN SEA OATS	1 GAL			68
	CORNUS STOLONIFERA 'FARROW' TM ARCTIC FIRE RED TWIG DOGWOOD	5 GAL			21
	DIERVILLA RIVULARIS 'KODIAK ORANGE' KODIAK ORANGE BUSH-HONEYSUCKLE	5 GAL			15
	JUNIPERUS CHINENSIS 'SEA GREEN' SEA GREEN JUNIPER	5 GAL			92
	JUNIPERUS SABINA 'BUFFALO' BUFFALO JUNIPER	5 GAL			11
	VIBURNUM NUDUM 'WINTERHUR' WINTERHUR VIBURNUM	5 GAL			15
GROUND COVERS	BOTANICAL / COMMON NAME	CONT		SPACING	
	FESTUCA TURF TYPE TALL FESCUE BLEND	SEED			79,385 SF
	FESTUCA TURF TYPE TALL FESCUE BLEND	SOD			52,655 SF
	RIVER ROCK SEE DETAILS FOR INFORMATION	SF			2,963 SF
NATIVE VEGETATION	BOTANICAL / COMMON NAME	CONT		SPACING	
	PANICUM VIRGATUM SWITCH GRASS	SEED			56,706 SF




DWG: F:\2021\04001-04500\021-04157-B\40-Design\AutoCAD\Final Plans\Sheets\GNVC\LSC02_B2104157.dwg
DATE: Dec 06, 2022 9:44am
XREFS: C:\BASE_B2104157 C:\BASE_B2104157 C:\PSURF_B2104157 C:\TLK_B2104157 C:\LSC01_B2104157
USER: Imoore
C:\TLK_B2104157 C:\PSURF_B2104157 C:\BASE_B2104157 C:\LSC01_B2104157




PLANT SCHEDULE L1.01				
DECIDUOUS TREES	BOTANICAL / COMMON NAME	SIZE	CALIPER	QTY
	EUCOMMIA ULMOIDES HARDY RUBBER TREE	B & B	3"	2
	GLEDITSIA TRIACANTHOS INERMIS 'SHADEMASTER' SHADEMASTER LOCUST	B & B	3"	2
	PLATANUS X ACERIFOLIA 'EXCLAMATION' TM EXCLAMATION LONDON PLANE TREE	B & B	3"	9
	QUERCUS BICOLOR SWAMP WHITE OAK	B & B	3"	6
	QUERCUS MACROCARPA BURR OAK	B & B	3"	2
EVERGREEN TREES	BOTANICAL / COMMON NAME	SIZE	CALIPER	QTY
	PICEA ABIES NORWAY SPRUCE	B&B, 8' HT.		4
SHRUBS	BOTANICAL / COMMON NAME	SIZE		
	CORNUS STOLONIFERA 'FARROW' TM ARCTIC FIRE RED TWIG DOGWOOD	5 GAL		4
GROUND COVERS	BOTANICAL / COMMON NAME	CONT		
	FESTUCA TURF TYPE TALL FESCUE BLEND	SOD		
	RIVER ROCK SEE DETAILS FOR INFORMATION	SF		
NATIVE VEGETATION	BOTANICAL / COMMON NAME	CONT		
	PANICUM VIRGATUM SWITCH GRASS	SEED		
GROUND COVERS	BOTANICAL / COMMON NAME	CONT		
	FESTUCA TURF TYPE TALL FESCUE BLEND	SEED		

SEE SHEET L1.0 FOR COMPLETE PLANT SCHEDULE FOR SIZE AND TOTAL QUANTITIES.
NOTE: ALL EQUIPMENT MUST BE SCREENED WHETHER OR NOT INDICATED ON PLANS. FIELD ADJUSTMENTS MAY BE NECESSARY TO ACCOMMODATE SITE CONDITIONS EQUIPMENT AND LANDSCAPE. COORDINATE WITH LANDSCAPE ARCHITECT FOR ADEQUATE SCREENING. MUST MEET CITY REQUIREMENTS.



KEY MAP
NOT TO SCALE



olsson

7301 West 133rd Street, Suite 200
Overland Park, KS 66213-7755
TEL 913.381.1170
www.olsosn.com

SCANNELL

PROPERTIES

STATE OF MISSOURI
JULY 2022
NUMBER
LA-2009014762
LANDSCAPE ARCHITECT

REV. NO.	DATE	REVISIONS DESCRIPTION
1	06-28-2022	CITY COMMENTS
2	06-28-2022	CITY COMMENTS
3	06-15-2022	CITY COMMENTS
4	10-04-2022	CITY COMMENTS
5	10-18-2022	CITY COMMENTS
6	11-11-2022	CITY COMMENTS
7	11-11-2022	CITY COMMENTS

LANDSCAPE PLAN - BUILDING 2

FINAL DEVELOPMENT PLAN - BUILDING 2

SCANNELL DEVELOPMENT LEE'S SUMMIT LOGISTICS

NORTHWEST CORNER OF TUDOR ROAD AND MAIN STREET

LEE'S SUMMIT, MISSOURI

2022

SHEET
L1.01

SEE SHEET L1.0 FOR COMPLETE PLANT SCHEDULE FOR SIZE AND TOTAL QUANTITIES.

NOTE: ALL EQUIPMENT MUST BE SCREENED WHETHER OR NOT INDICATED ON PLANS. FIELD ADJUSTMENTS MAY BE NECESSARY TO ACCOMMODATE SITE CONDITIONS EQUIPMENT AND LANDSCAPE. COORDINATE WITH LANDSCAPE ARCHITECT FOR ADEQUATE SCREENING. MUST MEET CITY REQUIREMENTS.






REV.	NO.	DATE	REVISIONS DESCRIPTION
1	06-25-2022	CITY COMMENTS	
2	07-26-2022	CITY COMMENTS	
3	09-13-2022	CITY COMMENTS	
4	10-10-2022	CITY COMMENTS	
5	10-19-2022	CITY COMMENTS	
6	11-21-2022	ADDENDUM 1	
			REVISIONS
2022			


drawn by: SI
checked by: LM
approved by: SR
QA/QC by: MK
project no.: B21-04157
drawing 00_LSC02_B2104157.dwg
date: 03.11.2022

SHEET
L1.02




PLANT SCHEDULE L1.03				
DECIDUOUS TREES	BOTANICAL / COMMON NAME	SIZE	CALIPER	QTY
	EUCOMMIA ULMOIDES HARDY RUBBER TREE	B & B	3"	1
EVERGREEN TREES	BOTANICAL / COMMON NAME	SIZE	CALIPER	QTY
	PICEA ABIES NORWAY SPRUCE	B&B, 8' HT.		2
GROUND COVERS	BOTANICAL / COMMON NAME	CONT		
	FESTUCA TURF TYPE TALL FESCUE BLEND	SEED		

EXISTING VEGETATION TO REMAIN, TYP.



KEY MAP
NOT TO SCALE



SEE SHEET L1.0 FOR COMPLETE PLANT SCHEDULE FOR SIZE AND TOTAL QUANTITIES.
NOTE: ALL EQUIPMENT MUST BE SCREENED WHETHER OR NOT INDICATED ON PLANS. FIELD ADJUSTMENTS MAY BE NECESSARY TO ACCOMMODATE SITE CONDITIONS EQUIPMENT AND LANDSCAPE, COORDINATE WITH LANDSCAPE ARCHITECT FOR ADEQUATE SCREENING. MUST MEET CITY REQUIREMENTS.

LANDSCAPE PLAN
FINAL DEVELOPMENT PLAN - BUILDING 2
SCANNELL DEVELOPMENT LEE'S SUMMIT LOGISTICS
NORTHWEST CORNER OF TUDOR ROAD AND MAIN STREET
LEE'S SUMMIT, MISSOURI

drawn by: SL
checked by: LM
approved by: SR
QA/QC by: MM
project no.: B21-04157
drawing no.: 021-SG02_B2104157.dwg
date: 03.11.2022

2022

REV.	NO.	DATE	REVISIONS DESCRIPTION	BY
1		06-28-2022	CITY COMMENTS	
2		06-28-2022	CITY COMMENTS	
3		06-15-2022	CITY COMMENTS	
4		10-04-2022	CITY COMMENTS	
5		10-18-2022	CITY COMMENTS	
6		11-14-2022	CITY COMMENTS	
7		11-14-2022	DESIGNER	


REVISIONS



SCANNELL
PROPERTIES

olsson


7301 West 133rd Street, Suite 200
Overland Park, KS 66213-7755
TEL 913.381.1170
www.olsson.com




MATCHLINE
SEE SHEET L1.02

PLANT SCHEDULE L1.04				
DECIDUOUS TREES	BOTANICAL / COMMON NAME	SIZE	CALIPER	QTY
	EUCOMMIA ULMOIDES HARDY RUBBER TREE	B & B	3"	4
	PLATANUS X ACERIFOLIA 'EXCLAMATION' TM EXCLAMATION LONDON PLANE TREE	B & B	3"	7
	QUERCUS BICOLOR SWAMP WHITE OAK	B & B	3"	1
	ZELKOVA SERRATA 'MUSASHINO' SAWLEAF ZELKOVA	B & B	3"	6
EVERGREEN TREES	BOTANICAL / COMMON NAME	SIZE	CALIPER	QTY
	PICEA ABIES NORWAY SPRUCE	B&B, 8' HT.		7
ORNAMENTAL TREES	BOTANICAL / COMMON NAME	SIZE	CALIPER	QTY
	CERCIS CANADENSIS EASTERN REDBUD	B & B	3"	3
	MALUS X 'PRAIRIFIRE' PRAIRIFIRE CRABAPPLE	B & B	3"	4
SHRUBS	BOTANICAL / COMMON NAME	SIZE		
	CORNUS STOLONIFERA 'FARROW' TM ARCTIC FIRE RED TWIG DOGWOOD	5 GAL		5
	JUNIPERUS CHINENSIS 'SEA GREEN' SEA GREEN JUNIPER	5 GAL		28
	JUNIPERUS SABINA 'BUFFALO' BUFFALO JUNIPER	5 GAL		7
GROUND COVERS	BOTANICAL / COMMON NAME	CONT		
	FESTUCA TURF TYPE TALL FESCUE BLEND	SOD		
NATIVE VEGETATION	BOTANICAL / COMMON NAME	CONT		
	PANICUM VIRGATUM SWITCH GRASS	SEED		
GROUND COVERS	BOTANICAL / COMMON NAME	CONT		
	FESTUCA TURF TYPE TALL FESCUE BLEND	SEED		

SEE SHEET L1.0 FOR COMPLETE PLANT SCHEDULE FOR SIZE AND TOTAL QUANTITIES.
NOTE: ALL EQUIPMENT MUST BE SCREENED WHETHER OR NOT INDICATED ON PLANS. FIELD ADJUSTMENTS MAY BE NECESSARY TO ACCOMMODATE SITE CONDITIONS EQUIPMENT AND LANDSCAPE. COORDINATE WITH LANDSCAPE ARCHITECT FOR ADEQUATE SCREENING. MUST MEET CITY REQUIREMENTS.



KEY MAP
NOT TO SCALE



DWG: F:\2021\04001-04500\021-04157-B\40-Design\AutoCAD\Final Plans\Sheets\GNVC\LSC02_B2104157.dwg
DATE: Dec 06, 2022 9:45am
XREFS: C:\BASE_B2104157 C:\BASE_B2104157 C:\PSURF_B2104157 C:\LSC01_B2104157 C:\TLK_B2104157
USER: Imoore
C:\TLK_B2104157

olsson

7301 West 133rd Street, Suite 200
Overland Park, KS 66204-7756
TEL 913.381.1170 www.olsson.com

SCANNELL

PROPERTIES

REV. NO.	DATE	REVISIONS DESCRIPTION
1	06-29-2022	CITY COMMENTS
2	06-29-2022	CITY COMMENTS
3	06-15-2022	CITY COMMENTS
4	10-04-2022	CITY COMMENTS
5	10-12-2022	CITY COMMENTS
6	11-15-2022	CITY COMMENTS

BY: _____

REVISIONS

2022

LANDSCAPE PLAN

FINAL DEVELOPMENT PLAN - BUILDING 2

SCANNELL DEVELOPMENT LEE'S SUMMIT LOGISTICS

NORTHWEST CORNER OF TUDOR ROAD AND MAIN STREET

LEE'S SUMMIT, MISSOURI

drawn by: _____

checked by: _____

QA/QC by: _____


project no: B21-04157

drawing no: 021-SG02_B2104157.dwg


date: 03.11.2022

SHEET


L1.04




1 Evergreen Tree Planting Detail
not to scale




3 Shrub Planting Detail
not to scale




2 Deciduous Tree Planting Detail
not to scale



4 V-Trench Edging Detail
not to scale



6 Ground Mounted Mechanical Equipment Screening Detail
not to scale



7 Mow Strip Detail
not to scale

PLANTING NOTES

- ALL WORK SHALL BE COORDINATED WITH THE WORK OF OTHER TRADES.
- LOCATE AND FLAG ALL UNDERGROUND UTILITIES PRIOR TO ANY CONSTRUCTION. CONTRACTOR SHALL PROTECT EXISTING OVERHEAD AND UNDERGROUND UTILITIES. ANY DAMAGE TO SUCH SHALL BE REPAIRED BY THE CONTRACTOR AT NO EXPENSE TO THE OWNER.
- PLANTS AND OTHER MATERIALS ARE QUANTIFIED AND SUMMARIZED FOR THE CONVENIENCE OF THE CITY AND LOCAL GOVERNING BODIES. CONFIRM AND INSTALL SUFFICIENT QUANTITIES TO COMPLETE THE WORK AS DRAWN.
- PLAN IS SUBJECT TO CHANGES BASED ON PLANT SIZE AND MATERIAL AVAILABILITY. ALL CHANGES OR SUBSTITUTIONS MUST BE APPROVED BY THE CITY OF LEE'S SUMMIT, MO AND THE LANDSCAPE ARCHITECT.
- ALL PLANT MATERIAL SHALL BE NURSERY GROWN TO MEET MINIMUM SIZE AS SPECIFIED IN THE AMERICAN STANDARD FOR NURSERY STOCK ESTABLISHED BY THE AMERICAN NURSERY & LANDSCAPE ASSOCIATION (ANLA). THE LANDSCAPE ARCHITECT OR OWNER'S REPRESENTATIVE RESERVES THE RIGHT TO REJECT ANY PLANT MATERIAL NOT MEETING SPECIFICATIONS.
- ALL TREES SHALL BE CALIPERED AND ANY UNDERSIZED TREES SHALL BE REJECTED. SPECIFIED CALIPER MEASUREMENT FOR TREES SHALL BE MEASURED AT 12" ABOVE THE GRADE.
- PLANTING OF TREES, SHRUBS, SODDED AND SEEDED TURFGRASS SHALL BE COMMENCED DURING EITHER THE SPRING (MARCH 15-JUNE 15) OR FALL (SEPTEMBER 1 - OCTOBER 15) PLANTING SEASON AND WITH WATER AVAILABLE FOR IRRIGATION PURPOSES.
- CONTRACTOR SHALL STAKE OR MARK ALL PLANT MATERIAL LOCATIONS PRIOR TO INSTALLATION. CONTRACTOR SHALL HAVE THE LANDSCAPE ARCHITECT APPROVE ALL STAKING PRIOR TO INSTALLATION. FIELD ADJUSTMENTS MAY BE NECESSARY BASED UPON FIELD CONDITIONS (I.E. ROOT BALL AND DROP INLET CONFLICT). ALL ADJUSTMENTS MUST BE APPROVED BY THE LANDSCAPE ARCHITECT.
- THE LANDSCAPE CONTRACTOR SHALL REMOVE ALL CONSTRUCTION DEBRIS AND MATERIALS INJURIOUS TO PLANT GROWTH FROM PLANTING PITS AND BEDS PRIOR TO BACKFILLING WITH PLANTING MIX.
- A PRE-EMERGENT HERBICIDE SHALL BE APPLIED TO ALL SHRUB BEDS PRIOR TO THE INSTALLATION OF ANY PLANT MATERIAL.
- BACKFILL ALL PLANTING BEDS TO A MINIMUM 12-INCH DEPTH WITH PLANTING SOIL MIX. PLANTING SOIL MIX SHALL CONSIST OF ONE (1) PART PERLITE, ONE (1) PART PEAT MOSS, AND TWO (2) PARTS CLEAN LOAM TOPSOIL. THOROUGHLY MIX PLANTING SOIL COMPONENTS PRIOR TO PLACEMENT.
- ALL LANDSCAPE PLANTING AREAS, EXCLUDING TURF AREAS SHALL BE MULCHED WITH A MINIMUM OF 3-4" SHREDDED HARDWOOD MULCH UNLESS OTHERWISE NOTED ON PLANS.
- V-TRENCH LANDSCAPE EDGING IS TO BE USED ON ALL LANDSCAPE BEDS ABUTTING SODDED AREAS.
- ALL LANDSCAPE AREAS SHALL BE IRRIGATED WITH A HIGH-EFFICIENCY, AUTOMATIC IRRIGATION SYSTEM ACHIEVING 100% EVEN COVERAGE OF ALL LANDSCAPE AREAS. IRRIGATION SYSTEM SHALL BE DESIGN-BUILD TO MEET ALL CITY REQUIREMENTS.
- LANDSCAPE CONTRACTOR IS TO BE RESPONSIBLE FOR WATERING ALL PLANT MATERIALS UNTIL THE TIME THE PERMANENT IRRIGATION SYSTEM IS FULLY FUNCTIONAL AND ACCEPTANCE OF THE PROJECT HAS TAKEN PLACE. ANY MATERIAL WHICH DIES, OR DEFOLIATES (PRIOR TO ACCEPTANCE OF THE WORK) WILL BE PROMPTLY REMOVED AND REPLACED.
- THE CONTRACTOR WILL COMPLETELY GUARANTEE ALL WORK FOR A PERIOD OF ONE YEAR BEGINNING AT THE DATE OF ACCEPTANCE. CONTRACTOR WILL MAKE ALL REPLACEMENTS PROMPTLY (AS PER DIRECTION OF OWNER).

SODDING NOTES

- ALL DISTURBED AREAS SHALL BE SODDED WITH TURF-TYPE TALL FESCUE SOD WITH A MINIMUM OF 3 CULTIVARS.
- ALL LAWN AREAS SHALL RECEIVE A MINIMUM 6-INCH DEPTH OF TOPSOIL COMPACTED TO 85% MAXIMUM DENSITY AT OPTIMUM MOISTURE CONTENT.
- THE ENTIRE SURFACE TO BE SODDED SHALL BE REASONABLY SMOOTH AND FREE FROM STONES, ROOTS, OR OTHER DEBRIS.
- SOD SHALL BE MACHINE STRIPPED AT A UNIFORM SOIL THICKNESS OF APPROXIMATELY ONE INCH (PLUS OR MINUS 1/4-INCH). THE MEASUREMENT FOR THICKNESS SHALL EXCLUDE TOP GROWTH AND THATCH, AND SHALL BE DETERMINED AT THE TIME OF CUTTING IN THE FIELD. PRECAUTIONS SHALL BE TAKEN TO PREVENT DRYING AND HEATING. SOD DAMAGED BY HEAT AND DRY CONDITIONS, AND SOD CUT MORE THAN 18 HOURS BEFORE BEING INCORPORATED INTO THE WORK SHALL NOT BE USED.
- HANDLING OF SOD SHALL BE DONE IN A MANNER THAT WILL PREVENT TEARING, BREAKING, DRYING, AND OTHER DAMAGE. PROTECT EXPOSED ROOTS FROM DEHYDRATION. DO NOT DELIVER MORE SOD THAN CAN BE LAID WITHIN 24 HOURS.
- MOISTEN PREPARED SURFACE IMMEDIATELY PRIOR TO LAYING SOD. WATER THOROUGHLY AND ALLOW SURFACE TO DRY BEFORE INSTALLING SOD. FERTILIZE, HARROW OR RAKE FERTILIZER IN THE TOP 1-1/2-INCHES OF TOPSOIL, AT A UNIFORM RATE OF ONE POUND OF NITROGEN PER 1000 S.F.
- SOD SHALL BE CAREFULLY PLACED IN THE DIRECTION PARALLEL WITH THE SLOPE OF THE AREA TO BE SODDED. SOD STRIPS SHALL BE BUTTED TOGETHER BUT NOT OVERLAPPED WITH THE SEAMS STAGGERED ON EACH ROW.
- FERTILIZER SHALL BE 20-10-5 COMMERCIAL FERTILIZER OF THE GRADE, TYPE, AND FORM SPECIFIED AND SHALL COMPLY WITH THE RULES OF THE STATE OF MISSOURI DEPT. OF AGRICULTURE. FERTILIZER SHALL BE IDENTIFIED ACCORDING TO THE PERCENT N, P, K, IN THAT ORDER.
- ALL SOD ON SLOPES GREATER THAN 5:1 AND WITHIN DETENTION AREAS SHALL BE STAKED.
- SATURATE SOD WITH FINE WATER SPRAY WITHIN TWO HOURS OF PLANTING. DURING FIRST WEEK AFTER PLANTING, WATER DAILY OR MORE FREQUENTLY AS NECESSARY TO MAINTAIN MOIST SOIL TO A MINIMUM DEPTH OF FOUR INCHES BELOW SOD.
- CONTRACTOR SHALL PROVIDE FULL MAINTENANCE FOR SODDED TURF GRASS FOR A PERIOD OF 30 DAYS AFTER THE DATE OF FINAL ACCEPTANCE. AT THE END OF THE MAINTENANCE PERIOD, A HEALTHY, WELL-ROOTED, EVEN-COLORED, VIABLE TURF MUST BE ESTABLISHED. THE TURF GRASS SHALL BE FREE OF WEEDS, OPEN JOINTS, BARE AREAS, AND SURFACE IRREGULARITIES.

olsson


SCANNELL
PROPERTIES



REV.	DATE	REVISIONS DESCRIPTION
1	06-29-2022	CITY COMMENTS
2	06-29-2022	CITY COMMENTS
3	06-13-2022	CITY COMMENTS
4	10-04-2022	CITY COMMENTS
5	10-18-2022	CITY COMMENTS
6	11-11-2022	CITY COMMENTS

REV.	DATE	REVISIONS DESCRIPTION
1	06-29-2022	CITY COMMENTS
2	06-29-2022	CITY COMMENTS
3	06-13-2022	CITY COMMENTS
4	10-04-2022	CITY COMMENTS
5	10-18-2022	CITY COMMENTS
6	11-11-2022	CITY COMMENTS

drawn by:	SL
checked by:	LM
approved by:	SR
GNCC by:	MM
project no.:	B21-04157
drawing no.:	B21-SG01_B2104157.dwg
date:	03.11.2022



SITE LIGHTING PHOTOMETRICS PLAN
FINAL DEVELOPMENT PLAN - BUILDING 2

SCANNELL DEVELOPMENT LEE'S SUMMIT LOGISTICS
NORTHWEST CORNER OF TUDOR ROAD AND MAIN STREET

LEE'S SUMMIT, MISSOURI

REV/NO.	DATE	REVISIONS DESCRIPTION	BY
1	09-29-2022	CITY COMMENTS	
2	10-03-2022	CITY COMMENTS	
3	09-13-2022	CITY COMMENTS	
4	10-04-2022	CITY COMMENTS	
5	10-13-2022	CITY COMMENTS	

drawn by: SP

checked by: TD

approved by: TD

QA/QC by: TD

project no.: B21-04157

drawing no.: E_NSITE_B02104157


date: 09.03.2022

2022


REVISIONS

SHEET


E1.01



SCANNELL
P R O P E R T I E S



7301 West 133rd Street, Suite 200
Overland Park, KS 66213-7750
TEL 913.381.1170
www.olsson.com



DWG: F:\2021\04001-04500\021-04157-b\40-design\AutoCAD\final plans\Sheets\MECH\Electrical\E_NSITE_B02104157.dwg USER: bpoyme2
DATE: Oct 27, 2022 9:10am XREFS: C_XBASE_B2104157 C_PBASE_B2104157 E_TBK_B2104157 E_PHOTO_B2104157 E_PBASE_B02104157

olsson

7301 West 133rd Street, Suite 200
Overland Park, KS 66213-7755
TEL 913.381.1170
www.olsson.com

SCANNELL
PROPERTIES

7301 West 133rd Street, Suite 200
Overland Park, KS 66213-7755
TEL 913.381.1170
www.olsson.com

SITE LIGHTING POWER PLAN
FINAL DEVELOPMENT PLAN - BUILDING 2
SCANNELL DEVELOPMENT LEE'S SUMMIT LOGISTICS
NORTHWEST CORNER OF TUDOR ROAD AND MAIN STREET
LEE'S SUMMIT, MISSOURI

drawn by: SP
checked by: TD
approved by: TD
QA/QC by: TD
project no.: B21-04157
drawing no.: E_NSITE_B02104157
date: 05.03.2022

2022

SHEET
E2.00

SECTION 260000 ELECTRICAL

1. GENERAL CONDITIONS:

- A. THIS CONTRACTOR SHALL INSPECT THE SITE WHERE THIS WORK IS TO BE PERFORMED AND FULLY FAMILIARIZE HIMSELF WITH ALL CONDITIONS RELATED TO THIS PROJECT.

B. THIS CONTRACTOR SHALL OBTAIN AND PAY FOR ALL PERMANENT AND TEMPORARY PERMITS AND LICENSES AND SHALL MAKE ALL DEPOSITS AND PAY ALL FEES REQUIRED FOR THE PERFORMANCE OF WORK UNDER THIS SECTION OTHER THAN THOSE DEPOSITS OR FEES WHICH ARE FULLY REFUNDABLE TO THE OWNER.

C. DRAWINGS SHOW THE GENERAL ARRANGEMENT OF ALL SYSTEMS AND COMPONENTS COVERED UNDER THIS SECTION. WHERE LOCAL CONDITIONS NECESSITATE A REARRANGEMENT, THE CONTRACTOR SHALL PREPARE, AND SUBMIT FOR APPROVAL, DRAWINGS OF THE PROPOSED REARRANGEMENT. THIS CONTRACTOR SHALL CAREFULLY INVESTIGATE THE STRUCTURAL AND FINISH CONDITIONS AFFECTING ALL OF HIS WORK AND SHALL ARRANGE SUCH WORK ACCORDINGLY, FURNISHING SUCH FITTINGS AND ACCESSORIES AS MAY BE REQUIRED TO MEET SUCH CONDITIONS AT NO ADDITIONAL COST TO THE OWNER.

D. THIS CONTRACTOR SHALL VERIFY ALL DIMENSIONS. DRAWINGS SHALL NOT BE SCALED TO DETERMINE DIMENSIONS.

E. SPECIFICATIONS AND DRAWINGS ARE COMPLEMENTARY AND WHAT IS CALLED FOR IN ONE SHALL BE AS BINDING AS IF CALLED FOR BY BOTH.

F. FURNISH LABOR, MATERIALS, EQUIPMENT AND SERVICES REQUIRED AS SHOWN ON THE DRAWINGS AND SPECIFIED IN DIVISION 15.

G. ALL WORK SHALL BE COMPLETE AND SHALL BE LEFT IN OPERATING CONDITION.

H. INCLUDE ALL PARTS AND LABOR WHICH ARE INCIDENTAL AND NECESSARY FOR A COMPLETE AND OPERABLE INSTALLATION EVEN THOUGH NOT SPECIFICALLY MENTIONED IN THE CONTRACT DOCUMENTS. .

I. REQUEST INSPECTIONS AS REQUIRED BY REGULATING AGENCIES AND/OR REGULATIONS. PAY ALL CHARGES FOR INSPECTIONS BY REGULATING AGENCIES OF INSTALLATIONS OF PLANS SPECIFICATIONS.

J. PROVIDE THE OWNER WITH A CERTIFICATE OF FINAL INSPECTION AND APPROVAL BY ENFORCEMENT AUTHORITIES.

K. FURNISH: TO OBTAIN, COORDINATE, SUBMIT THE NECESSARY DRAWINGS, DELIVER TO THE JOB SITE IN NEW CONDITION READY FOR INSTALLATION, UNLOAD AND UNPACK, AND GUARANTEE.

L. INSTALL: TO RECEIVE AT THE JOB SITE, STORE, ASSEMBLE, ERECT, SET IN PLACE, ANCHOR, APPLY, FINISH, PROTECT, CLEAN, TEST, START-UP, AND MAKE READY FOR OWNER'S USE.

M. PROVIDE: TO FURNISH AND INSTALL.

N. PROVIDE NEW MATERIAL AND EQUIPMENT, UNLESS NOTED OTHERWISE. PROTECT EQUIPMENT AND MATERIAL FROM DAMAGE, DIRT AND THE WEATHER.

O. THE ENGINEER RESERVES THE RIGHT TO REJECT MATERIAL OR WORKMANSHIP NOT IN ACCORDANCE WITH THE CONTRACT DOCUMENTS, BEFORE OR AFTER INSTALLATION, AT NO ADDITIONAL COST TO THE OWNER.

P. REFINISH ALL ELECTRICAL EQUIPMENT DAMAGED DURING SHIPPING, INSTALLATION AND/OR PRIOR TO FINAL ACCEPTANCE TO ITS ORIGINAL CONDITION. REMOVE ALL RUST, PRIME, AND PAINT PER MANUFACTURER'S RECOMMENDATIONS FOR FINISH EQUAL TO ORIGINAL.

Q. PROTECT OPENINGS AND EQUIPMENT FROM OBSTRUCTION, BREAKAGE, MISUSE, DAMAGE OR BLEMISHES. PROTECT MATERIALS AND EQUIPMENT IMMEDIATELY UPON RECEIPT AT THE JOB SITE OR IMMEDIATELY AFTER THEY HAVE BEEN REMOVED FROM THEIR SHIPPING CONTAINERS. UNLESS NOTED OTHERWISE, KEEP THEM CLEAN AND UNDAMAGED UNTIL FINAL ACCEPTANCE OF THE ENTIRE PROJECT BY THE OWNER. WHEN A PORTION OF THE BUILDING IS OCCUPIED BY THE OWNER BEFORE SUBSTANTIAL COMPLETION OF THE ENTIRE PROJECT, MAKE ARRANGEMENTS TO TRANSFER RESPONSIBILITY FOR PROTECTION AND HOUSEKEEPING FOR THE OCCUPIED PORTION.

R. CONTRACTOR IS RESPONSIBLE FOR ANY DAMAGE TO ELECTRICAL EQUIPMENT, MATERIALS WORK UNTIL FINAL ACCEPTANCE OF THE ENTIRE PROJECT BY THE OWNER.

S. KEEP THE PREMISES FREE FROM ACCUMULATION OF WASTE MATERIAL OR RUBBISH, CAUSED BY HIS EMPLOYEES OR WORK, AT ALL TIMES. REMOVE RUBBISH, TOOLS, SCAFFOLDING, AND SURPLUS MATERIALS FROM AND ABOUT THE BUILDING, AND LEAVE WORK AREAS "BROOM CLEAN" OR ITS EQUIVALENT DAILY. CLEAN ELECTRICAL EQUIPMENT AND REMOVE TEMPORARY IDENTIFICATION.

T. OPERATE EQUIPMENT AND SYSTEMS IN ALL THEIR OPERATING MODES. TO VERIFY PROPER OPERATION, PRIOR TO FINAL FIELD OBSERVATION AND OWNER INSTRUCTIONS. PREPARE A PRE-INSPECTION REPORT AND SUBMIT TO THE ENGINEER AND OWNER FOR REVIEW.

U. TEST ALL INSTALLED ELECTRICAL EQUIPMENT AND CABLES REQUIRED BY CONSTRUCTION DOCUMENTS ACCORDING TO THE REQUIREMENTS OF THE MOST CURRENT EDITION OF THE INTERNATIONAL ELECTRICAL TESTING ASSOCIATION, INC. (NETA). IF ACCEPTABLE PERFORMANCE OF ANY TEST IS NOT ACHIEVED, MAKE THE NECESSARY CORRECTIONS AND THE TEST SHALL BE REPEATED UNTIL ACCEPTABLE PERFORMANCE IS ACHIEVED. PROVIDE WRITTEN REPORTS OF ALL TESTS, WITH FAILURES IDENTIFIED, TO ENGINEER.

V. FULLY INSTRUCT THE OWNER'S DESIGNATED PERSONNEL IN THE OPERATION OF EACH ELECTRICAL SYSTEM AT THE TIME IT IS PUT INTO SERVICE. PROVIDE INSTRUCTION USING COMPETENT INSTRUCTORS AND FACTORY TRAINED PERSONNEL.

W. CONTRACTOR SHALL INSTALL ALL MATERIALS AND EQUIPMENT AS PER MANUFACTURER'S WRITTEN INSTRUCTIONS AND/OR RECOMMENDATIONS.

X. CONTRACTOR SHALL PROVIDE SHOP DRAWINGS FOR ALL EQUIPMENT INDICATED AND/OR REQUIRED FOR A COMPLETE AND OPERATIONAL SYSTEM. A FORM INDICATING ALL SHOP DRAWINGS TO BE PROVIDED AS PART OF THE PROJECT SHALL BE SUBMITTED FOR REVIEW BY THE ENGINEER PRIOR TO ANY SHOP DRAWING SUBMITTAL REVIEW.

Y. THIS SPECIFICATION SHALL INCORPORATE ALL PROJECT REQUIREMENTS AND RESPONSIBILITIES INDICATED WITHIN THE FRONT-END OF THE PROJECT MANUAL.

2. LAWS, REGULATIONS, ORDINANCES, STATUTES AND CODES:

- A. ALL WORK SHALL BE INSTALLED IN ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE, THE NATIONAL FIRE PROTECTION ASSOCIATION CODES, THE NATIONAL ELECTRICAL SAFETY CODE, LOCAL BUILDING CODE, AND ALL APPLICABLE LOCAL LAWS, REGULATIONS, ORDINANCES, STATUTES AND CODES. SHOULD ANY WORK SHOWN ON THE DRAWINGS OR SPECIFIED HEREIN BE OF LOWER STANDARD, THE CONTRACTOR SHALL REFER THE POINTS IN QUESTION TO THE ENGINEER FOR APPROVAL.

3. SCOPE OF WORK:

- A. WORK UNDER THIS SECTION SHALL CONSIST OF FURNISHING ALL LABOR, MATERIAL AND ASSOCIATED SERVICES REQUIRED TO COMPLETELY CONSTRUCT AND LEAVE ALL SYSTEMS OPERATIONAL AS SHOWN ON THE

DRAWINGS AND HEREIN DESCRIBED.

- B. ALL WORK PERFORMED UNDER THIS SECTION SHALL BE DONE IN A NEAT AND WORKMANLIKE MANNER.

4. MATERIALS AND EQUIPMENT REVIEW:

- A. AS SOON AS POSSIBLE AFTER THE AWARD OF THE CONTRACT, THIS CONTRACTOR SHALL SUBMIT FOR REVIEW SHOP DRAWINGS FOR ALL EQUIPMENT TO BE FURNISHED FOR THIS PROJECT. SUBMITTALS SHALL HIGHLIGHT THE MANUFACTURER'S NAME, MODEL NUMBER, DESCRIPTIVE ENGINEERING DATA AND ALL NECESSARY INFORMATION AS TO FINISH, MATERIAL, GAUGES AND ACCESSORIES.

B. ALL PORTIONS OF THE SHOP DRAWINGS THAT ARE INTENDED TO BE REVIEWED SHALL BE HIGHLIGHTED. ANY PORTION NOT CALLED OUT SHALL BE ASSUMED TO BE EXCLUDED FROM THE JOB.

5. GUARANTEE:

- A. THIS CONTRACTOR SHALL GUARANTEE COMPLETE SYSTEM OPERATION AND THAT THE APPARATUS FURNISHED AND INSTALLED WILL BE FREE FROM DEFECTS IN WORKMANSHIP AND MATERIALS AND WILL GIVE SATISFACTORY SERVICE. THE CONTRACTOR AGREES TO REPLACE, WITHOUT EXPENSE TO THE OWNER, ANY PART OF THE INSTALLATION WHICH PROVES OR BECOMES DEFECTIVE WITHIN ONE YEAR AFTER THE SYSTEM IS ACCEPTED.

6. COORDINATION:

- A. THIS CONTRACTOR SHALL EXAMINE ALL ARCHITECTURAL, MECHANICAL, STRUCTURAL AND OTHER DRAWINGS RELATED TO THIS PROJECT, AND IT SHALL BE HIS RESPONSIBILITY TO COORDINATE THE ELECTRICAL WORK WITH OTHER TRADES.

7. AS-BUILT DRAWINGS:

- A. THIS CONTRACTOR SHALL PREPARE COMPLETE AS-BUILT DRAWINGS OF ALL ELECTRICAL SYSTEMS AND TURN OVER TO THE ENGINEER REVISED ELECTRONIC CAD FILES.

B. THIS CONTRACTOR SHALL PREPARE AND SUBMIT TO THE OWNER'S REPRESENTATIVE FIVE BOUND SETS OF MANUFACTURER'S LITERATURE FOR ALL EQUIPMENT TO BE INSTALLED ON THIS PROJECT SHOWING ALL DETAILS OF EQUIPMENT, REPLACEMENT PART DATA AND MAINTENANCE INSTRUCTIONS.

8. EXCAVATION:

- A. ALL EXCAVATION AND BACKFILL REQUIRED FOR THE INSTALLATION OF ELECTRICAL WORK SHALL BE THE COMPLETE RESPONSIBILITY OF THE CONTRACTOR.

B. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROPER LAYOUT AND THE ESTABLISHMENT OF ALL LINES AND LEVELS REQUIRED FOR THE EXECUTION OF THE WORK.

C. WHEN SERVICES ARE TO BE RUN SIDE-BY-SIDE, A COMMON TRENCH MAY BE USED PROVIDING THE REQUIRED VERTICAL AND HORIZONTAL SEPARATION BETWEEN THE VARIOUS SERVICES ARE MAINTAINED AND PROVIDING THE METHODS OF BEDDING AND BACKFILL MEET THE APPROVAL OF THE ENGINEER. CONTRACTORS INVOLVED SHALL MAKE THEIR OWN AGREEMENT AS TO THE SHARING OF THE COST OF THE COMMON TRENCHING AND BACKFILL WORK.

D. LOCATE EXISTING UNDERGROUND UTILITIES IN AREAS OF EXCAVATION WORK. SHOULD UNCHARTED, OR INCORRECTLY CHARTED, PIPING OR OTHER UTILITIES BE ENCOUNTERED DURING EXCAVATION, CONSULT UTILITY ENGINEER IMMEDIATELY FOR DIRECTIONS. COOPERATE WITH OWNER AND UTILITY COMPANIES IN KEEPING RESPECTIVE SERVICES AND FACILITIES IN OPERATION. REPAIR DAMAGED UTILITIES TO SATISFACTION OF UTILITY OWNER.

9. EXTERIOR AND FOUNDATION WALLS:

- A. ALL PIPING THROUGH EXTERIOR OR FOUNDATION WALLS SHALL PASS THROUGH SCHEDULE 40 GALVANIZED STEEL SLEEVES WHICH SHALL BE LARGE ENOUGH TO ALLOW FOR CAULKING MATERIAL. NO SLEEVES ARE PERMITTED THROUGH CONCRETE STRUCTURAL MEMBERS. ALL SLEEVES SHALL BE COORDINATED AND APPROVED BY THE STRUCTURAL ENGINEER PRIOR TO INSTALLATION.

10. FLOORS:

- A. ALL PIPING THROUGH FLOORS SHALL BE PROVIDED WITH SCHEDULE 40 GALVANIZED STEEL PIPE SLEEVES, EXTENDING 2 INCHES ABOVE FLOOR.

11. CUTTING:

- A. ALL CUTTING OF EXISTING CONCRETE FLOORS/SLABS ON GRADE IN THE INTERIOR OF THE BUILDING SHALL BE PERFORMED BY "SAW CUTTING".

12. PATCHING:

- A. ON CONCRETE, PATCH THE OPENING WITH CONCRETE, FINISHED SMOOTH WITH ADJACENT SURFACES.

13. IDENTIFICATION OF SWITCHES AND APPARATUS:

- A. ALL CABINETS, SAFETY SWITCHES, AND OTHER APPARATUS USED FOR OPERATION AND CONTROL OF CIRCUITS, APPLIANCES, AND EQUIPMENT UNDER THIS CONTRACT SHALL BE PROPERLY IDENTIFIED BY MEANS OF ENGRAVED PLASTIC PLATES BLACK WITH WHITE LETTERS.

14. GROUNDING:

- A. ALL FEEDERS AND BRANCH CIRCUITS SHALL CONTAIN GROUND WIRES.

B. ALL CONDUCTORS, MOTOR FRAMES, RACEWAYS, CABINETS, ETC., THAT REQUIRE GROUNDING SHALL BE GROUNDED IN ACCORDANCE WITH THE REQUIREMENTS OF ARTICLE 250 OF THE NATIONAL ELECTRICAL CODE, THOSE OF THE SERVING UTILITY AND LOCAL AUTHORITIES HAVING JURISDICTION.

15. CONDUIT:

- A. ALL ELECTRICAL POWER WIRING, INCLUDING LOW VOLTAGE WIRING, SHALL BE INSTALLED IN CONDUIT AS HEREIN SPECIFIED. NO CONDUIT OR TUBING OF LESS THAN 3/4 INCH NOMINAL SIZE SHALL BE USED.

B. UNDERGROUND CONDUIT SHALL BE SCHEDULE 40 AS MANUFACTURED BY CARLON OR APPROVED EQUAL. ALL CONDUITS SHALL BE INSTALLED WITH MINIMUM 36" INCH COVER.

C. CONDUIT INSTALLED ABOVE GROUND EXTERIOR SHALL BE GALVANIZED RIGID STEEL AS MANUFACTURED BY THE ALLIED TUBE AND CONDUIT CORPORATION OR APPROVED EQUAL. CONDUIT SHALL BE SHERARDIZED OR HOT-DIP GALVANIZED INSIDE AND OUTSIDE INCLUDING ENDS AND THREADS AND ENAMELED OR LACQUERED INSIDE IN ADDITION TO GALVANIZING.

D. WHEN PVC CONDUITS PENETRATE CONCRETE FLOOR CONSTRUCTION, CONTRACTOR SHALL USE RIGID STEEL ELBOWS AND EXTENSION. PVC CONDUIT/FITTINGS SHALL NOT BE PERMITTED TO BE EXPOSED ABOVE THE FLOOR.

E. THIN WALL TUBING SHALL BE REPUBLIC "ELECTRUNITE E.M.T." OR APPROVED EQUAL. SHALL BE INSTALLED INDOORS.

- F. ALL FITTINGS SHALL BE OF THE COMPRESSION TYPE AND SHALL BE WATERTIGHT.

G. CONDUIT FOR INTERIOR WIRING, IN GENERAL, SHALL BE THINWALL TUBING UNLESS OTHERWISE NOTED.

H. RACEWAYS SHALL BE CONTINUOUS FROM OUTLET TO OUTLET AND FITTING TO FITTING. A RUN OF CONDUIT BETWEEN OUTLETS OR FITTINGS SHALL NOT CONTAIN MORE THAN THE EQUIVALENT OF FOUR QUARTER-BENDS INCLUDING THOSE BENDS LOCATED IMMEDIATELY AT THE OUTLET OR FITTING. THE RADIUS OF BENDS SHALL NEVER BE SHORTER THAN THAT OF THE CORRESPONDING TRADE ELBOW. THE SYSTEM SHALL BE COMPLETE WITH OUTLETS, DISTRIBUTION BOXES, ETC., SMOOTH INSIDE AND MECHANICALLY SECURE IN PLACE. APPROVED STRAPS, HANGERS, OR SUPPORTS SHALL BE USED TO SECURE CONDUITS IN PLACE. CONDUITS SHALL, IN GENERAL, BE SUPPORTED AT INTERVALS NOT EXCEEDING 10'-0" AND WITHIN 3'-0" OF EACH OUTLET BOX, JUNCTION BOX, CABINET OR FITTING.

I. CONDUITS SHALL BE PROTECTED DURING CONSTRUCTION; PLUG AND KEEP CLEAN AND DRY. CONDUIT ENDS SHALL BE BUTTED IN CENTERS OF COUPLINGS. NO CRACKS OR FLATTENED SECTIONS WILL BE PERMITTED AT BENDS OR ELSEWHERE. ALL ENDS OF CONDUIT SHALL BE REAMED TO REMOVE ROUGH EDGES. RUNNING THREADS WILL NOT BE PERMITTED.

J. CONDUITS SHALL BE CONCEALED WITHIN THE WALLS, CEILINGS, AND FLOORS WHERE POSSIBLE AND UNLESS OTHERWISE NOTED. EXPOSED CONDUIT SHALL BE RUN PARALLEL TO OR AT RIGHT ANGLES WITH THE BUILD-ING LINES.

18. WIRE AND CABLE:

- A. WIRE AND CABLE SHALL BE AMERICAN INSULATED WIRE CORP., GENERAL CABLE CORP., SENATOR WIRE AND CABLE CORP. SOUTH WIRE OR APPROVED EQUAL, OF SIZES AS SHOWN ON THE DRAWINGS OR HEREIN SPECIFIED.

B. ALL CONDUCTORS SHALL BE COPPER.

C. NO. 10 AWG AND SMALLER CONDUCTORS SHALL BE SOLID WITH INSULATION AND NO. 8 AWG AND LARGER CONDUCTORS SHALL BE STRANDED WITH TYPE THHN/THWN INSULATION EXCEPT THAT CONDUCTORS WITHIN 3 INCHES OF LIGHT FIXTURE BALLASTS SHALL HAVE RHH, THHN, OR EQUAL INSULATION RATED FOR 90 DEGREES C. APPLICATION.

SITE LIGHTING SPECIFICATIONS
FINAL DEVELOPMENT PLAN - BUILDING 2

SCANNELL DEVELOPMENT LEE'S SUMMIT LOGISTICS
NORTHWEST CORNER OF TUDOR ROAD AND MAIN STREET
LEE'S SUMMIT, MISSOURI

drawn by: _____ SH

checked by: _____ TD

approved by: _____ TD


QA/QC by: _____ TD

project no.: B21-04157

drawing no.: E_NDET_B02104157

date: 05.03.2022

SHEET
E4.0



REV. NO.	DATE	REVISIONS DESCRIPTION	BY
1	06-28-2022	CITY COMMENTS	
2	06-13-2022	CITY COMMENTS	
3	06-13-2022	CITY COMMENTS	
4	06-04-2022	CITY COMMENTS	
5	10-15-2022	CITY COMMENTS	

REVISIONS

2022