DISCOVERY PARK MACRO STORMWATER REPORT

Prepared for:

Discovery Park Lee's Summit, LLC Columbia, Missouri



January 2023

Revised June 2023

Olsson Project No. A21-04643



TABLE OF CONTENTS

1 Intro	duction	1
1.1.	FEMA Floodplain Classification	2
1.2.	Soil Classification	3
2 MET	THODOLOGY	5
3 EXIS	STING CONDITIONS ANALYSIS	9
3.1.	Existing Stormwater Storage Areas & Detention Facilities	14
3.2.	Existing Conditions Hydrologic Modeling Results	22
3.3.	Allowable Release Rate Calculations	24
4 MAC	CRO ANALYSIS	28
4.1.	Macro Stormwater Model: Proposed Conditions Analysis	28
4.2.	Macro Stormwater Model: Fully-Developed Conditions Analysis	39
4.3.	Proposed Stormwater Best Management Practices	49
5 SUN	MARY	52
6 CON	NCLUSION	56
7 CAL	CULATIONS AND MODEL RESULTS	57
8 EXH	IIBITS AND HYDROGRAPHS	58

LIST OF TABLES

Table 1.2-1. Soil Classifications	3
Table 2-1. Precipitation Depths	5
Table 3-1(a). Existing Conditions Input Data	9
Table 3-1(b). Existing Conditions Input Sub-Watershed Data	11
Table 3-2. Hydrologic Information – Existing Conditions Summary (Subareas)	11
Table 3-3. Muskingum Channel Reach Routing Information	13
Table 3.1-1(a). Existing Storage Volume – Pump Station Drive Storage Area	15
Table 3.1-1(b). Existing Conditions Storage Area Routing –	15
Point A3 – Pump Station Drive Culverts	15
Table 3.1-2(a). Existing Storage Volume – Boone Creek Embankment	16
Table 3.1-2(b): Existing Conditions Storage Area Routing	16
Point A5 – Former Pond	16
Table 3.1-3(a). Existing Storage Volume – Pump Station Drive Storage Area	17
Table 3.1-3(b). Existing Conditions Storage Area Routing	18
Point B1 – Lee's Summit Drive Culverts (Sta. 45+15)	18
Table 3.1-4(b): Existing Conditions Storage Area Routing	19
Point A7 – Lee's Summit Drive Culverts (Sta.25+65)	19
Table 3.1-5(a): Existing Storage Volume –	20
Proposed Sub-Basin B4 Detention Facility	20
Table 3.1-5(b). Existing Conditions Storage Area Routing	20
Sub-Basin B4 Detention Facility	20
Table 3.1-6(a). Existing Storage Volume – Storage Area C2	21
Table 3.1-6(b). Existing Conditions Storage Area Routing – Storage Area C2	21
Table 3.1-4(b): Existing Conditions Storage Area Routing	22
Point D4 – I-470 Highway Culvert	22
Table 3.2-1. Hydrologic Information – Existing Conditions Summary (Junctions)	23
Table 3.3-1. Existing Conditions Allowable Release Rate Calculations	25
Table 4.1-1(a). Macro-Study Proposed Conditions Input Data	29
Table 4.1-1(b). Macro-Study Proposed Conditions Input Sub-Watershed Data	30
Table 4.1-2(a). Hydrologic Information – Macro-Study Proposed Conditions Summary	
(Subareas)	
Table 4.1-2(b). Hydrologic Information –	31
Macro-Study Proposed vs. Existing Conditions Summary (Subareas)	31

A21-04643

Table 4.1-3(a). Hydrologic Information–Macro-Study Proposed Conditions Summary	
(Junctions) 32	
Un-Detained Hydrology (for Proposed Discovery Park Basin)	
Table 4.1-3(b). Hydrologic Information – Comparison of Results:	
Macro- Proposed vs. Existing Conditions Summary (Junctions) Un-Detained Hydrology	
Table 4.1-4. Allowable Release Rate Evaluation –	34
Proposed Conditions Macro Model – Without Detention	
Table 4.1-5(a). Proposed Conditions Storage Volume –	35
Discovery Park Stormwater Detention Facility	35
Table 4.1-5(b). Macro-Study Proposed Conditions Hydrologic Routing Summary	36
Discovery Park Stormwater Detention Facility	36
Table 4.1-6(a). Hydrologic Information – Macro- Proposed Conditions Summary (Junctions)	
Including Proposed Discovery Park Detention Basin	
Table 4.1-6(b). Hydrologic Information – Comparison of Results:	37
Macro- Proposed vs. Existing Conditions Summary (Junctions) Detained Hydrology	37
Table 4.1-7. Allowable Release Rate Evaluation –	38
Proposed Conditions Macro Study (With Detention)	38
Table 4.2-1(a). Macro-Study Fully-Developed Conditions Input Data	39
Table 4.2-1(b). Macro-Study Fully-Developed Conditions Input Sub-Watershed Data	40
Table 4.2-2(a). Hydrologic Information – Macro- Fully-Developed Conditions Summary	
(Subareas)	41
Table 4.2-2(b). Hydrologic Information – Macro- Fully-Developed Conditions Summary	
(Subareas)	42
Table 4.2-3(a). Hydrologic Information – Macro- Fully-Developed Conditions Summary	
(Junctions)	
Un-Detained Hydrology (for Proposed Discovery Park Basin)	
Table 4.2-3(b). Hydrologic Information – Comparison of Results:	
Macro- Fully-Developed vs. Existing Conditions Summary (Junctions) Un-Detained Hydrolog	y44
Table 4.2-4. Allowable Release Rate Evaluation –	44
Macro- Fully-Developed Conditions Summary Model – Without Detention	44
Table 4.2-5. Fully-Developed Conditions Hydrologic Routing Summary	45
Discovery Park Stormwater Detention Facility	45
Table 4.2-6(a). Hydrologic Information – Macro- Fully-Developed Conditions Summary	
(Junctions) Including Proposed Discovery Park Detention Basin	
Table 4.2-6(b). Hydrologic Information – Comparison of Results:	47

A21-04643 iv

Macro- Fully-Developed Conditions vs. Existing Conditions Summary (Junctions) Detained	
Hydrology	47
Table 4.2-7. Allowable Release Rate Evaluation –	48
Fully-Developed Conditions Macro Study (W/Detention)	48
Table 4.3-1. Water Quality Volume Calculations	49
Table 5-1. Macro- Proposed Peak Flowrate Comparison	52
Table 5-2. Macro-Fully Developed- Peak Flowrate Comparison	53
Table 5-3. Macro ARR Comparison	54

A21-04643

1. INTRODUCTION

This Stormwater Drainage Study has been prepared to evaluate the stormwater hydrology of multiple developments (current and future) that are being proposed within the watershed. Once fully developed, the area treated by improvements proposed within this study will include:

- Aria Apartments: a 22.50-ac apartment development (Zoned RP-4)
- Discovery Park Phase 1: a 39.42-ac commercial development (Zoned CP-2, currently being rezoned to PMIX)
- Discovery Park Phase 2: a 19.82-ac commercial development (Zoned PMIX)
- Discovery Park Future: a 116.26-ac planned mixed use development (Zoned PMIX)
- A future Multi-Family Residential development of approximately 14.96-ac along the west side of NW Lee's Summit Road (Zoned RP-4)

The site is located at the northwest corner of NE Douglas Street and NE Colbern Road, in the NE ¼ of Section 30 & SE ¼ of Section 19, Township 48 North, Range 31 West, entirely within the City of Lee's Summit, Jackson County, Missouri.

Stormwater runoff from the project site is tributary to Unity Lake Number One and Unity Lake Number Two. Unity Lake Number One is approximately 1,000 feet downstream of the Discovery Park Future study area. Unity Lake Number Two is approximately 2,500 feet downstream of the Discovery Park Phase 1 and Aria study areas.

This report, intended to serve as the project Macro Stormwater Drainage Study for Aria, Discovery Park Phase 1, and a portion of the Discovery Park Phase 2 Development, has been prepared to evaluate the Existing Conditions stormwater hydrology to establish Allowable Release Rates and to review impacts the proposed development has on the existing hydrology. The Existing Conditions stormwater hydrology will be analyzed for the Discovery Park Future areas to establish Allowable Release Rates similar to the Macro-study area, however, no proposed detention will be analyzed. A future Macro-study for that development area will be required with its Preliminary Development Plan submittal. Refer to Section 7 for hydrologic model input data and simulation results for Existing- and Proposed Conditions. Refer to Section 8 for maps and exhibits depicting the watersheds evaluated in the analyses.

A21-04643



Vicinity Map

1.1. FEMA Floodplain Classification

The FEMA FIRM Panel 29095C-0409G (eff. 20 January, 2017) depict the proposed development areas as "Zone X." This is the FEMA flood insurance rate zone that "corresponds to areas outside the 0.2-percent-annual-chance floodplain, areas within the 0.2-percent-annual-chance floodplain, areas of 1-percent-annual-chance flooding where average depths are less

than 1 foot, areas of 1-percent-annual-chance flooding where the contributing drainage area is less than 1 square mile, and areas protected from the 1-percent-annual-chance flood by levees. No BFE's or base flood depths are shown for this zone." Refer to the attached FEMA Floodplain Map (Exhibit 8-1.1) for depiction of the established floodplains relative to the project site.

The lower reaches of the modeled sub-watershed that is the subject of this report does include a "Zone AE" boundary along the Little Cedar Creek – Tributary No. 2 channel that forms the main branch of the Unity Lake Number 2 impoundment. No construction proposed for these three areas is proposed to affect the boundaries of the defined floodway for this channel.

1.2. Soil Classification

Soil Maps published in the Soil Survey for Jackson County, Missouri categorizes soils in this watershed as:

Table 1.2-1. Soil Classifications

HSG	Map Symbol	Туре	Land-Form
С	10000	Arisburg Silt Loam	1% to 5% Slopes
D	10024	Greenton-Urban Land Complex	5% to 9% Slopes
С	10026	Higginsville Silt Loam	5% to 9% Slopes
С	10082	Arisburg-Urban Land Complex	1% to 5% Slopes
D	10113	Oska Silty Clay Loam	5% to 9% Slopes, E
C/D	10116	Sampsel Silty Clay Loam	2% to 5% Slopes
C/D	10117	Sampsel Silty Clay Loam	5% to 9% Slopes
С	10120	Sharpsburg Silt Loam	2% to 5% Slopes
D	10128	Sharpsburg-Urban Land Complex	2% to 5% Slopes
D	10129	Sharpsburg-Urban Land Complex	5% to 9% Slopes
С	10132	Sibley Silt Loam	2% to 5% Slopes
С	10136	Sibley-Urban Land Complex	2% to 5% Slopes
D	10143	Snead-Urban Land Complex	9% to 30% Slopes
С	10179	Udarents-Urban Land-Oska Complex	5% to 9% Slopes
С	10180	Udarents-Urban Land-Sampsel Complex	2% to 5% Slopes
C/D	30080	Greenton Silty Clay Loam	5% to 9% Slopes
С	30180	Polo Silt Loam	5% to 9% Slopes
С	36083	Kennebec Silt Loam	1% to 4% Slopes, OF
D	40107	Snead-Rock Outcrop Complex, Warm	5% to 14% Slopes
D	40108	Snead-Rock Outcrop Complex, Warm	14% to 30% Slopes
-	99001	Water	-
-	99012	Urban Land, Upland	5% to 9% Slopes

(HSG = Hydrologic Soil Group, E=Eroded, OF=Occasionally Flooded)

A21-04643

NRCS Runoff Curve Numbers (CN's) in this study have been assigned to tributary areas based upon these Hydrologic Soil Groups and associated existing and proposed land use. The majority of land within the modeled sub-watersheds is previously developed, and the CN's are assigned accordingly. Refer to the Soils Map in Section 8 for distribution of soil types throughout the sub-watersheds.

2. METHODOLOGY

The hydrologic analysis provided in this report utilizes methods prescribed by the City of Lee's Summit, Missouri and the Kansas City Metropolitan Chapter of the APWA "Standard Specifications and Design Criteria," Division V, Section 5600 (February 2011) provides the overall framework for stormwater hydrology. The following approved methods were used in this report to model Existing- and Proposed Conditions for stormwater runoff.

- Haestad Methods, Inc. "PondPack" V8i (08.11.01.56).
- NRCS TR-55 Unit Hydrograph Method
- 2-, 10-, and 100-year Return Frequency, 24-hr. Storm Precipitation Depths (TP-40)
- ARC-II Soil Moisture Conditions
- 24-Hour NRCS Type II Rainfall Distribution
- Runoff Curve Numbers per NRCS TR-55 (Tables 2-2a 2-2c) and APWA Sec.5602.3
- NRCS TR-55 Methods for determination of Time of Concentration and Travel Time.

NOTE: Where detailed information pertaining to channel geometry is unavailable, "length & velocity" estimates for channel-flow Travel Time is utilized per Section 5602.7, Kansas City Metropolitan Chapter- APWA Standard Specifications and Design Criteria.

NOTE: PondPack models utilize "Time of Concentration" rather than "Lag Time" for computing subarea hydrology.

Input data for the Existing- and Proposed Conditions hydrology models and results of computations are included in Section 7. Refer to the attached Drainage Area Maps for Existing- and Proposed Conditions subarea locations, weighted Runoff Curve Numbers, and tributary acreage included in Section 8.

Stormwater runoff models were created for the 2-, 10-, and 100-year design storm events. The precipitation depths used in the analyses have been interpolated from the "Technical Paper No. 40 Rainfall Frequency Atlas of the United States" (TP-40; May 1961) isopluvial maps. The following table depicts the rainfall depths used in this analysis:

Table 2-1. Precipitation Depths

•	24-hour Precipitation
Return Period:	24-11001 Frecipitation
rtotum r onod.	Depth (in):
Water Quality Storm ¹	1.37
2-Year (50% Storm)	3.50
10-Year (10% Storm)	5.34
100-Year (1% Storm)	7.71

¹The "Water Quality Storm" is defined in the MARC & APWA "Manual of Best Management Practices for Stormwater Quality" as a 24-hr 1.37" rainfall depth. This particular storm event is utilized for proposed water quality analysis.

Each of the PondPack models constructed for this analysis evaluates multiple rainfall events using these three defined design storms.

The overall hydrology defines 9 modeled sub-watersheds (sub-watersheds "A," "B," "C," "D," "E," "F," "G," "H," "I"), and 30 subareas, encompassing approximately 998 acres overall.

Several offsite subareas are included in the models prepared for this report that will remain unaltered as a result of the proposed development areas. Sub-watersheds "B" and "C" are both offsite regions, as are some portions of sub-watershed "A," "D," "E," "F," "G," "H," "I".

- The Aria site lies within portions of Subareas A3, A4(E), and A5(E).
- The Discovery Park Phase 1 site is located within Subareas A4(E), A4(W), A5(E) and A5(W).
- The Discovery Park Phase 2 site is located within Subareas A6 and D2.
- The Discovery Park Future site is located within Subareas D2, E1, F2, G2, H1 and I1.
- The future Multi-Family Residential development is located within Subarea A1(E).

In accordance with the City-specified criterion and design provision established in the 2011 edition of APWA Section 5600, the proposed stormwater management plan shall "be consistent with the Comprehensive Control Strategy." This requirement establishes the maximum Allowable Release Rates for the 2-year (0.50 cfs/ac), 10-year (2.0 cfs/ac), and 100-year (3.0 cfs/ac) design storms. In addition to the large storm hydrology design constraints, this strategy requires extended detention (≥ 40hr.) of the "Water Quality Storm" runoff volume.

Points of Interest

The hydrologic models prepared for this stormwater Drainage Study includes 30 Points of Interest in total. The 17 critical points of interest to be analyzed are briefly described as:

- **Point A1**, located at the southern inlet to the Unity Lake Number 2 impoundment, the downstream point of interest modeled in this report.
- **Point A2** is the confluence of Channels A and B, located north of an existing sanitary holding basin. All stormwater runoff generated by the Aria and Discovery Park projects is conveyed to this point.
- Point A3 is a culvert in Channel B crossing an access drive for the existing sanitary holding basin.
- **Point A4** is a point within Channel A, upstream of Point A2, Portions of the Aria and Discovery Park projects contribute flow to this point of interest.
- **Point A5** is the downstream end of an existing pond with a breached embankment within Channel A.
- Point A6 is the downstream end of an existing culvert under NW Colbern Road. A
 portion of Discovery Park Phase 2 will contribute flow to this point of interest.

- Point A7 is the downstream end of an existing culvert within Channel A, located at station 25+65 of NE Douglas Street. All stormwater runoff contributed to this point is generated by offsite areas.
- Point B1 is the downstream end of an existing culvert within Channel B, located at station 45+15 of NE Douglas Street. All stormwater runoff contributed to this point is generated by offsite areas.
- Point D1 is located at an eastern inlet to the Unity Lake Number 1 impoundment, the
 downstream point of interest of sub-watershed D. Portions of Discovery Park Phase 1,
 Discovery Park Phase 2 and Discovery Park Future will contribute flow to this point of
 interest.
- Point D2 is the downstream end of an existing culvert under NW Colbern Road. Portions
 of Discovery Park Phase 2 and Discovery Park Future will contribute flow to this point of
 interest. This point is where the majority of offsite stormwater, from areas south of
 Interstate 470, will drain through the future development area.
- Point D4 is the downstream end of an existing culvert under I-470 highway. All stormwater runoff contributed to this point is generated by offsite areas. The culvert represents a choke point for all the offsite area draining to Discovery Park Future from South of I-470.
- Point E1 is the downstream end of an existing culvert under NW Colbern Road. A
 portion of Discovery Park Future will contribute flow to this point of interest.
- **Point F1** is located at a southeastern inlet to the Unity Lake Number 1 impoundment, the downstream point of interest of sub-watershed F. A portion of Discovery Park Future will contribute flow to this point of interest.
- Point F2 is the downstream end of an existing culvert under NW Colbern Road. A
 portion of Discovery Park Future will contribute flow to this point of interest.
- **Point G1** is located at a southwestern inlet to the Unity Lake Number 1 impoundment, the downstream point of interest of sub-watershed G. A portion of Discovery Park Future will contribute flow to this point of interest.
- Point G2 is the downstream end of an existing culvert under NW Colbern Road. A
 portion of Discovery Park Future will contribute flow to this point of interest.
- Point H1 is the downstream end of an existing culvert under N Main Street that discharges directly to Little Cedar Creek. A portion of Discovery Park Future will contribute flow to this point of interest.
- Point I1 is the downstream end of an existing culvert under N Main Street. A small
 portion of Discovery Park Future will contribute flow to this point of interest.

Several additional points are utilized in the models to assist with the hydrologic analysis for offsite areas. The locations of these points are depicted in the attached Drainage Area Maps,

and the results of the analyses are included in tables provided in this narrative, and in the attached modeling output.

In order to provide a direct comparison between the Existing and Proposed Conditions hydrology models, efforts have been made to ensure that the points of interest are consistent between these analyses with the exception of Point A5 as discussed in Section 4 of this report. As noted, additional points to those previously described are included in the hydrologic models, these junctions are of secondary interest to this particular development. Refer to the attached Drainage Area Maps for graphical representation of the modeled subareas and points of interest; refer to Section 7 for schematic view of the PondPack watershed model and connectivity between subareas, channel reaches, and points of interest.

3. EXISTING CONDITIONS ANALYSIS

The purpose of this report is to provide the Macro Stormwater Drainage analysis to ensure that the proposed site development is compliant with City of Lee's Summit, Missouri requirements. This section of the report will provide the Existing Conditions analysis, representing the current site hydrology. The results of this analysis will be used to establish the "Allowable Release Rates" for the project and will be compared to those of Proposed Conditions in order to determine the hydrologic effects of the development upon the receiving stormwater conveyances and sub-watersheds.

Runoff Curve Numbers have been developed based upon the current land use obtained from survey data, aerial photographs, and site visits. Refer to Section 7 for Existing Conditions weighted NRCS Runoff Curve Number (CN) and Time of Concentration (Tc) calculations. Table 3-1 contains the hydrologic parameters used to characterize subareas the Existing Conditions PondPack model. A graphical representation of the areas is provided on exhibit EX-300 in Section 8.

Table 3-1(a). Existing Conditions Input Data

				Discovery	Macro-		
		Aria	Discovery	Park	Study		
	Total	Onsite	Park Phase 1	Phase 2	Onsite	NRCS	
	Area	Area	Onsite Area	Onsite	Area	Weighted	Tc ¹
	(ac):	(ac):	(ac):	Area (ac):	(ac):	CN:	(hr):
Subarea A1(e):	27.97				12.36	77	0.1736
Subarea A1(w):	43.14					76	0.2511
Subarea A2(e):	3.08					80	0.0875
Subarea A2(w):	23.41					73	0.2133
Subarea A3:	24.42	11.62				80	0.1284
Subarea A4(e):	9.85	5.99	3.35			81	0.1367
Subarea A4(w):	17.41		9.19			73	0.1656
Subarea A5(e):	15.16	4.88	8.00			80	0.1195
Subarea A5(w):	19.77		18.66			76	0.1578
Subarea A6:	13.45			9.21		80	0.1063
Subarea A7:	30.60					76	0.1596
Subarea A8:	21.56					81	0.1299
Subarea A9:	31.84					84	0.1420
Subarea A10:	12.23					94	0.1545
Subtotal:	293.88	22.50	39.20	9.21	12.36		
Subarea B1:	31.94					79	0.1385
Subarea B2:	48.54					78	0.1987
Subarea B3:	40.69					83	0.1447
Subarea B4-DET:	25.05					94	0.1155

				Discovery	Macro-		
		Aria	Discovery	Park	Study		
	Total	Onsite	Park Phase 1	Phase 2	Onsite	NRCS	
	Area	Area	Onsite Area	Onsite	Area	Weighted	Tc1
	(ac):	(ac):	(ac):	Area (ac):	(ac):	CN:	(hr):
Subarea B4-BYP:	7.42					94	0.0787
Subtotal:	153.64						
Subarea C1:	45.21					90	0.2860
Subarea C2:	57.13					81	0.3308
Subarea C3:	52.36					83	0.1199
Subtotal:	154.70						
Subarea D1:	36.91		0.22			77	0.1275
Subarea D2:	47.00			10.62	24.74	78	0.1755
Subarea D3:	16.84					88	0.1561
Subarea D4:	112.38					88	0.1792
Subarea D5:	53.24					89	0.2652
Subtotal:	266.37		0.22	10.62	24.74		
Subarea E1:	22.59				20.68	80	0.1062
Subarea E2:	6.56					73	0.1021
Subtotal:	29.15				20.68		
Subarea F1:	7.85					77	0.0938
Subarea F2:	12.76				12.06	81	0.1260
Subtotal:	20.60				12.06		
Subarea G1:	14.04					81	0.1055
Subarea G2:	7.93				7.11	85	0.1175
Subtotal:	21.96				7.11		
Subarea H1:	56.17				51.06	78	0.1348
Subtotal:	56.17				51.06		
Subarea I1:	1.40				0.61	86	0.1019
Subtotal:	1.40				0.61		
Total:	997.89	22.50	39.42	19.83	128.62		

¹ **Note:** Per TR-55 documentation, minimum T_C is 0.10 hours; model is configured with default value of 0.10 hr. minimum Tc.

A21-04643

Table 3-1(b). Existing Conditions Input Sub-Watershed Data

. , ,			Discovery	Discovery	
		Aria	Park Phase 1	Park Phase 2	Macro-Study
	Total Area	Onsite	Onsite Area	Onsite Area	Onsite Area
	(ac):	Area (ac):	(ac):	(ac):	(ac):
Sub-W'Shed A Subtotal:	293.88	22.50	39.20	9.21	12.36
Sub-W'Shed B Subtotal:	153.64				
Sub-W'Shed C Subtotal:	154.70				
Sub-W'Shed D Subtotal:	266.37		0.22	10.62	24.74
Sub-W'Shed E Subtotal:	29.15				20.68
Sub-W'Shed F Subtotal:	20.60				12.06
Sub-W'Shed G Subtotal:	21.96				7.11
Sub-W'Shed H Subtotal:	56.17				51.06
Sub-W'Shed I Subtotal:	1.40				0.61
Modeled Total:	997.89	22.50	39.42	19.83	128.62

These tributary areas, Runoff Curve Numbers (CN), and Times of Concentration (T_C) for the corresponding subareas were used as input to the Existing Conditions PondPack model to evaluate the stormwater hydrology. The subareas representing Existing Conditions for the development and associated sub-watersheds are utilized in the PondPack model to compute the stormwater runoff for the three design storms. The resultant peak discharge rate (Q_P), peak time (T_P), and runoff volume (V_R) for the computed hydrographs of modeled subareas are included in Table 3-2.

Table 3-2. Hydrologic Information – Existing Conditions Summary (Subareas)

(cfs) Subarea A-1(e): 53.9	1 12.01	(ac-ft): 3.334 4.908	(cfs): 110.32	(hr.): 11.99	(ac-ft):	(cfs):	(hr.):	(ac-ft):
` '			110.32	11.99	6 783	407.00		
Cultana A 4/	5 12.05	4 908			0.703	187.82	11.99	11.675
Subarea A-1(w): 70.1		4.300	146.86	12.05	10.132	252.55	12.05	17.597
Subarea A-2(e): 7.64	11.94	0.420	14.90	11.93	0.819	24.63	11.93	1.374
Subarea A-2(w): 34.5	12.03	2.301	76.77	12.03	4.975	136.28	12.03	8.884
Subarea A-3: 57.6	1 11.96	3.330	112.58	11.95	6.495	186.13	11.95	10.895
Subarea A-4(e): 23.9	7 11.96	1.402	45.97	11.96	2.698	75.15	11.96	4.488
Subarea A-4(w): 27.5	12.01	1.712	60.85	11.99	3.700	108.22	11.99	6.607
Subarea A-5(e): 36.4	11.95	2.067	70.90	11.95	4.031	116.98	11.95	6.762
Subarea A-5(w): 37.0	2 12.00	2.249	77.10	11.99	4.643	132.61	11.97	8.064
Subarea A-6: 37.9	3 11.93	2.083	70.54	11.93	3.904	113.19	11.93	6.389
Subarea A-7: 57.2	12.00	3.482	119.03	11.98	7.186	204.90	11.98	12.481
Subarea A-8: 53.0	5 11.96	3.070	101.89	11.95	5.907	166.82	11.95	9.826
Subarea A-9: 87.1	5 11.97	5.138	158.95	11.96	9.507	252.78	11.96	15.435
Subarea A-10: 45.6	1 11.97	2.890	72.57	11.97	4.733	106.86	11.97	7.128

	Q _{P-2}	T _{P-2}	V _{R-2}	Q _{P-10}	T _{P-10}	V _{R-10}	Q _{P-100}	T _{P-100}	V _{R-100}
	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):
Subarea B-1:	70.94	11.97	4.168	140.29	11.96	8.242	234.20	11.95	13.944
Subarea B-2:	94.72	12.03	6.057	190.16	12.01	12.146	320.74	12.00	20.725
Subarea B-3:	106.50	11.97	6.302	197.62	11.96	11.812	317.37	11.96	19.332
Subarea B-4 (BYP):	30.29	11.93	1.753	48.22	11.92	2.871	71.04	11.92	4.324
Subarea B-4 (DET):	99.43	11.94	5.919	158.21	11.94	9.694	232.94	11.94	14.599
Subarea C-1:	124.83	12.05	9.223	209.38	12.05	15.842	317.10	12.05	24.565
Subarea C-2:	104.44	12.09	8.134	200.90	12.08	15.652	329.78	12.08	26.038
Subarea C-3:	142.61	11.95	8.110	264.83	11.94	15.199	425.51	11.94	24.875
Subarea D-1:	75.69	11.97	4.400	155.84	11.95	8.95	265.94	11.95	15.407
Subarea D-2:	99.28	12.00	6.134	195.91	12.00	12.128	326.27	11.98	20.518
Subarea D-3:	52.46	11.97	3.185	90.29	11.97	5.605	138.69	11.97	8.822
Subarea D-4:	338.74	11.99	21.246	582.43	11.99	37.391	894.20	11.99	58.857
Subarea D-5:	146.13	12.05	10.458	247.91	12.05	18.183	377.88	12.03	28.406
Subarea E-1:	55.42	11.94	3.080	107.96	11.94	6.008	178.18	11.93	10.078
Subarea E-2:	11.34	11.94	0.645	25.34	11.94	1.394	45.12	11.94	2.489
Subarea F-1:	16.88	11.94	0.935	34.70	11.93	1.903	59.21	11.93	3.275
Subarea F-2:	31.60	11.96	1.816	60.52	11.95	3.495	99.00	11.95	5.814
Subarea G-1:	36.14	11.94	1.999	69.23	11.93	3.846	113.41	11.93	6.398
Subarea G-2:	23.49	11.94	1.332	42.32	11.94	2.433	66.71	11.94	3.92
Subarea H-1:	119.73	11.97	7.009	240.97	11.96	14.056	406.72	11.95	23.984
Subarea I-1:	4.44	11.93	0.244	7.87	11.93	0.441	12.29	11.93	0.705

The PondPack models created for these analyses include 24 channel reaches modeled using the Muskingum Method. Various modeled points of interest are connected in the model by these channel reaches. The reach segments account for the time-lagging effect on the hydrograph peaks, including a relatively insignificant amount of peak flow rate attenuation as the flood wave travels downstream. Travel time for each reach is based upon the reach length and average bed-slope. The following table contains the input data for the channel reaches used in the Existing- and Proposed Conditions PondPack models.

January 2023

Table 3-3. Muskingum Channel Reach Routing Information

Table 9 9: Mask			No. of Sub-	K (ea. sub-
Reach I.D.	K (hr.):	X (coeff.):	reaches	reach) (hr.):
Route A2~A1:	0.0826	0.25	9	0.0092
Route A4~A2:	0.0288	0.25	3	0.0097
Route A5~A4:	0.0203	0.25	3	0.0067
Route A3~A2:	0.0192	0.25	2	0.0097
Route A6~A5:	0.0378	0.25	4	0.0094
Route A7~A5:	0.0412	0.25	5	0.0083
Route A8~A7:	0.0340	0.25	4	0.0086
Route A9~A7:	0.0390	0.25	4	0.0097
Route A10~A9:	0.0636	0.25	7	0.0092
Route B1~A3:	0.0331	0.25	4	0.0083
Route B2~B1:	0.0162	0.25	2	0.0081
Route B3~B2:	0.0824	0.25	9	0.0092
Route B4~B3:	0.0587	0.25	6	0.0097
Route C1~B1:	0.0210	0.25	3	0.0069
Route C2~C1:	0.0701	0.25	8	0.0089
Route C3~C2:	0.0148	0.25	2	0.0075
Route D2~D1:	0.0428	0.25	8	0.0053
Route D3~D2:	0.0758	0.25	6	0.0126
Route D4~D2:	0.0598	0.25	6	0.0100
Route D5~D4:	0.0475	0.25	5	0.0095
Route E1~D1:	0.0339	0.25	6	0.0056
Route E2~E1:	0.0336	0.25	3	0.0112
Route F2~F1:	0.0192	0.25	3	0.0064
Route G2~G1:	0.0244	0.25	3	0.0081

The preceding stormwater conveyances have been incorporated into both the Existing and Proposed Conditions PondPack models. The results of the Existing Conditions hydrologic routing are provided in Table 3.2-1, in Section 3.2, which provides the summary data for the points of interest defined in this Stormwater Drainage Study. Refer to the Existing Conditions Drainage Area Map for the location of the points of interest, modeled subareas, channels, and conveyances, in relation to proposed development area.

The defined subareas and stormwater conveyances, with associated hydrograph attenuation effects have been incorporated into the Existing (and Proposed) Conditions PondPack models. There are also several offsite storage areas included in the Existing- and Proposed Conditions models for the project site. The following section of this report provides the geometric configuration and hydrologic routing summary for existing locations. The results of the Existing Conditions hydrologic routing at the designated Points of Interest are provided in the Section 3.2.

3.1. Existing Stormwater Storage Areas & Detention Facilities

The following information is provided to define the geometry of the outfall structure and storage capacity for the existing modeled storage areas and stormwater detention basins included in the Existing Conditions hydrology models. The routing summary tables provided for each location contain the Existing Conditions hydrologic routing summary for each of the design storm events considered in this analysis.

Point A3 – Culverts at Pump Station Drive Culverts:

An access drive extends across the channel that runs along the northern edge of the Aria project site. This restricted-access drive leads to the pump station that is positioned at the confluence of two channels that define the upper regions of the modeled sub-watershed. The Existing- and Proposed Conditions geometry of the culverts positioned across the existing access drive to the pump station are defined as follows:

Primary Outlet Structure:

Dual 84" Diameter (modeled equivalent circular: 72" x 96" CMPA Culvert); Length \approx 66.6 L.F. Flowline In / Out \approx 900.81 / 900.43 (ft; NAVD)

Secondary Outlet Structure:

Roadway (Weir)-

Station (ft):	0	22	43.1	76.73	124.4	157.13	223.83	251	265.18	270.32	277.43
Elevation (ft):	912	910	908.52	907.24	907.44	908.16	908.35	908.6	909	910	912

Culvert flow at the threshold of overtopping/weir-flow is approximately 255 cfs.

The potential storage area upstream from this roadway crossing is defined in the following table based upon storage area for a given elevation. As depicted below, the potential storage area is somewhat modest, relative to the existing conditions flows that are contributed to this location.

Table 3.1-1(a). Existing Storage Volume – Pump Station Drive Storage Area

Elevation Storage Are		Incremental	Cumulative
(ft; NAVD):	(sq. ft.):	Volume (ft^3):	Volume (ac-ft):
900.81	106	0	0.000
901	114	21	0.000
902	691	362	0.009
902.4	908	319	0.016
903	1,252	645	0.031
904	3,270	2,182	0.081
906	7,400	10,393	0.320
908	38,290	41,682	1.276
910	58,812	96,371	3.489
912	84,827	142,847	6.768

Note: The conic method is used to compute the incremental volume between pond contours.

The sum of the computed incremental volumes provides the cumulative pond volume for a given elevation.

Utilizing these geometric parameters, the following table depicts the stormwater routing summary for this location.

Table 3.1-1(b). Existing Conditions Storage Area Routing – Point A3 – Pump Station Drive Culverts

	Peak Q In	T _P In	Peak Q Out	T _P Out	V _R	Peak WSEL	Max. Storage
	(cfs):	(hr.):	(cfs):	(hr.):	(ac-ft):	(ft; NAVD):	Volume (ac-ft):
WQv:	102.98	12.15	101.73	12.18	9.704	904.61	0.134
2-Year:	632.94	12.13	628.64	12.15	52.997	908.50	1.747
10-Year:	1,109.82	12.13	1,107.67	12.15	97.952	909.07	2.341
100-Year:	1,597.03	12.16	1,595.56	12.17	159.297	909.50	2.849

The preceding routing summary indicates that the culverts are somewhat under-sized for most large-storm events, though the Water Quality Volume storm event is readily conveyed by this system.

Point A5 – Former Pond:

The Existing Conditions geometry of the outfall structure for the former pond site that is located just north of the Discovery Park Phase 1 property is based upon field survey and LIDAR topographic data. This former pond-site has an embankment breach, and therefore provides relatively minimal attenuation for larger precipitation events. The feature does, however affect the hydrograph timing somewhat, and is therefore included in these models. The pond is proposed to be removed with the Discovery Park Phase 1 development. The following information provides the outfall geometry and storage area for the Existing Conditions PondPack model:

January 2023

Primary Outlet Structure- Weir Cut through Embankment:

Station (ft):	0	23.88	64.85	167.91	238.1	246.58	251.38	253.1	257.52	263.49	268.12	273.3	297.08	333.5
Elevation (ft):	940	938	936	934	932	930	929	929	930	932	934	936	938	940

The potential storage area upstream from this pond embankment is defined in the following table based upon a stage versus storage area for a given elevation.

Table 3.1-2(a). Existing Storage Volume – Boone Creek Embankment

Storage Area	Incremental	Cumulative
(sq. ft.):	Volume (ft^3):	Volume (ac-ft):
20,212	0	0.000
34,209	26,905	0.618
75,878	107,357	3.082
98,561	173,945	7.075
130,004	227,841	12.306
171,091	300,156	19.197
226,998	396,774	28.305
	Storage Area (sq. ft.): 20,212 34,209 75,878 98,561 130,004 171,091	Storage Area (sq. ft.): Incremental Volume (ft^3): 20,212 0 34,209 26,905 75,878 107,357 98,561 173,945 130,004 227,841 171,091 300,156

Note: The conic method is used to compute the incremental volume between pond contours.

The sum of the computed incremental volumes provides the cumulative pond volume for a given elevation.

The following table depicts the stormwater routing summary for this location under each of the modeled precipitation events.

Table 3.1-2(b): Existing Conditions Storage Area Routing – Point A5 – Former Pond

	Peak Q In	T _P In	Peak Q Out	T _P Out	V _R	Peak WSEL	Max. Storage
	(cfs):	(hr.):	(cfs):	(hr.):	(ac-ft):	(ft; NAVD):	Volume (ac-ft):
WQv:	47.52	12.08	22.44	12.24	3.428	930.22	0.800
2-Year:	315.36	12.05	242.32	12.15	20.98	932.48	3.940
10-Year:	552.78	12.05	489.66	12.12	39.91	933.43	5.828
100-Year:	847.10	12.05	799.19	12.10	66.087	934.15	7.413

Data provided in the preceding table indicates that, while larger storm events are not significantly affected by this feature, the more frequent events do exhibit some hydrograph attenuation at this location.

Point B1 - Lee's Summit Road RCB Culverts (Sta. 45+15):

Lee's Summit Road has a pair of RCB Culverts that convey stormwater across the roadway into the channel that runs along the northern edge of the Aria project site. This RCB includes stormwater flows generated by defined sub-watersheds "B" and "C." The following information provides the outfall geometry and storage area for this location in both Existing- and Proposed Conditions PondPack models:

Primary Outlet Structure:

Dual 10'-w x 7'-ht RCB Culvert; Length \approx 174.4 L.F. Flowline In / Out \approx 916.22 / 911.54 (ft; NAVD)

Secondary Outlet Structure:

Roadway (Weir)-

Station (ft):	0	64.20	155.0	244.3	309.0
Elevation (ft):	930	929	928.68	929	930

Culvert flow at the threshold of overtopping/weir-flow is approximately 1,800 cfs.

Table 3.1-3(a). Existing Storage Volume – Pump Station Drive Storage Area

Elevation	Storage Area	Incremental	Cumulative
(ft; NAVD):	(sq. ft.):	Volume (ft^3):	Volume (ac-ft):
916.22	377	0	0
917	2,013	848	0.019
918	8,841	5,024	0.135
919	14,303	11,463	0.398
920	18,052	16,141	0.769
921	21,576	19,788	1.223
922	25,405	23,464	1.761
923	29,240	27,300	2.388
924	39,203	34,100	3.171
925	50,630	44,795	4.199
926	60,928	55,700	5.478
927	71,454	66,121	6.996
928	83,880	77,584	8.777
929	139,252	110,403	11.312
930	178,519	158,480	14.950

Note: The conic method is used to compute the incremental volume between pond contours.

The sum of the computed incremental volumes provides the cumulative pond volume for a given elevation.

January 2023

The following table depicts the stormwater routing summary for this location under each of the modeled precipitation events.

Table 3.1-3(b). Existing Conditions Storage Area Routing –
Point B1 – Lee's Summit Drive Culverts (Sta. 45+15)

	Peak Q In	T _P In	Peak Q Out	T _P Out	V _R	Peak WSEL	Max. Storage
	(cfs):	(hr.):	(cfs):	(hr.):	(ac-ft):	(ft; NAVD):	Volume (ac-ft):
WQv:	101.70	12.11	100.64	12.12	9.245	917.82	0.101
2-Year:	634.00	12.07	615.14	12.11	49.667	921.57	1.519
10-Year:	1,121.63	12.07	1,076.61	12.11	91.457	923.99	3.164
100-Year:	1,726.54	12.06	1,551.65	12.14	148.401	926.77	6.626

Data provided in the preceding table indicates that each of the modeled events are effectively conveyed by the culverts, and sufficient freeboard appears to be available for the 100-year design storm.

Point A7 – NE Douglas Street RCB Culvert (Sta. 25+65):

NE Douglas Street has another RCB Culvert that conveys stormwater across the roadway into the channel that runs into the eastern edge of the Discovery Park project site. This culvert conveys stormwater into the project area from upper portions of the defined sub-watershed "A." The following information provides the outfall geometry and storage area for this location in both Existing- and Proposed Conditions PondPack models:

Primary Outlet Structure:

13'-w x 7'-ht RCB Culvert; Length ≈ 174.4 L.F. Flowline In / Out ≈ 945.3 / 937.5 (ft; NAVD)

Secondary Outlet Structure:

Roadway (Weir)-

Station	_	16 E	110 2	206.1	276.0	245.4	202.4
(ft):	0	46.5	118.2	206.1	276.8	345.4	392.4
Elevation	059	957	956	955.65	956	957	958
(ft):	958	957	936	900.00	956	957	906

Culvert flow at the threshold of overtopping/weir-flow is approximately 1,213 cfs.

Table 3.1-4(a): Existing Storage Volume –
Point A7 – Lee's Summit Road RCB Culvert (Sta. 25+65)

Elevation	Storage Area	Incremental	Cumulative
(ft; NAVD):	(sq. ft.):	Volume (ft^3):	Volume (ac-ft):
945.3	273	0	0.000
946	728	338	0.008
947	3,022	1,744	0.048
948	6,247	4,538	0.152
949	19,586	12,298	0.434
950	36,075	27,414	1.064
951	52,213	43,896	2.071
952	62,652	57,353	3.388
953	78,881	70,611	5.009
954	93,052	85,869	6.980
955	109,368	101,100	9.301
956	141,847	125,256	12.177
957	178,341	159,746	15.844
958	220,369	198,985	20.412
		I	

Note: The conic method is used to compute the incremental volume between pond contours.

The sum of the computed incremental volumes provides the cumulative pond volume for a given elevation.

The following table depicts the stormwater routing summary for this location under each of the modeled precipitation events.

Table 3.1-4(b): Existing Conditions Storage Area Routing –
Point A7 – Lee's Summit Drive Culverts (Sta.25+65)

	Peak Q In	T _P In	Peak Q Out	T _P Out	V _R	Peak WSEL	Max. Storage
	(cfs):	(hr.):	(cfs):	(hr.):	(ac-ft):	(ft; NAVD):	Volume (ac-ft):
WQv:	38.00	12.06	37.95	12.06	2.539	946.33	0.015
2-Year:	236.01	12.02	229.26	12.05	14.58	948.71	0.319
10-Year:	437.94	12.01	397.23	12.07	27.333	950.22	1.251
100-Year:	707.16	12.00	603.32	12.08	44.871	951.80	3.100

Data provided in the preceding table indicates that each of the modeled events is effectively conveyed by this existing culvert, and sufficient freeboard appears to be available for each design storm.

Sub-Basin B4- Stormwater Detention Facility:

The upper reaches of the sub-watershed "B" region includes a relatively large, impervious property that includes an onsite wet-basin stormwater detention facility. The following information provides the modeled outfall geometry and storage area for the Existing- and Proposed Conditions PondPack models:

January 2023

Primary Outlet Structure:

Inlet Box: 4.2 S.F. Opening; Crest Elev. ≈ 992.0 36" Dia. RCP Discharge Culvert: Length = 280 L.F.

Flowline In / Out ≈ 981 / 976 (ft; NAVD)

Table 3.1-5(a): Existing Storage Volume –
Proposed Sub-Basin B4 Detention Facility

Elevation	Storage Area	Incremental	Cumulative	
(ft; NAVD):	(sq. ft.):	Volume (ft^3):	Volume (ac-ft):	
992	75,323	0	0.000	
994	88,777	163,916	3.763	
996	101,439	190,076	8.127	
998	114,890	216,190	13.090	

Note: The conic method is used to compute the incremental volume between pond contours.

The following table depicts the stormwater routing summary for this location under each of the modeled precipitation events.

Table 3.1-5(b). Existing Conditions Storage Area Routing – Sub-Basin B4 Detention Facility

	Peak Q In	T _P In	Peak Q Out	T _P Out	V _R	Peak WSEL	Max. Storage
	(cfs):	(hr.):	(cfs):	(hr.):	(ac-ft):	(ft; NAVD):	Volume (ac-ft):
WQv:	30.27	11.95	8.05	12.15	1.713	992.37	0.642
2-Year:	99.43	11.94	22.46	12.16	5.919	993.25	2.284
10-Year:	158.21	11.94	28.68	12.19	9.694	994.04	3.850
100-Year:	232.94	11.94	34.97	12.24	14.599	995.03	5.948

The preceding routing summary indicates that the existing wet-basin detention facility provides significant attenuation for the modeled events.

Point C2 - Storage Area~Inlet C2:

The Existing- and Proposed Conditions models include a relatively significant storage unit in the defined sub-watershed "C" area. Geometric parameters for this storage area are based upon LIDAR topography and GIS base data. The following information provides the modeled outfall geometry and storage area for the Existing- and Proposed Conditions PondPack models:

Primary Outlet Structure:

Grate Inlet; Crest Elev. ≈ 956.85

Opening Area: 27.2 S.F.

66" Dia. RCP Discharge Culvert: Length = 177 L.F.

Flowline In / Out ≈ 945.7 / 945.1 (ft; NAVD)

The sum of the computed incremental volumes provides the cumulative pond volume for a given elevation.

Table 3.1-6(a). Existing Storage Volume – Storage Area C2

Elevation	Storage Area	Incremental	Cumulative
(ft; NAVD):	(sq. ft.):	Volume (ft^3):	Volume (ac-ft):
956.85	777	0	0
958	10,771	5,536	0.127
960	29,311	38,567	1.012
962	63,479	90,617	3.093
964	98,380	160,590	6.779
966	135,252	232,656	12.120
968	175,712	310,083	19.239
970	245,445	419,220	28.863
972	310,449	554,622	41.595

Note: The conic method is used to compute the incremental volume between pond contours.

The following table depicts the stormwater routing summary for this location under each of the modeled precipitation events.

Table 3.1-6(b). Existing Conditions Storage Area Routing – Storage Area C2

,	Peak Q In	T _P In	Peak Q Out	T _P Out	V _R	Peak WSEL	Max. Storage
	(cfs):	(hr.):	(cfs):	(hr.):	(ac-ft):	(ft; NAVD):	Volume (ac-ft):
WQv:	21.38	12.02	21.36	12.02	1.338	956.90	0.001
2-Year:	142.28	11.96	137.26	12.00	8.110	957.95	0.115
10-Year:	264.20	11.96	219.81	12.05	15.199	959.67	0.804
100-Year:	423.95	11.96	285.13	12.07	24.875	961.59	2.539

The preceding routing summary indicates that, while the more frequent events are minimally affected by this feature, the larger events do undergo some attenuation.

Point D4 – I-470 Highway Culvert:

I-470 Highway has an RCB Culvert that conveys stormwater across the highway into the Discovery Park Future project site. This culvert conveys stormwater into the project area from upper portions of the defined sub-watershed "D." The following information provides the outfall geometry and storage area for this location in the Existing-Conditions PondPack model:

Primary Outlet Structure:

5'-w x 8'-ht RCB Culvert; Length ≈ 323 L.F.

Flowline In / Out ≈ 952.00 / 948.00 (ft; NAVD)

The sum of the computed incremental volumes provides the cumulative pond volume for a given elevation.

Table 3.1-4(a): Existing Storage Volume – Point D4 – I-470 Highway Culvert

Elevation (ft; NAVD):	Storage Area (sq. ft.):	Incremental Volume (ft^3):	Cumulative Volume (ac-ft):
956	14,459	0	0
958	38,781	51,280	1.177
960	77,382	113,963	3.793
962	119,729	195,577	8.283
964	164,668	283,206	14.785
966	324,776	480,468	25.815

Note: The conic method is used to compute the incremental volume between pond contours.

The sum of the computed incremental volumes provides the cumulative pond volume for a given elevation.

The following table depicts the stormwater routing summary for this location under each of the modeled precipitation events.

Table 3.1-4(b): Existing Conditions Storage Area Routing –
Point D4 – I-470 Highway Culvert

	Peak Q In	T _P In	Peak Q Out	T _P Out	V _R	Peak WSEL	Max. Storage
	(cfs):	(hr.):	(cfs):	(hr.):	(ac-ft):	(ft; NAVD):	Volume (ac-ft):
WQv:	98.35	12.04	95.20	12.07	6.953	954.62	0.188
2-Year:	447.33	12.02	377.63	12.10	31.704	958.57	2.269
10-Year:	761.81	12.02	526.54	12.14	55.574	960.91	6.129
100-Year:	1157.85	12.02	638.44	12.19	87.262	963.49	13.467

Data provided in the preceding table indicates that each of the modeled events is effectively conveyed by this existing culvert, and sufficient freeboard below I-470 Highway appears to be available for each design storm.

The previously defined modeled stormwater conveyances and the associated hydrograph attenuation effects from the existing storage areas have been incorporated into both Existing-and Proposed Conditions PondPack models. Each of these storage areas is offsite from the proposed development areas contemplated by this Macro Stormwater Drainage Study. The results of the Existing Conditions hydrologic routing are provided in the following section. Additional minor storage and conveyance systems are included in the PondPack model to further expand and represent existing conditions for the watersheds. These systems are available within the model output provided in Section 8, for review.

3.2. Existing Conditions Hydrologic Modeling Results

The stormwater storage areas and resultant hydrograph attenuation effects are incorporated into the Existing Conditions PondPack models. The results of this hydrologic routing of the hydrographs generated by the modeled subareas through the sub-watersheds are provided in the following summary tables. This information is provided at the defined Points of Interest.

Refer to the Existing Conditions Drainage Area Map for the location of the points in relation to the proposed development areas, modeled subareas, channels, and conveyances.

Table 3.2-1. Hydrologic Information – Existing Conditions Summary (Junctions)

Table 3.2-1. H	Q _{P-2}	T _{P-2}	V _{R-2}	Q _{P-10}	T _{P-10}	V _{R-10}	Q _{P-100}	T _{P-100}	V _{R-100}
	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):
Point A1:	948.96	12.25	88.053	1,784.23	12.22	166.969	2,754.84	12.19	276.008
	909.05	12.17	79.810	1,691.73	12.15	150.055	2,566.59	12.13	246.736
	628.64	12.15	52.997	1,107.67	12.15	97.952	1,595.56	12.17	159.297
	260.92	12.15	24.092	539.49	12.11	46.309	906.56	12.09	77.182
	242.32	12.15	20.979	489.66	12.12	39.911	799.19	12.10	66.087
	37.98	11.93	2.083	70.54	11.93	3.904	113.19	11.93	6.389
	229.26	12.05	14.580	397.23	12.07	27.333	603.32	12.08	44.871
	53.05	11.96	3.070	101.89	11.95	5.907	166.82	11.95	9.826
Point A9:	128.79	12.00	8.028	223.48	11.99	14.240	346.07	11.99	22.563
Point A10:	45.61	11.97	2.890	72.57	11.97	4.733	106.86	11.97	7.128
Point B1:	615.14	12.11	49.667	1,076.61	12.11	91.457	1,551.65	12.14	148.401
Point B2:	242.31	12.05	20.032	446.43	12.04	36.522	715.56	12.03	58.980
Point B3:	153.04	11.99	13.975	266.04	11.98	24.377	411.65	11.97	38.255
Point B4:	48.10	11.94	7.673	71.04	11.93	12.565	98.80	11.93	18.924
Point C1:	350.42	12.09	25.466	604.01	12.10	46.692	890.10	12.10	75.478
Point C2:	232.89	12.04	16.244	417.32	12.07	30.851	614.91	12.08	50.912
Point C3:	142.61	11.95	8.110	264.83	11.94	15.199	425.51	11.94	24.875
Point D1:	560.43	12.08	49.147	941.67	12.07	89.659	1,351.30	12.05	144.576
Point D2:	485.06	12.10	41.022	752.83	12.06	73.431	1,052.38	12.06	117.417
Point D3:	52.46	11.97	3.185	90.29	11.97	5.605	138.69	11.97	8.822
Point D4:	377.63	12.10	31.704	526.54	12.14	55.574	638.44	12.19	87.262
Point D5:	142.73	12.07	10.458	239.98	12.08	18.183	357.61	12.09	28.406
Point E1:	65.98	11.95	3.725	106.88	11.99	7.278	143.00	11.98	11.753
Point E2:	11.34	11.94	0.645	25.34	11.94	1.394	45.12	11.94	2.489
Point F1:	47.57	11.97	2.752	74.89	11.96	5.398	106.16	11.94	9.090
Point F2:	31.56	11.96	1.816	45.26	12.06	3.495	65.86	12.07	5.814
Point G1:	50.00	11.95	3.331	102.21	11.94	6.279	163.43	11.97	10.317
Doint CO.	58.32	11.95	3.331						
Point G2:	23.29	11.96	1.332	36.98	12.02	2.433	62.01	11.99	3.920
						2.433	62.01	11.99	3.920 23.984

The information obtained in this Existing Conditions analysis is utilized to establish the "Allowable Release Rates" (ARR) for the project areas based upon percentages of onsite and offsite area draining to the points of interest. A summary of the computation of these ARR's is provided in the following section.

3.3. Allowable Release Rate Calculations

The purpose of this Stormwater Drainage Study for the proposed development is to ensure compliance with the current specifications and design criteria in effect for the City of Lee's Summit, Missouri. The Proposed Conditions and Macro hydrologic analyses are provided in Section 4. Results of that analysis will be compared to the Section 3, Existing Conditions results. The variation in quantity and rate of stormwater discharge between these two models represents the hydrologic effect generated by development of the project site. The Actual-versus Allowable Release Rates for the fully developed, Proposed Conditions will be evaluated in Section 4 for the Macro-Study analysis in order to demonstrate compliance with the design objectives for this project.

The following tables are provided to compute the "Allowable Release Rate" (ARR) for the three design storm events in order to demonstrate compliance with the stated design objectives. The Proposed Conditions Macro- Models utilize five defined points of discharge that receive stormwater runoff from the project site. The proposed Stormwater Management Plan for the proposed development areas will evaluate the ARR's at each of these modeled outlet locations.

Allowable Release Rate Calculations:

This section of the Stormwater Drainage Study for the proposed development is provided to establish the project Allowable Release Rates. The ARR is based upon the "Comprehensive Control" strategy provided in the Section 5600 of the APWA "Standard Specifications and Design Criteria" (Feb, 2011). This strategy provides the maximum ARR for the 2-, 10-, and 100-Year Design Storms at 0.50, 2.0, and 3.0 cfs-per-acre, respectively. Additional requirements include Extended Detention of the "Water Quality" design storm (defined as a 1.37" precipitation event).

The following table is provided in order to establish the project ARR for the Discovery Park Macro Stormwater Drainage analysis. The ARR for each of the three modeled events is based upon the sum of the "Allowable Bypass" for offsite flows and the onsite "Allowable Release Rate." In order to prevent skewing the results, the ARR is based upon the Existing Conditions model. This ensures that the allowable bypass flows are not increased by onsite development, and that any diversions of tributary regions that takes place upon development is not incorporated into the allowable rates.

January 2023

Information presented in the following table depicts the cumulative onsite and offsite areas for each of the Points, and the Existing Conditions peak discharge rates at these locations. From that information, the ARR is established in the second column from the right. The right-hand column depicts the relative difference in peak discharge rate that the proposed stormwater management plan would meet to achieve compliance with these targeted ARR's.

The Macro Study section of this report will provide a comparison of these Allowable Release Rates to the computed peak discharge rates at these Points of Interest to demonstrate compliance with the stated design objectives.

Table 3.3-1. Existing Conditions Allowable Release Rate Calculations

Table 3.3-1. Ex	Existing		Onsite	Onsite		Allowable		
	Conditions				Allowable	Onsite	Prop.	Difference
Retur	n Peak Flow	Total	(Offsite)	(Offsite)	Bypass	Discharge	Cond.	in Flow
Event		Area	Area	Area	Flows	Rate:	ARR	Rate:
Location: (Yr):	(cfs):	(ac):	(ac):	(%):	(cfs):	(cfs):	(cfs):	(cfs):
Point A1		604.82	85.87	14%				
2-Year					814.24	42.93	857.17	-91.79
10-Year	ŕ		(518.96)	(86%)	1530.93	171.73	1702.66	-81.57
100-Year	: 2,754.84				2363.74	257.60	2621.34	-133.50
Point A2		531.11	70.91	13%				
2-Year	909.05				787.68	35.46	823.14	-85.91
10-Year	: 1,691.73		(460.20)	(87%)	1465.86	141.82	1607.68	-84.05
100-Year	: 2,566.59				2223.92	212.73	2436.65	-129.94
Point A3		332.76	11.62	3%				
2-Year	: 628.64				606.69	5.81	612.50	-16.14
10-Year	: 1,107.67		(321.14)	(97%)	1068.99	23.24	1092.23	-15.44
100-Year	: 1,595.56				1539.85	34.86	1574.71	-20.85
Point A4		171.86	59.29	34%				
2-Year	260.92				170.90	29.65	200.55	-60.37
10-Year	: 539.49		(112.57)	(66%)	353.37	118.58	471.95	-67.54
100-Year	906.56				593.80	177.87	771.67	-134.89
Point A5		144.60	40.76	28%				
2-Year	: 242.32				174.02	20.38	194.40	-47.92
10-Year	: 489.66		(103.85)	(72%)	351.65	81.51	433.16	-56.50
100-Year	799.19				573.94	122.27	696.21	-102.98
Point A6		13.45	9.21	68%				
2-Year	: 37.98				11.97	4.61	16.57	-21.41
10-Year	: 70.54		(4.24)	(32%)	22.23	18.42	40.65	-29.89
100-Year	: 113.19				35.67	27.63	63.30	-49.89
Point A7		96.23	0.00	0%				
2-Year	229.26				229.26	0.00	229.26	0.00

	Existing		Onsite	Onsite		Allowable		
	Conditions				Allowable	Onsite	Prop.	Difference
Return	Peak Flow	Total	(Offsite)	(Offsite)	Bypass	Discharge	Cond.	in Flow
Event	Rate	Area	Area	Area	Flows	Rate:	ARR	Rate:
Location: (Yr):	(cfs):	(ac):	(ac):	(%):	(cfs):	(cfs):	(cfs):	(cfs):
10-Year:	397.23		(96.23)	(100%)	397.23	0.00	397.23	0.00
100-Year:	603.32				603.32	0.00	603.32	0.00
Point B1		308.34	0.00	0%				
2-Year:	615.14				615.14	0.00	615.14	0.00
10-Year:	1,076.61		(308.34)	(100%)	1076.61	0.00	1076.61	0.00
100-Year:	1,551.65				1551.65	0.00	1551.65	0.00
Point D1		295.52	56.26	19%				
2-Year:	560.43				453.75	28.13	481.87	-78.56
10-Year:	941.67		(239.26)	(81%)	762.41	112.51	874.92	-66.75
100-Year:	1351.30				1094.07	168.77	1262.83	-88.47
Point D2		229.46	35.36	15%				
2-Year:	485.06				410.31	17.68	427.99	-57.07
10-Year:	752.83		(194.10)	(85%)	636.82	70.72	707.54	-45.29
100-Year:	1052.38				890.21	106.08	996.29	-56.09
Point E1		29.15	20.68	71%				
2-Year:	65.98				19.17	10.34	29.51	-36.47
10-Year:	106.88		(8.47)	(29%)	31.06	41.36	72.41	-34.47
100-Year:	143.00				41.55	62.03	103.59	-39.41
Point F1		20.60	12.06	59%				
2-Year:	47.57				19.72	6.03	25.75	-21.82
10-Year:	74.89		(8.54)	(41%)	31.05	24.12	55.17	-19.72
100-Year:	106.16				44.02	36.18	80.20	-25.96
Point F2		12.76	12.06	95%				
2-Year:	31.56				1.72	6.03	7.75	-23.81
10-Year:	45.26		(0.70)	(5%)	2.47	24.12	26.59	-18.67
100-Year:	65.86				3.59	36.18	39.78	-26.08
Point G1		21.96	7.11	32%				
2-Year:	58.32				39.43	3.56	42.99	-15.33
10-Year:	102.21		(14.85)	(68%)	69.10	14.23	83.33	-18.88
100-Year:	163.43				110.49	21.34	131.84	-31.59
Point G2		7.93	7.11	90%				
2-Year:	23.29				2.39	3.56	5.94	-17.35
10-Year:	36.98		(0.82)	(10%)	3.79	14.23	18.02	-18.96
100-Year:	62.01				6.35	21.34	27.70	-34.31
Point H1		56.17	51.06	91%				
2-Year:	119.54				10.88	25.53	36.41	-83.13
10-Year:	240.90		(5.11)	(9%)	21.93	102.12	124.05	-116.85
			(5.11)	(9%)				

		Existing		Onsite	Onsite		Allowable		
		Conditions				Allowable	Onsite	Prop.	Difference
	Return	Peak Flow	Total	(Offsite)	(Offsite)	Bypass	Discharge	Cond.	in Flow
	Event	Rate	Area	Area	Area	Flows	Rate:	ARR	Rate:
Location:	(Yr):	(cfs):	(ac):	(ac):	(%):	(cfs):	(cfs):	(cfs):	(cfs):
10	0-Year:	406.43				37.00	153.18	190.18	-216.25
Point I1			1.40	0.61	44%				
	2-Year:	4.44				2.49	0.31	2.80	-1.64
1	0-Year:	7.87		(0.78)	(56%)	4.42	1.23	5.64	-2.23
10	0-Year:	12.29				6.90	1.84	8.74	-3.55

The greatest required relative reduction in peak discharge rate occurs at the Point A2 location. This is the anticipated location for the greatest required impact, as that point is located at the confluence of the two channels that convey stormwater runoff from the three subareas (Sub's A3, A4(E), & A5(E)) that include portions of the proposed Discovery Park development site.

When the northern Multi-Family Residential, Aria, Discovery Park Phase 2 and Discovery Park Future areas are to be developed it will need to be ensured that these allowable release rates are met. Detention basins will need to be provided to attenuate the peak flows generated from development, as needed. Those detention basins will be discussed in the future Macro-Studies to be prepared when each area is developed. Subareas D through I were analyzed to provide allowable release rates only for future development. These subareas will not be included in the proposed Macro analysis in this report.

4. MACRO ANALYSIS

This section of the Stormwater Drainage Study for the proposed development is provided to evaluate the Proposed Conditions hydrology for the project. As in the Existing Conditions analysis, the overall modeled stormwater drainage area for the Macro Study encompasses approximately 602 acres, including 74 acres within the proposed development site. Due to a diversion of approximately 0.20 acres from adjacent tributary areas, the overall drainage area is slightly increased to approximately 602.42 acres in the Macro Study. The following sub-section will provide the Proposed Conditions analysis for the Macro- analysis. As previously stated, this section will analyze and review the final macro conditions for subareas A, B, and C which includes the Aria, Discovery Park Phase 1, Discovery Park Phase 2, and the Multi-Family Residential developments. Subareas D through I are part of future Discovery Park developments, which will be further reviewed and analyzed with future Macro stormwater studies as those layouts and designs are further refined and Preliminary Development Plans are submitted for city review and approval.

The purpose of this report is to provide the Macro Stormwater Drainage analysis to ensure that the proposed site development is compliant with City of Lee's Summit requirements. This section of the report will provide the Proposed Conditions analysis, representing the fully developed hydrology for the site. The results of this analysis will be compared to those of Existing Conditions in order to determine the hydrologic effects of the development upon the receiving stormwater conveyances and sub-watersheds. Compliance with the project ARR's will also be evaluated through comparison of the Actual- versus Allowable Release Rates at the five defined Points of Interest.

4.1. Macro Stormwater Model: Proposed Conditions Analysis

This section of the Stormwater Drainage Study for the Discovery Park Phase 1 commercial development is provided to evaluate the Macro-Study Proposed Conditions hydrology for the project. The proposed development totals 74.06-acres including 39.42-acres of commercial development (office buildings, hotels, restaurants, multifamily residential buildings, associated drives, parking, utilities) and mass grading of the Aria and Discovery Park Phase 2 sites totaling 34.64-acres. As previously discussed, the existing pond located at point A5 is being removed with the proposed development, however all other existing flow-attenuating structures and features will remain unchanged.

Proposed Conditions Runoff Curve Numbers have been developed based upon the current Development Plan for this commercial project. Refer to Section 7 for Macro-Study Proposed Conditions weighted NRCS Runoff Curve Number (CN) and Time of Concentration (Tc) calculations.

The tributary areas, Runoff Curve Numbers (CN), and Times of Concentration (T_C) for the corresponding subareas that are provided in Table 4.1-1 are used as input into the Proposed Conditions PondPack model to evaluate the stormwater hydrology. Subareas included in the Proposed Conditions for the Discovery Park property are utilized in the PondPack model to compute the stormwater runoff for the three design storms. The resultant peak discharge rate (Q_P), peak time (T_P), and runoff volume (V_R) for the computed hydrographs of modeled subareas are included in Table 4.1-2(a). Areas that are unchanged from the Existing Conditions analysis are presented as *grey print* in the following tables.

Table 4.1-1(a). Macro-Study Proposed Conditions Input Data

1 abie 4.1-1(a). Ma			Discovery	Discovery	Macro-		
		Aria	Park	Park	Study		
	Total	Onsite	Phase 1	Phase 2	Onsite	NRCS	
	Area	Area	Onsite	Onsite	Area	Weighted	
	(ac):	(ac):	Area (ac):	Area (ac):	(ac):	CN:	Tc1 (hr):
Subarea A1(e):	27.97				12.36	77	0.1736
Subarea A1(w):	43.14					76	0.2511
Subarea A2(e):	3.08					80	0.0875
Subarea A2(w):	23.41					73	0.2133
Subarea A3:	24.06	11.07			11.07	82	0.0714
Subarea A4(e):	1.48	0.14	0.84		0.98	88	0.0184
Subarea A4(w):	8.75		0.59		0.59	72	0.1095
Subarea A5(e):	19.12	11.29	6.92		18.20	86	0.0769
Subarea A5(w):	33.42		31.08		31.08	95	0.0647
Subarea A6:	13.42			9.88	9.88	83	0.0842
Subarea A7:	30.60					76	0.1596
Subarea A8:	21.56					81	0.1299
Subarea A9:	31.84					84	0.1420
Subarea A10:	12.23					94	0.1545
Subtotal:	294.08	22.50	39.42	9.88	84.15		
Subarea B1:	31.94					79	0.1385
Subarea B2:	48.54					78	0.1987
Subarea B3:	40.69					83	0.1447
Subarea B4-DET:	25.05					94	0.1155
Subarea B4-BYP:	7.42					94	0.0787
Subtotal:	153.64						
Subarea C1:	45.21					90	0.2860
Subarea C2:	57.13					81	0.3308
Subarea C3:	52.36					83	0.1199
Subtotal:	154.70						
Total:	602.42	22.50	39.42	9.88			

¹ **Note:** Per TR-55 documentation, minimum T_c is 0.10 hours; model is configured with default value of 0.10 hr. minimum T_c

Table 4.1-1(b). Macro-Study Proposed Conditions Input Sub-Watershed Data

			Discovery	Discovery	
			Park	Park	Macro-
		Aria	Phase 1	Phase 2	Study
	Total Area	Onsite	Onsite	Onsite	Onsite
	(ac):	Area (ac):	Area (ac):	Area (ac):	Area (ac):
Sub-W'Shed A Subtotal:	294.08	22.50	39.42	9.88	84.15
Sub-W'Shed B Subtotal:	153.64				
Sub-W'Shed C Subtotal:	154.70				
Modeled Total:	602.42	22.50	39.42	9.88	84.15

These tributary areas, Runoff Curve Numbers (CN), and Times of Concentration (T_C) for the corresponding subareas were used as input to the Proposed Conditions PondPack model to evaluate the stormwater hydrology for this Macro-Study. The subareas representing Existing-(offsite) and Proposed Conditions (onsite) for the Discovery Park site are utilized in the PondPack model to compute the stormwater runoff for the three design storms. The resultant peak discharge rate (Q_P), peak time (T_P), and runoff volume (V_R) for the computed hydrographs of modeled subareas are included in Table 4.1-2.

Table 4.1-2(a). Hydrologic Information – Macro-Study Proposed Conditions Summary (Subareas)

Location:	Q _{P-2}	T _{P-2}	V_{R-2}	Q _{P-10}	T _{P-10}	V _{R-10}	Q _{P-100}	T _{P-100}	V _{R-100}
	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):
Subarea A-1(e):	53.91	12.01	3.334	110.32	11.99	6.783	187.82	11.99	11.675
Subarea A-1(w):	70.15	12.05	4.908	146.86	12.05	10.132	252.55	12.05	17.597
Subarea A-2(e):	7.64	11.94	0.420	14.90	11.93	0.819	24.63	11.93	1.374
Subarea A-2(w):	34.59	12.03	2.301	76.77	12.03	4.975	136.28	12.03	8.884
Subarea A-3:	65.13	11.93	3.574	122.96	11.93	6.787	199.22	11.93	11.198
Subarea A-4(e):	5.05	11.93	0.279	8.68	11.93	0.491	13.33	11.93	0.773
Subarea A-4(w):	14.08	11.96	0.817	32.12	11.94	1.796	58.07	11.94	3.239
Subarea A-5(e):	60.82	11.93	3.344	107.76	11.93	6.033	168.25	11.93	9.642
Subarea A-5(w):	139.52	11.92	8.184	219.80	11.92	13.246	322.03	11.92	19.806
Subarea A-6:	37.88	11.93	2.077	70.35	11.93	3.893	112.88	11.93	6.372
Subarea A-7:	57.26	12.00	3.482	119.03	11.98	7.186	204.90	11.98	12.481
Subarea A-8:	53.05	11.96	3.070	101.89	11.95	5.907	166.82	11.95	9.826
Subarea A-9:	87.15	11.97	5.138	158.95	11.96	9.507	252.78	11.96	15.435
Subarea A-10:	45.61	11.97	2.890	72.57	11.97	4.733	106.86	11.97	7.128
Subarea B-1:	70.94	11.97	4.168	140.29	11.96	8.242	234.20	11.95	13.944
Subarea B-2:	94.72	12.03	6.057	190.16	12.01	12.146	320.74	12.00	20.725
Subarea B-3:	106.50	11.97	6.302	197.62	11.96	11.812	317.37	11.96	19.332
Subarea B-4 (BYP):	30.29	11.93	1.753	48.22	11.92	2.871	71.04	11.92	4.324

January 2023

Project No. A21-04643

Location:	Q _{P-2}	T _{P-2}	V_{R-2}	Q _{P-10}	T _{P-10}	V _{R-10}	Q _{P-100}	T _{P-100}	V _{R-100}
	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):
Subarea B-4 (DET):	99.43	11.94	5.919	158.21	11.94	9.694	232.94	11.94	14.599
Subarea C-1:	124.83	12.05	9.223	209.38	12.05	15.842	317.10	12.05	24.565
Subarea C-2:	104.44	12.09	8.134	200.90	12.08	15.652	329.78	12.08	26.038
Subarea C-3:	142.61	11.95	8.110	264.83	11.94	15.199	425.51	11.94	24.875

The hydrologic impact resulting from the Macro-Study Proposed Conditions results is partially revealed by the comparison of the preceding subarea data to those established in Section 3 (Existing Conditions) of this report. The hydrologic conditions for offsite subareas remain unchanged between Existing- and Proposed Conditions analyses. However, the onsite subareas do exhibit changes in impervious cover and diversion of tributary area under Proposed Conditions. The hydrologic impact to the overall sub-watershed of these modified areas will become apparent in the summary tables for the Points of Interest.

The variation in quantity and rate of stormwater discharge between these two models represents the hydrologic effect generated by the proposed development project for given subareas. The following table depicts the difference in computed subarea hydrology between the Existing- and Proposed Conditions models.

Table 4.1-2(b). Hydrologic Information – Macro-Study Proposed vs. Existing Conditions Summary (Subareas)

Location:	Q _{P-2}	T _{P-2}	V _{R-2}	Q _{P-10}	T _{P-10}	V _{R-10}	Q _{P-100}	T _{P-100}	V _{R-100}
	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):
Subarea A-1(e):	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Subarea A-1(w):	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Subarea A-2(e):	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Subarea A-2(w):	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Subarea A-3:	7.52	-0.03	0.244	10.38	-0.02	0.292	13.09	-0.02	0.303
Subarea A-4(e):	-18.92	-0.03	-1.123	-37.29	-0.03	-2.207	-61.82	-0.03	-3.715
Subarea A-4(w):	-13.48	-0.05	-0.895	-28.73	-0.05	-1.904	-50.15	-0.05	-3.368
Subarea A-5(e):	24.42	-0.02	1.277	36.86	-0.02	2.002	51.27	-0.02	2.88
Subarea A-5(w):	102.50	-0.08	5.935	142.70	-0.07	8.603	189.42	-0.05	11.742
Subarea A-6:	-0.10	n/c	-0.006	-0.19	n/c	-0.011	-0.31	n/c	-0.017
Subarea A-7:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Subarea A-8:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Subarea A-9:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Subarea A-10:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Subarea B-1:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Subarea B-2:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Subarea B-3:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c

Location:	Q _{P-2}	T _{P-2}	V _{R-2}	Q _{P-10}	T _{P-10}	V _{R-10}	Q _{P-100}	T _{P-100}	V _{R-100}
Location.	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):
Subarea B-4 (BYP):	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Subarea B-4 (DET):	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Subarea C-1:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Subarea C-2:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Subarea C-3:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c

The sign-convention used in the preceding table is: Proposed Conditions minus Existing Conditions. Therefore, negative values indicate a reduction in computed value, whereas positive values reflect an increase. Those locations that do not exhibit any change in computed values are identified by "n/c."

The previously defined stormwater detention basins, outfall structures, and resultant hydrograph attenuation effects have been incorporated into the Proposed Conditions PondPack model. The channel reaches defined in the Existing Conditions analysis are also included in this routing. Results of this Proposed Conditions hydrologic routing are provided in the following summary table. This information is provided at the same "Points of Interest" used in the Existing Conditions hydrologic analysis for this Stormwater Drainage Study. Refer to the Proposed Conditions Drainage Area Map for the location of the points of interest in relation to the development site, modeled subareas, channels and conveyances. As in the preceding tables, locations that are unchanged from the Existing Conditions analysis are presented as grey print in the following tables.

Table 4.1-3(a). Hydrologic Information–Macro-Study Proposed Conditions Summary (Junctions)

Un-Detained Hydrology (for Proposed Discovery Park Basin)

Location:	Q _{P-2}	T _{P-2}	V _{R-2}	Q _{P-10}	T _{P-10}	V _{R-10}	Q _{P-100}	T _{P-100}	V _{R-100}
Location.	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):
Point A1:	1,036.29	12.19	91.367	1,891.07	12.16	171.623	2,890.34	12.14	281.712
Point A2:	979.74	12.11	83.974	1,759.80	12.09	155.560	2.641.51	12.08	253.290
Point A3:	625.11	12.16	52.191	1,100.39	12.15	97.194	1,586.54	12.08	158.549
Point A4:	414.66	12.03	29.282	697.74	12.03	52.792	1,047.68	12.03	84.703
Point A6:	37.88	11.94	2.077	70.35	11.93	3.893	112.88	11.93	6.372
Point A7:	229.26	12.05	14.580	397.23	12.07	27.333	603.32	12.08	44.871
Point A8:	53.05	11.96	3.070	101.89	11.95	5.907	166.82	11.95	9.826
Point A9:	128.79	12.00	8.028	223.48	11.99	14.240	346.07	11.99	22.563
Point A10:	45.61	11.97	2.890	72.57	11.97	4.733	106.86	11.97	7.128
Point B1:	615.14	12.11	49.667	1,076.61	12.11	91.457	1,551.65	12.14	148.401
Point B2:	242.31	12.05	20.032	446.43	12.04	36.522	715.56	12.03	58.980
Point B3:	153.04	11.99	13.975	266.04	11.98	24.377	411.65	11.97	38.255
Point B4:	48.10	11.94	7.673	71.04	11.93	12.565	98.80	11.93	18.924
Point C1:	350.42	12.09	25.466	604.01	12.10	46.692	890.10	12.10	75.478

Project No. A21-04643

Location:	Q _{P-2}	T _{P-2}	V _{R-2}	Q _{P-10}	T _{P-10}	V _{R-10}	Q _{P-100}	T _{P-100}	V _{R-100}
Location.	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):
Point C2:	232.89	12.04	16.244	417.32	12.07	30.851	614.91	12.08	50.912
Point C3:	142.61	11.95	8.110	264.83	11.94	15.199	425.51	11.94	24.875

As previously evaluated for the modeled Subareas, these Proposed Conditions results for the Points of Interest will be compared to those established in Section 3 (Existing Conditions) of this report. The points represent similar locations in both Existing- and Proposed Conditions analyses. Therefore, the variation in quantity and rate of stormwater discharge between these two models represents the hydrologic effect generated by the proposed development. The following table depicts the difference between the Existing- and Proposed Conditions models.

Table 4.1-3(b). Hydrologic Information – Comparison of Results:

Macro- Proposed vs. Existing Conditions Summary (Junctions) Un-Detained Hydrology

Location:	Q _{P-2}	T _{P-2}	V_{R-2}	Q _{P-10}	T _{P-10}	V_{R-10}	Q _{P-100}	T _{P-100}	V_{R-100}
Location.	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):
Point A1:	84.85	-0.06	3.32	102.45	-0.06	4.660	130.62	-0.05	5.706
Point A2:	68.10	-0.06	4.173	62.88	-0.06	5.511	66.98	-0.04	6.556
Point A3:	-5.18	0.01	-0.821	-10.28	n/c	-0.777	-12.83	-0.09	-0.796
Point A4:	152.42	-0.13	5.214	156.66	-0.09	6.518	140.21	-0.06	7.572
Point A6:	0.88	-0.03	-0.813	0.78	n/c	0.011	1.10	n/c	0.018
Point A7:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point A8:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point A9:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point A10:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point B1:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point B2:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point B3:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point B4:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point C1:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point C2:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point C3:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c

The sign-convention used in the preceding table is: Proposed Conditions minus Existing Conditions. Therefore, negative values indicate a reduction in computed value, whereas positive values reflect an increase. Those locations that do not exhibit any change in computed values are identified by "n/c."

Information presented in the preceding table exhibits an increase in peak rates at most points, relative to the existing conditions model. This is the result of reduced times of concentration and increased impervious areas that occur with Discovery Park development. In addition, overall runoff volumes exhibit modest increase.

The following table is provided to examine the difference between the computed peak discharge rates and the established ARR's for the Discovery Park Macro-Study.

Table 4.1-4. Allowable Release Rate Evaluation – Proposed Conditions Macro Model – Without Detention

l ropossa sona.		Model – Without Computed Peak	Dotonilo	-
		Discharge Rate	ARR	Difference
Location:	Event:	(cfs):	(cfs):	(cfs):
Point A1	2-Year:	1,036.29	927.14	109.15
	10-Year:	1,891.07	1,766.79	124.28
	100-Year:	2,890.34	2,724.11	166.23
Point A2	2-Year:	979.74	884.27	95.57
	10-Year:	1,759.80	1,670.03	89.77
	100-Year:	2,641.51	2,532.96	108.55
Point A3	2-Year:	625.11	613.94	11.17
	10-Year:	1,100.39	1,094.99	5.40
	100-Year:	1,586.54	1,578.20	8.34
Point A4	2-Year:	414.66	251.18	163.48
	10-Year:	697.74	528.69	169.05
	100-Year:	1,047.68	882.87	164.81
Point A6	2-Year:	37.88	16.57	21.31
	10-Year:	70.35	40.65	29.70
	100-Year:	112.88	63.30	49.58

The sign-convention utilized for the information presented in the preceding table is based upon "Computed Rate minus ARR." Therefore, positive values indicate an exceedance of the Allowable Release Rate, whereas negative values would indicate a peak rate that is lower than the ARR, thereby meeting the targeted peak discharge rates. The difference in the rates depicted in this table are all in exceedance of the targeted rates, therefore stormwater detention is required for the project.

Proposed Discovery Park Stormwater Detention Facility:

Based upon the Proposed Conditions analysis, it is apparent that some form of stormwater detention will be required for this project. A wet detention basin will be constructed in the northwest corner of Discovery Park Phase 1 that will serve both Discovery Park and Aria. The basin is proposed to be constructed to meet both detention and water quality treatment requirements. The areas A-4 and A-5 are proposed to discharge into the basin, with flows from

Project No. A21-04643

January 2023

area A-7 (East of Douglas Street), discharging into the basin through a proposed culvert directing flows into the basin.

Following is the Proposed Conditions geometry for basin and the outlet structure:

Basin Parameters:

Bottom of the basin = 920.00

Permanent water surface elevation = 929.00

Top of berm = 941.00

Primary Outlet Structure:

One (1) V-Notch weir

Flowline Elevation = 929.00 (ft; NAVD)

Weir Angle = 142 deg

Weir Top Elevation = 929.85 (ft, NAVD)

Weir Top Width = 4.89 ft

Four (4) 9.5'(W) x 6.5" (H) Openings on all 4 sides

Flowline Elevation = 929.85 (ft; NAVD)

Opening Top Elevation = 930.39 (ft; NAVD)

Open Top Outlet Structure

10.5'x10.5' Inside Outlet Structure

Open Top Elevation = 932.20 (ft; NAVD)

Secondary Outlet Structure:

Emergency Spillway (Weir) 83' L x 5.2' H with 3:1 side slopes;

Crest Elev. = 935.80

The proposed basin's storage area is provided in the following table. This proposed storage area is designed as the final configuration for the facility; it is intended to provide the necessary detention for the three separate development areas.

Table 4.1-5(a). Proposed Conditions Storage Volume – Discovery Park Stormwater Detention Facility

				Cumulative
Elevation	Storage Area	Incremental	Cumulative	Volume (Dry)
(ft; NAVD):	(sq. ft.):	Volume (ft^3):	Volume (ac-ft):	(ac-ft):
920	71,701.00	0.00	0.00	0.00
921	76,302.00	90,126.14	1.70	0.00
922	80,950.00	95,000.96	3.50	0.00
923	85,668.00	99,932.74	5.42	0.00
924	90,457.00	104,921.50	7.44	0.00
925	95,315.00	109,967.24	9.57	0.00
926	100,244.00	115,070.46	11.81	0.00
927	105,242.00	120,230.67	14.17	0.00

				Cumulative
Elevation	Storage Area	Incremental	Cumulative	Volume (Dry)
(ft; NAVD):	(sq. ft.):	Volume (ft^3):	Volume (ac-ft):	(ac-ft):
928	116,285.00	123,814.20	16.71	0.00
929	133,892.00	125,777.22	19.58	0.00
930	152,261.00	129,403.93	22.87	3.28
931	157,856.00	134,738.11	26.42	6.84
932	163,500.00	140,129.26	30.11	10.53
933	173,448.00	145,578.41	33.98	14.40
934	179,278.00	151,086.04	38.03	18.45
935	185,163.00	156,652.17	42.21	22.63
936	191,103.00	162,276.79	46.53	26.95
937	197,098.00	167,960.40	50.99	31.40
938	203,149.00	175,628.90	55.58	36.00
939	209,700.00	193,255.92	60.32	40.74
940	215,924.00	209,373.56	65.20	45.62

Note: The conic method is used to compute the incremental volume between pond contours.

The sum of the computed incremental volumes provides the cumulative pond volume for a given elevation.

Utilizing these geometric parameters in the Proposed Conditions model, the following table depicts the stormwater routing summary for this location.

Table 4.1-5(b). Macro-Study Proposed Conditions Hydrologic Routing Summary–Discovery Park Stormwater Detention Facility

	Peak Q In	T _P In	Peak Q Out	T _P Out	V _R	Peak WSEL	Max. Storage
	(cfs):	(hr.):	(cfs):	(hr.):	(ac-ft):	(ft; NAVD):	Volume (ac-ft):
2-Year:	415.53	12.01	160.08	12.22	29.282	931.92	10.247
10-Year:	699.01	12.02	395.22	12.22	52.792	933.49	16.364
100-Year:	1,049.30	12.01	728.04	12.15	84.703	934.66	21.196

The preceding routing summary indicates that the detention aspect of this facility provides substantial attenuation of the all storm events.

The proposed stormwater detention facility is included in the PondPack modeling for the following table output. These Macro-Study Proposed Conditions results will be compared to the Existing Conditions in the following table. Areas that are unchanged from the Existing Conditions analysis are presented as *grey print* in the following tables.

Table 4.1-6(a). Hydrologic Information – Macro- Proposed Conditions Summary

(Junctions) Including Proposed Discovery Park Detention Basin

Location:	Q _{P-2}	T _{P-2}	V _{R-2}	Q _{P-10}	T _{P-10}	V _{R-10}	Q _{P-100}	T _{P-100}	V _{R-100}
Location.	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):
Point A1:	840.82	12.25	91.367	1,593.89	12.25	171.623	2,524.85	12.24	281.712
Point A2:	799.40	12.17	83.974	1,513.84	12.18	155.560	2,381.07	12.18	253.290
Point A3:	625.11	12.16	52.191	1,100.39	12.15	97.194	1,586.54	12.17	158.549
Point A4:	160.04	12.24	29.282	394.92	12.22	52.792	727.66	12.17	84.703
Point A6:	37.88	11.93	2.077	70.35	11.93	3.893	112.88	11.93	6.372
Point A7:	229.26	12.05	14.580	397.23	12.07	27.333	603.32	12.08	44.871
Point A8:	53.05	11.96	3.070	101.89	11.95	5.907	166.82	11.95	9.826
Point A9:	128.79	12.00	8.028	223.48	11.99	14.240	346.07	11.99	22.563
Point A10:	45.61	11.97	2.890	72.57	11.97	4.733	106.86	11.97	7.128
Point B1:	615.14	12.11	49.667	1,076.61	12.11	91.457	1,551.65	12.14	148.401
Point B2:	242.31	12.05	20.032	446.43	12.04	36.522	715.56	12.03	58.980
Point B3:	153.04	11.99	13.975	266.04	11.98	24.377	411.65	11.97	38.255
Point B4:	48.10	11.94	7.673	71.04	11.93	12.565	98.80	11.93	18.924
Point C1:	350.42	12.09	25.466	604.01	12.10	46.692	890.10	12.10	75.478
Point C2:	232.89	12.04	16.244	417.32	12.07	30.851	614.91	12.08	50.912
Point C3:	142.61	11.95	8.110	264.83	11.94	15.199	425.51	11.94	24.875

The following table provides a comparison between the Macro-Study Proposed Conditions (with detention) and the Existing Conditions modeled results. As indicated by the grey font, the lowest six modeled points within the sub-watershed are the only locations that exhibit hydrologic impacts.

Table 4.1-6(b). Hydrologic Information – Comparison of Results: Macro- Proposed vs. Existing Conditions Summary (Junctions) Detained Hydrology

Location:	Q _{P-2}	T _{P-2}	V _{R-2}	Q _{P-10}	T _{P-10}	V _{R-10}	Q _{P-100}	T _{P-100}	V _{R-100}
Location.	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):
Point A1:	-108.14	0.00	3.314	-190.34	0.03	4.654	-229.99	0.05	5.704
Point A2:	-109.65	0.00	4.164	-177.89	0.03	5.505	-185.52	0.05	6.554
Point A3:	-3.53	0.01	-0.806	-7.28	0.00	-0.758	-9.02	0.00	-0.748
Point A4:	-100.88	0.09	5.190	-144.57	0.11	6.483	-178.90	80.0	7.521
Point A6:	-0.10	0.00	-0.006	-0.19	0.00	-0.011	-0.31	0.00	-0.017
Point A7:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point A8:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point A9:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point A10:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point B1:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point B2:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c

37 A21-04643

Location:	Q _{P-2}	T _{P-2}	V _{R-2}	Q _{P-10}	T _{P-10}	V _{R-10}	Q _{P-100}	T _{P-100}	V _{R-100}
Location.	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):
Point B3:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point B4:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point C1:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point C2:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point C3:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c

The sign-convention used in the preceding table is: Proposed Conditions minus Existing Conditions. Therefore, negative values indicate a reduction in computed value, whereas positive values reflect an increase. Those locations that do not exhibit any change in computed values are identified by "n/c."

Information presented in the preceding table exhibits a reduction in peak rates, relative to the existing conditions model. Overall runoff volumes exhibit modest increase.

The following table is provided to examine the difference between the computed peak discharge rates and the established ARR's for the Discovery Park Macro-Study.

Table 4.1-7. Allowable Release Rate Evaluation – Proposed Conditions Macro Study (With Detention)

		Computed Peak		
		Discharge Rate	ARR	Difference
Location:	Event:	(cfs):	(cfs):	(cfs):
Point A1	2-Year:	840.82	859.38	-18.56
	10-Year:	1593.89	1704.07	-110.18
	100-Year:	2524.85	2623.74	-98.89
Point A2	2-Year:	799.40	823.14	-23.74
	10-Year:	1513.84	1607.68	-93.84
	100-Year:	2381.07	2436.65	-55.58
Point A3	2-Year:	625.11	612.50	12.61
	10-Year:	1100.39	1092.23	8.16
	100-Year:	1586.54	1574.71	11.83
Point A4	2-Year:	160.04	200.55	-40.51
	10-Year:	394.92	471.95	-77.03
	100-Year:	727.66	771.67	-44.01
Point A6	2-Year:	37.88	16.57	21.31
	10-Year:	70.35	40.65	29.70
	100-Year:	112.88	63.30	49.58

Note: The sign-convention utilized for the information presented in the preceding table is based upon "Computed Rate minus ARR." Positive values indicate an exceedance of the ARR; negative values indicate that the peak rate is lower than the ARR.

The difference in the rates depicted in this table are generally in compliance with the targeted rates; the proposed stormwater management facility provides adequate attenuation for the primary Channel "A" tributary. The information provided in the preceding table does demonstrate that there are a few exceptions: Peak rates at Point A3 and A6. Point A3 is the terminal end of the Channel "B" tributary, immediately upstream from confluence at Point A2, while point A6 flows directly into the proposed basin.

Although the ARR is exceeded at the Point A3 location, the Proposed Conditions analysis does exhibit that areas further downstream are below ARR at all storm events. ARR is also exceeded at Point A6 during all storm events, however this point is located upstream of the proposed detention basin and is routed through the basin for attenuation.

4.2. Macro Stormwater Model: Fully-Developed Conditions Analysis

This section of the Stormwater Drainage Study for the Discovery Park commercial development is provided to evaluate the Fully-Developed Proposed Conditions hydrology for the Unity Lake #2 tributary. Proposed conditions include the fully-developed condition of Aria, Discovery Park, and the Multi-Family Residential developments.

Fully-Developed Conditions Runoff Curve Numbers have been developed based upon the current Aria and Discovery Park Phase 1 Development Plans and for the future Multi-Family Residential development and a portion of the Discovery Park Phase 2 development. Refer to Section 7 for Macro-Study Fully-Developed Conditions weighted NRCS Runoff Curve Number (CN) and Time of Concentration (Tc) calculations. These values, summarized in Table 4.2-1(a) are used as input into the Fully-Developed Conditions PondPack model to evaluate the Macro-Study Fully Developed Conditions stormwater runoff for the three design storms. The resultant peak discharge rate (Q_P), peak time (T_P), and runoff volume (V_R) for the computed hydrographs of modeled subareas are included in Tale 4.2-2(a). Areas that are unchanged from the Existing Conditions analysis are presented as *grey print* in the following tables.

Table 4.2-1(a). Macro-Study Fully-Developed Conditions Input Data

		_	Discovery	Discovery	Macro-		
		Aria	Park	Park	Study		
	Total	Onsite	Phase 1	Phase 2	Onsite	NRCS	
	Area	Area	Onsite	Onsite	Area	Weighted	
	(ac):	(ac):	Area (ac):	Area (ac):	(ac):	CN:	Tc 1 (hr):
Subarea A1(e):	30.57				14.96	85	0.1401
Subarea A1(w):	43.14					76	0.2511
Subarea A2(e):	3.08					80	0.0875
Subarea A2(w):	23.41					73	0.2133
Subarea A3:	24.06	11.07			11.07	87	0.0717

			Discovery	Discovery	Macro-		
		Aria	Park	Park	Study		
	Total	Onsite	Phase 1	Phase 2	Onsite	NRCS	
	Area	Area	Onsite	Onsite	Area	Weighted	
	(ac):	(ac):	Area (ac):	Area (ac):	(ac):	CN:	Tc 1 (hr):
Subarea A4(e):	1.48	0.14	0.84		0.98	89	0.0184
Subarea A4(w):	8.75		0.59		0.59	72	0.1095
Subarea A5(e):	19.12	11.29	6.92		18.20	92	0.0615
Subarea A5(w):	33.42		31.08		31.08	95	0.0647
Subarea A6:	13.42			9.88	9.88	94	0.0842
Subarea A7:	30.60					76	0.1596
Subarea A8:	21.56					81	0.1299
Subarea A9:	31.84					84	0.1420
Subarea A10:	12.23					94	0.1545
Subtotal:	296.68	22.50	39.43	9.88	86.76		
Subarea B1:	31.94					79	0.1385
Subarea B2:	48.54					78	0.1987
Subarea B3:	40.69					83	0.1447
Subarea B4-DET:	25.05					94	0.1155
Subarea B4-BYP:	7.42					94	0.0787
Subtotal:	153.64						
Subarea C1:	45.21					90	0.2860
Subarea C2:	57.13					81	0.3308
Subarea C3:	52.36					83	0.1199
Subtotal:	154.70						
Modeled Total:	605.02	22.50	39.42	9.88	86.76		

¹ Note: Per TR-55 documentation, minimum T_c is 0.10 hours; model is configured with default value of 0.10 hr. minimum T_c .

Table 4.2-1(b). Macro-Study Fully-Developed Conditions Input Sub-Watershed Data

, ,			Discovery	Discovery	
			Park	Park	Macro-
		Aria	Phase 1	Phase 2	Study
	Total Area	Onsite	Onsite	Onsite	Onsite
	(ac):	Area (ac):	Area (ac):	Area (ac):	Area (ac):
Sub-W'Shed A Subtotal:	296.68	22.50	39.43	9.88	86.76
Sub-W'Shed B Subtotal:	153.64				
Sub-W'Shed C Subtotal:	154.70				
Modeled Total:	605.02	22.50	39.43	9.88	86.76

As noted, these tributary areas, Runoff Curve Numbers (CN), and Times of Concentration (T_C) for the corresponding subareas were used as input to the Proposed Conditions PondPack model to evaluate the stormwater hydrology for the Fully-Developed section of this report. The subareas representing Existing- (offsite) and Proposed Conditions (onsite) for the development sites are utilized in the PondPack model to compute the stormwater runoff for the three design storms. The resultant peak discharge rate (Q_P), peak time (T_P), and runoff volume (V_R) for the computed hydrographs of modeled subareas are included in Table 4.2-2(a).

Table 4.2-2(a). Hydrologic Information – Macro- Fully-Developed Conditions Summary (Subareas)

Location	Q _{P-2}	T _{P-2}	V _{R-2}	Q _{P-10}	T _{P-10}	V _{R-10}	Q _{P-100}	T _{P-100}	V _{R-100}
Location:	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):
Subarea A-1(e):	87.32	11.96	5.137	157.07	11.96	9.384	247.45	11.96	15.116
Subarea A-1(w):	70.15	12.05	4.908	146.86	12.05	10.132	252.55	12.05	17.597
Subarea A-2(e):	7.64	11.94	0.420	14.90	11.93	0.819	24.63	11.93	1.374
Subarea A-2(w):	34.59	12.03	2.301	76.77	12.03	4.975	136.28	12.03	8.884
Subarea A-3:	79.39	11.93	4.376	138.56	11.93	7.797	214.51	11.93	12.366
Subarea A-4(e):	5.22	11.93	0.290	8.85	11.93	0.504	13.49	11.92	0.788
Subarea A-4(w):	14.08	11.96	0.817	32.12	11.94	1.796	58.07	11.94	3.239
Subarea A-5(e):	74.12	11.93	4.202	120.76	11.93	7.047	180.16	11.92	10.767
Subarea A-5(w):	139.52	11.92	8.184	219.79	11.92	13.245	322.02	11.92	19.806
Subarea A-6:	54.75	11.93	3.169	87.16	11.92	5.190	128.41	11.92	7.817
Subarea A-7:	57.26	12.00	3.482	119.03	11.98	7.186	204.90	11.98	12.481
Subarea A-8:	53.05	11.96	3.070	101.89	11.95	5.907	166.82	11.95	9.826
Subarea A-9:	87.15	11.97	5.138	158.95	11.96	9.507	252.78	11.96	15.435
Subarea A-10:	45.61	11.97	2.890	72.57	11.97	4.733	106.86	11.97	7.128
Subarea B-1:	70.94	11.97	4.168	140.29	11.96	8.242	234.20	11.95	13.944
Subarea B-2:	94.72	12.03	6.057	190.16	12.01	12.146	320.74	12.00	20.725
Subarea B-3:	106.50	11.97	6.302	197.62	11.96	11.812	317.37	11.96	19.332
Subarea B-4 (BYP):	30.29	11.93	1.753	48.22	11.92	2.871	71.04	11.92	4.324
Subarea B-4 (DET):	99.43	11.94	5.919	158.21	11.94	9.694	232.94	11.94	14.599
Subarea C-1:	124.83	12.05	9.223	209.38	12.05	15.842	317.10	12.05	24.565
Subarea C-1:	104.44	12.09	8.134	200.90	12.08	15.652	329.78	12.03	26.038
									24.875
Subarea C-3:	142.61	11.95	8.110	264.83	11.94	15.199	425.51	11.94	24.070

As in the previous section, the hydrologic impact resulting from the Fully-Developed Conditions results is partially revealed by the comparison of the preceding subarea data to those established in Section 3 (Existing Conditions) of this report. The hydrologic conditions for offsite subareas remain unchanged between Existing- and Proposed Conditions analyses. Onsite subareas do exhibit changes in impervious cover and diversion of tributary area under Fully-

Developed Conditions. The hydrologic impact to the overall sub-watershed of these modified areas will become apparent in the summary tables for the Points of Interest.

The variation in quantity and rate of stormwater discharge between these two models represents the hydrologic effect generated by the proposed development project for given subareas. The following table depicts the difference in computed subarea hydrology between the Existing- and Fully-Developed Conditions models.

Table 4.2-2(b). Hydrologic Information – Macro- Fully-Developed Conditions Summary

(Subareas)

(Subareas)	Q _{P-2}	T _{P-2}	V _{R-2}	Q _{P-10}	T _{P-10}	V _{R-10}	Q _{P-100}	T _{P-100}	V _{R-100}
Location:	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):
Subarea A-1(e):	33.41	-0.05	1.803	46.75	-0.03	2.601	59.63	-0.03	3.441
Subarea A-1(w):	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Subarea A-2(e):	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Subarea A-2(w):	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Subarea A-3:	21.78	-0.03	1.046	25.98	-0.02	1.302	28.38	-0.02	1.471
Subarea A-4(e):	-18.75	-0.03	-1.112	-37.12	-0.03	-2.194	-61.66	-0.04	-3.7
Subarea A-4(w):	-13.48	-0.05	-0.895	-28.73	-0.05	-1.904	-50.15	-0.05	-3.368
Subarea A-5(e):	37.72	-0.02	2.135	49.86	-0.02	3.016	63.18	-0.03	4.005
Subarea A-5(w):	102.50	-0.08	5.935	142.69	-0.07	8.602	189.41	-0.05	11.742
Subarea A-6:	16.77	n/c	1.086	16.62	-0.01	1.286	15.22	-0.01	1.428
Subarea A-7:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Subarea A-8:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Subarea A-9:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Subarea A-10:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Subarea B-1:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Subarea B-2:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Subarea B-3:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Subarea B-4 (BYP):	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Subarea B-4 (DET):	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Subarea C-1:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Subarea C-1:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Subarea C-3:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c

The sign-convention used in the preceding table is: Proposed Conditions minus Existing Conditions. Therefore, negative values indicate a reduction in computed value, whereas positive values reflect an increase. Those locations that do not exhibit any change in computed values are identified by "n/c."

The previously defined stormwater detention basins, outfall structures and resultant hydrograph attenuation effects have been incorporated into the Fully-Developed Conditions PondPack model. The channel reaches defined in the Existing Conditions analysis are also included in this routing. Results of this Fully-Developed Conditions hydrologic routing are provided in the

Project No. A21-04643

January 2023

following summary table. This information is provided at the same "Points of Interest" used in the Existing Conditions hydrologic analysis for this Stormwater Drainage Study. Refer to the Macro- Fully-Developed Drainage Area Map for the location of the points of interest in relation to the development sites, modeled subareas, channels and conveyances. As in the preceding tables, locations that are unchanged from the Existing Conditions analysis are presented as *grey print* in the following tables.

Table 4.2-3(a). Hydrologic Information – Macro- Fully-Developed Conditions Summary (Junctions)

Un-Detained Hydrology (for Proposed Discovery Park Basin)

Location:	Q _{P-2}	T _{P-2}	V _{R-2}	Q _{P-10}	T _{P-10}	V _{R-10}	Q _{P-100}	T _{P-100}	V _{R-100}
Location.	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):
Point A1:	1,074.58	12.17	95.932	1,932.54	12.16	177.559	2,939.19	12.14	288.906
Point A2:	1,005.57	12.10	86.736	1,784.23	12.09	158.893	2,665.36	12.08	257.043
Point A3:	627.78	12.15	52.992	1,103.02	12.15	98.204	1,588.55	12.17	159.717
Point A4:	436.65	12.03	31.243	718.69	12.03	55.115	1,066.26	12.03	87.287
Point A6:	54.75	11.93	3.169	87.16	11.92	5.190	128.41	11.92	7.817
Point A7:	229.26	12.05	14.580	397.23	12.07	27.333	603.32	12.08	44.871
Point A8:	53.05	11.96	3.070	101.89	11.95	5.907	166.82	11.95	9.826
Point A9:	128.79	12.00	8.028	223.48	11.99	14.240	346.07	11.99	22.563
Point A10:	45.61	11.97	2.890	72.57	11.97	4.733	106.86	11.97	7.128
Point B1:	615.14	12.11	49.667	1,076.61	12.11	91.457	1,551.65	12.14	148.401
Point B2:	242.31	12.05	20.032	446.43	12.04	36.522	715.56	12.03	58.980
Point B3:	153.04	11.99	13.975	266.04	11.98	24.377	411.65	11.97	38.255
Point B4:	48.10	11.94	7.673	71.04	11.93	12.565	98.80	11.93	18.924
Point C1:	350.42	12.09	25.466	604.01	12.10	46.692	890.10	12.10	75.478
Point C2:	232.89	12.04	16.244	417.32	12.07	30.851	614.91	12.08	50.912
Point C3:	142.61	11.95	8.110	264.83	11.94	15.199	425.51	11.94	24.875

As previously evaluated for the modeled Subareas, these Fully-Developed Proposed Conditions results for the Points of Interest will be compared to those established in Section 3 (Existing Conditions) of this report. The points represent similar locations in both Existing- and Proposed Conditions analyses. Therefore, the variation in quantity and rate of stormwater discharge between these two models represents the hydrologic effect generated by the proposed development. The following table depicts the difference between the Existing- and Fully-Developed Conditions models without provisions for onsite stormwater detention.

Project No. A21-04643 January 2023

Table 4.2-3(b). Hydrologic Information – Comparison of Results:

Macro- Fully-Developed vs. Existing Conditions Summary (Junctions) Un-Detained Hydrology

Location:	Q _{P-2}	T _{P-2}	V_{R-2}	Q _{P-10}	T _{P-10}	V _{R-10}	Q _{P-100}	T _{P-100}	V _{R-100}
Location.	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):
Point A1:	123.14	-0.08	7.888	143.92	-0.06	10.596	179.47	-0.05	12.900
Point A2:	93.93	-0.07	6.935	87.31	-0.06	8.844	90.83	-0.05	10.309
Point A3:	-2.51	n/c	-0.02	-7.65	n/c	0.223	-10.82	n/c	0.372
Point A4:	174.41	-0.12	7.175	177.61	-0.09	8.841	158.79	-0.06	10.156
Point A6:	17.21	-0.01	1.086	17.59	-0.01	1.286	21.55	-0.01	1.427
Point A7:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point A8:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point A9:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point A10:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point B1:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point B2:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point B3:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point B4:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point C1:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point C2:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point C3:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c

The sign-convention used in the preceding table is: Proposed Conditions minus Existing Conditions. Therefore, negative values indicate a reduction in computed value, whereas positive values reflect an increase. Those locations that do not exhibit any change in computed values are identified by "n/c."

Information presented in the preceding table exhibits an increase in peak rates at most Points of Interest, relative to the existing conditions model. This is the result of the substantial increased imperviousness for the onsite areas.

Additional analysis is required to determine whether the performance of the proposed development is able to establish compliance with the proposed stormwater management objectives. The following table is provided to examine the difference between the computed peak discharge rates and the established ARR's for the Discovery Park Macro-Study.

Table 4.2-4. Allowable Release Rate Evaluation – Macro- Fully-Developed Conditions Summary Model – Without Detention

	p		,	
		Computed Peak		
		Discharge Rate	ARR	Difference
Location:	Event:	(cfs):	(cfs):	(cfs):
Point A1	2-Year:	1,074.58	881.71	192.87
	10-Year:	1,932.54	1,725.98	206.56

	100-Year:	2,939.19	2,657.53	281.66
Point A2	2-Year:	1,005.57	848.13	157.44
	10-Year:	1,784.23	1,634.53	149.70
	100-Year:	2,665.36	2,478.07	187.29
Point A3	2-Year:	627.78	613.94	13.84
	10-Year:	1,103.02	1,094.99	8.03
	100-Year:	1,588.55	1,578.20	10.35
Point A4	2-Year:	436.65	220.67	215.98
	10-Year:	718.69	494.51	224.18
	100-Year:	1,066.26	815.03	251.23
Point A6	2-Year:	54.75	16.57	38.18
	10-Year:	87.16	40.65	46.51
	100-Year:	128.41	63.30	65.11

The sign-convention utilized for the information presented in the preceding table is based upon "Computed Rate minus ARR." Therefore, positive values indicate an exceedance of the Allowable Release Rate, whereas negative values would indicate a peak rate that is lower than the ARR, thereby meeting the targeted peak discharge rates. The difference in the rates depicted in this table are all in exceedance of the targeted rates. Though the increased peak discharge rates at the defined Points of Interest are relatively moderate, these exceedances are of noticeably greater magnitude.

Proposed Discovery Park Stormwater Detention Facility:

The proposed stormwater management facility that is defined in the Macro Study section of this report is configured for the fully-developed geometry. Therefore, the basin geometry is not repeated in this section. Utilizing the effects of this basin, the following table depicts the stormwater routing summary for the Macro-Study Fully-Developed Conditions.

Table 4.2-5. Fully-Developed Conditions Hydrologic Routing Summary–Discovery Park Stormwater Detention Facility

_	Peak Q In	T _P In	Peak Q Out	T _P Out	V _R	Peak WSEL	Max. Storage
	(cfs):	(hr.):	(cfs):	(hr.):	(ac-ft):	(ft; NAVD):	Volume (ac-ft):
2-Year:	447.89	12.01	167.83	12.20	31.243	932.15	11.079
10-Year:	738.58	12.01	423.35	12.17	55.115	933.61	16.832
100-Year:	1,095.79	12.01	767.11	12.13	87.287	934.78	21.709

The preceding routing summary indicates that, under Fully-Developed Conditions, this basin provides substantial attenuation of the modeled design storm events. Section 8 of this report includes hydrographs for this proposed stormwater management facility.

An emergency spillway is to be constructed on the northwest side of the basin at an elevation of 935.80. The spillway is designed to, should the primary outfall structure be clogged or completely fail, route the 100-year storm into the existing stream. The 100-year storm is calculated as a peak flow of 1,095.79 cfs. The spillway length is designed as 83 LF. In the 100-year storm, the water surface elevation in the weir is calculated as 938.00. The top of the basin is set at 941.00, giving the basin 3.00 LF of freeboard.

Results of this Fully-Developed Conditions hydrologic routing, including the proposed stormwater detention facility are provided in the following summary table. This information is provided at the same "Points of Interest" used in the Existing Conditions hydrologic analysis for this Stormwater Drainage Study. Refer to the Macro Fully-Developed Conditions Drainage Area Map for the location of the points of interest in relation to the development sites, modeled subareas, channels and conveyances. As in the preceding tables, locations that are unchanged from the Existing Conditions analysis are presented as *grey print* in the following tables.

Table 4.2-6(a). Hydrologic Information – Macro- Fully-Developed Conditions Summary

(Junctions) Including Proposed Discovery Park Detention Basin

Location:	Q _{P-2}	T _{P-2}	V_{R-2}	Q _{P-10}	T _{P-10}	V_{R-10}	Q _{P-100}	T _{P-100}	V_{R-100}
Location.	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):
Point A1:	856.69	12.24	95.932	1,640.07	12.25	177.559	2,574.30	12.23	288.906
Point A2:	812.04	12.17	86.736	1,556.43	12.18	158.893	2,425.09	12.17	257.043
Point A3:	627.78	12.15	52.992	1,103.02	12.15	98.204	1,588.55	12.17	159.717
Point A4:	167.79	12.23	31.243	423.01	12.19	55.115	766.66	12.15	87.287
Point A6:	54.75	11.93	3.169	87.16	11.92	5.190	128.41	11.92	7.817
Point A7:	229.26	12.05	14.580	397.23	12.07	27.333	603.32	12.08	44.871
Point A8:	53.05	11.96	3.070	101.89	11.95	5.907	166.82	11.95	9.826
Point A9:	128.79	12.00	8.028	223.48	11.99	14.240	346.07	11.99	22.563
Point A10:	45.61	11.97	2.890	72.57	11.97	4.733	106.86	11.97	7.128
Point B1:	615.14	12.11	49.667	1,076.61	12.11	91.457	1,551.65	12.14	148.401
Point B2:	242.31	12.05	20.032	446.43	12.04	36.522	715.56	12.03	58.980
Point B3:	153.04	11.99	13.975	266.04	11.98	24.377	411.65	11.97	38.255
Point B4:	48.10	11.94	7.673	71.04	11.93	12.565	98.80	11.93	18.924
Point C1:	350.42	12.09	25.466	604.01	12.10	46.692	890.10	12.10	75.478
Point C2:	232.89	12.04	16.244	417.32	12.07	30.851	614.91	12.08	50.912
Point C3:	142.61	11.95	8.110	264.83	11.94	15.199	425.51	11.94	24.875

As with the previous section, these Fully-Developed Conditions results for the Points of Interest will be compared to those established in Section 3 (Existing Conditions) of this report. The points represent similar locations in both Existing- and Proposed Conditions analyses. Therefore, the variation in quantity and rate of stormwater discharge between these two models represents the hydrologic effect generated by the proposed development. The following table depicts the difference between the Existing- and Fully-Developed Conditions models, including the effects of the proposed onsite stormwater detention facility.

Table 4.2-6(b). Hydrologic Information – Comparison of Results:

Macro- Fully-Developed Conditions vs. Existing Conditions Summary (Junctions)

Detaine	d H	vdro	loav

Location:	Q _{P-2}	T _{P-2}	V _{R-2}	Q _{P-10}	T _{P-10}	V _{R-10}	Q _{P-100}	T _{P-100}	V _{R-100}
Location.	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):	(cfs):	(hr.):	(ac-ft):
Point A1:	-92.27	-0.01	7.879	-144.16	0.03	10.59	-180.54	0.04	12.898
Point A2:	-97.01	0.00	6.926	-135.30	0.03	8.838	-141.50	0.04	10.307
Point A3:	-0.86	0.00	-0.005	-4.65	0.00	0.252	-7.01	0.00	0.420
Point A4:	-93.13	0.08	7.151	-116.48	0.08	8.806	-139.90	0.06	10.105
Point A6:	16.77	0.00	1.086	16.62	-0.01	1.286	15.22	-0.01	1.428
Point A7:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point A8:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point A9:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point A10:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point B1:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point B2:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point B3:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point B4:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point C1:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point C2:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c
Point C3:	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c	n/c

The sign-convention used in the preceding table is: Proposed Conditions minus Existing Conditions. Therefore, negative values indicate a reduction in computed value, whereas positive values reflect an increase. Those locations that do not exhibit any change in computed values are identified by "n/c."

Data presented in the preceding table depicts the significant reduction in peak rates relative to the Existing Conditions model along the Channel "A" tributary. There is no change from the Macro-Study Proposed Conditions at the Point A3 location. Although the peak discharge rates are reduced at the modeled Points of Interest, further analysis is required to establish compliance with the project's stormwater management objectives.

The following table is provided to examine the difference between the computed Fully-Developed Conditions peak discharge rates and the established ARR's for the overall development.

Table 4.2-7. Allowable Release Rate Evaluation – Fully-Developed Conditions Macro Study (W/Detention)

		Computed Peak		
		Discharge Rate	ARR	Difference
Location:	Event:	(cfs):	(cfs):	(cfs):
Point A1	2-Year:	856.69	859.38	-2.69
	10-Year:	1640.07	1704.07	-64.00
	100-Year:	2574.30	2623.74	-49.44
Point A2	2-Year:	812.04	823.14	-11.10
	10-Year:	1556.43	1607.68	-51.25
	100-Year:	2425.09	2436.65	-11.56
Point A3	2-Year:	627.78	612.50	15.28
	10-Year:	1103.02	1092.23	10.79
	100-Year:	1588.55	1574.71	13.84
Point A4	2-Year:	167.79	200.55	-32.76
	10-Year:	423.01	471.95	-48.94
	100-Year:	766.66	771.67	-5.01
Point A6	2-Year:	54.75	16.57	38.18
	10-Year:	87.16	40.65	46.51
l	100-Year:	128.41	63.30	65.11

Note: The sign-convention utilized for the information presented in the preceding table is based upon "Computed Rate minus ARR." Positive values indicate an exceedance of the ARR; negative values indicate that the peak rate is lower than the ARR.

The difference in the rates depicted in this table are generally in compliance with the targeted rates; the proposed stormwater management facility provides adequate attenuation for the primary Channel "A" tributary. The information provided in the preceding table does demonstrate that there are a few exceptions: Peak rates at Point A3 and A6. Point A3 is the terminal end of the Channel "B" tributary, immediately upstream from confluence at Point A2, while point A6 flows directly into the proposed basin. Although the ARR is exceeded at the Point A3 location, the Proposed Conditions analysis does exhibit that areas further downstream are below ARR at all storm events. ARR is also exceeded at Point A6 during all storm events, however this point is located upstream of the proposed detention basin and is routed through the basin for attenuation.

4.3. Proposed Stormwater Best Management Practices

This section of the study will address water quality treatment for the proposed development. While the City of Lee's Summit has not adopted the Mid America Regional Council and American Public Works Association "Manual of Best Management Practices for Stormwater Quality" (Oct. 2012), 40-hr extended detention of the water quality storm volume generated by the development is required.

The proposed wet detention basin provides sufficient storage and peak rate attenuation to meet all Allowable Release Rate requirements for the development, and it will also provide the required 40-hr extended detention of the water quality storm event for both proposed conditions and fully-developed conditions for portion of the development: Discovery Park Phase 1. It's proper to assume that water quality treatment designed for fully-developed conditions, which will be the focus of this section, will also satisfy water quality treatment requirements for proposed conditions.

The following table summarizes water quality volume that needs treatment from Discovery Park Phase 1. A total of 241,500 cu ft of water quality volume has to be provided at the wet detention basin, and this volume will be used to size the orifice and determine required depth of water.

Table 4.3-1. Water Quality Volume Calculations

Subarea	Total Trib. Area (s.f.):	Total Trib. Area (ac.):	Impervious Area (s.f.)	Pervious Area (s.f.)	Percent Impervious	Short- Cut Vol. Runoff Coeff. (Rv)	Small Storm Hydrology Vol. Runoff Coeff. (Rv)	WQv (c.f.)
A5e (Aria)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	Not Provided
A5w (Discovery Park Phase 1)	1,445,632	33.19	1,046,065	399,567	72.36%	0.70	0.77	127,529
A6 (Discovery Park Phase 2)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	Not Provided
Detention Basin	1,445,632	33.19	1,046,065	399,567	72.36%	0.70	0.77	127,529

A 142 deg V-Notch weir will be set at the bottom of the multistage outlet structure. The flow invert elevation of the weir is at 929.00, which matches permanent water surface elevation. This weir is sized and designed in accordance with the worksheet provided by MARC BMP Manual to ensure 40-hour release of the 90 percent mean annual event. A copy of the worksheet can be found in Section 7 of this report.

In accordance with the Lee's Summit Design and Construction Manual (DCM) Section 1002.A, a waiver is being requested to remove 10.3 acres of stream buffer located within the project site (outlined in Section 5605 of KC-APWA Section 5600). The need to remove the existing creek channel, as shown on the attached exhibit, is driven by:

- The site layout approved by the city TIF commission, which includes a wet-bottom detention basin that is part of a development amenity space with a pond, parkland, and walking trail.
- A required entrance drive off of NE Douglas Road with minimum spacing allowed by the project traffic study to the adjacent intersection placing it in conflict with the existing creek channel.
- A clubhouse with swimming pool between the proposed detention basin and entrance drive.

The upstream end of the existing creek channel begins at the outlet point of an existing concrete box culvert under NE Douglas Street. This box culvert will be extended approximately 670 linear feet and discharge into the proposed wet-bottom detention basin.

The proposed development has been extensively coordinated with Unity Village, the owner/operator of Unity Lake #2, an existing lake that is located approximately ½ mile downstream of the proposed stream buffer impacts. As indicated in the attached letter from Unity Village, with the level of storm water quality treatment and peak runoff rate control being provided by the proposed improvements, this project has their full support.

As part of the due diligence performed for the development, the following reviews were completed:

- A jurisdictional determination was requested by the United States Army Corps of Engineers (USACE). The USACE provided a determination letter (attached with this request) that states the affected creek channel and attached wetlands are not jurisdictional water of the US.
- Review of existing FEMA floodplains was completed and no regulated floodplains exist within the affected creek channel as shown on the attached FEMA FIRM panel.

As a part of any development, the City of Lee's Summit requires that 40-hour extended dry detention of the water quality storm event be provided for the project site or equivalent on-site water quality treatment per the APWA BMP Manual. This is to promote the removal of pollutants and debris out of storm water prior to being discharged downstream of the development site. Furthermore, with the culvert discharging into the wet-bottom detention basin with approximately 680 feet of travel length through a permanent pool of water, suspended solids and floatables that are conveyed into the basin from upstream (offsite) areas, not required to be treated by this development, will have an opportunity to settle out or be collected and disposed of. Discharging

the culvert extension directly into the permanent pool basin will also provide scour and erosion protection that is a common problem at pipe outlets into dry basins or creek channels. Permanent pool detention basins also promote wildlife and aquatic habitats where dry basins are typically mowed and maintained to prevent vegetation, often deemed as 'unsightly' by land owners, from growing.

To improve the aesthetics and quality of the proposed wet detention basin, landscape design guidelines are being established for the development. The proposed guidelines require a 15-ft buffer of native plantings around the perimeter of the pond, restricting the use of turf grass in that zone. The taller native plantings and grasses provide wildlife habitat and refuse while filtering physical and chemical pollutants. Native planted buffer zones in conjunction with the existing old growth tree preservation (when possible) will enhance wildlife habitat and connectivity.

In addition to the water quality treatment being provided for the development prior to discharging runoff into the creek, 5.2 acres of enhanced stream buffer is being proposed to be set aside downstream of the impacted creek channel to further offset any environmental/wildlife impact caused by removing stream buffer described.

Project No. A21-04643

5. SUMMARY

See Tables 5-1 and 5-2, below, for a summary comparison of Existing, Allowable, and Proposed peak flowrates during the Macro conditions.

Table 5-1. Macro- Proposed Peak Flowrate Comparison

1 4510 0 11	linaoro rro	JUSEU PEAK I	iomato co	parioon	Difference	Difference
		Existing		Proposed	(Existing vs.	(ARR vs.
		Flowrate	ARR	Flowrate	Proposed)	Proposed)
Location:	Event:	(cfs):	(cfs):	(cfs):	(cfs):	(cfs):
Point A1	2-Year:	948.96	859.38	840.82	-108.14	-18.56
	10-Year:	1,748.23	1704.07	1593.89	-190.34	-110.18
	100-Year:	2,754.84	2623.74	2524.85	-229.99	-98.89
Point A2	2-Year:	909.05	823.14	799.40	-109.65	-23.74
	10-Year:	1,691.73	1607.68	1513.84	-177.89	-93.84
	100-Year:	2,566.59	2436.65	2381.07	-185.52	-55.58
Point A3	2-Year:	628.64	612.50	625.11	-3.53	12.61
	10-Year:	1,107.67	1092.23	1100.39	-7.28	8.16
	100-Year:	1,595.56	1574.71	1586.54	-9.02	11.83
Point A4	2-Year:	260.92	200.55	160.04	-100.88	-40.51
	10-Year:	539.49	471.95	394.92	-144.57	-77.03
	100-Year:	906.56	771.67	727.66	-178.90	-44.01
Point A6	2-Year:	37.98	16.57	37.88	-0.10	21.31
	10-Year:	70.54	40.65	70.35	-0.19	29.70
	100-Year:	113.19	63.30	112.88	-0.31	49.58

Note: The sign-convention utilized for the information presented in the preceding table is based upon "Proposed Rate minus Existing (or ARR)." Positive values indicate an exceedance of the Existing (or ARR); negative values indicate that the peak rate is lower than the Existing (or ARR).

Table 5-2. Macro-Fully Developed- Peak Flowrate Comparison

		Developeu-			Difference	Difference
		Existing		Proposed	(Existing vs.	(ARR vs.
		Flowrate	ARR	Flowrate	Proposed)	Proposed)
Location:	Event:	(cfs):	(cfs):	(cfs):	(cfs):	(cfs):
Point A1	2-Year:	948.96	857.17	856.69	-92.27	-2.69
	10-Year:	1,784.23	1702.66	1640.07	-144.16	-64.00
	100-Year:	2,754.84	2621.34	2574.30	-180.54	-49.44
Point A2	2-Year:	909.05	823.14	812.04	-97.01	-11.10
	10-Year:	1,691.73	1607.68	1556.43	-135.30	-51.25
	100-Year:	2,566.59	2436.65	2425.09	-141.50	-11.56
Point A3	2-Year:	628.64	612.5	627.78	-0.86	15.28
	10-Year:	1,107.67	1092.23	1103.02	-4.65	10.79
	100-Year:	1,595.56	1574.71	1588.55	-7.01	13.84
Point A4	2-Year:	260.92	200.55	167.79	-93.13	-32.76
	10-Year:	539.49	471.95	423.01	-116.48	-48.94
	100-Year:	906.56	771.67	766.66	-139.90	-5.01
Point A6	2-Year:	37.98	16.57	54.75	16.77	38.18
	10-Year:	70.54	40.65	87.16	16.62	46.51
	100-Year:	113.19	63.3	128.41	15.22	65.11

Note: The sign-convention utilized for the information presented in the preceding table is based upon "Proposed Rate minus Existing (or ARR)." Positive values indicate an exceedance of the Existing (or ARR); negative values indicate that the peak rate is lower than the Existing (or ARR).

Table 5-3. Macro ARR Comparison

		Existing	
	Return	Conditions	
	Event	Flow Rate	ARR
Location:	(Yr):		(cfs):
Point A7			
	2-Year:	229.26	229.26
1	0-Year:	397.23	397.23
10	00-Year:	603.32	603.32
Point B1			
	2-Year:	615.14	615.14
1	0-Year:	1,076.61	1076.61
10	0-Year:	1,551.65	1551.65
Point D1			
	2-Year:	560.43	481.87
1	0-Year:	941.67	874.92
10	00-Year:	1351.30	1262.83
Point D2			
	2-Year:	485.06	427.99
1	0-Year:	752.83	707.54
10	0-Year:	1052.38	996.29
Point E1			
	2-Year:	65.98	29.51
1	0-Year:	106.88	72.41
10	0-Year:	143.00	103.59
Point F1			
	2-Year:	47.57	25.75
1	0-Year:	74.89	55.17
10	0-Year:	106.16	80.20
Point F2			
	2-Year:	31.56	7.75
1	0-Year:	45.26	26.59
10	0-Year:	65.86	39.78
Point G1			
	2-Year:	58.32	42.99
1	0-Year:	102.21	83.33
10	0-Year:	163.43	131.84
Point G2			
	2-Year:	23.29	5.94
1	0-Year:	36.98	18.02
10	00-Year:	62.01	27.70

January 2023

Project No. A21-04643

Location:	Return Event (Yr):	Existing Conditions Flow Rate	ARR (cfs):
Point H1			
	2-Year:	119.54	36.41
1	0-Year:	240.90	124.05
10	0-Year:	406.43	190.18
Point I1			
	2-Year:	4.44	2.80
1	0-Year:	7.87	5.64
10	0-Year:	12.29	8.74

The above table establishes ARR rates for locations unaffected in the Phase 1 Fully-Developed conditions. Future developments within the areas will by analyzed by their respective macro studies.

A design waiver is being requested to remove 10.3 acres of stream buffer located within the project site to allow for construction of a permanent pool detention basin, entrance drive off of NE Douglas Road, and clubhouse/pool amenity space for the development. Upstream water quality treatment is being provided to treat pollutants closer to the point source within the development, enhanced landscaping is required around the detention basin to promote wildlife and pollutant removal, and offsite discharges will be routed through the pond to allow for settlement and collection of suspended solids and floatable debris.

6. CONCLUSION

This study has been prepared to provide an analysis of the impacts that the fully-developed conditions of project site areas tributary to Unity Lake #2, and provide prescriptive release rate requirements for future development areas within the Discovery Park development. Once fully developed, the area treated by the proposed detention basin include:

- Aria Apartments: a 22.50-ac apartment development (Zoned RP-4)
- Discovery Park Phase 1: a 39.42-ac commercial development (Zoned CP-2)
- Discovery Park Phase 2: a 19.82-ac commercial development (currently zoned AG and to be rezoned at a future time)

Water quality treatment was provided to Discovery Park Phase 1 only.

As shown in the tables presented in the sections above, it has been determined that with the proposed development and detention basin, the peak runoff rates for the study area are reduced from the pre-developed conditions at all points analyzed. Comprehensive Control requirements are also met at the outfall points A1, A2, and A4 in the 2-, 10-, and 100-year storm events.

The existing basin located at Point A5 provides a slight attenuation of peak flows and delays in timing for offsite points A7, A8, A9 and A10. With construction of the new basin, the existing basin will be removed and flows from Point A7 will be rerouted into the proposed basin by extending the existing box culvert under Douglas Street. A design waiver is being requested to remove 10.3 acres of stream buffer while providing water quality treatment via upstream water quality systems to promote pollutant removal.

The results of this study demonstrate the overall general compliance with the City of Lee's Summit design criteria and a waiver is being submitted for approval of a deviation from the design criteria. We therefore request approval of this stormwater management report.

7	. CALCULATIO	NS AND MODE	L RESULTS	

Discovery Park Macro Stormwater Drainage Study NRCS Curve Number Calculations Existing Conditions 3/31/2023

	Total Area	Aria Onsite	Discovery Park Phase 1 Onsite	Discovery Park Phase 2 Onsite	Macro- Study Onsite Area	Weighted
Location ID:	(ac):	Area (ac):	Area (ac):	Area (ac):	(ac):	NRCS CN:
Subarea A1(e):	27.97				12.36	77
Subarea A1(w):	43.14					76
Subarea A2(e):	3.08					80
Subarea A2(w):	23.41					73
Subarea A3:	24.42	11.62				80
Subarea A4(e):	9.85	5.99	3.35			81
Subarea A4(w):	17.41		9.19			73
Subarea A5(e):	15.16	4.88	8.00			80
Subarea A5(w):	19.77		18.66			76
Subarea A6:	13.45			9.21		83
Subarea A7:	30.60					76
Subarea A8:	21.56					81
Subarea A9:	31.84					84
Subarea A10:	12.23					94
Subtotal:	293.88	22.50	39.20	9.21	12.36	
Subarea B1:	31.94					79
Subarea B2:	48.54					78
Subarea B3:	40.69					83
Subarea B4-DET:	25.05					94
Subarea B4-BYP:	7.42					94
Subtotal:	153.64					
Subarea C1:	45.21					90
Subarea C2:	57.13					81
Subarea C3:	52.36					83
Subtotal:	154.70					
Subarea D1:	36.91		0.22			77
Subarea D2:	47.00			10.62	24.74	79
Subarea D3:	16.84					88
Subarea D4:	112.38					88
Subarea D5:	53.24					89
Subtotal:	266.37		0.22	10.62	24.74	
Subarea E1:	22.59				20.68	80
Subarea E2:	6.56					73
Subtotal:	29.15				20.68	
Subarea F1:	7.85					77
Subarea F2:	12.76				12.06	81
Subtotal:	20.60				12.06	
Subarea G1:	14.04					81
Subarea G2:	7.93				7.11	85
Subtotal:	21.96				7.11	
Subarea H1:	56.17				51.06	78
Subtotal:	56.17				51.06	
Subarea I1:	1.40				0.61	86
Subtotal:	1.40				0.61	

Sub-W'Shed A Subtotal:	293.88	22.50	39.20	9.21	12.36
Sub-W'Shed B Subtotal:	153.64				
Sub-W'Shed C Subtotal:	154.70				
Sub-W'Shed D Subtotal:	266.37		0.22	10.62	24.74
Sub-W'Shed E Subtotal:	29.15				20.68
Sub-W'Shed F Subtotal:	20.60				12.06
Sub-W'Shed G Subtotal:	21.96				7.11
Sub-W'Shed H Subtotal:	56.17				51.06
Sub-W'Shed I Subtotal:	1.40				0.61
Modeled Total:	997.89	22.50	39.42	19.83	128.62

							2-	ACRE	1/2	ACRE																							
Land	Water/					Multi-Family		e-Family		-Family		rops SR		ops C & T						-Grass		-Grass											
Use:	Impervious	Comm			w	Residential		idential		dential		ood)		ood)		re (Fair)		e (Good)	Combinat		Combinat				Open Spa					s (Fair)	Woods		
HSG:		Type C	Type D	Туре С	Type D	Type C Type D	Type C	Type D	Type C	Type D	Type C	Type D	Type C	Type D	Type C	Type D	Type C	Type D	Type C	Type D	Type C	Type D	Type C	Type D	Type C	Type D	Type C	Type D	Type C	Type D	Type C	Type D	Weinkend
CN:	98	94	95	92	93	88 91	77	82	80	85	85	89	80	82	79	84	74	80	76	82	72	79	71	78	79	84	74	80	73	79	70	77	Weighted CN:
	0.27 0.49 0.26 0.07			0.61 0.14 2.98	1.25		1.45	0.42			0.93 4.58	0.30	6.69 4.39	1.93			8.98 8.39 0.34 10.08 0.05	6.67 1.58 2.60 4.84 0.12										1.55	6.09 0.79 1.46	0.67 2.22 3.28	2.83 4.94 15.98	6.49 12.36 0.70	76.58 76.11 79.92 72.85 79.79 81.37
	0.09	11.46 4.05	2.18 5.86	1.81 1.08 2.20 1.90 2.25 1.39 1.04	0.46 0.03 1.26 0.63 3.11 0.22 1.28		0.09	1.49	2.50		1.54		1.34 1.14 4.61	0.26 0.13	3.25 5.12 1.65 4.75	0.12 0.06		3.36								0.21	25.57 8.00 16.59	8.20	4.32 4.64 11.93	0.07	8.51		73.19 79.92 76.38 83.21 76.00 80.91 83.56 94.19
		8.29 14.71 4.33	0.97 9.25 2.76	1.50 11.26 0.40 0.12	0.46 0.69 0.21	13.51	20.14	1.46	7.19	1.19																	37.28 17.92						79.13 78.17 83.23 94.31 94.31
		15.20		22.85																							7.16						89.82
	17.56	1.77		21.60		1.29																					35.53 31.74						80.81 83.06
	2.92 3.33 7.42 2.60 1.09	1.29 34.36 9.83	33.19 19.60	1.06 0.85 5.12 1.06	1.00 0.40 3.90 3.38			0.37	0.49	1.13 0.10	4.03	0.10			12.32		0.22	2.70			8.01	0.52			3.08 6.84 4.38	1.02 3.44 2.58 2.40 0.88	7.93 4.42 4.14	0.71 8.32	6.12	0.11	7.12 11.17 13.42	6.33 5.21 2.96	77.21 79.32 88.14 88.41 88.77
	0.32 0.52			0.22	0.32						8.55	0.62											0.12		0.71 0.65						4.77 5.26	7.09	79.61 73.14
				0.42 0.68	0.16 0.02						1.00 8.24																				2.06 3.82	4.20	77.32 80.89
				0.29 0.39	0.41 0.43						3.44 6.27	1.57 0.16																			1.16 0.32	7.16 0.37	80.51 84.87
	1.16						0.09	1.61			14.30						1.21	6.08	1.74	1.40					0.99						14.87	12.71	78.15
																									. , ,								
				0.45	0.33		0.09	0.15			0.07						0.24	0.01													0.05		85.86

Discovery Park Macro Stormwater Drainage Study NRCS Curve Number Calculations Fully Developed Conditions 3/31/2023

Location ID:	Total Area (ac):	Aria Onsite Area (ac):	Discovery Park Phase 1 Onsite Area (ac):	Discovery Park Phase 2 Onsite Area (ac):	Macro- Study Onsite Area (ac):	Weighted
Subarea A1(e):	30.57				14.96	85
Subarea A1(w):	43.14					76
Subarea A2(e):	3.08					80
Subarea A2(w):	23.41					73
Subarea A3:	24.06	11.07			11.07	87
Subarea A4(e):	1.48	0.14	0.84		0.98	89
Subarea A4(w):	8.75		0.59		0.59	72
Subarea A5(e):	19.12	11.29	6.92		18.20	92
Subarea A5(w):	33.42		31.08		31.08	95
Subarea A6:	13.42			9.88	9.88	94
Subarea A7:	30.60					76
Subarea A8:	21.56					81
Subarea A9:	31.84					84
Subarea A10:	12.23					94
Subtotal:	296.68	22.50	39.42	9.88	86.76	
Subarea B1:	31.94					79
Subarea B2:	48.54					78
Subarea B3:	40.69					83
Subarea B4-DET:	25.05					94
Subarea B4-BYP:	7.42					94
Subtotal:	153.64					
Subarea C1:	45.21					90
Subarea C2:	57.13					81
Subarea C3:	52.36					83
Subtotal:	154.70					

Sub-W'Shed A Subtotal:	296.68	22.50	39.42	9.88	86.76
Sub-W'Shed B Subtotal:	153.64	0.00	0.00	0.00	0.00
Sub-W'Shed C Subtotal:	154.70	0.00	0.00	0.00	0.00
Modeled Total:	605.02	22.50	39.42	9.88	86.76

								2-A	CRE	1/2 A	CRE															
Land	Water/						Family		-Family	Single-			ops C & T						s-Grass							
Use:	Impervious	Comm			R/W		dential		lential	Resid			ood)		v (Good)		e (Good)	-	tion (Fair)				s (Fair)		(Good)	
HSG:		Type C	Type D	Type C	Type D	Type C	Type D	Type C	Type D	Type C	Type D	Type C	Type D	Type C	Type D	Type C	Type D	Type C	Type D	Type C	Type D	Type C	Type D	Type C	Type D	
																										Weighted
CN:	98	94	95	92	93	88	91	77	82	80	85	80	82	71	78	74	80	76	82	74	80	73	79	70	77	CN:
	0.27			0.61			14.96	0.00								1.37	6.15							1.32	5.89	84.50
	0.49											6.69	1.93			8.39	1.58					6.09	0.67	4.94	12.36	76.12
				0.14												0.34	2.60									79.88
												4.39									1.55	0.79		15.98	0.70	72.85
	0.26			3.17	1.25		11.07	1.45	0.42							0.50	3.85								2.10	86.98
	0.07		0.84				0.14																		0.42	89.35
			0.59																					8.16		71.67
			6.92	0.92			11.29																			92.49
			31.08	1.78	0.49																			0.06		94.76
			9.39	2.25	1.29												0.49									93.76
				1.90	0.63					2.50										25.57						76.00
				2.25	3.11															8.00	8.20					80.90
		11.46	2.18	1.39	0.22															16.59						83.55
		4.05	5.86	1.04	1.28																					94.20
				1.50	0.46			20.14	1.46	7.19	1.19															79.14
				11.26	0.40			20.14	1.40	7.10	1.10									37.28						78.18
		8.29	0.97	11.20		13.51														17.92						83.22
		14.71	9.25	0.40	0.69	13.01														17.32						94.31
		4.33	2.76	0.12	0.03																					94.31
		7.33	2.70	0.12	U.Z I																					34.31
		15.20		22.85																7.16						89.82
				21.60																35.53						80.81
	17.56	1.77				1.29														31.74						83.07

Discovery Park Macro Stormwater Drainage Study NRCS Curve Number Calculations Proposed Conditions 3/31/2023

Location ID:	Total Area (ac):	Aria Onsite Area (ac):	Discovery Park Phase 1 Onsite Area (ac):	Discovery Park Phase 2 Onsite Area (ac):	Macro- Study Onsite Area (ac):	Weighted NRCS CN:
Subarea A1(e):	27.97				12.36	77
Subarea A1(w):	43.14					76
Subarea A2(e):	3.08					80
Subarea A2(w):	23.41					73
Subarea A3:	24.06	11.07			11.07	82
Subarea A4(e):	1.48	0.14	0.84		0.98	88
Subarea A4(w):	8.75		0.59		0.59	72
Subarea A5(e):	19.12	11.29	6.92		18.20	86
Subarea A5(w):	33.42		31.08		31.08	95
Subarea A6:	13.42			9.88	9.88	83
Subarea A7:	30.60					76
Subarea A8:	21.56					81
Subarea A9:	31.84					84
Subarea A10:	12.23					94
Subtotal:	294.08	22.50	39.42	9.88	84.15	
Subarea B1:	31.94					79
Subarea B2:	48.54					78
Subarea B3:	40.69					83
Subarea B4-DET:	25.05					94
Subarea B4-BYP:	7.42					94
Subtotal:	153.64					
Subarea C1:	45.21					90
Subarea C2:	57.13					81
Subarea C3:	52.36					83
Subtotal:	154.70					

Sub-W'Shed A Subtotal:	294.08	22.50	39.42	9.88	84.15
Sub-W'Shed B Subtotal:	153.64	0.00	0.00	0.00	0.00
Sub-W'Shed C Subtotal:	154.70	0.00	0.00	0.00	0.00
Modeled Total:	602.42	22.50	39.42	9.88	84.15

								2-A	CRE	1/2 A	CRE															
Land	Water/						Family		-Family	Single-			ops C & T						s-Grass							
Use:	Impervious	Comm			R/W		dential		dential	Resid			ood)		v (Good)		e (Good)	-	tion (Fair)				s (Fair)		(Good)	
HSG:		Type C	Type D	Type C	Type D	Type C	Type D	Type C	Type D	Type C	Type D	Type C	Type D	Type C	Type D	Type C	Type D	Type C	Type D	Type C	Type D	Type C	Type D	Type C	Type D	
																									_	Weighted
CN:	98	94	95	92	93	88	91	77	82	80	85	80	82	71	78	74	80	76	82	74	80	73	79	70	77	CN:
	0.27			0.61				2.12								8.98	6.67							2.83	6.49	76.58
	0.49											6.69	1.93			8.39	1.58					6.09	0.67	4.94	12.36	76.12
				0.14												0.34	2.60									79.88
												4.39									1.55	0.79		15.98	0.70	72.85
	0.26			3.16	1.25			1.45	0.42							0.50	3.85				11.07				2.10	81.91
	0.07		0.84																		0.14			0.40	0.42	88.28
			0.59	0.00																	44.00			8.16		71.67
			6.92 31.08	0.92	0.40																11.29			0.00		86.00
			31.08	1.78	0.49												0.40				0.00			0.06		94.76
				2.25	1.29					0.50							0.49			05.57	9.39					83.26
				1.90 2.25	0.63					2.50										25.57	0.00					76.00 80.90
		11.46	2.18	1.39	3.11 0.22															8.00 16.59	8.20					83.55
		4.05	5.86	1.04	1.28															10.59						94.20
		4.00	0.00	1.04	1.20																					94.20
				1.50	0.46			20.14	1.46	7.19	1.19															79.14
				11.26	0.70			20.77	7. 70	7110	7.70									37.28						78.18
		8.29	0.97			13.51														17.92						83.22
		14.71	9.25	0.40	0.69																					94.31
		4.33	2.76	0.12	0.21																					94.31
		15.20		22.85																7.16						89.82
				21.60																35.53						80.81
	17.56	1.77				1.29														31.74						83.07

Discovery Park Macro Stormwater Drainage Study Allowable Release Rate (ARR) Calculations 12/12/2022

Total Area (ac):	Total Trib. Area (ac):	Aria Onsite Area (ac):	Discovery Park Onsite Area (ac):	Macro Onsite Area (ac):
Point A7:	96.23	0.00	0.00	0.00
Point A5:	144.60	4.88	26.66	31.54
Point A4:	171.86	10.74	38.03	48.77
Point B1:	308.34	0.00	0.00	0.00
Point A3:	332.76	11.62	0.00	11.62
Point A2:	531.11	22.36	38.03	60.39
Point A1:	602.22	22.36	38.03	72.75

Storm Event:	Onsite ARR (cfs/ac)
2-Yr:	0.5
10-Yr:	2
100-Yr:	3

Project Site:	Onsite ARR (cfs/ac)
Aria (ac):	22.36
Discovery Park (ac):	38.03
North-MFR (ac):	12.36

				Existing Conditions
	Return Event	Peak Flow	Total Area	Release Rate
	(yr):	Rate (cfs):	(ac):	(cfs/ac):
			602.22	
Point A1	2	951.44	602.22	1.58
POIIIL A I	10	1,788.62	602.22	2.97
	100	2,759.72	602.22	4.58
			531.11	
Point A2	2	911.64	531.11	1.72
POIIIL AZ	10	1,696.92	531.11	3.20
	100	2,574.53	531.11	4.85
			332.87	
Point A3	2	630.29	332.87	1.89
POIIII A3	10	1,110.67	332.87	3.34
	100	1,599.37	332.87	4.80
			171.75	
Point A4	2	262.24	171.75	1.53
POIIIL A4	10	541.08	171.75	3.15
	100	907.47	171.75	5.28
			144.6	
Point A5	2	244.35	144.6	1.69
roint A3	10	493.17	144.6	3.41
	100	804.09	144.6	5.56
			96.23	
Point A7	2	229.26	96.23	2.38
Polit A7	10	397.23	96.23	4.13
	100	603.32	96.23	6.27
			308.34	
Doint D4	2	615.14	308.34	2.00
Point B1	10	1,076.61	308.34	3.49
	100	1,551.65	308.34	5.03

Aria:	Discovery Park:	Macro - Model:
Onsite Area (ac):	Onsite Area (ac):	Onsite Area (ac):
22.36	38.03	72.75
22.36	38.03	60.39
11.62	0.00	11.62
10.74	38.03	48.77
4.88	26.66	31.54
0.00	0.00	0.00
0.00	0.00	0.00

Aria:	Discovery Park:	Macro - Model:
Allowable Bypass (ac):	Allowable Bypass (ac):	Allowable Bypass (ac):
916.11	891.36	836.50
1722.21	1675.67	1572.55
2657.25	2585.44	2426.34
873.26	846.36	807.98
1625.48	1575.41	1503.97
2466.14	2390.18	2281.79
608.29	630.29	608.29
1071.90	1110.67	1071.90
1543.54	1599.37	1543.54
245.84	204.17	187.77
507.24	421.27	387.44
850.72	706.53	649.79
236.10	199.30	191.05
476.53	402.24	385.60
776.95	655.84	628.70
229.26	229.26	229.26
397.23	397.23	397.23
603.32	603.32	603.32
000.02	000.02	000.02
615.14	615.14	615.14
1076.61	1076.61	1076.61
1551.65	1551.65	1551.65

Aria:	Discovery Park:	Macro - Model:
Allowable Onsite Discharge (cfs):	Allowable Onsite Discharge (cfs):	Allowable Onsite Discharge (cfs):
(5.5).	(5.5):	(0.0).
11.18	19.02	36.38
44.72	76.06	145.50
67.08	114.09	218.25
11.18	19.02	30.20
44.72	76.06	120.78
67.08	114.09	181.17
5.81	0.00	5.81
23.24	0.00	23.24
34.86	0.00	34.86
5.37	19.02	24.39
21.48	76.06	97.54
32.22	114.09	146.31
2.44	13.33	15.77
9.76	53.32	63.08
14.64	79.98	94.62
0.00	0.00	0.00
0.00	0.00	0.00
0.00	0.00	0.00
0.00	0.00	0.00
0.00	0.00	0.00
0.00	0.00	0.00
0.00	0.00	0.00

Aria:	Discovery Park:	Macro - Model:
Proposed Conditions ARR (cfs):	Proposed Conditions ARR (cfs):	Proposed Conditions ARR (cfs):
927.29	910.37	872.88
1766.93	1751.73	1718.05
2724.33	2699.53	2644.59
884.44	865.38	838.18
1670.20	1651.47	1624.75
2533.22	2504.27	2462.96
614.10	630.29	614.10
1095.14	1110.67	1095.14
1578.40	1599.37	1578.40
251.21	223.19	212.16
528.72	497.33	484.98
882.94	820.62	796.10
000.54	040.00	000.00
238.54	212.63	206.82
486.29	455.56	448.68
791.59	735.82	723.32
229,26	229.26	229,26
397.23	397.23	397.23
603.32	603.32	603.32
615.14	615.14	615.14
1076.61	1076.61	1076.61
1551.65	1551.65	1551.65

	Aria:	Discovery Park:	Macro - Model:
 s	Difference in Flow Rate (cfs)	Difference in Flow Rate (cfs)	Difference in Flow Rate (cfs)
			Point A1
	-24.15	-41.07	-78.56
	-21.69	-36.89	-70.57
	-35.39	-60.19	-115.13
	-27.20	-46.26	-73.46
	-26.72	-45.45	-72.17
	-41.31	-70.26	-111.57
	-16.19	0.00	-16.19
	-15.53	0.00	-15.53
	-20.97	0.00	-20.97
	-11.03	-39.05	-50.08
	-12.36	-43.75	-56.10
	-24.53	-86.85	-111.37
	-5.81	-31.72	-37.53
	-6.88	-37.61	-44.49
	-12.50	-68.27	-80.77
	0.00	0.00	0.00
	0.00	0.00	0.00
	0.00	0.00	0.00
	0.00	0.00	0.00
	0.00	0.00	0.00
	0.00	0.00	0.00

Discovery Park Macro Stormwater Drainage Study Time of Concentration (Tc) and Travel Time (TT) Macro Study - Fully Developed Conditions 3/31/2023

Subarea:	A1(e)	A1(w)	A2(e)	A2(w)	A3	A4(e)	A4(w)	A5(e)	A5(w)	A6	A7	A8	A9	A10	B1	B2	B3	B4(DT)	B4(BP)	C1	C2	C3
Sheet Flow:																						
_																						
Manning's "n":	0.050	0.060	0.060	0.060	0.013	0.013	0.060	0.013	0.013	0.060	0.060	0.050	0.050	0.050	0.060	0.060	0.050	0.013	0.013	0.013	0.013	0.013
Flow Length, L (ft):	93	100	100	90	74	100	100	45	68	100	100	100	100	100	100	100	100	149	100	140	110	125
Two-Year Rainfall, P2 (in):	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5
Land Slope, S (ft/ft):	0.0428	0.0116	0.0374	0.0079	0.0200	0.1737	0.0365	0.0200	0.0256	0.0374	0.0285	0.0184	0.0219	0.0635	0.0235	0.0157	0.0176	0.0404	0.0396	0.0070	0.0040	0.0110
(0.007(nL)^0.8)																						
(P2^0.5*S^0.4)	0.0451	0.0933	0.0584	0.1000	0.0173	0.0093	0.0590	0.0117	0.0147	0.0584	0.0651	0.0670	0.0625	0.0408	0.0703	0.0826	0.0682	0.0229	0.0168	0.0440	0.0453	0.0335
Shallow Concentrated Flow:																						
Surface Description	PAVED	UNPAVED	UNPAVED	UNPAVED	PAVED	UNPAVED	UNPAVED	PAVED	UNPAVED	UNPAVED	UNPAVED	UNPAVED	UNPAVED	PAVED	UNPAVED	UNPAVED	UNPAVED	PAVED	PAVED	UNPAVED	UNPAVED	PAVED
Flow Length, L (ft)	360	1306	340	1246	0	174	300	0	123	150	873	605	467	1075	508	907	425	972	656	1020	1294	544
Watercourse Slope, S (ft/ft)	0.0375	0.0643	0.0941	0.0626	0.0200	0.1073	0.0779	0.0200	0.1185	0.0765	0.0504	0.0496	0.0600	0.0167	0.0590	0.0640	0.0800	0.0206	0.0210	0.0098	0.0077	0.0220
Average Velocity, V (ft/s)	3.94	4.09	4.95	4.04	2.87	5.29	4.50	2.87	5.55	4.46	3.62	3.59	3.95	2.63	3.92	4.08	4.56	2.92	2.95	1.60	1.42	3.02
L/(3600*V)	0.0254	0.0887	0.0191	0.0857	0.0000	0.0091	0.0185	0.0000	0.0062	0.0093	0.0669	0.0468	0.0328	0.1137	0.0360	0.0617	0.0259	0.0925	0.0619	0.1774	0.2539	0.0501
Channel Flow:																						
Flow Length, L (ft)	1754	1742	252	695	1955	0	1151	1795	1579	592	695	579	1175	0	1158	1368	1275	0	0	1630	1138	1307
Channel Slope, S (ft/ft)	0.0137	0.0138	0.0079	0.0173	0.0339	0.0200	0.0494	0.0313	0.0292	0.0263	0.0167	0.0242	0.0136		0.0294	0.0124	0.0141			0.0061	0.0299	0.0214
Velocity (ft/s) ¹	7.00	7.00	7.00	7.00	10.00	10.00	10.00	10.00	10.00	10.00	7.00	10.00	7.00	7.00	10.00	7.00	7.00	7.00	7.00	7.00	10.00	10.00
T3 (hr):	0.0696	0.0691	0.0100	0.0276	0.0543	0.0000	0.0320	0.0499	0.0439	0.0164	0.0276	0.0161	0.0466	0.0000	0.0322	0.0543	0.0506	0.0000	0.0000	0.0647	0.0316	0.0363
² T _c =T1 + T2 + T3:	0.1401	0.2511	0.0875	0.2133	0.0717	0.0184	0.1095	0.0615	0.0647	0.0842	0.1596	0.1299	0.1420	0.1545	0.1385	0.1987	0.1447	0.1155	0.0787	0.2860	0.3308	0.1199
1 _C =11 + 12 + 13.	0.1401	0.2311	0.0073	0.2133	0.0717	0.0104	0.1093	0.0015	0.0047	0.0042	0.1390	0.1299	0.1420	0.1343	0.1303	0.1307	0.1447	0.1155	0.0767	0.2000	0.5506	0.1199

¹ Note: Where indicated, Channel Flow is approximated by Length & Velocity per APWA 5602.7 B.

Travel Time:

Reach Length, L (ft)
Channel Slope, S (ft/ft)
Velocity (ft/s)⁷
T3 (hr)

A2~A1	A3~A2	A4~A2	A5~A4	A6~A5	A7~A5	A8~A7	A9~A7	A10~A9	B1~A3	B2~B1	C1~B1	B3~B2	B4~B3	C2~C1	C3~C2
2081	485	726	732	470	1038	858	983	1603	835	409	530	2076	1480	1766	534
0.0125	0.0124	0.0165	0.0328	0.0256	0.0077	0.0163	0.0142	0.0187	0.0145	0.0147	0.0151	0.0106	0.0166	0.0102	0.0389
7.00	7.00	7.00	10.00	10.00	7.00	7.00	7.00	7.00	7.00	7.00	7.00	7.00	7.00	7.00	10.00
0.0826	0.0192	0.0288	0.0203	0.0131	0.0412	0.0340	0.0390	0.0636	0.0331	0.0162	0.0210	0.0824	0.0587	0.0701	0.0148

¹ Note: Where indicated, Channel Flow is approximated by Length & Velocity per APWA 5602.7 B and Mannings Eq.

² Note: Time of concentration shall not be below 6 min (0.1000 hrs) per APWA 5602.7 A.

Discovery Park Macro Stormwater Drainage Study Time of Concentration (Tc) and Travel Time (TT) Macro Study - Proposed Conditions 3/31/2023

Subarea:	A1(e)	A1(w)	A2(e)	A2(w)	А3	A4(e)	A4(w)	A5(e)	A5(w)	A6	A7	A8	A9	A10	B1	B2	В3	B4(DT)	B4(BP)	C 1	C2	C3
Sheet Flow:																						
Manning's "n":	0.050	0.060	0.060	0.060	0.013	0.013	0.060	0.030	0.013	0.060	0.060	0.050	0.050	0.050	0.060	0.060	0.050	0.013	0.013	0.013	0.013	0.013
Flow Length, L (ft):	93	100	100	90	74	100	100	100	68	100	100	100	100	100	100	100	100	149	100	140	110	125
Two-Year Rainfall, P2 (in):	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5	3.5
Land Slope, S (ft/ft): (0.007(nL)^0.8)	0.0428	0.0116	0.0374	0.0079	0.0200	0.1737	0.0365	0.0483	0.0256	0.0374	0.0285	0.0184	0.0219	0.0635	0.0235	0.0157	0.0176	0.0404	0.0396	0.0070	0.0040	0.0110
(P2^0.5*S^0.4)	0.0451	0.0933	0.0584	0.1000	0.0173	0.0093	0.0590	0.0303	0.0147	0.0584	0.0651	0.0670	0.0625	0.0408	0.0703	0.0826	0.0682	0.0229	0.0168	0.0440	0.0453	0.0335
Shallow Concentrated Flow:																						
Surface Description	UNPAVED	UNPAVED	UNPAVED	UNPAVED	PAVED	UNPAVED	PAVED	UNPAVED	UNPAVED	UNPAVED	PAVED	PAVED	UNPAVED	UNPAVED	PAVED							
Flow Length, L (ft)	868	1306	340	1246	0	174	300	421	123	150	873	605	467	1075	508	907	425	972	656	1020	1294	544
Watercourse Slope, S (ft/ft)	0.0645	0.0643	0.0941	0.0626	0.0200	0.1073	0.0779	0.0412	0.1185	0.0765	0.0504	0.0496	0.0600	0.0167	0.0590	0.0640	0.0800	0.0206	0.0210	0.0098	0.0077	0.0220
Average Velocity, V (ft/s)	4.10	4.09	4.95	4.04	2.87	5.29	4.50	3.27	5.55	4.46	3.62	3.59	3.95	2.63	3.92	4.08	4.56	2.92	2.95	1.60	1.42	3.02
L/(3600*V)	0.0588	0.0887	0.0191	0.0857	0.0000	0.0091	0.0185	0.0357	0.0062	0.0093	0.0669	0.0468	0.0328	0.1137	0.0360	0.0617	0.0259	0.0925	0.0619	0.1774	0.2539	0.0501
Channel Flow:																						
Flow Length, L (ft)	1754	1742	252	695	1945	0	1151	588	1579	592	695	579	1175	0	1158	1368	1275	0	0	1630	1138	1307
Channel Slope, S (ft/ft)	0.0137	0.0138	0.0079	0.0173	0.0341	0.0200	0.0494	0.0578	0.0292	0.0263	0.0167	0.0242	0.0136		0.0294	0.0124	0.0141			0.0061	0.0299	0.0214
Velocity (ft/s)	7.00	7.00	7.00	7.00	10.00	10.00	10.00	15.00	10.00	10.00	7.00	10.00	7.00	7.00	10.00	7.00	7.00	7.00	7.00	7.00	10.00	10.00
T3 (hr):	0.0696	0.0691	0.0100	0.0276	0.0540	0.0000	0.0320	0.0109	0.0439	0.0164	0.0276	0.0161	0.0466	0.0000	0.0322	0.0543	0.0506	0.0000	0.0000	0.0647	0.0316	0.0363
² T _c =T1 + T2 + T3:	0.1736	0.2511	0.0875	0.2133	0.0714	0.0184	0.1095	0.0769	0.0647	0.0842	0.1596	0.1299	0.1420	0.1545	0.1385	0.1987	0.1447	0.1155	0.0787	0.2860	0.3308	0.1199

Note: Where indicated, Channel Flow is approximated by Length & Velocity per APWA 5602.7 B.

Travel Time:

Reach Length, L (ft)
Channel Slope, S (ft/ft)
Velocity (ft/s)¹
T3 (hr)

A2~A1	A3~A2	A4~A2	A5~A4	A6~A5	A7~A5	A8~A7	A9~A7	A10~A9	B1~A3	B2~B1	C1~B1	B3~B2	B4~B3	C2~C1	C3~C2
2081	485	726	732	470	1038	858	983	1603	835	409	530	2076	1480	1766	534
0.0125	0.0124	0.0165	0.0328	0.0256	0.0077	0.0163	0.0142	0.0187	0.0145	0.0147	0.0151	0.0106	0.0166	0.0102	0.0389
7.00	7.00	7.00	10.00	10.00	7.00	7.00	7.00	7.00	7.00	7.00	7.00	7.00	7.00	7.00	10.00
0.0826	0.0192	0.0288	0.0203	0.0131	0.0412	0.0340	0.0390	0.0636	0.0331	0.0162	0.0210	0.0824	0.0587	0.0701	0.0148

¹ Note: Where indicated, Channel Flow is approximated by Length & Velocity per APWA 5602.7 B and Mannings Eq.

² Note: Time of concentration shall not be below 6 min (0.1000 hrs) per APWA 5602.7 A.




Table of Contents

	Master Network Summary	121
A-1(e)		
A-1(w)	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	1
()	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	3
A-10		
A-2(e)	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	5
n z(c)	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	7
A-2(w)		
A-3	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	9
	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	11
A-4(e)		
A-4(w)	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	13
, (w)	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	15
A-5(e)		
A-5(w)	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	17
()	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	19
A-6		
A-7	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	21
	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	23
A-8		
A-9	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	25
	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	27
B-1		
B-2	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	29
	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	31
B-3		
B-4 (BYP)	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	33
,	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	35

Table of Contents

B-4 (DET)		
	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	37
C-1	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	39
C-2	W. W. L	44
C-3	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	41
D-1	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	43
D-1	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	45
D-2	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	47
D-3	Sile riyarograpii odiiiilariyi 200 yedib (200 ii (ii 10))	.,
D-4	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	49
	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	51
D-5	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	53
E-1	W. W. L	
E-2	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	55
F-1	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	57
F-1	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	59
F-2	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	61
G-1	Chic Trydrograph Sammary, 100 years (100 Tr (Tr 10))	O1
G-2	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	63
	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	65
H-1	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	67
I-1		
D-5	Unit Hydrograph Summary, 100 years (100-Yr (TP-40))	69
	Unit Hydrograph (Hydrograph Table), 2 years (2-Yr (TP-40))	71
Basin B4		

Table of Contents

	Outlet Input Data, 100 years (100-Yr (TP-40))	81
E1 Overflow to D2		
	Outlet Input Data, 100 years (100-Yr (TP-40))	84
Highway Crossing D4		
	Outlet Input Data, 100 years (100-Yr (TP-40))	86
Inlet C2		
	Outlet Input Data, 100 years (100-Yr (TP-40))	89
Pt. A3 Drive Culverts		
D. 455 D. I	Outlet Input Data, 100 years (100-Yr (TP-40))	92
Pt. A5 Former Pond	Outlet Input Data, 100 years (100-Yr (TP-40))	95
RCB Sta,. 25+65	Outlet Input Data, 100 years (100-11 (17-40))	95
NCD 3ta ₁ . 23 103	Outlet Input Data, 100 years (100-Yr (TP-40))	97
RCB Sta. 45+15	04.00 1.104. 24.4, 200 ,04.0 (200 1. (1. 10))	
	Outlet Input Data, 100 years (100-Yr (TP-40))	100
Road Crossing D2		
	Outlet Input Data, 100 years (100-Yr (TP-40))	103
Road Crossing D5		
	Outlet Input Data, 100 years (100-Yr (TP-40))	106
Road Crossing E1		
	Outlet Input Data, 100 years (100-Yr (TP-40))	109
Road Crossing F2		
	Outlet Input Data, 100 years (100-Yr (TP-40))	112
Road Crossing G2		
	Outlet Input Data, 100 years (100-Yr (TP-40))	115
Road Crossing H1		
	Outlet Input Data, 100 years (100-Yr (TP-40))	118

Subsection: Master Network Summary

Catchments Summary

Label	Scenario	Return Event (years)	Hydrograph Volume (ac-ft)	Time to Peak (hours)	Peak Flow (ft³/s)
A-1(e)	2-Yr (TP-40)	2	3.334	12.0100	53.91
A-1(e)	10-Yr (TP-40)	10	6.783	11.9900	110.32
A-1(e)	100-Yr (TP-40)	100	11.675	11.9900	187.82
A-1(w)	2-Yr (TP-40)	2	4.908	12.0500	70.15
A-1(w)	10-Yr (TP-40)	10	10.132	12.0500	146.86
A-1(w)	100-Yr (TP-40)	100	17.597	12.0500	252.55
A-2(e)	2-Yr (TP-40)	2	0.420	11.9400	7.64
A-2(e)	10-Yr (TP-40)	10	0.819	11.9300	14.90
A-2(e)	100-Yr (TP-40)	100	1.374	11.9300	24.63
A-2(w)	2-Yr (TP-40)	2	2.301	12.0300	34.59
A-2(w)	10-Yr (TP-40)	10	4.975	12.0300	76.77
A-2(w)	100-Yr (TP-40)	100	8.884	12.0300	136.28
A-3	2-Yr (TP-40)	2	3.330	11.9600	57.61
A-3	10-Yr (TP-40)	10	6.495	11.9500	112.58
A-3	100-Yr (TP-40)	100	10.895	11.9500	186.13
A-4(e)	2-Yr (TP-40)	2	1.402	11.9600	23.97
A-4(e)	10-Yr (TP-40)	10	2.698	11.9600	45.97
A-4(e)	100-Yr (TP-40)	100	4.488	11.9600	75.15
A-4(w)	2-Yr (TP-40)	2	1.712	12.0100	27.56
A-4(w)	10-Yr (TP-40)	10	3.700	11.9900	60.85
A-4(w)	100-Yr (TP-40)	100	6.607	11.9900	108.22
A-5(e)	2-Yr (TP-40)	2	2.067	11.9500	36.40
A-5(e)	10-Yr (TP-40)	10	4.031	11.9500	70.90
A-5(e)	100-Yr (TP-40)	100	6.762	11.9500	116.98
A-5(w)	2-Yr (TP-40)	2	2.249	12.0000	37.02
A-5(w)	10-Yr (TP-40)	10	4.643	11.9900	77.10
A-5(w)	100-Yr (TP-40)	100	8.064	11.9700	132.61
A-6	2-Yr (TP-40)	2	2.083	11.9300	37.98
A-6	10-Yr (TP-40)	10	3.904	11.9300	70.54
A-6	100-Yr (TP-40)	100	6.389	11.9300	113.19
A-7	2-Yr (TP-40)	2	3.482	12.0000	57.26
A-7	10-Yr (TP-40)	10	7.186	11.9800	119.03
A-7	100-Yr (TP-40)	100	12.481	11.9800	204.90
A-8	2-Yr (TP-40)	2	3.070	11.9600	53.05
A-8	10-Yr (TP-40)	10	5.907	11.9500	101.89
A-8	100-Yr (TP-40)	100	9.826	11.9500	166.82
A-9	2-Yr (TP-40)	2	5.138	11.9700	87.15
A-9	10-Yr (TP-40)	10	9.507	11.9600	158.95
A-9	100-Yr (TP-40)	100	15.435	11.9600	252.78
A-10	2-Yr (TP-40)	2	2.890	11.9700	45.61
A-10	10-Yr (TP-40)	10	4.733	11.9700	72.57
A-10	100-Yr (TP-40)	100	7.128	11.9700	106.86
B-1	2-Yr (TP-40)	2	4.168	11.9700	70.94
B-1	10-Yr (TP-40)	10	8.242	11.9600	140.29
B-1	100-Yr (TP-40)	100	13.944	11.9500	234.20
B-2	2-Yr (TP-40)	2	6.057	12.0300	94.72
B-2	10-Yr (TP-40)	10	12.146	12.0100	190.16

Subsection: Master Network Summary

Catchments Summary

Catchments Sui	mmary				
Label	Scenario	Return Event (years)	Hydrograph Volume (ac-ft)	Time to Peak (hours)	Peak Flow (ft³/s)
B-2	100-Yr (TP-40)	100	20.725	12.0000	320.74
B-3	2-Yr (TP-40)	2	6.302	11.9700	
					106.50
B-3 B-3	10-Yr (TP-40)	10	11.812	11.9600	197.62
	100-Yr (TP-40)	100	19.332	11.9600	317.37
B-4 (BYP)	2-Yr (TP-40)	2	1.753	11.9300	30.29
B-4 (BYP)	10-Yr (TP-40)	10	2.871	11.9200	48.22
B-4 (BYP)	100-Yr (TP-40)	100	4.324	11.9200	71.04
C-1	2-Yr (TP-40)	2	9.223	12.0500	124.83
C-1	10-Yr (TP-40)	10	15.842	12.0500	209.38
C-1	100-Yr (TP-40)	100	24.565	12.0500	317.10
C-2	2-Yr (TP-40)	2	8.134	12.0900	104.44
C-2	10-Yr (TP-40)	10	15.652	12.0800	200.90
C-2	100-Yr (TP-40)	100	26.038	12.0800	329.78
C-3	2-Yr (TP-40)	2	8.110	11.9500	142.61
C-3	10-Yr (TP-40)	10	15.199	11.9400	264.83
C-3	100-Yr (TP-40)	100	24.875	11.9400	425.51
B-4 (DET)	2-Yr (TP-40)	2	5.919	11.9400	99.43
B-4 (DET)	10-Yr (TP-40)	10	9.694	11.9400	158.21
B-4 (DET)	100-Yr (TP-40)	100	14.599	11.9400	232.94
D-5	2-Yr (TP-40)	2	10.458	12.0500	146.13
D-5	10-Yr (TP-40)	10	18.183	12.0500	247.91
D-5	100-Yr (TP-40)	100	28.406	12.0300	377.88
D-4	2-Yr (TP-40)	2	21.246	11.9900	338.74
D-4	10-Yr (TP-40)	10	37.391	11.9900	582.43
D-4	100-Yr (TP-40)	100	58.857	11.9900	894.20
D-3	2-Yr (TP-40)	2	3.185	11.9700	52.46
D-3	10-Yr (TP-40)	10	5.605	11.9700	90.29
D-3	100-Yr (TP-40)	100	8.822	11.9700	138.69
D-2	2-Yr (TP-40)	2	6.134	12.0000	99.28
D-2	10-Yr (TP-40)	10	12.128	12.0000	195.91
D-2	100-Yr (TP-40)	100	20.518	11.9800	326.27
D-1	2-Yr (TP-40)	2	4.400	11.9700	75.69
D-1	10-Yr (TP-40)	10	8.950	11.9500	155.84
D-1	100-Yr (TP-40)	100	15.407	11.9500	265.94
E-2	2-Yr (TP-40)	2	0.645	11.9400	11.34
E-2	10-Yr (TP-40)	10	1.394	11.9400	25.34
E-2	100-Yr (TP-40)	100	2.489	11.9400	45.12
E-1	2-Yr (TP-40)	2	3.080	11.9400	55.42
E-1	10-Yr (TP-40)	10	6.008	11.9400	107.96
E-1	100-Yr (TP-40)	100	10.078	11.9300	178.18
F-1	2-Yr (TP-40)	2	0.935	11.9400	16.88
F-1	10-Yr (TP-40)	10	1.903	11.9300	34.70
F-1	100-Yr (TP-40)	100	3.275	11.9300	59.21
F-2	2-Yr (TP-40)	2	1.816	11.9600	31.60
F-2 F-2	10-Yr (TP-40)	10	3.495	11.9500	60.52
F-2 F-2	10-Yr (TP-40)	100	5.814	11.9500	99.00
G-1	2-Yr (TP-40)	2	1.999	11.9400	36.14
1 9-1	2-11 (1P-40)	4	ן פפפ.ו	11.9400	30.14

Subsection: Master Network Summary

Catchments Summary

Label	Scenario	Return Event (years)	Hydrograph Volume (ac-ft)	Time to Peak (hours)	Peak Flow (ft³/s)
G-1	10-Yr (TP-40)	10	3.846	11.9300	69.23
G-1	100-Yr (TP-40)	100	6.398	11.9300	113.41
G-2	2-Yr (TP-40)	2	1.332	11.9400	23.49
G-2	10-Yr (TP-40)	10	2.433	11.9400	42.32
G-2	100-Yr (TP-40)	100	3.920	11.9400	66.71
H-1	2-Yr (TP-40)	2	7.009	11.9700	119.73
H-1	10-Yr (TP-40)	10	14.056	11.9600	240.97
H-1	100-Yr (TP-40)	100	23.984	11.9500	406.72
I-1	2-Yr (TP-40)	2	0.244	11.9300	4.44
I-1	10-Yr (TP-40)	10	0.441	11.9300	7.87
I-1	100-Yr (TP-40)	100	0.705	11.9300	12.29

Node Summary

Label	Scenario	Return Event (years)	Hydrograph Volume (ac-ft)	Time to Peak (hours)	Peak Flow (ft³/s)
Point A1	2-Yr (TP-40)	2	88.053	12.2500	948.96
Point A1	10-Yr (TP-40)	10	166.969	12.2200	1,784.23
Point A1	100-Yr (TP-40)	100	276.008	12.1900	2,754.84
Point A2	2-Yr (TP-40)	2	79.810	12.1700	909.05
Point A2	10-Yr (TP-40)	10	150.055	12.1500	1,691.73
Point A2	100-Yr (TP-40)	100	246.736	12.1300	2,566.59
Point A3	2-Yr (TP-40)	2	52.997	12.1500	628.64
Point A3	10-Yr (TP-40)	10	97.952	12.1500	1,107.67
Point A3	100-Yr (TP-40)	100	159.297	12.1700	1,595.56
Point A4	2-Yr (TP-40)	2	24.092	12.1500	260.92
Point A4	10-Yr (TP-40)	10	46.309	12.1100	539.49
Point A4	100-Yr (TP-40)	100	77.182	12.0900	906.56
Point A5	2-Yr (TP-40)	2	20.979	12.1500	242.32
Point A5	10-Yr (TP-40)	10	39.911	12.1200	489.66
Point A5	100-Yr (TP-40)	100	66.087	12.1000	799.19
Point A6	2-Yr (TP-40)	2	2.083	11.9300	37.98
Point A6	10-Yr (TP-40)	10	3.904	11.9300	70.54
Point A6	100-Yr (TP-40)	100	6.389	11.9300	113.19
Point A7	2-Yr (TP-40)	2	14.580	12.0500	229.26
Point A7	10-Yr (TP-40)	10	27.333	12.0700	397.23
Point A7	100-Yr (TP-40)	100	44.871	12.0800	603.32
Point A8	2-Yr (TP-40)	2	3.070	11.9600	53.05
Point A8	10-Yr (TP-40)	10	5.907	11.9500	101.89
Point A8	100-Yr (TP-40)	100	9.826	11.9500	166.82
Point A9	2-Yr (TP-40)	2	8.028	12.0000	128.79
Point A9	10-Yr (TP-40)	10	14.240	11.9900	223.48
Point A9	100-Yr (TP-40)	100	22.563	11.9900	346.07
Point A10	2-Yr (TP-40)	2	2.890	11.9700	45.61
Point A10	10-Yr (TP-40)	10	4.733	11.9700	72.57
Point A10	100-Yr (TP-40)	100	7.128	11.9700	106.86
Point B1	2-Yr (TP-40)	2	49.667	12.1100	615.14

Discovery_Park_Ph-1_Macro_Ex-Cond.ppc 1/10/2023

Bentley Systems, Inc. Haestad Methods Solution Center 27 Siemon Company Drive Suite 200 W Watertown, CT 06795 USA +1-203-755-1666 PondPack CONNECT Edition [10.02.00.01] Page 123 of 131

Subsection: Master Network Summary

Node Summary

Noue Summary					
Label	Scenario	Return Event (years)	Hydrograph Volume (ac-ft)	Time to Peak (hours)	Peak Flow (ft³/s)
Point B1	10-Yr (TP-40)	10	91.457	12.1100	1,076.61
Point B1	100-Yr (TP-40)	100	148.401	12.1400	1,551.65
Point B2	2-Yr (TP-40)	2	20.032	12.0500	242.31
Point B2	10-Yr (TP-40)	10	36.522	12.0400	446.43
Point B2	100-Yr (TP-40)	100	58.980	12.0300	715.56
Point B3	2-Yr (TP-40)	2	13.975	11.9900	153.04
Point B3	10-Yr (TP-40)	10	24.377	11.9800	266.04
Point B3	100-Yr (TP-40)	100	38.255	11.9700	411.65
Point B4	2-Yr (TP-40)	2	7.673	11.9400	48.10
Point B4	10-Yr (TP-40)	10	12.565	11.9300	71.04
Point B4	100-Yr (TP-40)	100	18.924	11.9300	98.80
Point C1	2-Yr (TP-40)	2	25.466	12.0900	350.42
Point C1	10-Yr (TP-40)	10	46.692	12.1000	604.01
Point C1	100-Yr (TP-40)	100	75.478	12.1000	890.10
Point C1 Point C2	2-Yr (TP-40)	2	16.244	12.0400	232.89
Point C2 Point C2	10-Yr (TP-40)	10	30.851	12.0700	417.32
Point C2 Point C2	100-Yr (TP-40)	100	50.912	12.0800	614.91
Point C2 Point C3		2	8.110	11.9500	142.61
Point C3	2-Yr (TP-40)	10	15.199	11.9400	264.83
	10-Yr (TP-40)		24.875		
Point C3	100-Yr (TP-40)	100	88.053	11.9400 12.2500	425.51 948.96
Inlet-(U.V. Lake 2) Inlet-(U.V. Lake 2)	2-Yr (TP-40)	10	166.969	12.2200	1,784.23
Inlet-(U.V. Lake 2)	10-Yr (TP-40) 100-Yr (TP-40)	100	276.008	12.1900	•
Inlet-(U.V. Lake 2) Inlet-(U.V. Lake 1)	` '	2	55.229	12.1900	2,754.84
Inlet-(U.V. Lake 1)	2-Yr (TP-40) 10-Yr (TP-40)	10	101.336	12.0500	636.59 1,087.31
Inlet-(U.V. Lake 1)	100-Yr (TP-40)	100	163.983	12.0400	1,592.51
Point D5	2-Yr (TP-40)	2	10.458	12.0700	1,392.31
	, ,	10		12.0800	239.98
Point D5	10-Yr (TP-40) 100-Yr (TP-40)	100	18.183 28.406	12.0900	357.61
Point D5				12.1000	
Point D4	2-Yr (TP-40)	2 10	31.704 55.574		377.63
Point D4 Point D4	10-Yr (TP-40)	100	87.262	12.1400	526.54 638.44
Point D4 Point D3	100-Yr (TP-40) 2-Yr (TP-40)	2		12.1900	52.46
Point D3	10-Yr (TP-40)	10	3.185 5.605	11.9700 11.9700	90.29
Point D3	100-Yr (TP-40)	100	8.822	11.9700	138.69
Point D3 Point D2	2-Yr (TP-40)		41.022	12.1000	485.06
		2			752.83
Point D2	10-Yr (TP-40)	10	73.431	12.0600	
Point D2	100-Yr (TP-40)	100	117.417	12.0600	1,052.38
Point D1	2-Yr (TP-40)	2	49.147	12.0800	560.43
Point D1	10-Yr (TP-40)	10	89.659	12.0700	941.67
Point D1	100-Yr (TP-40)	100	144.576	12.0500	1,351.30
Point E1	2-Yr (TP-40)	2	3.725	11.9500	65.98
Point E1	10-Yr (TP-40)	10	7.278	11.9900	106.88
Point E1	100-Yr (TP-40)	100	11.753	11.9800	143.00
Point E2 Point E2	2-Yr (TP-40)	2	0.645	11.9400 11.9400	11.34
	10-Yr (TP-40) 100-Yr (TP-40)	10	1.394		25.34 45.13
Point E2	100-11 (17-40)	100	2.489	11.9400	45.12

Subsection: Master Network Summary

Node Summary

Label	Scenario	Return Event (years)	Hydrograph Volume (ac-ft)	Time to Peak (hours)	Peak Flow (ft³/s)
Point F2	2-Yr (TP-40)	2	1.816	11.9600	31.56
Point F2	10-Yr (TP-40)	10	3.495	12.0600	45.26
Point F2	100-Yr (TP-40)	100	5.814	12.0700	65.86
Point F1	2-Yr (TP-40)	2	2.752	11.9700	47.57
Point F1	10-Yr (TP-40)	10	5.398	11.9600	74.89
Point F1	100-Yr (TP-40)	100	9.090	11.9400	106.16
Point G2	2-Yr (TP-40)	2	1.332	11.9600	23.29
Point G2	10-Yr (TP-40)	10	2.433	12.0200	36.98
Point G2	100-Yr (TP-40)	100	3.920	11.9900	62.01
Point G1	2-Yr (TP-40)	2	3.331	11.9500	58.32
Point G1	10-Yr (TP-40)	10	6.279	11.9400	102.21
Point G1	100-Yr (TP-40)	100	10.317	11.9700	163.43
Point H1	2-Yr (TP-40)	2	7.009	11.9700	119.54
Point H1	10-Yr (TP-40)	10	14.056	11.9600	240.90
Point H1	100-Yr (TP-40)	100	23.984	11.9600	406.43
MAIN ST CULVERT H	2-Yr (TP-40)	2	7.009	11.9700	119.53
MAIN ST CULVERT H	10-Yr (TP-40)	10	14.056	11.9600	240.92
MAIN ST CULVERT H	100-Yr (TP-40)	100	23.984	11.9600	406.43
MAIN ST CULVERT I	2-Yr (TP-40)	2	0.244	11.9400	4.43
MAIN ST CULVERT I	10-Yr (TP-40)	10	0.447	11.8800	8.41
MAIN ST CULVERT I	100-Yr (TP-40)	100	0.710	11.8100	8.41
Point I1	2-Yr (TP-40)	2	0.244	11.9300	4.44
Point I1	10-Yr (TP-40)	10	0.441	11.9300	7.87
Point I1	100-Yr (TP-40)	100	0.705	11.9300	12.29

Label	Scenario	Return Event (years)	Hydrograph Volume (ac-ft)	Time to Peak (hours)	Peak Flow (ft³/s)	Maximum Water Surface Elevation (ft)	Maximum Pond Storage (ac-ft)
RCB 25+65 (IN)	2-Yr (TP-40)	2	14.580	12.0200	236.01	(N/A)	(N/A)
RCB 25+65 (OUT)	2-Yr (TP-40)	2	14.580	12.0500	229.26	948.7083	0.319
RCB 25+65 (IN)	10-Yr (TP-40)	10	27.333	12.0100	437.94	(N/A)	(N/A)
RCB 25+65 (OUT)	10-Yr (TP-40)	10	27.333	12.0700	397.23	950.2162	1.251
RCB 25+65 (IN)	100-Yr (TP-40)	100	44.871	12.0000	707.16	(N/A)	(N/A)
RCB 25+65 (OUT)	100-Yr (TP-40)	100	44.871	12.0800	603.32	951.7960	3.100
RCB 45+15 (IN)	2-Yr (TP-40)	2	49.667	12.0700	634.00	(N/A)	(N/A)
RCB 45+15 (OUT)	2-Yr (TP-40)	2	49.667	12.1100	615.14	921.5701	1.519

Subsection: Master Network Summary

rona Sanni	ı y						
Label	Scenario	Return Event (years)	Hydrograph Volume (ac-ft)	Time to Peak (hours)	Peak Flow (ft³/s)	Maximum Water Surface Elevation (ft)	Maximum Pond Storage (ac-ft)
RCB 45+15 (IN)	10-Yr (TP-40)	10	91.457	12.0700	1,121.63	(N/A)	(N/A)
RCB 45+15 (OUT)	10-Yr (TP-40)	10	91.457	12.1100	1,076.61	923.9927	3.164
RCB 45+15 (IN)	100-Yr (TP-40)	100	148.401	12.0600	1,726.54	(N/A)	(N/A)
RCB 45+15 (OUT)	100-Yr (TP-40)	100	148.401	12.1400	1,551.65	926.7702	6.626
Inlet Storage C2 (IN)	2-Yr (TP-40)	2	8.110	11.9600	142.28	(N/A)	(N/A)
Inlet Storage C2 (OUT)	2-Yr (TP-40)	2	8.110	12.0000	137.26	957.9495	0.115
Inlet Storage C2 (IN)	10-Yr (TP-40)	10	15.199	11.9600	264.20	(N/A)	(N/A)
Inlet Storage C2 (OUT)	10-Yr (TP-40)	10	15.199	12.0500	219.81	959.6693	0.804
Inlet Storage C2 (IN)	100-Yr (TP-40)	100	24.875	11.9600	423.95	(N/A)	(N/A)
Inlet Storage C2 (OUT)	100-Yr (TP-40)	100	24.875	12.0700	285.13	961.5938	2.539
Sub-B4 Basin (IN)	2-Yr (TP-40)	2	5.919	11.9400	99.43	(N/A)	(N/A)
Sub-B4 Basin (OUT)	2-Yr (TP-40)	2	5.919	12.1600	22.46	993.2524	2.284
Sub-B4 Basin (IN)	10-Yr (TP-40)	10	9.694	11.9400	158.21	(N/A)	(N/A)
Sub-B4 Basin (OUT)	10-Yr (TP-40)	10	9.694	12.1900	28.68	994.0428	3.850
Sub-B4 Basin (IN)	100-Yr (TP-40)	100	14.599	11.9400	232.94	(N/A)	(N/A)
Sub-B4 Basin (OUT)	100-Yr (TP-40)	100	14.599	12.2400	34.97	995.0349	5.948
Pt. A3 - Drive- Culverts (IN)	2-Yr (TP-40)	2	52.997	12.1300	632.94	(N/A)	(N/A)
Pt. A3 - Drive- Culverts (OUT)	2-Yr (TP-40)	2	52.997	12.1500	628.64	908.5044	1.747
Pt. A3 - Drive- Culverts (IN)	10-Yr (TP-40)	10	97.952	12.1300	1,109.82	(N/A)	(N/A)
Pt. A3 - Drive- Culverts (OUT)	10-Yr (TP-40)	10	97.952	12.1500	1,107.67	909.0685	2.341
Pt. A3 - Drive- Culverts (IN)	100-Yr (TP-40)	100	159.297	12.1600	1,597.02	(N/A)	(N/A)

Subsection: Master Network Summary

rona Sanni	•						
Label	Scenario	Return Event (years)	Hydrograph Volume (ac-ft)	Time to Peak (hours)	Peak Flow (ft³/s)	Maximum Water Surface Elevation (ft)	Maximum Pond Storage (ac-ft)
Pt. A3 - Drive- Culverts (OUT)	100-Yr (TP-40)	100	159.297	12.1700	1,595.56	909.5023	2.849
Pt. A5 - Former Pond (IN)	2-Yr (TP-40)	2	20.979	12.0500	315.36	(N/A)	(N/A)
Pt. A5 - Former Pond (OUT)	2-Yr (TP-40)	2	20.979	12.1500	242.32	932.4766	3.940
Pt. A5 - Former Pond (IN)	10-Yr (TP-40)	10	39.911	12.0500	552.78	(N/A)	(N/A)
Pt. A5 - Former Pond (OUT)	10-Yr (TP-40)	10	39.911	12.1200	489.66	933.4288	5.828
Pt. A5 - Former Pond (IN)	100-Yr (TP-40)	100	66.087	12.0500	847.10	(N/A)	(N/A)
Pt. A5 - Former Pond (OUT)	100-Yr (TP-40)	100	66.087	12.1000	799.19	934.1476	7.413
H1 Road Culvert (IN)	2-Yr (TP-40)	2	7.009	11.9700	119.73	(N/A)	(N/A)
H1 Road Culvert (OUT)	2-Yr (TP-40)	2	7.009	11.9700	119.54	912.4382	0.060
H1 Road Culvert (IN)	10-Yr (TP-40)	10	14.056	11.9600	240.97	(N/A)	(N/A)
H1 Road Culvert (OUT)	10-Yr (TP-40)	10	14.056	11.9600	240.90	912.7758	0.103
H1 Road Culvert (IN)	100-Yr (TP-40)	100	23.984	11.9500	406.72	(N/A)	(N/A)
H1 Road Culvert (OUT)	100-Yr (TP-40)	100	23.984	11.9600	406.43	912.9683	0.138
G2 Road Culvert (IN)	2-Yr (TP-40)	2	1.332	11.9400	23.49	(N/A)	(N/A)
G2 Road Culvert (OUT)	2-Yr (TP-40)	2	1.332	11.9600	23.29	947.0866	0.010
G2 Road Culvert (IN)	10-Yr (TP-40)	10	2.433	11.9400	42.32	(N/A)	(N/A)
G2 Road Culvert (OUT)	10-Yr (TP-40)	10	2.433	12.0200	36.98	948.5853	0.077
G2 Road Culvert (IN)	100-Yr (TP-40)	100	3.920	11.9400	66.71	(N/A)	(N/A)

Subsection: Master Network Summary

Label	Scenario	Return	Hydrograph	Time to Peak	Peak Flow	Maximum	Maximum
		Event (years)	Volume (ac-ft)	(hours)	(ft³/s)	Water Surface Elevation (ft)	Pond Storage (ac-ft)
G2 Road Culvert (OUT)	100-Yr (TP-40)	100	3.920	11.9900	62.01	949.3764	0.184
D2 Road Culvert (IN)	2-Yr (TP-40)	2	6.134	12.0000	99.28	(N/A)	(N/A)
D2 Road Culvert (OUT)	2-Yr (TP-40)	2	6.134	12.0200	98.92	928.3513	0.060
D2 Road Culvert (IN)	10-Yr (TP-40)	10	12.128	12.0000	195.91	(N/A)	(N/A)
D2 Road Culvert (OUT)	10-Yr (TP-40)	10	12.128	12.0100	194.04	929.6699	0.173
D2 Road Culvert (IN)	100-Yr (TP-40)	100	20.518	11.9800	326.27	(N/A)	(N/A)
D2 Road Culvert (OUT)	100-Yr (TP-40)	100	20.518	12.0300	315.15	931.0563	0.479
F1 Road Culvert (IN)	2-Yr (TP-40)	2	1.816	11.9600	31.60	(N/A)	(N/A)
F1 Road Culvert (OUT)	2-Yr (TP-40)	2	1.816	11.9600	31.56	943.9776	0.012
F1 Road Culvert (IN)	10-Yr (TP-40)	10	3.495	11.9500	60.52	(N/A)	(N/A)
F1 Road Culvert (OUT)	10-Yr (TP-40)	10	3.495	12.0600	45.26	946.0560	0.227
F1 Road Culvert (IN)	100-Yr (TP-40)	100	5.814	11.9500	99.00	(N/A)	(N/A)
F1 Road Culvert (OUT)	100-Yr (TP-40)	100	5.814	12.0700	65.86	947.6705	0.736
D4 Highway Culvert (IN)	2-Yr (TP-40)	2	31.704	12.0200	447.33	(N/A)	(N/A)
D4 Highway Culvert (OUT)	2-Yr (TP-40)	2	31.704	12.1000	377.63	958.5690	2.269
D4 Highway Culvert (IN)	10-Yr (TP-40)	10	55.574	12.0200	761.81	(N/A)	(N/A)
D4 Highway Culvert (OUT)	10-Yr (TP-40)	10	55.574	12.1400	526.54	960.9142	6.129
D4 Highway Culvert (IN)	100-Yr (TP-40)	100	87.262	12.0200	1,157.85	(N/A)	(N/A)
D4 Highway Culvert (OUT)	100-Yr (TP-40)	100	87.262	12.1900	638.44	963.4942	13.467

Subsection: Master Network Summary

	,						
Label	Scenario	Return Event (years)	Hydrograph Volume (ac-ft)	Time to Peak (hours)	Peak Flow (ft³/s)	Maximum Water Surface Elevation (ft)	Maximum Pond Storage (ac-ft)
E1 Road Culvert (IN)	2-Yr (TP-40)	2	3.080	11.9400	55.42	(N/A)	(N/A)
E1 Road Culvert (OUT)	2-Yr (TP-40)	2	3.080	11.9500	55.34	930.6110	0.020
E1 Road Culvert (IN)	10-Yr (TP-40)	10	6.008	11.9400	107.96	(N/A)	(N/A)
E1 Road Culvert (OUT)	10-Yr (TP-40)	10	6.008	12.0200	92.57	931.6780	0.256
E1 Road Culvert (IN)	100-Yr (TP-40)	100	10.078	11.9300	178.18	(N/A)	(N/A)
E1 Road Culvert (OUT)	100-Yr (TP-40)	100	10.078	12.0200	148.28	932.2909	0.722
D5 Road Culvert (IN)	2-Yr (TP-40)	2	10.458	12.0500	146.13	(N/A)	(N/A)
D5 Road Culvert (OUT)	2-Yr (TP-40)	2	10.458	12.0700	142.73	978.6959	0.301
D5 Road Culvert (IN)	10-Yr (TP-40)	10	18.183	12.0500	247.91	(N/A)	(N/A)
D5 Road Culvert (OUT)	10-Yr (TP-40)	10	18.183	12.0800	239.98	980.6424	0.610
D5 Road Culvert (IN)	100-Yr (TP-40)	100	28.406	12.0300	377.88	(N/A)	(N/A)
D5 Road Culvert (OUT)	100-Yr (TP-40)	100	28.406	12.0900	357.61	982.6928	1.126

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-1(e) Storm Event: 100-Yr (TP-40)

Storm Event	100-Yr (TP-40)
Return Event	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration	0.1736 hours
(Composite)	1 210 272 200 82
Area (User Defined)	1,218,373.200 ft²
Computational Time Increment	0.0231 hours
Time to Peak (Computed)	11.9900 hours
Flow (Peak, Computed)	187.83 ft ³ /s
Output Increment	0.0100 hours
Time to Flow (Peak Interpolated Output)	11.9900 hours
Flow (Peak Interpolated Output)	187.82 ft³/s
Drainage Area	
SCS CN (Composite)	77.000
Area (User Defined)	1,218,373.200 ft ²
Maximum Retention (Pervious)	2.99 in
Maximum Retention (Pervious, 20 percent)	0.60 in
0 1 11 5 15	
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	5.01 in
Runoff Volume (Pervious)	11.675 ac-ft
Hydrograph Volume (Area ur	nder Hydrograph curve)
Volume	11.675 ac-ft
SCS Unit Hydrograph Param	eters
Time of Concentration (Composite)	0.1736 hours
Computational Time Increment	0.0231 hours
Unit Hydrograph Shape Factor	483.432
K Factor	0.749
Receding/Rising, Tr/Tp	1.670
Unit peak, qp	182.55 ft ³ /s
Unit peak time, Tp	0.1157 hours
Unit receding limb, Tr	0.4629 hours
Total unit time, Tb	0.5787 hours
B # 5 :	

Subsection: Unit Hydrograph Summary

Return Event: 100 years

Label: A-1(e)

Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-1(w) Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

100-Yr (TP-40)
100 years
72.0000 hours
7.71 in
0.2511 hours
1,879,178.401 ft²
0.0335 hours
12.0528 hours
252.68 ft ³ /s
0.0100 hours
12.0500 hours
252.55 ft³/s
76.000
1,879,178.401 ft²
3.16 in
0.63 in
4.89 in
17.597 ac-ft
r Hydrograph curve)
i Hydrograph curve)
17.597 ac-ft
17.597 ac-ft ers 0.2511 hours
17.597 ac-ft ers 0.2511 hours 0.0335 hours
17.597 ac-ft ers 0.2511 hours 0.0335 hours 483.432
17.597 ac-ft ers 0.2511 hours 0.0335 hours 483.432 0.749
17.597 ac-ft 0.2511 hours 0.0335 hours 483.432 0.749 1.670
17.597 ac-ft 0.2511 hours 0.0335 hours 483.432 0.749 1.670 194.66 ft ³ /s

Bentley Systems, Inc. Haestad Methods Solution Center 27 Siemon Company Drive Suite 200 W Watertown, CT 06795 USA +1-203-755-1666

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-1(w) Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-10 Storm Event: 100-Yr (TP-40)

`	
Storm Event	100-Yr (TP-40)
Return Event	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration (Composite)	0.1545 hours
Area (User Defined)	532,738.800 ft²
Computational Time Increment	0.0206 hours
Time to Peak (Computed)	11.9686 hours
Flow (Peak, Computed)	106.99 ft ³ /s
Output Increment	0.0100 hours
Time to Flow (Peak Interpolated Output)	11.9700 hours
Flow (Peak Interpolated Output)	106.86 ft ³ /s
Drainage Area	
SCS CN (Composite)	94.000
Area (User Defined)	532,738.800 ft ²
Maximum Retention (Pervious)	0.64 in
Maximum Retention (Pervious, 20 percent)	0.13 in
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	6.99 in
Runoff Volume (Pervious)	7.128 ac-ft
Hydrograph Volume (Area ur	 nder Hydrograph curve)
Volume	7.128 ac-ft
SCS Unit Hydrograph Param	neters
Time of Concentration (Composite)	0.1545 hours
Computational Time Increment	0.0206 hours
Unit Hydrograph Shape Factor	483.432
K Factor	0.749
Receding/Rising, Tr/Tp	1.670
Unit peak, qp	89.69 ft ³ /s
Unit peak time, Tp	0.1030 hours
Unit receding limb, Tr	0.4120 hours
Total unit time, Tb	0.5150 hours
5 " 6 "	

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-10 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-2(e) Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Storm Event	100-Yr (TP-40)
Return Event	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration (Composite)	0.1000 hours
Area (User Defined)	134,164.800 ft ²
Computational Time Increment	0.0133 hours
Time to Peak (Computed)	11.9333 hours
Flow (Peak, Computed)	24.66 ft ³ /s
Output Increment	0.0100 hours
Time to Flow (Peak Interpolated Output)	11.9300 hours
Flow (Peak Interpolated Output)	24.63 ft³/s
Drainage Area	
SCS CN (Composite)	80.000
Area (User Defined)	134,164.800 ft ²
Maximum Retention (Pervious)	2.50 in
Maximum Retention (Pervious, 20 percent)	0.50 in
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	5.35 in
Runoff Volume (Pervious)	1.374 ac-ft
Hydrograph Volume (Area ur	nder Hydrograph curve)
Volume	1.374 ac-ft
SCS Unit Hydrograph Param	neters
Time of Concentration (Composite)	0.1000 hours
Computational Time Increment	0.0133 hours
Unit Hydrograph Shape Factor	483.432
K Factor	0.749
Receding/Rising, Tr/Tp	1.670
Unit peak, qp	34.90 ft ³ /s
Unit peak time, Tp	0.0667 hours
Unit receding limb, Tr	0.2667 hours
Total unit time, Tb	0.3333 hours
Rontley System	es Inc. Hacetad Mothods

Bentley Systems, Inc. Haestad Methods Solution Center 27 Siemon Company Drive Suite 200 W Watertown, CT 06795 USA +1-203-755-1666

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-2(e) Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-2(w) Storm Event: 100-Yr (TP-40)

`	
Storm Event	100-Yr (TP-40)
Return Event	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration	0.2133 hours
(Composite)	
Area (User Defined)	1,019,739.600 ft²
Computational Time Increment	0.0284 hours
Time to Peak (Computed)	12.0301 hours
Flow (Peak, Computed)	136.29 ft ³ /s
Output Increment	0.0100 hours
Time to Flow (Peak Interpolated Output)	12.0300 hours
Flow (Peak Interpolated Output)	136.28 ft³/s
Drainage Area	
SCS CN (Composite)	73.000
Area (User Defined)	1,019,739.600 ft ²
Maximum Retention (Pervious)	3.70 in
Maximum Retention (Pervious, 20 percent)	0.74 in
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	4.55 in
Runoff Volume (Pervious)	8.884 ac-ft
Hydrograph Volume (Area un	der Hydrograph curve)
Volume	8.884 ac-ft
SCS Unit Hydrograph Param	eters
Time of Concentration	0.2133 hours
(Composite)	0.2133 HUUIS
Computational Time Increment	0.0284 hours
Unit Hydrograph Shape Factor	483.432
K Factor	0.749
Receding/Rising, Tr/Tp	1.670
Unit peak, qp	124.35 ft ³ /s
Unit peak time, Tp	0.1422 hours
Unit receding limb, Tr	0.5688 hours
Total unit time, Tb	0.7110 hours
5 " 6 :	

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-2(w) Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-3 Storm Event: 100-Yr (TP-40)

Storm Event	100-Yr (TP-40)
Return Event	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration	0.1284 hours
(Composite) Area (User Defined)	1,063,798.710 ft²
	, ,
Computational Time	0.0171 hours
Increment Time to Book (Computed)	11 0400 hours
Time to Peak (Computed)	11.9498 hours
Flow (Peak, Computed)	186.17 ft ³ /s
Output Increment	0.0100 hours
Time to Flow (Peak Interpolated Output)	11.9500 hours
Flow (Peak Interpolated Output)	186.13 ft³/s
Drainage Area	
SCS CN (Composite)	80.000
Area (User Defined)	1,063,798.710 ft ²
Maximum Retention (Pervious)	2.50 in
Maximum Retention	0.50 in
(Pervious, 20 percent)	0.50
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	5.35 in
Runoff Volume (Pervious)	10.895 ac-ft
Hydrograph Volume (Area ur	nder Hydrograph curve)
Volume	10.895 ac-ft
SCS Unit Hydrograph Param	otore
Time of Concentration (Composite)	0.1284 hours
Computational Time Increment	0.0171 hours
Unit Hydrograph Shape Factor	483.432
K Factor	0.749
Receding/Rising, Tr/Tp	1.670
Unit peak, qp	215.50 ft ³ /s
Unit peak time, Tp	0.0856 hours
Unit receding limb, Tr	0.3424 hours
Total unit time, Tb	0.4280 hours
, <u> </u>	

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-3 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-4(e) Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Storm Event	100-Yr (TP-40)
Return Event	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration	0.1367 hours
(Composite) Area (User Defined)	428,925.950 ft²
Area (Oser Defined)	720,723.730 TC
Computational Time	
Increment	0.0182 hours
Time to Peak (Computed)	11.9567 hours
Flow (Peak, Computed)	75.35 ft ³ /s
Output Increment	0.0100 hours
Time to Flow (Peak Interpolated Output)	11.9600 hours
Flow (Peak Interpolated Output)	75.15 ft³/s
Drainage Area	
SCS CN (Composite)	81.000
Area (User Defined)	428,925.950 ft ²
Maximum Retention (Pervious)	2.35 in
Maximum Retention (Pervious, 20 percent)	0.47 in
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	5.47 in
Runoff Volume (Pervious)	4.488 ac-ft
Hydrograph Volume (Area ui	nder Hydrograph curve)
Volume	4.488 ac-ft
SCS Unit Hydrograph Param	neters
Time of Concentration (Composite)	0.1367 hours
Computational Time Increment	0.0182 hours
Unit Hydrograph Shape Factor	483.432
K Factor	0.749
Receding/Rising, Tr/Tp	1.670
Unit peak, qp	81.62 ft ³ /s
Unit peak time, Tp	0.0911 hours
Unit receding limb, Tr	0.3645 hours
Total unit time, Tb	0.4557 hours
Pontloy Cyston	as Inc. Haastad Mathads

Bentley Systems, Inc. Haestad Methods Solution Center 27 Siemon Company Drive Suite 200 W Watertown, CT 06795 USA +1-203-755-1666

Subsection: Unit Hydrograph Summary

Return Event: 100 years

Label: A-4(e)

Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-4(w) Storm Event: 100-Yr (TP-40)

`		
Storm Event	100-Yr (TP-40)	
Return Event	100 years	
Duration	72.0000 hours	
Depth	7.71 in	
Time of Concentration	0.1656 hours	
(Composite)	0.2000	
Area (User Defined)	758,410.700 ft²	
Computational Time Increment	0.0221 hours	
Time to Peak (Computed)	11.9894 hours	
Flow (Peak, Computed)	108.26 ft ³ /s	
Output Increment	0.0100 hours	
Time to Flow (Peak Interpolated Output)	11.9900 hours	
Flow (Peak Interpolated Output)	108.22 ft³/s	
Drainage Area		
SCS CN (Composite)	73.000	
Area (User Defined)	758,410.700 ft ²	
Maximum Retention (Pervious)	3.70 in	
Maximum Retention (Pervious, 20 percent)	0.74 in	
Cumulative Runoff		
Cumulative Runoff Depth (Pervious)	4.55 in	
Runoff Volume (Pervious)	6.607 ac-ft	
Hydrograph Volume (Area under Hydrograph curve)		
Volume	6.607 ac-ft	
SCS Unit Hydrograph Param	neters	
Time of Concentration (Composite)	0.1656 hours	
Computational Time Increment	0.0221 hours	
Unit Hydrograph Shape Factor	483.432	
K Factor	0.749	
Receding/Rising, Tr/Tp	1.670	
Unit peak, qp	119.12 ft ³ /s	
Unit peak time, Tp	0.1104 hours	
Unit receding limb, Tr	0.4416 hours	
Total unit time, Tb	0.5520 hours	
B # 5 :		

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-4(w) Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Subsection: Unit Hydrograph Summary

Return Event: 100 years

Label: A-5(e)

Storm Event: 100-Yr (TP-40)

Storm Event	100-Yr (TP-40)
Return Event	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration (Composite)	0.1195 hours
Area (User Defined)	660,258.090 ft ²
Computational Time Increment	0.0159 hours
Time to Peak (Computed)	11.9500 hours
Flow (Peak, Computed)	116.98 ft ³ /s
Output Increment	0.0100 hours
Time to Flow (Peak Interpolated Output)	11.9500 hours
Flow (Peak Interpolated Output)	116.98 ft³/s
Drainage Area	
SCS CN (Composite)	80.000
Area (User Defined)	660,258.090 ft ²
Maximum Retention (Pervious)	2.50 in
Maximum Retention (Pervious, 20 percent)	0.50 in
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	5.35 in
Runoff Volume (Pervious)	6.762 ac-ft
Hydrograph Volume (Area u	nder Hydrograph curve)
Volume	6.762 ac-ft
SCS Unit Hydrograph Paran	 neters
Time of Concentration (Composite)	0.1195 hours
Computational Time Increment	0.0159 hours
Unit Hydrograph Shape Factor	483.432
K Factor	0.749
Receding/Rising, Tr/Tp	1.670
Unit peak, qp	143.72 ft ³ /s
Unit peak time, Tp	0.0797 hours
Unit receding limb, Tr	0.3187 hours
Total unit time, Tb	0.3983 hours
Pontlan Custon	ns Inc. Haastad Mothods

Subsection: Unit Hydrograph Summary

Return Event: 100 years

Label: A-5(e)

Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-5(w) Storm Event: 100-Yr (TP-40)

Storm Event	100-Yr (TP-40)
Return Event	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration	0.1578 hours
(Composite)	0.20.0
Area (User Defined)	861,206.550 ft ²
Computational Time Increment	0.0210 hours
Time to Peak (Computed)	11.9718 hours
Flow (Peak, Computed)	132.83 ft³/s
Output Increment	0.0100 hours
Time to Flow (Peak Interpolated Output)	11.9700 hours
Flow (Peak Interpolated Output)	132.61 ft³/s
Drainage Area	
SCS CN (Composite)	76.000
Area (User Defined)	861,206.550 ft ²
Maximum Retention (Pervious)	3.16 in
Maximum Retention (Pervious, 20 percent)	0.63 in
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	4.89 in
Runoff Volume (Pervious)	8.064 ac-ft
Hydrograph Volume (Area ur	nder Hydrograph curve)
Volume	8.064 ac-ft
SCS Unit Hydrograph Param	neters
Time of Concentration (Composite)	0.1578 hours
Computational Time Increment	0.0210 hours
Unit Hydrograph Shape Factor	483.432
K Factor	0.749
Receding/Rising, Tr/Tp	1.670
Unit peak, qp	141.96 ft ³ /s
Unit peak time, Tp	0.1052 hours
Unit receding limb, Tr	0.4208 hours
Total unit time, Tb	0.5260 hours
B # 5 :	

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-5(w) Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-6 Storm Event: 100-Yr (TP-40)

`		
Storm Event	100-Yr (TP-40)	
Return Event	100 years	
Duration	72.0000 hours	
Depth	7.71 in	
Time of Concentration	0.1000 hours	
(Composite)		
Area (User Defined)	585,818.130 ft ²	
Computational Time Increment	0.0133 hours	
Time to Peak (Computed)	11.9333 hours	
Flow (Peak, Computed)	113.28 ft ³ /s	
Output Increment	0.0100 hours	
Time to Flow (Peak Interpolated Output)	11.9300 hours	
Flow (Peak Interpolated Output)	113.19 ft³/s	
Drainage Area		
SCS CN (Composite)	83.000	
Area (User Defined)	585,818.130 ft ²	
Maximum Retention (Pervious)	2.05 in	
Maximum Retention (Pervious, 20 percent)	0.41 in	
Cumulative Runoff		
Cumulative Runoff Depth (Pervious)	5.70 in	
Runoff Volume (Pervious)	6.389 ac-ft	
Hydrograph Volume (Area under Hydrograph curve)		
Volume	6.389 ac-ft	
SCS Unit Hydrograph Param	neters	
Time of Concentration (Composite)	0.1000 hours	
Computational Time Increment	0.0133 hours	
Unit Hydrograph Shape Factor	483.432	
K Factor	0.749	
Receding/Rising, Tr/Tp	1.670	
Unit peak, qp	152.38 ft ³ /s	
Unit peak time, Tp	0.0667 hours	
Unit receding limb, Tr	0.2667 hours	
Total unit time, Tb	0.3333 hours	

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-6 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Subsection: Unit Hydrograph Summary Return Event: 100 years

Label: A-7 Storm Event: 100-Yr (TP-40)

`	
Storm Event	100-Yr (TP-40)
Return Event	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration	0.1596 hours
(Composite) Area (User Defined)	1,332,936.000 ft²
7//cd (OSCI Delined)	1,332,330.000 10
Computational Time	
Increment	0.0213 hours
Time to Peak (Computed)	11.9806 hours
Flow (Peak, Computed)	204.96 ft ³ /s
Output Increment	0.0100 hours
Time to Flow (Peak Interpolated Output)	11.9800 hours
Flow (Peak Interpolated Output)	204.90 ft ³ /s
Drainage Area	
SCS CN (Composite)	76,000
Area (User Defined)	1,332,936.000 ft²
Maximum Retention (Pervious)	3.16 in
Maximum Retention (Pervious, 20 percent)	0.63 in
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	4.89 in
Runoff Volume (Pervious)	12.482 ac-ft
Hydrograph Volume (Area un	nder Hydrograph curve)
Volume	12.481 ac-ft
SCS Unit Hydrograph Param	eters
Time of Concentration (Composite)	0.1596 hours
Computational Time Increment	0.0213 hours
Unit Hydrograph Shape Factor	483.432
K Factor	0.749
Receding/Rising, Tr/Tp	1.670
Unit peak, qp	217.24 ft ³ /s
Unit peak time, Tp	0.1064 hours
Unit receding limb, Tr	0.4256 hours
Total unit time, Tb	0.5320 hours
5 " 5 "	

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-7 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-8 Storm Event: 100-Yr (TP-40)

`		
Storm Event	100-Yr (TP-40)	
Return Event	100 years	
Duration	72.0000 hours	
Depth	7.71 in	
Time of Concentration	0.1299 hours	
(Composite)	000 450 600 60	
Area (User Defined)	939,153.600 ft²	
Computational Time Increment	0.0173 hours	
Time to Peak (Computed)	11.9508 hours	
Flow (Peak, Computed)	166.91 ft³/s	
Output Increment	0.0100 hours	
Time to Flow (Peak Interpolated Output)	11.9500 hours	
Flow (Peak Interpolated Output)	166.82 ft³/s	
Drainage Area		
SCS CN (Composite)	81.000	
Area (User Defined)	939,153.600 ft ²	
Maximum Retention (Pervious)	2.35 in	
Maximum Retention (Pervious, 20 percent)	0.47 in	
Cumulative Runoff		
Cumulative Runoff Depth (Pervious)	5.47 in	
Runoff Volume (Pervious)	9.826 ac-ft	
Hydrograph Volume (Area under Hydrograph curve)		
Volume	9.826 ac-ft	
SCS Unit Hydrograph Param	neters	
Time of Concentration (Composite)	0.1299 hours	
Computational Time Increment	0.0173 hours	
Unit Hydrograph Shape Factor	483.432	
K Factor	0.749	
Receding/Rising, Tr/Tp	1.670	
Unit peak, qp	188.06 ft ³ /s	
Unit peak time, Tp	0.0866 hours	
Unit receding limb, Tr	0.3464 hours	
Total unit time, Tb	0.4330 hours	

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-8 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-9 Storm Event: 100-Yr (TP-40)

` <u> </u>	
Storm Event	100-Yr (TP-40)
Return Event	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration	0.1420 hours
(Composite)	3.2.2.
Area (User Defined)	1,386,950.400 ft²
Computational Time Increment	0.0189 hours
Time to Peak (Computed)	11.9659 hours
Flow (Peak, Computed)	252.90 ft ³ /s
Output Increment	0.0100 hours
Time to Flow (Peak Interpolated Output)	11.9600 hours
Flow (Peak Interpolated Output)	252.78 ft³/s
Drainage Area	
SCS CN (Composite)	84.000
Area (User Defined)	1,386,950.400 ft ²
Maximum Retention (Pervious)	1.90 in
Maximum Retention (Pervious, 20 percent)	0.38 in
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	5.82 in
Runoff Volume (Pervious)	15.435 ac-ft
Hydrograph Volume (Area under Hydrograph curve)	
Volume	15.435 ac-ft
SCS Unit Hydrograph Parameters	
Time of Concentration (Composite)	0.1420 hours
Computational Time Increment	0.0189 hours
Unit Hydrograph Shape Factor	483.432
K Factor	0.749
Receding/Rising, Tr/Tp	1.670
Unit peak, qp	254.06 ft ³ /s
Unit peak time, Tp	0.0947 hours
Unit receding limb, Tr	0.3787 hours
Total unit time, Tb	0.4733 hours
5 " 6 :	

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-9 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: B-1 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Storm Event	100-Yr (TP-40)	
Return Event	100 years	
Duration	72.0000 hours	
Depth	7.71 in	
Time of Concentration	0.1385 hours	
(Composite)	1 201 206 400 #3	
Area (User Defined)	1,391,306.400 ft²	
Computational Time Increment	0.0185 hours	
Time to Peak (Computed)	11.9479 hours	
Flow (Peak, Computed)	234.20 ft ³ /s	
Output Increment	0.0100 hours	
Time to Flow (Peak Interpolated Output)	11.9500 hours	
Flow (Peak Interpolated Output)	234.20 ft³/s	
Drainage Area		
SCS CN (Composite)	79.000	
Area (User Defined)	1,391,306.400 ft ²	
Maximum Retention		
(Pervious)	2.66 in	
Maximum Retention (Pervious, 20 percent)	0.53 in	
Cumulative Runoff		
Cumulative Runoff Depth	F 24 in	
(Pervious)	5.24 in	
Runoff Volume (Pervious)	13.943 ac-ft	
Hydrograph Volume (Area under Hydrograph curve)		
Volume	13.944 ac-ft	
CCC Unit Undragraph Daram	ootoro	
SCS Unit Hydrograph Param	leters	
Time of Concentration (Composite)	0.1385 hours	
Computational Time Increment	0.0185 hours	
Unit Hydrograph Shape Factor	483.432	
K Factor	0.749	
Receding/Rising, Tr/Tp	1.670	
Unit peak, qp	261.30 ft ³ /s	
Unit peak time, Tp	0.0923 hours	
Unit receding limb, Tr	0.3693 hours	
Total unit time, Tb	0.4617 hours	
Rontlay System	ne Inc. Haastad Mathads	

Bentley Systems, Inc. Haestad Methods Solution Center 27 Siemon Company Drive Suite 200 W Watertown, CT 06795 USA +1-203-755-1666

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: B-1 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: B-2 Storm Event: 100-Yr (TP-40)

Storm Event	100-Yr (TP-40)
Return Event	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration	0.1987 hours
(Composite) Area (User Defined)	2,114,402.401 ft²
Area (Oser Defined)	2,114,402.401 1(-
Computational Time	
Increment	0.0265 hours
Time to Peak (Computed)	12.0015 hours
Flow (Peak, Computed)	321.22 ft ³ /s
Output Increment	0.0100 hours
Time to Flow (Peak Interpolated Output)	12.0000 hours
Flow (Peak Interpolated Output)	320.74 ft³/s
Drainage Area	
SCS CN (Composite)	78.000
Area (User Defined)	2,114,402.401 ft²
Maximum Retention (Pervious)	2.82 in
Maximum Retention (Pervious, 20 percent)	0.56 in
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	5.12 in
Runoff Volume (Pervious)	20.725 ac-ft
Hydrograph Volume (Area ur	 nder Hydrograph curve)
Volume	20.725 ac-ft
SCS Unit Hydrograph Param	neters
Time of Concentration (Composite)	0.1987 hours
Computational Time Increment	0.0265 hours
Unit Hydrograph Shape Factor	483.432
K Factor	0.749
Receding/Rising, Tr/Tp	1.670
Unit peak, qp	276.79 ft ³ /s
Unit peak time, Tp	0.1325 hours
Unit receding limb, Tr	0.5299 hours
Total unit time, Tb	0.6623 hours
Pontley Cyatam	as Inc. Hapstad Mothods

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: B-2 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Subsection: Unit Hydrograph Summary Return Event: 100 years

Label: B-3 Storm Event: 100-Yr (TP-40)

`		
Storm Event	100-Yr (TP-40)	
Return Event	100 years	
Duration	72.0000 hours	
Depth	7.71 in	
Time of Concentration (Composite)	0.1447 hours	
Area (User Defined)	1,772,456.401 ft²	
Computational Time Increment	0.0193 hours	
Time to Peak (Computed)	11.9619 hours	
Flow (Peak, Computed)	317.74 ft³/s	
Output Increment	0.0100 hours	
Time to Flow (Peak Interpolated Output)	11.9600 hours	
Flow (Peak Interpolated Output)	317.37 ft³/s	
Drainage Area		
SCS CN (Composite)	83,000	
Area (User Defined)	1,772,456.401 ft²	
Maximum Retention (Pervious)	2.05 in	
Maximum Retention (Pervious, 20 percent)	0.41 in	
Cumulative Runoff		
Cumulative Runoff Depth (Pervious)	5.70 in	
Runoff Volume (Pervious)	19.331 ac-ft	
Hydrograph Volume (Area under Hydrograph curve)		
Volume	19.332 ac-ft	
SCS Unit Hydrograph Param	eters	
Time of Concentration (Composite)	0.1447 hours	
Computational Time Increment	0.0193 hours	
Unit Hydrograph Shape Factor	483.432	
K Factor	0.749	
Receding/Rising, Tr/Tp	1.670	
Unit peak, qp	318.61 ft ³ /s	
Unit peak time, Tp	0.0965 hours	
Unit receding limb, Tr	0.3859 hours	
Total unit time, Tb	0.4823 hours	
5 5		

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: B-3 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: B-4 (BYP) Storm Event: 100-Yr (TP-40)

Storm Event	100-Yr (TP-40)	
Return Event	100 years	
Duration	72.0000 hours	
Depth	7.71 in	
Time of Concentration (Composite)	0.1000 hours	
Area (User Defined)	323,215.200 ft²	
Computational Time Increment	0.0133 hours	
Time to Peak (Computed)	11.9200 hours	
Flow (Peak, Computed)	71.04 ft ³ /s	
Output Increment	0.0100 hours	
Time to Flow (Peak Interpolated Output)	11.9200 hours	
Flow (Peak Interpolated Output)	71.04 ft³/s	
Drainage Area		
SCS CN (Composite)	94.000	
Area (User Defined)	323,215.200 ft ²	
Maximum Retention (Pervious)	0.64 in	
Maximum Retention (Pervious, 20 percent)	0.13 in	
Cumulative Runoff		
Cumulative Runoff Depth (Pervious)	6.99 in	
Runoff Volume (Pervious)	4.324 ac-ft	
Hydrograph Volume (Area under Hydrograph curve)		
Volume	4.324 ac-ft	
SCS Unit Hydrograph Param	 neters	
Time of Concentration (Composite)	0.1000 hours	
Computational Time Increment	0.0133 hours	
Unit Hydrograph Shape Factor	483.432	
K Factor	0.749	
Receding/Rising, Tr/Tp	1.670	
Unit peak, qp	84.07 ft ³ /s	
Unit peak time, Tp	0.0667 hours	
Unit receding limb, Tr	0.2667 hours	
Total unit time, Tb	0.3333 hours	
Rontley System	ns Inc. Haastad Mathads	

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: B-4 (BYP) Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: B-4 (DET) Storm Event: 100-Yr (TP-40)

`		
Storm Event	100-Yr (TP-40)	
Return Event	100 years	
Duration	72.0000 hours	
Depth	7.71 in	
Time of Concentration	0.1155 hours	
(Composite)	53-2-2 33-33-2	
Area (User Defined)	1,091,178.000 ft ²	
Computational Time Increment	0.0154 hours	
Time to Peak (Computed)	11.9350 hours	
Flow (Peak, Computed)	233.88 ft ³ /s	
Output Increment	0.0100 hours	
Time to Flow (Peak Interpolated Output)	11.9400 hours	
Flow (Peak Interpolated Output)	232.94 ft³/s	
Drainage Area		
SCS CN (Composite)	94.000	
Area (User Defined)	1,091,178.000 ft ²	
Maximum Retention (Pervious)	0.64 in	
Maximum Retention (Pervious, 20 percent)	0.13 in	
Cumulative Runoff		
Cumulative Runoff Depth (Pervious)	6.99 in	
Runoff Volume (Pervious)	14.599 ac-ft	
Hydrograph Volume (Area under Hydrograph curve)		
Volume	14.599 ac-ft	
SCS Unit Hydrograph Parameters		
Time of Concentration (Composite)	0.1155 hours	
Computational Time Increment	0.0154 hours	
Unit Hydrograph Shape Factor	483.432	
K Factor	0.749	
Receding/Rising, Tr/Tp	1.670	
Unit peak, qp	245.74 ft³/s	
Unit peak time, Tp	0.0770 hours	
Unit receding limb, Tr	0.3080 hours	
Total unit time, Tb	0.3850 hours	

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: B-4 (DET) Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: C-1 Storm Event: 100-Yr (TP-40)

`	
Storm Event	100-Yr (TP-40)
Return Event	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration	0.2860 hours
(Composite)	
Area (User Defined)	1,969,347.601 ft²
Computational Time Increment	0.0381 hours
Time to Peak (Computed)	12.0501 hours
Flow (Peak, Computed)	317.13 ft³/s
Output Increment	0.0100 hours
Time to Flow (Peak Interpolated Output)	12.0500 hours
Flow (Peak Interpolated Output)	317.10 ft ³ /s
Drainage Area	
SCS CN (Composite)	90.000
Area (User Defined)	1,969,347.601 ft ²
Maximum Retention (Pervious)	1.11 in
Maximum Retention (Pervious, 20 percent)	0.22 in
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	6.52 in
Runoff Volume (Pervious)	24.565 ac-ft
Hydrograph Volume (Area ur	nder Hydrograph curve)
Volume	24.565 ac-ft
SCS Unit Hydrograph Param	eters
Time of Concentration (Composite)	0.2860 hours
Computational Time Increment	0.0381 hours
Unit Hydrograph Shape Factor	483.432
K Factor	0.749
Receding/Rising, Tr/Tp	1.670
Unit peak, qp	179.11 ft ³ /s
Unit peak time, Tp	0.1907 hours
Unit receding limb, Tr	0.7627 hours
Total unit time, Tb	0.9533 hours
.	

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: C-1 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Subsection: Unit Hydrograph Summary Return Event: 100 years

Label: C-2 Storm Event: 100-Yr (TP-40)

`		
Storm Event	100-Yr (TP-40)	
Return Event	100 years	
Duration	72.0000 hours	
Depth	7.71 in	
Time of Concentration (Composite)	0.3308 hours	
Area (User Defined)	2,488,582.801 ft ²	
Computational Time Increment	0.0441 hours	
Time to Peak (Computed)	12.0852 hours	
Flow (Peak, Computed)	330.94 ft ³ /s	
Output Increment	0.0100 hours	
Time to Flow (Peak Interpolated Output)	12.0800 hours	
Flow (Peak Interpolated Output)	329.78 ft³/s	
Drainage Area		
SCS CN (Composite)	81.000	
Area (User Defined)	2,488,582.801 ft ²	
Maximum Retention	2.35 in	
(Pervious) Maximum Retention		
(Pervious, 20 percent)	0.47 in	
Cumulative Runoff		
Cumulative Runoff Depth (Pervious)	5.47 in	
Runoff Volume (Pervious)	26.038 ac-ft	
Hydrograph Volume (Area un	ider Hydrograph curve)	
Volume	26.038 ac-ft	
SCS Unit Hydrograph Parameters		
Time of Concentration (Composite)	0.3308 hours	
Computational Time Increment	0.0441 hours	
Unit Hydrograph Shape Factor	483.432	
K Factor	0.749	
Receding/Rising, Tr/Tp	1.670	
Unit peak, qp	195.68 ft ³ /s	
Unit peak time, Tp	0.2205 hours	
Unit receding limb, Tr	0.8821 hours	
Total unit time, Tb	1.1027 hours	
B S		

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: C-2 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Subsection: Unit Hydrograph Summary Return Event: 100 years

Label: C-3 Storm Event: 100-Yr (TP-40)

Storm Event	100-Yr (TP-40)	
Return Event	100 years	
Duration	72.0000 hours	
Depth	7.71 in	
Time of Concentration	0.1199 hours	
(Composite) Area (User Defined)	2,280,801.601 ft ²	
Area (oser berinea)	2,200,001.001 10	
Communitational Times		
Computational Time Increment	0.0160 hours	
Time to Peak (Computed)	11.9420 hours	
Flow (Peak, Computed)	426.20 ft ³ /s	
Output Increment	0.0100 hours	
Time to Flow (Peak Interpolated Output)	11.9400 hours	
Flow (Peak Interpolated	425.51 ft³/s	
Output)		
Drainage Area		
SCS CN (Composite)	83.000	
Area (User Defined)	2,280,801.601 ft ²	
Maximum Retention	2,200,001.001 10	
(Pervious)	2.05 in	
Maximum Retention (Pervious, 20 percent)	0.41 in	
Cumulative Runoff		
Cumulative Runoff Depth (Pervious)	5.70 in	
Runoff Volume (Pervious)	24.875 ac-ft	
Hydrograph Volume (Area under Hydrograph curve)		
Volume	24.875 ac-ft	
SCS Unit Hydrograph Parame	eters	
Time of Concentration (Composite)	0.1199 hours	
Computational Time Increment	0.0160 hours	
Unit Hydrograph Shape Factor	483.432	
K Factor	0.749	
Receding/Rising, Tr/Tp	1.670	
Unit peak, qp	494.80 ft ³ /s	
Unit peak time, Tp	0.0799 hours	
Unit receding limb, Tr	0.3197 hours	
Total unit time, Tb	0.3997 hours	
-, -		

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: C-3 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: D-1 Storm Event: 100-Yr (TP-40)

Storm Event	100-Yr (TP-40)	
Return Event	100 years	
Duration	72.0000 hours	
Depth	7.71 in	
Time of Concentration	0.1275 hours	
(Composite)	1 607 770 500 63	
Area (User Defined)	1,607,778.500 ft²	
Computational Time Increment	0.0170 hours	
Time to Peak (Computed)	11.9510 hours	
Flow (Peak, Computed)	266.11 ft ³ /s	
Output Increment	0.0100 hours	
Time to Flow (Peak Interpolated Output)	11.9500 hours	
Flow (Peak Interpolated Output)	265.94 ft³/s	
Drainage Area		
SCS CN (Composite)	77.000	
Area (User Defined)	1,607,778.500 ft ²	
Maximum Retention (Pervious)	2.99 in	
Maximum Retention (Pervious, 20 percent)	0.60 in	
Cumulative Runoff		
Cumulative Runoff Depth		
(Pervious)	5.01 in	
Runoff Volume (Pervious)	15.407 ac-ft	
Hydrograph Volume (Area under Hydrograph curve)		
Volume	15.407 ac-ft	
SCS Unit Hydrograph Param	eters	
Time of Concentration (Composite)	0.1275 hours	
Computational Time Increment	0.0170 hours	
Unit Hydrograph Shape Factor	483.432	
K Factor	0.749	
Receding/Rising, Tr/Tp	1.670	
Unit peak, qp	328.00 ft ³ /s	
Unit peak time, Tp	0.0850 hours	
Unit receding limb, Tr	0.3400 hours	
Total unit time, Tb	0.4250 hours	
5 " 6 :		

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: D-1 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: D-2 Storm Event: 100-Yr (TP-40)

Storm Event	100-Yr (TP-40)	
Return Event	100 years	
Duration	72.0000 hours	
Depth	7.71 in	
Time of Concentration (Composite)	0.1755 hours	
Area (User Defined)	2,047,412.440 ft²	
Computational Time Increment	0.0234 hours	
Time to Peak (Computed)	11.9808 hours	
Flow (Peak, Computed)	326.57 ft ³ /s	
Output Increment	0.0100 hours	
Time to Flow (Peak Interpolated Output)	11.9800 hours	
Flow (Peak Interpolated Output)	326.27 ft³/s	
Drainage Area		
SCS CN (Composite)	79.000	
Area (User Defined)	2,047,412.440 ft ²	
Maximum Retention (Pervious)	2.66 in	
Maximum Retention (Pervious, 20 percent)	0.53 in	
Cumulative Runoff		
Cumulative Runoff Depth (Pervious)	5.24 in	
Runoff Volume (Pervious)	20.518 ac-ft	
Hydrograph Volume (Area under Hydrograph curve)		
Volume	20.518 ac-ft	
SCS Unit Hydrograph Parameters		
Time of Concentration (Composite)	0.1755 hours	
Computational Time Increment	0.0234 hours	
Unit Hydrograph Shape Factor	483.432	
K Factor	0.749	
Receding/Rising, Tr/Tp	1.670	
Unit peak, qp	303.45 ft ³ /s	
Unit peak time, Tp	0.1170 hours	
Unit receding limb, Tr	0.4680 hours	
Total unit time, Tb	0.5850 hours	
Pontloy System	es Inc. Haestad Methods	

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: D-2 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: D-3 Storm Event: 100-Yr (TP-40)

`		
Storm Event	100-Yr (TP-40)	
Return Event	100 years	
Duration	72.0000 hours	
Depth	7.71 in	
Time of Concentration (Composite)	0.1561 hours	
Area (User Defined)	733,712.810 ft ²	
Computational Time Increment	0.0208 hours	
Time to Peak (Computed)	11.9677 hours	
Flow (Peak, Computed)	138.90 ft ³ /s	
Output Increment	0.0100 hours	
Time to Flow (Peak Interpolated Output)	11.9700 hours	
Flow (Peak Interpolated Output)	138.69 ft³/s	
Drainage Area		
SCS CN (Composite)	88.000	
Area (User Defined)	733,712.810 ft²	
Maximum Retention (Pervious)	1.36 in	
Maximum Retention (Pervious, 20 percent)	0.27 in	
Cumulative Runoff		
Cumulative Runoff Depth (Pervious)	6.28 in	
Runoff Volume (Pervious)	8.822 ac-ft	
Hydrograph Volume (Area under Hydrograph curve)		
Volume	8.822 ac-ft	
SCS Unit Hydrograph Parameters		
Time of Concentration (Composite)	0.1561 hours	
Computational Time Increment	0.0208 hours	
Unit Hydrograph Shape Factor	483.432	
K Factor	0.749	
Receding/Rising, Tr/Tp	1.670	
Unit peak, qp	122.26 ft ³ /s	
Unit peak time, Tp	0.1041 hours	
Unit receding limb, Tr	0.4163 hours	
Total unit time, Tb	0.5203 hours	
5 " • •		

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: D-3 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: D-4 Storm Event: 100-Yr (TP-40)

Storm Event	100-Yr (TP-40)
Return Event	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration (Composite)	0.1792 hours
Area (User Defined)	4,895,129.650 ft ²
Computational Time Increment	0.0239 hours
Time to Peak (Computed)	11.9945 hours
Flow (Peak, Computed)	894.83 ft ³ /s
Output Increment	0.0100 hours
Time to Flow (Peak Interpolated Output)	11.9900 hours
Flow (Peak Interpolated Output)	894.20 ft³/s
Drainage Area	
SCS CN (Composite)	88.000
Area (User Defined)	4,895,129.650 ft ²
Maximum Retention (Pervious)	1.36 in
Maximum Retention (Pervious, 20 percent)	0.27 in
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	6.28 in
Runoff Volume (Pervious)	58.857 ac-ft
Hydrograph Volume (Area ur	nder Hydrograph curve)
Volume	58.857 ac-ft
SCS Unit Hydrograph Param	eters
Time of Concentration (Composite)	0.1792 hours
Computational Time Increment	0.0239 hours
Unit Hydrograph Shape Factor	483.432
K Factor	0.749
Receding/Rising, Tr/Tp	1.670
Unit peak, qp	710.53 ft ³ /s
Unit peak time, Tp	0.1195 hours
Unit receding limb, Tr	0.4779 hours
Total unit time, Tb	0.5973 hours

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: D-4 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: D-5 Storm Event: 100-Yr (TP-40)

`	
Storm Event	100-Yr (TP-40)
Return Event	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration (Composite)	0.2652 hours
Area (User Defined)	2,319,189.150 ft ²
Computational Time Increment	0.0354 hours
Time to Peak (Computed)	12.0224 hours
Flow (Peak, Computed)	377.90 ft ³ /s
Output Increment	0.0100 hours
Time to Flow (Peak Interpolated Output)	12.0300 hours
Flow (Peak Interpolated Output)	377.88 ft³/s
Drainage Area	
SCS CN (Composite)	89.000
Area (User Defined)	2,319,189.150 ft ²
Maximum Retention (Pervious)	1.24 in
Maximum Retention (Pervious, 20 percent)	0.25 in
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	6.40 in
Runoff Volume (Pervious)	28.406 ac-ft
Hydrograph Volume (Area un	der Hydrograph curve)
Volume	28.406 ac-ft
CCC Unit Under sweet Deven	
SCS Unit Hydrograph Param	eters ———————
Time of Concentration (Composite)	0.2652 hours
Computational Time Increment	0.0354 hours
Unit Hydrograph Shape Factor	483.432
K Factor	0.749
Receding/Rising, Tr/Tp	1.670
Unit peak, qp	227.47 ft ³ /s
Unit peak time, Tp	0.1768 hours
Unit receding limb, Tr	0.7072 hours
Total unit time, Tb	0.8840 hours

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: D-5 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: E-1 Storm Event: 100-Yr (TP-40)

`	
Storm Event	100-Yr (TP-40)
Return Event	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration	0.1062 hours
(Composite)	002 072 020 03
Area (User Defined)	983,972.820 ft²
Computational Time Increment	0.0142 hours
Time to Peak (Computed)	11.9369 hours
Flow (Peak, Computed)	178.76 ft ³ /s
Output Increment	0.0100 hours
Time to Flow (Peak Interpolated Output)	11.9300 hours
Flow (Peak Interpolated Output)	178.18 ft³/s
Drainage Area	
SCS CN (Composite)	80.000
Area (User Defined)	983,972.820 ft²
Maximum Retention (Pervious)	2.50 in
Maximum Retention (Pervious, 20 percent)	0.50 in
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	5.35 in
Runoff Volume (Pervious)	10.078 ac-ft
Hydrograph Volume (Area ur	nder Hydrograph curve)
Volume	10.078 ac-ft
SCS Unit Hydrograph Param	neters
Time of Concentration	
(Composite)	0.1062 hours
Computational Time Increment	0.0142 hours
Unit Hydrograph Shape Factor	483.432
K Factor	0.749
Receding/Rising, Tr/Tp	1.670
Unit peak, qp	241.00 ft ³ /s
Unit peak time, Tp	0.0708 hours
Unit receding limb, Tr	0.2832 hours
Total unit time, Tb	0.3540 hours
5 " - :	

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: E-1 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: E-2 Storm Event: 100-Yr (TP-40)

17-40)	
Storm Event	100-Yr (TP-40)
Return Event	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration	0.1021 hours
(Composite)	0.1021 Hours
Area (User Defined)	285,700.370 ft²
Computational Time Increment	0.0136 hours
Time to Peak (Computed)	11.9389 hours
Flow (Peak, Computed)	45.19 ft ³ /s
Output Increment	0.0100 hours
Time to Flow (Peak Interpolated Output)	11.9400 hours
Flow (Peak Interpolated Output)	45.12 ft³/s
Drainage Area	
SCS CN (Composite)	73.000
Area (User Defined)	285,700.370 ft ²
Maximum Retention (Pervious)	3.70 in
Maximum Retention (Pervious, 20 percent)	0.74 in
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	4.55 in
Runoff Volume (Pervious)	2.489 ac-ft
Hydrograph Volume (Area und	er Hydrograph curve)
Volume	2.489 ac-ft
SCS Unit Hydrograph Parame	ters
Time of Concentration (Composite)	0.1021 hours
Computational Time Increment	0.0136 hours
Unit Hydrograph Shape Factor	483.432
K Factor	0.749
Receding/Rising, Tr/Tp	1.670
Unit peak, qp	72.79 ft ³ /s
Unit peak time, Tp	0.0681 hours
Unit receding limb, Tr	0.2723 hours
Total unit time, Tb	0.3403 hours

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: E-2 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: F-1 Storm Event: 100-Yr (TP-40)

Storm Event	100-Yr (TP-40)
Return Event	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration (Composite)	0.1000 hours
Area (User Defined)	341,811.630 ft²
Computational Time Increment	0.0133 hours
Time to Peak (Computed)	11.9333 hours
Flow (Peak, Computed)	59.32 ft ³ /s
Output Increment	0.0100 hours
Time to Flow (Peak Interpolated Output)	11.9300 hours
Flow (Peak Interpolated Output)	59.21 ft³/s
Drainage Area	
SCS CN (Composite)	77.000
Area (User Defined)	341,811.630 ft ²
Maximum Retention (Pervious)	2.99 in
Maximum Retention (Pervious, 20 percent)	0.60 in
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	5.01 in
Runoff Volume (Pervious)	3.275 ac-ft
Hydrograph Volume (Area ur	nder Hydrograph curve)
Volume	3.275 ac-ft
SCS Unit Hydrograph Param	neters
Time of Concentration (Composite)	0.1000 hours
Computational Time Increment	0.0133 hours
Unit Hydrograph Shape Factor	483.432
K Factor	0.749
Receding/Rising, Tr/Tp	1.670
Unit peak, qp	88.91 ft ³ /s
Unit peak time, Tp	0.0667 hours
Unit receding limb, Tr	0.2667 hours
Total unit time, Tb	0.3333 hours
•	ne Inc. Haastad Mathads

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: F-1 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: F-2 Storm Event: 100-Yr (TP-40)

`	
Storm Event	100-Yr (TP-40)
Return Event	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration (Composite)	0.1260 hours
Area (User Defined)	555,711.140 ft ²
Computational Time Increment	0.0168 hours
Time to Peak (Computed)	11.9448 hours
Flow (Peak, Computed)	99.29 ft ³ /s
Output Increment	0.0100 hours
Time to Flow (Peak Interpolated Output)	11.9500 hours
Flow (Peak Interpolated Output)	99.00 ft³/s
Duciness Area	
Drainage Area	
SCS CN (Composite)	81.000
Area (User Defined)	555,711.140 ft ²
Maximum Retention (Pervious)	2.35 in
Maximum Retention (Pervious, 20 percent)	0.47 in
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	5.47 in
Runoff Volume (Pervious)	5.814 ac-ft
Hydrograph Volume (Area u	nder Hydrograph curve)
Volume	5.814 ac-ft
SCS Unit Hydrograph Paran	neters
Time of Concentration (Composite)	0.1260 hours
Computational Time Increment	0.0168 hours
Unit Hydrograph Shape Factor	483.432
K Factor	0.749
Receding/Rising, Tr/Tp	1.670
Unit peak, qp	114.72 ft ³ /s
Unit peak time, Tp	0.0840 hours
Unit receding limb, Tr	0.3360 hours
Total unit time, Tb	0.4200 hours

Subsection: Unit Hydrograph Summary

Return Event: 100 years

Label: F-2

Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: G-1 Storm Event: 100-Yr (TP-40)

Storm Event	100-Yr (TP-40)
Return Event	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration (Composite)	0.1055 hours
Area (User Defined)	611,472.170 ft²
Computational Time Increment	0.0141 hours
Time to Peak (Computed)	11.9285 hours
Flow (Peak, Computed)	113.48 ft ³ /s
Output Increment	0.0100 hours
Time to Flow (Peak Interpolated Output)	11.9300 hours
Flow (Peak Interpolated Output)	113.41 ft³/s
Drainage Area	
SCS CN (Composite)	81.000
Area (User Defined)	611,472.170 ft ²
Maximum Retention (Pervious)	2.35 in
Maximum Retention (Pervious, 20 percent)	0.47 in
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	5.47 in
Runoff Volume (Pervious)	6.398 ac-ft
Hydrograph Volume (Area ur	 nder Hydrograph curve)
Volume	6.398 ac-ft
SCS Unit Hydrograph Param	neters
Time of Concentration (Composite)	0.1055 hours
Computational Time Increment	0.0141 hours
Unit Hydrograph Shape Factor	483.432
K Factor	0.749
Receding/Rising, Tr/Tp	1.670
Unit peak, qp	150.76 ft ³ /s
Unit peak time, Tp	0.0703 hours
Unit receding limb, Tr	0.2813 hours
Total unit time, Tb	0.3517 hours
Pontley System	as Inc. Haastad Mothads

Subsection: Unit Hydrograph Summary

Return Event: 100 years

Label: G-1

Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

SCS Unit Hydrograph Parameters

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: G-2 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

*	
Storm Event	100-Yr (TP-40)
Return Event	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration	0.1175 hours
(Composite)	0.11/5 Hours
Area (User Defined)	345,304.250 ft²
Computational Time Increment	0.0157 hours
Time to Peak (Computed)	11.9380 hours
Flow (Peak, Computed)	66.80 ft ³ /s
Output Increment	0.0100 hours
Time to Flow (Peak Interpolated Output)	11.9400 hours
Flow (Peak Interpolated Output)	66.71 ft³/s
Drainage Area	
SCS CN (Composite)	85.000
Area (User Defined)	345,304.250 ft ²
Maximum Retention (Pervious)	1.76 in
Maximum Retention (Pervious, 20 percent)	0.35 in
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	5.93 in
Runoff Volume (Pervious)	3.920 ac-ft
Hydrograph Values (Ass	
nyurograph volume (Area un	der Hydrograph curve)
Volume Volume (Area un	der Hydrograph curve) 3.920 ac-ft
· · · · · · · · · · · · · · · · · · ·	3.920 ac-ft
Volume	3.920 ac-ft
Volume SCS Unit Hydrograph Parame Time of Concentration	3.920 ac-ft
Volume SCS Unit Hydrograph Parame Time of Concentration (Composite) Computational Time	3.920 ac-ft eters 0.1175 hours
Volume SCS Unit Hydrograph Parame Time of Concentration (Composite) Computational Time Increment Unit Hydrograph Shape	3.920 ac-ft eters 0.1175 hours 0.0157 hours
Volume SCS Unit Hydrograph Parame Time of Concentration (Composite) Computational Time Increment Unit Hydrograph Shape Factor	3.920 ac-ft eters 0.1175 hours 0.0157 hours 483.432
Volume SCS Unit Hydrograph Parame Time of Concentration (Composite) Computational Time Increment Unit Hydrograph Shape Factor K Factor	3.920 ac-ft eters 0.1175 hours 0.0157 hours 483.432 0.749
Volume SCS Unit Hydrograph Parame Time of Concentration (Composite) Computational Time Increment Unit Hydrograph Shape Factor K Factor Receding/Rising, Tr/Tp	3.920 ac-ft eters 0.1175 hours 0.0157 hours 483.432 0.749 1.670
Volume SCS Unit Hydrograph Parame Time of Concentration (Composite) Computational Time Increment Unit Hydrograph Shape Factor K Factor Receding/Rising, Tr/Tp Unit peak, qp	3.920 ac-ft eters 0.1175 hours 0.0157 hours 483.432 0.749 1.670 76.44 ft ³ /s

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: G-2 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

SCS Unit Hydrograph Parameters

Subsection: Unit Hydrograph Summary Return Event: 100 years

Label: H-1 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Storm Event	100-Yr (TP-40)
Return Event	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration (Composite)	0.1348 hours
Area (User Defined)	2,446,892.920 ft ²
Computational Time Increment	0.0180 hours
Time to Peak (Computed)	11.9523 hours
Flow (Peak, Computed)	407.68 ft ³ /s
Output Increment	0.0100 hours
Time to Flow (Peak Interpolated Output)	11.9500 hours
Flow (Peak Interpolated Output)	406.72 ft ³ /s
Drainage Area	
SCS CN (Composite)	78.000
Area (User Defined)	2,446,892.920 ft ²
Maximum Retention (Pervious)	2.82 in
Maximum Retention	0.56 in
(Pervious, 20 percent)	
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	5.12 in
Runoff Volume (Pervious)	23.984 ac-ft
Hydrograph Volume (Area ur	nder Hydrograph curve)
Volume	23.984 ac-ft
CCC Unit Usalina arra il Da	otoro
SCS Unit Hydrograph Param	eters
Time of Concentration (Composite)	0.1348 hours
Computational Time Increment	0.0180 hours
Unit Hydrograph Shape Factor	483.432
K Factor	0.749
Receding/Rising, Tr/Tp	1.670
Unit peak, qp	472.15 ft ³ /s
Unit peak time, Tp	0.0899 hours
Unit receding limb, Tr	0.3595 hours
Total unit time, Tb	0.4493 hours
Bentley System	s Inc. Haestad Methods

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: H-1 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

SCS Unit Hydrograph Parameters

Subsection: Unit Hydrograph Summary Return Event: 100 years

Label: I-1 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Storm Event	100-Yr (TP-40)
Return Event	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration (Composite)	0.1019 hours
Area (User Defined)	60,899.990 ft ²
Computational Time Increment	0.0136 hours
Time to Peak (Computed)	11.9291 hours
Flow (Peak, Computed)	12.30 ft ³ /s
Output Increment	0.0100 hours
Time to Flow (Peak Interpolated Output)	11.9300 hours
Flow (Peak Interpolated Output)	12.29 ft³/s
Drainage Area	
SCS CN (Composite)	86.000
Area (User Defined)	60,899.990 ft ²
Maximum Retention (Pervious)	1.63 in
Maximum Retention (Pervious, 20 percent)	0.33 in
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	6.05 in
Runoff Volume (Pervious)	0.705 ac-ft
Hydrograph Volume (Area u	nder Hydrograph curve)
Volume	0.705 ac-ft
SCS Unit Hydrograph Param	neters
Time of Concentration	
(Composite)	0.1019 hours
Computational Time Increment	0.0136 hours
Unit Hydrograph Shape Factor	483.432
K Factor	0.749
Receding/Rising, Tr/Tp	1.670
Unit peak, qp	15.55 ft ³ /s
Unit peak time, Tp	0.0679 hours
Unit receding limb, Tr	0.2717 hours
Total unit time, Tb	0.3397 hours
Pontlay Cysten	as Inc. Haastad Mathads

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: I-1 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

SCS Unit Hydrograph Parameters

Subsection: Unit Hydrograph (Hydrograph Table) Return Event: 2 years
Label: D-5 Storm Event: 2-Yr (TP-40)

Scenario: 2-Yr (TP-40)

Storm Event	2-Yr (TP-40)
Return Event	2 years
Duration	72.0000 hours
Depth	3.50 in
Time of Concentration (Composite)	0.2652 hours
Area (User Defined)	2,319,189.150 ft ²

HYDROGRAPH ORDINATES (ft³/s) Output Time Increment = 0.0100 hours Time on left represents time for first value in each row.

Time (hours)	Flow (ft³/s)	Flow (ft³/s)	Flow (ft³/s)	Flow (ft³/s)	Flow (ft³/s)
5.5500	0.00	0.00	0.00	0.00	0.00
5.6000	0.00	0.00	0.01	0.01	0.01
5.6500	0.01	0.01	0.01	0.02	0.02
5.7000	0.02	0.02	0.02	0.03	0.03
5.7500	0.03	0.03	0.04	0.04	0.04
5.8000	0.04	0.05	0.05	0.05	0.05
5.8500	0.06	0.06	0.06	0.07	0.07
5.9000	0.07	0.08	0.08	0.08	0.08
5.9500	0.09	0.09	0.09	0.10	0.10
6.0000	0.10	0.11	0.11	0.11	0.12
6.0500	0.12	0.12	0.13	0.13	0.13
6.1000	0.14	0.14	0.14	0.15	0.15
6.1500	0.15	0.16	0.16	0.16	0.17
6.2000	0.17	0.17	0.18	0.18	0.18
6.2500	0.19	0.19	0.19	0.20	0.20
6.3000	0.20	0.21	0.21	0.21	0.22
6.3500	0.22	0.22	0.23	0.23	0.23
6.4000	0.24	0.24	0.25	0.25	0.25
6.4500	0.26	0.26	0.26	0.27	0.27
6.5000	0.27	0.28	0.28	0.28	0.29
6.5500	0.29	0.29	0.30	0.30	0.31
6.6000	0.31	0.31	0.32	0.32	0.32
6.6500	0.33	0.33	0.33	0.34	0.34
6.7000	0.35	0.35	0.35	0.36	0.36
6.7500	0.36	0.37	0.37	0.37	0.38
6.8000	0.38	0.39	0.39	0.39	0.40
6.8500	0.40	0.40	0.41	0.41	0.42
6.9000	0.42	0.42	0.43	0.43	0.43
6.9500	0.44	0.44	0.45	0.45	0.45
7.0000	0.46	0.46	0.46	0.47	0.47
7.0500	0.48	0.48	0.48	0.49	0.49
7.1000	0.50	0.50	0.50	0.51	0.51
7.1500	0.52	0.52	0.52	0.53	0.53
7.2000	0.53	0.54	0.54	0.55	0.55
7.2500	0.55	0.56	0.56	0.57	0.57
7.3000	0.57	0.58	0.58	0.59	0.59
7.3500	0.59	0.60	0.60	0.61	0.61

Discovery_Park_Ph-1_Macro_Ex-Cond.ppc 1/10/2023

Bentley Systems, Inc. Haestad Methods Solution Center 27 Siemon Company Drive Suite 200 W Watertown, CT 06795 USA +1-203-755-1666

PondPack CONNECT Edition [10.02.00.01] Page 71 of 131

Subsection: Unit Hydrograph (Hydrograph Table) Return Event: 2 years
Label: D-5 Storm Event: 2-Yr (TP-40)

Scenario: 2-Yr (TP-40)

HYDROGRAPH ORDINATES (ft³/s) Output Time Increment = 0.0100 hours Time on left represents time for first value in each row.

	-	oresents time			
Time	Flow	Flow	Flow	Flow	Flow
(hours)	(ft³/s)	(ft³/s)	(ft³/s)	(ft³/s)	(ft³/s)
7.4000	0.61	0.62	0.62	0.63	0.63
7.4500	0.63	0.64	0.64	0.65	0.65
7.5000	0.65	0.66	0.66	0.67	0.67
7.5500	0.67	0.68	0.68	0.69	0.69
7.6000	0.69	0.70	0.70	0.71	0.71
7.6500	0.72	0.72	0.72	0.73	0.73
7.7000	0.74	0.74	0.74	0.75	0.75
7.7500	0.76	0.76	0.76	0.77	0.77
7.8000	0.78	0.78	0.79	0.79	0.79
7.8500	0.80	0.80	0.81	0.81	0.82
7.9000	0.82	0.82	0.83	0.83	0.84
7.9500	0.84	0.84	0.85	0.85	0.86
8.0000	0.86	0.87	0.87	0.87	0.88
8.0500	0.88	0.89	0.89	0.90	0.90
8.1000	0.91	0.91	0.92	0.92	0.93
8.1500	0.93	0.94	0.94	0.95	0.96
8.2000	0.96	0.97	0.98	0.98	0.99
8.2500	1.00	1.00	1.01	1.02	1.03
8.3000	1.03	1.04	1.05	1.06	1.06
8.3500	1.07	1.08	1.09	1.10	1.10
8.4000	1.11	1.12	1.13	1.14	1.15
8.4500	1.16	1.16	1.17	1.18	1.19
8.5000	1.20	1.21	1.22	1.23	1.24
8.5500	1.25	1.25	1.26	1.27	1.28
8.6000	1.29	1.30	1.31	1.32	1.33
8.6500	1.34	1.35	1.36	1.37	1.38
8.7000	1.39	1.40	1.41	1.42	1.43
8.7500	1.44	1.45	1.46	1.47	1.48
8.8000	1.49	1.50	1.51	1.52	1.53
8.8500	1.54	1.55	1.56	1.57	1.58
8.9000	1.60	1.61	1.62	1.63	1.64
8.9500	1.65	1.66	1.67	1.68	1.69
9.0000	1.71	1.72	1.73	1.74	1.75
9.0500	1.76	1.77	1.78	1.79	1.80
9.1000	1.81	1.83	1.84	1.85	1.86
9.1500	1.87	1.88	1.88	1.89	1.90
9.2000	1.91	1.92	1.93	1.94	1.94
9.2500	1.95	1.96	1.97	1.98	1.98
9.3000	1.99	2.00	2.00	2.01	2.02
9.3500	2.02	2.03	2.04	2.04	2.05
9.4000	2.06	2.06	2.07	2.07	2.08
9.4500	2.09	2.09	2.10	2.10	2.11
9.5000	2.12	2.12	2.13	2.13	2.14
9.5500	2.15	2.15	2.16	2.17	2.17
9.6000	2.18	2.19	2.20	2.21	2.22
9.6500	2.22	2.23	2.24	2.25	2.27
1 3.5556	I -:			2.23	_::-/

Discovery_Park_Ph-1_Macro_Ex-Cond.ppc 1/10/2023

Bentley Systems, Inc. Haestad Methods Solution Center 27 Siemon Company Drive Suite 200 W Watertown, CT 06795 USA +1-203-755-1666 PondPack CONNECT Edition [10.02.00.01] Page 72 of 131

Subsection: Unit Hydrograph (Hydrograph Table)

Return Event: 2 years

Label: D-5

Storm Event: 2-Yr (TP-40)

Scenario: 2-Yr (TP-40)

HYDROGRAPH ORDINATES (ft³/s) Output Time Increment = 0.0100 hours Time on left represents time for first value in each row.

Time (hours)	Flow (ft³/s)	Flow (ft³/s)	Flow (ft³/s)	Flow (ft³/s)	Flow (ft³/s)
9.7000	2.28	2.29	2.30	2.31	2.33
9.7500	2.34	2.35	2.37	2.38	2.40
9.8000	2.41	2.43	2.44	2.46	2.48
9.8500	2.49	2.51	2.52	2.54	2.56
9.9000	2.57	2.59	2.61	2.63	2.64
9.9500	2.66	2.68	2.70	2.72	2.73
10.0000	2.75	2.77	2.79	2.81	2.83
10.0500	2.85	2.87	2.89	2.91	2.93
10.1000	2.95	2.97	2.99	3.01	3.03
10.1500	3.05	3.07	3.10	3.12	3.14
10.2000	3.17	3.19	3.21	3.24	3.26
10.2500	3.29	3.31	3.34	3.36	3.39
10.3000	3.42	3.44	3.47	3.50	3.52
10.3500	3.55	3.58	3.60	3.63	3.66
10.4000	3.69	3.72	3.75	3.77	3.80
10.4500	3.83	3.86	3.89	3.92	3.95
10.5000	3.98	4.01	4.04	4.07	4.10
10.5500	4.13	4.16	4.19	4.23	4.26
10.6000	4.29	4.33	4.36	4.40	4.43
10.6500	4.47	4.51	4.54	4.58	4.62
10.7000	4.66	4.70	4.74	4.78	4.83
10.7500	4.87	4.91	4.96	5.00	5.05
10.8000	5.09	5.14	5.18	5.23	5.28
10.8500	5.33	5.38	5.42	5.47	5.52
10.9000	5.57	5.62	5.67	5.72	5.77
10.9500	5.82	5.88	5.93	5.98	6.03
11.0000	6.08	6.14	6.19	6.25	6.30
11.0500	6.36	6.42	6.48	6.54	6.60
11.1000	6.66	6.73	6.80	6.87	6.94
11.1500	7.02	7.10	7.17	7.26	7.34
11.2000	7.43	7.52	7.61	7.71	7.81
11.2500	7.91 8.43	8.01	8.11 8.65	8.21 8.77	8.32
11.3000 11.3500	9.00	8.54	9.24	8.77 9.35	8.88 9.47
11.4000	9.60	9.12 9.72	9.24	9.35 9.97	10.10
11.4500	10.22	10.35	10.48	10.61	10.10
11.5000	10.22	11.08	11.25	11.46	11.74
11.5500	12.02	12.31	12.72	13.19	13.66
11.6000	14.18	14.93	15.68	16.44	17.41
11.6500	18.48	19.56	20.70	22.21	23.72
11.7000	25.24	27.04	29.03	31.03	33.04
11.7500	35.44	37.84	40.24	42.93	45.88
11.8000	48.83	51.78	55.46	59.15	62.84
11.8500	66.90	71.42	75.95	80.47	85.78
11.9000	91.17	96.56	102.00	107.51	113.02
11.9500	118.53	123.23	127.76	132.30	136.28
11.5500	110.55	123.23	127.70	132.30	150.20

Discovery_Park_Ph-1_Macro_Ex-Cond.ppc 1/10/2023

Bentley Systems, Inc. Haestad Methods Solution Center 27 Siemon Company Drive Suite 200 W Watertown, CT 06795 USA +1-203-755-1666 PondPack CONNECT Edition [10.02.00.01] Page 73 of 131

Subsection: Unit Hydrograph (Hydrograph Table) Return Event: 2 years
Label: D-5 Storm Event: 2-Yr (TP-40)

Scenario: 2-Yr (TP-40)

HYDROGRAPH ORDINATES (ft³/s) Output Time Increment = 0.0100 hours Time on left represents time for first value in each row.

Time (hours) (ft³/s) (-	oresents time			
12,0000						
12.0500						
12.1000						
12.1500 112.24 107.04 101.91 96.83 91.75 12.2000 86.72 82.23 77.75 73.27 69.30 12.2500 65.78 62.25 58.74 56.13 53.53 12.3000 50.93 48.64 46.69 44.74 42.78 12.3500 41.24 39.72 38.20 36.81 35.61 12.4500 29.35 28.55 27.75 26.95 26.25 12.5000 25.57 24.89 24.24 23.65 23.07 12.5500 22.48 21.96 21.45 20.95 20.46 12.6500 18.00 17.63 17.31 17.00 16.68 12.7000 16.40 16.14 15.88 15.63 15.42 12.7500 15.21 14.99 14.80 14.63 14.46 12.8000 14.29 14.14 13.99 13.85 13.72 12.8500 13.03 12.92 12.82 12.72						
12.2000 86.72 82.23 77.75 73.27 69.30 12.2500 65.78 62.25 58.74 56.13 53.53 12.3000 50.93 48.64 46.69 44.74 42.78 12.3500 41.24 39.72 38.20 36.81 35.61 12.4000 34.41 33.21 32.21 31.24 30.27 12.4500 29.35 28.55 27.75 26.95 26.25 12.5000 25.57 24.89 24.24 23.65 23.07 12.5500 22.58 21.96 21.45 20.95 20.46 12.6000 20.02 19.58 19.15 18.75 18.37 12.6500 18.00 17.63 17.31 17.00 16.68 12.7500 15.21 14.99 14.80 14.63 14.64 12.8000 14.29 14.14 13.99 13.85 13.72 12.8500 13.60 13.47 13.35 13.24 <t< th=""><th></th><th></th><th></th><th></th><th></th><th></th></t<>						
12.2500 65.78 62.25 58.74 56.13 53.53 12.3000 50.93 48.64 46.69 44.74 42.78 12.3500 41.24 39.72 38.20 36.81 35.61 12.4000 34.41 33.21 32.21 31.24 30.27 12.5000 25.57 24.89 24.24 23.65 23.07 12.5500 22.48 21.96 21.45 20.95 20.46 12.6000 20.02 19.58 19.15 18.75 20.95 20.46 12.6000 18.00 17.63 17.31 17.00 16.68 12.7000 16.40 16.14 15.88 15.63 15.42 12.7500 15.21 14.99 14.80 14.63 14.46 12.8500 13.60 13.47 13.35 13.24 13.14 12.9000 13.03 12.92 12.82 12.72 12.61 12.9500 12.51 12.42 12.32 12.23						
12.3000 50.93 48.64 46.69 44.74 42.78 12.3500 41.24 39.72 38.20 36.81 35.61 12.4500 29.35 28.55 27.75 26.95 26.25 12.5000 25.57 24.89 24.24 23.65 23.07 12.5500 22.48 21.96 21.45 20.95 20.46 12.6500 18.00 17.63 17.31 17.00 16.80 12.7000 16.40 16.14 15.88 15.63 15.42 12.7500 15.21 14.99 14.80 14.63 14.46 12.8000 14.29 14.14 13.99 13.85 13.72 12.8500 13.60 13.47 13.35 13.24 12.24 12.9900 13.03 12.92 12.82 12.72 12.61 12.9500 12.51 12.42 12.32 12.23 12.13 13.0000 12.04 11.95 11.86 11.77 <t< th=""><th></th><th></th><th></th><th></th><th></th><th></th></t<>						
12.3500 41.24 39.72 38.20 36.81 35.61 12.4000 34.41 33.21 32.21 31.24 30.27 12.4500 29.35 28.55 27.75 26.95 26.25 12.5000 25.57 24.89 24.24 23.65 23.07 12.5500 22.48 21.96 21.45 20.95 20.46 12.6000 20.02 19.58 19.15 18.75 18.37 12.6500 18.00 17.63 17.31 17.00 16.68 12.7000 16.40 16.14 15.88 15.63 15.42 12.8000 14.29 14.14 13.99 13.85 13.72 12.8500 13.60 13.47 13.35 13.24 13.14 12.9000 13.03 12.92 12.82 12.72 12.61 12.9500 12.51 12.42 12.32 12.23 12.13 13.0000 11.59 11.50 11.42 11.33 <t< td=""><td></td><td></td><td></td><td></td><td></td><td></td></t<>						
12.4000 34.41 33.21 32.21 31.24 30.27 12.4500 29.35 28.55 27.75 26.95 26.25 12.5000 25.57 24.89 24.24 23.65 23.07 12.5500 22.48 21.96 21.45 20.95 20.46 12.6000 20.02 19.58 19.15 18.75 18.37 12.6500 18.00 17.63 17.31 17.00 16.68 12.7000 16.40 16.14 15.88 15.63 15.42 12.7500 15.21 14.99 14.80 14.63 14.46 12.8000 14.29 14.14 13.99 13.85 13.72 12.8500 13.60 13.47 13.35 13.24 13.14 12.9000 13.03 12.92 12.82 12.72 12.61 12.9500 12.51 12.42 12.32 12.23 12.13 13.0500 11.59 11.50 11.42 11.33 <t< th=""><th></th><th></th><th></th><th></th><th></th><th></th></t<>						
12.4500 29.35 28.55 27.75 26.95 26.25 12.5000 25.57 24.89 24.24 23.65 23.07 12.5500 22.48 21.96 21.45 20.95 20.46 12.6500 18.00 17.63 17.31 17.00 16.68 12.7000 16.40 16.14 15.88 15.63 15.42 12.7500 15.21 14.99 14.80 14.63 14.46 12.8000 14.29 14.14 13.99 13.85 13.72 12.8500 13.03 12.92 12.82 12.72 12.61 12.9500 12.51 12.42 12.32 12.23 12.13 13.0000 12.04 11.95 11.86 11.77 11.67 13.0500 11.59 11.50 11.42 11.33 11.25 13.1000 11.17 11.09 11.01 10.93 10.86 13.1500 10.78 10.71 10.64 10.57 <t< th=""><th></th><th></th><th></th><th></th><th></th><th></th></t<>						
12.5000 25.57 24.89 24.24 23.65 23.07 12.5500 22.48 21.96 21.45 20.95 20.46 12.6000 20.02 19.58 19.15 18.75 18.37 12.6500 18.00 17.63 17.31 17.00 16.68 12.7000 16.40 16.14 15.88 15.63 15.42 12.7500 15.21 14.99 14.80 14.63 14.46 12.8000 14.29 14.14 13.99 13.85 13.72 12.8500 13.60 13.47 13.35 13.24 13.14 12.9900 13.03 12.92 12.82 12.72 12.61 12.9500 12.51 12.42 12.32 12.23 12.23 13.0500 11.59 11.50 11.42 11.33 11.25 13.1000 11.17 11.09 11.01 10.93 10.86 13.2500 10.78 10.71 10.64 10.57 <t< td=""><td></td><td></td><td></td><td></td><td></td><td></td></t<>						
12.5500 22.48 21.96 21.45 20.95 20.46 12.6000 20.02 19.58 19.15 18.75 18.37 12.6500 18.00 17.63 17.31 17.00 16.68 12.7000 16.40 16.14 15.88 15.63 15.42 12.7500 15.21 14.99 14.80 14.63 14.46 12.8000 14.29 14.14 13.99 13.85 13.72 12.8500 13.60 13.47 13.35 13.24 13.14 12.9000 13.03 12.92 12.82 12.72 12.61 12.9500 12.51 12.42 12.32 12.23 12.13 13.0000 11.59 11.50 11.42 11.33 11.25 13.1000 11.17 11.09 11.01 10.93 10.86 13.2000 10.44 10.37 10.31 10.25 10.19 13.2500 10.13 10.07 10.02 9.96 <td< td=""><td></td><td></td><td></td><td></td><td></td><td></td></td<>						
12.6000 20.02 19.58 19.15 18.75 18.37 12.6500 18.00 17.63 17.31 17.00 16.68 12.7000 16.40 16.14 15.88 15.63 15.42 12.7500 15.21 14.99 14.80 14.63 14.46 12.8000 14.29 14.14 13.99 13.85 13.72 12.8500 13.60 13.47 13.35 13.24 13.14 12.9000 13.03 12.92 12.82 12.72 12.61 12.9500 12.51 12.42 12.32 12.23 12.13 13.0000 12.04 11.95 11.86 11.77 11.67 13.0500 11.59 11.50 11.42 11.33 11.25 13.1000 11.17 11.09 11.01 10.93 10.86 13.2000 10.44 10.37 10.31 10.25 10.19 13.2500 10.13 10.07 10.02 9.96 <td< td=""><td></td><td></td><td></td><td></td><td></td><td></td></td<>						
12.6500 18.00 17.63 17.31 17.00 16.68 12.7000 16.40 16.14 15.88 15.63 15.42 12.7500 15.21 14.99 14.80 14.63 14.46 12.8000 14.29 14.14 13.99 13.85 13.72 12.8500 13.60 13.47 13.35 13.24 13.14 12.9000 13.03 12.92 12.82 12.72 12.61 12.9500 12.51 12.42 12.32 12.23 12.13 13.0000 12.04 11.95 11.86 11.77 11.67 13.0500 11.159 11.50 11.42 11.33 11.25 13.1000 10.78 10.71 10.64 10.57 10.50 13.2000 10.44 10.37 10.31 10.25 10.19 13.2500 10.13 10.07 10.02 9.96 9.91 13.3000 9.85 9.80 9.75 9.69 9.6						
12.7000 16.40 16.14 15.88 15.63 15.42 12.7500 15.21 14.99 14.80 14.63 14.46 12.8000 14.29 14.14 13.99 13.85 13.72 12.8500 13.60 13.47 13.35 13.24 13.14 12.9000 13.03 12.92 12.82 12.72 12.61 12.9500 12.51 12.42 12.32 12.23 12.13 13.0000 12.04 11.95 11.86 11.77 11.67 13.0500 11.59 11.50 11.42 11.33 11.25 13.1000 11.17 11.09 11.01 10.93 10.86 13.2500 10.78 10.71 10.64 10.57 10.50 13.2500 10.13 10.07 10.02 9.96 9.91 13.3500 9.85 9.80 9.75 9.69 9.64 13.3500 9.35 9.30 9.25 9.20 9.15						
12.7500 15.21 14.99 14.80 14.63 14.46 12.8000 14.29 14.14 13.99 13.85 13.72 12.8500 13.60 13.47 13.35 13.24 13.14 12.9000 13.03 12.92 12.82 12.72 12.61 12.9500 12.51 12.42 12.32 12.23 12.13 13.0000 12.04 11.95 11.86 11.77 11.67 13.0500 11.59 11.50 11.42 11.33 11.25 13.1500 10.78 10.71 10.64 10.57 10.50 13.2000 10.44 10.37 10.31 10.25 10.19 13.3000 9.85 9.80 9.75 9.69 9.94 13.3500 9.85 9.80 9.75 9.69 9.64 13.4500 9.11 9.06 9.01 8.96 8.92 13.5000 8.87 8.82 8.78 8.73 8.68 <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>						
12.8000 14.29 14.14 13.99 13.85 13.72 12.8500 13.60 13.47 13.35 13.24 13.14 12.9000 13.03 12.92 12.82 12.72 12.61 12.9500 12.51 12.42 12.32 12.23 12.13 13.0000 12.04 11.95 11.86 11.77 11.67 13.0500 11.59 11.50 11.42 11.33 11.25 13.1000 11.17 11.09 11.01 10.93 10.86 13.1500 10.78 10.71 10.64 10.57 10.50 13.2000 10.44 10.37 10.31 10.25 10.19 13.3500 10.13 10.07 10.02 9.96 9.91 13.3500 9.85 9.80 9.75 9.69 9.64 13.4500 9.11 9.06 9.01 8.96 8.92 13.5000 8.87 8.82 8.78 8.73 8.68 13.5500 8.64 8.59 8.55 8.50 8.46 <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>						
12.8500 13.60 13.47 13.35 13.24 13.14 12.9000 13.03 12.92 12.82 12.72 12.61 12.9500 12.51 12.42 12.32 12.23 12.13 13.0000 12.04 11.95 11.86 11.77 11.67 13.0500 11.59 11.50 11.42 11.33 11.25 13.1000 11.17 11.09 11.01 10.93 10.86 13.1500 10.78 10.71 10.64 10.57 10.50 13.2000 10.44 10.37 10.31 10.25 10.19 13.3000 9.85 9.80 9.75 9.69 9.64 13.3500 9.85 9.80 9.75 9.69 9.64 13.4000 9.35 9.30 9.25 9.20 9.15 13.4500 9.11 9.06 9.01 8.96 8.92 13.5000 8.87 8.82 8.78 8.73 8.68						
12.9000 13.03 12.92 12.82 12.72 12.61 12.9500 12.51 12.42 12.32 12.23 12.13 13.0000 12.04 11.95 11.86 11.77 11.67 13.0500 11.59 11.50 11.42 11.33 11.25 13.1000 11.17 11.09 11.01 10.93 10.86 13.1500 10.78 10.71 10.64 10.57 10.50 13.2000 10.44 10.37 10.31 10.25 10.19 13.3000 9.85 9.80 9.75 9.69 9.64 13.3500 9.59 9.54 9.49 9.44 9.40 13.4000 9.35 9.30 9.25 9.20 9.15 13.5000 8.87 8.82 8.78 8.73 8.68 13.5000 8.87 8.82 8.78 8.73 8.68 13.5000 8.41 8.37 8.32 8.28 8.24 <tr< td=""><td></td><td></td><td></td><td></td><td></td><td></td></tr<>						
12.9500 12.51 12.42 12.32 12.23 12.13 13.0000 12.04 11.95 11.86 11.77 11.67 13.0500 11.59 11.50 11.42 11.33 11.25 13.1000 11.17 11.09 11.01 10.93 10.86 13.1500 10.78 10.71 10.64 10.57 10.50 13.2000 10.44 10.37 10.31 10.25 10.19 13.2500 10.13 10.07 10.02 9.96 9.91 13.3000 9.85 9.80 9.75 9.69 9.64 13.3500 9.59 9.54 9.49 9.44 9.40 13.4000 9.35 9.30 9.25 9.20 9.15 13.4500 9.11 9.06 9.01 8.96 8.92 13.5000 8.87 8.82 8.78 8.73 8.68 13.5000 8.41 8.37 8.32 8.28 8.24						
13.0000 12.04 11.95 11.86 11.77 11.67 13.0500 11.59 11.50 11.42 11.33 11.25 13.1000 11.17 11.09 11.01 10.93 10.86 13.1500 10.78 10.71 10.64 10.57 10.50 13.2000 10.44 10.37 10.31 10.25 10.19 13.2500 10.13 10.07 10.02 9.96 9.91 13.3000 9.85 9.80 9.75 9.69 9.64 13.3500 9.59 9.54 9.49 9.44 9.40 13.4500 9.11 9.06 9.01 8.96 8.92 13.5000 8.87 8.82 8.78 8.73 8.68 13.5500 8.64 8.59 8.55 8.50 8.46 13.6000 8.41 8.37 8.32 8.28 8.24 13.6500 8.19 8.15 8.11 8.07 8.03 13.7500 7.80 7.77 7.73 7.69 7.66 <td< td=""><td></td><td></td><td></td><td></td><td></td><td></td></td<>						
13.0500 11.59 11.50 11.42 11.33 11.25 13.1000 11.17 11.09 11.01 10.93 10.86 13.1500 10.78 10.71 10.64 10.57 10.50 13.2000 10.44 10.37 10.31 10.25 10.19 13.2500 10.13 10.07 10.02 9.96 9.91 13.3000 9.85 9.80 9.75 9.69 9.64 13.3500 9.59 9.54 9.49 9.44 9.40 13.4000 9.35 9.30 9.25 9.20 9.15 13.4500 9.11 9.06 9.01 8.96 8.92 13.5000 8.87 8.82 8.78 8.73 8.68 13.5000 8.64 8.59 8.55 8.50 8.46 13.6000 8.41 8.37 8.32 8.28 8.24 13.6500 8.19 8.15 8.11 8.07 8.03 13.7000 7.99 7.95 7.92 7.88 7.84 13.8						
13.1000 11.17 11.09 11.01 10.93 10.86 13.1500 10.78 10.71 10.64 10.57 10.50 13.2000 10.44 10.37 10.31 10.25 10.19 13.2500 10.13 10.07 10.02 9.96 9.91 13.3000 9.85 9.80 9.75 9.69 9.64 13.3500 9.59 9.54 9.49 9.44 9.40 13.4000 9.35 9.30 9.25 9.20 9.15 13.4500 9.11 9.06 9.01 8.96 8.92 13.5000 8.87 8.82 8.78 8.73 8.68 13.5500 8.64 8.59 8.55 8.50 8.46 13.6500 8.41 8.37 8.32 8.28 8.24 13.7500 7.99 7.95 7.92 7.88 7.84 13.7500 7.80 7.77 7.73 7.69 7.66 13.8000 7.62 7.59 7.55 7.52 7.48 13.9500 </td <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>						
13.1500 10.78 10.71 10.64 10.57 10.50 13.2000 10.44 10.37 10.31 10.25 10.19 13.2500 10.13 10.07 10.02 9.96 9.91 13.3000 9.85 9.80 9.75 9.69 9.64 13.3500 9.59 9.54 9.49 9.44 9.40 13.4500 9.11 9.06 9.01 8.96 8.92 13.5000 8.87 8.82 8.78 8.73 8.68 13.5500 8.64 8.59 8.55 8.50 8.46 13.6000 8.41 8.37 8.32 8.28 8.24 13.6500 8.19 8.15 8.11 8.07 8.03 13.7000 7.99 7.95 7.92 7.88 7.84 13.8000 7.62 7.59 7.55 7.52 7.48 13.8500 7.45 7.41 7.38 7.35 7.31 13.9500<						
13.2000 10.44 10.37 10.31 10.25 10.19 13.2500 10.13 10.07 10.02 9.96 9.91 13.3000 9.85 9.80 9.75 9.69 9.64 13.3500 9.59 9.54 9.49 9.44 9.40 13.4000 9.35 9.30 9.25 9.20 9.15 13.4500 9.11 9.06 9.01 8.96 8.92 13.5000 8.87 8.82 8.78 8.73 8.68 13.5500 8.64 8.59 8.55 8.50 8.46 13.6000 8.41 8.37 8.32 8.28 8.24 13.6500 8.19 8.15 8.11 8.07 8.03 13.7000 7.99 7.95 7.92 7.88 7.84 13.8500 7.62 7.59 7.55 7.52 7.48 13.8500 7.45 7.41 7.38 7.35 7.31 13.9000 7.28 7.24 7.21 7.18 7.14 13.9500						
13.2500 10.13 10.07 10.02 9.96 9.91 13.3000 9.85 9.80 9.75 9.69 9.64 13.3500 9.59 9.54 9.49 9.44 9.40 13.4000 9.35 9.30 9.25 9.20 9.15 13.4500 9.11 9.06 9.01 8.96 8.92 13.5000 8.87 8.82 8.78 8.73 8.68 13.5500 8.64 8.59 8.55 8.50 8.46 13.6000 8.41 8.37 8.32 8.28 8.24 13.6500 8.19 8.15 8.11 8.07 8.03 13.7000 7.99 7.95 7.92 7.88 7.84 13.8000 7.62 7.59 7.55 7.52 7.48 13.8500 7.45 7.41 7.38 7.35 7.31 13.9000 7.28 7.24 7.21 7.18 7.14 13.9500 7.11 7.08 7.04 7.01 6.97 14.0000 6						
13.3000 9.85 9.80 9.75 9.69 9.64 13.3500 9.59 9.54 9.49 9.44 9.40 13.4000 9.35 9.30 9.25 9.20 9.15 13.4500 9.11 9.06 9.01 8.96 8.92 13.5000 8.87 8.82 8.78 8.73 8.68 13.5500 8.64 8.59 8.55 8.50 8.46 13.6000 8.41 8.37 8.32 8.28 8.24 13.6500 8.19 8.15 8.11 8.07 8.03 13.7000 7.99 7.95 7.92 7.88 7.84 13.8500 7.62 7.59 7.55 7.52 7.48 13.8500 7.45 7.41 7.38 7.35 7.31 13.9000 7.28 7.24 7.21 7.18 7.14 13.9500 7.11 7.08 7.04 7.01 6.97 14.0000 6.94 6.91 6.88 6.84 6.81						
13.3500 9.59 9.54 9.49 9.44 9.40 13.4000 9.35 9.30 9.25 9.20 9.15 13.4500 9.11 9.06 9.01 8.96 8.92 13.5000 8.87 8.82 8.78 8.73 8.68 13.5500 8.64 8.59 8.55 8.50 8.46 13.6000 8.41 8.37 8.32 8.28 8.24 13.6500 8.19 8.15 8.11 8.07 8.03 13.7000 7.99 7.95 7.92 7.88 7.84 13.8500 7.62 7.59 7.55 7.52 7.48 13.8500 7.45 7.41 7.38 7.35 7.31 13.9000 7.28 7.24 7.21 7.18 7.14 13.9500 7.11 7.08 7.04 7.01 6.97 14.0000 6.94 6.91 6.88 6.84 6.81						
13.4000 9.35 9.30 9.25 9.20 9.15 13.4500 9.11 9.06 9.01 8.96 8.92 13.5000 8.87 8.82 8.78 8.73 8.68 13.5500 8.64 8.59 8.55 8.50 8.46 13.6000 8.41 8.37 8.32 8.28 8.24 13.6500 8.19 8.15 8.11 8.07 8.03 13.7000 7.99 7.95 7.92 7.88 7.84 13.7500 7.80 7.77 7.73 7.69 7.66 13.8000 7.62 7.59 7.55 7.52 7.48 13.8500 7.45 7.41 7.38 7.35 7.31 13.9000 7.28 7.24 7.21 7.18 7.14 13.9500 7.11 7.08 7.04 7.01 6.97 14.0000 6.94 6.91 6.88 6.84 6.81						
13.4500 9.11 9.06 9.01 8.96 8.92 13.5000 8.87 8.82 8.78 8.73 8.68 13.5500 8.64 8.59 8.55 8.50 8.46 13.6000 8.41 8.37 8.32 8.28 8.24 13.6500 8.19 8.15 8.11 8.07 8.03 13.7000 7.99 7.95 7.92 7.88 7.84 13.7500 7.80 7.77 7.73 7.69 7.66 13.8000 7.62 7.59 7.55 7.52 7.48 13.8500 7.45 7.41 7.38 7.35 7.31 13.9000 7.28 7.24 7.21 7.18 7.14 13.9500 7.11 7.08 7.04 7.01 6.97 14.0000 6.94 6.91 6.88 6.84 6.81						
13.5000 8.87 8.82 8.78 8.73 8.68 13.5500 8.64 8.59 8.55 8.50 8.46 13.6000 8.41 8.37 8.32 8.28 8.24 13.6500 8.19 8.15 8.11 8.07 8.03 13.7000 7.99 7.95 7.92 7.88 7.84 13.7500 7.80 7.77 7.73 7.69 7.66 13.8000 7.62 7.59 7.55 7.52 7.48 13.8500 7.45 7.41 7.38 7.35 7.31 13.9000 7.28 7.24 7.21 7.18 7.14 13.9500 7.11 7.08 7.04 7.01 6.97 14.0000 6.94 6.91 6.88 6.84 6.81						
13.5500 8.64 8.59 8.55 8.50 8.46 13.6000 8.41 8.37 8.32 8.28 8.24 13.6500 8.19 8.15 8.11 8.07 8.03 13.7000 7.99 7.95 7.92 7.88 7.84 13.7500 7.80 7.77 7.73 7.69 7.66 13.8000 7.62 7.59 7.55 7.52 7.48 13.8500 7.45 7.41 7.38 7.35 7.31 13.9000 7.28 7.24 7.21 7.18 7.14 13.9500 7.11 7.08 7.04 7.01 6.97 14.0000 6.94 6.91 6.88 6.84 6.81						
13.6000 8.41 8.37 8.32 8.28 8.24 13.6500 8.19 8.15 8.11 8.07 8.03 13.7000 7.99 7.95 7.92 7.88 7.84 13.7500 7.80 7.77 7.73 7.69 7.66 13.8000 7.62 7.59 7.55 7.52 7.48 13.8500 7.45 7.41 7.38 7.35 7.31 13.9000 7.28 7.24 7.21 7.18 7.14 13.9500 7.11 7.08 7.04 7.01 6.97 14.0000 6.94 6.91 6.88 6.84 6.81						
13.6500 8.19 8.15 8.11 8.07 8.03 13.7000 7.99 7.95 7.92 7.88 7.84 13.7500 7.80 7.77 7.73 7.69 7.66 13.8000 7.62 7.59 7.55 7.52 7.48 13.8500 7.45 7.41 7.38 7.35 7.31 13.9000 7.28 7.24 7.21 7.18 7.14 13.9500 7.11 7.08 7.04 7.01 6.97 14.0000 6.94 6.91 6.88 6.84 6.81						
13.7000 7.99 7.95 7.92 7.88 7.84 13.7500 7.80 7.77 7.73 7.69 7.66 13.8000 7.62 7.59 7.55 7.52 7.48 13.8500 7.45 7.41 7.38 7.35 7.31 13.9000 7.28 7.24 7.21 7.18 7.14 13.9500 7.11 7.08 7.04 7.01 6.97 14.0000 6.94 6.91 6.88 6.84 6.81						
13.7500 7.80 7.77 7.73 7.69 7.66 13.8000 7.62 7.59 7.55 7.52 7.48 13.8500 7.45 7.41 7.38 7.35 7.31 13.9000 7.28 7.24 7.21 7.18 7.14 13.9500 7.11 7.08 7.04 7.01 6.97 14.0000 6.94 6.91 6.88 6.84 6.81						
13.8000 7.62 7.59 7.55 7.52 7.48 13.8500 7.45 7.41 7.38 7.35 7.31 13.9000 7.28 7.24 7.21 7.18 7.14 13.9500 7.11 7.08 7.04 7.01 6.97 14.0000 6.94 6.91 6.88 6.84 6.81						
13.8500 7.45 7.41 7.38 7.35 7.31 13.9000 7.28 7.24 7.21 7.18 7.14 13.9500 7.11 7.08 7.04 7.01 6.97 14.0000 6.94 6.91 6.88 6.84 6.81						
13.9000 7.28 7.24 7.21 7.18 7.14 13.9500 7.11 7.08 7.04 7.01 6.97 14.0000 6.94 6.91 6.88 6.84 6.81						
13.9500 7.11 7.08 7.04 7.01 6.97 14.0000 6.94 6.91 6.88 6.84 6.81						
14.0000 6.94 6.91 6.88 6.84 6.81						
	14.0500	6.78	6.75	6.71	6.68	6.65
14.1000 6.62 6.60 6.57 6.54 6.51						
14.1500 6.49 6.46 6.41 6.39						
14.2000 6.37 6.35 6.32 6.31 6.29						
14.2500 6.27 6.25 6.23 6.21 6.20	14.2500	6.27	6.25	6.23	6.21	6.20

Discovery_Park_Ph-1_Macro_Ex-Cond.ppc 1/10/2023

Bentley Systems, Inc. Haestad Methods Solution Center 27 Siemon Company Drive Suite 200 W Watertown, CT 06795 USA +1-203-755-1666 PondPack CONNECT Edition [10.02.00.01] Page 74 of 131

Subsection: Unit Hydrograph (Hydrograph Table) Return Event: 2 years
Label: D-5 Storm Event: 2-Yr (TP-40)

Scenario: 2-Yr (TP-40)

HYDROGRAPH ORDINATES (ft³/s) Output Time Increment = 0.0100 hours Time on left represents time for first value in each row.

	-	oresents time			
Time	Flow	Flow	Flow	Flow	Flow
(hours)	(ft³/s)	(ft³/s)	(ft³/s)	(ft³/s)	(ft³/s)
14.3000	6.18	6.17	6.15	6.14	6.12
14.3500	6.11	6.09	6.08	6.07	6.05
14.4000	6.04	6.03	6.02	6.00	5.99
14.4500	5.98	5.96	5.95	5.94	5.93
14.5000	5.92	5.90	5.89	5.88	5.87
14.5500	5.86	5.85	5.83	5.82	5.81
14.6000	5.80	5.79	5.77	5.76	5.75
14.6500	5.74	5.73	5.72	5.70	5.69
14.7000	5.68	5.67	5.66	5.65	5.63
14.7500	5.62	5.61	5.60	5.59	5.58
14.8000	5.57	5.55	5.54	5.53	5.52
14.8500	5.51	5.50	5.48	5.47	5.46
14.9000	5.45	5.44	5.43	5.42	5.40
14.9500	5.39	5.38	5.37	5.36	5.35
15.0000	5.34	5.32	5.31	5.30	5.29
15.0500	5.28	5.27	5.25	5.24	5.23
15.1000	5.22	5.21	5.20	5.19	5.17
15.1500	5.16	5.15	5.14	5.13	5.12
15.2000	5.11	5.09	5.08	5.07	5.06
15.2500	5.05	5.03	5.02	5.01	5.00
15.3000	4.99	4.98	4.96	4.95	4.94
15.3500	4.93	4.92	4.91	4.90	4.88
15.4000	4.87	4.86	4.85	4.84	4.82
15.4500	4.81	4.80	4.79	4.78	4.77
15.5000	4.76	4.74	4.73	4.72	4.71
15.5500	4.70	4.69	4.67	4.66	4.65
15.6000	4.64	4.63	4.62	4.60	4.59
15.6500	4.58	4.57	4.56	4.55	4.53
15.7000	4.52	4.51	4.50	4.49	4.48
15.7500	4.46	4.45	4.44	4.43	4.42
15.8000	4.41	4.39	4.38	4.37	4.36
15.8500	4.35	4.33	4.32	4.31	4.30
15.9000	4.29	4.28	4.26	4.25	4.24
15.9500	4.23	4.22	4.21	4.19	4.18
16.0000	4.17	4.16	4.15	4.14	4.12
16.0500	4.11	4.10	4.09	4.08	4.07
16.1000	4.06	4.05	4.04	4.03	4.02
16.1500	4.01	4.00	3.99	3.98	3.98
16.2000	3.97	3.96	3.95	3.94	3.94
16.2500	3.93	3.92	3.92	3.91	3.91
16.3000	3.90	3.89	3.89	3.88	3.88
16.3500	3.87	3.87	3.86	3.86	3.86
16.4000	3.85	3.85	3.84	3.84	3.83
16.4500	3.83	3.82	3.82	3.81	3.81
16.5000	3.81	3.80	3.80	3.79	3.79
16.5500	3.78	3.78	3.78	3.77	3.77

Discovery_Park_Ph-1_Macro_Ex-Cond.ppc 1/10/2023

Bentley Systems, Inc. Haestad Methods Solution Center 27 Siemon Company Drive Suite 200 W Watertown, CT 06795 USA +1-203-755-1666 PondPack CONNECT Edition [10.02.00.01] Page 75 of 131

Subsection: Unit Hydrograph (Hydrograph Table) Return Event: 2 years
Label: D-5 Storm Event: 2-Yr (TP-40)

Scenario: 2-Yr (TP-40)

HYDROGRAPH ORDINATES (ft³/s) Output Time Increment = 0.0100 hours Time on left represents time for first value in each row.

	ne on left rep				
Time	Flow	Flow	Flow	Flow	Flow
(hours)	(ft³/s)	(ft³/s)	(ft³/s)	(ft³/s)	(ft³/s)
16.6000	3.76	3.76	3.75	3.75	3.75
16.6500	3.74	3.74	3.73	3.73	3.73
16.7000	3.72	3.72	3.71	3.71	3.71
16.7500	3.70	3.70	3.69	3.69	3.69
16.8000	3.68	3.68	3.67	3.67	3.66
16.8500	3.66	3.66	3.65	3.65	3.64
16.9000	3.64	3.63	3.63	3.63	3.62
16.9500	3.62	3.61	3.61	3.61	3.60
17.0000	3.60	3.59	3.59	3.59	3.58
17.0500	3.58	3.57	3.57	3.56	3.56
17.1000	3.55	3.55	3.55	3.54	3.54
17.1500	3.53	3.53	3.53	3.52	3.52
17.2000	3.51	3.51	3.50	3.50	3.50
17.2500	3.49	3.49	3.48	3.48	3.48
17.3000	3.47	3.47	3.46	3.46	3.45
17.3500	3.45	3.45	3.44	3.44	3.43
17.4000	3.43	3.43	3.42	3.42	3.41
17.4500	3.41	3.40	3.40	3.40	3.39
17.5000	3.39	3.38	3.38	3.38	3.37
17.5500	3.37	3.37	3.36	3.36	3.35
17.6000	3.35	3.34	3.34	3.34	3.33
17.6500	3.33	3.32	3.32	3.31	3.31
17.7000	3.31	3.30	3.30	3.29	3.29
17.7500	3.28	3.28	3.28	3.27	3.27
17.8000	3.26	3.26	3.25	3.25	3.25
17.8500	3.24	3.24	3.23	3.23	3.22
17.9000	3.22	3.22	3.21	3.21	3.20
17.9500	3.20	3.20	3.19	3.19	3.18
18.0000	3.18	3.17	3.17	3.17	3.16
18.0500	3.16	3.15	3.15	3.15	3.14
18.1000	3.14	3.13	3.13	3.12	3.12
18.1500	3.12	3.11	3.11	3.10	3.10
18.2000	3.10	3.09	3.09	3.08	3.08
18.2500	3.07	3.07	3.07	3.06	3.06
18.3000	3.05	3.05	3.05	3.04	3.04
18.3500	3.03	3.03	3.03	3.02	3.02
18.4000	3.01	3.01	3.00	3.00	3.00
18.4500	2.99	2.99	2.98	2.98	2.97
18.5000	2.97	2.97	2.96	2.96	2.95
18.5500	2.95	2.94	2.94	2.94	2.93
18.6000	2.93	2.92	2.92	2.91	2.91
18.6500	2.91	2.90	2.90	2.89	2.89
18.7000	2.88	2.88	2.87	2.87	2.87
18.7500	2.86	2.86	2.85	2.85	2.85
18.8000	2.84	2.84	2.83	2.83	2.83
18.8500	2.82	2.82	2.81	2.81	2.80

Discovery_Park_Ph-1_Macro_Ex-Cond.ppc 1/10/2023

Bentley Systems, Inc. Haestad Methods Solution Center 27 Siemon Company Drive Suite 200 W Watertown, CT 06795 USA +1-203-755-1666 PondPack CONNECT Edition [10.02.00.01] Page 76 of 131

Subsection: Unit Hydrograph (Hydrograph Table) Return Event: 2 years
Label: D-5 Storm Event: 2-Yr (TP-40)

Scenario: 2-Yr (TP-40)

HYDROGRAPH ORDINATES (ft³/s) Output Time Increment = 0.0100 hours Time on left represents time for first value in each row.

	-	oresents time			
Time	Flow	Flow	Flow	Flow	Flow
(hours)	(ft³/s)	(ft³/s)	(ft³/s)	(ft³/s)	(ft³/s)
18.9000	2.80	2.80	2.79	2.79	2.78
18.9500	2.78	2.77	2.77	2.77	2.76
19.0000	2.76	2.75	2.75	2.74	2.74
19.0500	2.74	2.73	2.73	2.72	2.72
19.1000	2.72	2.71	2.71	2.70	2.70
19.1500	2.70	2.69	2.69	2.68	2.68
19.2000	2.67	2.67	2.67	2.66	2.66
19.2500	2.65	2.65	2.64	2.64	2.64
19.3000	2.63	2.63	2.62	2.62	2.61
19.3500	2.61	2.61	2.60	2.60	2.59
19.4000	2.59	2.58	2.58	2.57	2.57
19.4500	2.57	2.56	2.56	2.55	2.55
19.5000	2.54	2.54	2.54	2.53	2.53
19.5500	2.52	2.52	2.51	2.51	2.51
19.6000	2.50	2.50	2.49	2.49	2.49
19.6500	2.48	2.48	2.47	2.47	2.46
19.7000	2.46	2.46	2.45	2.45	2.44
19.7500	2.44	2.44	2.43	2.43	2.42
19.8000	2.42	2.41	2.41	2.40	2.40
19.8500	2.40	2.39	2.39	2.38	2.38
19.9000	2.38	2.37	2.37	2.36	2.36
19.9500	2.36	2.35	2.35	2.34	2.34
20.0000	2.33	2.33	2.33	2.32	2.32
20.0500	2.31	2.31	2.30	2.30	2.30
20.1000	2.29	2.29	2.29	2.28	2.28
20.1500	2.28	2.27	2.27	2.27	2.26
20.2000	2.26	2.26	2.26	2.26	2.25
20.2500	2.25	2.25	2.25	2.25	2.24
20.3000	2.24	2.24	2.24	2.24	2.24
20.3500	2.24	2.23	2.23	2.23	2.23
20.4000	2.23	2.23	2.23	2.23	2.23
20.4500	2.22	2.22	2.22	2.22	2.22
20.5000	2.22	2.22	2.22	2.22	2.22
20.5500	2.22	2.21	2.21	2.21	2.21
20.6000	2.21	2.21	2.21	2.21	2.21
20.6500	2.21	2.21	2.20	2.20	2.20
20.7000	2.20	2.20	2.20	2.20	2.20
20.7500	2.20	2.20	2.20	2.20	2.20
20.8000	2.19	2.19	2.19	2.19	2.19
20.8500	2.19	2.19	2.19	2.19	2.19
20.9000	2.19	2.19	2.18	2.18	2.18
20.9500	2.18	2.18	2.18	2.18	2.18
21.0000	2.18	2.18	2.18	2.17	2.17
21.0500	2.17	2.17	2.17	2.17	2.17
21.1000	2.17	2.17	2.17	2.17	2.17
21.1500	2.17	2.16	2.16	2.16	2.16
•		·			

Discovery_Park_Ph-1_Macro_Ex-Cond.ppc 1/10/2023

Bentley Systems, Inc. Haestad Methods Solution Center 27 Siemon Company Drive Suite 200 W Watertown, CT 06795 USA +1-203-755-1666 PondPack CONNECT Edition [10.02.00.01] Page 77 of 131

Subsection: Unit Hydrograph (Hydrograph Table) Return Event: 2 years
Label: D-5 Storm Event: 2-Yr (TP-40)

Scenario: 2-Yr (TP-40)

HYDROGRAPH ORDINATES (ft³/s) Output Time Increment = 0.0100 hours Time on left represents time for first value in each row.

		oresents time			
Time	Flow	Flow	Flow	Flow	Flow
(hours)	(ft³/s)	(ft³/s)	(ft³/s)	(ft³/s)	(ft³/s)
21.2000	2.16	2.16	2.16	2.16	2.16
21.2500	2.16	2.16	2.16	2.15	2.15
21.3000	2.15	2.15	2.15	2.15	2.15
21.3500	2.15	2.15	2.15	2.15	2.15
21.4000	2.14	2.14	2.14	2.14	2.14
21.4500	2.14	2.14	2.14	2.14	2.14
21.5000	2.14	2.14	2.13	2.13	2.13
21.5500	2.13	2.13	2.13	2.13	2.13
21.6000	2.13	2.13	2.13	2.13	2.13
21.6500	2.12	2.12	2.12	2.12	2.12
21.7000	2.12	2.12	2.12	2.12	2.12
21.7500	2.12	2.12	2.11	2.11	2.11
21.8000	2.11	2.11	2.11	2.11	2.11
21.8500	2.11	2.11	2.11	2.10	2.10
21.9000	2.10	2.10	2.10	2.10	2.10
21.9500	2.10	2.10	2.10	2.10	2.10
22.0000	2.10	2.09	2.09	2.09	2.09
22.0500	2.09	2.09	2.09	2.09	2.09
22.1000	2.09	2.09	2.09	2.08	2.08
22.1500	2.08	2.08	2.08	2.08	2.08
22.2000	2.08	2.08	2.08	2.08	2.07
22.2500	2.07	2.07	2.07	2.07	2.07
22.3000	2.07	2.07	2.07	2.07	2.07
22.3500	2.07	2.07	2.06	2.06	2.06
22.4000	2.06	2.06	2.06	2.06	2.06
22.4500	2.06	2.06	2.06	2.06	2.05
22.5000	2.05	2.05	2.05	2.05	2.05
22.5500	2.05	2.05	2.05	2.05	2.05
22.6000	2.05	2.04	2.04	2.04	2.04
22.6500	2.04	2.04	2.04	2.04	2.04
22.7000	2.04	2.04	2.03	2.03	2.03
22.7500	2.03	2.03	2.03	2.03	2.03
22.8000	2.03	2.03	2.03	2.03	2.03
22.8500	2.02	2.02	2.02	2.02	2.02
22.9000	2.02	2.02	2.02	2.02	2.02
22.9500	2.02	2.02	2.01	2.01	2.01
23.0000	2.01	2.01	2.01	2.01	2.01
23.0500	2.01	2.01	2.01	2.00	2.00
23.1000	2.00	2.00	2.00	2.00	2.00
23.1500	2.00	2.00	2.00	2.00	2.00
23.2000	2.00	1.99	1.99	1.99	1.99
23.2500	1.99	1.99	1.99	1.99	1.99
23.3000	1.99	1.99	1.99	1.98	1.98
23.3500	1.98	1.98	1.98	1.98	1.98
23.4000	1.98	1.98	1.98	1.98	1.97
23.4500	1.97	1.97	1.97	1.97	1.97

Discovery_Park_Ph-1_Macro_Ex-Cond.ppc 1/10/2023

Bentley Systems, Inc. Haestad Methods Solution Center 27 Siemon Company Drive Suite 200 W Watertown, CT 06795 USA +1-203-755-1666 PondPack CONNECT Edition [10.02.00.01] Page 78 of 131

Subsection: Unit Hydrograph (Hydrograph Table) Return Event: 2 years
Label: D-5 Storm Event: 2-Yr (TP-40)

Scenario: 2-Yr (TP-40)

HYDROGRAPH ORDINATES (ft³/s) Output Time Increment = 0.0100 hours Time on left represents time for first value in each row.

	inite on left represents time for mot value in each row.					
Tir (hou		Flow (ft³/s)	Flow (ft³/s)	Flow (ft³/s)	Flow (ft³/s)	Flow (ft³/s)
•	3.5000		1.97		1.97	
		1.97	_	1.97	_	1.97
	3.5500	1.97	1.96	1.96	1.96	1.96
	3.6000	1.96	1.96	1.96	1.96	1.96
	3.6500	1.96	1.96	1.96	1.95	1.95
	3.7000	1.95	1.95	1.95	1.95	1.95
	3.7500	1.95	1.95	1.95	1.95	1.95
2	3.8000	1.94	1.94	1.94	1.94	1.94
2	3.8500	1.94	1.94	1.94	1.94	1.94
2	3.9000	1.94	1.93	1.93	1.93	1.93
2	3.9500	1.93	1.93	1.93	1.93	1.93
2	4.0000	1.92	1.92	1.91	1.89	1.88
2	4.0500	1.85	1.82	1.79	1.75	1.69
2	4.1000	1.63	1.57	1.51	1.43	1.35
2	4.1500	1.27	1.19	1.11	1.03	0.96
2	4.2000	0.88	0.81	0.74	0.68	0.62
2	4.2500	0.56	0.51	0.47	0.42	0.38
2	4.3000	0.35	0.32	0.29	0.26	0.24
2	4.3500	0.22	0.20	0.18	0.17	0.15
2	4.4000	0.14	0.13	0.11	0.10	0.09
2	4.4500	0.09	0.08	0.07	0.06	0.06
2	4.5000	0.05	0.05	0.04	0.04	0.04
2	4.5500	0.03	0.03	0.03	0.02	0.02
2	4.6000	0.02	0.02	0.02	0.01	0.01
	4.6500	0.01	0.01	0.01	0.01	0.01
	4.7000	0.01	0.01	0.00	0.00	0.00
	4.7500	0.00	0.00	0.00	0.00	0.00
	4.8000	0.00	0.00	(N/A)	(N/A)	(N/A)

Project Summary		
Title		_
Engineer		
Company		
Date	11/20/2014	
Notes		

Subsection: Outlet Input Data Return Event: 100 years Label: Basin B4 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Requested Pond Water Surface Elevations				
Minimum (Headwater) 992.0000 ft				
Increment (Headwater)	0.1000 ft			
Maximum (Headwater)	998.0000 ft			

Outlet Connectivity

Structure Type	Outlet ID	Direction	Outfall	E1 (ft)	E2 (ft)
Orifice-Area	Orifice - 1	Forward	Culvert - 1	992.0000	998.0001
Culvert-Circular	Culvert - 1	Forward	TW	981.0000	998.0001
Tailwater Settings	Tailwater			(N/A)	(N/A)

Subsection: Outlet Input Data Return Event: 100 years Label: Basin B4 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Structure ID: Orifice - 1 Structure Type: Orifice-Area	
Number of Openings	1
Elevation	992.0000 ft
Orifice Area	4.2 ft ²
Top Elevation	992.8300 ft
Datum Elevation	992.0000 ft
Orifice Coefficient	0.600
Structure ID: Culvert - 1 Structure Type: Culvert-Circular	
Number of Barrels	1
Diameter	36.0 in
Length	280.00 ft
Length (Computed Barrel)	280.04 ft
Slope (Computed)	0.018 ft/ft
Outlet Control Data	
Manning's n	0.013
Ke	0.500
Kb	0.007
Kr	0.500
Convergence Tolerance	0.0010 ft
Inlet Control Data	
Equation Form	Form 1
K	0.0098
М	2.0000
С	0.0398
Υ	0.6700
T1 ratio (HW/D)	1.151
T2 ratio (HW/D)	1.298
Slope Correction Factor	-0.500
Slope Correction ractor	0.500

Use unsubmerged inlet control 0 equation below T1 elevation.

Use submerged inlet control 0 equation above T2 elevation

In transition zone between unsubmerged and submerged inlet control, interpolate between flows at T1 & T2...

T1 Elevation	984.4539 ft	T1 Flow	42.85 ft ³ /s
T2 Elevation	984.8936 ft	T2 Flow	48.97 ft³/s

Subsection: Outlet Input Data Return Event: 100 years Label: Basin B4 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Structure ID: TW Structure Type: TW Setup, DS Channel				
Tailwater Type	Free Outfall			
Convergence Tolerances				
Maximum Iterations	30			
Tailwater Tolerance (Minimum)	0.0100 ft			
Tailwater Tolerance (Maximum)	0.5000 ft			
Headwater Tolerance (Minimum)	0.0100 ft			
Headwater Tolerance (Maximum)	0.5000 ft			
Flow Tolerance (Minimum)	0.001 ft ³ /s			
Flow Tolerance (Maximum)	10.000 ft ³ /s			

Subsection: Outlet Input Data Return Event: 100 years Label: E1 Overflow to D2 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Requested Pond Water Surface Elevations				
Minimum (Headwater)	927.1000 ft			
Increment (Headwater)	0.5000 ft			
Maximum (Headwater)	935.0000 ft			

Outlet Connectivity

Structure Type	Outlet ID	Direction	Outfall	E1 (ft)	E2 (ft)
Irregular Weir	Weir - 1	Forward	TW	931.0000	935.0001
Tailwater Settings	Tailwater			(N/A)	(N/A)

Subsection: Outlet Input Data Return Event: 100 years Label: E1 Overflow to D2 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Structure ID: Weir - 1 Structure Type: Irregular Weir

Station (ft)	Elevation (ft)
-43.42	935.00
-23.24	934.00
-18.95	933.00
-14.67	932.00
0.00	931.00
8.60	932.00
16.78	933.00
26.27	934.00
29.55	935.00

Lowest Elevation 931.0000 ft
Weir Coefficient 2.80 (ft^0.5)/s

Structure ID: TW

Structure Type: TW Setup, DS Channel

Tailwater Type	Free Outfall
Convergence Tolerances	
Maximum Iterations	30
Tailwater Tolerance (Minimum)	0.0100 ft
Tailwater Tolerance (Maximum)	0.5000 ft
Headwater Tolerance (Minimum)	0.0100 ft
Headwater Tolerance (Maximum)	0.5000 ft
Flow Tolerance (Minimum)	0.001 ft ³ /s
Flow Tolerance (Maximum)	10.000 ft ³ /s

Subsection: Outlet Input Data Return Event: 100 years Label: Highway Crossing D4 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Requested Pond Water Surface Elevations				
Minimum (Headwater) 952.0000 ft				
Increment (Headwater)	0.5000 ft			
Maximum (Headwater)	964.0000 ft			

Outlet Connectivity

Structure Type	Outlet ID	Direction	Outfall	E1 (ft)	E2 (ft)
Culvert-Box	Culvert - 1	Forward	TW	952.0000	966.0001
Tailwater Settings	Tailwater			(N/A)	(N/A)

Subsection: Outlet Input Data

Return Event: 100 years

Label: Highway Crossing D4

Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Structure ID: Culvert - 1 Structure Type: Culvert-Box	
Number of Barrels	1
Width	8.00 ft
Height	5.00 ft
Length	323.00 ft
Length (Computed Barrel)	323.02 ft
Slope (Computed)	0.012 ft/ft
Outlet Control Data	
Manning's n	0.013
Ke	0.200
Kb	0.003
Kr	0.500
Convergence Tolerance	0.0010 ft
Inlet Control Data	
Equation Form	Form 1
K	0.0045
М	2.0000
С	0.0317
Υ	0.6900
T1 ratio (HW/D)	1.136
T2 ratio (HW/D)	1.191
Slope Correction Factor	-0.500

Use unsubmerged inlet control 0 equation below T1 elevation.

Use submerged inlet control 0 equation above T2 elevation

In transition zone between unsubmerged and submerged inlet control,

interpolate between flows at T1 & T2...

T1 Elevation	957.6806 ft	T1 Flow	313.05 ft³/s
T2 Elevation	957.9550 ft	T2 Flow	357.77 ft³/s

Subsection: Outlet Input Data Return Event: 100 years Label: Highway Crossing D4 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

,			
Structure ID: TW Structure Type: TW Setup, DS Channel			
Tailwater Type	Free Outfall		
Convergence Tolerances			
Maximum Iterations	30		
Tailwater Tolerance (Minimum)	0.0100 ft		
Tailwater Tolerance (Maximum)	0.5000 ft		
Headwater Tolerance (Minimum)	0.0100 ft		
Headwater Tolerance (Maximum)	0.5000 ft		
Flow Tolerance (Minimum)	0.001 ft ³ /s		
Flow Tolerance (Maximum) 10.000 ft ³ /s			

Subsection: Outlet Input Data Return Event: 100 years Label: Inlet C2 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Requested Pond Water Surface Elevations			
Minimum (Headwater) 956.8500 ft			
Increment (Headwater)	0.1000 ft		
Maximum (Headwater)	972.0000 ft		

Outlet Connectivity

Structure Type	Outlet ID	Direction	Outfall	E1 (ft)	E2 (ft)
Orifice-Area	Grate Inlet	Forward	66" RCP	956.8500	972.0001
Culvert-Circular	66" RCP	Forward	TW	945.7000	972.0001
Tailwater Settings	Tailwater			(N/A)	(N/A)

Subsection: Outlet Input Data Return Event: 100 years Label: Inlet C2 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

0, , , , , , , , , , , ,			
Structure ID: Grate Inlet Structure Type: Orifice-Area			
Number of Openings	1		
Elevation	956.8500 ft		
Orifice Area	27.2 ft ²		
Top Elevation	0.0000 ft		
Datum Elevation	0.0000 ft		
Orifice Coefficient	0.600		
Structure ID: 66" RCP Structure Type: Culvert-Circular			
Number of Barrels	1		
Diameter	66.0 in		
Length	177.00 ft		
Length (Computed Barrel)	177.00 ft		
Slope (Computed)	0.003 ft/ft		
Outlet Control Data			
Manning's n	0.013		
Ke	0.200		
Kb	0.003		
Kr	0.500		
Convergence Tolerance	0.0010 ft		
Inlet Control Data			
Equation Form	Form 1		
K	0.0045		
М	2.0000		
С	0.0317		
Υ	0.6900		
T1 ratio (HW/D)	1.094		
T2 ratio (HW/D)	1.196		
Slope Correction Factor	-0.500		
K M C Y	0.0045 2.0000 0.0317 0.6900		

Use unsubmerged inlet control 0 equation below T1 elevation.

Use submerged inlet control 0 equation above T2 elevation

In transition zone between unsubmerged and submerged inlet control, interpolate between flows at T1 & T2...

T1 Elevation	951.7149 ft	T1 Flow	195.01 ft³/s
T2 Elevation	952.2753 ft	T2 Flow	222.87 ft³/s

Subsection: Outlet Input Data Return Event: 100 years Label: Inlet C2 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Structure ID: TW Structure Type: TW Setup, DS Channel				
Tailwater Type	Free Outfall			
Convergence Tolerances				
Maximum Iterations	30			
Tailwater Tolerance (Minimum)	0.0100 ft			
Tailwater Tolerance (Maximum)	0.5000 ft			
Headwater Tolerance (Minimum)	0.0100 ft			
Headwater Tolerance (Maximum)	0.5000 ft			
Flow Tolerance (Minimum)	0.001 ft ³ /s			
Flow Tolerance (Maximum)	10.000 ft ³ /s			

Subsection: Outlet Input Data

Return Event: 100 years

Label: Pt. A3 Drive Culverts

Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Requested Pond Water Surface Elevations			
Minimum (Headwater)	900.8100 ft		
Increment (Headwater)	0.1000 ft		
Maximum (Headwater)	912.0000 ft		

Outlet Connectivity

Structure Type	Outlet ID	Direction	Outfall	E1 (ft)	E2 (ft)
Culvert-Circular	Culvert - 1	Forward	TW	900.8100	912.0001
Irregular Weir	Weir - 1	Forward	TW	907.2400	912.0001
Tailwater Settings	Tailwater			(N/A)	(N/A)

Subsection: Outlet Input Data

Return Event: 100 years

Label: Pt. A3 Drive Culverts

Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Structure ID: Culvert - 1 Structure Type: Culvert-Circular	
Number of Barrels	1
Diameter	84.0 in
Length	66.60 ft
Length (Computed Barrel)	66.60 ft
Slope (Computed)	0.006 ft/ft
Outlet Control Data	
Manning's n	0.026
Ke	0.200
Kb	0.009
Kr	0.500
Convergence Tolerance	0.0010 ft
Inlet Control Data	
Equation Form	Form 1
K	0.0045
М	2.0000
С	0.0317
Υ	0.6900
T1 ratio (HW/D)	1.092
T2 ratio (HW/D)	1.194
Slope Correction Factor	-0.500

Use unsubmerged inlet control 0 equation below T1 elevation.

Use submerged inlet control 0 equation above T2 elevation

In transition zone between unsubmerged and submerged inlet control, interpolate between flows at T1 & T2...

T1 E	Elevation	908.4573 ft	T1 Flow	356.37 ft ³ /s
T2 E	Elevation	909.1704 ft	T2 Flow	407.28 ft ³ /s

Subsection: Outlet Input Data

Return Event: 100 years

Label: Pt. A3 Drive Culverts

Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Structure ID: Weir - 1
Structure Type: Irregular Weir

ociaccaic iypci	cg a.c	
Station (ft)		Elevation (ft)
	0.00	912.00
	22.00	910.00
	43.10	908.52
	76.73	907.24
	124.40	907.44
	157.13	908.16
	223.83	908.35
	251.00	908.60
	265.18	909.00
	270.32	910.00
	277.43	912.00

Lowest Elevation 907.2400 ft
Weir Coefficient 2.80 (ft^0.5)/s

Structure ID: TW Structure Type: TW Setup, DS Channel

Tailwater Type	Free Outfall		
Convergence Tolerances			
Maximum Iterations	30		
Tailwater Tolerance (Minimum)	0.0100 ft		
Tailwater Tolerance (Maximum)	0.5000 ft		
Headwater Tolerance (Minimum)	0.0100 ft		
Headwater Tolerance (Maximum)	0.5000 ft		
Flow Tolerance (Minimum)	0.001 ft ³ /s		
Flow Tolerance (Maximum)	10.000 ft ³ /s		

Subsection: Outlet Input Data Return Event: 100 years Label: Pt. A5 Former Pond Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Requested Pond Water Surface Elevations			
Minimum (Headwater) 929.0000 ft			
Increment (Headwater)	0.1000 ft		
Maximum (Headwater)	940.0000 ft		

Outlet Connectivity

Structure Type	Outlet ID	Direction	Outfall	E1 (ft)	E2 (ft)
Irregular Weir	Weir - 1	Forward	TW	929.0000	940.0001
Tailwater Settings	Tailwater			(N/A)	(N/A)

Subsection: Outlet Input Data Return Event: 100 years Label: Pt. A5 Former Pond Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Structure ID: Weir - 1 Structure Type: Irregular Weir

Station (ft)	Elevation (ft)
0.00	940.00
23.88	938.00
64.85	936.00
167.91	934.00
238.10	932.00
246.58	930.00
251.38	929.00
253.10	929.00
257.52	930.00
263.49	932.00
268.12	934.00
273.30	936.00
297.08	938.00
333.50	940.00

Lowest Elevation 929.0000 ft
Weir Coefficient 2.80 (ft^0.5)/s

Structure ID: TW Structure Type: TW Setup, DS Channel

Tailwater Type	Free Outfall			
Convergence Tolerances				
Maximum Iterations	30			
Tailwater Tolerance (Minimum)	0.0100 ft			
Tailwater Tolerance (Maximum)	0.5000 ft			
Headwater Tolerance (Minimum)	0.0100 ft			
Headwater Tolerance (Maximum)	0.5000 ft			
Flow Tolerance (Minimum)	0.001 ft ³ /s			
Flow Tolerance (Maximum)	10.000 ft ³ /s			

Subsection: Outlet Input Data Return Event: 100 years Label: RCB Sta,. 25+65 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Requested Pond Water Surface Elevations		
Minimum (Headwater) 945.3000 ft		
Increment (Headwater)	0.1000 ft	
Maximum (Headwater)	958.0000 ft	

Outlet Connectivity

Structure Type	Outlet ID	Direction	Outfall	E1 (ft)	E2 (ft)
Culvert-Box	RCB: 13 x 7 x 125.8'	Forward	TW	945.3000	958.0001
Irregular Weir	Roadway Weir	Forward	TW	955.6500	958.0001
Tailwater Settings	Tailwater			(N/A)	(N/A)

Subsection: Outlet Input Data Return Event: 100 years Label: RCB Sta,. 25+65 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Structure ID: RCB: 13 x 7 x 125.8' Structure Type: Culvert-Box	
Number of Barrels	1
Width	13.00 ft
Height	7.00 ft
Length	125.80 ft
Length (Computed Barrel)	126.04 ft
Slope (Computed)	0.062 ft/ft
Outlet Control Data	
Manning's n	0.013
Ke	0.200
Kb	0.002
Kr	0.500
Convergence Tolerance	0.0010 ft
Inlet Control Data	
Equation Form	Form 2
K	0.4860
М	0.6670
С	0.0249
Υ	0.8300
T1 ratio (HW/D)	1.121
T2 ratio (HW/D)	1.197
Slope Correction Factor	-0.500

Use unsubmerged inlet control 1 equation below T1 elevation.

Use submerged inlet control 1 equation above T2 elevation

In transition zone between unsubmerged and submerged inlet control,

interpolate between flows at T1 & T2...

T1 Elevation	953.1456 ft	T1 Flow	842.67 ft³/s
T2 Elevation	953.6818 ft	T2 Flow	963.05 ft³/s

Subsection: Outlet Input Data Return Event: 100 years Label: RCB Sta,. 25+65 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Structure ID: Roadway Weir Structure Type: Irregular Weir

	9
Station (ft)	Elevation (ft)
0	0.00 958.00
46	16.50 957.00
118	8.20 956.00
206	06.10 955.65
276	76.80 956.00
345	15.40 957.00
392	92.40 958.00

Lowest Elevation 955.6500 ft
Weir Coefficient 2.60 (ft^0.5)/s

Structure ID: TW

Structure Type: TW Setup, DS Channel

Tailwater Type	Free Outfall
Convergence Tolerances	
Maximum Iterations	30
Tailwater Tolerance (Minimum)	0.0100 ft
Tailwater Tolerance (Maximum)	0.5000 ft
Headwater Tolerance (Minimum)	0.0100 ft
Headwater Tolerance (Maximum)	0.5000 ft
Flow Tolerance (Minimum)	0.001 ft ³ /s
Flow Tolerance (Maximum)	10.000 ft ³ /s

Subsection: Outlet Input Data Return Event: 100 years Label: RCB Sta. 45+15 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Requested Pond Water Surface Elevations		
Minimum (Headwater)	916.2200 ft	
Increment (Headwater)	0.1000 ft	
Maximum (Headwater) 930.0000 ft		

Structure Type	Outlet ID	Direction	Outfall	E1 (ft)	E2 (ft)
Culvert-Box	RCB: 2x 10 x 7 x 174.4'	Forward	TW	916.2200	930.0001
Irregular Weir	Roadway Weir	Forward	TW	928.6800	930.0001
Tailwater Settings	Tailwater			(N/A)	(N/A)

Subsection: Outlet Input Data Return Event: 100 years Label: RCB Sta. 45+15 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Structure ID: RCB: 2x 10 x 7 x 174.4' Structure Type: Culvert-Box	
Number of Barrels	2
Width	10.00 ft
Height	7.00 ft
Length	174.40 ft
Length (Computed Barrel)	174.46 ft
Slope (Computed)	0.027 ft/ft
Outlet Control Data	
Manning's n	0.013
Ke	0.400
Kb	0.002
Kr	0.500
Convergence Tolerance	0.0010 ft
Inlet Control Data	
Equation Form	Form 2
K	0.5450
М	0.6670
С	0.0451
Υ	0.7300
T1 ratio (HW/D)	1.257
T2 ratio (HW/D)	1.437
Slope Correction Factor	-0.500

Use unsubmerged inlet control 1 equation below T1 elevation.

Use submerged inlet control 1 equation above T2 elevation

In transition zone between unsubmerged and submerged inlet control, interpolate between flows at T1 & T2...

 T1 Elevation
 925.0181 ft
 T1 Flow
 648.21 ft³/s

 T2 Elevation
 926.2817 ft
 T2 Flow
 740.81 ft³/s

Subsection: Outlet Input Data Return Event: 100 years Label: RCB Sta. 45+15 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Structure ID: Roadway Weir Structure Type: Irregular Weir

Station (ft)	Elevation (ft)
0.0	0 930.00
64.2	0 929.00
155.0	0 928.68
244.3	0 929.00
309.0	0 930.00

Lowest Elevation 928.6800 ft
Weir Coefficient 2.60 (ft^0.5)/s

Structure ID: TW Structure Type: TW Setu	p, DS Channel
Tailwater Type	Free Outfall

Tailwater Type Free Outfall	
Convergence Tolerances	
Maximum Iterations	30
Tailwater Tolerance (Minimum)	0.0100 ft
Tailwater Tolerance (Maximum)	0.5000 ft
Headwater Tolerance (Minimum)	0.0100 ft
Headwater Tolerance (Maximum)	0.5000 ft
Flow Tolerance (Minimum)	0.001 ft ³ /s
Flow Tolerance (Maximum)	10.000 ft ³ /s

Subsection: Outlet Input Data Return Event: 100 years Label: Road Crossing D2 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Requested Pond Water Surface Elevations		
Minimum (Headwater)	926.0400 ft	
Increment (Headwater)	0.5000 ft	
Maximum (Headwater) 935.0000 ft		

Structure Type	Outlet ID	Direction	Outfall	E1 (ft)	E2 (ft)
Culvert-Box	Culvert - 1	Forward	TW	926.0400	935.0001
Irregular Weir	Weir - 1	Forward	TW	931.0000	935.0001
Tailwater Settings	Tailwater			(N/A)	(N/A)

Subsection: Outlet Input Data Return Event: 100 years Label: Road Crossing D2 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Structure ID: Culvert - 1 Structure Type: Culvert-Box	
Number of Barrels	1
Width	10.00 ft
Height	6.00 ft
Length	40.51 ft
Length (Computed Barrel)	40.51 ft
Slope (Computed)	0.010 ft/ft
Outlet Control Data	
Manning's n	0.013
Ke	0.200
Kb	0.002
Kr	0.000
Convergence Tolerance	0.0010 ft
Inlet Control Data	
Equation Form	Form 1
K	0.0045
М	2.0000
С	0.0317
Υ	0.6900
T1 ratio (HW/D)	1.137
T2 ratio (HW/D)	1.192
Slope Correction Factor	-0.500

Use unsubmerged inlet control 0 equation below T1 elevation.

Use submerged inlet control 0 equation above T2 elevation

In transition zone between unsubmerged and submerged inlet control,

interpolate between flows at T1 & T2...

T1 Elevation	932.8650 ft	T1 Flow	514.39 ft³/s
T2 Elevation	933.1943 ft	T2 Flow	587.88 ft³/s

Subsection: Outlet Input Data Return Event: 100 years Label: Road Crossing D2 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Structure ID: Weir - 1 Structure Type: Irregular Weir

Station (ft)	Elevation (ft)
-43.42	935.00
-23.24	934.00
-18.95	933.00
-14.67	932.00
0.00	931.00
8.66	932.00
16.78	933.00
26.27	934.00
29.55	935.00

Lowest Elevation 931.0000 ft
Weir Coefficient 2.80 (ft^0.5)/s

Structure ID: TW

Structure Type: TW Setup, DS Channel

Tailwater Type	Free Outfall	
Convergence Tolerances		
Maximum Iterations	30	
Tailwater Tolerance (Minimum)	0.0100 ft	
Tailwater Tolerance (Maximum)	0.5000 ft	
Headwater Tolerance (Minimum)	0.0100 ft	
Headwater Tolerance (Maximum)	0.5000 ft	
Flow Tolerance (Minimum)	0.001 ft ³ /s	
Flow Tolerance (Maximum)	10.000 ft ³ /s	

Subsection: Outlet Input Data Return Event: 100 years Label: Road Crossing D5 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Requested Pond Water Surface Elevations			
Minimum (Headwater)	974.0000 ft		
Increment (Headwater)	0.5000 ft		
Maximum (Headwater) 986.0000 ft			

Structure Type	Outlet ID	Direction	Outfall	E1 (ft)	E2 (ft)
Culvert-Box	Culvert - 1	Forward	TW	974.0000	986.0001
Tailwater Settings	Tailwater			(N/A)	(N/A)

Subsection: Outlet Input Data Return Event: 100 years
Label: Road Crossing D5 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Structure ID: Culvert - 1 Structure Type: Culvert-Box	
Number of Barrels	1
Width	5.00 ft
Height	6.00 ft
Length	265.00 ft
Length (Computed Barrel)	265.07 ft
Slope (Computed)	0.023 ft/ft
Outlet Control Data	
Manning's n	0.013
Ke	0.200
Kb	0.003
Kr	0.500
Convergence Tolerance	0.0010 ft
Inlet Control Data	
Equation Form	Form 1
K	0.0045
M	2.0000
С	0.0317
Υ	0.6900
T1 ratio (HW/D)	1.131
T2 ratio (HW/D)	1.186
Slope Correction Factor	-0.500

Use unsubmerged inlet control 0 equation below T1 elevation.

Use submerged inlet control 0 equation above T2 elevation

In transition zone between unsubmerged and submerged inlet control, interpolate between flows at T1 & T2...

 T1 Elevation
 980.7859 ft
 T1 Flow
 257.20 ft³/s

 T2 Elevation
 981.1153 ft
 T2 Flow
 293.94 ft³/s

Subsection: Outlet Input Data Return Event: 100 years
Label: Road Crossing D5 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Structure ID: TW Structure Type: TW Setup, DS Channel				
Tailwater Type	Free Outfall			
Convergence Tolerances				
Maximum Iterations	30			
Tailwater Tolerance (Minimum)	0.0100 ft			
Tailwater Tolerance (Maximum)	0.5000 ft			
Headwater Tolerance (Minimum)	0.0100 ft			
Headwater Tolerance (Maximum)	0.5000 ft			
Flow Tolerance (Minimum)	0.001 ft ³ /s			
Flow Tolerance (Maximum)	10.000 ft ³ /s			

Subsection: Outlet Input Data Return Event: 100 years Label: Road Crossing E1 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Requested Pond Water Surface Elevations			
Minimum (Headwater)	927.1000 ft		
Increment (Headwater)	0.5000 ft		
Maximum (Headwater) 935.0000 ft			

Structure Type	Outlet ID	Direction	Outfall	E1 (ft)	E2 (ft)
Culvert-Box	Culvert - 1	Forward	TW	927.1000	935.0001
Tailwater Settings	Tailwater			(N/A)	(N/A)

Subsection: Outlet Input Data Return Event: 100 years
Label: Road Crossing E1 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Structure ID: Culvert - 1 Structure Type: Culvert-Box	
Number of Barrels	1
Width	3.00 ft
Height	4.00 ft
Length	48.89 ft
Length (Computed Barrel)	48.94 ft
Slope (Computed)	0.043 ft/ft
Outlet Control Data	
Manning's n	0.013
Ke	0.200
Kb	0.006
Kr	0.500
Convergence Tolerance	0.0010 ft
Inlet Control Data	
Equation Form	Form 1
K	0.0045
М	2.0000
С	0.0317
Υ	0.6900
T1 ratio (HW/D)	1.121
T2 ratio (HW/D)	1.176
Slope Correction Factor	-0.500

Use unsubmerged inlet control 0 equation below T1 elevation.

Use submerged inlet control 0 equation above T2 elevation

In transition zone between unsubmerged and submerged inlet control, interpolate between flows at T1 & T2...

 T1 Elevation
 931.5833 ft
 T1 Flow
 84.00 ft³/s

 T2 Elevation
 931.8029 ft
 T2 Flow
 96.00 ft³/s

Subsection: Outlet Input Data Return Event: 100 years
Label: Road Crossing E1 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Structure ID: TW Structure Type: TW Setup, DS Channel				
Tailwater Type Free Outfall				
30				
0.0100 ft				
0.5000 ft				
0.0100 ft				
0.5000 ft				
0.001 ft ³ /s				
10.000 ft ³ /s				

Subsection: Outlet Input Data Return Event: 100 years Label: Road Crossing F2 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Requested Pond Water Surface Elevations			
Minimum (Headwater)	940.6600 ft		
Increment (Headwater)	0.5000 ft		
Maximum (Headwater) 950.0000 ft			

Structure Type	Outlet ID	Direction	Outfall	E1 (ft)	E2 (ft)
Culvert-Box	Culvert - 1	Forward	TW	940.6600	950.0001
Irregular Weir	Weir - 1	Forward	TW	947.3600	950.0001
Tailwater Settings	Tailwater			(N/A)	(N/A)

Subsection: Outlet Input Data Return Event: 100 years Label: Road Crossing F2 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Structure ID: Culvert - 1 Structure Type: Culvert-Box	
Number of Barrels	1
Width	2.00 ft
Height	2.00 ft
Length	47.85 ft
Length (Computed Barrel)	47.90 ft
Slope (Computed)	0.044 ft/ft
Outlet Control Data	
Manning's n	0.013
Ke	0.200
Kb	0.012
Kr	0.500
Convergence Tolerance	0.0010 ft
Inlet Control Data	
Equation Form	Form 1
K	0.0045
М	2.0000
С	0.0317
Υ	0.6900
T1 ratio (HW/D)	1.120
T2 ratio (HW/D)	1.175
Slope Correction Factor	-0.500

Use unsubmerged inlet control 0 equation below T1 elevation.

Use submerged inlet control 0 equation above T2 elevation

In transition zone between unsubmerged and submerged inlet control,

interpolate between flows at T1 & T2...

T1 Elevation	942.9007 ft	T1 Flow	19.80 ft³/s
T2 Elevation	943.0105 ft	T2 Flow	22.63 ft³/s

Subsection: Outlet Input Data Return Event: 100 years Label: Road Crossing F2 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Structure ID: Weir - 1 Structure Type: Irregular Weir

ociaccaic iypei	09 4.10		
Station (ft)		Elevation (ft)	
	-121.53		950.00
	-91.57		949.00
	-55.98		948.00
	0.00		947.36
	75.05		948.00
	116.63		949.00
	160.45		950.00

Lowest Elevation 947.3600 ft
Weir Coefficient 2.80 (ft^0.5)/s

Structure ID: TW Structure Type: TW Setup, DS Channel

Flow Tolerance (Minimum)

Flow Tolerance (Maximum)

Tailwater Type Free Outfall Convergence Tolerances Maximum Iterations 30 Tailwater Tolerance 0.0100 ft (Minimum) Tailwater Tolerance 0.5000 ft (Maximum) **Headwater Tolerance** 0.0100 ft (Minimum) Headwater Tolerance 0.5000 ft (Maximum)

0.001 ft³/s

10.000 ft³/s

Subsection: Outlet Input Data Return Event: 100 years Label: Road Crossing G2 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Requested Pond Water Surface Elevations		
Minimum (Headwater)	944.5000 ft	
Increment (Headwater)	0.5000 ft	
Maximum (Headwater)	952.0000 ft	

Structure Type	Outlet ID	Direction	Outfall	E1 (ft)	E2 (ft)
Culvert-Box	Culvert - 1	Forward	TW	944.5000	952.0001
Irregular Weir	Weir - 1	Forward	TW	949.0000	952.0001
Tailwater Settings	Tailwater			(N/A)	(N/A)

Subsection: Outlet Input Data Return Event: 100 years Label: Road Crossing G2 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Structure ID: Culvert - 1	
Structure Type: Culvert-Box	
Number of Barrels	1
Width	2.00 ft
Height	2.00 ft
Length	39.34 ft
Length (Computed Barrel)	39.34 ft
Slope (Computed)	0.008 ft/ft
Outlet Control Data	
Manning's n	0.013
Ke	0.200
Kb	0.012
Kr	0.500
Convergence Tolerance	0.0010 ft
Inlet Control Data	
Equation Form	Form 1
K	0.0045
M	2.0000
С	0.0317
Υ	0.6900
T1 ratio (HW/D)	1.138
T2 ratio (HW/D)	1.193
Slope Correction Factor	-0.500

Use unsubmerged inlet control 0 equation below T1 elevation.

Use submerged inlet control 0 equation above T2 elevation

In transition zone between unsubmerged and submerged inlet control,

interpolate between flows at T1 & T2...

T1 Elevation	946.7767 ft	T1 Flow	19.80 ft ³ /s
T2 Elevation	946.8865 ft	T2 Flow	22.63 ft³/s

Subsection: Outlet Input Data Return Event: 100 years Label: Road Crossing G2 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Structure ID: Weir - 1 Structure Type: Irregular Weir

	- 5		
Station (ft)		Elevation (ft)	
	-150.53		952.00
	-119.12		951.00
	-78.68		950.00
	0.00		949.00
	72.91		950.00
	113.04		951.00
	141.59		952.00

Lowest Elevation 949.0000 ft
Weir Coefficient 2.80 (ft^0.5)/s

Structure ID: TW

Structure Type: TW Setup, DS Channel

Tailwater Type	Free Outfall
Convergence Tolerances	
Maximum Iterations	30
Tailwater Tolerance (Minimum)	0.0100 ft
Tailwater Tolerance (Maximum)	0.5000 ft
Headwater Tolerance (Minimum)	0.0100 ft
Headwater Tolerance (Maximum)	0.5000 ft
Flow Tolerance (Minimum)	0.001 ft ³ /s
Flow Tolerance (Maximum)	10.000 ft ³ /s

Subsection: Outlet Input Data Return Event: 100 years Label: Road Crossing H1 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Requested Pond Water Surface Elevations		
Minimum (Headwater)	908.3100 ft	
Increment (Headwater)	0.5000 ft	
Maximum (Headwater)	915.0000 ft	

Structure Type	Outlet ID	Direction	Outfall	E1 (ft)	E2 (ft)
Culvert-Circular	Culvert - 1	Forward	TW	908.3100	915.0001
Irregular Weir	Weir - 1	Forward	TW	912.0000	915.0001
Tailwater Settings	Tailwater			(N/A)	(N/A)

Subsection: Outlet Input Data Return Event: 100 years
Label: Road Crossing H1 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Structure ID: Culvert - 1 Structure Type: Culvert-Circular	
Number of Barrels	1
Diameter	36.0 in
Length	37.87 ft
Length (Computed Barrel)	38.07 ft
Slope (Computed)	0.103 ft/ft
Outlet Control Data	
Manning's n	0.026
Ke	0.200
Kb	0.029
Kr	0.500
Convergence Tolerance	0.0010 ft
Inlet Control Data	
Equation Form	Form 1
K	0.0045
M	2.0000
С	0.0317
Υ	0.6900
T1 ratio (HW/D)	1.044
T2 ratio (HW/D)	1.146
Slope Correction Factor	-0.500

Use unsubmerged inlet control 0 equation below T1 elevation.

Use submerged inlet control 0 equation above T2 elevation

In transition zone between unsubmerged and submerged inlet control, interpolate between flows at T1 & T2...

T1 Elevation	911.4411 ft	T1 Flow	42.85 ft³/s
T2 Elevation	911.7467 ft	T2 Flow	48.97 ft ³ /s

Subsection: Outlet Input Data Return Event: 100 years Label: Road Crossing H1 Storm Event: 100-Yr (TP-40)

Scenario: 100-Yr (TP-40)

Structure ID: Weir - 1 Structure Type: Irregular Weir

	-9		
Station (ft)		Elevation (ft)	
-29	98.66		915.00
-20	08.00		914.00
-15	51.01		913.00
	0.00		912.00
17	72.98		913.00
22	28.85		914.00
27	78.27		915.00

Lowest Elevation 912.0000 ft
Weir Coefficient 2.80 (ft^0.5)/s

Structure ID: TW

Structure Type: TW Setup, DS Channel

Otraditare Type. TW Octap, Bo Orianner		
Tailwater Type Free Outfall		
Convergence Tolerances		
Maximum Iterations	30	
Tailwater Tolerance (Minimum)	0.0100 ft	
Tailwater Tolerance (Maximum)	0.5000 ft	
Headwater Tolerance (Minimum)	0.0100 ft	
Headwater Tolerance (Maximum)	0.5000 ft	
Flow Tolerance (Minimum)	0.001 ft ³ /s	
Flow Tolerance (Maximum)	10.000 ft ³ /s	


Index

Α

```
A-1(e) (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...1, 2
A-1(w) (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...3, 4
A-10 (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...5, 6
A-2(e) (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...7, 8
A-2(w) (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...9, 10
A-3 (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...11, 12
A-4(e) (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...13, 14
A-4(w) (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...15, 16
A-5(e) (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...17, 18
A-5(w) (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...19, 20
A-6 (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...21, 22
A-7 (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...23, 24
A-8 (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...25, 26
A-9 (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...27, 28
В
B-1 (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...29, 30
B-2 (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...31, 32
B-3 (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...33, 34
B-4 (BYP) (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...35, 36
B-4 (DET) (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...37, 38
Basin B4 (Outlet Input Data, 100 years (100-Yr (TP-40)))...81, 82, 83
C
C-1 (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...39, 40
C-2 (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...41, 42
C-3 (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...43, 44
D
D-1 (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...45, 46
D-2 (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...47, 48
D-3 (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...49, 50
D-4 (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...51, 52
D-5 (Unit Hydrograph (Hydrograph Table), 2 years (2-Yr (TP-40)))...71, 72, 73, 74, 75,
76, 77, 78, 79
D-5 (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...53, 54
```

Е

E-1 (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...55, 56 E1 Overflow to D2 (Outlet Input Data, 100 years (100-Yr (TP-40)))...84, 85 E-2 (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...57, 58 F-1 (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...59, 60 F-2 (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...61, 62 G G-1 (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...63, 64 G-2 (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...65, 66 H-1 (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...67, 68 Highway Crossing D4 (Outlet Input Data, 100 years (100-Yr (TP-40)))...86, 87, 88 Ι I-1 (Unit Hydrograph Summary, 100 years (100-Yr (TP-40)))...69, 70 Inlet C2 (Outlet Input Data, 100 years (100-Yr (TP-40)))...89, 90, 91 Μ Master Network Summary...121, 122, 123, 124, 125, 126, 127, 128, 129 Pt. A3 Drive Culverts (Outlet Input Data, 100 years (100-Yr (TP-40)))...92, 93, 94 Pt. A5 Former Pond (Outlet Input Data, 100 years (100-Yr (TP-40)))...95, 96 R RCB Sta,. 25+65 (Outlet Input Data, 100 years (100-Yr (TP-40)))...97, 98, 99 RCB Sta. 45+15 (Outlet Input Data, 100 years (100-Yr (TP-40)))...100, 101, 102 Road Crossing D2 (Outlet Input Data, 100 years (100-Yr (TP-40)))...103, 104, 105 Road Crossing D5 (Outlet Input Data, 100 years (100-Yr (TP-40)))...106, 107, 108 Road Crossing E1 (Outlet Input Data, 100 years (100-Yr (TP-40)))...109, 110, 111 Road Crossing F2 (Outlet Input Data, 100 years (100-Yr (TP-40)))...112, 113, 114 Road Crossing G2 (Outlet Input Data, 100 years (100-Yr (TP-40)))...115, 116, 117 Road Crossing H1 (Outlet Input Data, 100 years (100-Yr (TP-40)))...118, 119, 120



DFG
Olsson
3/21/2023

Table of Contents

Master Network Summary	2
Unit Hydrograph Summary, 100 years (100-Year)	4
Unit Hydrograph Summary, 100 years (100-Year)	6
Unit Hydrograph Summary, 100 years (100-Year)	8
Unit Hydrograph Summary, 100 years (100-Year)	10
Unit Hydrograph Summary, 100 years (100-Year)	12
Unit Hydrograph Summary, 100 years (100-Year)	14
Unit Hydrograph Summary, 100 years (100-Year)	16
Unit Hydrograph Summary, 100 years (100-Year)	18
Unit Hydrograph Summary, 100 years (100-Year)	20
Unit Hydrograph Summary, 100 years (100-Year)	22
	Unit Hydrograph Summary, 100 years (100-Year)

Subsection: Master Network Summary

Catchments Summary

Label	Scenario	Return Event (years)	Hydrograph Volume (ac-ft)	Time to Peak (hours)	Peak Flow (ft³/s)
A-1(e)	100-Year	100	11.674	11.9900	187.81
A-1(w)	100-Year	100	17.597	12.0500	252.55
A-2(e)	100-Year	100	1.374	11.9300	24.63
A-2(w)	100-Year	100	8.884	12.0300	136.28
A-3	100-Year	100	11.198	11.9300	199.22
A-4(e)	100-Year	100	0.773	11.9300	13.33
A-4(w)	100-Year	100	3.239	11.9400	58.07
A-5(e)	100-Year	100	9.642	11.9300	168.25
A-5(w)	100-Year	100	19.806	11.9200	322.03
A-6	100-Year	100	6.372	11.9300	112.88
HYG-A-7	100-Year	100	44.871	12.0800	603.64
HYG-B1	100-Year	100	148.401	12.1400	1,553.02

Node Summary

•					
Label	Scenario	Return Event (years)	Hydrograph Volume (ac-ft)	Time to Peak (hours)	Peak Flow (ft³/s)
Point A1	100-Year	100	281.712	12.2400	2,524.85
Point A2	100-Year	100	253.290	12.1800	2,381.07
Point A3	100-Year	100	158.549	12.1700	1,586.54
Point A4	100-Year	100	84.703	12.1700	727.66
Point A5	100-Year	100	84.703	12.1500	728.04
Point A6	100-Year	100	6.372	11.9300	112.88
Point A7	100-Year	100	44.871	12.0800	603.64
Point B1	100-Year	100	148.401	12.1400	1,553.02

Pond Summary

Label	Scenario	Return Event (years)	Hydrograph Volume (ac-ft)	Time to Peak (hours)	Peak Flow (ft³/s)	Maximum Water Surface Elevation (ft)	Maximum Pond Storage (ac-ft)
PR-Basin (Discovery Park) (IN)	100-Year	100	84.703	12.0100	1,049.30	(N/A)	(N/A)
PR-Basin (Discovery Park) (OUT)	100-Year	100	84.703	12.1500	728.04	934.6610	21.196
Pt. A3 - Drive- Culverts (IN)	100-Year	100	158.549	12.1600	1,588.34	(N/A)	(N/A)

Subsection: Master Network Summary

Pond Summary

		_					
Label	Scenario	Return Event (years)	Hydrograph Volume (ac-ft)	Time to Peak (hours)	Peak Flow (ft³/s)	Maximum Water Surface Elevation (ft)	Maximum Pond Storage (ac-ft)
Pt. A3 - Drive- Culverts (OUT)	100-Year	100	158.549	12.1700	1,586.54	909.4948	2.839
Pt. A5 - Former Pond (IN)	100-Year	100	84.703	12.1500	728.04	(N/A)	(N/A)
Pt. A5 - Former Pond (OUT)	100-Year	100	84.703	12.1500	728.04	0.0000	0.000
WQv-Sub A1(e) (IN)	100-Year	100	11.674	11.9900	187.81	(N/A)	(N/A)
WQv-Sub A1(e) (OUT)	100-Year	100	11.184	11.9900	187.63	2.4594	0.518
WQv-Sub A1(w) (IN)	100-Year	100	17.597	12.0500	252.55	(N/A)	(N/A)
WQv-Sub A1(w) (OUT)	100-Year	100	17.237	12.0500	252.61	2.5607	0.382
WQv-Sub A2(e) (IN)	100-Year	100	1.374	11.9300	24.63	(N/A)	(N/A)
WQv-Sub A2(e) (OUT)	100-Year	100	1.344	11.9300	24.63	2.1163	0.031
WQv-Sub A2(w) (IN)	100-Year	100	8.884	12.0300	136.28	(N/A)	(N/A)
WQv-Sub A2(w) (OUT)	100-Year	100	8.694	12.0300	136.29	2.3709	0.201
WQv-Sub A3 (IN)	100-Year	100	11.198	11.9300	199.22	(N/A)	(N/A)
WQv-Sub A3 (OUT)	100-Year	100	10.148	11.9300	199.33	2.4788	1.074

Subsection: Unit Hydrograph Summary

Label: A-1(e) Scenario: 100-Year

<u>r</u>	
Storm Event	100-Year
Return Event	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration (Composite)	0.1736 hours
Area (User Defined)	1,218,273.200 ft ²
Computational Time Increment	0.0231 hours
Time to Peak (Computed)	11.9900 hours
Flow (Peak, Computed)	187.81 ft ³ /s
Output Increment	0.0100 hours
Time to Flow (Peak Interpolated Output)	11.9900 hours
Flow (Peak Interpolated Output)	187.81 ft³/s
 Drainage Area	
	77.000
SCS CN (Composite)	77.000
Area (User Defined) Maximum Retention	1,218,273.200 ft ²
(Pervious)	2.99 in
Maximum Retention (Pervious, 20 percent)	0.60 in
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	5.01 in
Runoff Volume (Pervious)	11.674 ac-ft
Hydrograph Volume (Area unde	er Hydrograph curve)
Volume	11.674 ac-ft
SCS Unit Hydrograph Paramete	ers
Time of Concentration (Composite)	0.1736 hours
S F = = ==/	
Computational Time	0.0221 have
Computational Time Increment	0.0231 hours
·	0.0231 hours 483.432
Increment Unit Hydrograph Shape	

Discovery_Park_Micro_Culvert_to_Pond_Meet_C Bentley Systems, Inc. Haestad Methods Solution C&WQ.ppc Center 6/9/2023 27 Siemon Company Drive Suite 200 W Watertown, CT 06795 USA +1-203-755-1666

PondPack CONNECT Edition [10.02.00.01] Page 4 of 24

Return Event: 100 years

Storm Event: 100-Year

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-1(e) Storm Event: 100-Year

Scenario: 100-Year

SCS Unit Hydrograph Parameters	
Unit peak, qp	182.54 ft ³ /s
Unit peak time, Tp	0.1157 hours
Unit receding limb, Tr	0.4629 hours
Total unit time, Tb	0.5787 hours

Subsection: Unit Hydrograph Summary

Label: A-1(w) Scenario: 100-Year

> Storm Event 100-Year Return Event 100 years Duration 72.0000 hours Depth 7.71 in Time of Concentration 0.2511 hours (Composite) Area (User Defined) 1,879,178,401 ft² Computational Time 0.0335 hours Increment Time to Peak (Computed) 12.0528 hours Flow (Peak, Computed) 252.68 ft3/s **Output Increment** 0.0100 hours Time to Flow (Peak 12.0500 hours Interpolated Output) Flow (Peak Interpolated 252.55 ft3/s Output) Drainage Area SCS CN (Composite) 76.000 Area (User Defined) 1,879,178.401 ft² Maximum Retention 3.16 in (Pervious) Maximum Retention 0.63 in (Pervious, 20 percent) Cumulative Runoff Cumulative Runoff Depth 4.89 in (Pervious) Runoff Volume (Pervious) 17.597 ac-ft Hydrograph Volume (Area under Hydrograph curve) 17.597 ac-ft Volume SCS Unit Hydrograph Parameters Time of Concentration 0.2511 hours (Composite) **Computational Time** 0.0335 hours Increment Unit Hydrograph Shape 483.432

> > 0.749

1.670

Receding/Rising, Tr/Tp

Factor

K Factor

Return Event: 100 years

Storm Event: 100-Year

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-1(w) Storm Event: 100-Year

Scenario: 100-Year

SCS Unit Hydrograph Parameters	
Unit peak, qp	194.66 ft³/s
Unit peak time, Tp	0.1674 hours
Unit receding limb, Tr	0.6696 hours
Total unit time, Tb	0.8370 hours

Subsection: Unit Hydrograph Summary

Label: A-2(e) Scenario: 100-Year Return Event: 100 years Storm Event: 100-Year

Storm Event	100-Year
Return Event	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration	0.1000 hours
(Composite) Area (User Defined)	134,164.800 ft ²
Area (Oser Defineu)	134,104.000 11-
Computational Time	
Increment	0.0133 hours
Time to Peak (Computed)	11.9333 hours
Flow (Peak, Computed)	24.66 ft ³ /s
Output Increment	0.0100 hours
Time to Flow (Peak	11.9300 hours
Interpolated Output)	
Flow (Peak Interpolated Output)	24.63 ft ³ /s
Drainage Area	
SCS CN (Composite)	80.000
Area (User Defined)	134,164.800 ft ²
Maximum Retention	2.50 in
(Pervious) Maximum Retention	
(Pervious, 20 percent)	0.50 in
Cumulative Runoff	
Cumulative Runoff Depth	5.35 in
(Pervious)	1 274 00 8
Runoff Volume (Pervious)	1.374 ac-ft
Hydrograph Volume (Area und	der Hydrograph curve)
Volume	1.374 ac-ft
SCS Unit Hydrograph Parama	atere
SCS Unit Hydrograph Parame	51019
Time of Concentration (Composite)	0.1000 hours
Computational Time Increment	0.0133 hours
Unit Hydrograph Shape Factor	483.432
K Factor	0.749
Receding/Rising, Tr/Tp	1.670

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-2(e) Storm Event: 100-Year

Scenario: 100-Year

SCS Unit Hydrograph Parameters	
Unit peak, qp	34.90 ft ³ /s
Unit peak time, Tp	0.0667 hours
Unit receding limb, Tr	0.2667 hours
Total unit time, Tb	0.3333 hours

Subsection: Unit Hydrograph Summary

Label: A-2(w) Scenario: 100-Year

<u>r</u>		
Storm Event	100-Year	
Return Event	100 years	
Duration	72.0000 hours	
Depth	7.71 in	
Time of Concentration (Composite)	0.2133 hours	
Area (User Defined)	1,019,739.600 ft ²	
Computational Time Increment	0.0284 hours	
Time to Peak (Computed)	12.0301 hours	
Flow (Peak, Computed)	136.29 ft ³ /s	
Output Increment	0.0100 hours	
Time to Flow (Peak Interpolated Output)	12.0300 hours	
Flow (Peak Interpolated Output)	136.28 ft³/s	
Drainage Area		
	72.000	
SCS CN (Composite)	73.000	
Area (User Defined) Maximum Retention	1,019,739.600 ft²	
(Pervious)	3.70 in	
Maximum Retention (Pervious, 20 percent)	0.74 in	
Cumulative Runoff		
Cumulative Runoff Depth (Pervious)	4.55 in	
Runoff Volume (Pervious)	8.884 ac-ft	
Hydrograph Volume (Area under Hydrograph curve)		
Volume	8.884 ac-ft	
SCS Unit Hydrograph Parameters		
Time of Concentration (Composite)	0.2133 hours	
Computational Time		
Increment	0.0284 hours	
Unit Hydrograph Shape Factor	483.432	
K Factor	0.749	
Receding/Rising, Tr/Tp	1.670	

Discovery_Park_Micro_Culvert_to_Pond_Meet_C Bentley Systems, Inc. Haestad Methods Solution C&WQ.ppc Center 6/9/2023 27 Siemon Company Drive Suite 200 W Watertown, CT 06795 USA +1-203-755-1666

Return Event: 100 years

Storm Event: 100-Year

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-2(w) Storm Event: 100-Year

Scenario: 100-Year

SCS Unit Hydrograph Parameters	
Unit peak, qp	124.35 ft ³ /s
Unit peak time, Tp	0.1422 hours
Unit receding limb, Tr	0.5688 hours
Total unit time, Tb	0.7110 hours

Subsection: Unit Hydrograph Summary

Depth

(Composite)
Area (User Defined)

(Pervious)

Runoff Volume (Pervious)

Time of Concentration

Label: A-3

Scenario: 100-Year

		Storm Event: 100-Year
Storm Event	100-Year	
Return Event	100 years	
Duration	72.0000 hours	

7.71 in

0.1000 hours

11.198 ac-ft

1,048,038.590 ft²

Computational Time Increment	0.0133 hours
Time to Peak (Computed)	11.9333 hours
Flow (Peak, Computed)	199.41 ft³/s
Output Increment	0.0100 hours
Time to Flow (Peak Interpolated Output)	11.9300 hours
Flow (Peak Interpolated Output)	199.22 ft³/s

Drainage Area	
SCS CN (Composite)	82.000
Area (User Defined)	1,048,038.590 ft ²
Maximum Retention (Pervious)	2.20 in
Maximum Retention (Pervious, 20 percent)	0.44 in
Cumulative Runoff	
Cumulative Runoff Depth	5.58 in

Hydrograph Volume (Area und	der Hydrograph curve)
Volume	11.198 ac-ft

SCS Unit Hydrograph Parameters		
Time of Concentration (Composite)	0.1000 hours	
Computational Time Increment	0.0133 hours	
Unit Hydrograph Shape Factor	483.432	
K Factor	0.749	
Receding/Rising, Tr/Tp	1.670	

Return Event: 100 years

Return Event: 100 years Subsection: Unit Hydrograph Summary Storm Event: 100-Year

Label: A-3

SCS Unit Hydrograph Parameters		
Unit peak, qp	272.61 ft³/s	
Unit peak time, Tp	0.0667 hours	
Unit receding limb, Tr	0.2667 hours	
Total unit time, Tb	0.3333 hours	

Subsection: Unit Hydrograph Summary

Label: A-4(e) Scenario: 100-Year

<u> </u>		
Storm Event	100-Year	
Return Event	100 years	
Duration	72.0000 hours	
Depth	7.71 in	
Time of Concentration (Composite)	0.1000 hours	
Area (User Defined)	64,316.530 ft ²	
Computational Time Increment	0.0133 hours	
Time to Peak (Computed)	11.9333 hours	
Flow (Peak, Computed)	13.33 ft ³ /s	
Output Increment	0.0100 hours	
Time to Flow (Peak Interpolated Output)	11.9300 hours	
Flow (Peak Interpolated Output)	13.33 ft³/s	
Drainage Area		
	99,000	
SCS CN (Composite) Area (User Defined)	88.000 64,316.530 ft²	
Maximum Retention	04,310.330 IC-	
(Pervious)	1.36 in	
Maximum Retention (Pervious, 20 percent)	0.27 in	
Cumulative Runoff		
Cumulative Runoff Depth (Pervious)	6.28 in	
Runoff Volume (Pervious)	0.773 ac-ft	
Hydrograph Volume (Area under Hydrograph curve)		
 		
Volume	0.773 ac-ft	
SCS Unit Hydrograph Paramete	ers	
Time of Concentration (Composite)	0.1000 hours	
Computational Time Increment	0.0133 hours	
Unit Hydrograph Shape Factor	483.432	
K Factor	0.749	
Receding/Rising, Tr/Tp	1.670	
· ·		

Discovery_Park_Micro_Culvert_to_Pond_Meet_C Bentley Systems, Inc. Haestad Methods Solution C&WQ.ppc Center 6/9/2023 27 Siemon Company Drive Suite 200 W Watertown, CT 06795 USA +1-203-755-1666

Return Event: 100 years

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-4(e) Storm Event: 100-Year

SCS Unit Hydrograph Parameters		
Unit peak, qp	16.73 ft ³ /s	
Unit peak time, Tp	0.0667 hours	
Unit receding limb, Tr	0.2667 hours	
Total unit time, Tb	0.3333 hours	

Subsection: Unit Hydrograph Summary

Label: A-4(w) Scenario: 100-Year

Storm Event	100-Year	
Return Event	100 years	
Duration	72.0000 hours	
Depth	7.71 in	
Time of Concentration (Composite)	0.1095 hours	
Area (User Defined)	381,204.740 ft ²	
Computational Time Increment	0.0146 hours	
Time to Peak (Computed)	11.9428 hours	
Flow (Peak, Computed)	58.13 ft ³ /s	
Output Increment	0.0100 hours	
Time to Flow (Peak Interpolated Output)	11.9400 hours	
Flow (Peak Interpolated Output)	58.07 ft³/s	
Drainage Area		
SCS CN (Composite)	72.000	
Area (User Defined)	381,204.740 ft ²	
Maximum Retention (Pervious)	3.89 in	
Maximum Retention (Pervious, 20 percent)	0.78 in	
Cumulative Runoff		
Cumulative Runoff Depth (Pervious)	4.44 in	
Runoff Volume (Pervious)	3.239 ac-ft	
(
Hydrograph Volume (Area under Hydrograph curve)		
Volume	3.239 ac-ft	
SCS Unit Hydrograph Parame	ters	
Time of Concentration (Composite)	0.1095 hours	
Computational Time Increment	0.0146 hours	
Unit Hydrograph Shape Factor	483.432	
K Factor	0.749	
Receding/Rising, Tr/Tp	1.670	

Return Event: 100 years

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-4(w) Storm Event: 100-Year

SCS Unit Hydrograph Parameters		
Unit peak, qp	90.55 ft ³ /s	
Unit peak time, Tp	0.0730 hours	
Unit receding limb, Tr	0.2920 hours	
Total unit time, Tb	0.3650 hours	

Subsection: Unit Hydrograph Summary

Label: A-5(e) Scenario: 100-Year

Storm Event 100-Year
Return Event 100 years
Duration 72.0000 hours
Depth 7.71 in
Time of Concentration
(Composite) 0.1000 hours
Area (User Defined) 833,009.080 ft²

Computational Time
Increment
Time to Peak (Computed) 11.9333 hours

Computational Time Increment	0.0133 hours
Time to Peak (Computed)	11.9333 hours
Flow (Peak, Computed)	168.32 ft ³ /s
Output Increment	0.0100 hours
Time to Flow (Peak Interpolated Output)	11.9300 hours
Flow (Peak Interpolated Output)	168.25 ft ³ /s

Drainage Area	
SCS CN (Composite)	86.000
Area (User Defined)	833,009.080 ft ²
Maximum Retention (Pervious)	1.63 in
Maximum Retention (Pervious, 20 percent)	0.33 in

Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	6.05 in
Runoff Volume (Pervious)	9.642 ac-ft

Hydrograph Volume (Area	a under Hydrograph curve)
Volume	9.642 ac-ft

SCS Unit Hydrograph Parameter	s
Time of Concentration (Composite)	0.1000 hours
Computational Time Increment	0.0133 hours
Unit Hydrograph Shape Factor	483.432
K Factor	0.749
Receding/Rising, Tr/Tp	1.670

Return Event: 100 years

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-5(e) Storm Event: 100-Year

SCS Unit Hydrograph Parameters				
Unit peak, qp	216.67 ft ³ /s			
Unit peak time, Tp	0.0667 hours			
Unit receding limb, Tr	0.2667 hours			
Total unit time, Tb	0.3333 hours			

Subsection: Unit Hydrograph Summary

Label: A-5(w) Scenario: 100-Year

ı	
Storm Event	100-Year
Return Event	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration (Composite)	0.1000 hours
Area (User Defined)	1,455,610.630 ft ²
,	· · ·
Computational Time Increment	0.0133 hours
Time to Peak (Computed)	11.9200 hours
Flow (Peak, Computed)	322.03 ft ³ /s
Output Increment	0.0100 hours
Time to Flow (Peak	
Interpolated Output)	11.9200 hours
Flow (Peak Interpolated Output)	322.03 ft ³ /s
Drainage Area	
SCS CN (Composite)	95.000
Area (User Defined)	1,455,610.630 ft ²
Maximum Retention (Pervious)	0.53 in
Maximum Retention (Pervious, 20 percent)	0.11 in
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	7.11 in
Runoff Volume (Pervious)	19.806 ac-ft
Hydrograph Volume (Area und	er Hydrograph curve)
Volume	19.806 ac-ft
SCS Unit Hydrograph Paramet	ters
Time of Concentration (Composite)	0.1000 hours
Computational Time Increment	0.0133 hours
Unit Hydrograph Shape Factor	483.432
K Factor	0.749
Receding/Rising, Tr/Tp	1.670
- - : · ·	

Discovery_Park_Micro_Culvert_to_Pond_Meet_C Bentley Systems, Inc. Haestad Methods Solution C&WQ.ppc Center 6/9/2023 27 Siemon Company Drive Suite 200 W Watertown, CT 06795 USA +1-203-755-1666

Return Event: 100 years

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-5(w) Storm Event: 100-Year

SCS Unit Hydrograph Parameters	
Unit peak, qp	378.62 ft³/s
Unit peak time, Tp	0.0667 hours
Unit receding limb, Tr	0.2667 hours
Total unit time, Tb	0.3333 hours

Subsection: Unit Hydrograph Summary

Label: A-6

Scenario: 100-Year

Return Event: 100 years Storm Event: 100-Year

Storm Event	100-Year				
Return Event	100 years				
Duration	72.0000 hours				
Depth	7.71 in				
Time of Concentration (Composite)	0.1000 hours				
Area (User Defined)	584,231.800 ft ²				
	•				
Computational Time Increment	0.0133 hours				
Time to Peak (Computed)	11.9333 hours				
Flow (Peak, Computed)	112.97 ft ³ /s				
Output Increment	0.0100 hours				
Time to Flow (Peak	11 0200 haves				
Interpolated Output)	11.9300 hours				
Flow (Peak Interpolated Output)	112.88 ft³/s				
Drainage Area					
Drainage Area					
SCS CN (Composite)	83.000				
Area (User Defined)	584,231.800 ft ²				
Maximum Retention (Pervious)	2.05 in				
Maximum Retention (Pervious, 20 percent)	0.41 in				
(1 civious, 20 percent)					
Cumulative Runoff					
Cumulative Runoff Depth (Pervious)	5.70 in				
Runoff Volume (Pervious)	6.372 ac-ft				
Hydrograph Volume (Area un					
Volume	6.372 ac-ft				
SCS Unit Hydrograph Param	eters				
Time of Concentration					
(Composite)	0.1000 hours				
Computational Time Increment	0.0133 hours				
Unit Hydrograph Shape Factor	483.432				
K Factor	0.749				
Receding/Rising, Tr/Tp	1.670				

Discovery_Park_Micro_Culvert_to_Pond_Meet_C Bentley Systems, Inc. Haestad Methods Solution C&WQ.ppc Center 6/9/2023 27 Siemon Company Drive Suite 200 W Watertown, CT 06795 USA +1-203-755-1666

PondPack CONNECT Edition [10.02.00.01] Page 22 of 24

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-6 Storm Event: 100-Year

SCS Unit Hydrograph Parameters				
Unit peak, qp	151.97 ft³/s			
Unit peak time, Tp	0.0667 hours			
Unit receding limb, Tr	0.2667 hours			
Total unit time, Tb	0.3333 hours			

Index

Α

A-1(e) (Unit Hydrograph Summary, 100 years (100-Year))...4, 5

A-1(w) (Unit Hydrograph Summary, 100 years (100-Year))...6, 7

A-2(e) (Unit Hydrograph Summary, 100 years (100-Year))...8, 9

A-2(w) (Unit Hydrograph Summary, 100 years (100-Year))...10, 11

A-3 (Unit Hydrograph Summary, 100 years (100-Year))...12, 13

A-4(e) (Unit Hydrograph Summary, 100 years (100-Year))...14, 15

A-4(w) (Unit Hydrograph Summary, 100 years (100-Year))...16, 17

A-5(e) (Unit Hydrograph Summary, 100 years (100-Year))...18, 19

A-5(w) (Unit Hydrograph Summary, 100 years (100-Year))...20, 21

A-6 (Unit Hydrograph Summary, 100 years (100-Year))...22, 23

Μ

Master Network Summary...2, 3

Project Summary	
Title	
Engineer	
Engineer Company	
Date	11/20/2014
	11/20/2014
Notes	

Table of Contents

Master Network Summary	2
Unit Hydrograph Summary, 100 years (100-Year)	4
Unit Hydrograph Summary, 100 years (100-Year)	6
Unit Hydrograph Summary, 100 years (100-Year)	8
Unit Hydrograph Summary, 100 years (100-Year)	10
Unit Hydrograph Summary, 100 years (100-Year)	12
Unit Hydrograph Summary, 100 years (100-Year)	14
Unit Hydrograph Summary, 100 years (100-Year)	16
Unit Hydrograph Summary, 100 years (100-Year)	18
Unit Hydrograph Summary, 100 years (100-Year)	20
Unit Hydrograph Summary, 100 years (100-Year)	22
	Unit Hydrograph Summary, 100 years (100-Year)

Subsection: Master Network Summary

Catchments Summary

Label	Scenario	Return Event (years)	Hydrograph Volume (ac-ft)	Time to Peak (hours)	Peak Flow (ft³/s)
A-1(e)	100-Year	100	15.116	11.9600	247.45
A-1(w)	100-Year	100	17.597	12.0500	252.55
A-2(e)	100-Year	100	1.374	11.9300	24.63
A-2(w)	100-Year	100	8.884	12.0300	136.28
A-3	100-Year	100	12.366	11.9300	214.51
A-4(e)	100-Year	100	0.788	11.9200	13.49
A-4(w)	100-Year	100	3.239	11.9400	58.07
A-5(e)	100-Year	100	10.767	11.9200	180.16
A-5(w)	100-Year	100	19.806	11.9200	322.02
A-6	100-Year	100	7.817	11.9200	128.41
HYG-A-7	100-Year	100	44.871	12.0800	603.64
HYG-B1	100-Year	100	148.401	12.1400	1,553.02

Node Summary

-					
Label	Scenario	Return Event (years)	Hydrograph Volume (ac-ft)	Time to Peak (hours)	Peak Flow (ft³/s)
Point A1	100-Year	100	288.906	12.2300	2,574.30
Point A2	100-Year	100	257.043	12.1700	2,425.09
Point A3	100-Year	100	159.717	12.1700	1,588.55
Point A4	100-Year	100	87.287	12.1500	766.66
Point A5	100-Year	100	87.287	12.1300	767.11
Point A6	100-Year	100	7.817	11.9200	128.41
Point A7	100-Year	100	44.871	12.0800	603.64
Point B1	100-Year	100	148.401	12.1400	1,553.02

Pond Summary

Label	Scenario	Return Event (years)	Hydrograph Volume (ac-ft)	Time to Peak (hours)	Peak Flow (ft³/s)	Maximum Water Surface Elevation (ft)	Maximum Pond Storage (ac-ft)
PR-Basin (Discovery Park) (IN)	100-Year	100	87.287	12.0100	1,095.79	(N/A)	(N/A)
PR-Basin (Discovery Park) (OUT)	100-Year	100	87.287	12.1300	767.11	934.7828	21.709
Pt. A3 - Drive- Culverts (IN)	100-Year	100	159.717	12.1600	1,590.30	(N/A)	(N/A)

Subsection: Master Network Summary

Pond Summary

Label	Scenario	Return Event (years)	Hydrograph Volume (ac-ft)	Time to Peak (hours)	Peak Flow (ft³/s)	Maximum Water Surface Elevation (ft)	Maximum Pond Storage (ac-ft)
Pt. A3 - Drive- Culverts (OUT)	100-Year	100	159.717	12.1700	1,588.55	909.4965	2.842
Pt. A5 - Former Pond (IN)	100-Year	100	87.287	12.1300	767.11	(N/A)	(N/A)
Pt. A5 - Former Pond (OUT)	100-Year	100	87.287	12.1300	767.11	0.0000	0.000
WQv-Sub A1(e) (IN)	100-Year	100	15.116	11.9600	247.45	(N/A)	(N/A)
WQv-Sub A1(e) (OUT)	100-Year	100	14.626	11.9600	247.40	2.5529	0.523
WQv-Sub A1(w) (IN)	100-Year	100	17.597	12.0500	252.55	(N/A)	(N/A)
WQv-Sub A1(w) (OUT)	100-Year	100	17.237	12.0500	252.61	2.5607	0.382
WQv-Sub A2(e) (IN)	100-Year	100	1.374	11.9300	24.63	(N/A)	(N/A)
WQv-Sub A2(e) (OUT)	100-Year	100	1.344	11.9300	24.63	2.1163	0.031
WQv-Sub A2(w) (IN)	100-Year	100	8.884	12.0300	136.28	(N/A)	(N/A)
WQv-Sub A2(w) (OUT)	100-Year	100	8.694	12.0300	136.29	2.3709	0.201
WQv-Sub A3 (IN)	100-Year	100	12.366	11.9300	214.51	(N/A)	(N/A)
WQv-Sub A3 (OUT)	100-Year	100	11.316	11.9300	214.67	2.5038	1.075

Subsection: Unit Hydrograph Summary

Label: A-1(e) Scenario: 100-Year

-	
Storm Event	100-Year
Return Event	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration (Composite)	0.1401 hours
Area (User Defined)	1,331,597.560 ft ²
Computational Time Increment	0.0187 hours
Time to Peak (Computed)	11.9552 hours
Flow (Peak, Computed)	248.26 ft ³ /s
Output Increment	0.0100 hours
Time to Flow (Peak Interpolated Output)	11.9600 hours
Flow (Peak Interpolated Output)	247.45 ft³/s
Drainage Area	
SCS CN (Composite)	85.000
Area (User Defined)	1,331,597.560 ft ²
Maximum Retention (Pervious)	1.76 in
Maximum Retention (Pervious, 20 percent)	0.35 in
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	5.93 in
Runoff Volume (Pervious)	15.116 ac-ft
Hydrograph Volume (Area un	ider Hydrograph curve)
Volume	15.116 ac-ft
000 Hait Hadas assalt D	-1
SCS Unit Hydrograph Parame	eters ————————————————————————————————————
Time of Concentration (Composite)	0.1401 hours
Computational Time Increment	0.0187 hours
Unit Hydrograph Shape Factor	483.432
K Factor	0.749
Receding/Rising, Tr/Tp	1.670

Return Event: 100 years

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-1(e) Storm Event: 100-Year

SCS Unit Hydrograph Parameters	
Unit peak, qp	247.23 ft ³ /s
Unit peak time, Tp	0.0934 hours
Unit receding limb, Tr	0.3736 hours
Total unit time, Tb	0.4670 hours

Subsection: Unit Hydrograph Summary Return Event: 100 years Storm Event: 100-Year

Label: A-1(w) Scenario: 100-Year

Storm Event	100-Year
Return Event	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration (Composite)	0.2511 hours
Area (User Defined)	1,879,178.401 ft²
0	
Computational Time Increment	0.0335 hours
Time to Peak (Computed)	12.0528 hours
Flow (Peak, Computed)	252.68 ft³/s
Output Increment	0.0100 hours
Time to Flow (Peak Interpolated Output)	12.0500 hours
Flow (Peak Interpolated Output)	252.55 ft³/s
Drainage Area	
SCS CN (Composite)	76.000
Area (User Defined)	1,879,178.401 ft ²
Maximum Retention (Pervious)	3.16 in
Maximum Retention (Pervious, 20 percent)	0.63 in
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	4.89 in
Runoff Volume (Pervious)	17.597 ac-ft
Hydrograph Volume (Area ur	 nder Hydrograph curve)
Volume	17.597 ac-ft
SCS Unit Hydrograph Param	neters
Time of Concentration (Composite)	0.2511 hours
Computational Time Increment	0.0335 hours
Unit Hydrograph Shape Factor	483.432
K Factor	0.749
Receding/Rising, Tr/Tp	1.670

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-1(w) Storm Event: 100-Year

SCS Unit Hydrograph Parameters	_
Unit peak, qp	194.66 ft ³ /s
Unit peak time, Tp	0.1674 hours
Unit receding limb, Tr	0.6696 hours
Total unit time, Tb	0.8370 hours

Subsection: Unit Hydrograph Summary

Label: A-2(e) Scenario: 100-Year Storm Event: 100-Year

Return Event: 100 years

Storm Event	100-Year
Return Event	
	100 years
Duration	72.0000 hours 7.71 in
Depth	7.71 111
Time of Concentration (Composite)	0.1000 hours
Area (User Defined)	134,164.800 ft ²
Computational Time Increment	0.0133 hours
Time to Peak (Computed)	11.9333 hours
Flow (Peak, Computed)	24.66 ft ³ /s
Output Increment	0.0100 hours
Time to Flow (Peak	11 0200 haves
Interpolated Output)	11.9300 hours
Flow (Peak Interpolated Output)	24.63 ft ³ /s
Drainage Area	
Drainage Area	
SCS CN (Composite)	80.000
Area (User Defined)	134,164.800 ft ²
Maximum Retention (Pervious)	2.50 in
Maximum Retention (Pervious, 20 percent)	0.50 in
(1 ci vious, 20 percent)	
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	5.35 in
Runoff Volume (Pervious)	1.374 ac-ft
ranen velame (i el vieus)	1107 1 40 10
Hydrograph Volume (Area ui	nder Hydrograph curve)
Volume	1.374 ac-ft
SCS Unit Hydrograph Param	neters
Time of Concentration (Composite)	0.1000 hours
Computational Time Increment	0.0133 hours
Unit Hydrograph Shape Factor	483.432
K Factor	0.749
Receding/Rising, Tr/Tp	1.670
	2.0, 0

Discovery_Park_Macro_Culvert_to_Pond_Meet_ Bentley Systems, Inc. Haestad Methods Solution CC.ppc
6/9/2023
27 Siemon Company Drive Suite 200 W
Watertown, CT 06795 USA +1-203-755-1666

PondPack CONNECT Edition [10.02.00.01] Page 8 of 24

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-2(e) Storm Event: 100-Year

SCS Unit Hydrograph Parameters	
Unit peak, qp	34.90 ft ³ /s
Unit peak time, Tp	0.0667 hours
Unit receding limb, Tr	0.2667 hours
Total unit time, Tb	0.3333 hours

Subsection: Unit Hydrograph Summary

Label: A-2(w) Scenario: 100-Year

Storm Event	100-Year
Return Event	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration (Composite)	0.2133 hours
Area (User Defined)	1,019,739.600 ft ²
Computational Time Increment	0.0284 hours
Time to Peak (Computed)	12.0301 hours
Flow (Peak, Computed)	136.29 ft ³ /s
Output Increment	0.0100 hours
Time to Flow (Peak Interpolated Output)	12.0300 hours
Flow (Peak Interpolated Output)	136.28 ft³/s
Drainage Area	
SCS CN (Composite)	73.000
Area (User Defined)	1,019,739.600 ft ²
Maximum Retention (Pervious)	3.70 in
Maximum Retention (Pervious, 20 percent)	0.74 in
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	4.55 in
Runoff Volume (Pervious)	8.884 ac-ft
Lleveler annuals VIII /A	- de a libertar anno 1
Hydrograph Volume (Area ur	nder Hydrograph curve)
Volume	8.884 ac-ft
SCS Unit Hydrograph Param	eters
Time of Concentration (Composite)	0.2133 hours
Computational Time Increment	0.0284 hours
Unit Hydrograph Shape Factor	483.432
K Factor	0.749
Receding/Rising, Tr/Tp	1.670
- - · ·	

Return Event: 100 years

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-2(w) Storm Event: 100-Year

SCS Unit Hydrograph Parameters	
Unit peak, qp	124.35 ft ³ /s
Unit peak time, Tp	0.1422 hours
Unit receding limb, Tr	0.5688 hours
Total unit time, Tb	0.7110 hours

Subsection: Unit Hydrograph Summary

Label: A-3

Scenario: 100-Year

ry Return Event: 100 years Storm Event: 100-Year

Storm Event	100-Year
Return Event	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration (Composite)	0.1000 hours
Area (User Defined)	1,048,038.590 ft ²
Computational Time Increment	0.0133 hours
Time to Peak (Computed)	11.9333 hours
Flow (Peak, Computed)	214.57 ft ³ /s
Output Increment	0.0100 hours
Time to Flow (Peak Interpolated Output)	11.9300 hours
Flow (Peak Interpolated Output)	214.51 ft³/s
Drainaga Aras	
Drainage Area	
SCS CN (Composite)	87.000
Area (User Defined)	1,048,038.590 ft ²
Maximum Retention (Pervious)	1.49 in
Maximum Retention (Pervious, 20 percent)	0.30 in
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	6.17 in
Runoff Volume (Pervious)	12.366 ac-ft
Hydrograph Volume (Area un	der Hydrograph curve)
Volume	12.366 ac-ft
SCS Unit Hydrograph Parame	eters
Time of Concentration (Composite)	0.1000 hours
Computational Time Increment	0.0133 hours
Unit Hydrograph Shape Factor	483.432
K Factor	0.749
Receding/Rising, Tr/Tp	1.670
	Inc. Haastad Mathada Salution

Discovery_Park_Macro_Culvert_to_Pond_Meet_ Bentley Systems, Inc. Haestad Methods Solution CC.ppc
6/9/2023
27 Siemon Company Drive Suite 200 W
Watertown, CT 06795 USA +1-203-755-1666

PondPack CONNECT Edition [10.02.00.01] Page 12 of 24

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-3 Storm Event: 100-Year

SCS Unit Hydrograph Parameters		
Unit peak, qp	272.61 ft ³ /s	
Unit peak time, Tp	0.0667 hours	
Unit receding limb, Tr	0.2667 hours	
Total unit time, Tb	0.3333 hours	

Subsection: Unit Hydrograph Summary

Label: A-4(e) Scenario: 100-Year

II	
Storm Event	100-Year
Return Event	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration (Composite)	0.1000 hours
Area (User Defined)	64,316.530 ft ²
Computational Time Increment	0.0133 hours
Time to Peak (Computed)	11.9200 hours
Flow (Peak, Computed)	13.49 ft ³ /s
Output Increment	0.0100 hours
Time to Flow (Peak Interpolated Output)	11.9200 hours
Flow (Peak Interpolated Output)	13.49 ft³/s
Drainage Area	
SCS CN (Composite)	89.000
Area (User Defined)	64,316.530 ft ²
Maximum Retention (Pervious)	1.24 in
Maximum Retention (Pervious, 20 percent)	0.25 in
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	6.40 in
Runoff Volume (Pervious)	0.788 ac-ft
Hydrograph Volume (Area une	dor Hydrograph augus)
Hydrograph Volume (Area und	
Volume	0.788 ac-ft
SCS Unit Hydrograph Parameters	
Time of Concentration (Composite)	0.1000 hours
Computational Time Increment	0.0133 hours
Unit Hydrograph Shape Factor	483.432
K Factor	0.749
Receding/Rising, Tr/Tp	1.670

Return Event: 100 years

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-4(e) Storm Event: 100-Year

SCS Unit Hydrograph Parameters	
Unit peak, qp	16.73 ft ³ /s
Unit peak time, Tp	0.0667 hours
Unit receding limb, Tr	0.2667 hours
Total unit time, Tb	0.3333 hours

Subsection: Unit Hydrograph Summary Return Event: 100 years Storm Event: 100-Year

Label: A-4(w) Scenario: 100-Year

Storm Event	100-Year
Return Event	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration (Composite)	0.1095 hours
Area (User Defined)	381,204.740 ft ²
Computational Time Increment	0.0146 hours
Time to Peak (Computed)	11.9428 hours
Flow (Peak, Computed)	58.13 ft³/s
Output Increment	0.0100 hours
Time to Flow (Peak Interpolated Output)	11.9400 hours
Flow (Peak Interpolated Output)	58.07 ft³/s
Drainage Area	
SCS CN (Composite)	72.000
Area (User Defined)	381,204.740 ft ²
Maximum Retention (Pervious)	3.89 in
Maximum Retention (Pervious, 20 percent)	0.78 in
Cumulative Runoff	
Cumulative Runoff Depth	
(Pervious)	4.44 in
Runoff Volume (Pervious)	3.239 ac-ft
Hydrograph Volume (Area under Hydrograph curve)	
Volume	3.239 ac-ft
SCS Unit Hydrograph Parameters	
Time of Concentration (Composite)	0.1095 hours
Computational Time Increment	0.0146 hours
Unit Hydrograph Shape Factor	483.432
K Factor	0.749
Receding/Rising, Tr/Tp	1.670

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-4(w) Storm Event: 100-Year

SCS Unit Hydrograph Parameters	
Unit peak, qp	90.55 ft ³ /s
Unit peak time, Tp	0.0730 hours
Unit receding limb, Tr	0.2920 hours
Total unit time, Tb	0.3650 hours

Subsection: Unit Hydrograph Summary

Label: A-5(e) Scenario: 100-Year Storm Event: 100-Year

Storm Event	100-Year
Return Event	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration	0.1000 hours
(Composite)	
Area (User Defined)	833,009.030 ft ²
Computational Time Increment	0.0133 hours
Time to Peak (Computed)	11.9200 hours
Flow (Peak, Computed)	180.16 ft ³ /s
Output Increment	0.0100 hours
Time to Flow (Peak Interpolated Output)	11.9200 hours
Flow (Peak Interpolated Output)	180.16 ft ³ /s
Drainage Area	
SCS CN (Composite)	92.000
Area (User Defined)	833,009.030 ft ²
Maximum Retention (Pervious)	0.87 in
Maximum Retention (Pervious, 20 percent)	0.17 in
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	6.76 in
Runoff Volume (Pervious)	10.767 ac-ft
Hudrograph Valuma /Araa	dor Undrograph sum (s)
Hydrograph Volume (Area und	
Volume	10.767 ac-ft
SCS Unit Hydrograph Parame	ters
Time of Concentration (Composite)	0.1000 hours
Computational Time Increment	0.0133 hours

 ${\tt Discovery_Park_Macro_Culvert_to_Pond_Meet_\ \ Bentley\ Systems,\ Inc.\ \ Haestad\ Methods\ Solution}$ CC.ppc 6/9/2023 Center 27 Siemon Company Drive Suite 200 W Watertown, CT 06795 USA +1-203-755-1666

Unit Hydrograph Shape

Receding/Rising, Tr/Tp

Factor

K Factor

483.432

0.749

1.670

Return Event: 100 years

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-5(e) Storm Event: 100-Year

SCS Unit Hydrograph Parameters	
Unit peak, qp	216.67 ft ³ /s
Unit peak time, Tp	0.0667 hours
Unit receding limb, Tr	0.2667 hours
Total unit time, Tb	0.3333 hours

Subsection: Unit Hydrograph Summary

Label: A-5(w) Scenario: 100-Year

Storm Event	100-Year
Return Event	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration (Composite)	0.1000 hours
Area (User Defined)	1,455,578.170 ft ²
Computational Time Increment	0.0133 hours
Time to Peak (Computed)	11.9200 hours
Flow (Peak, Computed)	322.02 ft ³ /s
Output Increment	0.0100 hours
Time to Flow (Peak Interpolated Output)	11.9200 hours
Flow (Peak Interpolated Output)	322.02 ft³/s
Drainage Area	
SCS CN (Composite)	95.000
Area (User Defined)	1,455,578.170 ft ²
Maximum Retention (Pervious)	0.53 in
Maximum Retention (Pervious, 20 percent)	0.11 in
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	7.11 in
Runoff Volume (Pervious)	19.806 ac-ft
Hydrograph Volume (Area ur	nder Hydrograph curve)
Volume	19.806 ac-ft
Volume	17.000 dc It
SCS Unit Hydrograph Param	eters
Time of Concentration (Composite)	0.1000 hours
Computational Time Increment	0.0133 hours
Unit Hydrograph Shape Factor	483.432
K Factor	0.749
Receding/Rising, Tr/Tp	1.670

Return Event: 100 years

Subsection: Unit Hydrograph Summary Return Event: 100 years Label: A-5(w) Storm Event: 100-Year

SCS Unit Hydrograph Parameters	
Unit peak, qp	378.61 ft³/s
Unit peak time, Tp	0.0667 hours
Unit receding limb, Tr	0.2667 hours
Total unit time, Tb	0.3333 hours

Subsection: Unit Hydrograph Summary

Label: A-6

Scenario: 100-Year

Return Event: 100 years Storm Event: 100-Year

Storm Event	100-Year
Return Event	
	100 years
Duration	72.0000 hours
Depth	7.71 in
Time of Concentration (Composite)	0.1000 hours
Area (User Defined)	584,231.800 ft ²
Computational Time Increment	0.0133 hours
Time to Peak (Computed)	11.9200 hours
Flow (Peak, Computed)	128.41 ft³/s
Output Increment	0.0100 hours
Time to Flow (Peak	
Interpolated Output)	11.9200 hours
Flow (Peak Interpolated Output)	128.41 ft³/s
Drainage Area	
SCS CN (Composite)	94.000
Area (User Defined)	584,231.800 ft²
Maximum Retention (Pervious)	0.64 in
Maximum Retention (Pervious, 20 percent)	0.13 in
(1 civious, 20 percent)	
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	6.99 in
Runoff Volume (Pervious)	7.817 ac-ft
Hydrograph Volume (Area u	nder Hydrograph curve)
Volume	7.817 ac-ft
000	
SCS Unit Hydrograph Paran	neters
Time of Concentration (Composite)	0.1000 hours
Computational Time Increment	0.0133 hours
Unit Hydrograph Shape Factor	483.432
K Factor	0.749
Receding/Rising, Tr/Tp	1.670

Macro Proposed Conditions

Return Event: 100 years Subsection: Unit Hydrograph Summary Label: A-6 Storm Event: 100-Year

Scenario: 100-Year

SCS Unit Hydrograph Parameters	
Unit peak, qp	151.97 ft ³ /s
Unit peak time, Tp	0.0667 hours
Unit receding limb, Tr	0.2667 hours
Total unit time, Tb	0.3333 hours

Macro Proposed Conditions

Index

A-1(e) (Unit Hydrograph Summary, 100 years (100-Year))...4, 5

A-1(w) (Unit Hydrograph Summary, 100 years (100-Year))...6, 7

A-2(e) (Unit Hydrograph Summary, 100 years (100-Year))...8, 9

A-2(w) (Unit Hydrograph Summary, 100 years (100-Year))...10, 11

A-3 (Unit Hydrograph Summary, 100 years (100-Year))...12, 13

A-4(e) (Unit Hydrograph Summary, 100 years (100-Year))...14, 15


A-4(w) (Unit Hydrograph Summary, 100 years (100-Year))...16, 17


A-5(e) (Unit Hydrograph Summary, 100 years (100-Year))...18, 19


A-5(w) (Unit Hydrograph Summary, 100 years (100-Year))...20, 21


A-6 (Unit Hydrograph Summary, 100 years (100-Year))...22, 23


Master Network Summary...2, 3





























































































USGS The National Map: Orthoimagery. Data refreshed April 2020

FLOOD HAZARD INFORMATION

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP



Base Flood Elevation Line (BFE)

Jurisdiction Boundary

Limit of Study

OTHER

FEATURES

NOTES TO USERS

For information and questions about this Flood Insurance Rate Map (FIRM), available products associated with this FIRM, including historic versions, the current map date for each FIRM panel, how to order products, or the National Flood Insurance Program (NFIP) in general, please call the FEMA Map Information eXchange at 1-877-FEMA-MAP (1-877-336-2627) or visit the FEMA Flood Map Service Center website at https://msc.fema.gov. Available products may include previously issued Letters of Map Change, a Flood Insurance Study Report, and/or digital versions of this map. Many of these products can be ordered or obtained directly from the website.

Communities annexing land on adjacent FIRM panels must obtain a current copy of the adjacent panel as well

as the current FIRM Index. These may be ordered directly from the Flood Map Service Center at the number

For community and countywide map dates, refer to the Flood Insurance Study Report for this jurisdiction.

To determine if flood insurance is available in this community, contact your Insurance agent or call the National Flood Insurance Program at 1-800-638-6620.

Basemap information shown on this FIRM was provided in digital format by USDA, Farm Service Agency (FSA). This information was derived from NAIP, dated April 11, 2018.

This map was exported from FEMA's National Flood Hazard Layer (NFHL) on 8/26/2020 8:37 AM and does not reflect changes or amendments subsequent to this date and time. The NFHL and effective information may change or become superseded by new data over time. For additional information, please see the Flood Hazard Mapping Updates Overview Fact Sheet at https://www.fema.gov/media-library/assets/documents/118418

This map complies with FEMA's standards for the use of digital flood maps if it is not void as described below. The basemap shown complies with FEMA's basemap accuracy standards. This map image is void if the one or more of the following map elements do not appear: basemap imagery, flood zone labels, legend, scale bar, map creation date, community identifiers, FIRM panel number, and FIRM effective date.

SCALE

Map Projection: GCS, Geodetic Reference System 1980; Vertical Datum: NAVD88

For information about the specific vertical datum for elevation features, datum conversions, or vertical monuments used to create this map, please see the Flood Insurance Study (FIS) Report for your community at https://msc.fema.gov

	1	1 inch = 500 feet			1:6,00	00
	0	250 5	00	1,000	1,500	2,000 Fee
\I					Meters	1 66
IV	0	50 100	200	300	400	

National Flood Insurance Program S ZONE X


NATIONAL FLOOD INSURANCE PROGRAM FLOOD INSURANCE RATE MAP

94°22'29.6"W 38°56'8.44"N

JACKSON COUNTY, MISSOURI AND INCORPORATED AREAS PANEL 409 OF 605

Panel Contains:		
COMMUNITY	NUMBER	PANEL
CITY OF KANSAS CITY	290173	0409
/ILLAGE OF UNITY	290513	0409
CITY OF LEE'S	290174	0409

MAP NUMBER 29095C0409G **EFFECTIVE DATE** January 20, 2017



MAP LEGEND MAP INFORMATION The soil surveys that comprise your AOI were mapped at Area of Interest (AOI) С 1:24.000. Area of Interest (AOI) C/D Soils Warning: Soil Map may not be valid at this scale. D Soil Rating Polygons Enlargement of maps beyond the scale of mapping can cause Not rated or not available Α misunderstanding of the detail of mapping and accuracy of soil **Water Features** line placement. The maps do not show the small areas of A/D Streams and Canals contrasting soils that could have been shown at a more detailed Transportation B/D Rails ---Please rely on the bar scale on each map sheet for map measurements. Interstate Highways C/D Source of Map: Natural Resources Conservation Service **US Routes** Web Soil Survey URL: D Major Roads Coordinate System: Web Mercator (EPSG:3857) Not rated or not available -Local Roads Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts Soil Rating Lines Background distance and area. A projection that preserves area, such as the Aerial Photography Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required. This product is generated from the USDA-NRCS certified data as of the version date(s) listed below. Soil Survey Area: Jackson County, Missouri Survey Area Data: Version 20, Sep 16, 2019 Soil map units are labeled (as space allows) for map scales 1:50.000 or larger. Not rated or not available Date(s) aerial images were photographed: Sep 6, 2019—Nov 16. 2019 **Soil Rating Points** The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background A/D imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident. B/D

Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
10000	Arisburg silt loam, 1 to 5 percent slopes	С	19.2	0.7%
10024	Greenton-Urban land complex, 5 to 9 percent slopes	D	294.2	10.0%
10026	Higginsville silt loam, 5 to 9 percent slopes	С	64.2	2.2%
10113	Oska silty clay loam, 5 to 9 percent slopes, eroded	D	26.5	0.9%
10116	Sampsel silty clay loam, 2 to 5 percent slopes	C/D	22.2	0.8%
10117	Sampsel silty clay loam, 5 to 9 percent slopes	C/D	61.8	2.1%
10120	Sharpsburg silt loam, 2 to 5 percent slopes	С	232.0	7.9%
10122	Sharpsburg silt loam, 5 to 9 percent slopes, eroded	С	5.2	0.2%
10128	Sharpsburg-Urban land complex, 2 to 5 percent slopes	D	206.3	7.0%
10132	Sibley silt loam, 2 to 5 percent slopes	С	253.0	8.6%
10136	Sibley-Urban land complex, 2 to 5 percent slopes	С	458.4	15.6%
10141	Snead-Rock outcrop complex, 14 to 30 percent slopes	D	194.8	6.6%
10142	Snead-Rock outcrop complex, 5 to 14 percent slopes	D	287.3	9.8%
10143	Snead-Urban land complex, 9 to 30 percent slopes	D	1.6	0.1%
10180	Udarents-Urban land- Sampsel complex, 2 to 5 percent slopes	С	40.4	1.4%
30080	Greenton silty clay loam, 5 to 9 percent slopes	C/D	684.9	23.3%
30180	Polo silt loam, 5 to 9 percent slopes, eroded	С	43.7	1.5%

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
36083	Kennebec silt loam, 1 to 4 percent slopes, occasionally flooded	С	2.1	0.1%
99001	Water		39.4	1.3%
Totals for Area of Interest			2,937.2	100.0%

Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.


If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.


Rating Options

Aggregation Method: Dominant Condition

Component Percent Cutoff: None Specified

Tie-break Rule: Higher






Location ID:	Total Area	Aria Onsite	Discovery Park Onsite	Onsite Area Macro-Study	Weighted NRCS CN:
Subarea A1(e):	(ac): 27.97	Area (ac):	Area (ac):	(ac):	77
Subarea A1(w):	43.14			72.50	76
Subarea A 2(e):	3.08				80
Subarea A2(w):					73
Subarea A3:		11.07		11.07	82
Subarea A4(e):		0.14	0.84	0.98	88
		0.14	0.59	0.59	72
Subarea A4(w):		11.29	6.92	18.20	86
Subarea A5(e):		11.29	31.08	31.08	95
Subarea A5(w):			31.00		
Subarea A6:				9.88	83
Subarea A7:					76
Subarea A8:	21.56				81
Subarea A9:	31.84				84
Subarea A10:	12.23				94
Subtotal:	294.08	22.50	39.43	84.16	
Subarea B1:	31.94				79
Subarea B2:	48.54				78
Subarea B3:	40.69				83
Subarea B4-DET:	25.05				94
Subarea B4-BYP:	7.42				94
Subtotal:	153.64				
Subarea C1:	45.21				90
Subarea C2:	57.13				81
Subarea C3:	52.36				83
Subtotal:	154.70				

Sub-W'Shed A Subtotal:	294.08	22.50	39.43	84.16
Sub-W'Shed B Subtotal:	153.64	0.00	0.00	0.00
Sub-W'Shed C Subtotal:	154.70	0.00	0.00	0.00
Modeled Total:	602.42	22.50	39.43	84.16






PROJECT NO: A21-04643

DRAWN BY: DFG

DATE: 01/18/2023




DISCOVERY PARK MACRO PROPOSED CONDITIONS


olsson

1301 Burlington Street North Kansas City, MO 64116 TEL 816.361.1177

EX-301



Sub-W'Shed A Subtotal:	296.68	22.50	39.43	86.76
Sub-W'Shed B Subtotal:	153.64	0.00	0.00	0.00
Sub-W'Shed C Subtotal:	154.70	0.00	0.00	0.00
Modeled Total:	605.02	22.50	39.43	86.76



SCALE IN FEET

PROJECT NO: A21-04643 DRAWN BY: DFG DATE: 01/18/2023

MACRO FULLY-DEVELOPED CONDITIONS



POINT ALO

1301 Burlington Street North Kansas City, MO 64116 TEL 816.361.1177

EXHIBIT EX-302

Area diverted into subarea Ale in proposed conditions SUBAREA C2 POINT AT -POINT C2 SUBAREA B1 POINT C3 SUBAREA C POINT C1 - POINT BI POINT B2 SUBAREA A1w SUBAREA B2 - POINT B3 SUBAREA B3 DETENTION BASIN POINT AT SUBAREA A7

DISCOVERY PARK MACRO STORMWATER REPORT

Lee's Summit, MO

January 2023 Revised June 2023 Olsson Project No. A21-04643