


LEGEND:	
A/E	- ACCESS EASEMENT
BC	- BACK OF CURB
B/B	- BACK TO BACK
BM	- BENCHMARK
BL or B.L.	- BUILDING LINE
CO	- CLEANOUT
TJB	- TELEPHONE JUNCTION BOX
C&G	- CURB AND GUTTER
D/E	- DRAINAGE EASEMENT
E/E	- ELECTRICAL EASEMENT
EL	- ELEVATION
FL	- FLOW LINE
G/E	- GAS LINE EASEMENT
HDPE	- HIGH-DENSITY POLYETHYLENE
UE	- LANDSCAPE EASEMENT
MSFE	- MINIMUM SERVICEABLE FLOOR ELEVATION
PVC	- POLYVINYL CHLORIDE
P/L	- PROPERTY LINE
PUB/E	- PUBLIC EASEMENT
RCP	- REINFORCED CONCRETE PIPE
ROW or R/W	- RIGHT-OF-WAY
S/E	- SANITARY SEWER EASEMENT
SL	- SERVICE LINE
S/W	- SIDEWALK
TE	- TOP ELEVATION
U/E	- UTILITY EASEMENT
WSE	- WATER SURFACE ELEVATION
W/E	- WATERLINE EASEMENT
ASPHALT PAVEMENT - EXISTING	
ASPHALT PAVEMENT - PROPOSED	
CONCRETE PAVEMENT - EXISTING	
ASPHALT PAVEMENT - EXISTING	
CONCRETE SIDEWALK - EXISTING	
CONCRETE SIDEWALK - PROPOSED	
CURB & GUTTER	
CURB & GUTTER - EXISTING	
TREELINE	
EXISTING LOT AND R/W LINES	
EXISTING PLAT LINES	
PROPERTY LINES	
RIGHT-OF-WAY	
SANITARY SEWER MAIN	
SANITARY SEWER MAIN - EXIST.	
STORM SEWER	
STORM SEWER - EXISTING	
CABLE TV - EXISTING	
FIBER OPTIC CABLE - EXISTING	
TELEPHONE LINE - EXIST.	
ELECTRIC LINE - EXISTING	
OVERHEAD POWER LINE - EXIST.	
UNDERGROUND ELECTRIC - EX.	
GAS LINE - EXISTING	
WATERLINE - EXISTING	
LIGHT - EXISTING	
EXISTING MANHOLE	
CLEANOUT	
EXISTING SANITARY MANHOLE	
PROPOSED SANITARY MANHOLE	
EXISTING AREA INLET	
EXISTING CURB INLET	
EXISTING GRATE INLET	
EXISTING JUNCTION BOX	
EXISTING STORM MANHOLE	
AI	
CI	
GI	
JB	



SECTION 11-47-31

LOCATION MAP
SCALE 1" = 2000'

UTILITY CONTACTS:

MISSOURI DEPARTMENT OF TRANSPORTATION (MODOT)

Steve Holloway
600 NE Coborn Road
Lee's Summit, MO 64086
(816) 607-2186

SPIRE
Brent Jones
3025 SE Clover Drive
Lee's Summit, MO 64082
(816) 399-0663 brent.jones@spireenergy.com

EVERGY
Philip Ingram
1300 SE Hamblin Road
Lee's Summit, MO 64081
Office: (816) 347-3474-4339
philip.ingram@evergy.com

CITY OF LEES SUMMIT PUBLIC WORKS

Dena Mezger
220 SE Green Street
Lee's Summit, MO 64063
(816) 969-1800

AT&T
Mark Manion or Marty Loper
500 E. 8th Street, Room 370
Kansas City, MO 64106
(816) 275-2341 or (816) 275-1550

COMCAST CABLE
John Meadows
4700 Little Blue Parkway
Independence, MO 64057
(816) 795-2257

CITY OF LEE'S SUMMIT WATER UTILITIES

Mark Schaefer
1200 SE Hamblin Road
Lee's Summit, MO 64081
(816) 969-1900



811 or
1-800-344-7433
mo1call.com

SUMMARY OF QUANTITIES

	ITEM	QUANTITY	UNITS
1	EARTHWORK (FINAL GRADING)	1	LS
2	INSTALL 6" TYPE 5 BASE	10,350	SY
3	INSTALL 9" SUBGRADE STABILIZATION	10,350	SY
4	INSTALL 2" TYPE 5 OR 6 ASPHALT PAVEMENT	8,446	SY
5	INSTALL 4" TYPE 5 ASPHALT PAVEMENT	8,446	SY
6	INSTALL TYPE CG-2 CURB AND GUTTER	5,675	LF
7	INSTALL 5' CONCRETE SIDEWALK	1,195	LF
8	INSTALL TYPE A SIDEWALK RAMPS	15	EA
9	INSTALL TYPE B SIDEWALK RAMPS	3	EA
10	INSTALL TYPE M SIDEWALK RAMPS	1	EA
11	INSTALL 6x4' CURB INLET	23	EA
12	INSTALL 6x5' CURB INLET	2	EA
13	INSTALL 42" FLARED END SECTION W/ TOEWALL	1	EA
14	INSTALL 15" HDPE	846	LF
15	INSTALL 18" HDPE	615	LF
16	INSTALL 24" HDPE	288	LF
17	INSTALL 30" HDPE	167	LF
18	INSTALL 36" HDPE	192	LF
19	INSTALL 42" HDPE	436	EA
20	INSTALL RIPRAP	32	CY
21	TRENCHING UNDER FUTURE STREET	575	LF
22	SEEDING & MULCH DISTRIBUTED AREAS	1	LS
23	EROSION CONTROL (MAINTENANCE & REMOVAL)	1	LS
24	PERMANENT STREET SIGNING	1	LS

PUBLIC STREET AND STORM SEWER PLANS

FOR REUNION AT BLACKWELL

IN THE CITY OF LEE'S SUMMIT JACKSON COUNTY, MO

GENERAL NOTES:

- ALL CONSTRUCTION TO FOLLOW THE CITY OF LEE'S SUMMIT DESIGN AND CONSTRUCTION MANUAL AS ADOPTED BY ORDINANCE 5813.
- ALL WORKMANSHIP AND MATERIALS SHALL BE SUBJECT TO THE INSPECTION AND APPROVAL OF THE ENGINEERING DEPARTMENT OF THE CITY OF LEE'S SUMMIT, MISSOURI.
- LINEAL FOOT MEASUREMENTS SHOWN ON THE PLANS ARE HORIZONTAL MEASUREMENTS, NOT SLOPE MEASUREMENTS. ALL PAYMENTS SHALL BE MADE ON HORIZONTAL MEASUREMENTS.
- NO GEOLOGICAL INVESTIGATION HAS BEEN PERFORMED ON THE SITE.
- THE UTILITY LOCATIONS SHOWN ON THESE PLANS ARE TAKEN FROM UTILITY COMPANY RECORDS AND APPARENT FIELD LOCATIONS. THE CONTRACTOR SHALL VERIFY THE LOCATION AND DEPTH OF ALL UTILITIES PRIOR TO CONSTRUCTION.
- THE CONTRACTOR SHALL ADHERE TO THE PROVISIONS OF THE SENATE BILL NUMBER 583, 78TH GENERAL ASSEMBLY OF THE STATE OF MISSOURI. THE BILL REQUIRES THAT ANY PERSON OR FIRM DOING EXCAVATION ON PUBLIC RIGHT OF WAY DO SO ONLY AFTER GIVING NOTICE TO, AND OBTAINING INFORMATION FROM, UTILITY COMPANIES. STATE LAW REQUIRES 48 HOURS ADVANCE NOTICE. THE CONTRACTOR MAY ALSO UTILIZE THE FOLLOWING TOLL FREE PHONE NUMBER PROVIDED BY "MISSOURI ONE CALL SYSTEM, INC." 1-800-400-RITE. THIS PHONE NUMBER IS APPLICABLE ANYWHERE WITHIN THE STATE OF MISSOURI. PRIOR TO COMMENCEMENT OF WORK, THE CONTRACTOR SHALL NOTIFY ALL THOSE COMPANIES WHICH HAVE FACILITIES IN THE NEAR VICINITY OF THE CONSTRUCTION TO BE PERFORMED.
- PRIOR TO ORDERING PRECAST STRUCTURES, SHOP DRAWING SHALL BE SUBMITTED TO THE DESIGN ENGINEER FOR APPROVAL. AFTER APPROVAL OF THE SHOP DRAWINGS, A COPY OF THE APPROVED AND SIGNED SHOP DRAWINGS SHALL BE PROVIDED TO THE CITY INSPECTOR UPON REQUEST.
- THE CONTRACTOR SHALL PROTECT ALL MAJOR TREES FROM DAMAGE. NO TREE SHALL BE REMOVED WITHOUT PERMISSION OF THE OWNER, UNLESS SHOWN OTHERWISE.
- CLEARING AND GRUBBING OPERATIONS AND DISPOSAL OF ALL DEBRIS THEREFROM SHALL BE PERFORMED BY THE CONTRACTOR IN STRICT ACCORDANCE WITH ALL LOCAL CODES AND ORDINANCES.
- ALL WASTE MATERIAL RESULTING FROM THE PROJECT SHALL BE DISPOSED OF OFF-SITE BY THE CONTRACTOR, OR AS DIRECTED BY THE OWNER.
- ALL EXCAVATIONS SHALL BE UNCLASSIFIED. NO SEPARATE PAYMENT WILL BE MADE FOR ROCK EXCAVATION.
- THE CONTRACTOR SHALL CONTROL THE EROSION AND SILTATION DURING ALL PHASES OF CONSTRUCTION, AND SHALL KEEP THE STREETS CLEAN OF MUD AND DEBRIS.
- ALL MANHOLES, CATCH BASINS, UTILITY VALVES AND METER PITS TO BE ADJUSTED OR REBUILT TO GRADE AS REQUIRED.
- THE CONTRACTOR SHALL CONTACT DEVELOPMENT SERVICES INSPECTIONS AT: 816-969-1200 TO OBTAIN A DEVELOPMENT SERVICES CONSTRUCTION PERMIT. A MINIMUM 48 HOUR NOTICE SHALL BE GIVEN PRIOR TO PERMIT ISSUANCE.
- THE CONTRACTOR SHALL CONTACT THE RIGHT OF WAY INSPECTOR AT 816-969-1800 PRIOR TO ANY LAND DISTURBANCE ACTIVITIES WITHIN THE RIGHT OF WAY. THESE ACTIVITIES MAY REQUIRE A PERMIT.
- THE CONTRACTOR SHALL PROVIDE AND MAINTAIN ALL TRAFFIC HANDLING MEASURES NECESSARY TO ENSURE THAT THE GENERAL PUBLIC IS PROTECTED AT ALL TIMES. TRAFFIC CONTROL SHALL CONFORM TO THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD-LATEST EDITION).

STREET NOTES:

- ALL STREET CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE CITY OF LEE'S SUMMIT DESIGN AND CONSTRUCTION MANUAL. ALL APPLICABLE AASHTO STANDARDS HAVE BEEN MET.
- THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING ALL EXISTING UTILITY LOCATIONS PRIOR TO EXCAVATION.
- ALL INSPECTION OF STREET CONSTRUCTION TO BE PERFORMED BY THE CITY OF LEE'S SUMMIT DEVELOPMENT ENGINEERING.
- CURB RETURN RADII SHALL BE 25' AT BACK OF CURB UNLESS OTHERWISE NOTED.
- SUBGRADE TO BE COMPACTED TO 95% STANDARD PROCTOR DENSITY.
- ASSUMED DESIGN SPEED = 25 MPH (RESIDENTIAL LOCAL).
- MINIMUM STOPPING SIGHT DISTANCE = 155 FEET.
- GRADE INTERSECTIONS TO DRAIN AS SHOWN.
- SSD = STOPPING SIGHT DISTANCE.
- ALL ADA SIDEWALK RAMPS SHALL BE CONSTRUCTED BY THE DEVELOPER WITH THE PUBLIC INFRASTRUCTURE.

DESIGN SPEED = 30 MPH

POSTED SPEED = 25 MPH


EARTHWORK:

- It is recommended that a Geotechnical Engineer observe and document all earthwork activities.
- Contours have been shown at 1-foot or 2-foot intervals, as indicated. Grading shall consist of completing the earthwork required to bring the physical ground elevations of the existing site to the finished grade (or sub-grade) elevations provided on the plans as spot grades, contours or others means as indicated on the plans.
- The existing site topography depicted on the plans by contouring has been established by aerial photography and field verified by g.p.s. observation near 11/11/2021. The contour elevations provided may not be exact ground elevations, but rather interpretations of such. Accuracy shall be considered to be such that not more than 10 percent of spot elevation checks shall be in error by more than one-half the contour interval provided, as defined by the National Map Accuracy Standards. Any quantities provided for earthwork volumes are established using this topography contour accuracy, and therefore the inherent accuracy of any earthwork quantity is assumed from the topography accuracy.
- Proposed contours are to approximate finished grade.
- Unless otherwise noted, payment for earthwork shall include backfilling of the curb and gutter, sidewalk and further manipulation of utility trench spoils. The site shall be left in a moveable condition and positive drainage maintained throughout.
- Unless otherwise noted, all earthwork is considered Unclassified. No additional compensation will be provided for rock or shale excavation, unless specifically stated otherwise.
- Prior to earthwork activities, pre-disturbance erosion and sediment control devices shall be in place per the Storm Water Pollution Prevention Plan and/or the Erosion and Sediment Control Plan prepared for this site.
- All topsoil shall be stripped from all areas to be graded and stockpiled adjacent to the site at an area specified by the project owner or his appointed representative. Vegetation, trash, trees, brush, tree roots and limbs, rock fragments greater than 6-inches and other deleterious materials shall be removed and properly disposed of offsite or as directed by the owner or his appointed representative.
- Unless otherwise specified in the Geotechnical Report, all fills shall be placed in maximum 6-inch lifts and compacted to 95-percent of maximum density as defined using a standard proctor test (AASHTO T99/ASTM 698).
- Subgrade for pavements shall be pro-rolled prior to paving operations utilizing a fully loaded tandem axle dump truck. All areas exhibiting excessive pumping and heaving shall be removed, filled and compacted with suitable materials and retested until acceptable results are achieved and final approval has been obtained from the Geotechnical Engineer.
- Subgrade for building pad shall include a minimum of 18-inches of Low Volume Change (LVC) material, or as identified in the site specific Geotechnical Report.
- Fill materials shall be per Geotechnical Report and shall not include organic matter, debris or topsoil. All fills placed on slopes greater than 6:1 shall be benched.
- The Contractor shall be responsible for redistributing the topsoil over proposed turf and landscaped areas to a minimum depth of 6-inches below final grade.
- All areas shall be graded for positive drainage. Unless noted otherwise the following grades shall apply:
 - a. Turf Areas - 2.5% Minimum, 4H:1V Maximum
 - b. Paved Areas - 1.2% Minimum, 5% Maximum
- A.D.A. parking stalls shall not be sloped greater than 2% in any direction and constructed per A.D.A. requirements.
- All disturbed areas shall be fertilized, seeded and mulched immediately after earthwork activities have ceased. Seeding shall be per the Erosion and Sediment Control Plan and/or Landscape Plan. If not specified seeding shall be per APWA Section 2400, latest edition. Unless otherwise noted, seeding shall be subsidiary to the contract price for earthwork and grading activities.
- All disturbed areas in the right-of-way shall be sodded.
- Underdrains are recommended for all paved areas adjacent to irrigated turf and landscaped beds.
- Contractor shall adhere to the reporting requirements outlined in the Storm Water Pollution Prevention Plan (SWPPP) prepared for this project. Erosion and Sediment control devices shall be properly maintained and kept clean of silt and debris and in good working order. Additional erosion and sediment control measures shall be installed as required.

UTILITIES:

- Existing utilities have been shown to the greatest extent possible based upon information provided to the Engineer. The contractor is responsible for contacting the respective utility companies and field locating utilities prior to construction and identifying any potential conflicts. All conflicts shall immediately be brought to the attention of the Engineer.
- The contractor shall be responsible for coordinating any required utility relocations. Utilities damaged through the negligence of the contractor shall be repaired at the contractor's expense.
- Contractor shall verify flow-lines and structure tops prior to construction, and shall notify Engineer of any discrepancies. Provide shop drawings for all precast and manufactured utility structures for review by the Engineer prior to construction of the structures.
- Utility Separation: Waterlines shall have a minimum of 10 feet horizontal and 2 feet vertical separation from all sanitary sewer lines, manholes, and sanitary sewer service laterals, as measured from edge to edge. If minimum separations can not be obtained, concrete encasement of the sanitary line shall be required 10 feet in each direction of the conflict.
- Payment for trenching, backfilling, pipe embedment, flowable fill, backfill materials, clean up, seeding, sodding and any other items necessary for the construction of the utility line shall be included in the contract price for the utility installation.
- The Contractor shall be responsible for contacting respective utility companies 48-hours in advance for the inspection of any proposed utility main extension or service line or service connection to any existing main.
- Trench spoils shall be neatly placed onsite adjacent to the trench, and compacted to prevent saturation and excess sediment runoff. Unsuitable materials, excess rock and shale, asphalt, concrete, trees, brush etc. shall be properly disposed of offsite. Materials may be wasted onsite at the direction of the Owner or his appointed representative.
- All excavation is considered unclassified, unless noted otherwise. Unclassified excavation for utility trenching is subsidiary to the unit price provided for the pipe. Any quantity provided for rock excavation is estimated based on the best information provided to the Project Engineer. The Engineer has the authority to identify and define the physical characteristics to determine the classification. Unit price quantities for rock excavation will be paid at a trench width of the nominal pipe diameter of the installed main plus 18 inches. Contractor is required to dispose of excess rock from their trenches by disposing it in areas as specified by the Project Engineer.

Sheet Number	Sheet Title
1	COVER SHEET
2	TYPICAL SECTIONS
3	GENERAL LAYOUT
4	OVERALL GRADING PLAN
5	GRADING PLAN
6	OVERALL DRAINAGE MAP
7	REUNION - DRAINAGE MAP
8	PRE-CONSTRUCTION EROSION CONTROL PLAN
9	EROSION CONTROL PLAN
10	POST-CONSTRUCTION EROSION CONTROL PLAN
11	SE WOOD LANE - PLAN & PROFILE
12	SE HIGHLAND PARK DRIVE - PLAN & PROFILE
13	SE 5TH TERRACE - PLAN & PROFILE
14	SE LINDBERG LANE - PLAN & PROFILE
15	INTERSECTION DETAILS
16	INTERSECTION DETAILS
17	STREET DETAILS
18	STREET

PREPARED BY:

 STATE OF MISSOURI
 MARK ALLEN BREUER
 NUMBER PE-2009007268
 09.18.2023

SCHLAGEL & ASSOCIATES, P.A.

REUNION AT BLACKWELL
PUBLIC STREET AND STORM SEWER PLANS

SE SHENANDOAH DRIVE LEE'S SUMMIT, MO

PUBLIC STREETS

TABLE LS-2: MINIMUM ASPHALT PAVEMENT THICKNESSES

Street Classification	Pavement Option	AC Surface (in.)	AC Base (in.)	Aggregate Base (in.)	Chemical Subgrade Stabilization (in.)	Geogrid / Geotextile ⁽¹⁾
Residential Local/Access	A	2	4	6	6	--
	B	2	4	10	--	Geogrid / Geotextile
Residential Collector	A	2	5.5	6	9	--
	B	2	5.5	12	--	Geogrid / Geotextile
Commercial Industrial Local/Collector	A	2	7.5	6	9	--
	B	2	7.5	12	--	Geogrid / Geotextile

Notes:

(1) Geogrid shall be polypropylene material and Geotextile shall be woven, polypropylene as shown in the City's Approved Products List

Asphalt location	Mix Type	Recycled Mix Allowed?	Upper PG Limit	Lower PG limit
Industrial/Arterial surface	5 or 6	no	70 or greater	-22 or less
Base courses greater than 2 inches below the surface on industrial and arterial streets	5	yes	64 or greater	-22 or less
Local and Collector surface	5 or 6	no	64 or greater	-22 or less
Base courses greater than 2 inches below the surface on local and collector streets	5	yes	64 or greater	-22 or less

STREET NOTES:

- ALL STREET CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE CITY OF LEE'S SUMMIT DESIGN AND CONSTRUCTION MANUAL. ALL APPLICABLE AASHTO STANDARDS HAVE BEEN MET.
- THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING ALL EXISTING UTILITY LOCATIONS PRIOR TO EXCAVATION.
- ALL INSPECTION OF STREET CONSTRUCTION TO BE PERFORMED BY THE CITY OF LEE'S SUMMIT DEVELOPMENT ENGINEERING.
- CURB RETURN RADII SHALL BE 25' AT BACK OF CURB UNLESS OTHERWISE NOTED.
- SUBGRADE TO BE COMPACTED TO 95% STANDARD PROCTOR DENSITY.
- ASSUMED DESIGN SPEED = 25 MPH (RESIDENTIAL LOCAL).
- MINIMUM STOPPING SIGHT DISTANCE = 155 FEET.
- MINIMUM K-SAG CURVE = 26 (14 WITH LIGHTING). CREST CURVE = 12.
- GRADE INTERSECTIONS TO DRAIN AS SHOWN.
- SSD = STOPPING SIGHT DISTANCE.
- ALL ADA SIDEWALK RAMPS SHALL BE CONSTRUCTED BY THE DEVELOPER WITH THE PUBLIC INFRASTRUCTURE.

MO GRS BENCHMARK:

STATION NAME - JA-90


KC METRO ALUMINUM GRS DISK SET IN CONCRETE STAMPED "JA-90, 1988" LOCATED NEAR THE INTERSECTION OF LANGSFORD ROAD AND OLD LANGSFORD ROAD, 43 FEET SOUTHEAST OF THE CENTER OF LANGSFORD ROAD AND 32 FEET NORTH OF THE CENTER OF OLD LANGSFORD ROAD. N:1001052.8503, E:2845604.8272

ELEV. 997.045

PROJECT BENCHMARK:

"SQUARE" CUT IN TOP OF CONCRETE STORM MANHOLE. STORM MANHOLE IS LOCATED APPROX. 130 FEET EAST OF THE INTERSECTION OF SE JOEL AVE & BLUE PARKWAY AND 26 FEET SOUTH OF THE CENTERLINE OF BLUE PARKWAY. N:996874.9690, E:2840937.1365

ELEV. 1005.719




PUBLIC STREETS
 RESIDENTIAL LOCAL
 SE WOOD LANE STA. 0+48.00 TO STA. 4+50.61
 SE HIGHLAND PARK DRIVE STA. 0+39.00 TO STA. 11+28.00
 SE 5TH STREET STA. 17+85.61 TO STA. 25+50.00
 SE LINDBERG LANE STA. 25+50.00 TO STA. 31+77.53
 (NTS)

REUNION AT BLACKWELL PUBLIC STREET AND STORM SEWER PLANS

SE SHENANDOAH DRIVE LEE'S SUMMIT, MO

3



PRIVATE ROAD NOTE:
SE LINCOLN STREET, SE GOLDEN LANE & SE 6TH STREET ARE
PRIVATE ROADS AND WILL BE CONSTRUCTED UNDER A SEPARATE PLAN SET.

SIDEWALK NOTE:
SIDEWALKS ADJACENT TO BUILDINGS WILL BE INSTALLED BY
OTHERS, UNLESS NOTED OTHERWISE.

MO GRS BENCHMARK:

STATION NAME - JA-90


KC METRO ALUMINUM GRS DISK SET IN CONCRETE STAMPED "JA-90, 1988"
LOCATED NEAR THE INTERSECTION OF LANGSFORD ROAD AND OLD
LANGSFORD ROAD, 43 FEET SOUTHEAST OF THE CENTER OF OLD LANGSFORD ROAD.
N:1001052.8503, E:2845604.8272

ELEV. 997.045

PROJECT BENCHMARK:

"SQUARE" CUT IN TOP OF CONCRETE STORM MANHOLE
STORM MANHOLE IS LOCATED APPROX. 130 FEET EAST OF THE
INTERSECTION OF SE JOEL AVE & BLUE PARKWAY AND 26 FEET SOUTH
OF THE CENTERLINE OF BLUE PARKWAY.
N:996874.9630, E:2840937.1365

ELEV. 1005.719



0 50' 100'

SCALE: 1" = 50'

GENERAL LAYOUT	
DRAWN BY: TRC 05/05/2023	DESCRIPTION PER CITY COMMENTS △ 05/05/2023 △ 05/05/2023 △ 05/05/2023

SHEET


3

3



REUNION AT BLACKWELL PUBLIC STREET AND STORM SEWER PLANS

SE SHENANDOAH DRIVE LEE'S SUMMIT, MO



GRADING LEGEND:

- 1000 — EXISTING CONTOUR
- 1000 — PROPOSED CONTOUR (FINISHED GRADE)

NOTES:

1. ALL CONSTRUCTION ON THIS PROJECT SHALL CONFORM TO THE CITY OF LEE'S SUMMIT TECHNICAL SPECIFICATIONS.
2. THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING ALL EXISTING UTILITY LOCATIONS PRIOR TO EXCAVATION.

MO GRS BENCHMARK:

STATION NAME - JA-90

KC METRO ALUMINUM GRS DISK SET IN CONCRETE STAMPED "JA-90, 1988" LOCATED NEAR THE INTERSECTION OF LANGSFORD ROAD AND OLD LANGSFORD ROAD, 43 FEET SOUTHEAST OF THE CENTER OF LANGSFORD ROAD AND 32 FEET NORTH OF THE CENTER OF OLD LANGSFORD ROAD.
N:396874.9690, E:2840937.1365
ELEV. 1005.719


ELEV. 997.045

PROJECT BENCHMARK:


"SQUARE" CUT IN TOP OF CONCRETE STORM MANHOLE STORM MANHOLE IS LOCATED APPROX. 130 FEET EAST OF THE INTERSECTION OF SE JOEL AVE & BLUE PARKWAY AND 26 FEET SOUTH OF THE CENTERLINE OF BLUE PARKWAY.
N:396874.9690, E:2840937.1365

OVERALL GRADING PLAN

SHEET



PREPARED BY:




MARK ALLEN BREUER
NUMBER PE-2009007268
09.18.2023

SCHLAGEL & ASSOCIATES, P.A.

**REUNION AT BLACKWELL
PUBLIC STREET AND STORM SEWER PLANS**

SE SHENANDOAH DRIVE LEE'S SUMMIT, MO



GRADING LEGEND:

- 1000 — EXISTING CONTOUR
- 1000 — PROPOSED CONTOUR (FINISHED GRADE)

NOTES:

1. ALL CONSTRUCTION ON THIS PROJECT SHALL CONFORM TO THE CITY OF LEE'S SUMMIT TECHNICAL SPECIFICATIONS.
2. THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING ALL EXISTING UTILITY LOCATIONS PRIOR TO EXCAVATION.

MO GRS BENCHMARK:

STATION NAME - JA-90

KC METRO ALUMINUM GRS DISK SET IN CONCRETE STAMPED "JA-90, 1988" LOCATED NEAR THE INTERSECTION OF LANGSFORD ROAD AND OLD LANGSFORD ROAD, 43 FEET SOUTHEAST OF THE CENTER OF OLD LANGSFORD ROAD AND 32 FEET NORTH OF THE CENTER OF NEW LANGSFORD ROAD.
N:1001052.8503, E:2845604.8272

ELEV. 997.045

PROJECT BENCHMARK:


"SQUARE" CUT IN TOP OF CONCRETE STORM MANHOLE STORM MANHOLE IS LOCATED APPROX. 130 FEET EAST OF THE INTERSECTION OF SE JOEL AVE & BLUE PARKWAY AND 26 FEET SOUTH OF THE CENTERLINE OF BLUE PARKWAY.
N:996874.9690, E:2840937.1365

ELEV. 1005.719

GRADING PLAN	
DRAWN BY: TRC 06/06/2023	DESCRIPTION PER CITY COMMENTS 06/06/2023 PER CITY COMMENTS 06/06/2023 PER CITY COMMENTS
CHECKED BY: MAB 06/06/2023	
DATE PREPARED: 06/06/2023	
PROJ. NUMBER: 22-097	
SHEET	



SHEET



5



REUNION AT BLACKWELL PUBLIC STREET AND STORM SEWER PLANS SE SHENANDOAH DRIVE LEE'S SUMMIT, MO

ON-SITE CONSTRUCTION AREAS:

- ONSITE 2**: AREA = 4.93 AC CN = 94
- ONSITE 4**: AREA = 23.79 AC CN = 85
- ONSITE 5**: AREA = 19.08 AC CN = 88
- EX OFFSITE 1**: AREA = 6.94 AC CN = 88
- ONSITE 3**: AREA = 12.00 AC CN = 88

UNPLATTED PARCEL #

60-500-01-02-02-0-00-000

FURRY, MICHAEL E

PIERSON, ARMINDA K

FURRY, BLAKE

NE CORNER NW 1/4

SEC. 11-47-31

NS

SLS

NS




09.18.2023

SCHLAGEL & ASSOCIATES, P.A.

**REUNION AT BLACKWELL
PUBLIC STREET AND STORM SEWER PLANS**


SE SHENANDOAH DRIVE LEE'S SUMMIT, MO




REUNION - DRAINAGE MAP		DESCRIPTION
DRAWN BY:	REVISION DATE	PER CITY COMMENTS
####	09.05.2023	PER CITY COMMENTS
CHECKED BY:	####	PER CITY COMMENTS
####	09.05.2023	PER CITY COMMENTS
DATE PREPARED	09.05.2023	PER CITY COMMENTS
PROJ. NUMBER:	22-097	PER CITY COMMENTS
SHEET		
	0	60'
	60'	120'
	120'	
	SCALE: 1" = 60'	

REUNION AT BLACKWELL PUBLIC STREET AND STORM SEWER PLANS

SE SHENANDOAH DRIVE LEE'S SUMMIT, MO



PREPARED BY:




MARK ALLEN BREUER
 NUMBER PE-2009007-268

09.18.2023

SCHLAGEL & ASSOCIATES, P.A.

**REUNION AT BLACKWELL
 PUBLIC STREET AND STORM SEWER PLANS**

SE SHENANDOAH DRIVE LEE'S SUMMIT, MO



NOTES:

- ALL CONSTRUCTION ON THIS PROJECT SHALL CONFORM TO THE CITY OF LEE'S SUMMIT TECHNICAL SPECIFICATIONS.
- THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING ALL EXISTING UTILITY LOCATIONS PRIOR TO EXCAVATION.
- SEE SHEET 8 FOR EROSION CONTROL NOTES, LEGEND AND STAGING CHART.

MO GRS BENCHMARK:

STATION NAME - JA-90

KC METRO ALUMINUM GRS DISK SET IN CONCRETE STAMPED "JA-90, 1988" LOCATED NEAR THE INTERSECTION OF LANGSFORD ROAD AND OLD LANGSFORD ROAD, 43 FEET SOUTHEAST OF THE CENTERLINE OF LANGSFORD ROAD AND 32 FEET NORTH OF THE CENTER OF OLD LANGSFORD ROAD.
 N:1001052.8503, E:2845604.8272

ELEV. 997.045

PROJECT BENCHMARK:


"SQUARE" CUT IN TOP OF CONCRETE STORM MANHOLE STORM MANHOLE IS LOCATED APPROX. 130 FEET EAST OF THE INTERSECTION OF SE JOEL AVE & BLUE PARKWAY AND 26 FEET SOUTH OF THE CENTERLINE OF BLUE PARKWAY.
 N:996874.9690, E:2840937.1365

ELEV. 1005.719

**EROSION
 CONTROL PLAN**

SHEET

6



PRIVATE ROAD NOTE:
 SE LINCOLN STREET, SE GOLDEN LANE & SE 6TH STREET ARE PRIVATE ROADS AND WILL BE CONSTRUCTED UNDER A SEPARATE PLAN SET.

SCALE: 1" = 100'

PREPARED BY:
STATE OF MISSOURI
MARK ALLEN BREUER
NUMBER PE-2009007268
09.18.2023

SCHLAGEL & ASSOCIATES, P.A.


**REUNION AT BLACKWELL
PUBLIC STREET AND STORM SEWER PLANS**

SE SHENANDOAH DRIVE LEE'S SUMMIT, MO


POST-CONSTRUCTION
EROSION
CONTROL PLAN

SHEET

10



SCALE: 1" = 100'



PRIVATE ROAD NOTE:
SE LINCOLN STREET, SE GOLDEN LANE & SE 6TH STREET ARE
PRIVATE ROADS AND WILL BE CONSTRUCTED UNDER A SEPARATE PLAN SET.

NOTES:

1. ALL CONSTRUCTION ON THIS PROJECT SHALL CONFORM TO THE CITY OF LEE'S SUMMIT TECHNICAL SPECIFICATIONS.
2. THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING ALL EXISTING UTILITY LOCATIONS PRIOR TO EXCAVATION.
3. SEE SHEET 8 FOR EROSION CONTROL NOTES, LEGEND AND STAGING CHART.

MO GRS BENCHMARK:

STATION NAME - JA-90

KC METRO ALUMINUM GRS DISK SET IN CONCRETE STAMPED "JA-90, 1988"
LOCATED NEAR THE INTERSECTION OF LANGSFORD ROAD AND OLD
LANGSFORD ROAD, 43 FEET SOUTHEAST OF THE CENTER OF LANGSFORD ROAD
N:1001052.8503, E:2845604.8272


ELEV. 997.045

PROJECT BENCHMARK:

"SQUARE" CUT IN TOP OF CONCRETE STORM MANHOLE
STORM MANHOLE IS LOCATED APPROX. 130 FEET EAST OF THE
INTERSECTION OF SE JOEL AVE & BLUE PARKWAY AND 26 FEET SOUTH
OF THE CENTERLINE OF BLUE PARKWAY.
N:996874.9690, E:2840937.1365

ELEV. 1005.719


DRAWN BY:	DESCRIPTION
TRC	09/05/2023 PER CITY COMMENTS
	09/05/2023 PER CITY COMMENTS
	09/05/2023 PER CITY COMMENTS
MAB	09/06/2023 PER CITY COMMENTS
	09/06/2023 PER CITY COMMENTS
	09/06/2023 PER CITY COMMENTS
DATE PREPARED	09/05/2023
PROJ. NUMBER	22-097



SCHLAGEL & ASSOCIATES, P.A.

SE SHENANDOAH DRIVE LEE'S SUMMIT, MO

SE WOOD LANE - PLAN & PROFILE		DESCRIPTION	PER CITY COMMENTS	PER CITY COMMENTS	PER CITY COMMENTS
DRAWN BY:	REVISION DATE				
TRC	08/09/2023				
CHECKED BY:	08/09/2023				
MAB	08/09/2023				
DATE PREPARED:	08/09/2023				
PROJ. NUMBER:	11				
FILE NUMBER:	22-097				



PROJECT BENCHMARK:

"SQUARE" CUT IN TOP OF CONCRETE STORM MANHOLE
STORM MANHOLE IS LOCATED APPROX. 130 FEET EAST OF THE
INTERSECTION OF SE JOEL AVE & BLUE PARKWAY AND 26 FEET SOUTH
OF THE CENTERLINE OF BLUE PARKWAY.
N:996874.9690, E:2840937.1365

ELEV. 1005.719

MO GRS BENCHMARK:

STATION NAME - JA-90

KC METRO ALUMINUM GRS DISK SET IN CONCRETE STAMPED "JA-90, 1988"
LOCATED NEAR THE INTERSECTION OF LANGSFORD ROAD AND OLD
LANGSFORD ROAD, 43 FEET SOUTHEAST OF THE CENTER OF LANGSFORD
ROAD AND 32 FEET NORTH OF THE CENTER OF OLD LANGSFORD ROAD.
N:1001052.8503, E:2845604.8272


ELEV. 997.045

STREET NOTES:


- ALL STREET CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE CITY OF LEE'S SUMMIT DESIGN AND CONSTRUCTION MANUAL. ALL APPLICABLE AASHTO STANDARDS HAVE BEEN MET.
- THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING ALL EXISTING UTILITY LOCATIONS PRIOR TO EXCAVATION.
- ALL INSPECTION OF STREET CONSTRUCTION TO BE PERFORMED BY THE CITY OF LEE'S SUMMIT DEVELOPMENT ENGINEERING.
- CURB RETURN RADII SHALL BE 25' AT BACK OF CURB UNLESS OTHERWISE NOTED.
- SUBGRADE TO BE COMPACTED TO 95% STANDARD PROCTOR DENSITY.
- ASSUMED DESIGN SPEED = 25 MPH (RESIDENTIAL LOCAL).
- MINIMUM STOPPING SIGHT DISTANCE = 155 FEET.
- MINIMUM K, SAG CURVE = 26 (14 WITH LIGHTING), CREST CURVE = 12.
- GRADE INTERSECTIONS TO DRAIN AS SHOWN.
- SSD = STOPPING SIGHT DISTANCE.
- ALL ADA SIDEWALK RAMPS SHALL BE CONSTRUCTED BY THE DEVELOPER WITH THE PUBLIC INFRASTRUCTURE.

PRIVATE ROAD NOTE:
SE BRADFREE STREET, SE GOLDEN LANE & SE 6TH STREET ARE PRIVATE ROADS AND WILL BE CONSTRUCTED UNDER A SEPARATE PLAN SET.

SIDEWALK NOTE:
SIDEWALKS ADJACENT TO BUILDINGS WILL BE INSTALLED BY OTHERS, UNLESS NOTED OTHERWISE.




SCALE: 1" = 50'



PREPARED BY:

 MARK ALLEN BREUER
 NUMBER PE-2009007268
 09.18.2023

SCHLAGEL & ASSOCIATES, P.A.



STREET NOTES:

- ALL STREET CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE CITY OF LEE'S SUMMIT DESIGN AND CONSTRUCTION MANUAL. ALL APPLICABLE AASHTO STANDARDS HAVE BEEN MET.
- THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING ALL EXISTING UTILITY LOCATIONS PRIOR TO EXCAVATION.
- ALL INSPECTION OF STREET CONSTRUCTION TO BE PERFORMED BY THE CITY OF LEE'S SUMMIT DEVELOPMENT ENGINEERING.
- CURB RETURN RADII SHALL BE 25' AT BACK OF CURB UNLESS OTHERWISE NOTED.
- SUBGRADE TO BE COMPACTED TO 95% STANDARD PROCTOR DENSITY.
- ASSUMED DESIGN SPEED = 25 MPH (RESIDENTIAL LOCAL).
- MINIMUM STOPPING SIGHT DISTANCE = 155 FEET.
- MINIMUM K, SAG CURVE = 26 (14 WITH LIGHTING), CREST CURVE = 12.
- GRADE INTERSECTIONS TO DRAIN AS SHOWN.
- SSD = STOPPING SIGHT DISTANCE.
- ALL ADA SIDEWALK RAMPS SHALL BE CONSTRUCTED BY THE DEVELOPER WITH THE PUBLIC INFRASTRUCTURE.

MO GRS BENCHMARK:

STATION NAME - JA-90

KC METRO ALUMINUM GRS DISK SET IN CONCRETE STAMPED "JA-90, 1988" LOCATED NEAR THE INTERSECTION OF LANGSFORD ROAD AND OLD LANGSFORD ROAD, 43 FEET SOUTHEAST OF THE CENTER OF LANGSFORD ROAD AND 32 FEET NORTH OF THE CENTERLINE OF OLD LANGSFORD ROAD. N:1001052.8503, E:2845604.8272

ELEV. 997.045


PROJECT BENCHMARK:

"SQUARE" CUT IN TOP OF CONCRETE STORM MANHOLE. STORM MANHOLE IS LOCATED APPROX. 130 FEET EAST OF THE INTERSECTION OF SE JOEL AVE & BLUE PARKWAY AND 26 FEET SOUTH OF THE CENTERLINE OF BLUE PARKWAY. N:996874.9690, E:2840937.1365

ELEV. 1005.719


PRIVATE ROAD NOTE:
 SE BRADFREE STREET, SE GOLDEN LANE & SE 6TH STREET ARE PRIVATE ROADS AND WILL BE CONSTRUCTED UNDER A SEPARATE PLAN SET.

SIDEWALK NOTE:
 SIDEWALKS ADJACENT TO BUILDINGS WILL BE INSTALLED BY OTHERS, UNLESS NOTED OTHERWISE.



SCALE: 1" = 50'

SE HIGHLAND PARK DRIVE (PUBLIC)



REUNION AT BLACKWELL PUBLIC STREET AND STORM SEWER PLANS


SE SHENANDOAH DRIVE LEE'S SUMMIT, MO

12

SHEET	DRAWN BY: TRC	REVISION DATE: 05/05/2023	DESCRIPTION	
			PER CITY COMMENTS	PER CITY COMMENTS
SE HIGHLAND PARK DRIVE - PLAN & PROFILE	CHECKED BY: MAB	05/05/2023	05/05/2023	05/05/2023
	DATE PREPARED: 05/05/2023		05/05/2023	05/05/2023
	PROJ. NUMBER: 22-097			

PREPARED BY:
 STATE OF MISSOURI
 MARK ALLEN BREUER
 NUMBER PE-2009007268
 09.18.2023

SCHLAGEL & ASSOCIATES, P.A.



STREET NOTES:

- ALL STREET CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE CITY OF LEE'S SUMMIT DESIGN AND CONSTRUCTION MANUAL. ALL APPLICABLE AASHTO STANDARDS HAVE BEEN MET.
- THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING ALL EXISTING UTILITY LOCATIONS PRIOR TO EXCAVATION.
- ALL INSPECTION OF STREET CONSTRUCTION TO BE PERFORMED BY THE CITY OF LEE'S SUMMIT DEVELOPMENT ENGINEERING.
- CURB RETURN RADII SHALL BE 25' AT BACK OF CURB UNLESS OTHERWISE NOTED.
- SUBGRADE TO BE COMPACTED TO 95% STANDARD PROCTOR DENSITY.
- ASSUMED DESIGN SPEED = 25 MPH (RESIDENTIAL LOCAL).
- MINIMUM STOPPING SIGHT DISTANCE = 155 FEET.
- MINIMUM K-SAG CURVE = 26 (WITH LIGHTING), CREST CURVE = 12.
- GRADE INTERSECTIONS TO DRAIN AS SHOWN.
- SSD = STOPPING SIGHT DISTANCE.
- ALL ADA SIDEWALK RAMPS SHALL BE CONSTRUCTED BY THE DEVELOPER WITH THE PUBLIC INFRASTRUCTURE.

MO GRS BENCHMARK:

STATION NAME - JA-90

KC METRO ALUMINUM GRS DISK SET IN CONCRETE STAMPED "JA-90, 1988" LOCATED NEAR THE INTERSECTION OF LANGSFORD ROAD AND OLD LANGSFORD ROAD, 43 FEET SOUTHEAST OF THE CENTER OF LANGSFORD ROAD AND 32 FEET NORTH OF THE CENTER OF OLD LANGSFORD ROAD. N:1001052.8503, E:2845604.8272

ELEV. 997.045

PROJECT BENCHMARK:

"SQUARE" CUT IN TOP OF CONCRETE STORM MANHOLE. STORM MANHOLE IS LOCATED APPROX. 130 FEET EAST OF THE INTERSECTION OF SE JOEL AVE & BLUE PARKWAY AND 26 FEET SOUTH OF THE CENTERLINE OF BLUE PARKWAY. N:996874.9690, E:2840937.1365



ELEV. 1005.719

PRIVATE ROAD NOTE:

SE BRADFREE STREET, SE GOLDEN LANE & SE 6TH STREET ARE PRIVATE ROADS AND WILL BE CONSTRUCTED UNDER A SEPARATE PLAN SET.

SIDEWALK NOTE:

SIDEWALKS ADJACENT TO BUILDINGS WILL BE INSTALLED BY OTHERS, UNLESS NOTED OTHERWISE.




**REUNION AT BLACKWELL
PUBLIC STREET AND STORM SEWER PLANS**

SE SHENANDOAH DRIVE LEE'S SUMMIT, MO

SE 5TH TERRACE - PLAN & PROFILE		DESCRIPTION	REVISION DATE	PER CITY COMMENTS
SHEET	DRAWN BY:	TRC	05/05/2023	PER CITY COMMENTS
	CHECKED BY:	△	05/05/2023	PER CITY COMMENTS
	MAB	△	05/05/2023	PER CITY COMMENTS
DATE PREPARED	5/5/2023	△	05/05/2023	PER CITY COMMENTS
PROJ. NUMBER	22-097	△	05/05/2023	PER CITY COMMENTS
13				


PREPARED BY:



SCHLAGEL & ASSOCIATES, P.A.

SE SHENANDOAH DRIVE LEE'S SUMMIT, MO

REUNION AT BLACKWELL PUBLIC STREET AND STORM SEWER PLANS



STREET NOTES:

- ALL STREET CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE CITY OF LEE'S SUMMIT DESIGN AND CONSTRUCTION MANUAL. ALL APPLICABLE AASHTO STANDARDS HAVE BEEN MET.
- THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING ALL EXISTING UTILITY LOCATIONS PRIOR TO EXCAVATION.
- ALL INSPECTION OF STREET CONSTRUCTION TO BE PERFORMED BY THE CITY OF LEE'S SUMMIT DEVELOPMENT ENGINEERING.
- CURB RETURN RADII SHALL BE 25' AT BACK OF CURB UNLESS OTHERWISE NOTED.
- GRADE INTERSECTIONS TO DRAIN AS SHOWN.
- SSD = STOPPING SIGHT DISTANCE.
- MINIMUM STOPPING SIGHT DISTANCE = 155 FEET.
- MINIMUM K, SAG CURVE = 26 (14 WITH LIGHTING), CREST CURVE = 12.
- ADA SIDEWALK RAMPS SHALL BE CONSTRUCTED BY THE DEVELOPER WITH THE PUBLIC INFRASTRUCTURE.

MO GRS BENCHMARK:


STATION NAME - JA-90
KC METRO ALUMINUM GRS DISK SET IN CONCRETE STAMPED "JA-90, 1988" LOCATED NEAR THE INTERSECTION OF LANGSFORD ROAD AND OLD LANGSFORD ROAD AND 32 FEET NORTH OF THE CENTERLINE OF OLD LANGSFORD ROAD. N:1001052.8503, E:2845604.8272
ELEV. 997.045

PROJECT BENCHMARK:

"SQUARE" CUT IN TOP OF CONCRETE STORM MANHOLE. STORM MANHOLE IS LOCATED APPROX. 130 FEET EAST OF THE INTERSECTION OF SE JOEL AVE & BLUE PARKWAY AND 26 FEET SOUTH OF THE CENTERLINE OF BLUE PARKWAY. N:996874.9690, E:2840937.1365
ELEV. 1005.719


PRIVATE ROAD NOTE:
SE BRADFREE STREET, SE GOLDEN LANE & SE 6TH STREET ARE PRIVATE ROADS AND WILL BE CONSTRUCTED UNDER A SEPARATE PLAN SET.





SIDEWALK NOTE:
SIDEWALKS ADJACENT TO BUILDINGS WILL BE INSTALLED BY OTHERS, UNLESS NOTED OTHERWISE.



SCALE: 1" = 50'

SE LINDBERG LANE (PUBLIC)





REUNION AT BLACKWELL PUBLIC STREET AND STORM SEWER PLANS


SE SHENANDOAH DRIVE LEE'S SUMMIT, MO

DESCRIPTION	
DRAWN BY:	REVISION DATE
TRC	1 05/05/2023 PER CITY COMMENTS
MAB	2 06/02/2023 PER CITY COMMENTS
	3 06/27/2023 PER CITY COMMENTS
	4 09/06/2023 PER CITY COMMENTS
DATE PREPARED:	
6 03/03/2023	
PROJ. NUMBER:	
8 22-097	

INTERSECTION DETAILS

SHEET

15




PREPARED BY:

 STATE OF MISSOURI
 MARK ALLEN BREUER
 NUMBER PE-2009007268
 09.18.2023

SCHLAGEL & ASSOCIATES, P.A.

**REUNION AT BLACKWELL
PUBLIC STREET AND STORM SEWER PLANS
SE SHENANDOAH DRIVE LEE'S SUMMIT, MO**


SE LINDBERG LANE (PUBLIC) & SE 6TH STREET (PRIVATE)




0 10' 20'

16

SCALE: 1" = 10'




SE 5TH TERRACE (PUBLIC) & SE BRADFREE STREET (PRIVATE)




SE LINDBERG LANE (PUBLIC) & SE 6TH STREET (PRIVATE)


SE 5TH TERRACE (PUBLIC) & SE HIGHLAND PARK DRIVE (PUBLIC)




SE 5TH TERRACE (PUBLIC) & SE HIGHLAND PARK DRIVE (PUBLIC)



SE 5TH TERRACE (PUBLIC) & SE HIGHLAND PARK DRIVE (PUBLIC)




SE 5TH TERRACE (PUBLIC) & SE HIGHLAND PARK DRIVE (PUBLIC)



SE 5TH TERRACE (PUBLIC) & SE HIGHLAND PARK DRIVE (PUBLIC)

PREPARED BY:



09.18.2023

SCHLAGEL & ASSOCIATES, P.A.

LEE'S SUMMIT MISSOURI

PUBLIC WORKS ENGINEERING DIVISION | 1205 GREEN STREET | LEE'S SUMMIT, MO 64063

CITY OF LEE'S SUMMIT, MO
LEE'S SUMMIT, JACKSON COUNTY, MO
ADA RAMP RETROFIT DETAIL

Drawn By: MAB
Checked By: DL
Date: 05/2021
Proj. #: GEN-3B


Not to Scale

Sheet No. 1

Page No. 1

Page 1 of 1



PREPARED BY:



09.18.2023

SCHLAGEL & ASSOCIATES, P.A.

**REUNION AT BLACKWELL
PUBLIC STREET AND STORM SEWER PLANS
SE SHENANDOAH DRIVE LEE'S SUMMIT, MO**




SHEET	DRAWN BY:	REVISION DATE	DESCRIPTION		
			PER CITY COMMENTS	PER CITY COMMENTS	PER CITY COMMENTS
18	TRC	05/05/2023	△ 05/05/2023	△ 05/05/2023	△ 05/05/2023
	MAB	05/05/2023	△ 05/05/2023	△ 05/05/2023	△ 05/05/2023
	DATE PREPARED	05/05/2023	△ 05/05/2023	△ 05/05/2023	△ 05/05/2023
	PROJ. NUMBER:	22-097			

PREPARED BY:
STATE OF MISSOURI
MARK ALLEN BREUER
NUMBER PE-2009007268
09.18.2023

SCHLAGEL & ASSOCIATES, P.A.

**REUNION AT BLACKWELL
PUBLIC STREET AND STORM SEWER PLANS**

SE SHENANDOAH DRIVE LEE'S SUMMIT, MO



STORM PLAN	
SHEET 19	
DRAWN BY: TRC 08/09/2023 PER CITY COMMENTS	
CHECKED BY: MAB 08/09/2023 PER CITY COMMENTS	
DATE PREPARED: 08/09/2023 PER CITY COMMENTS	
PROJ. NUMBER: 22-097	
DESCRIPTION	
EXIST 8" PVC SDR-26 SANITARY SEWER	
WATER LINE F - PUBLIC (BY SEPARATE PLAN SET)	
20' U/E	
32.50' R/E	
50' R/W	
3.5' B-22'	
M.8 M.8 M.8 M.8 M.8	
PROPERTY LINE	
N	
0 50' 100'	
SCALE: 1" = 50'	

PREPARED BY:

 MARK ALLEN BREUER
NUMBER
PE-2009007268
09.18.2023

SCHLAGEL & ASSOCIATES, P.A.


**REUNION AT BLACKWELL
PUBLIC STREET AND STORM SEWER PLANS
SE SHENANDOAH DRIVE LEE'S SUMMIT, MO**

Design Storm:		10																											
"K" Value:		1.00																											
"F" Factor:		1.00																											
Runoff Calculations																													
Inlet #	Area (acres)		"C" Value		Cumul. Area (acres)		Cumul. Cx A		Runoff To Inlet		Runoff Cumul. Runoff		Up Pipe Cap.		Up Pipe Vel.		Up Piped Inlet 1		Up Piped Inlet 2		Up Area (acres)		Up Cx A		Pipe Properties				

LINE 100	101	0.61	0.66	20.40	13.46	8.6	6.38	2.57	85.94	103.97	10.81	201	301	0.00	0.00	101	100	HDPE	0.012	42	55.00	0.91	0.50	984.50	984.00	995.20	988.80
	102	0.40	0.66	19.79	13.06	8.6	6.39	1.69	83.45	231.47	24.06	201	301	3.52	2.32	102	101	HDPE	0.012	42	35.50	4.51	0.50	986.60	985.00	995.20	990.22
	103	0.37	0.66	15.87	10.47	8.3	6.45	1.58	67.59	78.60	8.17	401		0.42	0.28	103	102	HDPE	0.012	42	133.63	0.52	0.50	987.80	987.10	996.61	999.99
	104	0.22	0.66	15.08	9.95	7.9	6.55	0.95	65.22	82.29	8.55	501	601	1.57	1.04	104	103	HDPE	0.012	42	211.60	0.57	0.50	989.50	988.30	998.95	992.63
	105	0.11	0.66	13.29	8.77	7.7	6.61	0.48	58.02	68.17	9.64			0.00	0.00	105	104	HDPE	0.012	36	145.31	0.89	0.50	991.30	990.00	1000.55	994.44
	106	0.18	0.66	13.18	8.70	7.6	6.64	0.79	57.72	67.01	9.48	701		6.73	4.44	106	105	HDPE	0.012	36	46.74	0.86	0.50	992.20	991.80	1001.44	995.63
	107	0.64	0.66	6.27	4.14	6.9	6.80	2.87	28.14	41.21	8.39			0.00	0.00	107	106	HDPE	0.012	30	35.00	0.86	0.50	993.00	992.70	1001.44	995.72
	108	0.18	0.66	5.63	3.72	6.8	6.82	0.81	25.36	37.44	7.63	801		0.26	0.17	108	107	HDPE	0.012	30	42.40	0.71	0.50	993.80	993.50	1001.65	1002.51
	109	0.12	0.66	5.19	3.43	6.6	6.89	0.55	23.61	37.18	7.57	901		0.66	0.44	109	108	HDPE	0.012	30	113.76	0.70	0.50	995.10	994.30	1002.98	1001.20
	110	0.11	0.66	4.41	2.91	6.4	6.93	0.50	20.17	22.19	7.06	1001		1.50	0.99	110	109	HDPE	0.012	24	60.72	0.82	0.50	996.09	995.60	1004.14	1005.24
	111	0.53	0.66	2.80	1.85	6.3	6.97	2.44	12.87	20.70	11.72	1101		0.65	0.43	111	110	HDPE	0.012	18	90.66	3.31	0.50	999.59	996.59	1006.03	1009.01
	112	0.42	0.66	1.62	1.07	5.6	7.16	1.98	7.65	9.28	7.57	1201		0.47	0.31	112	111	HDPE	0.012	15	306.71	1.76	0.50	1005.49	1000.09	1011.58	1018.29
	113	0.34	0.66	0.73	0.48	5.1	7.33	1.64	3.53	8.96	7.30		0.00	0.00	113	112	HDPE	0.012	15	244.59	1.64	0.50	1010.00	1005.99	1015.97	1013.70	
	114	0.39	0.66	0.39	0.26	5.0	7.35	1.89	8.84	8.34	6.80		0.00	0.00	114	113	HDPE	0.012	15	35.14	1.42	N/A	1011.00	1010.50	1016.02	1013.84	

LINE 200	201	2.31	0.66	2.31	1.52	5.0	7.35	11.21	11.21	41.95	13.35		0.00	0.00	201	102	HDPE	0.012	24	58.00	2.93	N/A	989.80	988.10	993.70	991.25
LINE 300	301	0.52	0.66	1.21	0.80	5.1	7.32	2.51	5.84	11.31	9.21		0.00	0.00	301	102	HDPE	0.012	15	216.69	2.61	0.50	994.51	988.85	999.68	995.74
	302	0.69	0.66	0.69	0.46	5.0	7.35	3.35	7.54	6.14		0.00	0.00	302	301	HDPE	0.012	15	43.08	1.16	N/A	995.51	995.01	1000.36	1000.16	
LINE 400	401	0.42	0																							

PREPARED BY:




MARK ALLEN BREUER
NUMBER
PE-2009007268

09.18.2023

SCHLAGEL & ASSOCIATES, P.A.


**REUNION AT BLACKWELL
PUBLIC STREET AND STORM SEWER PLANS
SE SHENANDOAH DRIVE LEE'S SUMMIT, MO**

RUNOFF CALCULATIONS												INLET DESIGN								GUTTER DESIGN				
INLET #	COMPOSITE "C"	AREA	Tc	INLET INTENSITY	RUNOFF	UPSTREAM INLET	UPSTREAM INLET	UPSTREAM INLET	UPSTREAM INLET	BYPASS FROM UPSTREAM INLET	TOTAL RUNOFF	STREET GRADE	STREET CROSS SLOPE	CURB TYPE	INLET LENGTH	EFFECTIVE LENGTH 80% CAP	INLET INTERCEPTION	BYPASS TO DOWNSTREAM INLET	STREET GRADE	STREET CROSS SLOPE	DEPTH AT CURB	SPREAD OF FLOW		
LINE 1																								
101	0.66	0.61	5	7.35	2.96	302	401				1.31	4.27	SUMP	2.00	A	6	4.8	13.44	0.00	SUMP	2.00	< 0.21	< 12	
102	0.66	0.40	5	7.35	1.94	103	301				0.82	2.76	SUMP	2.00	A	6	4.8	13.44	0.00	SUMP	2.00	< 0.21	< 12	
103	0.66	0.37	5	7.35	1.79	104					0.23	2.03	1.20	2.00	A	6	6	1.81	0.22	1.20	2.00	0.18	9.27	
104	0.66	0.22	5	7.35	1.07	501	502				1.02	2.08	1.20	2.00	A	6	6	1.85	0.23	1.20	2.00	0.18	9.36	
105	0.66	0.11	5	7.35	0.53	106	107	108			0.86	1.39	1.20	2.00	A	6	6	1.29	0.10	1.20	2.00	0.15	8.11	
106	0.66	0.18	5	7.35	0.87	701					0.12	1.00	1.20	2.00	A	6	6	0.95	0.05	1.20	2.00	0.13	7.22	
107	0.66	0.64	5	7.35	3.10	1401					0.68	3.78	1.20	2.00	A	6	6	3.00	0.77	1.20	2.00	0.22	11.57	
108	0.66	0.18	5	7.35	0.87	109					0.02	0.89	1.20	2.00	A	6	6	0.85	0.03	1.20	2.00	0.13	6.93	
109	0.66	0.12	5	7.35	0.58	110					0.08	0.66	1.21	2.00	A	6	6	0.64	0.02	1.21	2.00	0.11	6.25	
110	0.66	0.11	5	7.35	0.53	111					0.58	1.11	1.66	2.00	A	6	6	1.03	0.08	1.66	2.00	0.13	7.08	
111	0.66	0.53	5	7.35	2.57	112					0.34	2.91	1.66	2.00	A	6	6	2.33	0.58	1.66	2.00	0.19	9.94	
112	0.66	0.42	5	7.35	2.04	113					0.18	2.22	1.66	2.00	A	6	6	1.88	0.34	1.66	2.00	0.17	9.03	
113	0.66	0.34	5	7.35	1.65						0.00	1.65	1.66	2.00	A	6	6	1.47	0.18	1.66	2.00	0.15	8.13	
114	0.66	0.39	5	7.35	1.89						0.00	1.89	1.64	2.00	A	6	6	1.65	0.24	1.64	2.00	0.16	8.55	
LINE 3																								
301	0.66	0.52	5	7.35	2.52						0.00	2.52	2.70	2.00	A	6	6	1.92	0.60	2.70	2.00	0.16	8.67	
302	0.66	0.69	5	7.35	3.35						0.00	3.35	2.70	2.00	A	6	6	2.33	1.02	2.70	2.00	0.18	9.59	
LINE 4																								
401	0.66	0.42	5	7.35	2.04	601					0.30	2.34	1.20	2.00	A	6	6	2.04	0.30	1.20	2.00	0.18	9.75	
LINE 5																								
501	0.66	0.43	5	7.35	2.09						0.00	2.09	1.09	2.00	A	6	6	1.87	0.22	1.09	2.00	0.18	9.52	
502	0.66	0.71	5	7.35	3.44	702					0.52	3.97	1.09	2.00	A	6	6	3.17	0.80	1.09	2.00	0.23	11.98	
LINE 6																								
601	0.66	0.43	5	7.35	2.09	801					0.27	2.35	1.20	2.00	A	6	6	2.05	0.30	1.20	2.00	0.19	9.77	
LINE 7																								
701	0.66	0.32	5	7.35	1.55						0.00	1.55	1.20	2.00	A	6	6	1.43	0.12	1.20	2.00	0.16	8.43	
702	0.66	0.58	5	7.35	2.81	703					0.29	3.10	1.19	2.00	A	6	6	2.58	0.52	1.19	2.00	0.21	10.80	
703	0.66	0.46	5	7.35	2.23	704					0.08	2.31	1.19	2.00	A	6	6	2.02	0.29	1.19	2.00	0.18	9.72	
704	0.66	0.26	5	7.35	1.26	1601					0.02	1.28	1.19	2.00	A	6	6	1.20	0.08	1.19	2.00	0.15	7.88	
705	0.66	0.07	5	7.35	0.34						0.00	0.34	1.19	2.00	A	6	6	0.34	0.00	1.19	2.00	0.09	4.99	
706	0.66	0.03	5	7.35	0.15						0.00	0.15	1.19	2.00	A	6	6	0.15	0.00	1.19	2.00	0.07	3.77	
707	0.66	0.49	5	7.35	2.38	1601					0.02	2.39	SUMP	2.00	A	6	4.8	13.44	0.00	SUMP	2.00	< 0.21	< 12	
707	0.66	0.50	5	7.35</																				

PREPARED BY:

MARK ALLEN
NUMBER
PE-2005007268
09.18.2023

SCHLAGEL & ASSOCIATES, P.A.

LINE 100
REUNION AT BLACKWELL
PUBLIC STREET AND STORM SEWER PLANS
SE SHENANDOAH DRIVE LEE'S SUMMIT, MO






PREPARED BY:
 STATE OF MISSOURI
 MARK ALLEN BREUER
 NUMBER PE-2009007268
 09.18.2023


SCHLAGEL & ASSOCIATES, P.A.

**REUNION AT BLACKWELL
 PUBLIC STREET AND STORM SEWER PLANS**

23



SHEET	STORM PROFILES	
	DRAWN BY:	REVISION DATE
	TRC	08/05/2023
	checked by:	08/05/2023
	MAB	08/02/2023
	DATE PREPARED:	08/05/2023
	PROJ. NUMBER:	22-097


PREPARED BY:

 MARK ALLEN BREUER
NUMBER PE-2009007268
09.18.2023

SCHLAGEL & ASSOCIATES, P.A.


**REUNION AT BLACKWELL
PUBLIC STREET AND STORM SEWER PLANS
SE SHENANDOAH DRIVE LEE'S SUMMIT, MO**

SHEET	STORM PROFILES		
	DRAWN BY:	REVISION DATE	DESCRIPTION
	TRC	08/05/2023	PER CITY COMMENTS
		08/05/2023	PER CITY COMMENTS
		08/02/2023	PER CITY COMMENTS
	MAB	08/05/2023	PER CITY COMMENTS
		08/05/2023	DATE PREPARED
		08/05/2023	PROJ. NUMBER
		22-097	


LINE 700




LINE 800




LINE 1400




LINE 1500



LINE 1600







PREPARED BY:

 STATE OF MISSOURI
 MARK ALLEN BREUER
 NUMBER PE-2009007268
 09.18.2023


SCHLAGEL & ASSOCIATES, P.A.

**REUNION AT BLACKWELL
PUBLIC STREET AND STORM SEWER PLANS
SE SHENANDOAH DRIVE LEE'S SUMMIT, MO**

STORM DETAILS	
DRAWN BY:	REVISION DATE
TRC	05/05/2023
CHECKED BY:	PER CITY COMMENTS
MAB	05/05/2023
DATE PREPARED:	05/05/2023
PROJ. NUMBER:	030302023
Proj. #	22-097
SHEET	





RIP-RAP AT OUTLET
NOT TO SCALE

PREPARED BY:

 MARK ALLEN BREUER
NUMBER PE-2009007268
09.18.2023


SCHLAGEL & ASSOCIATES, P.A.

**REUNION AT BLACKWELL
PUBLIC STREET AND STORM SEWER PLANS**


SE SHENANDOAH DRIVE LEE'S SUMMIT, MO



LEE'S SUMMIT
MISSOURI
PUBLIC WORKS ENGINEERING DIVISION | 220 SE GREEN STREET | LEE'S SUMMIT, MO 64063
STORM MANHOLE FRAME DETAIL DWG-7



STORM DETAILS		DESCRIPTION	Date: 05/2021
DRAWN BY:	TRC	PER CITY COMMENTS	Drawn By: MIF
CHECKED BY:	MAB	PER CITY COMMENTS	Checked By: DL
DATE PREPARED:	05/06/2023	PER CITY COMMENTS	
PROJ. NUMBER:	AL2020038005		STM-6
SHEET	22-097		

PREPARED BY:

 MARK ALLEN BREUER
 NUMBER PE-2009007268
 09.18.2023

SCHLAGEL & ASSOCIATES, P.A.


**REUNION AT BLACKWELL
 PUBLIC STREET AND STORM SEWER PLANS
 SE SHENANDOAH DRIVE LEE'S SUMMIT, MO**


STREET SIGN PLAN		DESCRIPTION	REVISION DATE
DRAWN BY:	TRC	PER CITY COMMENTS	05/05/2023
CHECKED BY:		PER CITY COMMENTS	06/05/2023
MAB		PER CITY COMMENTS	06/02/2023
DATE PREPARED	6/5/2023	PER CITY COMMENTS	05/05/2023
PROJ. NUMBER	6		22-007

SHEET

27

SCALE: 1" = 50'





PREPARED BY:
MARK ALLEN BREUER
NUMBER PE-200607268

09.18.2023

SCHLAGEL & ASSOCIATES, P.A.

