

NEW LONGVIEW MANSION PARKING LOT STORMWATER DRAINAGE STUDY

Prepared for:

NLV Mansion, LLC
1125 Grand Blvd Ste 202
Kansas City, MO 64106

Prepared By:

Olsson, Inc.
1301 Burlington, Suite 100
North Kansas City, MO 64116
(816) 361-1177



Revised January 2024

Revised December 2023

October 2023

Olsson Project No. 022-06318



TABLE OF CONTENTS

1... Introduction	1
1.1. FEMA Floodplain Classification	2
1.2. Soil Classification	2
2... METHODOLOGY	3
3... EXISTING CONDITIONS ANALYSIS	4
4... PROPOSED CONDITIONS ANALYSIS	7
4.1. Effects of Development.....	7
4.2. Proposed BMP Facilities.....	10
5... SUMMARY	11
6... CONCLUSIONS AND RECOMMENDATIONS.....	12
7... REFERENCES.....	13

LIST OF FIGURES

Figure 1. Vicinity Map.....	1
-----------------------------	---

LIST OF TABLES

Table 1. Soil Classifications	2
Table 2. Precipitation Depths.	3
Table 3. Curve Numbers.	4
Table 4. Existing Conditions Area Data.	5
Table 5. Existing Conditions Flow Rate at Outfall.	5
Table 6. Existing Conditions Detention Basin Data.	5
Table 7. Allowable Peak Flow Rates.	6
Table 8. Proposed Conditions Area Data.	8
Table 9. Proposed Conditions at Point of Interest.	8
Table 10. Proposed Conditions Detention Basin Data.	8
Table 11. Proposed Conditions vs. Allowable Release Rates.	8
Table 12. Proposed Conditions vs. Existing Conditions at Point of Interest A.	8
Table 13. Proposed Conditions vs. Existing Conditions at Existing Detention Basin.	9

APPENDICES

Appendix A Site Maps

Appendix B Existing Conditions Model Input and Results

Appendix C Proposed Conditions Model Input and Results

1. INTRODUCTION

This Stormwater Drainage Study has been prepared to evaluate the stormwater hydrology of a proposed parking lot within the New Longview Mansion (NLV Mansion) property. The proposed parking lot will be placed on portions of developed and undeveloped areas.

The site is located northwest of the NLV Mansion building in Lee's Summit, Jackson County, Missouri. Figure 1 shows the general location of the proposed parking lot within the NLV Mansion property.

Stormwater runoff from the project site is tributary to Longview Lake, approximately 1/4 mile downstream of the study area.

This report is intended to serve as the project Stormwater Drainage Study for the NLV Mansion parking lot and has been prepared to evaluate the Existing and Proposed Conditions stormwater hydrology. Refer to Appendix B and C for hydrologic model input data and simulation results for Existing and Proposed Conditions. Refer to Appendix A for maps and exhibits.




Figure 1. Vicinity Map

1.1. FEMA Floodplain Classification

The FEMA FIRM Panel 29095C0414G (eff. January 20, 2017) depicts the proposed development areas as “Zone X.” This zone is described as “areas determined to be outside the 0.2% annual-chance floodplain.” Refer to the attached FEMA Floodplain Map (Exhibit 8-1.1) for depiction of the established floodplains relative to the project site.

1.2. Soil Classification

Soil Maps published in the Soil Survey for Jackson County, Missouri categorizes soils in the study area as:

Table 1. Soil Classifications

Hydrologic Soil Group	Map Symbol	Type	Slopes
C/D	30080	Greenton silty clay loam	5-9%
D	10128	Sharpsburg-Urban land complex	2-5%
C/D	10117	Sampsel silty clay loam	5-9%
C	99034	Udarents-Urban land complex	9-20%

NRCS Runoff Curve Numbers (CN's) in this study have been assigned to tributary areas based upon these Hydrologic Soil Groups (HSG's) and associated existing and proposed land use. Land uses in the study area include open space, streets, and residential lots for twin gallery homes. The CN's are assigned accordingly. Refer to the Soils Map in Appendix A for distribution of soil types throughout the sub-watersheds.

2. METHODOLOGY

The base data for the models prepared for this report has been obtained from available online maps and aerial imagery. Stormwater management is based upon methods and objectives defined in the Kansas City Metropolitan Chapter of the American Public Works Association's (KC-APWA) 2011 design guidance document called "Section 5600 Storm Drainage Systems & Facilities" (2011).

Runoff rates were analyzed using Autodesk Storm and Sanitary Analysis 2022 (SSA). SSA utilizes the following methods to model Existing and Proposed Conditions for stormwater runoff.

- NRCS TR-55 Unit Hydrograph Method
- 2-, 10-, and 100-year Return Frequency, 24-hour Storm Precipitation Depths (TP-40)
 - ARC Type II Soil Moisture Conditions
 - 24-Hour NRCS Type II Rainfall Distribution
 - Runoff Curve Numbers per NRCS TR-55 (Tables 2-2a – 2-2c) and KCAPWA Section 5602.3
 - NRCS TR-55 Methods for determination of Time of Concentration and Travel Time.
 - Note: SSA models use "Time of Concentration" for computing subarea hydrology.

Stormwater runoff models were created for the 2-, 10-, and 100-year design storm events. The precipitation depths used in the analysis have been interpolated from the "Technical Paper No. 40 Rainfall Frequency Atlas of the United States" (TP-40) isopluvial maps (May 1961). Table 2 below summarizes the rainfall depths used in this analysis:

Table 2. Precipitation Depths.

Return Period	24-Hour Precipitation Depth (inches)
Water Quality Storm* (WQ)	1.37
2-Year (50% Storm)	3.60
10-year (10% Storm)	5.34
100-Year (1% Storm)	7.90

*The "Water Quality Storm" is defined in the MARC & APWA "Manual of Best Management Practices for Stormwater Quality" as a 24-hour 1.37" rainfall depth. This particular storm event is utilized for proposed water quality analysis.

3. EXISTING CONDITIONS ANALYSIS

To quantify the effects of the proposed parking lot, the following area and point of interest have been chosen for existing and proposed conditions analysis. See Exhibit 01 – Existing Conditions Drainage Map in Appendix A for a visual depiction of the drainage area and point of interest.

Drainage Area represents the area north of the NLV Mansion building, which slopes westward toward SW County Park Road, then discharges to an existing 24" CMP running under the existing road. In existing conditions, the drainage area has an area of 10.56 acres.

Point of Interest A is located at the downstream invert of the existing 24" CMP on the west side of SW County Park Road and includes stormwater overtopping the road. The model references this point of interest as "Out-01" which stands for "outfall".

Existing Detention is located at the upstream invert of the existing 24" CMP, on the east side of SW County Park Road. This detention is dry and is purely used in this study to effects of stormwater events at the road. The depth of Detention is 4.5', from the invert of the 24" CMP and the crown of the roadway. See below for a brief description of the detention:

- Top of Roadway Elevation = 930.50
- Bottom of Basin / 24" CMP Invert = 926.00
- Outlet Pipe
 - 24" Corrugated Metal Pipe
 - Invert In = 926.00
 - Invert Out = 924.65
 - Pipe slope = 2.70%
 - Pipe length = 50.00'

Tables 3, 4, and 5 below summarize the results of the existing conditions analysis. The proposed conditions data is compared to these results in Section 4 of this report. Refer to Appendix B for output and a schematic for the existing conditions model and detailed calculations for the time of concentration.

Curve numbers were determined for existing and proposed conditions as shown in Table 3.

Table 3. Curve Numbers.

Land Use	Hydrologic Soil Group	Curve Number
Woods & Grass Combination	D	79
Paved Parking & Roofs	D	98

Table 4. Existing Conditions Area Data.

Area Name	Total Area (acres)	T _C (hours)	Weighted Curve Number	Q ₂ (cfs*)	Q ₁₀ (cfs*)	Q ₁₀₀ (cfs*)
A	10.56	0.294	80.47	20.52	39.26	65.27

*cfs = cubic feet per second

Table 5. Existing Conditions Flow Rate at Outfall.

Flowrate at Outfall	Q ₂ (cfs*)	Q ₁₀ (cfs)	Q ₁₀₀ (cfs)
A	20.52	36.37	63.10

*cfs = cubic feet per second

Table 6. Existing Conditions Detention Basin Data.

	Peak Q In (cfs)	T _P In (hr.)	Peak Q Out (cfs)	T _P Out (hr.)	Max V _R (ac-ft)	Peak W.S.E. (ft)
2-Year	20.44	12.17	20.02	12.17	0.008	927.64
10-Year	39.09	12.17	33.48	12.17	0.175	930.63 (Overtop)
100-Year	64.58	12.17	62.86	12.17	0.235	930.75 (Overtop)

*cfs = cubic feet per second

As seen in Table 6, the 10- and 100-year storm events overtop the crown of the roadway under existing conditions.

Per APWA Section 5608.4 and the City of Lee's Summit criteria, the performance criteria for comprehensive control is to provide detention to limit peak flow rates at downstream points of interest to maximum release rates:

- 50 percent storm peak rate less than or equal to 0.5 cubic feet per second (cfs) per site acre
- 10 percent storm peak rate less than or equal to 2.0 cfs per site acre
- 1 percent storm peak rate less than or equal to 3.0 cfs per site acre

Extended detention of the 90 percent mean annual event is also required for comprehensive control per APWA Section 5608.4.

Allowable release rates were calculated for the point of interest. Table 6 below summarizes the amount of area and the allowable discharges for each storm event.

Table 7. Allowable Peak Flow Rates.

Point of Interest	Allowable 2-Year (cfs)	Allowable 10-Year Q (cfs)	Allowable 100-Year Q (cfs)
A	5.28	21.12	31.68

4. PROPOSED CONDITIONS ANALYSIS

The proposed conditions sections of this analysis assume the parking lot at NLV Mansion is fully constructed. This analysis includes the construction of the pavement, curb, and BMPs. The difference between the existing conditions model and the proposed conditions model will be evaluated in this section as well as the allowable release rates. Refer to Exhibit 02 – Proposed Conditions Drainage Map in Appendix A for a visual depiction of the drainage area and point of interest.

During the pre-application meeting for this project, it was agreed upon with City of Lee's Summit officials that detention for this project should be waived due to the proximity of the parking lot and Longview Lake at ¼ mile. To keep the balance of stormwater that drains from the site to Longview Lake close to the current time of concentration, detention of stormwater will not be included for this project on site. BMPs are still required to meet the MARC manual water quality volume requirements.

4.1. Effects of Development

The proposed conditions analysis assumes completion of the parking lot at New Longview Mansion. The modeled point of interest is the same as the existing conditions model. The drainage area also remains the same since the parking lot is surrounded by the drainage area boundary. The following is a summary of the proposed conditions drainage area. See Exhibit 02 – Proposed Conditions Drainage Map in Appendix A. Table 7 summarizes the proposed conditions area data.

Drainage Area represents the same area as described in the existing conditions. Impervious area and curve number have been increased due to the parking lot.

To meet or reduce the increase of stormwater overtopping SW County Park Road compared to existing conditions, a 15" HDPE pipe is proposed to run parallel to the existing 24" CMP with the same invert elevations.

The analysis provided in Section 3 established existing conditions of the parking lot's drainage area.

The following tables summarize the results of the proposed conditions analysis. Tables 7 and 8 shows the effects of the parking lot for the drainage area. Refer to Appendix C for output and a schematic of the proposed conditions Storm and Sanitary Analysis 2022 model.

Table 8. Proposed Conditions Area Data.

Area Name	Total Area (acres)	T _C * (hours)	Weighted Curve Number	Q ₂ (cfs*)	Q ₁₀ (cfs*)	Q ₁₀₀ (cfs*)
A	10.56	0.294	81.58	21.56	40.49	66.57

*T_C = Time of Concentration**Table 9. Proposed Conditions at Point of Interest.**

Point of Interest	Q ₂ (cfs)	Q ₁₀ (cfs)	Q ₁₀₀ (cfs)
A	21.51	32.64	65.29

Table 10. Proposed Conditions Detention Basin Data.

	Peak Q In (cfs)	T _P In (hr.)	Peak Q Out (cfs)	T _P Out (hr.)	Max V _R (ac-ft)	Peak W.S.E. (ft)
2-Year	21.51	12.08	21.47	12.10	0.002	927.01
10-Year	40.45	12.08	32.17	12.10	0.102	929.96
100-Year	66.44	12.08	64.22	12.10	0.215	930.72 (Overtop)

*cfs = cubic feet per second

Table 11 shows post-development peak discharge values at the points of interest.

Table 11. Proposed Conditions vs. Allowable Release Rates.

Point of Interest	Q ₂ (cfs)	Q ₁₀ (cfs)	Q ₁₀₀ (cfs)
A	+16.07	+11.32	+32.54

Table 12. Proposed Conditions vs. Existing Conditions at Point of Interest A.

Point of Interest	Q ₂ (cfs)	Q ₁₀ (cfs)	Q ₁₀₀ (cfs)
A	+0.99	-3.73	+2.19

Table 13. Proposed Conditions vs. Existing Conditions at Existing Detention Basin.

	Peak Q In (cfs)	T _P In (hr.)	Peak Q Out (cfs)	T _P Out (hr.)	Max V _R (ac-ft)	Peak W.S.E. (ft)
2-Year						
Existing	20.44	12.17	20.02	12.17	0.008	927.64
Proposed	21.51	12.08	21.47	12.10	0.002	927.01
Difference	+1.07	-0.09	+1.45	-0.07	-0.006	-0.63
10-Year						
Existing	39.09	12.17	33.48	12.17	0.175	930.63 (Overtop)
Proposed	40.45	12.08	32.17	12.10	0.102	929.96
Difference	+1.36	-0.09	-1.31	-0.07	-0.073	-0.67
100-Year						
Existing	64.58	12.17	62.86	12.17	0.235	930.75 (Overtop)
Proposed	66.44	12.08	64.22	12.10	0.215	930.72 (Overtop)
Difference	+1.86	-0.09	+1.36	-0.07	-0.020	-0.03

Tables 11, 12, and 13 show increases of flow from the proposed condition compared to the allowable release rates and existing conditions at the Point of Interest, except for the 10-year flow due to the proposed 15" pipe. The 15" pipe removes the overtopping of stormwater of the road in the 10-year proposed condition and reduces the amount of stormwater overtopping the road in the 100-year proposed condition.

With the reduction in stormwater overtopping SW County Park Road and the increase of stormwater being directed under the road towards Longview Lake, a waiver is requested that the proposed conditions be accepted as is, with the increase of these flows. It should be noted that the increase of the flow to existing conditions is not more than 5% for all storm events.

4.2. Proposed BMP Facilities

Although detention for the proposed parking lot is requested to be waived, water quality volume requirements must be met through BMPs. The treatment area for the BMPs will only include areas of disturbance, and not the entire drainage area. BMP Worksheet 1 in Appendix C shows that the level of service required for the parking lot is a 7, with most of the disturbed area being impervious.

With the requirement of a level of service 7, an infiltration trench will be used with the high value rating and versatile footprint required to meet the level of service. The soil type, Greenton silty clay loam, that covers the entire disturbed area for the parking lot, has a low hydraulic conductivity and would not naturally be able to drain the treatment area under 72 hours, a requirement per the MARC Manual. Soil with a hydraulic conductivity rate of 2 micrometers/second or higher must be placed at a depth of 2' minimum below the infiltration trench to obtain proper hydraulic conductivity. A perforated pipe to drain heavy stormwater flows to the point of interest within the drainage area (see Exhibit-03 in Appendix A). A worksheet for calculations of the infiltration trench can be found in Appendix C that show meeting the design criteria for water quality volume.

5. SUMMARY

This stormwater drainage study was prepared to evaluate the hydrologic impact generated by the development of NLV Mansion parking lot and to provide a comprehensive stormwater management plan for the proposed project. Once fully constructed, the area will include 77 parking stalls, pavement, pavement striping, and an infiltration trench.

Increases in peak flow rates caused by the project are requested to be waived per the proximity to Longview Lake, and reduction of stormwater overtopping SW County Park Road. Water quality volume and level of service will be mitigated by an infiltration trench.

6. CONCLUSIONS AND RECOMMENDATIONS

The results of the analysis demonstrate that the proposed stormwater management plan for the project achieves compliance with water quality volume requirements. Once constructed, the 2- and 100-year flows at the point of interest are above the existing conditions and allowable release rates; however, stormwater flows in the 10-year proposed condition are below existing conditions at the point of interest. A waiver for the increases in flows to keep flowrates and concentration times to Longview Lake close to existing conditions and not withhold stormwater for an extended amount of time. We therefore request approval of this NLV Mansion Stormwater Drainage Study.

7. REFERENCES

KC-APWA (Kansas City Metropolitan Chapter of the American Public Works Association). (2011). "Section 5600 Storm Drainage & Facilities."

United States Weather Bureau. "Technical Paper No. 40 Rainfall Frequency Atlas of the United States" (1961). Department of Commerce, Washington, D.C

APPENDIX A


Exhibits

DWG: F:\2022\06001-06500\022-06318\40-Design\Reports\GNCV\Stormwater Drainage Study\Cals\Existing Drainage Areas_02206318_Rev2.dwg
DATE: Jan 06, 2024 8:47pm USER: ssaylor XREFS: C_PBASE_02206318



LEGEND

-  DRAINAGE AREA
-  IMPERVIOUS AREA
-  WOODS/GRASS



SCALE IN FEET

OLSSON - CIVIL ENGINEERING
MISSOURI CERTIFICATE OF AUTHORITY # 001592

PROJECT NO: 022-06318
DRAWN BY: SMS
DATE: 01/08/2024

NLV MANSION PARKING LOT
EXISTING CONDITIONS DRAINAGE MAP

olsson

1301 Burlington Street
North Kansas City, MO 64116
TEL 816.361.1177

EXHIBIT

EX-01

DWG: F:\2022\06001-06500\022-06318\40-Design\Reports\GNCV\Stormwater Drainage Study\Cals\Proposed Drainage Areas_02206318_Rev2.dwg
DATE: Jan 06, 2024 8:56pm
USER: ssaylor
XREFS: C_PBASE_02206318



LEGEND

-  DRAINAGE AREA
-  IMPERVIOUS AREA
-  WOODS/GRASS

TOTAL IMPERVIOUS AREA = 1.44 ACRES
TOTAL WOODS/GRASS AREA = 9.12 ACRES



SCALE IN FEET

OLSSON - CIVIL ENGINEERING
MISSOURI CERTIFICATE OF AUTHORITY # 001592

PROJECT NO: 022-06318
DRAWN BY: SMS
DATE: 01/08/2024

NLV MANSION PARKING LOT
PROPOSED CONDITIONS DRAINAGE MAP


olsson

1301 Burlington Street
North Kansas City, MO 64116
TEL 816.361.1177

EXHIBIT


EX-02

DWG: F:\2022\06001-06500\022-06318\40-Design\Reports\GNCV\Stormwater Drainage Study\Cals\Proposed BMP Exhibit_02300941_Rev1.dwg
DATE: Dec 12, 2023 3:36am XREFS: C_PBASE_02206318 USER: ssaylor



LEGEND

- TREATMENT AREA
- INFILTRATION TRENCH



OLSSON - CIVIL ENGINEERING
MISSOURI CERTIFICATE OF AUTHORITY # 001592

PROJECT NO: 022-06318
DRAWN BY: SMS
DATE: 12/12/2023

NLV MANSION PARKING LOT
BMP MAP


olsson

1301 Burlington Street
North Kansas City, MO 64116
TEL 816.361.1177

EXHIBIT


EX-03

Soil Map—Jackson County, Missouri (NLV Mansion Parking Lot)



Soil Map may not be valid at this scale.

Map Scale: 1:3,570 if printed on A landscape (11" x 8.5") sheet.



Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 15N WGS84



**Natural Resources
Conservation Service**

Web Soil Survey
National Cooperative Soil Survey

10/25/2023
Page 1 of 3

Soil Map—Jackson County, Missouri
(NLV Mansion Parking Lot)

MAP LEGEND

Area of Interest (AOI)

 Area of Interest (AOI)

Soils

 Soil Map Unit Polygons

 Soil Map Unit Lines

 Soil Map Unit Points

Special Point Features



Blowout



Borrow Pit



Clay Spot



Closed Depression



Gravel Pit



Gravelly Spot



Landfill



Lava Flow



Marsh or swamp



Mine or Quarry



Miscellaneous Water



Perennial Water



Rock Outcrop



Saline Spot



Sandy Spot



Severely Eroded Spot



Sinkhole



Slide or Slip



Sodic Spot



Spoil Area



Stony Spot



Very Stony Spot



Wet Spot



Other



Special Line Features

Water Features



Streams and Canals

Transportation



Rails



Interstate Highways



US Routes



Major Roads



Local Roads

Background



Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service

Web Soil Survey URL:

Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Jackson County, Missouri

Survey Area Data: Version 25, Aug 22, 2023

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Aug 30, 2022—Sep 8, 2022

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.


Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
10117	Sampsel silty clay loam, 5 to 9 percent slopes	10.4	22.9%
10128	Sharpsburg-Urban land complex, 2 to 5 percent slopes	9.8	21.5%
30080	Greenton silty clay loam, 5 to 9 percent slopes	20.0	44.0%
40107	Snead-Rock outcrop complex, warm, 5 to 14 percent slopes	0.0	0.0%
99034	Udarents-Urban land complex, 9 to 20 percent slopes	5.3	11.6%
Totals for Area of Interest		45.4	100.0%

National Flood Hazard Layer FIRMMette



94°27'29"W 38°54'21"N



1:6,000

94°26'52"W 38°53'53"N

Basemap Imagery Source: USGS National Map 2023

Legend

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR FIRM PANEL LAYOUT

SPECIAL FLOOD HAZARD AREAS		Without Base Flood Elevation (BFE) Zone A, V, A99
		With BFE or Depth Zone AE, AO, AH, VE, AR
		Regulatory Floodway
OTHER AREAS OF FLOOD HAZARD		0.2% Annual Chance Flood Hazard, Areas of 1% annual chance flood with average depth less than one foot or with drainage areas of less than one square mile Zone X
		Future Conditions 1% Annual Chance Flood Hazard Zone X
		Area with Reduced Flood Risk due to Levee. See Notes. Zone X
		Area with Flood Risk due to Levee Zone D
OTHER AREAS		NO SCREEN Area of Minimal Flood Hazard Zone X
		Effective LOMRs
		Area of Undetermined Flood Hazard Zone D
GENERAL STRUCTURES		Channel, Culvert, or Storm Sewer
		Levee, Dike, or Floodwall
OTHER FEATURES		20.2 Cross Sections with 1% Annual Chance Water Surface Elevation
		17.5 Cross Sections with 1% Annual Chance Water Surface Elevation
		Coastal Transect
		Base Flood Elevation Line (BFE)
		Limit of Study
		Jurisdiction Boundary
MAP PANELS		Coastal Transect Baseline
		Profile Baseline
		Hydrographic Feature
MAP PANELS		Digital Data Available
		No Digital Data Available
		Unmapped



The pin displayed on the map is an approximate point selected by the user and does not represent an authoritative property location.

This map complies with FEMA's standards for the use of digital flood maps if it is not void as described below. The basemap shown complies with FEMA's basemap accuracy standards

The flood hazard information is derived directly from the authoritative NFHL web services provided by FEMA. This map was exported on 10/25/2023 at 4:41 PM and does not reflect changes or amendments subsequent to this date and time. The NFHL and effective information may change or become superseded by new data over time.

This map image is void if the one or more of the following map elements do not appear: basemap imagery, flood zone labels, legend, scale bar, map creation date, community identifiers, FIRM panel number, and FIRM effective date. Map images for unmapped and unmodernized areas cannot be used for regulatory purposes.

APPENDIX B

Existing Conditions Model Input and Results

50% Chance Storm

Project Description

File Name Existing_Rev1.SPF

Project Options

Flow Units CFS
Elevation Type Elevation
Hydrology Method SCS TR-55
Time of Concentration (TOC) Method SCS TR-55
Link Routing Method Kinematic Wave
Enable Overflow Ponding at Nodes YES
Skip Steady State Analysis Time Periods ... YES

Analysis Options

Start Analysis On	00:00:00	0:00:00
End Analysis On	00:00:00	0:00:00
Start Reporting On	00:00:00	0:00:00
Antecedent Dry Days	0	days
Runoff (Dry Weather) Time Step	0 01:00:00	days hh:mm:ss
Runoff (Wet Weather) Time Step	0 00:05:00	days hh:mm:ss
Reporting Time Step	0 00:05:00	days hh:mm:ss
Routing Time Step	30	seconds

Number of Elements

	Qty
Rain Gages	1
Subbasins.....	1
Nodes.....	2
<i>Junctions</i>	0
<i>Outfalls</i>	1
<i>Flow Diversions</i>	0
<i>Inlets</i>	0
<i>Storage Nodes</i>	1
Links.....	2
<i>Channels</i>	0
<i>Pipes</i>	1
<i>Pumps</i>	0
<i>Orifices</i>	0
<i>Weirs</i>	1
<i>Outlets</i>	0
Pollutants	0
Land Uses	0

Rainfall Details

SN	Rain Gage ID	Data Source	Data Source ID	Rainfall Type	Rain Units	State	County	Return Period (years)	Rainfall Depth (inches)	Rainfall Distribution
49		Time Series	002-YEAR	Cumulative	inches	Missouri	Jackson	2.00	3.50	SCS Type II 24-hr

Subbasin Summary

SN	Subbasin ID	Area	Peak Rate Factor	Weighted Curve Number	Total Rainfall	Total Runoff	Total Runoff Volume	Peak Runoff	Time of Concentration
		(ac)			(in)	(in)	(ac-in)	(cfs)	(days hh:mm:ss)
1	Sub-01	10.56	484.00	80.47	3.50	1.67	17.63	20.52	0 00:17:38

Node Summary

SN	Element ID	Element Type	Invert Elevation	Ground/Rim (Max) Elevation	Initial Water Elevation	Surcharge Elevation	Ponded Area	Peak Inflow	Max HGL Elevation Attained	Max Surcharge Depth Attained	Min Freeboard Attained	Time of Peak Flooding Occurrence	Total Flooded Volume	Total Time Flooded
			(ft)	(ft)	(ft)	(ft)	(ft²)	(cfs)	(ft)	(ft)	(ft)	(days hh:mm)	(ac-in)	(min)
1	Out-01	Outfall	924.65					20.52	926.33					
2	Detention	Storage Node	926.00	933.00	926.00		0.00	20.44	927.64				0.00	0.00

Subbasin Hydrology

Subbasin : Sub-01

Input Data

Area (ac)	10.56
Peak Rate Factor	484
Weighted Curve Number	80.47
Rain Gage ID	Rain Gage-01

Composite Curve Number

32	Area	Soil	Curve
Soil/Surface Description	(acres)	Group	Number
Woods & grass combination, Good	9.74	D	79
Paved parking & roofs	0.82	D	98
Composite Area & Weighted CN	10.56		80.47

Time of Concentration

TOC Method : SCS TR-55

Sheet Flow Equation :

$T_c = (0.007 * ((n * L_f)^{0.8})) / ((P^{0.5}) * (S_f^{0.4}))$

Where :

- Tc = Time of Concentration (hr)
- n = Manning's roughness
- Lf = Flow Length (ft)
- P = 2 yr, 24 hr Rainfall (inches)
- Sf = Slope (ft/ft)

Shallow Concentrated Flow Equation :

- V = 16.1345 * (Sf^0.5) (unpaved surface)
- V = 20.3282 * (Sf^0.5) (paved surface)
- V = 15.0 * (Sf^0.5) (grassed waterway surface)
- V = 10.0 * (Sf^0.5) (nearly bare & untilled surface)
- V = 9.0 * (Sf^0.5) (cultivated straight rows surface)
- V = 7.0 * (Sf^0.5) (short grass pasture surface)
- V = 5.0 * (Sf^0.5) (woodland surface)
- V = 2.5 * (Sf^0.5) (forest w/heavy litter surface)
- Tc = (Lf / V) / (3600 sec/hr)

Where:

- Tc = Time of Concentration (hr)
- Lf = Flow Length (ft)
- V = Velocity (ft/sec)
- Sf = Slope (ft/ft)

Channel Flow Equation :

$V = (1.49 * (R^{(2/3)})) * (S_f^{0.5}) / n$
 $R = A_q / W_p$
 $T_c = (L_f / V) / (3600 \text{ sec/hr})$

Where :

- Tc = Time of Concentration (hr)
- Lf = Flow Length (ft)
- R = Hydraulic Radius (ft)
- Aq = Flow Area (ft²)
- Wp = Wetted Perimeter (ft)
- V = Velocity (ft/sec)
- Sf = Slope (ft/ft)
- n = Manning's roughness

Sheet Flow Computations	Subarea A	Subarea B	Subarea C
Manning's Roughness :	0.3	0	0
Flow Length (ft) :	100	0	0
Slope (%) :	2.49	0	0
2 yr, 24 hr Rainfall (in) :	3.5	0	0
Velocity (ft/sec) :	0.11	0	0
Computed Flow Time (min) :	14.94	0	0
Shallow Concentrated Flow Computations	Subarea A	Subarea B	Subarea C
Flow Length (ft) :	488	0	0
Slope (%) :	6.457	0	0
Surface Type :	Unpaved	Unpaved	Unpaved
Velocity (ft/sec) :	4.1	0	0
Computed Flow Time (min) :	1.98	0	0
Channel Flow Computations	Subarea A	Subarea B	Subarea C
Manning's Roughness :	0.03	0	0
Flow Length (ft) :	389	0	0
Channel Slope (%) :	2.57	0	0
Cross Section Area (ft²) :	28	0	0
Wetted Perimeter (ft) :	23	0	0
Velocity (ft/sec) :	9.08	0	0
Computed Flow Time (min) :	0.71	0	0
Total TOC (min)	17.64		

Subbasin Runoff Results

Total Rainfall (in)	3.5
Total Runoff (in)	1.67
Peak Runoff (cfs)	20.52
Weighted Curve Number	80.47
Time of Concentration (days hh:mm:ss)	0 00:17:38

Storage Nodes

Storage Node : Detention

Input Data


Invert Elevation (ft)	926
Max (Rim) Elevation (ft)	933
Max (Rim) Offset (ft)	7
Initial Water Elevation (ft)	926
Initial Water Depth (ft)	0
Ponded Area (ft²)	0
Evaporation Loss	0

Storage Area Volume Curves

Storage Curve : Storage-01

Stage	Storage Area	Storage Volume
(ft)	(ft²)	(ft³)
0	5	0
1	205	105
2	818	616.5
3	1840	1945.5
4	3484	4607.5
4.5	4356	6567.5
5	43560	18546.5

Storage Area Volume Curves



Storage Area Storage Volume

Storage Node : Detention (continued)

Output Summary Results

Peak Inflow (cfs)	20.44
Peak Lateral Inflow (cfs)	20.44
Peak Outflow (cfs)	20.14
Peak Exfiltration Flow Rate (cfm)	0
Max HGL Elevation Attained (ft)	927.64
Max HGL Depth Attained (ft)	1.64
Average HGL Elevation Attained (ft)	926.06
Average HGL Depth Attained (ft)	0.06
Time of Max HGL Occurrence (days hh:mm)	0 12:10
Total Exfiltration Volume (1000-ft³)	0
Total Flooded Volume (ac-in)	0
Total Time Flooded (min)	0
Total Retention Time (sec)	0

10% Chance Storm

Project Description

File Name Existing_Rev1.SPF

Project Options

Flow Units CFS
Elevation Type Elevation
Hydrology Method SCS TR-55
Time of Concentration (TOC) Method SCS TR-55
Link Routing Method Kinematic Wave
Enable Overflow Ponding at Nodes YES
Skip Steady State Analysis Time Periods ... YES

Analysis Options

Start Analysis On	00:00:00	0:00:00
End Analysis On	00:00:00	0:00:00
Start Reporting On	00:00:00	0:00:00
Antecedent Dry Days	0	days
Runoff (Dry Weather) Time Step	0 01:00:00	days hh:mm:ss
Runoff (Wet Weather) Time Step	0 00:05:00	days hh:mm:ss
Reporting Time Step	0 00:05:00	days hh:mm:ss
Routing Time Step	30	seconds

Number of Elements

	Qty
Rain Gages	1
Subbasins.....	1
Nodes.....	2
<i>Junctions</i>	0
<i>Outfalls</i>	1
<i>Flow Diversions</i>	0
<i>Inlets</i>	0
<i>Storage Nodes</i>	1
Links.....	2
<i>Channels</i>	0
<i>Pipes</i>	1
<i>Pumps</i>	0
<i>Orifices</i>	0
<i>Weirs</i>	1
<i>Outlets</i>	0
Pollutants	0
Land Uses	0

Rainfall Details

SN	Rain Gage ID	Data Source	Data Source ID	Rainfall Type	Rain Units	State	County	Return Period (years)	Rainfall Depth (inches)	Rainfall Distribution
49		Time Series	010-YEAR	Cumulative	inches	Missouri	Jackson	10.00	5.30	SCS Type II 24-hr

Subbasin Summary

SN	Subbasin ID	Area	Peak Rate Factor	Weighted Curve Number	Total Rainfall	Total Runoff	Total Runoff Volume	Peak Runoff	Time of Concentration
		(ac)			(in)	(in)	(ac-in)	(cfs)	(days hh:mm:ss)
1	Sub-01	10.56	484.00	80.47	5.30	3.20	33.79	39.26	0 00:17:38

Node Summary

SN	Element ID	Element Type	Invert Elevation	Ground/Rim (Max) Elevation	Initial Water Elevation	Surcharge Elevation	Ponded Area	Peak Inflow	Max HGL Elevation Attained	Max Surcharge Depth Attained	Min Freeboard Attained	Time of Peak Flooding Occurrence	Total Flooded Volume	Total Time Flooded
			(ft)	(ft)	(ft)	(ft)	(ft²)	(cfs)	(ft)	(ft)	(ft)	(days hh:mm)	(ac-in)	(min)
1	Out-01	Outfall	924.65					36.37	926.63					
2	Detention	Storage Node	926.00	933.00	926.00		0.00	39.09	930.63				0.00	0.00

Subbasin Hydrology

Subbasin : Sub-01

Input Data

Area (ac)	10.56
Peak Rate Factor	484
Weighted Curve Number	80.47
Rain Gage ID	Rain Gage-01

Composite Curve Number

32	Area	Soil	Curve
Soil/Surface Description	(acres)	Group	Number
Woods & grass combination, Good	9.74	D	79
Paved parking & roofs	0.82	D	98
Composite Area & Weighted CN	10.56		80.47

Time of Concentration

TOC Method : SCS TR-55

Sheet Flow Equation :

$T_c = (0.007 * ((n * L_f)^{0.8})) / ((P^{0.5}) * (S_f^{0.4}))$

Where :

- Tc = Time of Concentration (hr)
- n = Manning's roughness
- Lf = Flow Length (ft)
- P = 2 yr, 24 hr Rainfall (inches)
- Sf = Slope (ft/ft)

Shallow Concentrated Flow Equation :

- V = 16.1345 * (Sf^0.5) (unpaved surface)
- V = 20.3282 * (Sf^0.5) (paved surface)
- V = 15.0 * (Sf^0.5) (grassed waterway surface)
- V = 10.0 * (Sf^0.5) (nearly bare & untilled surface)
- V = 9.0 * (Sf^0.5) (cultivated straight rows surface)
- V = 7.0 * (Sf^0.5) (short grass pasture surface)
- V = 5.0 * (Sf^0.5) (woodland surface)
- V = 2.5 * (Sf^0.5) (forest w/heavy litter surface)
- Tc = (Lf / V) / (3600 sec/hr)

Where:

- Tc = Time of Concentration (hr)
- Lf = Flow Length (ft)
- V = Velocity (ft/sec)
- Sf = Slope (ft/ft)

Channel Flow Equation :

- $V = (1.49 * (R^{2/3})) * (S_f^{0.5}) / n$
- R = Aq / Wp
- Tc = (Lf / V) / (3600 sec/hr)

Where :

- Tc = Time of Concentration (hr)
- Lf = Flow Length (ft)
- R = Hydraulic Radius (ft)
- Aq = Flow Area (ft²)
- Wp = Wetted Perimeter (ft)
- V = Velocity (ft/sec)
- Sf = Slope (ft/ft)
- n = Manning's roughness

	Subarea	Subarea	Subarea
	A	B	C
Sheet Flow Computations			
Manning's Roughness :	0.3	0	0
Flow Length (ft) :	100	0	0
Slope (%) :	2.49	0	0
2 yr, 24 hr Rainfall (in) :	3.5	0	0
Velocity (ft/sec) :	0.11	0	0
Computed Flow Time (min) :	14.94	0	0
	Subarea	Subarea	Subarea
	A	B	C
Shallow Concentrated Flow Computations			
Flow Length (ft) :	488	0	0
Slope (%) :	6.457	0	0
Surface Type :	Unpaved	Unpaved	Unpaved
Velocity (ft/sec) :	4.1	0	0
Computed Flow Time (min) :	1.98	0	0
	Subarea	Subarea	Subarea
	A	B	C
Channel Flow Computations			
Manning's Roughness :	0.03	0	0
Flow Length (ft) :	389	0	0
Channel Slope (%) :	2.57	0	0
Cross Section Area (ft²) :	28	0	0
Wetted Perimeter (ft) :	23	0	0
Velocity (ft/sec) :	9.08	0	0
Computed Flow Time (min) :	0.71	0	0
Total TOC (min)	17.64		

Subbasin Runoff Results

Total Rainfall (in)	5.3
Total Runoff (in)	3.2
Peak Runoff (cfs)	39.26
Weighted Curve Number	80.47
Time of Concentration (days hh:mm:ss)	0 00:17:38

Storage Nodes

Storage Node : Detention

Input Data


Invert Elevation (ft)	926
Max (Rim) Elevation (ft)	933
Max (Rim) Offset (ft)	7
Initial Water Elevation (ft)	926
Initial Water Depth (ft)	0
Ponded Area (ft²)	0
Evaporation Loss	0

Storage Area Volume Curves

Storage Curve : Storage-01

Stage	Storage Area	Storage Volume
(ft)	(ft²)	(ft³)
0	5	0
1	205	105
2	818	616.5
3	1840	1945.5
4	3484	4607.5
4.5	4356	6567.5
5	43560	18546.5

Storage Area Volume Curves



Storage Area Storage Volume

Storage Node : Detention (continued)

Output Summary Results

Peak Inflow (cfs)	39.09
Peak Lateral Inflow (cfs)	39.09
Peak Outflow (cfs)	36.37
Peak Exfiltration Flow Rate (cfm)	0
Max HGL Elevation Attained (ft)	930.63
Max HGL Depth Attained (ft)	4.63
Average HGL Elevation Attained (ft)	926.1
Average HGL Depth Attained (ft)	0.1
Time of Max HGL Occurrence (days hh:mm)	0 12:12
Total Exfiltration Volume (1000-ft³)	0
Total Flooded Volume (ac-in)	0
Total Time Flooded (min)	0
Total Retention Time (sec)	0

1% Chance Storm

Project Description

File Name Existing_Rev1.SPF

Project Options

Flow Units CFS
Elevation Type Elevation
Hydrology Method SCS TR-55
Time of Concentration (TOC) Method SCS TR-55
Link Routing Method Kinematic Wave
Enable Overflow Ponding at Nodes YES
Skip Steady State Analysis Time Periods ... YES

Analysis Options

Start Analysis On	00:00:00	0:00:00
End Analysis On	00:00:00	0:00:00
Start Reporting On	00:00:00	0:00:00
Antecedent Dry Days	0	days
Runoff (Dry Weather) Time Step	0 01:00:00	days hh:mm:ss
Runoff (Wet Weather) Time Step	0 00:05:00	days hh:mm:ss
Reporting Time Step	0 00:05:00	days hh:mm:ss
Routing Time Step	30	seconds

Number of Elements

	Qty
Rain Gages	1
Subbasins.....	1
Nodes.....	2
<i>Junctions</i>	0
<i>Outfalls</i>	1
<i>Flow Diversions</i>	0
<i>Inlets</i>	0
<i>Storage Nodes</i>	1
Links.....	2
<i>Channels</i>	0
<i>Pipes</i>	1
<i>Pumps</i>	0
<i>Orifices</i>	0
<i>Weirs</i>	1
<i>Outlets</i>	0
Pollutants	0
Land Uses	0

Rainfall Details

SN	Rain Gage ID	Data Source	Data Source ID	Rainfall Type	Rain Units	State	County	Return Period (years)	Rainfall Depth (inches)	Rainfall Distribution
49		Time Series	100-YEAR	Cumulative	inches	Missouri	Jackson	100.00	7.70	SCS Type II 24-hr

Subbasin Summary

SN	Subbasin ID	Area	Peak Rate Factor	Weighted Curve Number	Total Rainfall	Total Runoff	Total Runoff Volume	Peak Runoff	Time of Concentration
		(ac)			(in)	(in)	(ac-in)	(cfs)	(days hh:mm:ss)
1	Sub-01	10.56	484.00	80.47	7.70	5.40	56.99	65.27	0 00:17:38

Node Summary

SN	Element ID	Element Type	Invert Elevation	Ground/Rim (Max) Elevation	Initial Water Elevation	Surcharge Elevation	Ponded Area	Peak Inflow	Max HGL Elevation Attained	Max Surcharge Depth Attained	Min Freeboard Attained	Time of Peak Flooding Occurrence	Total Flooded Volume	Total Time Flooded
			(ft)	(ft)	(ft)	(ft)	(ft²)	(cfs)	(ft)	(ft)	(ft)	(days hh:mm)	(ac-in)	(min)
1	Out-01	Outfall	924.65					63.10	926.65					
2	Detention	Storage Node	926.00	933.00	926.00		0.00	64.58	930.75				0.00	0.00

Subbasin Hydrology

Subbasin : Sub-01

Input Data

Area (ac)	10.56
Peak Rate Factor	484
Weighted Curve Number	80.47
Rain Gage ID	Rain Gage-01

Composite Curve Number

32	Area	Soil	Curve
Soil/Surface Description	(acres)	Group	Number
Woods & grass combination, Good	9.74	D	79
Paved parking & roofs	0.82	D	98
Composite Area & Weighted CN	10.56		80.47

Time of Concentration

TOC Method : SCS TR-55

Sheet Flow Equation :

$T_c = (0.007 * ((n * L_f)^{0.8})) / ((P^{0.5}) * (S_f^{0.4}))$

Where :

- Tc = Time of Concentration (hr)
- n = Manning's roughness
- Lf = Flow Length (ft)
- P = 2 yr, 24 hr Rainfall (inches)
- Sf = Slope (ft/ft)

Shallow Concentrated Flow Equation :

- V = 16.1345 * (Sf^0.5) (unpaved surface)
- V = 20.3282 * (Sf^0.5) (paved surface)
- V = 15.0 * (Sf^0.5) (grassed waterway surface)
- V = 10.0 * (Sf^0.5) (nearly bare & untilled surface)
- V = 9.0 * (Sf^0.5) (cultivated straight rows surface)
- V = 7.0 * (Sf^0.5) (short grass pasture surface)
- V = 5.0 * (Sf^0.5) (woodland surface)
- V = 2.5 * (Sf^0.5) (forest w/heavy litter surface)
- Tc = (Lf / V) / (3600 sec/hr)

Where:

- Tc = Time of Concentration (hr)
- Lf = Flow Length (ft)
- V = Velocity (ft/sec)
- Sf = Slope (ft/ft)

Channel Flow Equation :

$V = (1.49 * (R^{(2/3)})) * (S_f^{0.5}) / n$
 $R = A_q / W_p$
 $T_c = (L_f / V) / (3600 \text{ sec/hr})$

Where :

- Tc = Time of Concentration (hr)
- Lf = Flow Length (ft)
- R = Hydraulic Radius (ft)
- Aq = Flow Area (ft²)
- Wp = Wetted Perimeter (ft)
- V = Velocity (ft/sec)
- Sf = Slope (ft/ft)
- n = Manning's roughness

	Subarea	Subarea	Subarea
	A	B	C
Sheet Flow Computations			
Manning's Roughness :	0.3	0	0
Flow Length (ft) :	100	0	0
Slope (%) :	2.49	0	0
2 yr, 24 hr Rainfall (in) :	3.5	0	0
Velocity (ft/sec) :	0.11	0	0
Computed Flow Time (min) :	14.94	0	0
	Subarea	Subarea	Subarea
	A	B	C
Shallow Concentrated Flow Computations			
Flow Length (ft) :	488	0	0
Slope (%) :	6.457	0	0
Surface Type :	Unpaved	Unpaved	Unpaved
Velocity (ft/sec) :	4.1	0	0
Computed Flow Time (min) :	1.98	0	0
	Subarea	Subarea	Subarea
	A	B	C
Channel Flow Computations			
Manning's Roughness :	0.03	0	0
Flow Length (ft) :	389	0	0
Channel Slope (%) :	2.57	0	0
Cross Section Area (ft ²) :	28	0	0
Wetted Perimeter (ft) :	23	0	0
Velocity (ft/sec) :	9.08	0	0
Computed Flow Time (min) :	0.71	0	0
Total TOC (min)	17.64		

Subbasin Runoff Results

Total Rainfall (in)	7.7
Total Runoff (in)	5.4
Peak Runoff (cfs)	65.27
Weighted Curve Number	80.47
Time of Concentration (days hh:mm:ss)	0 00:17:38

Storage Nodes

Storage Node : Detention

Input Data


Invert Elevation (ft)	926
Max (Rim) Elevation (ft)	933
Max (Rim) Offset (ft)	7
Initial Water Elevation (ft)	926
Initial Water Depth (ft)	0
Ponded Area (ft²)	0
Evaporation Loss	0

Storage Area Volume Curves

Storage Curve : Storage-01

Stage	Storage Area	Storage Volume
(ft)	(ft²)	(ft³)
0	5	0
1	205	105
2	818	616.5
3	1840	1945.5
4	3484	4607.5
4.5	4356	6567.5
5	43560	18546.5

Storage Area Volume Curves



Storage Area Storage Volume

Storage Node : Detention (continued)

Output Summary Results

Peak Inflow (cfs)	64.58
Peak Lateral Inflow (cfs)	64.58
Peak Outflow (cfs)	63.1
Peak Exfiltration Flow Rate (cfm)	0
Max HGL Elevation Attained (ft)	930.75
Max HGL Depth Attained (ft)	4.75
Average HGL Elevation Attained (ft)	926.14
Average HGL Depth Attained (ft)	0.14
Time of Max HGL Occurrence (days hh:mm)	0 12:10
Total Exfiltration Volume (1000-ft³)	0
Total Flooded Volume (ac-in)	0
Total Time Flooded (min)	0
Total Retention Time (sec)	0

APPENDIX C

Proposed Conditions Model Input and Results

WORKSHEET 1: REQUIRED LEVEL OF SERVICE - UNDEVELOPED SITE

Project : NLV Mansion Parking Lot

Location: Lee's Summit, MO

By: SMS

Date: 12/12/2023

Date:

1. Runoff Curve Number

A. Predevelopment CN

Cover Description	Soil HSG	CN	Area (ac.)	Product of CN x Area
Woods-grass (Good)	D	79	1.00	79
				0
				0
Totals:			1.00	79

Area-Weighted CN = total product/total area =

79

79

B. Postdevelopment CN

<u>Cover Description</u>	<u>Soil HSG</u>	<u>CN</u>	<u>Area (ac.)</u>	<u>Product of CN x Area</u>
Woods-grass (Good)	D	79	0.36	28.44
Parking Lot	D	98	0.64	62.72
Totals:			1.00	91

Area-Weighted CN = total product/total area =

91.16

91

C. Level of Service (LS) Calculation

Predevelopment CN: 79

Postdevelopment CN: 91

Difference: 12

LS Required: 7

Change in CN

17+

8

7 to 16

7

4 to 6

6

1 to 3

5

0

4

-7 to -1

3

-8 to -17

2

-18 to -21

1

-22-

0


WORKSHEET 2: DEVELOP MITIGATION PACKAGE(S) THAT MEET THE REQUIRED LS
Project : NLV Mansion Parking Lot

Location: Lee's Summit, MO

By: SMS

Checked:
Date: 12/12/2023

Date:
1. Required LS (from Table 1 or 1A or Worksheet 1 or 1A, as appropriate):
7
2. Proposed BMP Option Package No. 1

Plan ID	BMP #	Cover/BMP Description	Treatment Area	VR from Table 4.4 or 4.6	Product of VR x Area
	1	Infiltration Trench	0.78	9.00	7.02
	2		0.00	0.00	0.00
	3		0.00	0.00	0.00
	4		0.00	0.00	0.00
	5		0.00	0.00	0.00
	6		0.00	0.00	0.00
	7		0.00	0.00	0.00
	8		0.00	0.00	0.00
	-	Untreated Area	0.22	-	-
Total:			1.00	Total:	7.02
			Weighted VR		7.02

Meets required LS (Yes/No)?
☒ **YES**

(if No, or if additional options are being tested, proceed below)

3. Proposed BMP Option Package No. 2

Plan ID	BMP #	Cover/BMP Description	Treatment Area	VR from Table 4.4 or 4.6	Product of VR x Area
	1		0.00	0.00	0
	2		0.00	0.00	0
	3		0.00	0.00	0
	4		0.00	0.00	0
	5		0.00	0.00	0
	6		0.00	0.00	0
	7		0.00	0.00	0
	8		0.00	0.00	0
	-	Untreated Area	1.00	-	-
Total:			1.00	Total:	0
			Weighted VR		

Meets required LS (Yes/No)?
☐

(if No, or if additional options are being tested, proceed below)

	Infiltration Trench	Trench 1
Water Quality Volume	$WQ_v = P \cdot R_v$	
	P (in.)	1.37
	Impervious % =	100
	$R_v =$	0.95
	WQ_v (in.)	1.3015
	Treated Area (acre)	0.77
	WQ_v (ft ³)	3637.82
Infiltration Trench Geometry & Data	Soil Hydraulic Conductivity (μm/sec)	2
	Soil Hydraulic Conductivity (ft/hr)	0.023622
	Proposed Trench Area (ft ²)	2420
	Proposed Trench Depth (ft)	4
	Storage Void Ratio %	40
Infiltration Trench Storage & Infiltration Calculations	Trench Infiltration Rate = (Area)*(Conductivity)	
	Trench Infiltration Rate (ft ³ /hr)	57.165354
	Trench Infiltration Rate (ft ³ /sec)	0.0158793
	Total Infiltration = (Rate)*(24Hr)	
	Total Infiltration (ft ³)	1371.9685
	Infiltration Trench Storage = (Area)*(Depth)*(VoidRatio)	
	Infiltration Trench Storage (ft ³)	3872
	Storage > WQv	OK
	Trench Drain Time (hr)	68

50% Chance Storm

Project Description

File Name Proposed_Rev2_AddPipe.SPF

Project Options

Flow Units CFS
Elevation Type Elevation
Hydrology Method SCS TR-55
Time of Concentration (TOC) Method SCS TR-55
Link Routing Method Kinematic Wave
Enable Overflow Ponding at Nodes YES
Skip Steady State Analysis Time Periods ... YES

Analysis Options

Start Analysis On 00:00:00 0:00:00
End Analysis On 00:00:00 0:00:00
Start Reporting On 00:00:00 0:00:00
Antecedent Dry Days 0 days
Runoff (Dry Weather) Time Step 0 01:00:00 days hh:mm:ss
Runoff (Wet Weather) Time Step 0 00:05:00 days hh:mm:ss
Reporting Time Step 0 00:01:00 days hh:mm:ss
Routing Time Step 5 seconds

Number of Elements

Qty
Rain Gages 1
Subbasins..... 1
Nodes..... 3
 Junctions 1
 Outfalls 1
 Flow Diversions 0
 Inlets 0
 Storage Nodes 1
Links..... 4
 Channels 0
 Pipes 3
 Pumps 0
 Orifices 0
 Weirs 1
 Outlets 0
Pollutants 0
Land Uses 0

Rainfall Details

SN	Rain Gage ID	Data Source	Data Source ID	Rainfall Type	Rain Units	State	County	Return Period (years)	Rainfall Depth (inches)	Rainfall Distribution
49		Time Series	002-YEAR	Cumulative	inches	Missouri	Jackson	2.00	3.50	SCS Type II 24-hr

Subbasin Summary

SN	Subbasin ID	Area	Peak Rate Factor	Weighted Curve Number	Total Rainfall	Total Runoff	Total Runoff Volume	Peak Runoff	Time of Concentration
		(ac)			(in)	(in)	(ac-in)	(cfs)	(days hh:mm:ss)
1	Sub-01	10.56	484.00	81.58	3.50	1.75	18.49	21.56	0 00:17:38

Node Summary

SN	Element ID	Element Type	Invert Elevation	Ground/Rim (Max) Elevation	Initial Water Elevation	Surcharge Elevation	Ponded Area	Peak Inflow	Max HGL Elevation Attained	Max Surcharge Depth Attained	Min Freeboard Attained	Time of Peak Flooding Occurrence	Total Flooded Volume	Total Time Flooded
			(ft)	(ft)	(ft)	(ft)	(ft²)	(cfs)	(ft)	(ft)	(ft)	(days hh:mm)	(ac-in)	(min)
1	1-Jun	Junction	924.65	930.50	0.00	0.00	0.00	21.51	925.66	0.00	4.84	0 00:00	0.00	0.00
2	Out-01	Outfall	924.65					21.51	924.65					
3	Detention	Storage Node	926.00	933.00	926.00		0.00	21.51	927.01				0.00	0.00

Link Summary

SN	Element ID	Element Type	From (Inlet) Node	To (Outlet) Node	Length	Inlet Invert Elevation	Outlet Invert Elevation	Average Slope	Diameter or Height	Manning's Roughness	Peak Flow	Design Flow Capacity	Peak Flow/ Design Flow Ratio	Peak Flow Velocity	Peak Flow Depth	Peak Flow Depth/ Total Depth Ratio	Total Time Reported	Surcharged Condition
					(ft)	(ft)	(ft)	(%)	(in)		(cfs)	(cfs)		(ft/sec)	(ft)		(min)	
1	Existing_CMP	Pipe	Detention	1-Jun	50.00	926.00	924.65	2.7000	24.000	0.0240	10.19	20.14	0.51	6.43	1.01	0.50	0.00	Calculated
2	Junction_to_Outfall_Direct	Pipe	1-Jun	Out-01	11.08	0.00	924.65	-8345.2200	0.000	0.0150	21.51	0.00	0.51	0.00	1.01	0.50	0.00	Calculated
3	Prop_HDPE	Pipe	Detention	1-Jun	50.00	926.00	924.65	2.7000	15.000	0.0120	11.31	11.50	0.98	10.68	1.01	0.81	0.00	Calculated
4	Roadway	Weir	Detention	1-Jun		926.00	924.65				0.00							

Subbasin Hydrology

Subbasin : Sub-01

Input Data

Area (ac)	10.56
Peak Rate Factor	484
Weighted Curve Number	81.58
Rain Gage ID	Rain Gage-01

Composite Curve Number

32	Area	Soil	Curve
Soil/Surface Description	(acres)	Group	Number
Woods & grass combination, Good	9.12	D	79
Paved parking & roofs	1.44	D	98
Composite Area & Weighted CN	10.56		81.58

Time of Concentration

TOC Method : SCS TR-55

Sheet Flow Equation :

$T_c = (0.007 * ((n * L_f)^{0.8})) / ((P^{0.5}) * (S_f^{0.4}))$

Where :

- Tc = Time of Concentration (hr)
- n = Manning's roughness
- Lf = Flow Length (ft)
- P = 2 yr, 24 hr Rainfall (inches)
- Sf = Slope (ft/ft)

Shallow Concentrated Flow Equation :

- V = 16.1345 * (Sf^0.5) (unpaved surface)
- V = 20.3282 * (Sf^0.5) (paved surface)
- V = 15.0 * (Sf^0.5) (grassed waterway surface)
- V = 10.0 * (Sf^0.5) (nearly bare & untilled surface)
- V = 9.0 * (Sf^0.5) (cultivated straight rows surface)
- V = 7.0 * (Sf^0.5) (short grass pasture surface)
- V = 5.0 * (Sf^0.5) (woodland surface)
- V = 2.5 * (Sf^0.5) (forest w/heavy litter surface)
- Tc = (Lf / V) / (3600 sec/hr)

Where:

- Tc = Time of Concentration (hr)
- Lf = Flow Length (ft)
- V = Velocity (ft/sec)
- Sf = Slope (ft/ft)

Channel Flow Equation :

$V = (1.49 * (R^{(2/3)}) * (S_f^{0.5})) / n$
 $R = A_q / W_p$
 $T_c = (L_f / V) / (3600 \text{ sec/hr})$

Where :

- Tc = Time of Concentration (hr)
- Lf = Flow Length (ft)
- R = Hydraulic Radius (ft)
- Aq = Flow Area (ft²)
- Wp = Wetted Perimeter (ft)
- V = Velocity (ft/sec)
- Sf = Slope (ft/ft)
- n = Manning's roughness

Sheet Flow Computations	Subarea A	Subarea B	Subarea C
Manning's Roughness :	0.3	0	0
Flow Length (ft) :	100	0	0
Slope (%) :	2.49	0	0
2 yr, 24 hr Rainfall (in) :	3.5	0	0
Velocity (ft/sec) :	0.11	0	0
Computed Flow Time (min) :	14.94	0	0
Shallow Concentrated Flow Computations	Subarea A	Subarea B	Subarea C
Flow Length (ft) :	488	0	0
Slope (%) :	6.457	0	0
Surface Type :	Unpaved	Unpaved	Unpaved
Velocity (ft/sec) :	4.1	0	0
Computed Flow Time (min) :	1.98	0	0
Channel Flow Computations	Subarea A	Subarea B	Subarea C
Manning's Roughness :	0.03	0	0
Flow Length (ft) :	389	0	0
Channel Slope (%) :	2.57	0	0
Cross Section Area (ft²) :	28	0	0
Wetted Perimeter (ft) :	23	0	0
Velocity (ft/sec) :	9.08	0	0
Computed Flow Time (min) :	0.71	0	0
Total TOC (min)	17.64		

Subbasin Runoff Results

Total Rainfall (in)	3.5
Total Runoff (in)	1.75
Peak Runoff (cfs)	21.56
Weighted Curve Number	81.58
Time of Concentration (days hh:mm:ss)	0 00:17:38

Storage Nodes

Storage Node : Detention

Input Data


Invert Elevation (ft)	926
Max (Rim) Elevation (ft)	933
Max (Rim) Offset (ft)	7
Initial Water Elevation (ft)	926
Initial Water Depth (ft)	0
Ponded Area (ft²)	0
Evaporation Loss	0

Storage Area Volume Curves

Storage Curve : Storage-01

Stage	Storage Area	Storage Volume
(ft)	(ft²)	(ft³)
0	5	0
1	205	105
2	818	616.5
3	1840	1945.5
4	3484	4607.5
4.5	4356	6567.5
5	43560	18546.5

Storage Area Volume Curves



Storage Area Storage Volume

Storage Node : Detention (continued)

Outflow Weirs

SN	Element	Weir	Flap	Crest	Crest	Length	Weir Total	Discharge
	ID	Type	Gate	Elevation	Offset		Height	Coefficient
				(ft)	(ft)	(ft)	(ft)	
1	Roadway	Trapezoidal	No	930.50	4.50	100.00	1.00	3.33

Output Summary Results

Peak Inflow (cfs)	21.51
Peak Lateral Inflow (cfs)	21.51
Peak Outflow (cfs)	21.51
Peak Exfiltration Flow Rate (cfm)	0
Max HGL Elevation Attained (ft)	927.01
Max HGL Depth Attained (ft)	1.01
Average HGL Elevation Attained (ft)	926.04
Average HGL Depth Attained (ft)	0.04
Time of Max HGL Occurrence (days hh:mm)	0 12:05
Total Exfiltration Volume (1000-ft³)	0
Total Flooded Volume (ac-in)	0
Total Time Flooded (min)	0
Total Retention Time (sec)	0

10% Chance Storm

Project Description

File Name Proposed_Rev2_AddPipe.SPF

Project Options

Flow Units CFS
Elevation Type Elevation
Hydrology Method SCS TR-55
Time of Concentration (TOC) Method SCS TR-55
Link Routing Method Kinematic Wave
Enable Overflow Ponding at Nodes YES
Skip Steady State Analysis Time Periods ... YES

Analysis Options

Start Analysis On 00:00:00 0:00:00
End Analysis On 00:00:00 0:00:00
Start Reporting On 00:00:00 0:00:00
Antecedent Dry Days 0 days
Runoff (Dry Weather) Time Step 0 01:00:00 days hh:mm:ss
Runoff (Wet Weather) Time Step 0 00:05:00 days hh:mm:ss
Reporting Time Step 0 00:01:00 days hh:mm:ss
Routing Time Step 5 seconds

Number of Elements

Qty
Rain Gages 1
Subbasins..... 1
Nodes..... 3
 Junctions 1
 Outfalls 1
 Flow Diversions 0
 Inlets 0
 Storage Nodes 1
Links..... 4
 Channels 0
 Pipes 3
 Pumps 0
 Orifices 0
 Weirs 1
 Outlets 0
Pollutants 0
Land Uses 0

Rainfall Details

SN	Rain Gage ID	Data Source	Data Source ID	Rainfall Type	Rain Units	State	County	Return Period (years)	Rainfall Depth (inches)	Rainfall Distribution
49		Time Series	010-YEAR	Cumulative	inches	Missouri	Jackson	10.00	5.30	SCS Type II 24-hr

Subbasin Summary

SN	Subbasin ID	Area	Peak Rate Factor	Weighted Curve Number	Total Rainfall	Total Runoff	Total Runoff Volume	Peak Runoff	Time of Concentration
		(ac)			(in)	(in)	(ac-in)	(cfs)	(days hh:mm:ss)
1	Sub-01	10.56	484.00	81.58	5.30	3.31	34.92	40.49	0 00:17:38

Node Summary

SN	Element ID	Element Type	Invert Elevation	Ground/Rim (Max) Elevation	Initial Water Elevation	Surcharge Elevation	Ponded Area	Peak Inflow	Max HGL Elevation Attained	Max Surcharge Depth Attained	Min Freeboard Attained	Time of Peak Flooding Occurrence	Total Flooded Volume	Total Time Flooded
			(ft)	(ft)	(ft)	(ft)	(ft²)	(cfs)	(ft)	(ft)	(ft)	(days hh:mm)	(ac-in)	(min)
1	1-Jun	Junction	924.65	930.50	0.00	0.00	0.00	32.64	926.40	0.00	4.10	0 00:00	0.00	0.00
2	Out-01	Outfall	924.65					32.64	924.65					
3	Detention	Storage Node	926.00	933.00	926.00		0.00	40.45	929.96				0.00	0.00

Link Summary

SN	Element ID	Element Type	From (Inlet) Node	To (Outlet) Node	Length	Inlet Invert Elevation	Outlet Invert Elevation	Average Slope	Diameter or Height	Manning's Roughness	Peak Flow	Design Flow Capacity	Peak Flow/ Design Flow Ratio	Peak Flow Velocity	Peak Flow Depth	Peak Flow Depth/ Total Depth Ratio	Total Time Reported Surcharged Condition
					(ft)	(ft)	(ft)	(%)	(in)		(cfs)	(cfs)		(ft/sec)	(ft)		(min)
1	Existing_CMP	Pipe	Detention	1-Jun	50.00	926.00	924.65	2.7000	24.000	0.0240	21.15	20.14	1.05	7.75	1.85	0.93	0.00 > CAPACITY
2	Junction_to_Outfall_Direct	Pipe	1-Jun	Out-01	11.08	0.00	924.65	-8345.2200	0.000	0.0150	32.64	0.00	1.05	0.00	1.85	0.93	0.00 > CAPACITY
3	Prop_HDPE	Pipe	Detention	1-Jun	50.00	926.00	924.65	2.7000	15.000	0.0120	12.05	11.50	1.05	11.18	1.16	0.94	0.00 > CAPACITY
4	Roadway	Weir	Detention	1-Jun		926.00	924.65				0.00						

Subbasin Hydrology

Subbasin : Sub-01

Input Data

Area (ac)	10.56
Peak Rate Factor	484
Weighted Curve Number	81.58
Rain Gage ID	Rain Gage-01

Composite Curve Number

32	Area	Soil	Curve
Soil/Surface Description	(acres)	Group	Number
Woods & grass combination, Good	9.12	D	79
Paved parking & roofs	1.44	D	98
Composite Area & Weighted CN	10.56		81.58

Time of Concentration

TOC Method : SCS TR-55

Sheet Flow Equation :

$T_c = (0.007 * ((n * L_f)^{0.8})) / ((P^{0.5}) * (S_f^{0.4}))$

Where :

- Tc = Time of Concentration (hr)
- n = Manning's roughness
- Lf = Flow Length (ft)
- P = 2 yr, 24 hr Rainfall (inches)
- Sf = Slope (ft/ft)

Shallow Concentrated Flow Equation :

- V = 16.1345 * (Sf^0.5) (unpaved surface)
- V = 20.3282 * (Sf^0.5) (paved surface)
- V = 15.0 * (Sf^0.5) (grassed waterway surface)
- V = 10.0 * (Sf^0.5) (nearly bare & untilled surface)
- V = 9.0 * (Sf^0.5) (cultivated straight rows surface)
- V = 7.0 * (Sf^0.5) (short grass pasture surface)
- V = 5.0 * (Sf^0.5) (woodland surface)
- V = 2.5 * (Sf^0.5) (forest w/heavy litter surface)
- Tc = (Lf / V) / (3600 sec/hr)

Where:

- Tc = Time of Concentration (hr)
- Lf = Flow Length (ft)
- V = Velocity (ft/sec)
- Sf = Slope (ft/ft)

Channel Flow Equation :

- $V = (1.49 * (R^{2/3}) * (S_f^{0.5})) / n$
- $R = A_q / W_p$
- $T_c = (L_f / V) / (3600 \text{ sec/hr})$

Where :

- Tc = Time of Concentration (hr)
- Lf = Flow Length (ft)
- R = Hydraulic Radius (ft)
- Aq = Flow Area (ft²)
- Wp = Wetted Perimeter (ft)
- V = Velocity (ft/sec)
- Sf = Slope (ft/ft)
- n = Manning's roughness

	Subarea	Subarea	Subarea
	A	B	C
Sheet Flow Computations			
Manning's Roughness :	0.3	0	0
Flow Length (ft) :	100	0	0
Slope (%) :	2.49	0	0
2 yr, 24 hr Rainfall (in) :	3.5	0	0
Velocity (ft/sec) :	0.11	0	0
Computed Flow Time (min) :	14.94	0	0
	Subarea	Subarea	Subarea
	A	B	C
Shallow Concentrated Flow Computations			
Flow Length (ft) :	488	0	0
Slope (%) :	6.457	0	0
Surface Type :	Unpaved	Unpaved	Unpaved
Velocity (ft/sec) :	4.1	0	0
Computed Flow Time (min) :	1.98	0	0
	Subarea	Subarea	Subarea
	A	B	C
Channel Flow Computations			
Manning's Roughness :	0.03	0	0
Flow Length (ft) :	389	0	0
Channel Slope (%) :	2.57	0	0
Cross Section Area (ft ²) :	28	0	0
Wetted Perimeter (ft) :	23	0	0
Velocity (ft/sec) :	9.08	0	0
Computed Flow Time (min) :	0.71	0	0
Total TOC (min)	17.64		

Subbasin Runoff Results

Total Rainfall (in)	5.3
Total Runoff (in)	3.31
Peak Runoff (cfs)	40.49
Weighted Curve Number	81.58
Time of Concentration (days hh:mm:ss)	0 00:17:38

Storage Nodes

Storage Node : Detention

Input Data


Invert Elevation (ft)	926
Max (Rim) Elevation (ft)	933
Max (Rim) Offset (ft)	7
Initial Water Elevation (ft)	926
Initial Water Depth (ft)	0
Ponded Area (ft²)	0
Evaporation Loss	0

Storage Area Volume Curves

Storage Curve : Storage-01

Stage	Storage Area	Storage Volume
(ft)	(ft²)	(ft³)
0	5	0
1	205	105
2	818	616.5
3	1840	1945.5
4	3484	4607.5
4.5	4356	6567.5
5	43560	18546.5

Storage Area Volume Curves



Storage Area Storage Volume

Storage Node : Detention (continued)

Outflow Weirs

SN	Element	Weir	Flap	Crest	Crest	Length	Weir Total	Discharge
	ID	Type	Gate	Elevation	Offset		Height	Coefficient
				(ft)	(ft)	(ft)	(ft)	
1	Roadway	Trapezoidal	No	930.50	4.50	100.00	1.00	3.33

Output Summary Results

Peak Inflow (cfs)	40.45
Peak Lateral Inflow (cfs)	40.45
Peak Outflow (cfs)	31.63
Peak Exfiltration Flow Rate (cfm)	0
Max HGL Elevation Attained (ft)	929.96
Max HGL Depth Attained (ft)	3.96
Average HGL Elevation Attained (ft)	926.06
Average HGL Depth Attained (ft)	0.06
Time of Max HGL Occurrence (days hh:mm)	0 12:11
Total Exfiltration Volume (1000-ft³)	0
Total Flooded Volume (ac-in)	0
Total Time Flooded (min)	0
Total Retention Time (sec)	0

1% Chance Storm

Project Description

File Name Proposed_Rev2_AddPipe.SPF

Project Options

Flow Units CFS
Elevation Type Elevation
Hydrology Method SCS TR-55
Time of Concentration (TOC) Method SCS TR-55
Link Routing Method Kinematic Wave
Enable Overflow Ponding at Nodes YES
Skip Steady State Analysis Time Periods ... YES

Analysis Options

Start Analysis On 00:00:00 0:00:00
End Analysis On 00:00:00 0:00:00
Start Reporting On 00:00:00 0:00:00
Antecedent Dry Days 0 days
Runoff (Dry Weather) Time Step 0 01:00:00 days hh:mm:ss
Runoff (Wet Weather) Time Step 0 00:05:00 days hh:mm:ss
Reporting Time Step 0 00:01:00 days hh:mm:ss
Routing Time Step 5 seconds

Number of Elements

Qty
Rain Gages 1
Subbasins..... 1
Nodes..... 3
 Junctions 1
 Outfalls 1
 Flow Diversions 0
 Inlets 0
 Storage Nodes 1
Links..... 4
 Channels 0
 Pipes 3
 Pumps 0
 Orifices 0
 Weirs 1
 Outlets 0
Pollutants 0
Land Uses 0

Rainfall Details

SN	Rain Gage ID	Data Source	Data Source ID	Rainfall Type	Rain Units	State	County	Return Period (years)	Rainfall Depth (inches)	Rainfall Distribution
49		Time Series	100-YEAR	Cumulative	inches	Missouri	Jackson	100.00	7.70	SCS Type II 24-hr

Subbasin Summary

SN	Subbasin ID	Area	Peak Rate Factor	Weighted Curve Number	Total Rainfall	Total Runoff	Total Runoff Volume	Peak Runoff	Time of Concentration
		(ac)			(in)	(in)	(ac-in)	(cfs)	(days hh:mm:ss)
1	Sub-01	10.56	484.00	81.58	7.70	5.53	58.35	66.57	0 00:17:38

Node Summary

SN	Element ID	Element Type	Invert Elevation	Ground/Rim (Max) Elevation	Initial Water Elevation	Surcharge Elevation	Ponded Area	Peak Inflow	Max HGL Elevation Attained	Max Surcharge Depth Attained	Min Freeboard Attained	Time of Peak Flooding Occurrence	Total Flooded Volume	Total Time Flooded
			(ft)	(ft)	(ft)	(ft)	(ft²)	(cfs)	(ft)	(ft)	(ft)	(days hh:mm)	(ac-in)	(min)
1	1-Jun	Junction	924.65	930.50	0.00	0.00	0.00	65.29	926.39	0.00	4.11	0 00:00	0.00	0.00
2	Out-01	Outfall	924.65					65.29	924.65					
3	Detention	Storage Node	926.00	933.00	926.00		0.00	66.44	930.72				0.00	0.00

Link Summary

SN	Element ID	Element Type	From (Inlet) Node	To (Outlet) Node	Length	Inlet Invert Elevation	Outlet Invert Elevation	Average Slope	Diameter or Height	Manning's Roughness	Peak Flow	Design Flow Capacity	Peak Flow/ Design Flow Ratio	Peak Flow Velocity	Peak Flow Depth	Peak Flow Depth/ Total Depth Ratio	Total Time Reported Surcharged Condition
					(ft)	(ft)	(ft)	(%)	(in)		(cfs)	(cfs)		(ft/sec)	(ft)		(min)
1	Existing_CMP	Pipe	Detention	1-Jun	50.00	926.00	924.65	2.7000	24.000	0.0240	21.12	20.14	1.05	7.79	1.85	0.93	0.00 > CAPACITY
2	Junction_to_Outfall_Direct	Pipe	1-Jun	Out-01	11.08	0.00	924.65	-8345.2200	0.000	0.0150	65.29	0.00	1.05	0.00	1.85	0.93	0.00 > CAPACITY
3	Prop_HDPE	Pipe	Detention	1-Jun	50.00	926.00	924.65	2.7000	15.000	0.0120	12.05	11.50	1.05	11.43	1.17	0.94	0.00 > CAPACITY
4	Roadway	Weir	Detention	1-Jun		926.00	924.65				33.65						

Subbasin Hydrology

Subbasin : Sub-01

Input Data

Area (ac)	10.56
Peak Rate Factor	484
Weighted Curve Number	81.58
Rain Gage ID	Rain Gage-01

Composite Curve Number

32	Area	Soil	Curve
Soil/Surface Description	(acres)	Group	Number
Woods & grass combination, Good	9.12	D	79
Paved parking & roofs	1.44	D	98
Composite Area & Weighted CN	10.56		81.58

Time of Concentration

TOC Method : SCS TR-55

Sheet Flow Equation :

$T_c = (0.007 * ((n * L_f)^{0.8})) / ((P^{0.5}) * (S_f^{0.4}))$

Where :

- Tc = Time of Concentration (hr)
- n = Manning's roughness
- Lf = Flow Length (ft)
- P = 2 yr, 24 hr Rainfall (inches)
- Sf = Slope (ft/ft)

Shallow Concentrated Flow Equation :

- V = 16.1345 * (Sf^0.5) (unpaved surface)
- V = 20.3282 * (Sf^0.5) (paved surface)
- V = 15.0 * (Sf^0.5) (grassed waterway surface)
- V = 10.0 * (Sf^0.5) (nearly bare & untilled surface)
- V = 9.0 * (Sf^0.5) (cultivated straight rows surface)
- V = 7.0 * (Sf^0.5) (short grass pasture surface)
- V = 5.0 * (Sf^0.5) (woodland surface)
- V = 2.5 * (Sf^0.5) (forest w/heavy litter surface)
- Tc = (Lf / V) / (3600 sec/hr)

Where:

- Tc = Time of Concentration (hr)
- Lf = Flow Length (ft)
- V = Velocity (ft/sec)
- Sf = Slope (ft/ft)

Channel Flow Equation :

- $V = (1.49 * (R^{2/3}) * (S_f^{0.5})) / n$
- R = Aq / Wp
- Tc = (Lf / V) / (3600 sec/hr)

Where :

- Tc = Time of Concentration (hr)
- Lf = Flow Length (ft)
- R = Hydraulic Radius (ft)
- Aq = Flow Area (ft²)
- Wp = Wetted Perimeter (ft)
- V = Velocity (ft/sec)
- Sf = Slope (ft/ft)
- n = Manning's roughness

	Subarea	Subarea	Subarea
	A	B	C
Sheet Flow Computations			
Manning's Roughness :	0.3	0	0
Flow Length (ft) :	100	0	0
Slope (%) :	2.49	0	0
2 yr, 24 hr Rainfall (in) :	3.5	0	0
Velocity (ft/sec) :	0.11	0	0
Computed Flow Time (min) :	14.94	0	0
	Subarea	Subarea	Subarea
	A	B	C
Shallow Concentrated Flow Computations			
Flow Length (ft) :	488	0	0
Slope (%) :	6.457	0	0
Surface Type :	Unpaved	Unpaved	Unpaved
Velocity (ft/sec) :	4.1	0	0
Computed Flow Time (min) :	1.98	0	0
	Subarea	Subarea	Subarea
	A	B	C
Channel Flow Computations			
Manning's Roughness :	0.03	0	0
Flow Length (ft) :	389	0	0
Channel Slope (%) :	2.57	0	0
Cross Section Area (ft ²) :	28	0	0
Wetted Perimeter (ft) :	23	0	0
Velocity (ft/sec) :	9.08	0	0
Computed Flow Time (min) :	0.71	0	0
Total TOC (min)	17.64		

Subbasin Runoff Results

Total Rainfall (in)	7.7
Total Runoff (in)	5.53
Peak Runoff (cfs)	66.57
Weighted Curve Number	81.58
Time of Concentration (days hh:mm:ss)	0 00:17:38

Storage Nodes

Storage Node : Detention

Input Data


Invert Elevation (ft)	926
Max (Rim) Elevation (ft)	933
Max (Rim) Offset (ft)	7
Initial Water Elevation (ft)	926
Initial Water Depth (ft)	0
Ponded Area (ft²)	0
Evaporation Loss	0

Storage Area Volume Curves

Storage Curve : Storage-01

Stage	Storage Area	Storage Volume
(ft)	(ft²)	(ft³)
0	5	0
1	205	105
2	818	616.5
3	1840	1945.5
4	3484	4607.5
4.5	4356	6567.5
5	43560	18546.5

Storage Area Volume Curves



Storage Node : Detention (continued)

Outflow Weirs

SN	Element	Weir	Flap	Crest	Crest	Length	Weir Total	Discharge
	ID	Type	Gate	Elevation	Offset		Height	Coefficient
				(ft)	(ft)	(ft)	(ft)	
1	Roadway	Trapezoidal	No	930.50	4.50	100.00	1.00	3.33

Output Summary Results

Peak Inflow (cfs)	66.44
Peak Lateral Inflow (cfs)	66.44
Peak Outflow (cfs)	65.29
Peak Exfiltration Flow Rate (cfm)	0
Max HGL Elevation Attained (ft)	930.72
Max HGL Depth Attained (ft)	4.72
Average HGL Elevation Attained (ft)	926.09
Average HGL Depth Attained (ft)	0.09
Time of Max HGL Occurrence (days hh:mm)	0 12:06
Total Exfiltration Volume (1000-ft³)	0
Total Flooded Volume (ac-in)	0
Total Time Flooded (min)	0
Total Retention Time (sec)	0

NEW LONGVIEW MANSION PARKING LOT STORMWATER REPORT

Lee's Summit, MO

January 2024

Olsson Project No. 022-06318