





Not To Scale

PRUNE OUT DEAD OR DAMAGED BRANCHES PRIOR TO PLANTING. ROOTBALL TO BE PLANTED SLIGHTLY ABOVE FINISH GRADE. REMOVE ALL TWINE FROM TOP OF ROOTBALL AND PULL BURLAP AWAY FROM TRUNK. 3" SHREDDED HARDWOOD — Water Ring — 80% Topsoil, 20% Compost —— SUBGRADE.

DECIDUOUS TREE PLANTING DETAIL Not To Scale

> THE PLANT LIST IS PROVIDED FOR THE CONVENIENCE OF THE CONTRACTOR. THE CONTRACTOR SHALL VERIFY ALL PLANT COUNTS AND IF A DISCREPANCY EXISTS THE PLAN SHALL GOVERN. LANDSCAPE CONTRACTOR SHALL BE RESPONSIBLE FOR BECOMING AWARE OF ALL UNDERGROUND UTILITIES, PIPES, AND STRUCTURES. THE LANDSCAPE CONTRACTOR SHALL BE HELD RESPONSIBLE FOR CONTACTING ALL UTILITY COMPANIES FOR FIELD LOCATION OF ALL UNDERGROUND UTILITY LINES PRIOR TO ANY EXCAVATION. LANDSCAPE CONTRACTOR TO RECEIVE SITE GRADED TO ± -0.10 FOOT OF FINISHED

PLANTING BACK FILL MIX IS TO CONSIST OF 80% NATIVE TOPSOIL, AND 20% ORGANIC MATTER.

SHRUB BEDS, BERMS, AND TREE WELLS ARE TO BE MULCHED WITH 3-4" DYED HARDWOOD MULCH. ALL BED AND LAWN AREAS SHALL BE IRRIGATED.

ONLY ORNAMENTAL TREES AND SHRUBS MAY BE PLANTED IN ANY EASEMENTS.

TRENCHING.

ALL LAWN AREAS TO BE SODDED WITH TALL FESCUE SOD. LANDSCAPE CONTRACTOR SHALL GUARANTEE ALL PLANT MATERIAL FOR A PERIOD OF TWELVE MONTHS. ALL PLANTING BEDS AND TREE RINGS TO BE SEPERATED FROM TURF AREAS BY 'V'

ALL PLANT MATERIAL MUST MEET THE SPECIFICATIONS OF THE AMERICAN ASSOCIATION OF NURSERYMEN. PLANT LOCATIONS MAY BE ADJUSTED ONSITE TO AVOID UTILITIES, SITE FEATURES, ETC.

QUANTITY	SYMBOL	PLANT NAME	PLANT TYPE	SIZE
5	EF	ELM 'FRONTIER'	MEDIUM / LARGE TREE	3"
8	ZGV	ZELKOVA 'GREEN VASE'	MEDIUM / LARGE TREE	3"
6	MSS	MIYABI MAPLE 'STATE STREET'	MEDIUM / LARGE TREE	3"
6	HEA	HORNBEAM 'EMERALD AVENUE'	MEDIUM / LARGE TREE	3"
6	CST	CRABAPPLE 'SUGARTYME'	ORNAMENTAL TREE	2.5
2	CRR	CRABAPPLE 'ROYAL RAINDROPS	ORNAMENTAL TREE	2.5
3	RBA	REDBUD 'APPALACHIAN'	ORNAMENTAL TREE	2.5
6	NAJ	NINEBARK 'AMBER JUBILEE'	DECIDUOUS SHRUB	#5
11	HLL	HYDRANGEA 'LITTLE LIME'	DECIDUOUS SHRUB	##
12	HRS	HYDRANGEA 'RUBY SLIPPERS'	DECIDUOUS SHRUB	#5
3	SBB	SPIREA 'BIG BANG'	DECIDUOUS SHRUB	#5
11	BGV	BOXWOOD 'GREEN VELVET'	EVERGREEN SHRUB	#5
18	JSG	JUNIPER 'SEA GREEN'	EVERGREEN SHRUB	#5

LEE'S SUMMIT, MISSOURI CODE OF ORDINANCES: DIVISION III – LANDSCAPING, BUFFERS, AND TREE PROTECTION SITE ZONED: PMIX, PROPOSED: PMIX		
STREET FRONTAGE TREES		
1 TREE PER 30 FEET OF STREET FRONTAGE		
DOUGLAS AVE - 398 LF STREET FRONTAGE	14 TREES REQUIRED	14 TREES PROPOSE
NE COLBURN RD - 214 LF STREET FRONTAGE	7 TREES REQUIRED	7 TREES PROPOSE
<u>OPEN YARD TREES</u>		
1 TREE PER 5,000 SF OF TOTAL LOT AREA, EXCLUDING BUILDING FOOTPRINT		
TOTAL LOT AREA = 75,287 SF	15 TREES REQUIRED	15 TREES PROPOSE
STREET FRONTAGE SHRUBS		
1 SHRUB PER 20 FEET OF STREET FRONTAGE		
DOUGLAS AVE - 398 LF STREET FRONTAGE	20 SHRUBS REQUIRED	20 SHRUBS PROPOSE
NE COLBURN RD - 214 LF STREET FRONTAGE	11 SHRUBS REQUIRED	11 SHRUBS PROPOSE
<u>OPEN YARD SHRUBS</u>		
2 SHRUBS PER 5,000 SF OF TOTAL LOT AREA, EXCLUDING BUILDING FOOTPRINT		
TOTAL LOT AREA = 75,287 SF	30 SHRUBS REQUIRED	30 SHRUBS PROPOSE

EX. 15' DRAINAGE ESMT. i H I

JACKSON

SUMMIT,

H

|| REVISIONS:

THIS SHEET HAS BEEN SIGNED, SEALED AND DATED ELECTRONICALLY

NATHAN THOMAS ECKHOFF

MO LICENSE-2003014960

DRAWING INCLUDES:

LANDSCAPING PLAN

DESIGNED: NTE

DRAWN: NMD

SHEET: CE 8.1

PROJECT NO.: 230286