


THE SUMMIT CHURCH

CONSTRUCTION PLANS

SEC-3 TWP-47 RNG-32 W 1/2 NW 1/4
LEE'S SUMMIT, JACKSON COUNTY, MISSOURI



INDEX OF SHEETS:

C.001	COVER SHEET
C.002	EXISTING SURVEY
C.010	DEMOLITION PLAN
C.050	ESC PHASE 1 PLAN
C.051	ESC PHASE 2 PLAN
C.052	ESC PHASE 3 PLAN
C.053	FAIRCLOTH SKIMMER DETAIL
C.100	SITE PLAN
C.101	DIMENSION PLAN
C.200	GRADING PLAN
C.201	SPOT GRADING PLAN
C.202	STREET PLAN & PROFILE
C.203	STREET PLAN & PROFILE
C.204	RETAINING WALL
C.205	RETAINING WALL
C.206	DRAINAGE MAP
C.207	ENTRY SPOT GRADE PLAN
C.300	STORM SEWER PLAN
C.301	STORM SEWER PLAN & PROFILE
C.302	STORM SEWER PLAN & PROFILE
C.303	STORM SEWER PLAN & PROFILE
C.304	SANITARY DETAILS
C.400	SANITARY SEWER PLAN & PROFILE
C.401	SANITARY SEWER PLAN & PROFILE
C.402	SANITARY SEWER PLAN & PROFILE
C.403	SANITARY SEWER PLAN & PROFILE
C.500	WATER PLAN
C.501	WATER PLAN & PROFILE
C.600	DETAIL SHEET
C.601	DETAIL SHEET
C.602	DETAIL SHEET

PROPERTY DESCRIPTION

Description taken verbatim from Deed of Trust Instrument No. 2010EQ080118

All that part of the West one half of Lot 2 of the NW 1/4 of Section 3, Township 47 N, Range 32 W, in Lee's Summit, Jackson County, Missouri, except the East 16.5 feet, and except that part in existing street rights of way, more particularly described as follows:
Commencing at the Northwest corner of said Section 3; thence S 86°41'55" E along the North line of said 1/4 Section, a distance of 30.00 feet; thence S 03°18'59" W, a distance of 30.00 feet to the Point of Beginning, said point being the intersection of the existing East right of way line of View High Drive and the South line of the existing right of way line of Chipman Road; thence S 86°41'55" E parallel with the North line of said 1/4 Section, a distance of 337.94 feet; thence S 86°35'42" E parallel with the North line of said 1/4 Section, a distance of 945.57 feet; thence S 03°22'09" W, West of parallel with and 16.5 feet distant from the East line of the West 1/2 of said Lot 2, a distance of 1420.09 feet to a point on the South line of the West 1/2 of said Lot 2; thence N 87°16'57" W along said South line, a distance of 1282.27 feet; thence N 03°18'59" E along a line, East of parallel with and 30.00 feet distant from the West line of said Lot 2, a distance of 1434.84 feet to the Point of Beginning, containing 42.046 acres, more or less, all being subject to easements, restrictions, and rights of way of record.

Site Data Table

Total Area	1,831,226.10 Sq. Ft. (42.04 Ac.)
Area North of Ashurst Drive	1,169,284.28 Sq. Ft. (26.84 Ac.)
Area South of Ashurst Drive	661,941.82 Sq. Ft. (15.20 Ac.)

Phase 1 Impervious Area

(All Property North of Ashurst Drive.)

Area	1,169,284.28 Sq. Ft. (26.84 Ac.)
Building	34,393.00 Sq. Ft. (0.79 Ac.)
Asphalt/Sidewalk	188,830.39 Sq. Ft. (4.34 Ac.)
Impervious Area	223,223.40 Sq. Ft. (5.13 Ac. = 19.1% of Site)
Parking Spaces	289 Standard / 54 Handicap

Future Impervious Area (Includes Phase 1)

(All Property North of Ashurst Drive.)

Area	1,169,284.28 Sq. Ft. (26.84 Ac.)
Building	67,055.00 Sq. Ft. (1.54 Ac.)
Asphalt/Sidewalk	235,625.84 Sq. Ft. (5.41 Ac.)
Impervious Area	302,680.84 Sq. Ft. (6.95 Ac. = 25.9% of Site)
	(Adds more "x" road)

Site Improvement Notes

Sanitary Sewer Improvements

-The site will require a gravity sanitary main extension from the existing Edgewood Trail subdivision to the east. The main will extend toward the northeast corner of this parcel of land and then goes east toward existing City Manhole #27-031, located at the northeast corner of Lot 4, Edgewood Trails. This sewer main extension will require an off-site sanitary sewer easement that does not currently exist and will need to be negotiated with the adjacent property owners.

Water Main Improvements

-The existing 8" water main located at the west end of Ashurst Drive in Edgewood Trails will be extended onto the site and three (3) new fire hydrants will be required to provide adequate fire access to the site. The main will then continue north and be connected to the existing public main located on the south side of Chipman Road. At this time this main extension is anticipated to be private and will require a backflow vault prior to the connection of Chipman Road and Ashurst Drive. The water service will then be tapped separately from the existing 8" main on Chipman Road with the meter and pit being located near the north property line.

Storm Sewer

-Enclosed pipe systems and inlets will be collected and convey the onsite storm water runoff and direct it toward the new detention facility located at the northeast corner of the site. The storm sewer shall be designed to convey the 10 year storm event and the building runoff will be collected and directed into the enclosed pipe system.

Storm Water Detention

-The site will be designed to control the storm water runoff per the current standards as set forth in APWA Section 5600. The system will be an open aired basin in Phase 1 and release into the existing channel located on the South and East side of Chipman Road. This system can be converted in later phases into an underground system to allow for additional parking to be built atop the detention system.

Storm Water Quality Elements

-The detention system will incorporate an infiltration system into the bottom of the basin to provide the opportunity for infiltration back into the existing ground. The system will be designed to handle and control the 2 year storm flows and will consist of a gravel base and filter fabric. Additionally the existing storm inlet located on the eastern side of the site will be converted into an infiltration system to control the storm discharge east towards Eastwood Trails and the provide a water quality element for the storm drainage being discharged to the east. No developed runoff flows are designed to be released into this system, only the open space grass areas shall drain easterly into this system.

Road Extension to View High


-The westerly road extension from the parking area to View High road is intended to be temporary in nature and not designed to be the final location. This access will be right in / right out only and will be permanently located once the final plans for the "Future Development Area" have been developed. At that time Ashurst Drive will be required to extend easterly to View High Drive, however the apparent gap located between the Westerly property line of Eastwood Trails and the Easterly property line of this parcel needs to be addressed.

Chipman Road

-No improvements are anticipated for Chipman Road.

View High Drive

-No improvements are anticipated for View High Drive.



Oil - GAS WELLS
ACCORDING TO EDWARD ALTON'S ENVIRONMENTAL IMPACT STUDY OF ABANDONED OIL AND GAS WELLS IN LEE'S SUMMIT, MISSOURI IN 1995, THERE ARE NO OIL AND GAS WELLS WITHIN 185 FEET OF THE PROPERTY AS SURVEYED HEREON.

UTILITY COMPANIES:

THE FOLLOWING LIST OF UTILITY COMPANIES IS PROVIDED FOR INFORMATION ONLY. WE DO NOT OFFER A GUARANTEE OR WARRANTY THAT THIS LIST IS COMPLETE OR ACCURATE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONTACTING ALL UTILITY COMPANIES THAT MAY BE AFFECTED BY THE PROPOSED CONSTRUCTION AND VERIFYING THE ACTUAL LOCATION OF EACH UTILITY LINE. THE CONTRACTOR SHALL NOTIFY ENGINEERING SOLUTIONS AT 816.623.9888 OF ANY CONFLICT WITH PROPOSED IMPROVEMENTS.

KCP&L - 298-1196
MISSOURI GAS ENERGY - 756-5261
SOUTHWESTERN BELL TELEPHONE - 761-5011
COMCAST CABLE - 795-1100
WILLIAMS PIPELINE - 422-6300
CITY OF LEE'S SUMMIT PUBLIC WORKS - 969-1800
CITY OF LEE'S SUMMIT PUBLIC WORKS INSPECTIONS - 969-1800
CITY OF LEE'S SUMMIT WATER UTILITIES - 969-1900
MISSOURI ONE CALL (DIG RITE) - 1-800-344-7483

GENERAL NOTES:

- 1 - ALL CONSTRUCTION SHALL CONFORM TO THE CITY OF LEE'S SUMMIT DESIGN AND CONSTRUCTION MANUAL AS ADOPTED BY ORDINANCE 5813.
- 2 - ALL REQUIRED EASEMENTS WITHIN THE BOUNDARY OF THIS PROJECT SHALL BE PROVIDED BY SEPARATE DOCUMENT.
- 3 - ANY REQUIRED EASEMENT LOCATED OUTSIDE OF THE BOUNDARY OF THIS PROJECT SHALL BE PROVIDED BY SEPARATE INSTRUMENT PRIOR TO ISSUANCE OF CONSTRUCTION PERMITS.
- 4 - THE CONTRACTOR SHALL NOTIFY THE CITY OF LEE'S SUMMIT PUBLIC WORKS INSPECTION AT 816.969.1800 AT LEAST 48 HOURS PRIOR TO THE COMMENCEMENT OF ANY CONSTRUCTION.
- 5 - THE CONTRACTOR SHALL NOTIFY ENGINEERING SOLUTIONS AT 816.623.9888 OF ANY CONFLICT WITH THE IMPROVEMENTS PROPOSED BY THESE PLANS AND SITE CONDITIONS.
- 6 - THE CONTRACTOR SHALL NOTIFY THE CITY ENGINEER AND OBTAIN THE APPROPRIATE BLASTING PERMITS FOR A REQUIRED BLASTING. IF BLASTING IS ALLOWED, ALL BLASTING SHALL CONFORM TO STATE REGULATIONS AND LOCAL ORDINANCES.

ALL PAVING ON THE PARKING LOT WILL COMPLY WITH THE UNIFIED DEVELOPMENT ORDINANCE ARTICLE 12 IN TERMS OF PAVING THICKNESS AND BASE.

RECEIVED

MAY 12 2016



Planning & Codes Admin

-2015-158-



TOPOGRAPHIC SURVEY

Easements are shown in accordance with Title Commitment No. KCS 255758-KCTV provided by First American Title Insurance Company dated September 19, 2006. According to Lee's Summit's "ABANDONED UTILITIES STUDY", page 101, figure B-11, there are no Oil or Gas Wells on this property. This Property is in Zone C according to FEMA FIRM 0019C, 1989. Community Panel Number 290174. This is an Urban Class Property. Bearings are Grid Bearings.




SUMMIT SURVEY COMPANY
526 S.W. THIRD STREET
LEE'S SUMMIT, MISSOURI 64063
TEL: 816-347-9220
FAX: 816-347-9221

SURVEYOR'S CERTIFICATE
I hereby certify that the within survey is based on an actual survey made by me or under my direct supervision and that said survey was performed in accordance with the minimum requirements of the standards for property boundary surveys adopted by the Missouri Board for Architects, Professional Engineers and Land Surveyors.

PROPERTY DESCRIPTION:
All that part of the West one-half of Lot 2 of the NW 1/4 of Section 2, Township 47 N., Range 32 W., Lee's Summit, Jackson County, Missouri, except the East 16.5 feet, and except that part in existing street rights of way more particularly described as follows: Commencing at the Northwest corner of said Section 2, thence S 86°41'55" E, a distance of 337.94 feet to the North line of said 1/4 Section, a distance of 337.94 feet to the South line of the existing right of way line of Chipman Road, thence S 86°41'55" E, a distance of 945.57 feet, thence S 03°22'09" W, a distance of 1420.09 feet to the East line of said 1/2 of said Lot 2, a distance of 1282.27 feet to a point on the South line of the West 1/2 of said Lot 2, thence N 87°16'57" W, a distance of 1328.77 feet to the Point of Beginning, containing 42.046 acres, more or less, all being subject to easements, restrictions, and rights of way of record.

Surveyor's Name: Larry J. Moxey
Survey Number: LS 1785
Date: _____

- = Fenceline
- = Water Valve (W.V.)
- = Fire Hydrant (F.H.)
- = Power Pole (P.P.)
- = Light Pole (L.P.)
- = Survey Monument Found & Noted
- = Section Line
- = Existing



RECEIVED

MAY 12 2016

Planning & Codes Admin

2015-158-

ENGINEERING SOLUTIONS
Professional Registrar
Missouri
Engineering 20060021
Surveying 20060031
Kansas
Engineering E-188
Surveying LS-218
Oklahoma
Engineering 6254
Nebraska
Engineering CA282

The Summit Church
3381 Northwest Chipman Road
Lee's Summit, Jackson County, Missouri

Project:
THE SUMMIT CHURCH, L3ND
Issue Date:
October 15, 2015


TOPOGRAPHIC SURVEY
The Summit Church:
Lee's Summit, Jackson County, Missouri

Matthew J. Schi
MO PE 2006019
KS PE 19071
OK PE 25521
NE PE E-1433

REVISIONS
11-17-15 Modified
01-25-16 City Comm
03-18-16 City Comm
4-8-16 City Comm
5-12-16 Final Pl


RECEIVED

MAY 12 2016



DEMOLITION PLAN
SCALE: 1" = 50'

Planning & Codes Admin



Professional Registrations
Missouri
Engineering 200500216
Surveying 200500311
Kansas
Engineering E-1898
Surveying LS-218
Oklahoma
Engineering 6254
Nebraska
Engineering CA282

Project:
The Summit Church
3381 Northwest Chipman Road
Lee's Summit, Jackson County, Missouri

Project:
THE SUMMIT
CHURCH, LSHD
Issue Date:
October 13, 2015

Demolition Plan
The Summit Church:
Lee's Summit, Jackson County, Missouri

Matthew J. Schli
MO PE 20060197
KS PE 19071
OK PE 25226
NE PE E-1433

REVISIONS

11-17-15	Modified V
01-25-16	City Comm
03-18-16	City Comm
4-8-16	City Comm
5-12-16	Final PE



PRE CLEARING PLAN
SCALE: 1" = 70'

MAINTENANCE:
TO MAINTAIN THE EROSION AND SEDIMENT CONTROLS, THE FOLLOWING PROCEDURES WILL BE PERFORMED:
SEDIMENT CAPTURE DEVICES: SEDIMENT WILL BE REMOVED FROM THE UPSTREAM OR UPSLOPE SIDE OF THE FILTER FABRIC FENCES, WHEN THE DEPTH OF ACCUMULATED SEDIMENT REACHES ABOUT ONE-THIRD THE HEIGHT OF THE STRUCTURE.
STORM SEWER INLETS: ANY SEDIMENT IN THE STORM SEWER INLETS WILL BE REMOVED AND DISPOSED OF PROPERLY.
TEMPORARY CONTROLS: ALL TEMPORARY CONTROLS WILL BE REMOVED AFTER THE DISTURBED AREAS HAVE BEEN STABILIZED.

INSPECTION PROCEDURES:
INSPECTIONS WILL BE DONE BY THE RESPONSIBLE PERSON(S) AT LEAST EVERY WEEK AND WITHIN 24 HOURS EACH STORM EVENT PRODUCING ANY AMOUNT OF RAINFALL. AREAS THAT HAVE BEEN RESEEDED WILL BE INSPECTED REGULARLY AFTER SEED GERMINATION TO ENSURE COMPLETE COVERAGE OF EXPOSED AREAS. DISTURBED AREAS THAT HAVE NOT BEEN FINALLY STABILIZED SHALL HAVE ALL POLLUTION CONTROL MEASURES INSPECTED FOR PROPER INSTALLATION, OPERATION AND MAINTENANCE. LOCATIONS WHERE STORM WATER LEAVES THE SITE SHALL BE INSPECTED FOR EVIDENCE OF EROSION OR SEDIMENT DEPOSITION. ANY DEFICIENCIES SHALL BE NOTED IN A REPORT OF THE INSPECTION AND CORRECTED WITHIN SEVEN CALENDAR DAYS OF THE INSPECTION. THE PERMITTEE SHALL PROMPTLY NOTIFY THE SITE CONTRACTORS RESPONSIBLE FOR OPERATION AND MAINTENANCE OF POLLUTION CONTROL DEVICES OF DEFICIENCIES.

IF THE EXISTING GROUND COVER IS NATURAL GRASS, DISTURBED AREAS SHALL BE TEMPORARILY SEED WITH WHEAT/RYE AT A RATE OF 1.5 POUNDS PER 1000 SQUARE FEET. PERMANENT SEEDING SHALL CONSIST OF 80% IN THREE EQUAL PARTS OF THIN BLADE, TURF-TYPE, TALL FESCUE AND 10% BLUEGRASS SEED AT A RATE OF 10 POUNDS PER 1000 SQUARE FEET. BOTH TEMPORARY AND PERMANENT SEEDS SHALL BE MULCHED AND WATERED TO MAINTAIN THE PROPER MOISTURE LEVEL OF THE SOIL TO ESTABLISH GRASS. NEW GRASS SHALL BE WATERED AND MAINTAINED UNTIL IT REACHES A HEIGHT OF 3 INCHES. ANY BARE AREAS SHALL BE RESEED.

ALL EROSION CONTROL DEVICES SHALL BE REMOVED BY GENERAL CONTRACTOR AFTER SITE STABILIZATION IS COMPLETE AND APPROVED BY ENGINEER.

THE DEVELOPER WILL DESIGNATE A QUALIFIED PERSON OR PERSONS TO PERFORM THE FOLLOWING INSPECTIONS:
STABILIZATION MEASURES: DISTURBED AREAS AND AREAS USED FOR STORAGE OF MATERIALS THAT ARE EXPOSED TO PRECIPITATION WILL BE INSPECTED FOR EVIDENCE OF, OR THE POTENTIAL FOR, POLLUTANTS ENTERING THE DRAINAGE SYSTEM. AFTER A PORTION OF THE SITE IS FINALLY STABILIZED, INSPECTIONS WILL BE CONDUCTED AT LEAST ONCE EVERY MONTH THROUGHOUT THE LIFE OF THE PROJECT. CONTRACTOR CAN CONTACT ENGINEERING SOLUTIONS FOR COPIES OF THE INSPECTION FORM TO BE USED FOR STABILIZATION MEASURES.

STRUCTURAL CONTROLS: FILTER FABRIC FENCES AND ALL OTHER EROSION AND SEDIMENT CONTROL MEASURES IDENTIFIED IN THE PLAN WILL BE INSPECTED REGULARLY FOR PROPER POSITIONING, ANCHORING, AND EFFECTIVENESS IN TRAPPING SEDIMENTS. SEDIMENT WILL BE REMOVED FROM THE UPSTREAM OR UPSLOPE SIDE OF THE FILTER FABRIC. CONTRACTOR CAN CONTACT ENGINEERING SOLUTIONS FOR COPIES OF THE INSPECTION FORM TO BE USED FOR STABILIZATION MEASURES.

DISCHARGE POINTS: DISCHARGE POINTS OR LOCATIONS WILL BE INSPECTED TO DETERMINE WHETHER EROSION CONTROL MEASURES ARE EFFECTIVE IN PREVENTING SIGNIFICANT AMOUNTS OF POLLUTANTS FROM ENTERING RECEIVING WATERS.

CONSTRUCTION ENTRANCE: LOCATIONS WHERE VEHICLES ENTER OR EXIT THE SITE WILL BE INSPECTED FOR EVIDENCE OF OFF-SITE SEDIMENT TRACKING.
A LOG OF EACH INSPECTION SHALL BE KEPT. THE INSPECTION REPORT IS TO INCLUDE THE FOLLOWING MINIMUM INFORMATION: INSPECTOR'S NAME, DATE OF INSPECTION, OBSERVATIONS RELATIVE TO THE EFFECTIVENESS OF THE POLLUTION CONTROL DEVICES, ACTIONS TAKEN OR NECESSARY TO CORRECT DEFICIENCIES, AND LISTING OF AREAS WHERE LAND DISTURBANCE OPERATIONS HAVE PERMANENTLY OR TEMPORARILY STOPPED. THE INSPECTION REPORT SHALL BE SIGNED BY THE PERMITTEE OR BY THE PERSON PERFORMING THE INSPECTION IF DULY AUTHORIZED TO DO SO.

DURING ALL PHASES OF CONSTRUCTION, INACTIVE AREA STABILIZATION METHODS AS DESCRIBED IN APWA SECTION 511.3 SHALL BE USED TO CONTROL EROSION AND SILTATION.

SILT FENCE PROTECTION TO BE MAINTAINED BY CONTRACTOR

LEGEND

- Phase 1 Silt Fence — SF-1 — SF-1 —
Phase 2 Silt Fence — SF-2 — SF-2 —
Existing Water Line — X — X —

NOTES: The Land Disturbance Plans indicates the final placement of erosion control devices. The contractor(s) may proceed with construction prior to the final placement of these devices by providing additional devices to control erosion on their items of work. These devices shall be maintained until the final devices are in place.

EROSION CONTROL DESCRIPTION:
1) SILT FENCE SHALL BE PLACED AT THE PERIMETER OF THE GRADING PLANT AND AT INTERMEDIATE AREAS THROUGHOUT THE SITE AS SHOWN ON THE PLAN. INLET SEDIMENT TRAPS SHALL BE PLACED SURROUNDING ALL STORM INLETS.
2) INSTALL TEMPORARY CONSTRUCTION ENTRANCE AS SHOWN ON PLAN.

EROSION CONTROL PROCEDURE:
1) SILT FENCE AND TEMPORARY CONSTRUCTION ENTRANCE SHALL BE INSTALLED AT THE PERIMETER OF THE GRADED AREAS PRIOR TO BEGINNING OF CLEARING OR DEMOLITION OPERATIONS. THE CONTRACTOR SHALL INSTALL SILT FENCE AS SHOWN ON PLANS AS GRADING PROGRESSES.


TEMPORARY CONSTRUCTION ENTRANCE NOTES:

- A) INSTALLATION
1) AVOID LOCATING ON STEEP SLOPES OR AT CURVES ON PUBLIC STREETS. IF POSSIBLE, LOCATE WHERE PERMANENT ROADS WILL EVENTUALLY BE CONSTRUCTED.
2) REMOVE ALL VEGETATION AND OTHER UNSUITABLE MATERIAL FROM THE FOUNDATION AREA, GRADE AND CROWN FOR POSITIVE DRAINAGE.
3) IF SLOPE TOWARDS THE PUBLIC ROAD EXCEED 2% CONSTRUCT A 4 TO 8 INCH HIGH RIDGE WITH 3H: 1V SIDE SLOPES ACROSS THE FOUNDATION APPROXIMATELY 15 FEET FROM THE EDGE OF THE PUBLIC ROAD TO DIVERT RUNOFF AWAY FROM IT.
4) INSTALL PIPE UNDER THE ENTRANCE IF NEEDED TO MAINTAIN DRAINAGE DITCHES ALONG PUBLIC ROADS.
5) PLACE STONE TO DIMENSIONS AND GRADES AS SHOWN ON PLANS. LEAVE SURFACE SMOOTH AND SLOPED FOR DRAINAGE.
6) DIVERT ALL SURFACE RUNOFF AND DRAINAGE FROM THE ENTRANCE TO A SEDIMENT CONTROL DEVICE.
7) IF WET CONDITIONS ARE ANTICIPATED PLACE GEOTEXTILE FABRIC ON THE GRADED FOUNDATION TO IMPROVE STABILITY.

- B) TROUBLESHOOTING
1) CONSULT WITH A QUALIFIED DESIGN PROFESSIONAL IF ANY OF THE FOLLOWING OCCUR:
- INADEQUATE RUNOFF CONTROLS TO THE EXTENT THAT SEDIMENT WASHES ONTO PUBLIC ROADS
- INSTALL DIVERSIONS OR OTHER RUNOFF CONTROL MEASURES
- SMALL STONE, THIN PAD, OR ABSENCE OF GEOTEXTILE FABRIC RESULTS IN RUTS AND MUDDY CONDITIONS AS STONE IS PRESSED INTO SOIL - INCREASE STONE SIZE OR PAD THICKNESS OR ADD GEOTEXTILE FABRIC
- PAD TOO SHORT FOR HEAVY CONSTRUCTION TRAFFIC - EXTEND PAD BEYOND THE MINIMUM 50 FOOT LENGTH AS NECESSARY

- C) INSPECTION AND MAINTENANCE
1) INSPECT STONE PAD AND SEDIMENT DISPOSAL AREA WEEKLY AND AFTER ANY RAIN EVENT
2) RESHAPE PAD AS NEEDED FOR PROPER DRAINAGE AND RUNOFF CONTROL
3) TOP DRESS WITH CLEAN 2 AND 3 INCH STONE AS NEEDED
4) IMMEDIATELY REMOVE MUD OR SEDIMENT TRACKED OR WASHED ONTO PUBLIC ROADWAY. REPAIR ANY BROKEN ROAD PAVEMENT IMMEDIATELY
5) REMOVE ALL TEMPORARY ROAD MATERIALS FROM AREAS WHERE PERMANENT VEGETATION WILL BE ESTABLISHED

TEMPORARY SEDIMENT TRAP #1 CALCULATIONS:
1. TOTAL AREA DRAINING TO BASIN = 7.47 ac
2. REQUIRED VOLUME OF TRAP = 3,600-cft PER acre
= 7.47 X 3,600 = 26,892 cft
3. VOLUME OF PROPOSED TRAP = 35,000 cft



RECEIVED

MAY 12 2016

Planning & Codes A


Matthew J. Schli
MO PE 20060197
KS PE 19071
OK PE 25226
NE PE E-1433

REVISIONS
11-17-15 Modified V
01-25-16 City Comm
03-18-16 City Comm
4-8-16 City Comm
5-12-16 Final PC



INACTIVE AREA STABILIZATION PLAN

SCALE: 1" = 70'



SILT FENCE PROTECTION
TO BE MAINTAINED BY CONTRACTOR

LEGEND

- Phase 1 Silt Fence — SF-1 — SF-1
- Phase 2 Silt Fence — SF-2 — SF-2
- Proposed Storm Line — S — S — S
- Existing Storm Line — X-STM —

DURING ALL PHASES OF CONSTRUCTION,
INACTIVE AREA STABILIZATION METHODS AS
DESCRIBED IN APWA SECTION 5111.3 SHALL
BE USED TO CONTROL EROSION AND
SILTATION.

NOTES: The Land Disturbance Plans indicates the final
placement of erosion control devices. The contractor(s)
may proceed with construction prior to the final
placement of these devices by providing additional
devices to control erosion on their items of work.
These devices shall be maintained until the final devices
are in place.

RECEIVED

MAY 12 2016

Planning & Codes Admin

-2015-158-



SILT FENCE PROTECTION
TO BE MAINTAINED BY CONTRACTOR

LEGEND

- PHASE 1 SILT FENCE
- PHASE 2 SILT FENCE

DURING ALL PHASES OF CONSTRUCTION, INACTIVE AREA STABILIZATION METHODS AS DESCRIBED IN APWA SECTION 5111.3 SHALL BE USED TO CONTROL EROSION AND SILTATION.

NOTES:

- The Land Disturbance Plans indicate the final placement of erosion control devices. The contractor may proceed with construction prior to the final placement of these devices by providing additional devices to control erosion or their items of work. These devices shall be maintained until the final devices are in place.
- Per Unified Ordinance Section 14.050 B.2, All portions of the site not covered with paving or buildings shall be landscaped. Open areas not covered with other materials shall be covered with sod. Ground cover shall be utilized on all slopes in excess of 3:1 slope.

SEED AND MULCH NOTES:

Seeding shall be done before the proposed seedbed becomes eroded, crusted, or dried out and shall not be done when the ground is frozen, or covered with snow. The seed shall comply with the requirements of the Missouri Seed Law and the Federal Seed Act. Also, it shall contain no seed of any plant on the Federal Noxious Weed List. Other weed seeds shall not exceed one percent by weight of mix.

Seed and Fertilizer Rates:

Mix I - Rye Grass / Blue Grass	100 lbs. per Acre
Mix II - Tall Fescue / Blue Grass	195 lbs. per Acre
Lime	2000 lbs per Acre (50 lbs. per 1000 sq. ft.)
Fertilizer	800 to 1200 lbs per Acre (25 lbs per 1000 sq. ft.)

During the dates December 15th through May 31 ALL lime fertilizer, seed and mulch shall be applied to finished slopes of disturbed areas. During the months of June, July, October and November 1st through December 15th, lime fertilizer, seed and mulch shall be applied at the following rates:

- Lime - 100% of specified quantity
- Fertilizer - 75% of the specified quantity
- Seed - 50% of the specified quantity
- Mulch - 100% of the specified quantity


Mulch shall be Vegetative type, cereal straw from stalks of oats, rye, or barley, or approved equal. The straw shall be free of prohibited weed seed and relatively free of all other noxious and undesirable seed. Mulch shall be applied at the rate of 2 tons per acre, (70 to 90 lbs per 1000 sq. ft.). Mulch shall be embedded by a mulch anchoring tool or disk type roller having flat serrated disks spaced not more than 10 inches apart and cleaning scrapers shall be provided.

RECEIVED

MAY 12 2016

Planning & Codes Admin

-2015-158-



RECEIVED

MAY 12 2016

Planning & Codes Admin

-2015-158-

The Summit Church
3381 Northwest Chipman Road
Lee's Summit, Jackson County, Missouri


Project: THE SUMMIT CHURCH, LSHD
Issue Date: October 13, 2015

ESC - Details
The Summit Church:
Lee's Summit, Jackson County, Missouri

Matthew J. Schli
MO PE 20060197
KS PE 19071
OK PE 25226
NE PE E-1433

REVISIONS
11-17-15 Modified W
01-25-16 City Comm
03-18-16 City Comm
4-8-16 City Comm
5-12-16 Final PD

C.053



Note:
All Access Roads, Including
The Access From Chipman
Road And View High Drive
Shall Be Constructed To
Public Standards

- Indicates Fire Lane and Heavy Asphalt
- Indicates Light Asphalt
- See C.600 for Asphalt Details
- Indicates Standard City Residential and Commercial Pavement Section. Reference C.202 & C.203

RECEIVED

MAY 12 2016

Planning & Codes Admin

-2015-158-

Site Data Table


Total Area 1,831,226.10 Sq. Ft. (42.04 Ac.)
Area North of Ashurst Drive 1,169,284.28 Sq. Ft. (26.84 Ac.)
Area South of Ashurst Drive 661,941.82 Sq. Ft. (15.20 Ac.)

Phase 1 Impervious Area
(All Property North of Ashurst Drive)

Area Building 1,169,284.28 Sq. Ft. (26.84 Ac.)
Asphalt/Sidewalk 34,393.00 Sq. Ft. (0.79 Ac.)
Impervious Area 1,203,677.28 Sq. Ft. (27.63 Ac.)
Parking Spaces 223,223.40 Sq. Ft. (5.13 Ac. = 19.1% of Site)
286 Standard / 54 Handicap

Future Impervious Area (Includes Phase 1)
(All Property North of Ashurst Drive)

Area Building 1,169,284.28 Sq. Ft. (26.84 Ac.)
Asphalt/Sidewalk 67,055.00 Sq. Ft. (1.54 Ac.)
Impervious Area 1,236,339.28 Sq. Ft. (28.38 Ac.)
302,680.84 Sq. Ft. (6.95 Ac. = 25.9% of Site)
(Adds more road)



North
SCALE: 1" = 50'

Phase 1 Parking
289 Standard Spaces
54 Accessible Spaces

RECEIVED
MAY 12 2016
Planning & Code

2015-15



Professional Registrar
Missouri
Engineering 20050021
Surveying 200500831
Kansas
Engineering E-188
Surveying E-218
Oklahoma
Engineering 6254
Nebraska
Engineering CA282



The Summit Church
3381 Northwest Chipman Road
Lee's Summit, Jackson County, Missouri

Project:
THE SUMMIT
CHURCH - 4, LSHD
Issue 1: 10/15/2015
Date of 10/15/2015

DIMENSION PLAN
The Summit Church:
Lee's Summit, Jackson County, Missouri

Matthew J. Schil
MO PE 2006019
KS PE 19071
OK PE 25226
NE PE E-1433

REVISIONS
11-17-15 Modified
01-25-16 City Comm
03-18-16 City Comm
4-8-16 City Comm
5-12-16 Final Pl



RECEIVED
MAY 12 2016
Planning & Codes Admin
-2015-158-

Estimated Cut / Fill Quantities	
Site Area	20.25 Acres
Cut Volume (Unadjusted)	48,835 c.y.
Fill Volume (Unadjusted)	31,767 c.y.
Street & Sidewalk Cut Volume	7,500 c.y.
Building Pad Cut Volume	3,500 c.y.
Net Export Required	28,068 c.y. (Unadjusted)

- Notes**
- Contractor is responsible for verifying all existing utility locations prior to excavation.
 - There are no known natural or artificial water storage detention areas, or wetlands in the area designated for construction.
 - No part of the project lies within the 100 year flood plain.
 - All erosion and sediment control measures need to be implemented prior to construction.
 - Additional erosion control may be required by the City Engineer, Design Engineer or Owner at any time problematic areas are noted in the field or existing measures are found to be ineffective.
 - Soil Stabilization of disturbed areas shall be completed within 14 days of construction inactivity.
 - Contractor responsible for all density testing of roadway subgrade and granular base.
 - Contractor responsible to provide Engineering Solutions an Asbuilt topographic survey of the site to verify grades.

ENGINEERING SOLUTIONS
ENGINEERING & SURVEYING
Professional Registrar
Missouri
Engineering 20000021
Surveying 200000831
Kansas
Engineering E-189
Surveying L.S-218
Oklahoma
Engineering 6254
Nebraska
Engineering CA282


The Summit Church
3381 Northwest Chipman Road
Lee's Summit, Jackson County, Missouri

Project:
THE SUMMIT
CHURCH, LSNH
Issue Date:
October 15, 2015


GRADING PLAN
The Summit Church:
Lee's Summit, Jackson County, Missouri

REVISIONS	
11-17-15	Modified
01-25-16	City Comm
03-18-16	City Comm
4-8-16	City Comm
5-12-16	Final Pl

MAY 12 2016



- 2015 - 158 -



The Summit Church
3381 Northwest Chipman Road
Lee's Summit, Jackson County, Missouri



THE SUMMIT
CHURCH, LSMD

SPOT ELEVATIONS
The Summit Church:
Lee's Summit, Jackson County, Missouri


Matthew J. Schlie
PE 20060197
KS PE 19071
OK PE 25226
E PE E-1433

REVISIONS

15	Modified W
16	City Comm
16	City Comm
6	City Comm
2-16	Final PD



TYPICAL SECTION
(RESIDENTIAL STREET)
N.T.S.



RECEIVED
MAY 12 2016

Planning & Codes Admin

-2015-158-